

Initial Environmental Examination

June 2015

Second Greater Mekong Subregion Corridor Towns Development Project (CTDP), PPTA 8425

Kampot and Sihanoukville Towns, Cambodia

This initial environmental examination is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature.

CURRENCY EQUIVALENTS

(12 February 2015)

Currency Unit	–	Riel R
R1.00	=	\$0.00025
\$1.00	=	R3,983

ABBREVIATIONS

ADB	-	Asian Development Bank
DAFF	-	Department of Agriculture, Forestry and Fisheries
DOE	-	Department of Environment
DPWT	-	Department of Public Works and Transport
DOT	-	Department of Tourism
DOWRAM	-	Department of Water Resources and Meteorology
EA	-	Executing Agency
ECA	-	Environmental Compliance Audit
EIA	-	Environmental Impact Assessment
EMP	-	Environment Management Plan
GMS	-	Greater Mekong Subregion
Government	-	Government of Cambodia
IEE	-	Initial Environment Examination
IEIA	-	Initial Environmental Impact Assessment
MOE	-	Ministry of Environment
PAM	-	Project Administration Manual
PIC	-	Project Implementation Consultant
PIU	-	Project Implementation Unit
PPTA	-	Project Preparatory Technical Assistance
PPMU	-	Provincial Project Management Unit
REA	-	Rapid Environmental Assessment
RP	-	Resettlement Plan
GRC	-	Royal Government of Cambodia
SPS	-	Safeguard Policy Statement (2009)
WWTP	-	Wastewater Treatment Plant

WEIGHTS AND MEASURES

km	-	kilometer
kg	-	kilogram
ha	-	hectare

In this report, "\$" refers to US dollars.

EXECUTIVE SUMMARY

Kampot and Sihanoukville are the towns in Cambodia that are participating in the Second Greater Mekong Subregion Corridor Towns Development Project¹. The two town-subprojects consist of small infrastructure and environmental improvement investments that are being implemented with the immediate and ultimate goals of improving urban environments, and promoting socioeconomic development. Linked to the urban infrastructure investments of the subprojects is parallel development of Strategic Local Economic Development Plans (SLEDP) for each town. The selection of the urban infrastructure investments and the development of the SLEDPs are guided by the ADB Green City Agenda².

The initial environmental examination (IEE) presented herein addresses the two subprojects in Kampot and Sihanoukville. The IEEs of the other five town-subprojects in Lao PDR and Viet Nam have been prepared separately.

Project Summary

The components of the subprojects in Cambodia at the feasibility design stage are summarized below³.

Kampot, Kampot Province
Wastewater Collection and Treatment
Solid Waste Management
Urban Drainage
Sihanoukville, Preah Sihanouk Province
Solid Waste Management
Urban Drainage

Potential Impacts

Both subprojects in Cambodia are Category B for environment. The examination of the subprojects indicates that potential environmental impacts are largely restricted to the construction phase of the subproject components. Construction-related disturbances such as noise, dust, soil erosion, surface water sedimentation, tree removal, solid and liquid waste pollution, worker camp disturbances, increased traffic and risk of worker and public injury can be managed with standard construction practices and guidelines (e.g., IFC/World Bank 2007).

Noise, dust, and traffic disruption created during construction of the new WWTP in Kampot, the drainage improvements in both towns can be minimized with standard construction management practices. Public safety measures in both towns can be managed with speed limits, cordoned off construction areas, and sufficient signage warning of construction activities.

¹ Lao PDR and Viet Nam also participate in the Second GMS Corridor Towns Development Project

² :<http://www.adb.org/publications/enabling-green-cities-operational-framework-integrated-urban-development-southeast-asia>

³ From Interim Project Report 12-14

The construction of the new wastewater treatment plant in Kampot must include management measures to prevent or contain soil erosion and prevent sedimentation of the Teuk Chhou river. Standard mitigation measures such as berms or plastic sheet fencing should be used to contain loose soil created from the civil works. Similarly, erosion caused by construction of the pipelines to the Kampot WWTP must be managed and carefully contained closely to the sites. The treated effluent from the WWTP must meet the current government standards for effluent discharge, and be monitored regularly after the Kampot WWTP is commissioned.

The existing landfill in Kampot must be closed with an internationally accepted closure procedure which must be timed with the commissioning of the nearby replacement new landfill. Similar to the new WWTPs, construction of the new landfill must apply standard construction management techniques to prevent local solid and domestic waste pollution, erosion, and surface water sedimentation. Potential traffic disruption, noise, and dust caused from landfill construction and access road upgrades can be managed to a minimum. A tree replacement program should be implemented to offset the trees that must be removed for the subproject components. Drainage around the new landfills in both subproject towns also must be designed to accommodate increases in the frequency and severity of flood events. The new and upgraded drainages in both towns must be constructed large enough to be able to contain and convey increased flood volumes as a result of climate change-induced increases in rainfall.

The new WWTP in Kampot was screened with the REA and factors of AWARE to be the most sensitive to climate change as defined by projected sea level rise, and inland flooding from an increased frequency and severity of rainfall events. The coastal Kampot WWTP is considered the most sensitive subproject components to climate change due to exposure to sea level rise and typhoon storm surge. The grade elevation of the WWTP in Kampot needs to be resilient to the current seasonal flood events, and to climate change-induced increases in flooding from the Teuk Chhou river from basin rainfall and/or from sea level rise and storm surge from Kampot bay.

The results of REA and AWARE provides the basis for the more in depth CVRA of potential socioeconomic and financial impacts of climate change in both towns. The climate vulnerability and resilience assessment of the subproject indicated that climate change resilience and proofing measures such as elevated facility foundations, and adequate grading and drainage must be addressed by the final designs of the subproject components.

The subproject components with the greatest potential for generating GHGs are wastewater treatment, and the new and renovated landfills due to the production of methane (CH₄) from anaerobic digestion of wastewater, and the decomposition of organic solid waste in modern, managed landfills. Methane is 40-50 times stronger than CO₂ as a greenhouse gas. The Kampot WWTP will consist of a combination of anaerobic and aerobic WWT processes and thus will produce methane. Similarly, the new and renovated landfills will also generate methane as a result of the anaerobic decomposition of organic waste in the lined landfill cells. Moreover, at the feasibility design stage of the subprojects the technology to capture and flare or otherwise neutralize the methane produced from the new WWTP and landfills is not included which means the methane will dissipate to the environment.

The only perceived induced, or potential cumulative impacts of the two subprojects in Cambodia are increased resource consumption and pollution that may be caused by the decided goal of increased socioeconomic development in both town areas. Overall the subprojects will yield positive impacts on the environmental quality of both towns.

Conclusions

The IEE concludes that the description of the feasibility designs of the two subprojects combined with available information on the affected environments is sufficient to identify the scope of potential environmental impacts of the project. Providing that significant changes do not occur to the design of one or more of the subproject components, and that new sensitive environmental or social receptor data are not discovered, the subprojects will remain Category B for environment and will not require further detailed environmental impact assessment (EIA).

The EMPs developed for each town subproject provide impact mitigation plans, environmental monitoring plans, and specify the institutional responsibilities and capacity needs for the environmental management of the subprojects. The EMPs will need to be reviewed and updated at the detailed design phase to ensure that they fully address the potential impacts of the final subproject designs.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	3
Project Summary	3
Potential Impacts	3
Conclusions	5
I. INTRODUCTION	8
A. Background to IEE	8
B. Assessment Context	10
C. Structure of report	10
II. POLICY, LEGAL, AND ADMINISTRATIVE FRAMEWORK	10
A. Environmental Impact Assessment	10
B. Legal and Policy Framework for Environmental Protection	11
C. Agencies Responsible for Environmental Management and Assessment	12
D. Climate Change Directives	13
E. ADB Safeguard Policy	13
F. Environmental Due Diligence of Subprojects	13
III. DESCRIPTION OF CAMBODIA SUBPROJECTS	15
A. Kampot	16
B. Sihanoukville	25
IV. DESCRIPTION OF AFFECTED ENVIRONMENTS	28
A. Southern Cambodia Profile	29
B. Kampot and Sihanoukville Subproject Areas	30
C. Features of Subproject sites	37
V. PUBLIC CONSULTATION	40
A. Identification of Stakeholders	41
B. Discussion Guide	41
C. Summary of Public Consultation	42
VI. POTENTIAL ENVIRONMENTAL IMPACTS AND MITIGATIONS	46
A. Subproject Benefits	46
B. Subproject Impacts and Mitigations	47
C. Induced and Cumulative Impacts	53
D. Climate Change	53
VII. ANALYSIS OF ALTERNATIVES	56
A. Kampot:	56
B. Sihanoukville	57
VIII. INFORMATION DISCLOSURE AND GRIEVANCE REDRESS MECHANISM	57
IX. CONCLUSIONS AND RECOMMENDATION	59
APPENDIX A: RAPID ENVIRONMENTAL ASSESSMENTS OF SUBPROJECTS	60
APPENDIX B: PARTICIPANTS OF PUBLIC CONSULTATIONS	74
APPENDIX C: DRAFT TOR FOR GROUNDWATER STUDY	83
APPENDIX D: INDICATIVE LANDFILL CLOSURE PROCEDURE	87

Table 1. Cambodia subproject components	8
Table 2. Summary of environmental due diligence of subprojects Error! Bookmark not defined.	
Table 3: Example rivers discharging to ocean from Sihanoukville and Kampot areas	31
Table 4. Dry-season river and coastal water quality 2005 – 2006	31
Table 5. Guiding Questions and Information Requests for Stakeholder Consultations	41
Table 6. Example Environmental Components Used to Guide Stakeholder Discussions.	42
Table 7. Summary of Stakeholder Views in Kampot and Sihanoukville	43
Table 8. Groundwater variables to be determined at landfill and WWTP sites.....	85
Figure 1. Seven subproject towns of Second Corridor Towns Development Project	9
Figure 2. Location of major subproject components in Kampot	17
Figure 3. Three wastewater catchments and new WWTP site in Kampot	19
Figure 4. Existing and new landfill sites north of Kampot	21
Figure 5. Plan view of new landfill in Kampot	22
Figure 6. Cross sectional views of landfill cells and access road.....	22
Figure 7. Locations of drainage network to be upgraded in Kampot.....	24
Figure 8. Generic road upgraded drains for Kampot.....	25
Figure 9. Sihanoukville centre showing drainage network	26
Figure 10. Existing solid waste dump site in Sihanoukville	27
Figure 11: Soil types of Cambodia	29
Figure 12: Forest types of Cambodia	30
Figure 13. Water quality sampling sites in Kampot Bay and near Sihanoukville	32
Figure 14: Location of Bokor and Ream National Parks near subprojects.	33
Figure 15. Important bird areas in National Parks of Kampot and Sihanoukville.....	34
Figure 16: Mangroves, coral reefs, and seagrass areas in Kampot and Sihanoukville.	35
Figure 17. Site of new WWTP (left) east of Teuk Chhou river (on right)	38
Figure 18. Existing dumpsite, and site of new landfill north of Kampot	38
Figure 19. Example town drain outfall to Teuk Chhou river, and WW canal	39
Figure 20. Main dumpsite of Sihanoukville, and onsite well head.....	39

I. INTRODUCTION

A. Background to IEE

1. The Second Greater Mekong Subregion (GMS) Corridor Towns Development Project (PPTA 8425) is a multi-sector urban development project in Viet Nam, Cambodia, and the Lao PDR. The project is comprised of small urban infrastructure and environmental improvement investments in seven subproject towns in the three participating countries. The project consists of two primary outputs as defined below:

- 1) Strategic Local Economic Development Plans (SLEDP) for the seven towns; and
- 2) Feasibility stage designs for urban infrastructure investments to improve the environmental quality of the towns and to ultimately strengthen socioeconomic development.

2. The selection of the urban infrastructure and environmental improvement investments, and the development of the SLEDPs are guided by the ADB Green City Agenda⁴. The seven SLEDPs are presented elsewhere in the main body of the report.

3. The subprojects in the towns of Kampot and Sihanoukville of Cambodia are the focus of the IEE presented herein. The IEEs for the subproject towns in Viet Nam and Lao PDR were prepared separately. The country-level IEE reporting structure for PPTA 8425 is the same safeguard reporting structure that was used for the first ADB Corridor Towns Development Project (CTDP) in the same countries in 2012. Table 1 summarizes the subproject components of both corridor towns of PPTA 8425.


Table 1. Cambodia subproject components

Kampot
Wastewater Collection and Treatment
Solid Waste Management
Urban Drainage
Sihanoukville
Solid Waste Management
Urban Drainage

⁴<http://www.adb.org/publications/enabling-green-cities-operational-framework-integrated-urban-development-southeast-asia>

Figure 1. Seven subproject towns of Second Corridor Towns Development Project

SECOND GMS CORRIDOR TOWNS DEVELOPMENT PROJECT



Two towns in Cambodia

- Sihanouville
- Kampot

Two towns in Lao PDR

- Houayxay
- Luang Namtha

Three towns in Viet Nam:

- Sapa
- Bac Giang
- Mong Cai

Indicative outputs:

- Wastewater collection and treatment
- Drainage, flood control and river embankment
- Road and street lighting
- Solid waste management and sanitary landfill
- Recreational area, park

- Project City
- State Capital
- Provincial Capital
- Economic Corridor
- Main road
- Country administrative limit

0 300km

B. Assessment Context

4. The project is category B pursuant to ADB's 2009 *Safeguard Policy Statement*⁵ and recent good practice sourcebook.⁶ A category B project will have potential adverse impacts that are less adverse than those of a Category A project, are site-specific, largely reversible, and can be mitigated with an environmental management plan (EMP).⁷ The initial rapid environmental assessments (REA) of the subprojects are found in Appendix A

5. The IEE was prepared for the subprojects of Cambodia in the feasibility design stage of the project using available data and information on sensitive ecological and cultural receptors that exist at the different subproject sites. Detailed designs of the subprojects will follow project approval. EMPs that have been prepared for the subprojects will be updated where necessary to meet the final detailed designs of the subprojects.

Impact Footprints

6. The town subproject components are located in established urban and peri-urban areas. Moreover, some subproject component sites already exist such as urban roads and landfills. Thus, the potential environmental impacts of the subprojects will be mostly marginal to the existing urban impacts.

C. Structure of report

7. The report on the IEE follows the format of an EIA in Appendix 1 of the SPS (2009). The IEE was conducted and the results presented by individual town in order to minimize redundancy of background information. The report structure is consistent with, and supports the individual subproject environmental management plans (EMPs) that have been prepared for each subproject town, and which are based on the results of the IEE.

II. POLICY, LEGAL, AND ADMINISTRATIVE FRAMEWORK

A. Environmental Impact Assessment

8. Environmental impact assessment in Cambodia is guided by the Royal Government of Cambodia (RGC) sub-decree on EIA. In compliance with the sub-decree on EIA, all individuals, private companies, joint-venture companies, public companies, ministries and government agencies are obliged to conduct an environmental impact assessment for proposed projects or activities, which must be submitted for approval by the MOE. The decree provides a list of project types that proponents use to screen projects for requiring either an EIA or Initial EIA (IEIA). Consultations with the MOE and provincial Departments of Environment (DOE) indicated the final subprojects in Kampot and Sihanoukville will require either a Cambodian IEIA or EIA that will be administered by MOE. As dictated by No 72 ANRK.BK, the MOE is required to complete their review of a submitted IEIA or EIA within 30 days to conclude the approval process.

⁵ ADB. 2009. Safeguard Policy Statement. Manila.

⁶ ADB. 2012. Environmental Safeguards, A Good Practice Sourcebook, Draft. Manila.

⁷ Footnote 2, pg 19.

9. The IEE presented herein exceeds the requirements of Sub-decree No 72 ANRK.BK on EIA. The scope of the assessment of the IEE required of the ADB SPS (2009) also exceeds the supporting RGC Prakas guideline IEIA/EIA.

B. Legal and Policy Framework for Environmental Protection

10. The Government of Cambodia has established specific laws and regulations for forests, protected areas, and land management to ensure sustainable development. The key elements of the legal and policy framework for the project include the following:

- Law on Environmental Protection and Natural Resources Management, , enacted by National Assembly, 1996, and promulgated by Preah Reach Kram/NS/RKM-1296/36;
- Law on Natural Protected Areas enacted by National Assembly, 2008 promulgated by Preah Reach Kram/NS/RKM/0208/007;
- Law on Fisheries Management and Administration(1989);
- Law on Forest enacted by National Assembly, 2002 promulgated by Preah Reach Kram/NS/RKM/0802/016;
- Law on Land enacted by National Assembly, 2001 promulgated by Prea Reach Kram/NS/RKM/0801/14;
- Law on Water Resource Management produced by Ministry of Water Resources and Meteorology (MOWRAM); and
- Circular No 01 SRNn issued on February 3rd, 2012, Royal Government Of Cambodia on Cambodia Coastal Zone Development

11. Key directives in support of the Law on Environmental Protection and Natural Resources Management include:

- Law on Protection of Natural Areas (2008); and
- Sub-decree on Water Pollution Control (1999):
 - Annex 2: Industrial effluent standards (including WWTPs);
 - Annex 4: Water quality standards for public water and biodiversity; and
 - Annex 5: Water quality standards for public waters and health.

12. Other pertinent regulations, policy, or guidelines for the project are as follows:

- Directive on Industrial Sludge Management (MOE, 2000);
- Directive on Industrial Hazardous Waste Management (MOE, 2000);
- Directive on Managing Health Wastes in the Kingdom of Cambodia (MOH, 2008)
- Preach Reach Kept on Creation of Fisheries Communities (2005); and
- Anklets on establishment of protected forests, natural resources conservations, wildlife protection areas, protected forest for biodiversity conservation (2002 and 2004).

13. Cambodia is signatory to many international environmental treaties and conventions which provide a comprehensive legal framework related to coastal management. These include: the Coordinating Body of the Seas of East Asia (1995), Association of South East Asian Nations (1999), MARPOL (1994), Biodiversity convention (1994), CITES convention (1997), Ramsar convention (1999) and Climate Change convention (1995) (MOE 2006). The closest Ramsar site to the subproject areas is more than 100 km away in Koh Kapok, Koh Kong province to the west.

14. Occupation and Community Safety and Health (OHS) guidelines for Government follow the recent OHS Programme for Cambodia (2010-2013) that was developed by the International Labour Organization (ILO). The draft guidelines provide the framework for instituting OHS at the workplace and in the community.

15. For all other applicable environmental standards and criteria such as ambient air quality, vibration, noise, contaminated soil, and workplace and community safety the standards and protocols of the Environment, Health and Safety Guidelines of the World Bank (2007) will apply.

C. Agencies Responsible for Environmental Management and Assessment

16. The national agencies that oversee environment and natural resources management are listed below. Most of Ministries have provincial counterpart departments.

- Ministry of Environment (MOE);
- Ministry of Agriculture, Forestry and Fisheries (MAFF);
- Ministry of Water Resources and Meteorology (MOWRAM);
- Ministry of Mine and Energy (MME);
- Ministry of Industry and Handicraft (MIH)
- Ministry of Land Management; and Urban Planning (MLUP);
- Ministry of Tourism (MOT);
- Ministry of Public Works and Transport (MPWT) and a cross-ministerial policy body of
- National Climate Change Committee (NCCC).

17. The MAFF is responsible for the management and protection of coastal mangrove forests, and wildlife and fisheries. The Fisheries Administration (FA) at the national and provincial levels is responsible for all fisheries related matters as summarized below:

- Prepare and establish fishery resource and aquaculture inventories;
- Enact laws, regulations, and orders for fishery protection, management and improvement of fishery resources and habitat;
- Manage fishery zones, fishery conservation and establish fishery resource development policies;
- Conduct scientific studies of fisheries and aquaculture; and
- Inspect and manage fishery resource exploitation and aquaculture activities.

18. The EIA Department of the MOE oversees and regulates EIA, and coordinates the implementation of projects in collaboration with project executive agencies (EA) and concerned ministries. The MOE has the following responsibilities:

1. Review, evaluate, and approve submitted environmental impact assessments in collaboration with other concerned ministries; and
2. Monitor to ensure a project owner (the executing agency of the project) satisfactorily implements the Environmental Management Plan (EMP) throughout pre-construction, construction and operational phases of the projects.

19. The ministries are represented and supported at the provincial, town, and district/commune levels by counterpart line departments, agencies, and sub-offices. The counterparts are responsible to extend and implement the mandate of their parent ministries to the commune level.

20. The IEE prepared for subprojects in Cambodia meets or exceeds the EIA requirements of the MOE. The IEE will provide guidance to the national consultants of the Ministry of Public Works and Transport who will prepare the IEIA or EIA for the MOE.

D. Climate Change Directives

21. The following initiatives have been undertaken to combat climate change in Cambodia. These have been derived in part by the Cambodia Climate Change Alliance (CCCA).

- Cambodia Climate Change Strategic Plan (2014 – 2023)
- National Strategic Development Plan (2014 – 2018) - Addressing Climate Change
- National Monitoring and Evaluation Framework for Climate Change (ongoing)
- Climate Change Education and Awareness Strategy

E. ADB Safeguard Policy

22. The ADB safeguard policy statement (ADB 2009) along with the recent *Good Practice Safeguard Sourcebook* clarify the rationale, scope and content of an environmental assessment and supported by technical guidelines (e.g., Environmental Assessment Guidelines, 2003). Projects are initially screened to determine the level of assessment that is required according to the following three environmental categories (A, B, or C).

23. Category A is assigned to projects that normally cause significant or major environmental impacts that are irreversible, diverse or unprecedented such as hydroelectric dams (an Environmental Impact Assessment is required). Category B projects have potential adverse impacts that are less adverse than those of category A, are site-specific, largely reversible, and for which mitigation measures can be designed more readily than for category A projects (an Initial Environmental Examination is required). Category C projects are likely to have minimal or no negative environmental impacts. An environmental assessment for Category C projects is not required but environmental implications need to be reviewed.

F. Environmental Due Diligence of Subprojects

24. The environmental due diligence (DD) of the subprojects in Kampot and Sihanoukville required by the ADB and the RGC⁸ proceed in series with the ADB IEE and loan approval completed first. A significant difference in the DD of Cambodia and the ADB is the timing of the IEE for ADB and the EIA or IEIA for Cambodia. The ADB IEE is prepared for the feasibility design stage of the subprojects whereas the EIA/IEIA for Cambodia is prepared for the detailed - completed subproject designs. Thus, the ADB IEE is approved by the government EA⁹ and the ADB long before the Cambodian EIA/IEIA is prepared. Table 2 summarizes the general DD processes and timelines of the two jurisdictions.

⁸ Sub-decree No 72 ANRK.BK on EIA.

⁹ Government appointed Project Executing Agency

25. The Cambodian government does not require the ADB IEE/EMPs prepared for a project to comply with any specific environmental regulations or guidelines, however, the draft IEE/EMPs must be reviewed and approved by the EA (not the MOE) after the initial review and approval by the ADB. The approval is by formal letter.

Table 2. Summary of environmental due diligence during project implementation

Design and Implementation	Environmental DD and Approvals			Milestones & Notes
	ADB / PPTA	Cambodia	PMIS ¹⁰ / Contractor	
Feasibility design				
Initial stakeholder disclosure & consultation	PPTA	EA assists		
Draft IEEs and EMPs	PPTA			Draft IEEs & EMPs completed
Finalize IEEs and EMPs	ADB review & approves IEE/EMPs			ADB approved IEE/EMP as per SPS (2009).
		EA reviews and approves IEE/EMPs		EA approved IEE/EMP with formal letter only. Compliance with specific RGC / EA regulations not required
Loan documents (PAM/RRP)	Document preparation, approval by ADB	Review & approval of PAM		Loan approval
Detailed engineering design				
Continued stakeholder disclosure & consultation		IA/PIU ¹¹ lead	ES ¹² support to PMIS	As per PCP (2012) ¹³ stakeholder disclosure and consultations continue throughout construction phase coincident with initiation of GRM ¹⁴ .
Update EMPs		Support to ES	Lead by ES	Approval of updated EMP by EA and ADB
Initiation of Cambodia environmental DD ¹⁵		EA leads with oversight from MOE		DOE approved CAM IEE or IEIA follows independently

¹⁰ International Project Implementation Management Support Consultant (see Environmental Management Plan EMP)

¹¹ Project Implementation Agency assigned by EA (see EMP) with supporting Implementation Unit

¹² International and national environment specialists of PMIS (see EMP)

¹³ ADB Public Communication Policy (2012)

¹⁴ Grievance Redress Mechanism (see EMP)

¹⁵ Footnote 8

Design and Implementation	Environmental DD and Approvals			Milestones & Notes
	ADB / PPTA	Cambodia	PMIS ¹⁰ / Contractor	
Tendering / contract award				
EMPs included in tender documents		Lead by EA/IU	Support by ES	
Tenders let and bids prepared		Lead by EA	Contractor drafts CEMP ¹⁶	CEMPs prepared and included in contractor bids
Construction packages	Input from ADB		CEMPs reviewed by ES/PMIS	Construction package awards
Construction & supervision				
Implementation of mitigation and monitoring plans		Support from IU/PIU	By contractor with support from ES	CEMP implemented by contractor, other aspects of EMP overseen by ES
Continued stakeholder disclosure and consultation		IA/PIU lead	Support from ES	As part of GRM
Monitoring reporting	To ADB	IA/PIU lead preparation of regular reports to ADB	Support from ES	Reports provide input for review missions

III. DESCRIPTION OF CAMBODIA SUBPROJECTS

26. Explicit with selection of the subproject components are the Strategic Local Economic Development Plans (SLEDP) for Kampot and Sihanoukville from the main PPTA report, and the inherent theme of the greening of the affected urban environments, vis-à-vis, ADB's Green City Agenda. Coupled to the objective socioeconomic-based urban infrastructure developments is the opportunity to improve and rehabilitate the natural urban environments. The selection criteria for the subproject components included improvements to green spaces.

27. The descriptions of the subproject components in Kampot and Sihanoukville are provided below¹⁷. The subproject components that are similar, or physically related are combined in order to prevent redundant assessment.

Kampot
Wastewater Collection and Treatment
Solid Waste Management
Urban Drainage

¹⁶ Construction Environmental Management Plan based on EMP in tender documents (see EMP)

¹⁷ Updated from Fact Finding Mission, 5/15

Sihanoukville
Solid Waste Management
Urban Drainage

A. Kampot

28. The major subproject components of Kampot from Table 1 are shown in Figure 2.

Figure 2. Location of major subproject components in Kampot



1. Wastewater Collection and Treatment

29. Wastewater in Kampot presently flows untreated directly to the Teuk Chhou river through combined road drains, or via a canal southeast of town. The proportion of some form of pumpable septic tank in use in the town is estimated at 70-80%. There are 8 drain outfalls to the river in the town centre area which smell badly particularly during the dry season and low tide conditions when dilution is minimal.

30. The subproject will separate wastewater at source and treat it at a new wastewater treatment plant (WWTP) 2 km south of the town on the east bank of the Teuk Chhou river. The three catchment areas for separate wastewater collection and treatment at new WWTP are described below, and shown in Figure 3 in different colours.

- A core area on the north side of town a block from the old town centre to the market area. This is the most densely populated area of Kampot;
- The city centre area east of National Road (NR) 3; and
- South of town in vicinity of provincial government buildings.

31. Because Kampot is a small town the extra work involved in including all three core areas instead one or two areas is small. Thus, it is recommended that all three core areas in Figure 3 are included in the subproject component. The type of the WWTP should be lagoon-based. The three catchment areas are divided approximately by NR#3. Wastewater will be gravity fed to strategically located pump stations which will deliver wastewater to the WWTP. The WWTP will require a capacity of 4,500 m³/day to meet demands for a 20 year design life.

32. Sihanoukville subproject town has good experience with these WWTP systems from an earlier ADB project thereby allowing skills and experience transfer to benefit of Kampot. To learn from the Sihanoukville experience all connections to the system should be provided to property owners free of charge with a connection and grease trap chamber included for each household under project implementation.

33. The proposed WWTP site is an undeveloped wetland approximately 100m from the east bank of the Teuk Chhou river, 1.8 km south of the provincial government offices in town, or 2.5 km from the market square (Figure 3). The area is seasonally flooded, and as such the WWTP will need to be climate-proofed by sufficient grading with all lagoons bunded above recorded flood levels. The approximately 6.1 ha of land private and will need to be purchased. The previous 2.9 ha site identified in the town masterplan is too small, too close to town centre, and cannot be used for a lagoon based WWTP. Construction of the wastewater pipeline network should be carried out in the dry season to minimize erosion and spread of construction waste.

34. A septic tank septage treatment or storage facility is also required on site. Septage treatment could be by co-treatment in the proposed WWTP, however, due to the high solids content of the septage, the capacity of the primary lagoon will be reduced. The design of the primary lagoon will need to be enlarged to take this into account. The alternative is to dispose of the septage in lined storage pits at the WWTP site. The first option is recommended because the septage will be treated and as the WWTP is at pre-design stage, any additional measures that need to be incorporated into the design to treat septage can be taken (for example larger

Figure 3. Three wastewater catchments and new WWTP site in Kampot



primary lagoon, access ramps for vacuum trucks and odour reducing receiving well). Two vacuum trucks will be provided, one 6m³ and one 2m³ for access down smaller lanes.

35. In March 2015 a regional NGO GRET proposal a basic septage drying pilot plant for Kampot. No treatment (anaerobic or aerobic digestion in lagoons) would occur prior to drying. Land has been identified near the former airport (1,000m²) and funding of Eur30,000 has been secured for construction of drying beds of capacity to 20m² of septage per month. The project also aims to improve access to latrines through grants for poor households and to help develop the private sector in septage collection services. This is a small “pilot” project and will not affect the planning for the component, rather would supplement the WWTP to raise awareness and capacity for septage removal and treatment in advance of the subcomponent construction.

2. Solid Waste Management

36. The existing dump site (Figure 4) is in a flat and hilly area 10 km north of the town in Prey Khmom commune, Teuk Chhou district, and is accessed with a 3 km unsealed track off the main highway. A solid waste collection service currently is contracted by the Government with approximately 85% of houses on the collection route having garbage collected. The province reported that originally the 17.2 ha site was divided into three parts: a) dump site (15.2 ha); b) hazardous waste site (1 ha); and c) a composting area (1 ha).

37. The dump site was originally divided into 80m x 30m x 4m deep cells. However, the current facility as inspected in September and November 2014 is an uncontrolled dump with no leachate collection or cell management. The cells are not distinguishable. Garbage is dumped over a wide area close to the access road without organized compaction or regular covering with earth. Garbage is periodically burned. There is a separate composting facility operated by an NGO with a consultant project manager located in town. Collection and dump management are currently contracted out to Gaia, a private company.

38. A new landfill is proposed north of the existing landfill with a design that is between a controlled dump and a controlled landfill as opposed to a sanitary landfill (Figures 5 and 6). The design of the landfill includes clay lining, groundwater monitoring, planned cell development, leachate collection and storage, surface water management, cover soil storage, regular covering of waste and controlled waste picking. The proposed location of the landfill is 11.5km north of the city on 19ha of government land in Prey Khmom commune, Teuk Chhou district. There are no people living on the proposed site. An improved 3.1 km access road connecting to (NR3) is included. The closure and restoration the existing dump site is included (Appendix D).

39. A separate pit for medical waste will be provided along with a small incinerator with shed for infectious waste. Provision of relevant equipment and machinery for collection and processing will be made and included in the subproject. Equipment will include one rear-loader compactor truck and one open 6m³ truck for waste collection, ten steel bins (skips) of 1m³, ten hand carts, and two skip-carrying trucks equipped with hydraulic lifting arms.

40. The mechanism proposed for improved waste collection from areas with difficult access will involve establishing transfer stations at each village with appointed community members contracted to collect waste from each household and deliver it to the skip located at the transfer stations. Either the province or a contractor will then collect the skip for transfer to landfill.

Figure 4. Existing and new landfill sites north of Kampot



Figure 5. Plan view of new landfill in Kampot

LAYOUT PLAN OF SANITARY LANDFILL IN KAMPOT





Figure 6. Cross sectional views of landfill cells and access road


Typical Cross Section of Solid Waste Landfill Cell and Leachate Pond

Not to scale




Typical Cross Section of Access Road

Not to scale




Typical Cross Section of Access Road

Not to scale



Typical Cross Section of Road Connect From NR3

Not to scale



3. Urban Drainage


41. In Kampot roadside drains line the main sealed roads in the urban area with the main drains running down to outfalls at Teuk Chhou riverbank which create plumes of combined black water and stormwater. Some areas of the town are still susceptible to flooding as the undersized pipes are commonly blocked. The area around the market is particularly flood prone.

42. Separated wastewater system upgrades to the road drains and receiving channels are required to stop regular flooding. The areas of chronic flooding include the market area, one side of the main garden square, the road next to the hospital at the river, and the road from the southern-most roundabout to the river. There are also two collector channels on the west side of the river and one main channel on the east side that require dredging, re-defining, and installation of stone masonry banks where appropriate. Figure 7 shows the drains of the town that will be upgraded by the subproject, and Figure 8 provides a generic schematic of lateral upgraded roads drains that will be installed.

Figure 7. Locations of drainage network to be upgraded in Kampot.

1:5.000

PROJECT LOCATION MAP (KAMPOT CITY ROAD)



NOTES

Existing Drainage


Project Location (Pipe Culverts Dia. 0,60m = 2.273,00m)

Project Location (Box Culverts @ 2,00 x 1,5 , Length = 1.504,00m)

Project Location (Box Culverts 2@ 2,00 x 1,5 , Length = 835,00m)

Project Location (Retaining wall)

Figure 8. Generic road upgraded drains for Kampot



B. Sihanoukville

43. Sihanoukville centre outlining the urban drainage network is shown in Figure 9.

1. Urban Drainage


44. There are drains along some of the sealed roads in the urban area but others with drains along other roads either missing, blocked, or of a type that are difficult to maintain and require replacement.

45. Eleven areas have been identified for new drains. Concrete pipe drains with manholes every 25m are proposed for ease of maintenance. Existing drains will be removed and the same alignment will be used for the proposed drains. In order of priority the locations requiring drains are as follows (Figure 9):

Priority	Description	Length (m)
1	Occheuteal Rd No.500	3,370
2	Lumhe Preah Phomin Road No.400	3,130
3	Vithey No. 500	325
4	Pi Thnou Road No.600	8,340
5	Cambodia- Soviet Road No.703	2,485
6	Phe/port Rd No. 700	2,441
7	O'Pir Rd No. 800	5,087
8	Vithei Prampi Makara, Damban Montipet Bang Ek Krong No.200	2,085
9	Damban Tomnup Rolork-Samdech Hun Sen Road No.148	5,845
10	Damban Outoniyum/Meteorology region	1,357
11	Damban O'Tres Chah No.149	8,740
12	New Road from NR#4 at km188 to Otres Beach	5,894
13	Vithei Borei Kamakor,	3,000

46. Construction of as many of the drains as possible is proposed within the remaining \$9.34M budget which is the estimated budget remaining from the ADB loan allocated to Sihanoukville after the solid waste and wastewater subprojects has been made budgeted.

Figure 9. Sihanoukville centre showing drainage network



2. Solid Waste Management

47. The existing dump site is approximately 25km from the town (Figure 10). The state of the dump site is poor, and provides limited space and topography not suited to a landfill or dump site. Access is along a 1km dirt road from national road 4 which is difficult to access during the wet season. Waste is spread along the access road for a distance of 2-300m before the actual dump site due to difficulty with wet weather access. Waste is dumped at the side of the access road and is periodically pushed over the side of the hill. There is no leachate collection, periodical covering with earth or use of cells. There are approximately 168 people working on the dump site, many of which are day visitors, and the rest permanent residents. They earn up to \$50/month collecting recyclables and selling on to a dealer.

Figure 10. Existing solid waste dump site in Sihanoukville



48. Currently collection is made by the private sector carrying 24 truckloads a day from some areas only. In the limited areas served collection rate is close to 100%. However, many areas do not have collection service due to difficult access by the large collection trucks. The private contract with CINTRI for dump site management expires in December 2015.

49. Originally, the plan was to close and replace the existing landfill with a new landfill site about 1 km further north in a densely forested area. However, this proposal was rejected because the new site was on sloping land, too far from town, and required a forest clear-cut equal to total footprint area of the new landfill.

50. Alternatively, the plan is to upgrade the existing solid waste management system in Sihanoukville which includes expand the urban collection service area, and renovate current landfill site as a controlled landfill. A controlled landfill is much better than the status quo but not as advanced as a sanitary landfill. The current dump will have solid waste moved into one confined area, compacted in layers, and covered with earth, leaving further area within the current boundary to be utilized as controlled landfill. The renovated landfill will include a clay lining, groundwater monitoring, planned cell development, leachate collection and storage, surface water management, regular covering of waste and controlled waste picking. A separate pit for medical waste will be provided, and a small incinerator with shed for infectious waste.

51. Equipment and machinery for collection and processing will be provided such as one rear-loader compactor truck and one open 6m³ truck for waste collection, ten steel bins (skips) of 1m³, ten hand carts, and two skip-carrying 4 X 4 trucks equipped with hydraulic lifting arms. An area outside of the landfill site will be set aside for resettlement of permanent residents of the existing dump, with water supply and sanitation provided.

52. The Provincial authorities requested that a package treatment plant be provided to treat the leachate prior to discharge to the environment. However, because the existing landfill will be renovated there is insufficient area for a package plant, and moreover, the expense of a package treatment plant is no longer viable.

53. The subproject will include a public awareness campaign to increase the collection service area, and capacity building for the DOE operators. The solution for improved waste collection from areas with difficult access will involve establishing transfer stations at each village, with appointed community members contracted to collect waste from each household and deliver it to a skip located at the transfer stations. Either the province or a contractor will then collect the skip for transfer to the landfill.

IV. DESCRIPTION OF AFFECTED ENVIRONMENTS

54. The description of the affected environments of Kampot and Sihanoukville focuses on the immediate subproject areas that could possibly be affected by the different infrastructure and environmental improvement investments in the two subproject towns, or the environmental features that could possibly influence the successful implementation and operation of the completed subprojects. Other regional environmental information is included for required context only.

55. Environmental baseline information was obtained primarily from recent provincial State of the Environment Reports (SOER) prepared by the provincial DOEs and supplemented with information from other reports where available. Because the provincial capitals of Kampot and Sihanoukville are close and share the same coastal environment as indicated by the overlapping SOERs, the description of the affected environments are presented jointly to prevent repetition. The data and information obtained for the two subproject areas, which target the natural environments and land use, is sufficient to obtain a sufficient understanding of the potential environmental impacts of the different subproject components. The detailed description of the socioeconomic and demographic profiles of Kampot and Sihanoukville areas is provided in the Social Assessment and Land Acquisition - Resettlement chapters of the draft final report.

A. Southern Cambodia Profile

1. Climate

56. Southern coastal Cambodia experiences a tropical monsoon climate with two distinct seasons defined by; (1) the dry season from approximately November to April associated with the northeast monsoon which provides drier and cooler air with February being the driest month; and (ii) the wet season from May to October during which rainfall is largely derived from the southwest monsoon drawn inland from the Indian Ocean.

57. The rainfall pattern is bi-modal with peaks in June and September/October. In the dry season, the temperature of the province is high in April with an average of 36.6°C and the coldest month is February with an average temperature of 21.10°C. The average annual rainfall in Kampot-Sihanoukville is 1,407 mm with the greatest recorded total annual rainfall of 2,604mm.


2. Soils

58. The soils of coastal Kampot and Sihanoukville are dominated by a mix of old and young alluvium soils of sediment deposits from rivers and streams (Figure 11).¹⁸ These are mainly finer sediments, thus a high concentration of silt is found in the coastal and nearshore areas. Alluvial deposits normally result in fertile land.

3. Forest Areas

59. The forest types and areas of Cambodia are shown in Figure 12.¹⁹ Most of the major forests are situated in the southeastern, central, and northeastern regions of the country. Forest cover in Kampot and Sihanoukville is relatively sparse due to long past land clearing deforestation with the closest major forests located in Bokor National Park northwest of Kampot


Figure 11: Soil types of Cambodia



¹⁸ MOE 2004

¹⁹ NREM DATA TOOL BOX -Royal Danish Embassy- Danida - Phnom Penh, Cambodia, March 2007.

Figure 12: Forest types of Cambodia



and in Ream National Park east of Sihanoukville (Figure 14). Other forested areas in the Preah Sihanouk province are located far north of Sihanoukville town.

B. Kampot and Sihanoukville Subproject Areas

60. The province of Kampot is located in southwestern Cambodia with a total coastline of 73 kilometers. The province occupies 4,873 km² and consists of 8 districts, 92 communes, and 104,993 households. The total population of the province is 528,405. The 8 districts are Kampong Bay, Kampot, Chhuk, Dang Tung, Chum Kiri, Kampong Trach, Banteay Meas, and Angkor Chey. Three of these districts – Kampong Bay, Kampot and Kampong Trach are located in the coastal area with 26 villages.

61. Sihanoukville town is also located on the coast approximately 100 km west of Kampot town. Preah Sihanouk province is bordered to north by Koh Kong province, and to the east with Kampot province. Sihanoukville municipality expands 868 km² and consists of three districts (Khan) and 22 communes (Sangkat)²⁰

1. Physical Resources

62. The topography and land use of the coastal zone south of Kampot town is characterized by a mix of relatively sparse agriculture, salt harvesting fields, and mangrove forests which occur along the Teuk Chhou River which flows through Kampot town south to Kampot Bay. The salt producing operations (seawater evaporation) adjacent to the Teuk Chuu River are extensive

²⁰ 2002, MOE. State of Environment Report of Sihanoukville, 31pgs.

and dominate the peri-urban land use of the area. Kampot town lies in the flood plain and estuary of the Teuk Chhou river.

63. The topography of Sihanoukville consists of mix of lowland and upland areas. The lowland periphery of the town consists of coastal beaches, scattered mangrove forests extending east to Preah National Park, and scattered aquaculture. North from the beaches the town rises abruptly to an elevated plain area that has been designated as a water recharge zone. Across the elevated plain area is scattered agriculture and patchy forest. The economic zone and port lands area extends west and northwest around and along the coast.

a. Rivers

64. Many rivers drain to the coastal area some of which commonly dry up in the dry season. During the dry season the lower reaches of the rivers are brackish. Some rivers emptying to the sea are listed in Table 3.²¹

Table 3: Example rivers discharging to ocean from Sihanoukville and Kampot areas

Kampot Bay	Sihanoukville
Kbal Romeas River	Prektropaing River
Teuk Chhou River	Kountany River
Koh Toch River	Kountaveit River
Kdart River	Proh River
Smach River	Kampong Chen
	Preak Traeng stream

b. Surface Water Quality

65. The available surface and coastal water quality data of southern Cambodia is relatively good compared to other regions of Southeast Asia. However, the steadily increasing industrial development, intensive agriculture, and deforestation in Cambodia is reducing the quality of surface waters in different areas due pollution from untreated effluents, land erosion, and agriculture chemicals.

66. A summary of water quality during the dry season at river and coastal sites is summarized in Table 4 with water quality survey sites for Kampot and Sihanoukville shown in Figure 13.²² Baseline to be updated during detailed design phase (see EMP).

Table 4. Dry-season river and coastal water quality 2005 – 2006


Variable	Average	Maximum	Minimum	Government Standard
River 288 samples from 12 sites				
Temp	30.5	33.2	27.6	
pH	7.7	8.1	7.3	6.5 - 8.5

²¹ DOE and Danida, 2002. State of Environment Report for Kampot province

²² DOE and Danida, 2006. Second Annual Monitoring Report for Coastal Rivers and Nearshore Coastal Waters of Cambodia.

Variable	Average	Maximum	Minimum	Government Standard
Salinity (‰)	12.9	20.3	3.8	
Secchi depth (m)	1.4	1.9	0.8	
total suspended solids (mg/l)	11.1	26.5	2.7	25-100
dissolved oxygen (mg/l)	5.2	6.1	4.5	2.0 - 7.5
biological oxygen demand mg/l)	0.7	1.2	0.4	1 - 10
total nitrogen (mg/l)	0.09	0.18	0.04	
total phosphorous (mg/l)	0.008	0.02	0.002	
Coastal				
96 samples from 8 sites				
Temp	29.6	32.5	26.1	
pH	7.8	8.1	7.6	7.0 – 8.3
Salinity (‰)	25.8	30.1	20.8	
Secchi depth (m)	1.9	2.3	1.3	
total suspended solids (mg/l)	17.7	37.6	3.1	
dissolved oxygen (mg/l)	5.3	6.0	4.7	2.0 - 7.5
biological oxygen demand mg/l)	0.7	1.1	0.3	
total nitrogen (mg/l)	0.1	0.21	.05	0.1 - 1.0
total phosphorous (mg/l)	0.008	0.018	0.002	0.02 – 0.09

Figure 13. Water quality sampling sites in Kampot Bay and near Sihanoukville



c. Air quality

67. No air quality data are available for the subproject areas. Baseline data to be updated during detailed design phase (see EMP).

2. Biological resources

a. Protected Areas

68. There are two ecological protected areas in the vicinity of the subproject areas (Figure 14). Bokor National Park in Kampot is located approximately 25 km northwest of Kampot. Ream National Park is located closer to Sihanoukville but still well away from the subproject areas which situated to the west in the town centre and north of Hwy #4.


69. The important bird areas (IBA)²³ in the region are located inside the two national parks and away from the subproject areas (Figure 15). There are no rare or endangered terrestrial wildlife in the subproject areas.

Figure 14: Location of Bokor and Ream National Parks near subprojects.



²³<http://birdlifeindochina.org/datazone/14>

Figure 15. Important bird areas in National Parks of Kampot and Sihanoukville



b. Marine Coastal Zone of Kampot and Sihanoukville

70. Kampot and Sihanoukville along with the provinces of Koh Kong and Kep form Cambodia’s coastal zone along the Gulf of Thailand. Cambodia’s coastal resources play an important role in the country’s development by supporting the fisheries, aquaculture, agriculture and tourism sectors. Of particular importance are the role of mangroves, seagrass, and corals in the fisheries and tourism industries.

i. Mangroves Forests

71. The area of mangrove forests along the coastline of Cambodia has declined significantly over the last two decades. However, the estimated 56,000 ha that remains represents a rich resource and area of critical habitat in relation to other areas in Southeast Asia. The largest mangrove areas in the subproject areas are situated in Koh Kong province north of Sihanoukville, and between Sihanoukville and Kampot (Figure 16). The remaining mangroves in Sihanoukville are situated just west of the town centre. In Kampot dense mangrove forests grow along the west bank of the Teuk Chhou River south of Kampot, and extend west along the coastline of Kampot Bay. Similar to seagrass, mangrove forests are critical habitat and play an essential role in the lifecycle of many marine organisms, and provide spawning or nursery grounds that support the rich biodiversity of fish species which include commercially important species. The mangroves forests of Koh Kong provide

Figure 16: Mangroves, coral reefs, and seagrass areas in Kampot and Sihanoukville.

Fig 16a: Mangroves



Fig. 16b: Coral reefs



Fig 16c: Seagrass



habitat for the rare and endangered smooth-coated and the hairy-nosed otters.

72. Mangroves play an essential role in protecting the coastline and provide an effective buffer against climate change-related sea level rise, cyclonic activity and storm surges. Mangrove loss is due to shoreline infilling and development, illegal harvesting for fire wood and charcoal, and shrimp aquaculture among other uses.

a. Coral Reefs

73. Cambodia supports an estimated 2,700 ha of coral reefs with the most extensive coverage occurring in off Kampot and Sihanoukville²⁴ (Figure 16) Approximately 70 coral species are found within the coastal zone, though little is known about the relative distribution and composition of the reefs. These reefs are threatened by development, overfishing, coral harvesting degradation of the water quality, and destructive fishing practices such as dynamite.

b. Seagrass

74. Cambodia's coastal zone supports one of the world's largest areas of seagrass habitat in the shallow nearshore zone.²⁵ This critical habitat provides rich reproductive, nursery, and feeding habitat for many different species including rare and endangered species such as the Dugong marine mammal, sea turtles, seahorses, and an array of finfish and shellfish. The defined seagrass beds of Kampot and Sihanoukville (Figure 16) with particular reference to the estimated 25,420 ha seagrass off Kampot is also critical habit for inshore and offshore fisheries. There are indications that seagrass habitat is being lost to degraded water quality

²⁴ UNEP 2009

²⁵ UNEP 2009.

from increased turbidity caused by forest clearing, shoreline infilling, sand dredging. The Fisheries Administration of MAFF has produced a National Action Plan for Coral Reef and Seagrass Management in Cambodia (2006-2015).²⁶

c. Marine Fisheries

75. Estimates of the average annual catch²⁷ of fish in Kampot province is between 7,000-8,000 tones, and over 450 tones in Kep. There has been a shift from smaller to bigger boats away from the inshore fishery. While overall fish catch has been increasing since about 1980 due to the increase in marine fishermen and industrial-scale technologies, fish catch per unit has been steadily declining, principally due to an increasing coastal population and unrestricted development in ecologically-sensitive habitats.

76. Early estimates indicated that there were over 416 motorized fishing boats in Kampot which will have increased significantly to date. The common groups of fishes caught include fishes, shrimps, and octopus. Coastal fishing communities may be boosted following the advent of Community Fishing Area Management Plans (CFAMP)²⁸ along the coastline. The plans detail activities and goals for improved resource management and community development but currently suffer a lack of a baseline understanding of current resources.

3. Land use at subproject sites

77. Land use in Kampot and Sihanoukville ranges broadly from the urban settlements of each town to mixed agriculture including the salt farms of Kampot, aquaculture, fishing, and the industrial development zone and portlands of western Sihanoukville. Managed forests exist to the north of Kampot and Sihanoukville with protected forests located inside Bokor and Ream National Parks. Kampot settlement areas such as Kampot town to barren areas commonly seen as such rock outcrops. Dense broad leafed forest is found within both National Parks.

C. Features of Subproject sites

1. Kampot

78. Figure 17 shows the site of the new WWTP south of Kampot just east of the Teuk Chhou river. The vegetated lowland site is inundated during the rainy season and will require infilling to isolate the lagoons and facilities from seasonal flooding. A densely treed fenced perimeter will be required to isolate negative aesthetics of the WWTP such as odour and noise from adjacent houses. Treated discharge pipe and outfall to Teuk Chhou river will be placed either south or north (foreground) of house in Figure 17.

²⁶ MAFF, 2006. 'National Action Plan for Coral Reef and Seagrass Management', 2006-2015.

²⁷ MOE and Danida, 2002. State of Environment Report for Kampot

²⁸ The CFAMPs developed collaboratively by Fisheries Authority and communes. SorSarin, DAF pers comm. 2013

Figure 17. Site of new WWTP (left) east of Teuk Chhou river (on right)



Figure 18. Existing dumpsite, and site of new landfill north of Kampot



79. The existing dumpsite, and the site for new landfill just to the north are shown in Figure 18. The dumpsite will be closed after the waste field is consolidated to a smaller area (Appendix D). No data exist for the depth and quality of local groundwater which will need to be investigated during the detailed design in order to complete the detailed design of the new landfill and closure of dumpsite (Appendix C).

80. Figure 19 shows an example outfall of an urban drain to the Teuk Chhou river, and the existing raw WW canal that flows to the Teuk Chhou river south of town just north of site of new WWTP. The canal will not be used for WW after new WWTP and pipeline are commissioned.

Figure 19. Example town drain outfall to Teuk Chhou river, and WW canal



2. Sihanoukville

81. Figure 20 shows the main dumping area of the existing landfill site northeast of Sihanoukville, and a groundwater well located between the waste picker houses adjacent to dumping area. The operation of the well head will need to be checked as part of the groundwater study (Appendix C) required to finalize the planned renovations of the dumpsite to landfill status.

Figure 20. Main dumpsite of Sihanoukville, and onsite well head





Natural Hazards and UXO

82. Being coastal the subprojects in Kampot and Sihanoukville are sensitive to the same primary natural hazard which are typhoons and related typhoon surge from the Gulf of Thailand. Both areas experience heavy seasonal monsoon rains, however, coastal storms are more dominant.

83. The years of civil war during the 70s and earlier Viet Nam-American war has resulted in the continued risk of UXO harm especially in areas of new excavation. Both subproject sites need careful screening for UXO during the pre-construction phase.

V. PUBLIC CONSULTATION

84. The stakeholder consultation strategy during project preparation embodied the principles of meaningful engagement, transparency, participation, and inclusiveness to ensure that affected and marginalized groups such as women and the poor were given equal opportunities to participate in the design of the project, in accordance with the requirements ADB's *Safeguard Policy Statement* (2009), and the ADB Public Communication Policy (2012). Stakeholder consultations for the environment were conducted jointly with the parallel social impact assessment of the two subprojects in Kampot and Sihanoukville.

85. The approach to stakeholder consultation for environmental concerns or issues with the Kampot and Sihanoukville subprojects consisted of the following three avenues of inquiry and data collection:

- 1) As part of the household and village leader interviews conducted by the social development team;
- 2) Where possible separate consultations with provincial agencies and other stakeholders with by social development team; and
- 3) Individual interviews conducted by the International Environment Specialist during project meetings with provincial and national environmental management agencies.

86. Public Consultation will continue during the detailed design and construction phases as per the PCP (2012) and general requirements of Cambodia. Table 2 in section summarizes the insertion points for public consultation in the final design and implementation of the subprojects.

A. Identification of Stakeholders

87. Stakeholders were identified and engaged in a participatory manner. Stakeholder communication to date has focused on institutional stakeholders, affected communities, and persons directly affected by proposed subproject interventions. The stakeholders involved in the design of the project include:

- Institutional stakeholders invited including the (i) project EA and IUs (ii) provincial agencies (e.g., Environment, Women’s Affairs, Commerce, Tourism, Water Resources, Public Works & Transport); private sector groups, and chambers of commerce;
- Communities living near the subproject areas who will benefit from the project, and who have an interest in identifying measures to enhance or maximize the benefits;
- Communities within the subproject area who may be directly and/or adversely affected, and who have an interest in the identification and implementation of measures to avoid or minimize negative impacts;
- Vulnerable and/or marginalized groups who have an interest in the identification and implementation of measures that support and promote their involvement and participation in the project; and
- Other institutions or individuals with a vested interest in the outcomes and/or impacts of the project.

B. Discussion Guide

88. Five open-ended questions, and information requests (Table 5) were posed guide discussions of the stakeholders.

Table 5. Guiding Questions and Information Requests for Stakeholder Consultations

<p>1. What will be the benefits of the subproject?</p> <p style="padding-left: 40px;">Please list benefits of project.</p>
<p>2. Do you have any environmental concerns with the subproject?</p> <p style="padding-left: 40px;">Please list environmental concerns of project.</p>
<p>3. Do you any have environmental concerns with the construction activities of the subproject?</p> <p style="padding-left: 40px;">Please list environmental concerns of construction phase activities.</p>

4. Do you have environmental concerns with the **completed operation phase** of the completed subproject?

Please list environmental concerns of the operation of completed subproject.

5. Do you think the subproject design or operation should be changed to prevent negative environmental, or community impacts?

Please list changes to subproject that you think will prevent or reduce negative environmental, or community impacts?

89. To help orient the discussions on environmental issues and concerns of subprojects a list of environmental components (Table 5) was introduced to the stakeholders ahead of the question and answer period. The stakeholders were encouraged to add their own components of environment to the discussions.

Table 6. Example Environmental Components Used to Guide Stakeholder Discussions.

<ul style="list-style-type: none"> • drinking water quality and availability • surface water quality and quantity • groundwater quality and quantity • air quality • climate • land and soil quality • coastal zone, ocean, rivers, reservoirs, • mangroves, trees, other vegetation, • coastal and terrestrial resources e.g., seagrass beds, mangroves, forests, salt beds 	<ul style="list-style-type: none"> • terrestrial and aquatic animals, e.g., fish, birds, small mammals • ecological protected areas (e.g., national parks, wildlife sanctuaries), • land and coastal zone uses (e.g., agriculture, fisheries, forestry, navigation, aquaculture, commercial, other), • public safety • public movement and access • physical cultural values (e.g., pagodas, cemeteries, monuments)
---	---

C. Summary of Public Consultation

The list of participants and recorded minutes and photographs of the public consultation meetings held in Kampot and Sihanoukville are found in Appendix B. provide below is a summary of the meetings.

1. Kampot

90. The environmental consultative meetings were conducted in Kampot City Hall on Feb 20, 2015. The meeting was separated between the provincial department levels, and community levels.

91. The provincial department level the meeting was conducted in the provincial hall office and chaired by the Vice Governor. Five provincial departments invited to participate defined by Environment, Tourism, Land Management, Public Works, and the Municipality of Kampot. The community level meeting was conducted in a different room. The participants of the community-level meeting represented all areas of the different subproject components. The forty (40) participants including individual villagers, representative of villages, and community level representatives for the entire subproject service area

2. Sihanoukville

92. The consultative meetings for environment were conducted in Sihanoukville town hall on February 17, 2015. Similar to the meetings in Kampot participants were invited from different provincial departments (Environment, Commerce, Womens Affairs, Tourism, Land Management, Public Works & Transport, and the Municipality of Sihanoukville), households/villages affected by the subproject components. The fifty (50) non-government participants consisted of individual villagers, and village representatives of the areas affected by the different subproject components.

93. The stakeholder consultations in both subproject towns showed overall positive support for the subprojects in Kampot and Sihanoukville. Table 6 summarizes the comments and concerns of the stakeholders in Sihanoukville and Kampot. The table also include input from the provincial DOEs obtained by the International Environment Specialist.

94. Also summarized in Tables 6 is how the EMPs for Kampot and Sihanoukville will respond to the environmental issues and concerns that were raised by stakeholders. The follow-up stakeholder consultations that may be required during the detailed design phase will begin with a review of the issues and mitigations initially identified by the stakeholders.

Table 7. Summary of Stakeholder Views in Kampot and Sihanoukville

Benefits of subprojects expressed by stakeholders	<ul style="list-style-type: none"> • Improved living standard of people in Kampot and Sihanoukville due to upgraded and construct new waste water treatment system; • Improve drainage system in the town with upgraded capacity; • Reduced flooding in rainy season due to improved drainage systems; • Rivers will be less polluted due to new waste water treatment plants; • Improved environments from new sanitation landfill in Kampot and improved existing landfill in Sihanoukville; • Kampot and Sihanoukville will be cleaner due to the new infrastructure of subprojects; • The provincial development plans of Kampot and Sihanoukville will be supported by subprojects; • Increased GDP in Kampot and Sihanoukville due to subprojects; • Reduce the disease from infection from drainage and sewage when systems are separated; • City is clean with good infrastructure;
	Subprojects Safeguard Response
Construction phase issues	<ul style="list-style-type: none"> • Noise from construction activities; • Air pollution from dust during constructing; • Waste from the construction material; Remain some soils after construction in front of house; • Dust and noise from the construction activities; • Disturbance to the people living next to project site during the construction; <ul style="list-style-type: none"> • For the construction phase of both subprojects in Kampot and Sihanoukville the EMPs specify mitigation sub-plans for constructions disturbances such as noise, dust, solid and liquid waste management, traffic congestion, public & worker safety, blocked access, and management of waste from worker camps. • The EMPs also prescribe

	<ul style="list-style-type: none"> • Traffic congestion may disturb to tourist and people living in Kampot and Sihanoukville city; • Traffic Accident during construction; • Block entrance road to home of people living along the project construction; • Wastewater from camp of workers; • Construction Workers may infect HIV/AIDS to local people; • Drug Traffic with workers; • Affect to income of people have shop in front of house when project construct the drainage and sewage system; • Affect to people income due to loss structure without compensate; • Affect to structures and tree along the road and proposed area of project. 	<p>measures to prevent or reduce social issues arising between the community and worker force such as HIV/Aids</p> <ul style="list-style-type: none"> • The separate social impact and land acquisition assessments prescribe compensation measure for lost income or property due to subprojects • Tree loss mitigation, and site restoration plans are included in the two EMPs for the subprojects in Kampot and Sihanoukville. • All potential loss or damage to structures and cultural property will be avoided as per specifications of EMP.
Operational phase issues	<ul style="list-style-type: none"> • It may pollute the water in river due to wastewater treatment plant does not have the good capacity to treat. • It may affect to people living along the road to landfill due to waste collection truck. • It may obstruct/destroy the sewage system/pipe and drainage system during operating due to there is not good management and cooperation. • It may affect to waste collectors in landfill due to trucks drive so fast. • if landfill managed by company, they will not apply the technical management. 	<ul style="list-style-type: none"> • Incorporated into the operational phase of the new WWTP in Kampot is regular monitoring of treated effluent quality to ensure effluent meets original design criteria for environmental protection • Included with the new and improved landfills in both towns is a re-designed operations and schedule of garbage trucks traveling to/from the landfills to increase safety and reduce costs.. This will include speed limits along access roads in and town. • The new drainage system that is installed will include new stormwater drain as and new WW drains so there is no risk of damaging existing drains during operation • The private companies that may operate the new/improved landfills will have to abide by the new rules of operations in order to obtain and then retain their government issued licenses to operate the

		landfills
Suggested impact mitigation measures	<ul style="list-style-type: none"> • Construction on roads for drainage and sewage system will be finished by block before starting to another place. • Traffic on the road should have facilitator to resolve during construction. • Sub-constructor has to spray water on road that they used during construction. • Good machineries should be used during construction to avoid air pollution. • Waste water and solid waste management system should be done in order to minimize the environmental impacts; • Keep the existing vegetation along the canal/river bank as possible or plant more if not exist; • Standard construction management on both safety and environment should be applied; • Human resources development on the operation and management of waste water treatment plant and landfill should be applied. • Compensate affected people if there are lost assets. • For sewage and drainage system, it should have the responsible team to resolve all matters during operation; if the project doesn't establish this team, we will have the problem again. This team has to control and prepare the penalty for villager or who destroy the system. • All affection has to give the compensation; • Subcontractor has to spray water on used road regularly to avoid dust; • Solid waste generated from project has to collect to dispose every day; • In the operation phase, landfill has to management properly as 	<ul style="list-style-type: none"> • The drainage upgrades will be done in discrete sections with the new drains of a section being completed and operational before the next section is started. • Throughout the construction phase and into the operational phase construction traffic will be managed to minimize congestions, and prevent accidents with the public. • As part of the mitigation sub-plans for dust, water or other wetting agents will be used on all construction roads to prevent dust • Similarly, contractors will have to keep all construction vehicles in good working order. • All construction wastewater will isolated and disposed according to DOE regulations. • The site restoration sub-plan of EMP includes riverbank vegetation. • Existing MoL and ILO regulations for worker and public safety will be applied to the subprojects during construction and operational phases. • The subprojects incorporate a large capacity development and training program for all agencies responsible for the operation and maintenance of the new infrastructure in Kampot and Sihanoukville. • Asset loss compensation is part of the preconstruction phase of the subprojects as indicated above. • As part of capacity development and training, the roles and responsibilities of the operators of the new Kampot WWTP and drainage systems, and appropriate penalties for public violators will be clarified in order to ensure the sustainability of the new systems. • Solid waste will be collected daily according to the needs of each

	<p>technical, thus monitoring from provincial level has to be done to avoid company does freely. During transport, waste must not be allowed to fall on to roads.</p> <ul style="list-style-type: none"> • All waste collection trucks must be cleaned regularly. 	<p>sector in the towns.</p> <ul style="list-style-type: none"> • Strict operating guidelines and rules for the new and upgraded landfill site will be identified and enforced to ensure the sustainability of effective solid waste management including operation of covered garbage trucks.
--	--	--

VI. POTENTIAL ENVIRONMENTAL IMPACTS AND MITIGATIONS

95. The assessment of potential impacts of the subprojects in Kampot and Sihanoukville towns is structured by the three development phases define by: a) *pre-construction*; b) *construction*; and c) *post-construction operational* in order to distinguish the important impact periods of subproject implementation, and to prevent redundancy in the assessment and reporting. This assessment structure is carried forward and is used to structure the environmental management plans (EMP) prepared for the subprojects.

96. To further prevent redundancy in the assessment potential impacts that are common to all subproject components are identified and discussed together. This enables clearer assessment and discussion of subproject component – specific potential impacts.

97. The area of influence combines direct and indirect effects of the subprojects. The area of influence is delimited by the area immediately affected by the infrastructure developments, and the “downstream” effects defined by for example receiving water quality, socioeconomic and cultural effects of centre-town enhancements and improved garbage management, expanded access to previously seasonally flooded areas, and reduced incidence of waterborne disease.

A. Subproject Benefits

98. Summarized below are the benefits of the subprojects mirrored by the output from the public consultations as well as from the targeted benefits of the entire PPTA.

1. Kampot

99. The addition of the first WWTP and collection system will greatly improve the urban environments for residents and visitors to Kampot. The incidence of water borne infection and disease should decrease as a result the collection and treatment of domestic waste. The quality of the Teuk Chhou river through the centre of town should improve from the removal of raw water discharges.

100. The new more modern landfill will improve the environment in the vicinity of both the old and new landfill sites. The closure of the existing, poorly operated landfill will put an end to large solid waste pollution, and a major aesthetic problem in the area. The new land fill will provide waste pickers with a more organized, clean, and safe operation with which to work with. The lined new landfill with leachate collection will prevent contamination of local groundwater.

101. The improved drainage network in town will greatly reduce the seasonal major flooding events that occur during heavy rainfall events. The absence of untreated sewage and flooding in the streets will enhance the natural beauty of the town, and enrich the tourist experience of Kampot. All of these infrastructure investments will lead to socioeconomic development of the town and immediate area.

2. Sihanoukville

102. The improvements to the solid waste management system in Sihanoukville including renovation of the landfill site, more efficient garbage transport, and better working conditions for waste pickers will improve environmental conditions of affected areas, and the life and livelihoods of solid waste management workers.

103. Similar to Kampot improved drainage in Sihanoukville will reduce chronic seasonal flooding thereby improving the urban environment, lives of residents, and the experience of tourists to the area.

B. Subproject Impacts and Mitigations

1. Pre-construction Phase

104. Potential negative impacts associated with the pre-construction phase of the subprojects concern land acquisition and resettlement. At the feasibility design stage the requirements for local resettlement and compensation are expected to vary amongst the subprojects in the two corridor towns. The details of the impacts and required management actions are addressed in the Resettlement Plans (RP) and inventory of Losses (IoL) (or Due Diligence Report in the case of Sihanoukville where there is no land acquisition and resettlement impacts) that have been prepared for both subprojects under separate cover. Involuntary resettlement and required compensation for land or asset loss identified at the feasibility design stage is summarized below:

- In Kampot 13 households (HH) will be required to give up some land for the new WWTP. No resettlement will be required from subproject.
- No land acquisition or resettlement will be required for the subproject components in Sihanoukville.

a. Groundwater study for landfill components

105. The depth and quality of the groundwater, and soil type at the existing and new landfill sites in Kampot, and at the existing landfill site in Sihanoukville are not well understood. The soil type and porosity, and the depth of the water table will be required for the design of the new landfill at Kampot and should be available for the renovation of the existing landfill at Sihanoukville. A local groundwater and soils investigation will be needed for both subproject components during the pre-construction-detailed design phase. A draft ToR for a groundwater study at the landfill sites in Kampot and Sihanoukville is provided in Appendix C.

b. Updating EMPs

106. The EMPs for the Kampot and Sihanoukville subprojects will need to be updated during the pre-construction detailed design stage to ensure the EMPs meet the final detailed designs of the subprojects. This will involve finalization of the mitigation sub-plans to manage potential impact areas such as erosion, sedimentation of surface waters, noise, dust and air quality, spoil disposal, traffic, UXO clearance, and worker and public safety at the project sites. The impact mitigations of the pre-construction phase are detailed in the EMPs for the subprojects which are prepared under separate cover.

107. Key impact mitigation measures of the pre-construction phase are:

- 1) Initiation of the project's resettlement and/or compensation plan;
- 2) Groundwater and soils investigation at landfill sites and at new Kampot WWTP site;
- 3) Completion of detailed designs of the subprojects; and
- 4) Updating and initiation of the EMPs.

108. Updating the EMPs also involves updating the environmental baseline descriptions of affected areas where needed to better understand potential impacts of subprojects and to maximize effectiveness of required mitigations. In particular water quality of Teuk Chhou river and beach area of drainages should be sampled to update published SOER (2006) data cited in IEE. The groundwater and soils investigation (Appendix C) is an important addition to the environmental baseline.

2. Construction Phase

a. Common potential impacts of subproject components

109. The potential environmental impacts of the subprojects in Kampot and Sihanoukville are primarily construction phase-disturbances of the individual subproject components. Common impacts of the civil works will consist of for example, reduced and/or blocked public access to areas, disrupted business and recreation, noise, dust caused by increased truck traffic and heavy equipment use, soil and surface water pollution caused by equipment operation and maintenance, public and worker accidents, increased traffic congestion & traffic accidents, land erosion and surface water sedimentation such as Teuk Chhou river, localized drainage and flooding problems, solid waste and domestic pollution from worker camps, and communicable disease and community problems caused by migrant workers. These short-term impacts and disturbances will occur at different levels of magnitude depending on the civil works activity and the subproject site.

i. Mitigation measures

110. Management measures to mitigate common potential impacts associated with the construction phase of all subproject components are presented below. The mitigation measures are detailed further in the subproject EMPs.

1. Care must be taken to ensure that sites for earthworks (e.g., excavations, trenches) in the rural and urban sites in Kampot or Sihanoukville that are suspected to have unexploded ordnance (UXO) should be surveyed by the Government prior to construction. If such ordnance is detected clearing work will need to be commissioned prior to undertaking civil works.

2. Open excavations should be fenced, and trenches covered where public walkways or vehicles must cross.
3. A cultural chance find management plan must be in place for cultural artifacts and property.
4. Regular use of wetting agents should be employed at construction sites to minimize dust.
5. All construction vehicles and equipment should be maintained in proper working order, and not operated at night if possible to minimize noise.
6. Speed limits should be posted and adhered to by construction vehicles, and the public.
7. Where possible construction vehicles should use different roads or dedicated lanes of roads shared by the public.
8. Trees and other vegetation at all construction sites and along road corridors such as access road to new landfill in Kampot should be protected. Tree removal must be minimized.
9. Present and past land use should be reviewed to assess whether excavated soils are contaminated. Contaminated spoil should be disposed at the existing landfills for Kampot and Sihanoukville, or locations approved by the DOEs.
10. Berms and/or silt curtains should be constructed around all excavation/trench sites and along all surface waters such as the Teuk Chhou river to prevent soil erosion and surface water sedimentation.
11. Local workers should be used as much as possible to prevent or minimize influx of migrant workers, and incidence of social disease and community unrest.
12. Worker camps must have adequate domestic waste collection facilities and sufficient pit latrines that are located away from public areas and surface waters.
13. Dedicated fuel storage areas must be established away from public areas and marked clearly.
14. To minimize the impact of construction on the public and workers the recent Cambodia Occupational, Health, and Safety (OHS) Programme guidelines developed for Cambodia by the International Labour Organization (ILO) should be followed. The IFC World Bank Environment, Health, and Safety Guidelines (2007) cited above should be followed to supplement the OHS if necessary.
15. Aggregates (e.g., sand, gravel, rock) that are transported by truck must be covered.
16. Prolonged use of temporary storage piles should be avoided, or covered, or wetted regularly to prevent dust and erosion.
17. Sand extraction from rivers should be avoided, and only occur from licensed areas.
18. Storage of bulk fuel should be on covered concrete pads away from the public and worker camp. Fuel storage areas and tanks must be clearly marked, protected and lighted. Contractors should be required to have an emergency plan to handle fuel and oil spillage.

b. Kampot subproject

Solid waste management

111. The draft closure plan for the existing landfill (Appendix D) needs to ensure the safety of the public, prevention of environmental contamination, and the preservation of waste picker livelihoods. The closed landfill should be fenced to prevent access with clearly posted signage for the public indicating danger and no trespassing. The plan for waste pickers of the closed landfill is addressed by the separate social assessment of the PPTA.

112. The waste field of existing landfill (Figure 18) should be consolidated into appropriately sized areas [with a bulldozer], and covered, or conversely, excavated in whole or part and disposed of in a new unused cell of the new landfill. Consolidated waste left at existing landfill must be covered with a sufficient layer of natural material with or without methane flares to ensure either methane is contained or is flared off the heap naturally.

113. As part of the groundwater study for the new landfill bore holes should be drilled downslope below the closed landfill to determine extent of leachate contamination of groundwater, and to track groundwater quality following landfill closure.

114. The depth of water table, and quality of groundwater below and downslope of the new landfill site (Figure 18) needs to be conducted along with a soil permeability analysis to be able to complete the design of landfill cells, liners, and required leachate management system to prevent contamination of local groundwater.

115. The public must be kept out of the existing and new landfill sites during closure and construction periods with well signed fencing. Construction vehicle traffic along the new access road to the new landfill needs to be regulated speed limits, and wetting agents applied to control dust. All trees removed for new road and landfill must be replaced with 3 three trees for each tree removed.

Wastewater collection and treatment

116. The low lying area of the WWTP site in Kampot (Figure 17) suggests the water table is very shallow if not at the surface. The anaerobic lagoons with liners need to be designed at a depth that poses no risk of groundwater contamination. Temporary earth berms or plastic sheet fencing must be placed around the WWTP site to prevent erosion and sedimentation of the irrigation canal to the south and Teuk Chhou river to the west.

117. Infilling of the entire WWTP site is required to ensure that the WWTP facility is constructed at a grade that makes the facility insensitive to current and future seasonal flooding events. The isolation of all WWTP buildings and treatment facilities from the adjacent environment is necessary to protect the integrity of the WWTP operations, and to protect the adjacent environment from WWTP operations.

Urban drainage and WW network

118. The improvements to the drainage network and the installation of the new WW collection network and pipeline for the WWTP will cause major disturbances to the streetscapes in Kampot from the trench construction method that will be used. As requested during the public consultations, effort must be expended to start and finish improvements to drains a section at a time so that major disruptions to normal street activities will be as short as possible. Quiet civil works activities should be conducted at night if possible.

c. Sihanoukville subproject

Solid waste management

119. The renovation of the existing landfill (Figure 20) will cause short-term disturbances to the operation of the landfill. However, the performance of the renovated landfill including enhanced waste picker conditions and livelihoods far outweigh the disturbances. Similarly, the

improvements to other elements of the solid waste management system (e.g., more efficient collection and transport of garbage, improved access road) strongly offset any disturbances caused by the implementation of the improvements. The collection and handling of solid waste from source to landfill site will become more cost-efficient with reduced pollution.

120. In addition to better structuring and managing the existing dumpsite, an important environmental safeguard requirement is to better understand the fate of the current leachate stream from the landfill site. Similar to the landfills in Kampot groundwater bore holes should be installed at, and downslope of the landfill to determine if a leachate plume exists, whether local groundwater quality is affected. This information will enable a more effective renovation of the landfill site. The first step is to assess whether the well head that currently exists at the Sihanoukville dumpsite at the top of the dump area (Figure 20) yields groundwater for analysis.

Urban drainage

121. The same construction issues of the drainage improvements in Kampot apply to Sihanoukville. The major disturbances caused by the trench installation method need to be managed to be minimal as much as possible.

d. All subproject components

Protected Areas, Rare and Endangered Species, and Cultural Property and Values

122. There are no known rare or endangered terrestrial wildlife species or critical habitat in the immediate vicinity of the subprojects in Kampot and Sihanoukville. And, as indicated in Figure 13, the subprojects are not near the Bokor and Ream National Parks. There are no physical cultural resources that are at risk of being damaged by the subprojects at the feasibility design stage. Thus, the construction phase activities that are implemented along with specified mitigation measures should not negatively affect sensitive ecosystem and cultural resources and values.

123. Because the final locations of facilities and components of the subprojects will only be determined at the detailed design phase, the potential exists for valued ecological and cultural resources to be negatively affected should subproject locations be altered significantly. Thus, as part of the detailed design stage when subproject siting and designs are finalized, and as part of updating the EMPs to meet the detailed designs, a review of the proximity and sensitivity of all valued eco-cultural resources of the subproject areas in relation to finalized infrastructure developments should be undertaken. Moreover, final siting and designs of all subprojects need to be reviewed to ensure that the targeted original subproject selection criteria are met.

3. Operation Phase

a. Kampot and Sihanoukville subprojects

Solid waste management

124. Posted speed limits along the access roads to the new and renovated landfill sites must be enforced to prevent accidents, and sufficient annual O&M budgets should be provided to maintain all garbage trucks and all other vehicles in good working order to reduce the air pollution. Wetting agents should be periodically applied to access roads and both landfill areas to control dust, and wind-blown debris.

125. Groundwater quality from the monitoring bore holes that are installed at the landfill sites should be monitored regularly to ensure local groundwater is not contaminated by the landfill cells or leachate streams of the landfills. The waste sorting facilities, and working conditions of the waste pickers need to be reviewed regularly to ensure that the original equipment, and the working and if appropriate living conditions of the pickers remain as originally designed or renovated.

Wastewater collection and treatment

126. The quality of treated effluents of new Kampot WWTP must be monitored to ensure they meet design criteria, and sludge from the WWTP must be disposed in a location acceptable by DOE which will be finalized during detailed design phase of the subproject.

127. Other issues with the creating new Kampot WWTP are aesthetics and public safety. The new and improved WWTP must not become negative externalities in the urban and rural landscape. Potential impacts are as follows:

1. Production of odor, noise, and altered visual aesthetics of the WWTP facilities;
2. Contamination of land or surface water from spills, or uncontrolled discharge of untreated and treated wastewater, arising from pipeline or equipment failure;
3. Increased incidence of vector carried disease arising from the treatment ponds; and
4. Risk of public injury from exposure to the treatment pond operations.

The detailed design phase of the Kampot WWTP will address these issues including siting and O&M. The composite impact mitigation for the new WWTP and pipeline consists of:

- a) Sustained, safe collection and transport wastewater to the WWTP;
- b) Consistent treatment of wastewater to effluent quality design specifications;
- c) Ability of Teuk Chhou river to assimilate the treated effluent year-round;
- d) Safe sludge disposal; and
- e) Ability of wastewater system not to impinge on the aesthetics of the area.

128. Additional mitigations for the potential impacts of the operation of Kampot WWTP and pipeline are provided below. All mitigation measures are detailed in the EMP.

- a) A maintained fenced, treed perimeter berm built around entire WWTP property to isolate facility from the area, reduce noise and odor, and prevent negative aesthetics;
- b) Enforced well marked speed limits will be posted on roads used by staff working at the WWTPs, and vehicles kept in good working order;
- c) Designs ensure treatment lagoons do not contaminate groundwater and land, monitored by regular groundwater testing;
- d) A regular effluent and sludge quality testing protocol;
- e) All equipment and processes are kept maintained in good working order with back-up equipment and processes in place in critical areas;
- f) Engineering and management systems are in place to prevent and address emergency spill and discharge situations; and
- g) All staff are properly trained with regular refresher courses;

Urban drainage

129. Sufficient annual O&M budget must be provided to ensure all upgraded drains are kept clear, and in good working condition.

C. Induced and Cumulative Impacts

130. A potential induced spatial and temporal cumulative impact of the targeted increase in socioeconomic development of the subprojects in Kampot and Sihanoukville is an increase in consumption of natural resources, and production of pollution. Sihanoukville may be more sensitive than Kampot due to the comparatively large tourist industry and density that current exists in Sihanoukville that is, and will continue to be focused on the relatively small beach areas of the town.

D. Climate Change

1. Projections

131. Recent reports and summaries, e.g.,^{29, 30, 31} of climate change scenarios for Cambodia based on the most recent climate change projections of the different Global Circulation Models (GCM) and Regional Climate Models (RCM) indicate that by 2060 average annual air temperature in the country may increase between 0.7 - 2.7C°, and total rainfall may increase between -11 and +31% during the rainy season but decrease between -11 and + 35% during dry season. By 2050 mean sea level is project to increase 0.5 m.

2. Climate Risk and Vulnerability

132. The vulnerability of the subprojects to climate change was assessed using a climate risk flowchart of increasing sensitivity analysis that was prepared for ADB infrastructure investments³². The initial rapid environmental assessment checklist (REA) of the subprojects (Appendix A) indicated that the sensitivity to climate change is variable between the subprojects. However, the climate risk screened at *Medium* (Appendix A) for the new WWTP in Kampot that subproject component is considered most sensitive to climate change due to the proximity of the facility at the coast, and at elevations close to sea level.

133. While all both subproject areas will experience increased rainy season rainfall and flooding, the Kampot WWTP will also be exposed to sea level rise, and likely most significantly increased typhoon storm surge up the tidal Teuk Chhou river in Kampot.

134. Following initial REA screening checklist the next more detailed screening of the climate risk flowchart was application of the factors of the AWARE climate sensitivity software. Once again the single climate-related factor on which the coastal WWTP in Kampot was judged to be sea level rise and potential typhoon storm surge.

135. The next step in the climate risk flowchart is application of the more in depth CVRA to obtain an understanding of the potential socioeconomic, stakeholder, and financial implications

²⁹ UNEP, 2010. Assessment of Capacity Gaps and Needs of Southeast Asian Countries Addressing Impacts, Vulnerabilities, and Adaption to Climate Variability and Climate Change, 215 pgs + references

³⁰ World Bank, GFDDR, 2011. Vulnerability, Risk Reduction, and Adaptation to Climate Change: Cambodia, 15 pgs.

³¹ PenhPal, 2013. Climate Change Impact in Cambodia: Sea Level

³² ADB (2014) Climate Proofing ADB Investment in the Transport Sector: Initial Experience, 88 pgs + Appendices

the risk of the new coastal WWTP. The CVRA represents a stand-alone detailed study that requires biophysical, financial, and stakeholder assessments in addition to the IEE.

3. Mitigation and Adaptation

136. The measures to protect the new WWTP in Kampot from climate change-induced increased flood events from by sea level rise and storm surge and/or overland flooding are in the design of the facility. As indicated by REA (Appendix A), the facility grading, use of berms and bunds, and placement of emergency pumping equipment at each site will result in the WWTP being resilient to climate change-induced increases in overland and ocean flooding. The alignments and foundations for the raw WW and treated effluent pipelines and outfalls of WWTP must be secure and erosion proof. The costs of the design of the WWTP must reflect the technical requirements to make both facilities resilient to climate change. As part of the capacity development and training program for the new WWTP training and skill development on must include managing wastewater collection and treatment during extreme flood events.

4. Contribution to Global Climate Change

a. Greenhouse gas emissions

i. Overview

137. The single potential major sources of GHGs of the subprojects in Kampot and Sihanoukville are the wastewater treatment (WWT) and solid waste management (SWM) components. The production and emission of GHGs - the most important of which is methane (CH₄) – by wastewater treatment processes and solid waste landfilling depends on the extent of anaerobic digestion processes and the capture of released methane^{33, 34}. Methane is the key GHG because it is approximately 40-50 times stronger a greenhouse gas than carbon dioxide (CO₂). A bi-product of anaerobic digestion of wastewater or decomposition of organic matter (garbage) in landfills is methane which is emitted to the atmosphere unless captured and flared or otherwise neutralized.

ii. Feasibility design

WWT

138. Aerobic waste water treatment processes (e.g., the oxygen ditch-type WWT of subprojects in Viet Nam) produce little no methane and thus are more GHG friendly. However, the WWT process planned for the WWTP Kampot will use a combination of anaerobic and aerobic treatment lagoons, and therefore, will produce methane. The extent of methane production will depend on the extent of use of the anaerobic lagoons. At the feasibility design stage a plan to capture the methane produced did not exist so all methane produced will be released to the atmosphere.

³³ Bogner et al. 2007. Waste Management, In Climate Change 2007: Mitigation. Contribution of Working Group III to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA

³⁴ Doorn and Irving 2006. IPCC Guidelines for Greenhouse Gas Inventories, Wastewater Treatment & Discharge

139. The current practice in Kampot of discharging untreated wastewater into ditches and canals results in aerobic decomposition of the wastewater, thus at the feasibility stage the net effect of the WWT component in Kampot will be the production and release of methane. However, the detailed designs describing actual flow-through volumes of actual types of wastewater, and operational designs of the treatment lagoons are required before any attempt to quantify methane emissions can occur.

SWM

140. Similar to anaerobic digestion of wastewater, the decomposition of organic solid waste in managed landfills produces methane. The SWM subproject component in Kampot consists of closing an unmanaged dumpsite and replacing it with a new more modern managed landfill that is lined, has a network of covered cells, and a leachate collection system. The new landfill will produce more methane than the unmanaged dumpsite because by design the new solid waste cells will be more anaerobic³⁵ than the scattered piles of solid waste that comprise the current dumpsite.

141. At the feasibility design stage there is no plan to capture and flare, or otherwise neutralize the methane produced from the new managed landfill. Similarly, at feasibility design there is no plan to capture and flare/neutralize any residual methane that may be produced from the closed dumpsite.

142. The renovation of the existing unmanaged dumpsite in Sihanoukville to a more modern managed landfill will result in the same net production and release of methane. The feasibility design of the renovated landfill does not include active capture and flaring/neutralizing of methane.

143. Factors that will offset methane production from the anaerobic landfill cells in both towns will be increases in recycling, and use of new, larger garbage trucks. The SWM components in both towns include new trucks that will carry larger loads and produce lower GHGs per tonne of garbage transported. However, the SWM components do not include provision of modern Material Recycling Facilities (MRF) so any increase in recycling will be passive.

144. Consideration should be given at detailed engineering design stage of including methane flaring at the new and renovated landfills, and at the new WWTP in Kampot as well as developing more modern on-site MRFs at the landfills to actively promoting recycling. These technical options will act to offset the production of GHGs.

iii. Retroactive estimation of GHGs

145. A defensible, retroactive quantitative assessment of the effect of the SWM components on GHG production is strongly limited by the uncertainties and lack of information on key parameters such as biophysical features of the dumpsite areas, inventory of types and volumes of solid waste, unknown future changes to recycling, and final WWT process in Kampot. The GHG assessment parameters need to be explicit in the design of the PPTA otherwise only qualitative estimations of the impact of the subprojects on GHGs are defensible.

³⁵ Footnote 24

IGES Simulation Model

146. An example tool for estimating GHG production and emissions from landfills is the simulation model developed by the Institute for Global Environmental Studies (IGES). The model integrates the range of factors influencing GHG production and emissions of SWM activities from the literature into a commercial spreadsheet to allow simulation of the effects of different types of SWM techniques and activities for different combinations of solid wastes on GHG emissions including recycling and garbage truck transport. However, for credible estimations the model requires detailed information on biophysical conditions, accurate solid waste types and volumes, and transportation which were beyond the scope of the PPTA design.

147. Assuming that all activities of SWM at the dumpsite sites remain the same and only an increase in the anaerobic decomposition of solid waste occurred with the installation of the modern waste cells, the SWM IGES model would simulate a general marginal increase in GHG production from the renovated landfills. However, again the simulation is decidedly crude because of the absence of detailed input data for the simulation.

148. Consideration of climate change includes measures to reduce the carbon footprints of the subprojects. Effort needs to be taken to reduce carbon footprints by for example ensuring that posted speed limits along the new landfill access road are enforced, and all new garbage trucks are maintained in good working order. All lighting installed at the all new subproject facilities in both towns will use light bulbs that are energy efficient.

VII. ANALYSIS OF ALTERNATIVES

A. Kampot:

1. Wastewater treatment and collection

149. The first site for the WWTP was closer to the town centre, and too small for the area required for the planned anaerobic treatment lagoons. Moreover, the proximity to the town centre would have increased the risk of the facility becoming a major aesthetic environmental problem due to odour and noise. Management of that risk would have required increased expense with the design of the perimeter of the facility in order to buffer the town and residents from those negative externalities.

150. The second final site is farther from town in a much less dense area. However, the site is lower in elevation and will require infilling to bring the site up to a grade that will make the entire facility resilient to flooding. Both sites would discharge treated effluent at about the same location in the Teuk Chhou river.

2. Solid waste management

151. An alternate site for the new land fill site was not investigated.

B. Sihanoukville

1. Solid waste management

152. The alternative to renovating the existing landfill and improving the solid waste management system of Sihanoukville was to close the existing dumpsite and open a new more modern landfill just north of the existing site in a heavily forested area. That alternative was abandoned because the new landfill site would require clear-cutting of dense forest equal to entire footprint of the area for the new landfill. The loss of forest could not be justified given the vast areas of cleared land that exists between the existing dump site and Sihanoukville. Further, the proposed new landfill site was located farther from town than the existing dumpsite which is more 25km from town, and which retroactively cannot be justified due to the current high costs of garbage transport.

VIII. INFORMATION DISCLOSURE AND GRIEVANCE REDRESS MECHANISM

153. The subproject components were introduced to the public and stakeholders during consultation meetings which included verbal and visual presentations of all subproject components. Pursuant to the ADB Public Communication Policy (2012), the IEE must be easily available to the stakeholders contacted during project preparation, in written and verbal forms, and in local language. At a minimum the Executive Summary of the IEE should be translated to Khmer and distributed to all APs. The IEE should be available on the MOE/DOE and MPWT/DPWT web sites, at their respective offices, district offices, and subproject sites. Similarly, all project reporting with specific reference to stakeholder consultation minutes, environmental monitoring, and reports on EMP implementation released by the EA/PSC/IU should be available at the same offices and web sites. The IEE will also be available on the ADB web site. And after implementation of the subprojects begins, all environmental and EMP reporting submitted by the EA/IU will also be available on the project and ADB web site.

154. A well-defined grievance redress and resolution mechanism will be established to address all affected stakeholders lodge grievances and complaints regarding environment, land acquisition, and compensation and resettlement, in a timely and satisfactory manner. All stakeholders will be made fully aware of their rights, and the detailed procedures for filing grievances and an appeal process will be published through an effective public information campaign. The grievance redress mechanism and appeal procedures will also be explained in a project information booklet (PIB) that will be distributed to all stakeholders.

155. APs are entitled to lodge complaints regarding any perceived issue with the affected environment, or aspect of the land acquisition and resettlement requirements such as entitlements, rates and payment and procedures for resettlement and income restoration programs. APs complaints can be made verbally or in written form. In the case of verbal complaints, the committee on grievance will be responsible to make a written record during the first meeting with the APs.

156. A Grievance Committee that has experience with environmental and social issues will be organized in local communes, comprising local leaders designated for such tasks. The designated commune officials shall exercise all efforts to settle issues at the commune level through appropriate community consultation. All meetings shall be recorded by the Grievance Committee and copies of meeting minutes shall be provided to affected persons. A copy of the

minutes of meetings and actions undertaken shall also be provided to the DPWT, IU, and ADB upon request.

157. The procedures for environmental and social grievance redress are set out below. The procedure described below is consistent with the legal process for resolution of disputes in Cambodia.

- i) Stage 1: Complaints from APs for the first time shall be lodged verbally or in written form with the village head or commune leader. The complaints shall be discussed with the APs and the designated Head of Grievance Committee or members of the committee. Because initial environmental issues will most likely be construction-related the Environment Officer/contractor and Safeguards Specialist/IU need to be notified immediately. It will be the responsibility of the Head of Grievance Committee to resolve the issue within 15 days from the date the complaint is received. All meetings shall be recorded and copies of the minutes of meetings will be provided to APs.
- ii) Stage 2: If no understanding or amicable solution can be reached or if no response is received from the Grievance Committee within 15 days from filing the complaint, the APs can elevate the case to the District Grievance Committee. The District Grievance Committee is expected to respond within 15 days upon receiving the APs appeal.
- iii) Stage 3: If the AP is not satisfied with the decision of the District Office, or in the absence of any response, the APs can appeal to the Provincial Grievance Committee (PGC). The PGC will review and issue a decision on the appeal within 30 days from the day the complaint is received.
- iv) Stage 4: If the AP is still not satisfied with the decision of the PGC or in the absence of any response within the stipulated time, the APs, as a last resort may submit his/her case to the provincial court. The court will address the appeal by written decision and submit copies to the respective entities which include the DPWT, DGC/PGC and the APs. If however, the AP is still not satisfied the court's decision, the case may be elevated to the provincial court. If however, the decision of the provincial court is still unsatisfactory to the APs, the APs may bring the complaints to the Higher Court.

158. The PSC will be responsible for checking the procedures and resolutions of grievances and complaints. The sustainability and monitoring coordination unit of the PSC must have expertise and experience in social and environmental issues associated with infrastructure developments. The PSC may recommend further measures to be taken to redress unresolved grievances. The environmental specialists of the PIC will provide the necessary training to improve grievance procedures and strategy for the grievance committee members when required.

159. The executing agency will shoulder all administrative and legal fees that will be incurred in the resolution of grievances and complaints if the APs win their case. Other costs incurred by legitimate complaints will also be refunded by the project if the APs win their case.

160. In cases where APs do not have the writing skills or are unable to express their grievances verbally, APs are encouraged to seek assistance from the recognized local groups, NGOs, other family members, village heads, or community chiefs to have their grievances recorded in writing and to have access other documentation, and to any survey or valuation of assets, to ensure that where disputes do occur, all the details have been recorded accurately enabling all parties to be treated fairly. Throughout the grievance redress process, the responsible committee will ensure that the concerned APs are provided with copies of complaints and decisions or resolutions reached.

161. If efforts to resolve disputes using the grievance procedures remain unresolved or are unsatisfactory, APs have the right to directly discuss their concerns or problems with ADB's Southeast Asia Department through the ADB Cambodia Resident Mission (CARM). If APs are still not satisfied with the responses of CARM and the Southeast Asia Department, they can directly contact the ADB Office of the Special Project Facilitator (OSPF).

IX. CONCLUSIONS AND RECOMMENDATION

162. The examination of the subprojects in Kampot and Sihanoukville indicates that the potential environmental impacts are largely restricted to the construction phase of the subproject components. The civil construction disturbances such dust, noise, traffic disruptions, erosion and sedimentation, and public and worker safety can be managed effectively with standard construction practices (e.g., IFC/World Bank 2007).

163. The description of the feasibility designs of the two subprojects combined with available information on the affected environment is sufficient to identify the scope of potential environmental impacts of the project. Providing that significant changes do not occur to the design of one or more of the subproject components, and that new sensitive environmental or social receptor data is not discovered, a further detailed environmental impact assessment (EIA) of the project is not required.

164. The separate EMPs developed for the subprojects provide impact mitigation plans, environmental monitoring plans, and specify the institutional responsibilities and capacity needs for the environmental management of the subprojects. The EMPs will need to be reviewed and updated at the detailed design phase to ensure that they fully address the potential impacts of the final subproject designs.

APPENDIX A: RAPID ENVIRONMENTAL ASSESSMENTS OF SUBPROJECTS

Kampot

Rapid Environmental Assessment (REA) Checklist: SEWAGE TREATMENT

Country/Project Title: Second Corridor Towns Development Project, PPTA 8425 VIE **Kampot**

Sector Division: Wastewater Collection and Treatment / Urban Development / SERD

Screening Questions	Yes	No	Remarks
B. Project Siting Is the project area in.			
▪ Densely populated?		X	
▪ Heavy with development activities?		X	
▪ Adjacent to or within environmentally sensitive areas?			
• Cultural heritage site		X	
• Protected Area		X	
• Wetland	X		Site of WWTP is a lowland area beside Teuk Chhou river. Mitigation measures including compensatory (or offset) measures will be included in the EMP and C/EMP to achieve no net loss of biodiversity will be applied.
• Mangrove		X	
• Estuarine	X		At low flow periods Teuk Chhou river adjacent to WWTP site is brackish. Teuk Chhou estuary approx.4-5 km downstream. Mitigation measures including compensatory (or offset) measures will be included in the EMP and C/EMP to achieve no net loss of biodiversity will be applied.
• Buffer zone of protected area		X	
• Special area for protecting biodiversity		X	
• Bay	X		Teuk Chhou river empties Kampot bay 5 kms downstream. Mitigation measures including compensatory (or offset) measures will be included in the EMP and C/EMP to achieve no net loss of biodiversity will be applied.

Screening Questions	Yes	No	Remarks
A. Potential Environmental Impacts Will the Project cause...			
▪ impairment of historical/cultural monuments/areas and loss/damage to these sites?		X	
▪ interference with other utilities and blocking of access to buildings; nuisance to neighboring areas due to noise, smell, and influx of insects, rodents, etc.?		X	
▪ dislocation or involuntary resettlement of people?		X	
▪ disproportionate impacts on the poor, women and children, Indigenous Peoples or other vulnerable groups?		X	
▪ impairment of downstream water quality due to inadequate sewage treatment or release of untreated sewage?	X		The quality of treated effluent must meet support water quality for sensitive aquatic habitat and marine species resources such as marine mammals seagrass and mangroves located at the mouth of Teuk Chhou river at Kampot bay
▪ overflows and flooding of neighboring properties with raw sewage?		X	
▪ environmental pollution due to inadequate sludge disposal or industrial waste discharges illegally disposed in sewers?	X		Unclear how sludge from lagoon-WWTP will be disposed. Expectedly into a MOE-approved sludge disposal area
▪ noise and vibration due to blasting and other civil works?	X		The EMP for project prescribes mitigation measures for construction noise. Blasting is not required.
▪ risks and vulnerabilities related to occupational health and safety due to physical, chemical, and biological hazards during project construction and operation?		X	
▪ discharge of hazardous materials into sewers, resulting in damage to sewer system and danger to workers?		X	
▪ inadequate buffer zone around pumping and treatment plants to alleviate noise and other possible nuisances, and protect facilities?	X		New WWTP site will include a treed buffer perimeter
▪ road blocking and temporary flooding due to land excavation during the rainy season?		X	
▪ noise and dust from construction activities?	X		As above the EMP for project prescribes mitigation sub-plans short-term noise, and dust disturbances
▪ traffic disturbances due to construction material transport and wastes?	X		The EMP for project prescribes mitigation measures for short-term construction-caused traffic problems

Screening Questions	Yes	No	Remarks
▪ temporary silt runoff due to construction?	X		The EMP for project prescribes mitigation measures to prevent or contain land erosion and sedimentation of Teuk Chhou river during construction phase
▪ hazards to public health due to overflow flooding, and groundwater pollution due to failure of sewerage system?		X	
▪ deterioration of water quality due to inadequate sludge disposal or direct discharge of untreated sewage water?		X	A MOE-approved site for sludge disposal will be selected where necessary
▪ contamination of surface and ground waters due to sludge disposal on land?		X	A MOE-approved site for sludge disposal will be selected when required
▪ health and safety hazards to workers from toxic gases and hazardous materials which may be contained in confined areas, sewage flow and exposure to pathogens in untreated sewage and un-stabilized sludge?		X	
▪ large population increase during project construction and operation that causes increased burden on social infrastructure (such as sanitation system)?		X	
▪ social conflicts between construction workers from other areas and community workers?	X		Migrant worker population is expected to be small, however, the EMP for project prescribes mitigation sub-plans for these social local issues.
▪ risks to community health and safety due to the transport, storage, and use and/or disposal of materials such as explosives, fuel and other chemicals during construction and operation?		X	
▪ community safety risks due to both accidental and natural hazards, especially where the structural elements or components of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning?		X	

A Checklist for Preliminary Climate Risk Screening

Country/Project Title: GMS Second Corridor Towns Development Project PPTA 8474 REG

Sector: Urban Development

Subsector: Wastewater Collection and Treatment

Division/Department: Urban development / SERD

Screening Questions	Score	Remarks
Location and Is siting and/or routing of the project	1	The site for WWTP is at sea level near the coast at

Screening Questions		Score	Remarks
Design of project	(or its components) likely to be affected by climate conditions including extreme weather related events such as floods, droughts, storms, landslides?		Kampot bay. The WWTP will require facility foundations, to be set at elevations resilient to increased flooding and sea level from climate change
	Would the project design (e.g. the clearance for bridges) need to consider any hydro-meteorological parameters (e.g., sea-level, peak river flow, reliable water level, peak wind speed etc)?	1	As above, incoming pipelines up pump stations will require foundation elevations resilient to climate change-induced sea level rise, and increased rainfall/flooding events.
Materials and Maintenance	Would weather, current and likely future climate conditions (e.g. prevailing humidity level, temperature contrast between hot summer days and cold winter days, exposure to wind and humidity hydro-meteorological parameters likely affect the selection of project inputs over the life of project outputs (e.g. construction material)?	0	
	Would weather, current and likely future climate conditions, and related extreme events likely affect the maintenance (scheduling and cost) of project output(s) ?	0	

Options for answers and corresponding score are provided below:

Response	Score
Not Likely	0
Likely	1
Very Likely	2

Result of Initial Screening (Low, Medium, High): Medium

Other Comments: n/a

Rapid Environmental Assessment (REA) Checklist

SOLID WASTE

Country/Project Title: Second Corridor Towns Development Project, PPTA 8425 VIE **Kampot**

Sector Division: Solid Waste Management / Urban Development / SERD

Screening Questions	Yes	No	Remarks
A. Project Siting Is the project area			
▪ Densely populated?		X	

Screening Questions	Yes	No	Remarks
▪ Heavy with development activities?		X	
▪ Adjacent to, or within any environmentally sensitive areas?			
• Cultural heritage site		X	
• Protected Area		X	
• Wetland		X	
• Mangrove		X	
• Estuarine		X	
• Buffer zone of protected area		X	
• Special area for protecting biodiversity		X	
• Bay		X	
B. Potential Environmental Impacts Will the Project cause...			
▪ impacts associated with transport of wastes to the disposal site or treatment facility		X	
▪ impairment of historical/cultural monuments/areas and loss/damage to these sites?		X	
▪ degradation of aesthetic and property value loss?		X	
▪ nuisance to neighboring areas due to foul odor and influx of insects, rodents, etc.?		X	Nearest settlement a few km away
▪ dislocation or involuntary resettlement of people?		X	
▪ disproportionate impacts on the poor, women and children, Indigenous Peoples or other vulnerable groups?		X	
▪ risks and vulnerabilities related occupational health and safety due to physical, chemical, biological, and radiological hazards during project construction and operation?		X	
▪ public health hazards from odor, smoke from fire, and diseases transmitted by flies, insects, birds and rats?		X	New landfill site between two hills away from settlements
▪ deterioration of water quality as a result of contamination of receiving waters by leachate from land disposal system?		X	No surface water in site. However, leachate ponds will be constructed
▪ contamination of ground and/or surface water by leachate from land disposal system?	X		New landfill will be lined with clay and include leachate collection and storage system which should protect groundwater quality. A groundwater quality study in area is required
▪ land use conflicts?		X	

Screening Questions	Yes	No	Remarks
<ul style="list-style-type: none"> pollution of surface and ground water from leachate coming from sanitary landfill sites or methane gas produced from decomposition of solid wastes in the absence of air, which could enter the aquifer or escape through soil fissures at places far from the landfill site? 	X		Site selection criteria included no surface water on or draining site. Upgraded landfill will be lined with clay and include leachate collection and storage system which should protect groundwater quality. Methane gas produced by landfill will dissipate uncollected.
<ul style="list-style-type: none"> inadequate buffer zone around landfill site to alleviate nuisances? 		X	
<ul style="list-style-type: none"> road blocking and/or increased traffic during construction of facilities? 		X	
<ul style="list-style-type: none"> noise and dust from construction activities? 	X		The EMP prescribes mitigation measures for controlling noise and dust during construction at site and along access road
<ul style="list-style-type: none"> temporary silt runoff due to construction? 		X	
<ul style="list-style-type: none"> hazards to public health due to inadequate management of landfill site caused by inadequate institutional and financial capabilities for the management of the landfill operation? 		X	
<ul style="list-style-type: none"> emission of potentially toxic volatile organics from land disposal site? 		X	Domestic waste is targeted waste for landfill
<ul style="list-style-type: none"> surface and ground water pollution from leachate and methane gas migration? 		X	Clay liner and leachate collection system should prevent contamination of groundwater by leachate. Methane gas will dissipate freely
<ul style="list-style-type: none"> loss of deep-rooted vegetation (e.g. trees) from landfill gas? 		X	
<ul style="list-style-type: none"> explosion of toxic response from accumulated landfill gas in buildings? 		X	
<ul style="list-style-type: none"> contamination of air quality from incineration? 		X	
<ul style="list-style-type: none"> public health hazards from odor, smoke from fire, and diseases transmitted by flies, rodents, insects and birds, etc.? 	X		Landfill located away from settlements
<ul style="list-style-type: none"> health and safety hazards to workers from toxic gases and hazardous materials in the site? 		X	
<ul style="list-style-type: none"> large population influx during project construction and operation that causes increased burden on social infrastructure and services (such as water supply and sanitation systems)? 		X	Local worker force is expected
<ul style="list-style-type: none"> social conflicts if workers from other regions or countries are hired? 		X	Local worker force is expected
<ul style="list-style-type: none"> risks to community health and safety due to the transport, storage, and use and/or disposal of materials such as explosives, fuel and other chemicals during construction and operation? 		X	

Screening Questions	Yes	No	Remarks
<ul style="list-style-type: none"> community safety risks due to both accidental and natural hazards, especially where the structural elements or components (e.g., landfill or incinerator) of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning? 		X	

A Checklist for Preliminary Climate Risk Screening

Country/Project Title: GMS Second Corridor Towns Development Project PPTA 8474 REG

Sector: Urban Development

Subsector: Solid Waste Management

Division/Department: Urban Development / SERD

Screening Questions		Score	Remarks
Location and Design of project	Is siting and/or routing of the project (or its components) likely to be affected by climate conditions including extreme weather related events such as floods, droughts, storms, landslides?	0	New landfill site is adequately sloped, and located at an elevation that is not susceptible to flooding
	Would the project design (e.g. the clearance for bridges) need to consider any hydro-meteorological parameters (e.g., sea-level, peak river flow, reliable water level, peak wind speed etc)?	0	
Materials and Maintenance	Would weather, current and likely future climate conditions (e.g. prevailing humidity level, temperature contrast between hot summer days and cold winter days, exposure to wind and humidity hydro-meteorological parameters likely affect the selection of project inputs over the life of project outputs (e.g. construction material)?	0	
	Would weather, current and likely future climate conditions, and related extreme events likely affect the maintenance (scheduling and cost) of project output(s) ?	0	
Performance of project outputs	Would weather/climate conditions, and related extreme events likely affect the performance (e.g. annual power production) of project output(s) (e.g. hydro-power generation facilities) throughout their design life time?	0	

Options for answers and corresponding score are provided below:

Response	Score
Not Likely	0
Likely	1
Very Likely	2

Result of Initial Screening (Low, Medium, High): Low

Other Comments: A groundwater study to determine water table depth and groundwater quality will need to be conducted at detailed design phase. Existing dumpsite will need to be closed with internationally acceptable methods

Rapid Environmental Assessment (REA) Checklist

URBAN DEVELOPMENT

Country/Project Title: Second Corridor Towns Development Project, PPTA 8425 VIE – Kampot

Sector Division: Drainage / Urban Development / SERD

Screening Questions	Yes	No	Remarks
A. Project Siting Is the project area			
▪ Densely populated?		X	
▪ Heavy with development activities?		X	
▪ Adjacent to or within any environmentally sensitive areas?		X	
• Cultural heritage site	X		Drainage upgrades will enhance heritage area intown
• Protected Area		X	
• Wetland		X	
• Mangrove		X	
• Estuarine		X	
• Buffer zone of protected area		X	
• Special area for protecting biodiversity		X	
• Bay		X	
B. Potential Environmental Impacts Will the Project cause...			
▪ impacts on the sustainability of associated sanitation and solid waste disposal systems and their interactions with other urban services.		X	
▪ deterioration of surrounding environmental conditions due to rapid urban population growth, commercial and industrial activity, and increased waste generation to the point that both manmade and natural systems are overloaded and the capacities to manage these systems are overwhelmed?		X	
▪ degradation of land and ecosystems (e.g. loss of wetlands and wild lands, coastal zones, watersheds and forests)?		X	

Screening Questions	Yes	No	Remarks
▪ dislocation or involuntary resettlement of people?		X	
▪ disproportionate impacts on the poor, women and children, Indigenous Peoples or other vulnerable group?		X	
▪ degradation of cultural property, and loss of cultural heritage and tourism revenues?		X	
▪ occupation of low-lying lands, floodplains and steep hillsides by squatters and low-income groups, and their exposure to increased health hazards and risks due to pollutive industries?		X	
▪ water resource problems (e.g. depletion/degradation of available water supply, deterioration for surface and ground water quality , and pollution of receiving waters?		X	
▪ air pollution due to urban emissions?		X	
▪ risks and vulnerabilities related to occupational health and safety due to physical, chemical and biological hazards during project construction and operation?		X	
▪ road blocking and temporary flooding due to land excavation during rainy season?		X	
▪ noise and dust from construction activities?	X		The EMP for subproject prescribes mitigation measures for noise and dust during construction.
▪ traffic disturbances due to construction material transport and wastes?	X		The EMP for subproject prescribes mitigation measures for increased traffic and risk of traffic accidents during construction.
▪ temporary silt runoff due to construction?		X	
▪ hazards to public health due to ambient, household and occupational pollution, thermal inversion, and smog formation?		X	
▪ water depletion and/or degradation?		X	
▪ overpaying of ground water, leading to land subsidence, lowered ground water table, and salinization?		X	
▪ contamination of surface and ground waters due to improper waste disposal?		X	
▪ pollution of receiving waters resulting in amenity losses, fisheries and marine resource depletion, and health problems?		X	
▪ large population influx during project construction and operation that causes increased burden on social infrastructure and services (such as water supply and sanitation systems)?		X	

Screening Questions	Yes	No	Remarks
▪ social conflicts if workers from other regions or countries are hired?		X	
▪ risks to community health and safety due to the transport, storage, and use and/or disposal of materials such as explosives, fuel and other chemicals during operation and construction?		X	
▪ community safety risks due to both accidental and natural hazards, especially where the structural elements or components of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning?		X	

A Checklist for Preliminary Climate Risk Screening

Country/Project Title: GMS Second Corridor Towns Development Project PPTA 8474 REG

Sector: Urban Development

Subsector: Drainage

Division/Department: Urban Development / SERD

Screening Questions		Score	Remarks
Location and Design of project	Is siting and/or routing of the project (or its components) likely to be affected by climate conditions including extreme weather related events such as floods, droughts, storms, landslides?	0	
	Would the project design (e.g. the clearance for bridges) need to consider any hydro-meteorological parameters (e.g., sea-level, peak river flow, reliable water level, peak wind speed etc)?	0	
Materials and Maintenance	Would weather, current and likely future climate conditions (e.g. prevailing humidity level, temperature contrast between hot summer days and cold winter days, exposure to wind and humidity hydro-meteorological parameters likely affect the selection of project inputs over the life of project outputs (e.g. construction material)?	0	
	Would weather, current and likely future climate conditions, and related extreme events likely affect the maintenance (scheduling and cost) of project output(s) ?	0	
Performance of project outputs	Would weather/climate conditions, and related extreme events likely affect the performance (e.g. annual power production) of project output(s) (e.g. hydro-power generation facilities) throughout their design life time?	0	

Options for answers and corresponding score are provided below:

Response	Score
Not Likely	0
Likely	1
Very Likely	2

Result of Initial Screening (Low, Medium, High): Low,

Other Comments: n/a

Sihanoukville

Rapid Environmental Assessment (REA) Checklist

SOLID WASTE

Country/Project Title: Second Corridor Towns Development Project, PPTA 8425 VIE – Sihanoukville

Sector Division: Solid Waste Management & Drainage / Urban Development /

Screening Questions	Yes	No	Remarks
A. PROJECT SITING IS THE PROJECT AREA			
▪ DENSELY POPULATED?		X	
▪ HEAVY WITH DEVELOPMENT ACTIVITIES?		X	
▪ ADJACENT TO, OR WITHIN ANY ENVIRONMENTALLY SENSITIVE AREAS?			
• CULTURAL HERITAGE SITE		X	
• PROTECTED AREA		X	
• WETLAND		X	
• MANGROVE		X	
• ESTUARINE		X	
• BUFFER ZONE OF PROTECTED AREA		X	
• SPECIAL AREA FOR PROTECTING BIODIVERSITY		X	
• BAY		X	
B. POTENTIAL ENVIRONMENTAL IMPACTS WILL THE PROJECT CAUSE...			
▪ impacts associated with transport of wastes to the disposal site or treatment facility		X	
▪ impairment of historical/cultural monuments/areas and loss/damage to these sites?		X	
▪ degradation of aesthetic and property value loss?		X	
▪ nuisance to neighboring areas due to foul odor and influx of insects, rodents, etc.?		X	Nearest village a few km away
▪ dislocation or involuntary resettlement of people?		X	

Screening Questions	Yes	No	Remarks
▪ disproportionate impacts on the poor, women and children, Indigenous Peoples or other vulnerable groups?		X	
▪ risks and vulnerabilities related occupational health and safety due to physical, chemical, biological, and radiological hazards during project construction and operation?		X	
▪ public health hazards from odor, smoke from fire, and diseases transmitted by flies, insects, birds and rats?		X	Renovated landfill site located far from Sihanoukville. Only a few households are nearby.
▪ deterioration of water quality as a result of contamination of receiving waters by leachate from land disposal system?	X		Surface waters below landfill site will be protected from contamination with renovated leachate collection and storage facility design
▪ contamination of ground and/or surface water by leachate from land disposal system?	X		Renovated landfill will be lined with clay and will include leachate collection and storage system which should protect groundwater quality. A groundwater quality study in area is required
▪ land use conflicts?		X	
▪ pollution of surface and ground water from leachate coming from sanitary landfill sites or methane gas produced from decomposition of solid wastes in the absence of air, which could enter the aquifer or escape through soil fissures at places far from the landfill site?	X		Renovated landfill will be lined with clay and include leachate collection and storage system which should protect groundwater quality, and the stream that drain the site. Methane gas produced by landfill will dissipate uncollected. However, a study of groundwater in the area will be needed at detailed design phase
▪ inadequate buffer zone around landfill site to alleviate nuisances?		X	
▪ road blocking and/or increased traffic during construction of facilities?		X	
▪ noise and dust from construction activities?	X		The EMP prescribes mitigation measures for controlling noise and dust during construction at site and along access road
▪ temporary silt runoff due to construction?		X	The EMP prescribes mitigation measures to contain soil erosion, and to prevent sedimentation of stream, and other surface waters.
▪ hazards to public health due to inadequate management of landfill site caused by inadequate institutional and financial capabilities for the management of the landfill operation?		X	

Screening Questions	Yes	No	Remarks
▪ emission of potentially toxic volatile organics from land disposal site?		X	Domestic waste is targeted waste for landfill
▪ surface and ground water pollution from leach ate and methane gas migration?		X	Renovated clay liner and leachate collection system should prevent contamination of groundwater by leachate. Methane gas will dissipate freely. A study of groundwater in the area will be needed at detailed design phase
▪ loss of deep-rooted vegetation (e.g. tress) from landfill gas?		X	
▪ explosion of toxic response from accumulated landfill gas in buildings?		X	
▪ contamination of air quality from incineration?		X	
▪ public health hazards from odor, smoke from fire, and diseases transmitted by flies, rodents, insects and birds, etc.?	X		Renovated landfill located away from major settlements
▪ health and safety hazards to workers from toxic gases and hazardous materials in the site?		X	
▪ large population influx during project construction and operation that causes increased burden on social infrastructure and services (such as water supply and sanitation systems)?		X	Local worker force is expected
▪ social conflicts if workers from other regions or countries are hired?		X	Local worker force is expected
▪ risks to community health and safety due to the transport, storage, and use and/or disposal of materials such as explosives, fuel and other chemicals during construction and operation?		X	
▪ community safety risks due to both accidental and natural hazards, especially where the structural elements or components (e.g., landfill or incinerator) of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning?		X	

A Checklist for Preliminary Climate Risk Screening

Country/Project Title: GMS Second Corridor Towns Development Project PPTA 8474 REG

Sector: Urban Development

Subsector: Solid Waste Management & Drainage

Division/Department: Urban Development / SERD

Screening Questions	Score	Remarks
Location and Design of project Is siting and/or routing of the project (or its components) likely to be affected by climate conditions including extreme weather related events such as floods, droughts, storms, landslides?	0	New landfill site is adequately sloped, and located at an

			elevation that is not susceptible to flooding
	Would the project design (e.g. the clearance for bridges) need to consider any hydro-meteorological parameters (e.g., sea-level, peak river flow, reliable water level, peak wind speed etc)?	0	
Materials and Maintenance	Would weather, current and likely future climate conditions (e.g. prevailing humidity level, temperature contrast between hot summer days and cold winter days, exposure to wind and humidity hydro-meteorological parameters likely affect the selection of project inputs over the life of project outputs (e.g. construction material)?	0	
	Would weather, current and likely future climate conditions, and related extreme events likely affect the maintenance (scheduling and cost) of project output(s) ?	0	
Performance of project outputs	Would weather/climate conditions, and related extreme events likely affect the performance (e.g. annual power production) of project output(s) (e.g. hydro-power generation facilities) throughout their design life time?	0	

Response	Score
Not Likely	0
Likely	1
Very Likely	2

Result of Initial Screening (Low, Medium, High): Low

Other Comments: A groundwater study to determine water table depth and groundwater quality will need to be conducted at detailed design phase. Existing dumpsite will need to be closed with internationally acceptable methods.

APPENDIX B: PARTICIPANTS OF PUBLIC CONSULTATIONS

Kampot

	
<p align="center">Subproject introduced by engineer</p>	<p align="center">Ideas and discussion of participants</p>

Example Environmental and Social Public Consultation Response Form

Province: Kampot	City/District: Kampot town	Commune: kampot town
Date: 20/Feb/15	Time: 2:00 – 4:30 pm	Attendance (no.): 40 (10 females)
<i>Statements and Inquiries Provided by Attendees:</i>		
No.1 Name: Mr. A Ly	Sex: Female Age: 60	Occupation: villager
Statement or Inquiry: My children usually get the skin disease whenever rain that it floods from sewage system, thus is project can improve this system I and my villagers will support 100%. But, I suggest to avoid construct in rainy season. I worry rain can disturb working.		
No.2 Name: Ms. Mi Toch	Sex: Female Age: 63	Occupation: Villagers
Statement or Inquiry: I worry leakage oil and dust from construct ion to affect children and family. So, please take care about oil and dust; please spray water on place that project construction. Also, some projects did not build the enough toilet for workers, they went to deficit in place next to local people's house; thus I hope this project will have enough toilet for them. Standard of construction has to apply in this project.		
No.3 Name: Mr. Ouch Sam Arng	Sex: Male Age: 65	Occupation: Villagers
Statement or Inquiry: I support these 4 subprojects, but I would like to suggest as:		
<ul style="list-style-type: none"> - All affection has to give the compensation; - Subcontractor has to spray water on used road regularly to avoid dust; - Solid waste generated from project has to collect to dispose every day; - In the operation phase, landfill has to management properly as technical, thus monitoring from provincial level has to be done to avoid company does freely. During transport waste, company has not to let the waste spill out on the road. 		

- All waste collection tracks have to be clean regularly.		
No.4 Name: Mr. Pock Chea	Sex: Male Age: <u>40</u>	Occupation: villager
Statement or Inquiry: For landfill location, it should be far from village and residential spots. We worry about some insects as fly and other to disturb our villagers. Fence has to be built surrounding the landfill to avoid cow and dog.		
No.4 Name: Mr. Seng Hean	Sex: Male Age: <u>63</u>	Occupation: villager
Statement or Inquiry: I worry traffic congestion during construction the drainage, sewage and landfill. Also, entrance road in front of my house may be blocked during construction, thus I suggest to work as step. It means that finish by block with 10 or 20 meters for a step by keeping small road for owner of house.		
No.4 Name: Mr. Meng Huo	Sex: Female Age: <u>35</u>	Occupation: villager
Statement or Inquiry: It is good that we have the project for conserve our old house, built in France Colony; however, project has to discuss with house owner. If they have enough money, they don't need this project, they will do it by themself.		
All work on the road should plan to finish daily to avoid disturbing us long time. I also suggest as the following:		
<ul style="list-style-type: none"> - For sewage and drainage system, it should have the responsible team to resolve all matters during operation; if the project doesn't establish this team, we will have the problem again. - This team has to control and prepare the penalty for villager or who destroy the system. - In construction phase, please select my villagers to be workers. 		

Participants List for Public Consultation in Kampot

**ADB TA: 8425 REG
SECOND GREATER MEKONG SUBREGION CORRIDOR TOWNS
DEVELOPMENT PROJECT**

1. Town Kampot
2. Component
3. Location (Commune/ District) Municipality, Ital
4. Activity Public Consultation - Community People

LIST OF ATTENDEES/ RESPONDENTS 20 / Feb / 2015

	Name	Address	Signature
1	Ms. អៀន សុខា	ភូមិស្រែចម្ការ, សង្កាត់ស្រែចម្ការ, ក្រុងកំពត	CS
2	Ms. ហ៊ុន សារី	"	CS
3	Mr. គឹម វិថី	"	CS
4	Ms. លីម ផាត	ផ្ទះ ១២៧, ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
5	Mr. គឹម វិថី	ភូមិស្រែចម្ការ, សង្កាត់ស្រែចម្ការ, ក្រុងកំពត	CS
6	Ms. គឹម វិថី	" (ស្រែចម្ការ)	CS
7	Mr. គឹម វិថី	"	CS
8	Mr. គឹម វិថី	"	CS
9	Ms. គឹម វិថី	ផ្ទះ ១២៧, ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
10	Mr. គឹម វិថី	" (ស្រែចម្ការ)	CS
11	Mr. គឹម វិថី (Mr.)	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
12	Mr. គឹម វិថី (Mr.)	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
13	Ms. គឹម វិថី (Ms.)	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
14	Ms. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត (ស្រែចម្ការ)	CS
15	Mr. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត (ស្រែចម្ការ)	CS
16	Ms. គឹម វិថី (Ms.)	ភូមិស្រែចម្ការ	CS
17	Mr. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
18	Ms. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
19	Ms. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
20	Ms. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS
21	Ms. គឹម វិថី	"	CS
22	Ms. គឹម វិថី	ភូមិស្រែចម្ការ, ក្រុងកំពត	CS

	Name	Address	Signature
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			

Sihanoukville



Introduction of subproject by engineer



Ideas and discussion raised by participants

Example Environmental and Social Public Consultation Response Form

Province: Sihanouk ville	City/District: Sihanoukville City	Commune: Sihanoukville City
Date: 17/Feb/15	Time: 2:30 – 4:30 pm	Attendance (no.): 40 (10 females)
<i>Statements and Inquiries Provided by Attendees:</i>		
No.1 Name: Mr. Loy Chey	Sex: male Age: <u>67</u>	Occupation: villager
Statement or Inquiry: my village always faced with the flood during raining, because there is no good drainage system. I suggest constructing in dry season to avoid any pollution to my living village and soil quality there.		
No.2 Name: Mr. Puon Than	Sex: Female Age: <u>56</u>	Occupation: Villagers

Statement or Inquiry: I worry about remained soil after excavated. Moreover, if the project affect to my property, project has to give the compensation. All compensation has to be done before project implemented.		
No.3 Name: Mr. Nong Sopheap	Sex: Male Age: <u>33</u>	Occupation: Villagers
Statement or Inquiry: For drainage system and sewage system construction along the road, constructor should have the symbol sign to avoid accident at night because it is along the road and some locations have no lamp at night.		
No.4 Name: Ms. Chan Vicheka	Sex: Male Age: <u>40</u>	Occupation: villager
Statement or Inquiry: When excavate along the road side, it may break to existing clean water pipe line that it will affect to our community.		
No.4 Name: Mr. Towng Putheavy	Sex: Female Age: <u>39</u>	Occupation: villager
Statement or Inquiry: All roads used by project have to pray water regularly to avoid air pollution by dust.		
No.4 Name: Ms. Suon Sina	Sex: Female Age: <u>33</u>	Occupation: villager
Statement or Inquiry: All affected property need to give the compensation as the original price.		
<ul style="list-style-type: none"> - Tree and structures along the proposed area of project need to give compensation if they will be affected by the project. - Please inform us before implementing the project, because we are easy to prepare for this affection. 		
No.4 Name: Mr. Tim Seng	Sex: Male Age: <u>78</u>	Occupation: villager
Statement or Inquiry: After landfill were improved, provincial authority has to look for suitable place for waste collector to collect waste transport from source.		
No.4 Name: Mr. Prom Buoy	Sex: Male Age: <u>57</u>	Occupation: villager
Statement or Inquiry: Landfill should have fence to avoid cow and dog to eat garbage.		
No.4 Name: Ms. Kem Srey Neng	Sex: Female Age: <u>21</u>	Occupation: represent from Golden Sea hotel
Statement or Inquiry: During construction, please take care about quality and clean. When cut the path road in front of hotel has to keep a side of entrance road for my customer. The level of waste water system has to consider about level of land condition to avoid pumping that it waste much money.		
<ul style="list-style-type: none"> - If we don't have these system our beach will be pollute very soon in near future. - However, we need project to practice the safeguard for social and environment during construction. 		
No.4 Name: Mr. Prom Buoy	Sex: Male Age: <u>57</u>	Occupation: villager
Statement or Inquiry: Landfill should have fence to avoid cow and dog to eat garbage or other waste.		

Participants List for Public Consultation in Sihanoukville

ព្រះរាជាណាចក្រកម្ពុជា
ជាតិ សាសនា ព្រះមហាក្សត្រ
២០២០ ០៩០៩

ក្រសួងមហាផ្ទៃ
សាលារដ្ឋប្រឹក្សាស៊ីហ្គេត

បណ្ដឹងគ្រប់គ្រង

កិច្ចប្រជុំពិគ្រោះយោបល់ជាមួយប្រជាពលរដ្ឋក្នុងក្រុងព្រះសីហនុ ស្តីពីផែនការសាងសង់ប្រយោជន៍នៃបរិស្ថាន និងសេដ្ឋកិច្ចសង្គម
ថ្ងៃទី ១៧ ខែ កុម្ភៈ ឆ្នាំ២០១៥ សាលាក្រុងព្រះសីហនុ

ល.រ No.	ឈ្មោះ និង គោត្តនាម Full Name	ភេទ Sex	មុខតំណែង/មន្ទីរ-អង្គភាព Position and Agencies	លេខទូរស័ព្ទ Contact Number	ហត្ថលេខា Signatures
១	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
២	លោក អ៊ិន	ប	អគ្គនាយកដ្ឋានស្រុក		
៣	លោក ព្រះសុខាភិបាល	ប	ប្រគល់ជូនប្រជាពលរដ្ឋ		
៤	លោក គន	ស	ប្រគល់ជូនប្រជាពលរដ្ឋ		
៥	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
៦	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
៧	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
៨	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
៩	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		B.S.
១០	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
១១	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក	០១៦៤៤៣៤៣៦	
១២	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
១៣	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
១៤	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
១៥	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក		
១៦	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក	០១១២១២៧៧	
១៧	លោក គុណ	ប	អគ្គនាយកដ្ឋានស្រុក	០១៦១២១១១	125

No.	ឈ្មោះ ម៉ឺន ពេញឈ្មោះ Full Name	ភេទ Sex	មុខតំណែង/មន្ទីរ-អង្គភាព Position and Agencies	លេខទូរស័ព្ទ Contact Number	ហត្ថលេខា Signatures
១៣	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	093934444	ស្រី
១៤	ស្រី ឈ	ស	ស្រីរតន	016566121	
១៥	ស្រី ឈ	ស	ស្រី 3		
១៦	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	0978202828	ស្រី
១៧	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	012434971	ស្រី
១៨	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016966440	ស្រី
១៩	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	070 045666	ស្រី
២០	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016372919	ស្រី
២១	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016531678	ស្រី
២២	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016 980025	ស្រី
២៣	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	070 29041	ស្រី
២៤	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016751957	ស្រី
២៥	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	0968033847	ស្រី
២៦	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016704467	ស្រី
២៧	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	012 851258	ស្រី
២៨	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន		
២៩	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016678770	ស្រី
៣០	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	0828321588	ស្រី
៣១	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	012 986718	ស្រី
៣២	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016 54949	ស្រី
៣៣	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	010 608270	ស្រី
៣៤	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	012 7277 0	ស្រី
៣៥	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	016 545928	ស្រី
៣៦	ស្រី ឈ	ស	គ្រូបង្រៀន ស្រីរតន	012 229 999	ស្រី

No.	នាម ម៉ឺង ពេញនាម Full Name	ភេទ Sex	មុខតំណែង/មន្ទីរ-អង្គភាព Position and Agencies	លេខទូរស័ព្ទ Contact Number	ហត្ថលេខា Signatures
៤២	ឈុំ ឈុំ		គោរព តារាង ១៧	០១៦៧១៣៦១	
៤៣	ឈុំ ឈុំ	ប	ឈុំ ឈុំ	០១៦៧៥៥៧៧	
៤៤	ឈុំ ឈុំ	ប	ឈុំ ឈុំ	០១២-១៨៣/៤១	
៤៥	ឈុំ ឈុំ	ប	ឈុំ ឈុំ		
៤៦	ឈុំ ឈុំ	ប	ឈុំ ឈុំ		
៤៧	ឈុំ ឈុំ	ប	ឈុំ ឈុំ		
៤៨	ឈុំ ឈុំ	ប	ឈុំ ឈុំ		
៤៩	ឈុំ ឈុំ	ប	ឈុំ ឈុំ		
៥០	ឈុំ ឈុំ	ប	ឈុំ ឈុំ	០១៦៥១១១៦	
៥១	ឈុំ ឈុំ	ប	ឈុំ ឈុំ	០១៧៧៤០០៣	
៥២					
៥៣					
៥៤					
៥៥					
៥៦					
៥៧					
៥៨					
៥៩					
៦០					
៦១					
៦២					
៦៣					
៦៤					
៦៥					

**GMS Second Corridor Towns Development Project
GMS PPTA 8425 REG**

**Groundwater Sampling and Analysis in Kampot and
Sihanoukville, Cambodia**

Terms of Reference

DRAFT

April, 2015

Introduction & Rationale

165. The Asian Development Bank (ADB) is supporting small infrastructure developments the towns of Kampot and Sihanoukville Cambodia with the objective to improve both urban environments and stimulate socioeconomic development. The project will construct a new landfill site and a new WWTP and collection system in Kampot (KPT). In Sihanoukville (SNL) a new WWTP will be constructed with improvements to an existing landfill site. The new and renovated landfills, and new WWTPs require information on local groundwater as well as the proximity of active domestic wells near the landfills and WWTP sites.

166. These draft ToRs were prepared to provide the basis for a Request for Quote (RFQ) for a groundwater study in Kampot and Sihanoukville as part of the ADB PPTA. The quote should include costs for all field and laboratory analyses, and costs for travel to/from Phnom Penh.

Objectives

167. The objective of the assignment is to determine the depth and quality of groundwater in the area of the sites of the new and renovated landfills, and new WWTPs in KPT and SNL. The scope of the assignment includes:

- 1) Identification of existing active domestic wells near new WWTP sites, and at new and existing landfill sites;
- 2) Bore hole drilling at the WWTP and landfill sites to supplement existing active wells; and
- 3) Sampling and laboratory analyses of groundwater quality from domestic wells and from new bore hole sites;
- 4) Report preparation

1. Coordination with National Engineer

168. The assignment will be coordinated with the national engineers of the ADB project who is overseeing the siting and development of the WWTPs and landfill sites. The locations of all groundwater sampling locations will be determined in consultation with the engineers.

Detailed Requirements

The requirements of the assignment are as follows:

2. Landfill Sites

New (1) and Existing (2) Landfill Sites in KPT and SNL

- 1) Confirm the location of existing active domestic wells that are near the three sites. There appears to be a well at the existing landfill site in SNL.
- 2) Identify the number of supplementary bore holes that need to be drilled to provide a total of 4 equidistant sampling sites on an approximate 500-800 m radius around each site. Two of the sampling sites must be down-slope of the site. The sites chosen must also be useful for future groundwater monitoring;
- 3) Collect and preserve the groundwater samples from the 4 sites using accepted International procedures (e.g., AWWA)³⁶ to maintain the in situ quality of the samples while they are transported to laboratory in Phnom Penh.
- 4) Analyze samples in laboratory using accepted International procedures (e.g., AWWA).

New WWTPs (2) in KPT and SNL

- 1) Confirm the location of existing active domestic wells that are near the new WWTP site adjacent to Teuk Chhu river in KPT, and at northwest site at SNL.
- 2) Clarify whether 1-2 bore holes are needed to supplement the absence of domestic wells in the immediate area. Bore holes should be located over the location of the anaerobic lagoons. The sites chosen must also be useful for future groundwater monitoring;
- 3) Collect and preserve the groundwater samples from the 2 sites using accepted International procedures (e.g., AWWA) to maintain the in situ quality of the samples while they are transported to laboratory in Phnom Penh.
- 4) Analyze samples in laboratory using accepted International procedures (e.g., AWWA).

3. Groundwater variables to be sampled and analyzed at each site

169. The groundwater parameters that need to be sampled and analyzed at all sites are listed in Table 7.

³⁶ American Water Works Association AWWA, 2013). Standard Methods for Examination of Water and Wastewater: Water Wells.

Table 8. Groundwater variables to be determined at landfill and WWTP sites.

Groundwater Variable	Location of Analysis
depth of water table	at well site
temperature (C°)	at well site with meter
dissolved oxygen DO (mg/l)	at well site with meter
pH	at well site with meter
conductivity	at well site with meter
chemical oxygen demand COD (mg/l)	in laboratory
total dissolved solids DS (mg/l)	in laboratory
heavy metals: As, Cd, Fe, Pb, Zn, Cu (mg/l))	in laboratory
oil and grease (mg/l)	in laboratory
total and faecal coliform bacteria (mpn)	in laboratory
nitrogen: TN, NH ₃ , NO ₃ , NO ₂ (mg/l)	in laboratory
phosphorus: TP, PO ₄ (mg/l)	in laboratory
hydrogen sulphide H ₂ S, (mg/l)	in laboratory
surfactants (detergents) (mg/l)	in laboratory
Quality Control & Assurance Samples	
2 field sampling blanks with distilled water: 1 for existing landfill and 1 for new SLF	
2 laboratory analysis blanks: 1 for samples from existing landfill, and 1 for new SLF samples	

4. Reporting

170. A report on the above field and laboratory investigations must be prepared.

a. Location of sampling sites

171. The report must provide simple maps indicating the location of the groundwater sampling sites in relation to the WWTP sites and landfill sites. Each sampling site must include a latitude and longitude coordinate. The maps should also indicate the location of the nearest houses or settlements. The sampling locations and data summary must distinguish the bore hole sites from existing domestic well sites.

b. Groundwater quality

172. In a table format the report must provide the groundwater quality variables from Table 7 that were determined in the field, and in the laboratory for both sites. The tables should also include the QA/QC samples for all variables from Table 7.

c. Sampling & Analysis Methodology

173. The report must include a brief description of all field and laboratory methods that were used to sample and analyze the groundwater samples.

**GMS Second Corridor Towns Development Project
GMS PPTA 8425 REG**

Indicative Landfill Closure Procedure
in
Kampot, Cambodia

DRAFT

April 2015

Current Situation:

The existing landfill in Kampot is an unmanaged dumpsite of simplest design. It does not have segregated cells, or a liner, or a leachate collection system. The operation of the landfill appears unplanned and not well organised.

The following indicative criteria were adopted for the subproject for the decommissioning and closure of the existing landfill in Kampot:

- a. Consolidate the waste field into a smaller area;
- b. completely cover the consolidated field;
- c. prevent rain water and surface water from penetrate into consolidated field; and
- d. provide a solution for oxidation or removal of methane (CH₄) from the site.

Elements of the indicative closure procedure presented here are applicable to the renovation of the existing landfill in Sihanoukville.

Indicative Closure Procedure:

Based on a preliminary assessment the following indicative closure procedure has been identified:

1. Garbage pickers and sorters notified of closure and location of new landfill to the north of existing site.
2. A high perimeter fence and guarded gate installed around existing landfill site with signs indicating landfill closed.
3. Level & shape landfill made convex with a minimum slope of 2% letting rain water flow to the

adjacent perimeter.

4. Ensure open cut-off ditches capture & discharge rain water to outside the site area.
5. Lay down 40 cm of impermeable clay excavated from DOE-authorized areas at or near the site.
6. Add a 10 cm layer of sandy material excavated from DOE-authorized areas at or near the site that provides drainage for rainwater to the sides that distributes gas emanating from solid waste below.
 7. Lay down a 20 cm top layer of soil suitable for grass re-vegetation, and for supporting bacteria oxidization of methane gas (local soil mixed with earth); and
 8. Plant robust grass as top vegetation.
 9. Monitoring of groundwater quality from existing or newly established bore holes biannually for 3 years.

The cost for this preliminary procedure has not been estimated in detail.

Environmental Management Plan

June 2015

Kingdom of Cambodia: Second Greater Mekong
Subregion Corridor Towns Development Project,
PPTA 8425

Kampot Subproject

This environmental management plan is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature.

CURRENCY EQUIVALENTS

(as of 26 March 2015)

Currency Unit	–	Riel R
R1.00	=	\$0.00025
\$1.00	=	R3,941

ABBREVIATIONS

ADB	-	Asian Development Bank
CEMP	-	Contractor Environmental Management Plan
DAFF	-	Department of Agriculture, Forestry and Fisheries
DOE	-	Department of Environment
DPWT	-	Department of Public Works and Transport
DOT	-	Department of Tourism
DOWRAM	-	Department of Water Resources and Meteorology
EA	-	Executing Agency
EIA	-	Environmental Impact Assessment
EMC	-	Environmental Monitoring Consultant
EMP	-	Environment Management Plan
EO	-	Environmental Officer
ERT	-	Emergency Response Team
EERT	-	External Emergency Response Team
GDPW	-	General Department of Public Works
GMS	-	Greater Mekong Subregion
Government	-	Government of Cambodia
IA	-	Project Implementing Agency
IEE	-	Initial Environment Examination
IEIA	-	Initial Environmental Impact Assessment
PIU	-	Project Implementation Unit
MAFF	-	Ministry of Agriculture, Forestry and Fisheries
MOE	-	Ministry of Environment
MIME	-	Ministry of Industry, Mines and Energy
MPWT	-	Ministry of Public Works and Transport
MOT	-	Ministry of Tourism
MOWRAM	-	Ministry of Water Resources and Meteorology
PA	-	Project Administration Manual
PMIS	-	Project Management Implementation Support
PSC	-	Project Steering Committee
PPTA	-	Project Preparatory Technical Assistance
RP	-	Resettlement Plan
GRC	-	Royal Government of Cambodia
SPS	-	ADB's safeguard policy statement (2009)
SO	-	Safeguards Officer
WWTP	-	Wastewater Treatment Plant

WEIGHTS AND MEASURES

km	-	kilometer
kg	-	kilogram
ha	-	hectare

In this report, "\$" refers to US.

TABLE OF CONTENTS

I.	INTRODUCTION	1
	A. Kampot Subproject	1
II.	INSTITUTIONAL ARRANGEMENTS & RESPONSIBILITIES	1
	A. Worker and Community Health and Safety	4
	B. Regulatory Framework for Kampot Subproject Components	5
III.	SUMMARY OF POTENTIAL IMPACTS	5
	A. Public Consultation	6
	1. Follow-up Consultation	6
IV.	MITIGATION PLAN	7
V.	MONITORING PLAN	19
	A. Environmental Standards for Subproject Components	19
	B. Performance Monitoring	19
VI.	REPORTING	19
VII.	ESTIMATED COST OF EMP	24
VIII.	EMERGENCY RESPONSE PLAN	25
	A. Alert Procedures	26
	B. Emergency Response Situations	27
IX.	INSTITUTIONAL CAPACITY REVIEW AND NEEDS	29
	ANNEX 1: INDICATIVE TORS FOR ENVIRONMENTAL SPECIALISTS OF PMIS	30
	ANNEX 2: ENVIRONMENTAL STANDARDS FOR CAMBODIA	32
	Table 1: Summary of subproject components of Kampot	1
	Table 2: Regulations and guidelines applicable to subproject.	5
	Table 3: Summary of potential environmental impacts and mitigations of subproject	6
	Table 4: Environmental impact mitigation plan	8
	Table 5: Environmental monitoring plan	20
	Table 6. Performance monitoring indicators for Kampot subproject.....	23
	Table 7: Estimated costs for environmental monitoring plan of EMP	24
	Table 8: Roles and responsibilities in emergency incident response	25
	Table 9: Evacuation procedure	27
	Table 10: Response procedure during medical emergency.....	28
	Table 11: Response procedure in case of fire	28

I. INTRODUCTION

1. The environmental management plan (EMP) for the subproject in Kampot, Kampot province provided herein is one of two EMPs that have been prepared for the subprojects of the Second Greater Mekong Subregion Corridor Towns Development Project (the project) in Cambodia. The other EMP addresses the subproject in neighbouring Sihanoukville, Preah Sihanoukville province. A single Initial Environmental Examination (IEE) of both subprojects was prepared under separate cover. The separate EMPs are comprehensive and are developed as stand-alone management tools that are supported by the parent IEE.

A. Kampot Subproject

2. The subproject in Kampot consists of four components summarized in Table 1.

Table 1: Summary of subproject components of Kampot

Component	General Specifications
Wastewater Collection and Treatment	<ul style="list-style-type: none">• New anaerobic lagoon treatment plant• 4,500 m³/day capacity• New and upgraded collection network
Solid Waste Management	<ul style="list-style-type: none">• New modern landfill with discrete cells, liner, leachate collection system;• New access road• Closure of existing landfill• Transferred and improved waste sorting process at site
Urban Drainage	<ul style="list-style-type: none">• New separated stormwater collection network and outfalls

II. INSTITUTIONAL ARRANGEMENTS & RESPONSIBILITIES

3. At the feasibility stage the management framework¹ for the implementation of the environmental management plan for the subproject is summarized as follows. The Ministry of Public Works and Transport (MPWT) which is the executing agency (EA) for the project will take overall responsibility for successful implementation of the EMP. The EA will establish a Phnom Penh-based Project Steering Committee (PSC). The General Department of Public Works (GDPW) will be the project implementation agency (IA) in which a project management unit (PMU) will be assigned for the entire subproject. The IA/PMU will implement the EMP with an internally assigned Safeguards Officer (SO). The PMU/SO will lead the implementation of the EMP in conjunction with the Environmental Officer(s) (EO) of the construction contractor(s).

4. The EA/PSC will provide operational guidance to the IA/PMU for implementation of the EMP and will liaise with the ADB on safeguard reporting and issues. The SO of the PMU/IA will oversee the work of the EO of the contractor(s) on the implementation of the CEMP² for particular construction packages.

¹ Adapted from Interim Report 12/14.

² Contractor Environmental Management Plan prepared by contractor as part of bid documents based on updated EMP

5. External support for the implementation of the EMP will be provided by the International and National Environment Specialists (ES) of the Project Management Implementation Support (PMIS) who will have a budget for an external Environmental Monitoring Consultant (EMC). The EMC will conduct any required field sampling, and laboratory analyses of field samples (e.g., water quality, air quality) that cannot be performed by the contractor or PIU. Provided below is a summary of responsibilities for implementation of the EMP.

6. The responsibilities of the EA as supported by PSC include:

- Provide coordination for environmental and social safeguards and monitoring;
- Liaise with ADB on the implementation of the EMP; and
- Coordinate resolution with IA, and ADB if necessary with issues arising from the implementation of EMP.

7. The responsibilities of the Safeguards Officer (SO) of the PIU/PMU include:

- Assist PMIS with updating the EMP to meet final detailed subproject designs;
- Notify MPWT to verify that Government approvals of project are met, and that the EMP is compliant with requirements of Royal Government of Cambodia (RGC) sub-decree on EIA, No 72 ANRK.BK, issued by the Ministry of Environment (MOE, 1999);
- Assist the PMIS with inclusion of CEMP requirements in bidding documents, including bid evaluations, based on the updated EMP;
- Undertake day to day management of EMP implementation activities;
- Work with EMC on implementation of monitoring plan of EMP;
- Ensuring compliance with loan covenants and assurances in respect of all subprojects, including EMPs (as well as the GAP and resettlement plans);
- Lead follow-up meetings with all affected stakeholders;
- Prepare and submit quarterly reports on EMP implementation to the IA/EA;
- Oversee implementation of the CEMP by contractor;
- Coordinate with ES of PMIS for EMP implementation;
- Undertake regular construction site inspections to ensure contractor implements the CEMP properly; and
- Ensure the contractor's EO submits monthly reports on construction mitigations and monitoring.

8. The responsibilities of the Environmental Specialists of the PMIS are detailed in the Terms of Reference for the two positions in Annex 1. Their key responsibilities for the EMP are listed below:

- Update the EMP to meet final detailed design requirements of subprojects;
- Provide technical direction and support to SO/PMU for implementation of the EMP;
- Oversee the design and delivery of capacity development and training of PMU staff and the contractor's EO ;
- Provide advice and support to the EMC with their monitoring activities;
- Review all reports prepared by the PIU and EMC for EA/PSC and ADB; and
- Review and inspect the location of any possible contaminated sites near subprojects.

9. The responsibilities of Environmental Officer (EO) of Contractor include:

- Implement the CEMP during the construction phase of subproject; and
- Prepare and submit monthly reports on mitigation and monitoring activities of CEMP and any environmental issues at construction sites.

10. The responsibilities of Environmental Monitoring Consultant (EMC) include:

- Implement the environmental sampling required for monitoring plan of EMP that cannot be conducted by the contractor and PIU/PMU.
- Perform required laboratory analyses for the monitoring program detailed in EMP; and
- Prepare and submit quarterly reports to the PMIS and PIU on monitoring activities.

11. The implementation of the EMP as part of the overall environmental due diligence (DD) of the subproject is conducted alongside the separate parallel DD of the government. Table 2 reproduces the summary table of environmental due diligence from the IEE. Table 2 shows that the ADB IEE and loan is approved well before the government EIA/IEIA is initiated, and that the EA must approve the ADB IEE and EMP by formal letter. The ADB IEE/EMP is not contingent on compliance with any specific government regulation.

Table 2. Summary of environmental due diligence during project implementation

Design and Implementation	Environmental DD and Approvals			Milestones & Notes
	ADB / PPTA	Cambodia	PMIS / Contractor	
Feasibility design				
Initial stakeholder disclosure & consultation	PPTA	EA assists		
Draft IEEs and EMPs	PPTA			Draft IEEs & EMPs completed
Finalize IEEs and EMPs	ADB review & approves IEE/EMPs			ADB approved IEE/EMP as per SPS (2009).
		EA reviews and approves IEE/EMPs		EA approved IEE/EMP with formal letter only. Compliance with specific RGC / EA regulations not required
Loan documents (PAM/RRP)	Document preparation, approval by ADB	Review & approval of PAM		Loan approval
Detailed engineering design				
Continued stakeholder disclosure & consultation		IA/PIU lead	ES support to PMIS	As per PCP (2012) ³ stakeholder disclosure and consultations continue throughout construction phase

³ ADB Public Communication Policy (2012)

Design and Implementation	Environmental DD and Approvals			Milestones & Notes
	ADB / PPTA	Cambodia	PMIS / Contractor	
				coincident with initiation of GRM.
Update EMPs		Support to ES	Lead by ES	Approval of updated EMP by EA and ADB
Initiation of Cambodia environmental DD		EA leads with oversight from MOE		DOE approved CAM IEE or IEIA follows independently
Tendering / contract award				
EMPs included in tender documents		Lead by EA/IU	Support by ES	
Tenders let and bids prepared		Lead by EA	Contractor drafts CEMP	CEMPs prepared and included in contractor bids
Construction packages	Input from ADB		CEMPs reviewed by ES/PMIS	Construction package awards
Construction & supervision				
Implementation of mitigation and monitoring plans		Support from IU/PIU	By contractor with support from ES	CEMP implemented by contractor, other aspects of EMP overseen by ES
Continued stakeholder disclosure and consultation		IA/PIU lead	Support from ES	As part of GRM
Monitoring reporting	To ADB	IA/PIU lead preparation of regular reports to ADB	Support from ES	Reports provide input for review missions

12. The Department of Environment (DOE) is the provincial agency which oversees environmental management of Kampot. The DOE with district staff provide direction and support for environmental protection-related matters including application of the Law on Environmental Protection and Natural Resources Management, enacted by National Assembly, 1996, promulgated by Preah Reach Kram/NS/RKM-1296/36; and environmental standards

13. The ADB provides guidance to EA/PSC with any issues related to EMP and reviews quarterly reports on EMP activities compiled and submitted by the EA which are disclosed on ADB website pursuant to ADB Policy on Public Communication (2011).

A. Worker and Community Health and Safety

14. In 2003 the International Labour Organization (ILO) created the New Global Strategy for Occupational Safety and Health (OSH). Based on the OSH⁴, the Ministry of Labour and Vocational Training (MLVT) through the Department of Occupational Safety & Health is developing the Occupational Safety and Health Master Plan (OSHM; 2009-2013) of Cambodia.

⁴ ILO. 2009. Asean-Oshnet, Occupational Safety and Health Practices.

15. The emerging OSHM, *inter alia*, addresses worker and public safety in the construction and operation of small-medium enterprises and notably rural roads. The EA/PSC as supported by the PIUs must obtain and implement the directives of the OSH Master Plan. The pertinent associated law and directives is the Labour Law of Cambodia (1997) with specific reference to chapter VIII governing health and welfare of workers and the public.

16. To supplement the OSHM the IFC/World Bank Environment, Health, and Safety Guidelines (2007) should also be consulted the IFC EHS guidelines currently provide the international standard for worker and public safety.

17. ADB assists the PSC with timely guidance at each stage of project implementation following agreed implementation arrangements and reviews all documents that require ADB approval including environmental safeguards.

B. Regulatory Framework for Kampot Subproject Components

18. Regulations and guidelines that apply to the construction the new WWTP and landfill in Kampot are summarized in Table 3. The current environmental standards for Cambodia are provided in Annex 2. See the IEE for complete the legal and regulatory framework for environmental management in Kampot province.

Table 3: Regulations and guidelines applicable to subproject.

Solid Waste Management and Wastewater Management
<ul style="list-style-type: none"> • Law on Environmental Protection and Natural Resources Management, enacted by National Assembly, 1996, promulgated by Preah Reach Kram/NS/RKM-1296/36; <ul style="list-style-type: none"> ○ Sub-decree on Water Pollution Control (1999): <ul style="list-style-type: none"> - Annex 2: Industrial effluent standards (including WWTPs); - Annex 4: Water quality standards for public water & biodiversity; and - Annex 5: Water quality standards for public waters and health. ○ Sub-decree on Solid Waste Management, No 36 ANRK/BK (1999): • Directive for Managing Health Wastes in the Kingdom of Cambodia (MOH, 2008).

III. SUMMARY OF POTENTIAL IMPACTS

19. The potential impacts of the Kampot subproject from the IEE are summarized in Table 4. Potential impacts concern the civil works during the construction phase of the subproject. The short-term disturbances of the construction and civil works activities will be noise, dust, reduced access, increased traffic and risk of traffic accidents, worker and public safety, soil erosion and sedimentation of the Teuk Chuu River and solid and liquid waste can be managed and mitigated.

Table 4: Summary of potential environmental impacts and mitigations of subproject

Pre-construction Phase
<ul style="list-style-type: none"> • Land acquisition for new WWTP. • Groundwater contamination at new landfill site and new WWTP will be avoided with the groundwater study to determine depth of water table, and groundwater quality with installed bore hole sampling wells (Appendix D of IEE) • Potential public injury from old landfill prevented and minimized with proper closure and isolation of old landfill (see Appendix D of IEE).
Construction Phase
<p><u>New WWTP, upgraded drainage, new landfill and access road</u></p> <ul style="list-style-type: none"> • Disturbances & impacts from civil works such as reduced and/or blocked public access to areas, disrupted business and recreation, noise, dust caused by increased truck traffic and heavy equipment use, soil and surface water pollution caused by equipment operation and maintenance, public and worker accidents, increased traffic congestion & traffic accidents, land erosion and surface water sedimentation such as Teuk Chhou river , localized drainage and flooding problems, solid waste and domestic pollution from worker camps, and communicable disease and community problems caused by migrant workers. Permanent loss of vegetation and local agriculture for new access road to new WWTP in Kampot. <p><u>Wastewater Collection and Treatment</u></p> <ul style="list-style-type: none"> • Sedimentation of Teuk Chhou river and adjacent irrigation canal prevented with construction of berms or plastic fencing around WWTP site during construction • Local contamination of groundwater at low lying WWTP site will be prevented with use of sufficient infilling with impervious material (e.g., clay) on which anaerobic lagoons and WWTP building will be constructed without excavations required
Operation Phase
<p><u>Solid Waste Management</u></p> <ul style="list-style-type: none"> • Groundwater quality contamination from new landfill avoided with regular monitoring of groundwater quality with site bore wells, and from sufficient O&M to maintain landfill in good working order. <p><u>Wastewater Collection and Treatment</u></p> <ul style="list-style-type: none"> • Pollution of Teuk Chhou river avoided by regular analysis of treated effluent quality and sufficient O&M to maintain WWTP facilities and processes to original design specification • Local aesthetic issues of odour and noise of new WWTP avoided by regular maintenance of dense treed, fenced perimeter around WWTP. <p><u>Improved Drainage</u></p> <ul style="list-style-type: none"> • Flooding events prevented with regular cleaning and maintenance of upgraded drains.

A. Public Consultation

20. The stakeholder consultation strategy that was developed for the IEE will be continued with the start of the pre-construction phase of the subproject. The first step will be the disclosure of the draft IEE to the affected stakeholders that were consulted to obtain their review and comment.

1. Follow-up Consultation

21. As indicated in the IEE, the primary concern of the public and stakeholders of the subproject were disturbances during construction phase of the subproject components. These

issues will be reviewed during follow-up consultations throughout the pre-construction, construction, and operation of the completed subproject components.

IV. MITIGATION PLAN

22. The mitigation measures of the EMP are presented in the mitigation plan for the subproject in Table 5. Following the structure of the IEE, the mitigation plan is organized by the three development phases of the subproject defined by the pre-construction; construction; and the post construction operational phase. The mitigation plan addresses the environmental issues and concerns raised at the stakeholder meetings.

23. The mitigation plan combines construction phase impacts that are common to the new WWTP, landfill, improved drainage and enhancements to the town centre for which single mitigation measures are prescribed. In this way redundant mitigation measures are not re-stated numerous times. However, impacts and required mitigations specific to a subproject component are also identified. Or, common mitigations that are particularly important for a subproject component are underscored. The mitigation plan identifies potential impacts, required mitigations, responsible parties, location, timing, and indicative costs. The mitigation plan is decidedly comprehensive in order for it to be easily updated at the detailed design phase to fully address the potential impacts of the final subproject designs.

Table 5: Environmental impact mitigation plan

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
<i>Pre-Construction, Detailed Design Phase</i>								
Confirmation of no required resettlement, relocations, & compensation	No negative environmental impacts	1. Affected persons well informed well ahead of subproject implementation.	All affected persons in subproject areas	Before project implemented	See resettlement plans	See resettlement plan	EA/IA	Resettlement committees
Disclosure, & engagement of community	No community impacts	2. Initiate Information Disclosure and Grievance process of IEE	For all construction sites.	Beginning of project	Quarterly	No marginal cost ⁶	PMU	PIU
Government approvals	No negative impact	3. Notify DoE of subproject initiation to complete EA requirements, and obtain required project permits and certificates.	Entire subproject	Before construction	As required	No marginal cost	PIU/DoE	DoE
Detailed designs of subproject,	Minimize negative environmental impacts	4. Work with PMIS ⁷ to complete detailed designs of the new WWTP and landfill, and upgraded drainage. Ensure the following measures are included: a) identification of spill management prevention plans, and emergency response plans for all construction sites; b) no disturbance or damage to culture property and values; c) no, or minimal acquisition of agriculture or forested areas near new landfill north of Kampot. d) locate aggregate borrow pits and rock supply areas away from human settlements with fencing and access barriers; e) no, or minimal disruption to village water supplies along access roads, utilities, and electricity with contingency plans for unavoidable disruptions; f) no, or minimal disruption to normal pedestrian and vehicle traffic along all road segments with contingency alternate routes; g) for residential areas include specific plan to notify & provide residents and merchants of construction activities & schedule to minimize disruption to normal commercial and residential activities.	Final siting	Before construction initiated	Once with detailed designs documents	No, marginal cost	PMIS	EA/IA

⁵ Costs will need to be updated during detailed design phase.

⁶ No marginal cost indicates that costs to implement mitigation are to be built into cost estimates of bids of contractors

⁷ PMIS is detailed design and supervision consultant.

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		h) finalize disposal site for sludge from new WWTP south of Kampot with MOE						
Update EMP	Positive environmental impacts	5. Review and finalize closure plan for old landfill ensuring protection of public with fencing, and GHG emissions with adequate consolidation and coverage 6. Review and finalize draft TOR for required groundwater study of new and old landfill sites. Contact potential consultants in Phnom Penh 7. Re-clarify with DoE that no known rare or endangered species inhabit the subproject areas 8. Identify any new potential environmental impacts of subproject and include in EMP. 9. Update mitigation measures and monitoring requirements of EMP where necessary to meet detailed designs, and to protect affected environments. 10. Submit updated EMP with new potential impacts to ADB to review. 11. Develop individual management subplans for: a) Construction drainage; b) Erosion; c) Noise and Dust; d) Contaminated Spoil Disposal; e) Solid and Liquid Waste Disposal; f) Construction & Urban Traffic; g) Utility and Power Disruption; h) Worker and Public Safety; i) Tree and Vegetation Removal and Site Restoration; j) Construction Materials Acquisition, Transport, & Storage, and k) Cultural chance finds.	All sites	Before construction initiated	Once with detailed designs documents		PMIS	PMU/PIU
Create awareness of physical cultural resources in area	No negative environmental impact	12. Dept of Tourism to review potential locations of physical cultural resources, and explain possible PCR to contractors and PMIS	All subproject areas	Before construction begins	Once	No marginal cost	DoT	DoT/PIU
Confirm Government approved construction waste disposal sites	No negative impact	13. Contact DoE to confirm locations of sites for borrow pits and disposal areas for construction and hazardous waste for subprojects, and obtain required permits.	Entire subproject	Before construction	As required	No marginal cost	PMU/DoE/DAFF/DPWT	PIU
UXO survey, & removal	Injured worker or public	14. Ensure Government is consulted for UXO, and clears areas where necessary	All construction sites.	Beginning of subproject	Once	See Monitoring Plan below	PMU/PIU	Government
Obtain &	Prevent or	15. Contractors to comply with all statutory requirements	For all	Beginning of	Once	No marginal	PMIS	PIU &

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
activate permits and licenses	minimize impacts	set out by Government for use of construction equipment, and operation construction plants such as concrete batching.	construction sites	construction		cost		contractors
Develop bid documents	No negative environmental impact	16. Ensure updated EMP is included in contractor tender documents, and that tender documents specify requirements of CEMP must be budgeted. 17. Specify in bid documents that contractor must have experience with implementing EMPs, or provide staff with the experience.	All subproject areas	Before construction begins	Once for all tenders	No marginal cost	PMIS	PIU
Capacity development	No negative environmental impact	18. Develop and schedule training plan for (PIU/SO) to be able to fully implement EMP, and to manage implementation of mitigation measures by contractors. 19. Create awareness and training plan for contractors whom will implement mitigation measures.	All subproject areas	Before construction begins	Initially, refresher later if needed	No marginal cost	PMIS	PMIS
Recruitment of workers	Spread of sexually transmitted disease	20. Use local workers as much as possible thereby reducing number of migrant worker	All work forces.	Throughout construction phase	Worker hiring stages	No marginal cost	PMU/PIU	Contractor's bid documents
Construction Phase of new WWTP, new Landfill, and Upgraded Drainage								
Initiate EMP & sub-plans,	Prevent or minimize impacts	21. Initiate updated EMP & CEMP including individual management sub-plans for different potential impact areas that are completed in pre-construction phase (see sub-plan guidance below).	For all construction sites	Beginning of construction	Once	No marginal cost	PMIS	PIU & contractors
Worker camps	Pollution and social problems	22. Locate worker camps away from human settlements. 23. Ensure adequate housing and waste disposal facilities including pit latrines and garbage cans. 24. A solid waste collection program must be established and implemented that maintains a clean worker camps 25. Locate separate pit latrines for male and female workers away from worker living and eating areas. 26. A clean-out or infill schedule for pit latrines must be established and implemented to ensure working latrines are available at all times. 27. Worker camps must have adequate drainage. 28. Local food should be provided to worker camps. Guns and weapons not allowed in camps. 29. Transient workers should not be allowed to interact with the local community. HIV/Aids education should be given to workers. 30. Camp areas must be restored to original condition after	All worker camps	Throughout construction phase	Monthly	No marginal cost	PMIS/PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		construction completed.						
Training & capacity	Prevent of impacts through education	31. Implement training and awareness plan for PIU/SO and contractors.	PIU office, construction sites	Beginning of construction	After each event	No marginal cost	PMIS	PMIS/PIU
Implement construction materials acquisition, transport, and storage sub-plan	Pollution, injury, increased traffic, disrupted access	32. All borrow pits should be approved by DoE. 33. Select pits and quarries in areas with low gradient and as close as possible to construction sites. 34. Required aggregate volumes must be carefully calculated prior to extraction to prevent wastage. 35. Pits should not be located near surface waters, forested areas, critical habitat for wildlife, or cultural property or values. 36. All topsoil and overburden removed should be stockpiled for later restoration. 37. All borrow pits should have a fence perimeter with signage to keep public away. 38. After use pits should be dewatered and permanent fences installed with signage to keep public out, and restored as much as possible using original overburden and topsoil. 39. Unstable slope conditions in/adjacent to the quarry or pit caused by the extractions should be rectified with tree planting. 40. Define & schedule how materials are extracted from borrow pits and rock quarries, transported, and handled & stored at sites. 41. Define and schedule how fabricated materials such as steel, wood structures, and scaffolding will transported and handled. 42. All aggregate loads on trucks should be covered.	For all construction areas.	Throughout construction phase	Monthly	No marginal cost	PMIS/PIU	contractor
DBST production, and application (if used)	Air pollution, land and water contamination, and traffic & access problems,	43. Piles of aggregates at sites should be used/or removed promptly, or covered and placed in non-traffic areas 44. Stored DBST materials well away from all human activity and settlements, and cultural (e.g., schools, hospitals), and ecological receptors. Bitumen production and handling areas should be isolated. 45. Contractors must be well trained and experienced with the production, handling, and application of bitumen. 46. All spills should be cleaned immediately and handled as per hazardous waste management plan, and according to Government regulations.	For all construction areas.	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		47. Bitumen should only be spread on designated road beds, not on other land, near or in any surface waters, or near any human activities. 48. Bitumen should not be used as a fuel.						
Implement spoil management subplan	Contamination of land and surface waters from excavated spoil, and construction waste	49. Uncontaminated spoil to be disposed of in Government-designated sites, which must never be in or adjacent surface waters such as Teuk Chhou river. Designated sites must be clearly marked and identified. 50. Spoil must not be disposed of on sloped land, near cultural property or values, ecologically important areas, or on/near any other culturally or ecologically sensitive feature. 51. Where possible spoil should be used at other construction sites, or disposed in spent quarries or borrow pits. 52. A record of type, estimated volume, and source of disposed spoil must be recorded. 53. Contaminated spoil disposal must follow Government regulations including handling, transport, treatment (if necessary), and disposal. 54. Suspected contaminated soil must be tested, and disposed of in designated sites identified as per Government regulations. 55. Before treatment or disposal contaminated spoil must be covered with plastic and isolated from all human activity.	All excavation areas	Throughout construction phase	Monthly	See Monitoring Plan for contaminated soil analyses	PMIS & PIU & DoE	contractor
Implement solid and liquid construction waste sub-plan	Contamination of land and surface waters from construction waste	56. Management of general solid and liquid waste of construction will follow Government regulations, and will cover, collection, handling, transport, recycling, and disposal of waste created from construction activities and worker force. 57. Areas of disposal of solid and liquid waste to be determined by Government. 58. Disposed of waste should be catalogued for type, estimated weigh, and source. 59. Construction sites should have large garbage bins. 60. A schedule of solid and liquid waste pickup and disposal must be established and followed that ensures construction sites are as clean as possible. 61. Solid waste should be separated and recyclables sold to buyers in community.	All construction sites and worker camps	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU & DoE	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		<u>Hazardous Waste</u> 62. Collection, storage, transport, and disposal of hazardous waste such as used oils, gasoline, paint, and other toxics must follow Government regulations. 63. Wastes should be separated (e.g., hydrocarbons, batteries, paints, organic solvents) 64. Wastes must be stored above ground in closed, well labeled, ventilated plastic bins in good condition well away from construction activity areas, all surface water, water supplies, and cultural and ecological sensitive receptors. 65. All spills must be cleaned up completely with all contaminated soil removed and handled with by contaminated spoil sub-plan.						
Implement noise and dust sub-plan	Dust Noise	66. Regularly apply wetting agents to exposed soil and construction roads. 67. Cover or keep moist all stockpiles of construction aggregates, and all truck loads of aggregates. 68. Minimize time that excavations and exposed soil are left open/exposed. Backfill immediately after work is completed. 69. As much as possible restrict working time between 07:00 and 17:00. In particular are activities such as pile driving. 70. Maintain equipment in proper working order 71. Replace unnecessarily noisy vehicles and machinery. 72. Vehicles and machinery to be turned off when not in use. 73. Construct temporary noise barriers around excessively noisy activity areas where possible.	All construction sites.	Fulltime	Monthly	No marginal cost	PMIS & PIU	contractor
Implement utility and power disruption sub-plan	Loss or disruption of utilities and services such as water supply and electricity	74. Develop carefully a plan of days and locations where outages in utilities and services will occur, or are expected. 75. Contact local utilities and services with schedule, and identify possible contingency back-up plans for outages. 76. Contact affected community to inform them of planned outages. 77. Try to schedule all outages during low use time such between 24:00 and 06:00.	All construction sites.	Fulltime	Monthly	No marginal cost	PMIS & PIU & Utility company	contractor
Implement	Damage or loss	78. Contact provincial forestry department for advice on	All	Beginning	Monthly	No marginal	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
tree and vegetation removal, and site restoration sub-plan	of trees, vegetation, and landscape	<p>how to minimize damage to trees and vegetation</p> <p>79. Restrict tree and vegetation removal to within RoWs.</p> <p>80. Within RoWs minimize removals, and install protective physical barriers around trees that do not need to be removed.</p> <p>81. All RoWs to be re-vegetated and landscaped after construction completed. Consult provincial forestry department to determine the most successful restoration strategy and techniques. Three trees should be replanted for each tree that has to be removed.</p>	construction sites.	and end of subproject		cost		
Implement erosion control sub-plan	Land erosion	<p>82. Berms, and plastic sheet fencing should be placed around all excavations and earthwork areas.</p> <p>83. Earthworks should be conducted during dry periods.</p> <p>84. Maintain a stockpile of topsoil for immediate site restoration following backfilling.</p> <p>85. Protect exposed or cut slopes with planted vegetation, and have a slope stabilization protocol ready.</p> <p>86. Re-vegetate all soil exposure areas immediately after work is completed.</p>	All construction sites	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Implement worker and public safety sub-plan	Public and worker injury, and health	<p>87. Proper fencing, protective barriers, and buffer zones should be provided around all construction sites.</p> <p>88. Sufficient signage and information disclosure, and site supervisors and night guards should be placed at all sites.</p> <p>89. Worker and public safety guidelines Government should be followed. See draft Occupational Safety & Health Master Plan of Ministry of Labor & Vocational Training (MLVT)).</p> <p>90. Population near blast areas should be notified 24 hrs ahead, and evacuated well before operation. Accepted Government blast procedures and safety measures implemented.</p> <p>91. Speed limits suitable for the size and type of construction vehicles, and current traffic patterns should be developed, posted, and enforced on all roads used by construction vehicles in Kampot.</p> <p>92. Standing water suitable for disease vector breeding should be filled in.</p> <p>93. Worker education and awareness seminars for construction hazards should be given at beginning of construction phase, and at ideal frequency of monthly.</p>	All construction sites.	Fulltime	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		<p>A construction site safety program should be developed and distributed to workers.</p> <p>94. Appropriate safety clothing and footwear should be mandatory for all construction workers.</p> <p>95. Adequate medical services must be on site or nearby all construction sites.</p> <p>96. Drinking water must be provided at all construction sites.</p> <p>97. Sufficient lighting be used during necessary night work.</p> <p>98. All construction sites should be examined daily to ensure unsafe conditions are removed.</p>						
Civil works	Degradation of water quality & aquatic resources	<p>99. Protective coffer dams, berms, plastic sheet fencing, or silt curtains should be placed between all earthworks and nearby surface waters.</p> <p>100. Erosion channels must be built around aggregate stockpile areas to contain rain-induced erosion.</p> <p>101. Earthworks should be conducted during dry periods.</p> <p>102. All construction fluids such as oils, and fuels should be stored and handled well away from surface waters.</p> <p>103. No waste of any kind is to be thrown in surface waters.</p> <p>104. No washing or repair of machinery near surface waters.</p> <p>105. Pit latrines to be located well away from surface waters.</p> <p>106. No unnecessary earthworks in or adjacent to water courses.</p> <p>107. No aggregate mining from rivers or lakes.</p> <p>108. All irrigation canals and channels to be protected the same way as rivers, streams, and lakes</p>	All construction sites	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Civil works	Degradation of terrestrial resources	<p>109. All construction sites should be located away forested or all plantation areas as much as possible.</p> <p>110. No unnecessary cutting of trees.</p> <p>111. All construction fluids such as oils, and fuels should be stored and handled well away from forested and plantation areas.</p> <p>112. No waste of any kind is to be discarded on land or in forests/plantations.</p>	All construction sites	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Implement construction and urban traffic sub-plan	Traffic disruption, accidents, public injury	<p>113. Schedule construction vehicle activity during light traffic periods. Create adequate traffic detours, and sufficient signage & warning lights.</p> <p>114. Post speed limits, and create dedicated construction vehicle roads or lanes.</p>	All construction sites	Fulltime	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		115. Inform community of location of construction traffic areas, and provide them with directions on how to best co-exist with construction vehicles on their roads. 116. Demarcate additional locations where pedestrians can develop road crossings away from construction areas. 117. Increase road and walkway lighting.						
Implement construction drainage sub-plan	Loss of drainage & flood storage	118. Provide adequate short-term drainage away from construction sites to prevent ponding and flooding. 119. Manage to not allow borrow pits and quarries to fill with water. Pump periodically to land infiltration or nearby water courses. 120. Install temporary storm drains or ditches for construction sites 121. Ensure connections among surface waters (ponds, streams) are maintained or enhanced to sustain existing storm water storage capacity. 122. Protect surface waters from silt and eroded soil.	All areas with surface waters	Design & construction phases	Monthly	No marginal cost	PMIS & PIU	contractor
Civil works: cultural chance finds sub-plan	Damage to cultural property or values, and chance finds	123. As per detailed designs all civil works should be located away from all cultural property and values. DoT identified potential sites and types of PCR in pre-con phase. 124. Chance finds of valued relics and cultural values should be anticipated by contractors. Site supervisors should be on the watch for finds. 125. Upon a chance find all work stops immediately, find left untouched, and PIU notified to determine if find is valuable. Culture section of DoT notified by telephone if valuable. 126. Work at find site will remain stopped until DoT allows work to continue.	All construction sites	At the start , and throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Construction of New Landfill (& closure of old landfill)								
Closure of old landfill	Public safety	127. Ensure old landfill is fenced completed with locked gate, adequate signage indicating landfill closed and no trespassing	Old landfill site	At start of closure	Biannual	No marginal cost	PMIS / PIU	DPWT
	Emission of GHGs	128. Ensure closure procedure includes adequate measures to either contain GHGs (CH ₄) with appropriate clay cover, or remove GHGs by flaring or transfer of consolidated solid waste to new landfill.						
Construction	Groundwater	129. Ensure depth of water table is located as part of groundwater and soil permeability study to ensure	New landfill	Before construction	Quarterly	No marginal	PMIS	DPWT

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
of new landfill	contamination	excavation of cells does not penetrated water table, and that a sufficient buffer layer exists between completed lined cells and leachate collection system and water table depending on soil permeability .	site	begins		cost		
Construction of New WWTP								
Civil works for new WWTP	Sedimentation of Teuk Chhou river	130. Ensure an earthen berm or plastic fence is installed around WWTP site to contain any wind or runoff erosion away from river	New WWTP site	Before construction begins	Quarterly	No marginal cost	PMIS	DPWT
	Contamination of groundwater	131. The low lying WWTP site needs to be infilled to a grade that will create adequate buffer between water table and excavation operations for anaerobic lagoons, and after lagoons are in operation						
Post-construction Operation of New Landfill								
Operation of new access road	Increased risk of accident or injury.	130. Enforce well marked speed limits along road where needed, and educate local villages on new road safety.	New access road	Fulltime	Biannual	O&M	DPWT	
	Increased air pollution & noise	131. Ensure vehicles maintained in proper working condition		Periodic checks				
Operation of new landfill	Contamination of groundwater	132. Groundwater wells installed during groundwater study should be maintained and used to regularly sample groundwater to ensure waste cell liners and leachate collection system are working according to design specification	At new landfill	Throughout live span of landfill	Biannual	O&M	DPWT	
Post-construction Operation of New WWTP								
Operation of WWTP	Contamination of Teuk Chhou river	133. Regular sampling and analysis of treated effluent to ensure effluent quality meets design criteria	At effluent discharge pipe	Quarterly	Biannual	O&M	DPWT	
Operation of WWTP	Contamination of sludge disposal site (landfill)	134. Regular sampling of sludge quality to ensure WWTP operating properly and not producing contaminated sludge	lagoons	Biannual	Biannual	O&M	DPWT	
Post-construction Operation of Upgraded Drains								

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
Operation of drains	Periodic back-up and local flooding	135. Improved drains must be regularly cleaned and surfaced to maintain design capacity flows	Along all upgraded drains	Before/after rainy season	Biannual	O&M	DPWT	

V. MONITORING PLAN

24. The environmental monitoring plan for the EMP is provided in Table 6. The monitoring plan focuses on all three phases (pre-construction, construction, post-construction operation) of the subproject components, and consists of environmental indicators, the sampling locations and frequency, method of data collection, responsible parties, and estimated costs. The purpose of the monitoring plan is to determine the effectiveness of the impact mitigations, and to document any unexpected positive or negative environmental impacts of the subproject. Table 2 summarizes the responsibilities for monitoring during the construction-implementation of the subproject.

A. Environmental Standards for Subproject Components

25. Environmental standards for ambient water quality for Cambodia are found in Annex 2. The environmental standards provided by the Environmental, Health and Safety Guidelines of the IFC/World Bank (2007) (e.g., ambient air quality and noise) should be followed to supplement standards that are not provided by the Government.

26. An independent environmental monitoring consultant (EMC) will be required to implement the environmental monitoring program. The EMC will be responsible for the sampling of environmental parameters that must be analyzed in a laboratory. The SO and EO will coordinate with the EMC. The PMIS/PIU will provide logistical support to the EMC where necessary for the implementation of environmental monitoring plan.

B. Performance Monitoring

27. Performance monitoring is required to assess the overall performance of the EMP. A project performance monitoring system will be developed by the EA for the entire subproject. Select indicators of major components of the environment that will be affected primarily by the construction phase are drawn from the mitigation and monitoring plans and summarized in Table 7.

VI. REPORTING

28. Regular reporting on the implementation of mitigation measures and on monitoring activities during construction phase of the subproject is required. Reporting is the responsibility of PIU and should be conducted in conjunction with regular meetings with stakeholders as part of the continuation of stakeholder communications. The mitigation and monitoring plans (Tables 5 and Table 6) summarize proposed timing of reporting. A report on environmental monitoring and implementation of EMP will be prepared quarterly for the EA/PSC by the PIU. The PIU report will compile monthly reports provided by the EO of contractor, the reports of the EMC on monitoring, and input from the ES of the PMIS. The PIU report will also be sent to the DOE and to the PSC for consolidation and transmission to ADB quarterly.

29. The reports will assess all indicators measured with the monitoring plan of EMP including performance monitoring indicators (Table 7), and will include relevant Government environmental quality standards. Templates for the monitoring reports to be prepared by the EO, PIU, and EMC will be developed by the ES of the PMIS at detailed design. Annex 3 provides a monitoring report template for the PIU that the PIU with assistance from the PMU and PMIS must complete and attach as part of regular PIU reporting to the PMU/IA.

Table 6: Environmental monitoring plan

ENVIRONMENTAL EFFECTS MONITORING							
Environmental Indicators	Location	Means of Monitoring	Frequency	Reporting	Responsibility		Estimated ⁸ Cost (USD)
					Supervision	Implementation	
Pre-construction Phase – Update Baseline Conditions							
Where needed update baseline on sensitive receptors (e.g., cultural property & values, schools or hospitals, , critical habitat), and aquatic resources of Teuk Chhou river	A) New landfill & and access road, B) New WWTP	Contact DOE, community consultations	Once	Once	PMU/PIU	Environmental Monitoring Consultant	\$1,000.
A) Qualitative air quality: dust, noise, wind, and vibration levels B) Teuk Chhou river water quality: TSS, heavy metals (As, Cd, Pb,) oil and grease, pH, DO, COD, BOD ₅ , temperature, TDS, NH ₃ , NH ₄ , other nutrient forms of N & P C) Water table depth and groundwater quality (see groundwater study TOR in Appendix E IEE)	A): At two sites above levels B): Teuk Chuu river at WWTP discharge C): Water table depth at new WWTP and landfill sites, and groundwater quality at new & old landfill sites	Using field and analytical methods approved by DoE.	One day and one night measurement during rainy & dry seasons.	One baseline supplement report before construction phase starts	PIU	Environmental Monitoring Consultant	A) \$1,000. B) \$5,000. C) \$50,000
Inventory of present and past land uses that could cause contaminated soil.	Possible contaminated lands at all excavation sites	Using field and analytical methods approved by DoE.	Once	Once	PIU	Environmental Monitoring Consultant	\$500.
Construction Phase of all Subproject Components							
Analysis of soil quality (heavy metals (As, Cd, Pb, oil & grease, hydrocarbons).	Possible contaminated lands at all excavation sites	Using field and analytical methods approved by DoE.	Once if needed	Once	PIU	Environmental Monitoring Consultant	\$2,000.

⁸ Estimated costs will need to be updated with the EMP at detailed design stage.

ENVIRONMENTAL EFFECTS MONITORING							
Environmental Indicators	Location	Means of Monitoring	Frequency	Reporting	Responsibility		Estimated ⁸ Cost (USD)
					Supervision	Implementation	
A) Qualitative air quality: dust, noise, wind, temperature, and vibration levels B) Teuk Chhou river water quality: TSS, heavy metals (As, Cd, Pb) oil and grease, pH, DO, COD, BOD ₅ C) Analysis of soil quality (heavy metals (As, Cd, Pb, Hg, Mn) and hydrocarbons. D) Domestic (worker) and construction solid waste inside & outside construction sites including worker camps. E) Public comments and complaints F) Incidence of worker or public accident or injury	A & B): Baseline sites of pre-construction phase. C) At sites where contaminated soil is suspected. D) All construction sites and worker camps E) Using hotline number placed at construction areas F) At all construction areas	A – C): Using field and analytical methods approved by DoE. Include visual observations of dust and noise from contractor & public reports. D) Visual observation E) Information transferred by telephone hotline number posted at all construction sites. F) regular reporting by contractors/PIU	(A – B): Quarterly during construction periods Daily visual records C) Once at start of excavations D) Monthly E) Continuous public input F) Continuous	Monthly	(A - D):		
					PIU	Monitoring Consultant	A & B: \$5,000./yr C: \$1,500./yr D: \$0.0
					(E & F) & daily observations:		
					PMU/PIU	contractor	E: \$1,000./yr F: \$0.0
					Operation of New Landfill		
Groundwater quality (see groundwater study in Appendix E of IEE)	Bore wells at landfill.	Using field and analytical methods approved by DoE.	Biannually for 5 years	Biannual	DPWT	\$3000. /yr	
Traffic accidents	Access road.	Regular record keeping.	Continuously	For each event	DPWT	\$0.0	
Operation of WWTP							
TSS, heavy metals (As, Cd, Pb,) oil and	At discharge pipe	Using field and analytical	Quarterly				

ENVIRONMENTAL EFFECTS MONITORING

Environmental Indicators	Location	Means of Monitoring	Frequency	Reporting	Responsibility		Estimated ⁸ Cost (USD)
					Supervision	Implementation	
grease, pH, DO, COD, BOD ₅ , temperature, TDS, NH ₃ , NH ₄ , other nutrient forms of N & P, coliform		methods approved by DoE.		Biannual		DPWT	\$9,000. /yr

Table 7. Performance monitoring indicators for Kampot subproject

Major Environmental Component	Key Indicator	Performance Objective	Data Source
Pre-construction Phase			
Public Consultation and Disclosure	Affected public and stakeholders	Meetings with stakeholders contacted during IEE & new stakeholders convened for follow-up consultation and to introduce grievance mechanism	Minutes of meeting, and participants list
EMP	Updated EMP	All stakeholders contacted during IEE re-contacted for follow-up consultation	EMP
Bid Documents	Requirements of EMP (CEMP) ⁹	EMP appended to bidding documents with clear instructions to bidders for CEMP	Bid documents
Training of PMU/PIU/SO	Training course(s) & schedule	By end of preconstruction phase, required course(s) that will be delivered are designed and scheduled	Course(s) outline, participants, and schedule
Construction Phase			
All subproject areas	Critical habitat, rare or endangered species <i>if present</i>	All <i>present</i> critical habitat and R & E species if unchanged, and unharmed	Monitoring by EMC ¹⁰
Groundwater quality	Heavy metals, coliform bacteria, TDS, H ₂ S, BOD ₅ , TN, NH ₃ , TP, nutrient forms of N & P ¹¹	Government environmental standards and criteria met	Monitoring by EMC
Surface water quality	TSS, DO, BOD, COD, pH, oil & grease, nutrient forms of T & N, metals (Pb, Fe, As) ¹²	Government environmental standards and criteria met	Monitoring by EMC
Air quality	Dust, noise, vibration	Levels never exceed pre-construction baseline levels	EMC & contractor monitoring reports,
Soil quality	Solid and liquid waste	Rigorous program of procedures and rules to collect and store all waste from construction camps and sites practiced.	Contractor and EMC monitoring reports
Hazardous materials and waste	Oil, gasoline, grease, alum, chlorine, soda	Rigorous program of procedures to manage and store all waste from construction camps and sites practiced.	Contractor and EMC monitoring reports
Public and worker safety	Frequency of injuries	Adherence to Government policy and site-specific procedures to prevent accidents ¹³	Contractor reports

⁹ Contractor Environmental Management Plan developed from EMP in contractor bidding document

¹⁰ Environmental Monitoring Consultant hired to assist implementation of Environmental Monitoring Plan

¹¹ See Annex 2 for environmental standards, analyzed by laboratory facilities in Phnom Penh.

¹² Footnote 10

¹³ MLVT's new Occupational Safety & Health Master Plan needs to be applied, or IFC World Bank EHS (2007)

Major Environmental Component	Key Indicator	Performance Objective	Data Source
Cultural property	Incidence of damage or complaints	No valued cultural property, or unearthed valuable relic is harmed in any way	Public input, contractor reports, public input, EMC reports
Traffic	Frequency of disruptions and/or blocked roadways	Disruptions, stoppages, or detours are managed to absolute minimum.	Public input, contractor reports, EMC reports
Operation Phase of WWTP			
Treated effluent quality	TSS, DO, BOD, COD, pH, oil & grease, nutrient forms of T & N, metals (Pb, Fe, As)	No deviation from design quality	DPWT/DOE
Operation of Landfill Site			
Groundwater quality	Heavy metals, coliform bacteria, TDS, H ₂ S, BOD ₅ , TN, NH ₃ , TP, nutrient forms of N & P	No deviation from background levels, compliance with standards Appendix 2	DPWT/DOE
Public safety	Incidence of traffic accidents on access road	No deviation from baseline frequency	DPWT

VII. ESTIMATED COST OF EMP

30. The marginal costs for implementing the EMP are primarily for environmental monitoring because the costs for implementing impact mitigation measures during the construction phase are included with the construction costs in contractor bid documents.

31. From Table 6 the preliminary costs for the implementation of the EMP for subproject in Kampot are summarized in Table 8. These costs include per diem technician fees. Note that a margin of cost uncertainty/contingency to the total EMP cost has been added. These costs include per diem technician fees.

32. An estimated budget of \$50,000 is allocated for the groundwater study including bore hole construction at the new and old landfill sites (Appendix E of IEE). An estimated budget of \$10,000 is required for capacity building and training for environmental management for PIU/PMU in conjunction with other capacity development activities of the subproject. The costs will need to be reviewed and updated by the PMIS in conjunction with the PIU during the pre-construction phase.

Table 8: Estimated costs for environmental monitoring plan of EMP

Activity Type	Estimated Cost (USD)
Pre-construction Phase	
Updating Environmental Baseline	
cultural receptors	\$1,000
environmental quality	\$6,500
groundwater study at landfills	\$50,000
Construction Phase	
environmental quality	\$15,000

public consultation	\$2,000
Post-construction Operation Phase	
environmental quality	\$24,000
public input	\$0.0
Training and capacity development	\$10,000
Total	\$108,500

VIII. EMERGENCY RESPONSE PLAN

33. The Contractor must develop emergency or incident response procedures during construction. In the operational phase the operator/civil authorities will have responsibility for any emergencies or serious incidents. The construction phase should ensure:

- i) Emergency Response Team (ERT) of the Contractor as initial responder;
- ii) The District fire and police departments, emergency medical service, the Department of Public Health (DPH), collectively referred to as the External Emergency Response Team (EERT), as ultimate responders.

34. The Contractor will provide and sustain the required technical, human and financial resources for quick response during construction.

Table 9: Roles and responsibilities in emergency incident response

Entity	Responsibilities
Contractor Team (ERT)	<ul style="list-style-type: none"> - Communicates / alerts the EERT. - Prepares the emergency site to facilitate the response action of the EERT, e.g., vacating, clearing, restricting site. - When necessary & requested by the EERT, lends support / provides assistance during EERT's response operations.
External Emergency Response Team (EERT)	<ul style="list-style-type: none"> - Solves the emergency/incident
Contractor Resources	<ul style="list-style-type: none"> - Provide and sustain the people, equipment, tools and funds necessary to ensure Subproject's quick response to emergency situations. - Maintain good communication lines with the EERT to ensure prompt help response & adequate protection, by keeping them informed of subproject progress.

35. The ERT will be led by the Contractor's senior engineer (designated ERTL) on site with a suitably trained foreman or junior engineer as deputy. Trained first-aiders and security crew will be the core members of the ERT.

36. The Contractor will ensure that ERT members are physically, technically and psychologically fit for their emergency response roles and responsibilities.

37. Prior to the mobilization of civil works, the Contractor, through its Construction Manager, ERTL, in coordination with the PSC/IA, will meet with the ultimate response institutions to discuss the overall construction process, including, but not limited to:

- i) Subproject sites;
- ii) construction time frame and phasing;
- iii) any special construction techniques and equipment that will be used; i
- iv) any hazardous materials that will be brought to and stored in the construction premise and details on their applications and handling/management system;
- v) the Contractor's Emergency Management Plan
- vi) names and contact details of the ERT members

38. The objective of this meeting is to provide the ultimate response institutions the context for:

- i) their comments on the adequacy of the respective Emergency Management Plans
- ii) their own assessment of what types, likely magnitude and likely incidence rate of potential hazards are anticipated
- iii) the arrangements for coordination and collaboration.

39. To ensure effective emergency response, prior to mobilization of civil works, the Contractor will:

- i) set up the ERT;
- ii) set up all support equipment and facilities in working condition
- iii) made arrangements with the EERT;
- iv) conducted proper training of ERT members, and encouraged and trained volunteers from the work force;
- v) conduct orientation to all construction workers on the emergency response procedures and facilities, particularly evacuation procedures, evacuation routes, evacuation assembly points, and self-first response, among others; and
- vi) conduct drills for different possible situations.

40. To sustain effective emergency response throughout subproject implementation an adequate budget shall be provided to sustain the capabilities and efficiency of the emergency response mechanism, the emergency response equipment, tools, facilities and supplies. Drills and reminders will take place regularly, the former at least every two months and the latter at least every month.

A. Alert Procedures

41. Means of communicating, reporting and alerting an emergency situation may be any combination of the following: (i) audible alarm (siren, bell or gong); (ii) visual alarm (blinking/rotating red light or orange safety flag); (iii) telephone (landline); (iv) mobile phone; (v) two-way radio; and (vi) public address system/loud speakers. Some rules relative to communicating/alerting will be:

- (i) Whoever detects an emergency situation first shall immediately :
 - call the attention of other people in the emergency site,
 - sound the nearest alarm, and/or
 - report/communicate the emergency situation to the ERT.

- (ii) Only the ERTL and, if ERTL is not available, the Deputy ERTL are authorized to communicate with the EERT. Exceptional cases to this rule may be necessary and should be defined in the Emergency Management Plans.
- (iii) When communicating/alerting an emergency to the EERT, it is important to provide them with at least: (i) the type of emergency situation; (ii) correct location of the emergency; (iii) estimated magnitude of the situation; (iv) estimated persons harmed; (v) time it happened; (vi) in case of a spill, which hazardous substance spilled; and (vii) in case of fire and explosion, what caused it. Such details would allow the EERT to prepare for the appropriate response actions.

For an effective reporting/alerting of an emergency situation:

- (i) The names and contact details of the relevant persons and institutions should be readily available in, or near to, all forms of communication equipment, and strategically posted (at legible size) in all Subproject sites and vehicles:
 - Most relevant construction/operations staffs namely, the ERTL, Deputy ERTL, first-aiders, supervising engineers, foremen
 - EERT institutions/organizations
 - Concerned village authority/ies
 - PIU Office, SS
- (ii) All subproject sites should have good access to any combination of audible and visual alarms, landline phones, mobile phones and two-way radio communication at all times.
- (iii) Contractor's construction vehicles should also be equipped with the appropriate communication facilities.

B. Emergency Response Situations

45. The following tables suggest general procedures that will be refined in the final EMP during detailed design, and described in more detail in the Emergency Management Plans of the Contractor.

Table 10: Evacuation procedure

Procedure	Remarks
<ul style="list-style-type: none"> • Move out as quickly as possible as a group, but avoid panic. 	<ul style="list-style-type: none"> • All workers/staff, sub-contractors, site visitors to move out, guided by the ERT.
<ul style="list-style-type: none"> • Evacuate through the directed evacuation route. 	<ul style="list-style-type: none"> • The safe evacuation shall have been determined fast by the ERTL/Deputy ERTL & immediately communicated to ERT members.
<ul style="list-style-type: none"> • Keep moving until everyone is safely away from the emergency site and its influence area. 	<ul style="list-style-type: none"> • A restricted area must be established outside the emergency site, all to stay beyond the restricted area.
<ul style="list-style-type: none"> • Once outside, conduct head counts. 	<ul style="list-style-type: none"> • Foremen to do head counts of their subgroups; ERTL/Deputy ERTL of the ERT.
<ul style="list-style-type: none"> • Report missing persons to EERT immediately. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL to communicate with the EERT.
<ul style="list-style-type: none"> • Assist the injured in evacuation & hand them over to the ERT first-aiders or EERT medical group 	<ul style="list-style-type: none"> • ERT to manage injured persons to ensure proper handling.
<ul style="list-style-type: none"> • If injury warrants special care, DO NOT MOVE them, unless necessary & instructed/directed by the EERT. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL communicates with EERT to get instructions/directions in handling the injured.

Table 11: Response procedure during medical emergency

Procedure	Remarks
<ul style="list-style-type: none"> Administer First Aid regardless of severity immediately. 	<ul style="list-style-type: none"> Fundamentals when giving First Aid: <ul style="list-style-type: none"> Safety first of both the rescuer and the victim. Do not move an injured person unless: <ul style="list-style-type: none"> victim is exposed to more danger when left where they are, e.g., during fire, chemical spill it would be impossible for EERT to aid victims in their locations, e.g., under a collapsed structure instructed or directed by the EERT. First Aid to be conducted only by a person who has been properly trained in giving First Aid.
<ul style="list-style-type: none"> Call the EERT emergency medical services &/or nearest hospital. 	<ul style="list-style-type: none"> ERTL/Deputy ERTL or authorized on-site emergency communicator
<ul style="list-style-type: none"> Facilitate leading the EERT to the emergency site. 	<ul style="list-style-type: none"> ERTL/Deputy ERTL to instruct: <ul style="list-style-type: none"> an ERT member on-site to meet EERT in access road/strategic location. He/she shall hold orange safety flag to get their attention & lead them to site. Other ERT members to clear access road for smooth passage of the EERT.
<ul style="list-style-type: none"> If applicable, vacate site & influence area at once, restrict site, suspend work until further notice. 	<ul style="list-style-type: none"> Follow evacuation procedure.

Table 12: Response procedure in case of fire

Procedure	Remarks
<ul style="list-style-type: none"> Alert a fire situation. 	<ul style="list-style-type: none"> Whoever detects the fire shall immediately: <ul style="list-style-type: none"> call the attention of other people in the site, sound the nearest alarm, and/or Foreman or any ERT member among the construction sub-group contacts the fire department (in this case it should be agreed on that it is alright for any ERT member in the sub-group to alert the fire department) report/communicate the emergency situation to the ERTL/Deputy ERTL.
<ul style="list-style-type: none"> Stop all activities/operations and evacuate. 	<ul style="list-style-type: none"> All (non-ERT) workers/staff sub-contractors, site visitors and concerned public to move out to safe grounds following the evacuation procedure.
<ul style="list-style-type: none"> Activate ERT to contain fire/control fire from spreading. 	<ul style="list-style-type: none"> Guided by the training they undertook, ERT members assigned to mitigate the fire shall assess their own safety situation first before attempting to control fire spread.
<ul style="list-style-type: none"> Call the nearest fire & police stations &, if applicable, emergency medical services. 	<ul style="list-style-type: none"> When alerting the EERT, ERTL will give the location, cause of fire, estimated fire alarm rating, any injuries.
<ul style="list-style-type: none"> Facilitate leading the EERT to the emergency site. 	<ul style="list-style-type: none"> ERTL/Deputy ERTL to instruct: <ul style="list-style-type: none"> an ERT member to meet the EERT in the access road or strategic location and lead

Procedure	Remarks
	<p>them to the site. He/she shall hold the orange safety flag to get their attention and lead them to the site.</p> <ul style="list-style-type: none"> - some ERT members to stop traffic in, & clear, the access road to facilitate passage of the EERT.
<ul style="list-style-type: none"> • ERT to vacate the site as soon as their safety is assessed as in danger. 	<ul style="list-style-type: none"> • Follow appropriate evacuation procedure.

IX. INSTITUTIONAL CAPACITY REVIEW AND NEEDS

46. Currently there is little experience and capacity for environmental assessment and management amongst national counterparts responsible for the implementation of the EMP, i.e., the DPWT/PMU in Kampot province. No dedicated environmental staff exist in the DPWT and thus the PIU. The PMIS with assistance from the safeguards specialists of the subproject will develop and deliver training courses to the PIU/PMU staff responsible for the implementation of the subproject. The purpose of the course(s) is to strengthen the ability of the PIU/PMU to oversee implementation of the EMP by construction contractors, and the EMC. The safeguards specialists, who will be full-time environmental member of the PIU, as well as the EO of the contractor, should attend training courses as required. Costs for training should be included with costs for implementation of the EMP.

47. Training on the implementation of an EMP should address two thematic areas. The first area should be principles environmental management focused on the potential impacts of subproject activities on the natural and social environment. The second area should be environmental safeguard requirements of the ADB and Government, with specific reference to the EMP.

ANNEX 1: INDICATIVE TORS FOR ENVIRONMENTAL SPECIALISTS OF PMIS

International Environmental Specialist. With assistance from the national environmental specialist the international consultant will be responsible for updating the subproject EMP at detailed design, and assisting the PIU with overall environmental management of the implementation of the subproject in Kampot. The consultant will: (i) update environmental management plan (EMP) for the subproject in Kampot to ensure that EMP addresses the detailed designs and engineering of the subproject. Updates to EMP include mitigation and monitoring plans, budget, and capacity development needs of executing agency (EA and IA (DPWT)); (ii) with national consultant design comprehensive training plan for safeguards officer/PIU and on principles of EIA, and the purpose, content, and roles and responsibilities for implementation of updated EMPs highlighting environmental issues of subprojects; (iii) ensure that all relevant safeguards of the EMPs are adequately addressed in the bidding documents (instruction to bidders), and in the evaluation criteria for awarding contracts; (iv) Coordinate and work with the PIU to ensure that contractors finalize their respective site-specific CEMPs based on the updated EMP and the actual site conditions; (v) oversee the implementation of all safeguards of the EMP relating to construction phase activities including handling of construction spoil and waste, water and air quality protection, public nuisance impacts (noise, dust, traffic, blocked access, workers, and camps), and public safety; (vi) Coordinate with the DPWT to finalize the groundwater monitoring program and landfill closure program for the new and old landfills; (vii) coordinate with the DPWT on all relevant environmental regulatory compliance issues (e.g. noise and dust from construction sites, sanitation in workers campsite etc); (viii) prepare ToR(s) for survey, detection, and removal of unexploded ordnance (UXO) at all civil works sites. Ensure that EA and/or PIU consult Government authorities to assist with TOR development and implementation; (ix) with PIU, prepare TORs for the follow-up interviews and consultations with the same affected stakeholder and local residents contacted during the PPTA on issues and concerns arising during project construction. Of particular concern is upgrades to access roads; (x) prepare TOR(s) for external national environment monitoring consultant (EMC) for conducting water and air quality sampling, and laboratory analyses for the monitoring plans for the provincial EMPs; (xi) coordinate with DPWT to address vehicle traffic issues; (xii) advise PIU on environment-related concerns arising during subproject construction, and recommend corrective measures; (xiii) with DPWT ensure dissemination to stakeholders the results of environment quality monitoring and implementation of safeguards, especially among households or small businesses near the civil construction works areas; (xiv) assist EA and PIU prepare a table of contents for regular reports PIU must submit to the EA on implementation of EMPs, environmental issues, and corrective actions; (xv) assist PIU prepare simple report template for construction contractors to report monthly on mitigation activities, and environmental issues that occur during construction phase; and (xvi) prepare a quarterly status report on implementation of EMPs, environmental issues, and public safety protection to be submitted through the IA and EA to the DPWT and ADB. The consultant should have an advanced university degree in the environmental sciences and at least 7 years experience implementing and managing environmental assessment of infrastructure projects in southeast Asia countries (preferably Cambodia) including: a) understanding of ADB and national environmental safeguard requirements; b) experience working with and supervising the activities of provincial and national environmental management agencies with environmental safeguards; and c) designing and delivering training and capacity development programs to provincial environment, subproject implementing units.

National Environmental Specialist. Provide assistance to the international environmental specialist including acquisition of information new information to update the subproject EMP at detailed design, and work with the PIU with overall environmental management of the implementation of the subproject in Kampot. The national consultant will assist with: (i) updating environmental management plan (EMP) for subproject in Kampot to ensure that EMP addresses the detailed designs and engineering of subproject; (ii) deliver initial training to DPWT/PMU on the purpose, content, and roles and responsibilities for implementation of updated EMP; (iii) ensure relevant safeguards of the EMP are addressed in the bidding documents in paccurate local language and in evaluation criteria for awarding contracts; (iv) help PIU to ensure that contractors prepare their respective site-specific plans based on the updated EMP and the actual site conditions; (v) help the international consultant oversee the implementation of all safeguards of the EMP relating to construction phase activities including handling of construction spoil and waste, water and air quality protection, public nuisance impacts (noise, dust, traffic, blocked access, workers, and camps), and public safety; (vi) assist coordination with the DPWT on all relevant environmental regulatory compliance issues (e.g. noise and dust from construction sites, sanitation in workers campsite etc); (vii) with PIU prepare TORs for the follow-up interviews and consultations with the same affected stakeholder and local residents contacted during the PPTA on issues and concerns arising during project construction. Of particular concern is upgrades to access roads; (viii) assist DPWT to address vehicle traffic issues; (ix) with the international consultant advise the PIU on environment-related concerns arising during subproject construction, and recommend corrective measures; (x) with PIU ensure dissemination to stakeholders the results of environment quality monitoring and implementation of safeguards, especially among households or small businesses near the civil construction works areas; (xi) assist with all reporting for the EMP. The consultant should have a university degree in the environmental sciences and at least 5 years with environmental assessment of infrastructure projects in Cambodia including: a) understanding of ADB and national environmental safeguard requirements; b) experience working with international consultants; and c) delivering training and capacity development programs to subproject implementing units.

ANNEX 2: ENVIRONMENTAL STANDARDS FOR CAMBODIA

From Government Sub-decree on Water Pollution Control (1999)
<http://www.wepa-db.net/policies/law/cambodia/02.htm>

Table 1. Effluent standard for pollution sources discharging wastewater to public water areas or sewer access

No	Parameters	Unit	Allowable limits for pollutant substance discharging to	
			Protected public water area	Public water area and sewer
1	Temperature	°C	< 45	< 45
2	pH		6 – 9	5 - 9
3	BOD5 (5 days at 200 C)	mg/l	< 30	< 80
4	COD	mg/l	< 50	< 100
5	Total Suspended Solids	mg/l	< 50	< 80
6	Total Dissolved Solids	mg/l	< 1000	< 2000
7	Grease and Oil	mg/l	< 5.0	< 15
8	Detergents	mg/l	< 5.0	< 15
9	Phenols	mg/l	< 0.1	< 1.2
10	Nitrate (NO3)	mg/l	< 10	< 20
11	Chlorine (free)	mg/l	< 1.0	< 2.0
12	Chloride (ion)	mg/l	< 500	< 700
13	Sulphate (as SO4)	mg/l	< 300	< 500
14	Sulphide (as Sulphur)	mg/l	< 0.2	< 1.0
15	Phosphate (PO4)	mg/l	< 3.0	< 6.0
16	Cyanide (CN)	mg/l	< 0.2	< 1.5
17	Barium (Ba)	mg/l	< 4.0	< 7.0
18	Arsenic (As)	mg/l	< 0.10	< 1.0
19	Tin (Sn)	mg/l	< 2.0	< 8.0
20	Iron (Fe)	mg/l	< 1.0	< 20
21	Boron (B)	mg/l	< 1.0	< 5.0
22	Manganese (Mn)	mg/l	< 1.0	< 5.0
23	Cadmium (Cd)	mg/l	< 0.1	< 0.5
24	Chromium (Cr)+3	mg/l	< 0.2	< 1.0
25	Chromium (Cr)+6	mg/l	< 0.05	< 0.5
26	Copper (Cu)	mg/l	< 0.2	< 1.0
27	Lead (Pb)	mg/l	< 0.1	< 1.0
28	Mercury (Hg)	mg/l	< 0.002	< 0.05
29	Nickel (Ni)	mg/l	< 0.2	< 1.0
30	Selenium (Se)	mg/l	< 0.05	< 0.5
31	Silver (Ag)	mg/l	< 0.1	< 0.5
32	Zinc (Zn)	mg/l	< 1.0	< 3.0
33	Molybdenum (Mo)	mg/l	< 0.1	< 1.0
34	Ammonia (NH3)	mg/l	< 5.0	< 7.0
35	DO	mg/l	> 2.0	> 1.0

36	Polychlorinated Biphenyl	mg/l	< 0.003	< 0.003
37	Calcium	mg/l	< 150	< 200
38	Magnesium	mg/l	< 150	< 200
39	Carbon tetrachloride	mg/l	< 3	< 3
40	Hexachloro benzene	mg/l	< 2	< 2
41	DTT	mg/l	< 1.3	< 1.3
42	Endrin	mg/l	< 0.01	< 0.01
43	Dieldrin	mg/l	< 0.01	< 0.01
44	Aldrin	mg/l	< 0.01	< 0.01
45	Isodrin	mg/l	< 0.01	< 0.01
46	Perchloro ethylene	mg/l	< 2.5	< 2.5
47	Hexachloro butadiene	mg/l	< 3	< 3
48	Chloroform	mg/l	< 1	< 1
49	1,2 Dichloro ethylene	mg/l	< 2.5	< 2.5
50	Trichloro ethylene	mg/l	< 1	< 1
51	Trichloro benzene	mg/l	< 2	< 2
52	Hexachloro cyclohexene	mg/l	< 2	< 2

Remark: The Ministry of Environment and the Ministry of Agriculture, Forestry and Fishery shall collaborate to set up the standard of pesticides which discharged from pollution sources.

Table 2: Water Quality Standard in public water areas for bio-diversity conservation

I. For River			
No	Parameter	Unit	Standard Value
1	pH	mg/l	6.5 – 8.5
2	BOD5	mg/l	1 – 10
3	Suspended Solid	mg/l	25 – 100
4	Dissolved Oxygen	mg/l	2.0 - 7.5
5	Coliform	MPN/100ml	< 5000
II. Lakes and Reservoirs			
No	Parameter	Unit	Standard Value
1	pH	mg/l	6.5 – 8.5
2	COD	mg/l	1 – 8
3	Suspended Solid	mg/l	1 – 15
4	Dissolved Oxygen	mg/l	2.0 - 7.5
5	Coliform	MPN/100ml	< 1000
6	Total Nitrogen	mg/l	– 0.6
7	Total Phosphorus	mg/l	0.005 – 0.05
III. Coastal Water			
No	Parameter	Unit	Standard Value
1	pH	mg/l	7.0 – 8.3
2	COD	mg/l	2 – 8
3	Dissolved Oxygen	mg/l	2 - 7.5
4	Coliform	MPN/100ml	< 1000

5	Oil content	mg/l	0
6	Total Nitrogen	mg/l	- 1.0
7	Total Phosphorus	mg/l	0.02 – 0.09

Table 3. Water Quality Standard in public water areas for public health protection

No	Parameter	Unit	Standard Value
1	Carbon tetrachloride	µg/l	< 12
2	Hexachloro-benzene	µg/l	< 0.03
3	DDT	µg/l	< 10
4	Endrin	µg/l	< 0.01
5	Dieldrin	µg/l	< 0.01
6	Aldrin	µg/l	< 0.005
7	Isodrin	µg/l	< 0.005
8	Perchloroethylene	µg/l	< 10
9	Hexachlorobutadiene	µg/l	< 0.1
10	Chloroform	µg/l	< 12
11	1,2 Trichloroethylene	µg/l	< 10
12	Trichloroethylene	µg/l	< 10
13	Trichlorobenzene	µg/l	< 0.4
14	Hexachloroethylene	µg/l	< 0.05
15	Benzene	µg/l	< 10
16	Tetrachloroethylene	µg/l	< 10
17	Cadmium	µg/l	< 1
18	Total mercury	µg/l	< 0.5
19	Organic mercury	µg/l	0
20	Lead	µg/l	< 10
21	Chromium, valent 6	µg/l	< 50
22	Arsenic	µg/l	< 10
23	Selenium	µg/l	< 10
24	Polychlorobiohenyl	µg/l	0
25	Cyanide	µg/l	< 0.005

ANNEX 3: MONITORING REPORT TEMPLATE FOR PROJECT IMPLEMENTATION UNIT

Safeguards Monitoring Report

This report is to be completed by the PIU with assistance from the PMIS and PMU. The report forms part of the regular reporting of PIU to PMU and ultimately to the EA and ADB.

1. Introduction and Project Overview

Project Number and Title:		
Safeguards Category	Environment	B
	Indigenous Peoples	C
	Involuntary Resettlement	B
Reporting period:		
Last report date:		
Key sub-project activities since last report:	<p><i>This section can include, among others, the following:</i></p> <ul style="list-style-type: none"> • <i>Activities of PIU/PMU</i> • <i>Progress of work (% physical completion)</i> • <i>Changes of surrounding environment</i> • <i>Status of permits / consents</i> 	
Report prepared by:		

2. Environmental Performance Monitoring

a. Summary of Compliance with EMAP Requirements (Environmental Performance)

Monitoring Requirements	Compliance Status (Yes, No, Partial)	Comment or Reasons for Non-Compliance	Issues for Further Action
<i>Use tabled performance monitoring indicators of EMP</i>			

b. Issues for Further Action

Issue	Required Action	Responsibility and Timing	Resolution
Old Issues from Previous Reports			
<i>List of monitoring or mitigation measures or activities not completed</i>			

<i>(last column of previous table)</i>			
New Issues from This Report			

c. Other activities

- Other issues not covered by mitigation or monitoring plans of EMP
- Any additional environmental monitoring required (e.g., air quality, water sampling)

3. Occupational, Health and Safety (OHS) Performance Monitoring

a. OHS for worker

Issue	Required Action	Responsibility and Timing	Resolution
Old Issues from Previous Reports			
New Issues from This Report			

b. Public Safety

Issue	Required Action	Responsibility and Timing	Resolution
Old Issues from Previous Reports			

New Issues from This Report			

4. Information Disclosure and Socialization including Capability Building

Prepare brief summary of the information below where applicable

- Field visits conducted (sites visited, dates, persons met)
- Public consultations and meetings conducted (date; time; location; agenda; number of participants disaggregated by sex and ethnic group, not including project staff; Issues raised by participants and how these were addressed by the project team)
- Training conducted (nature of training, number of participants disaggregated by gender and ethnicity, date, location, etc.)
- Press/Media releases
- Material development/production (e.g., brochure, leaflet, posters)

5. Grievance Redress Mechanism

Summary:

- Number of new grievances, if any, since last monitoring period: _____
- Number of grievances resolved: _____
- Number of outstanding grievances: _____

Type of Grievance	Details (Date, person, address, contact details, etc.)	Required Action, Responsibility and Timing	Resolution
Old Issues from Previous Reports			
New Issues from This Report			

6. Conclusion

- Important results from the implementation of mitigation and monitoring of EMP
- Recommendations to improve EMP implementation

7. Attachments

- Consents / permits
- Monitoring data (water quality, air quality, etc.)
- Photographs
- Maps

Environmental Management Plan

June 2015

Kingdom of Cambodia: Second Greater Mekong
Subregion Corridor Towns Development Project,
PPTA 8425

Sihanoukville Subproject

This environmental management plan is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature.

CURRENCY EQUIVALENTS

(as of 26 March 2015)

Currency Unit	–	Riel R
R1.00	=	\$0.00025
\$1.00	=	R3,941

ABBREVIATIONS

ADB	-	Asian Development Bank
CEMP	-	Contractor Environmental Management Plan
DAFF	-	Department of Agriculture, Forestry and Fisheries
DOE	-	Department of Environment
DPWT	-	Department of Public Works and Transport
DOT	-	Department of Tourism
DOWRAM	-	Department of Water Resources and Meteorology
EA	-	Executing Agency
ECA	-	Environmental Compliance Audit
EIA	-	Environmental Impact Assessment
EMC	-	Environmental Monitoring Consultant
EMP	-	Environment Management Plan
EO	-	Environmental Officer
ERT	-	Emergency Response Team
EERT	-	External Emergency Response Team
GMS	-	Greater Mekong Subregion
Government	-	Government Of Cambodia
IA	-	Project Implementation Agency
IEE	-	Initial Environment Examination
IEIA	-	Initial Environmental Impact Assessment
PIU	-	Project Implementation Unit
MAFF	-	Ministry Of Agriculture, Forestry And Fisheries
MOE	-	Ministry Of Environment
MIME	-	Ministry Of Industry, Mines And Energy
MPWT	-	Ministry Of Public Works And Transport
MOT	-	Ministry Of Tourism
MOWRAM	-	Ministry Of Water Resources And Meteorology
PA	-	Project Administration Manual
PMIS	-	Project Management Implementation Support
PSC	-	Project Steering Committee
PPTA	-	Project Preparatory Technical Assistance
RP	-	Resettlement Plan
GRC	-	Royal Government Of Cambodia
SPS	-	ADB's Safeguard Policy Statement (2009)
SO	-	Safeguards Officer

WEIGHTS AND MEASURES

km	-	kilometer
kg	-	kilogram
ha	-	hectare

In this report, "\$" refers to US.

TABLE OF CONTENTS

I.	INTRODUCTION	1
	A. Sihanoukville Subproject	1
II.	INSTITUTIONAL ARRANGEMENTS & RESPONSIBILITIES	1
	A. Worker and Community Health and Safety	4
	B. Regulatory Framework for Sihanoukville Subproject Components	5
III.	SUMMARY OF POTENTIAL IMPACTS	5
	A. Public Consultation	6
	1. Follow-up Consultation	6
IV.	MITIGATION PLAN	6
V.	MONITORING PLAN	16
	A. Environmental Standards for Subproject Components	16
	B. Performance Monitoring	16
VI.	REPORTING	16
VII.	ESTIMATED COST OF EMP	20
VIII.	EMERGENCY RESPONSE PLAN	21
	A. Alert Procedures	22
	B. Emergency Response Situations	23
IX.	INSTITUTIONAL CAPACITY REVIEW AND NEEDS	25
	ANNEX 1: INDICATIVE TORS FOR ENVIRONMENTAL SPECIALISTS OF PMIS	26
	ANNEX 2: ENVIRONMENTAL STANDARDS FOR CAMBODIA	28
	ANNEX 3: MONITORING REPORT TEMPLATE FOR PROJECT IMPLEMENTATION UNIT	31
	Table 1: Summary of subproject components of Sihanoukville.....	1
	Table 2: Summary of environmental due diligence during project implementation.....	3
	Table 3: Regulations and guidelines applicable to subproject.	5
	Table 4: Summary of potential environmental impacts and mitigations of subproject	5
	Table 5: Environmental impact mitigation plan	7
	Table 6: Environmental monitoring plan	17
	Table 7: Performance monitoring indicators for Sihanoukville subproject.....	19
	Table 8: Estimated costs for environmental monitoring plan of EMP	20
	Table 9: Roles and responsibilities in emergency incident response	21
	Table 10: Evacuation procedure	23
	Table 11: Response procedure during medical emergency.....	23
	Table 12: Response procedure in case of fire	24

I. INTRODUCTION

1. The environmental management plan (EMP) for the subproject in Sihanoukville, Preah Sihanouk province provided herein is one of two EMPs that have been prepared for the subprojects of the Second Greater Mekong Subregion Corridor Towns Development Project (the project) in Cambodia. The other EMP addresses the subproject in neighboring Kampot, Kampot province. A single Initial Environmental Examination (IEE) of both subprojects was prepared under separate cover. The separate EMPs are comprehensive and are developed as stand-alone management tools that are supported by the parent IEE.

A. Sihanoukville Subproject

2. The subproject in Sihanoukville consists of three components summarized in Table 1.

Table 1: Summary of subproject components of Sihanoukville

Component	General Specifications
Solid Waste Management	<ul style="list-style-type: none">• Renovated existing landfill• Improved solid waste management system;• Improved waste sorting process at landfill
Urban Drainage	<ul style="list-style-type: none">• New separated stormwater collection network

II. INSTITUTIONAL ARRANGEMENTS & RESPONSIBILITIES

3. At the feasibility stage the management framework¹ for the implementation of the environmental management plan for the subproject is summarized as follows. The Ministry of Public Works and Transport (MPWT) which is the executing agency (EA) for the project will take overall responsibility for successful implementation of the EMP. The EA will establish a Phnom Penh-based Project Steering Committee (PSC). The General Department of Public Works (GDPW) will be the project implementation agency (IA) in which a project management unit (PMU) will be assigned for the entire subproject. The IA/PMU will implement the EMP with an internally assigned Safeguards Officer (SO). The PMU/SO will lead the implementation of the EMP in conjunction with the Environmental Officer(s) (EO) of the construction contractor(s).

4. The EA/PSC will provide operational guidance to the IA/PMU for implementation of the EMP and will liaise with the ADB on safeguard reporting and issues. The SO of the PMU/IA will oversee the work of the EO of the contractor(s) on the implementation of the CEMP² for particular construction packages.

5. External support for the implementation of the EMP will be provided by the International and National Environment Specialists (ES) of the Project Management Implementation Support (PMIS) who will have a budget for an external Environmental Monitoring Consultant (EMC). The EMC will conduct any required field sampling, and laboratory analyses of field samples (e.g., water quality, air quality) that cannot be performed by the contractor or PIU. Provided below is a summary of responsibilities for implementation of the EMP.

¹ Adapted from Interim Report 12/14.

² Contractor Environmental Management Plan prepared by contractor as part of bid documents based on updated EMP

6. The responsibilities of the EA as supported by PSC include:
 - Provide coordination for environmental and social safeguards and monitoring;
 - Liaise with ADB on the implementation of the EMP; and
 - Coordinate resolution with IA, and ADB if necessary with issues arising from the implementation of EMP.
7. The responsibilities of the Safeguards Officer (SO) of the PIU/PMU include:
 - Assist PMIS with updating the EMP to meet final detailed subproject designs;
 - Notify MPWT to verify that Government approvals of project are met, and that the EMP is compliant with requirements of Royal Government of Cambodia (RGC) sub-decree on EIA, No 72 ANRK.BK, issued by the Ministry of Environment (MOE, 1999);
 - Assist the PMIS with inclusion of CEMP requirements in bidding documents, including bid evaluations, based on the updated EMP;
 - Undertake day to day management of EMP implementation activities;
 - Work with EMC on implementation of monitoring plan of EMP;
 - Ensuring compliance with loan covenants and assurances in respect of all subprojects, including EMPs (as well as the GAP and resettlement plans);
 - Lead follow-up meetings with all affected stakeholders;
 - Prepare and submit quarterly reports on EMP implementation to the IA/EA;
 - Oversee implementation of the CEMP by contractor;
 - Coordinate with ES of PMIS for EMP implementation;
 - Undertake regular construction site inspections to ensure contractor implements the CEMP properly; and
 - Ensure the contractor's EO submits monthly reports on construction mitigations and monitoring.
8. The responsibilities of the Environmental Specialists of the PMIS are detailed in the Terms of Reference for the two positions in Annex 1. Their key responsibilities for the EMP are listed below:
 - Update the EMP to meet final detailed design requirements of subprojects;
 - Provide technical direction and support to SO/PMU for implementation of the EMP;
 - Oversee the design and delivery of capacity development and training of PMU staff and the contractor's EO ;
 - Provide advice and support to the EMC with their monitoring activities;
 - Review all reports prepared by the PIU and EMC for EA/PSC and ADB; and
 - Review and inspect the location of any possible contaminated sites near subprojects.
9. The responsibilities of Environmental Officer (EO) of Contractor include:
 - Implement the CEMP during the construction phase of subproject; and
 - Prepare and submit monthly reports on mitigation and monitoring activities of CEMP and any environmental issues at construction sites.
10. The responsibilities of Environmental Monitoring Consultant (EMC) include:

- Implement the environmental sampling required for monitoring plan of EMP that cannot be conducted by the contractor and PIU/PMU.
- Perform required laboratory analyses for the monitoring program detailed in EMP; and
- Prepare and submit quarterly reports to the PMIS and PIU on monitoring activities.

11. The implementation of the EMP as part of the overall environmental due diligence (DD) of the subproject is conducted alongside the separate parallel DD of the government. Table 2 reproduces the summary table of environmental due diligence from the IEE. Table 2 shows that the ADB IEE and loan is approved well before the government EIA/IEIA is initiated, and that the EA must approve the ADB IEE and EMP by formal letter. The ADB IEE/EMP is not contingent on compliance with any specific government regulation.

Table 2. Summary of environmental due diligence during project implementation

Design and Implementation	Environmental DD and Approvals			Milestones & Notes
	ADB / PPTA	Cambodia	PMIS / Contractor	
Feasibility design				
Initial stakeholder disclosure & consultation	PPTA	EA assists		
Draft IEEs and EMPs	PPTA			Draft IEEs & EMPs completed
Finalize IEEs and EMPs	ADB review & approves IEE/EMPs			ADB approved IEE/ EMPs as per SPS (2009).
		EA reviews and approves IEE/EMPs		EA approved IEE/ EMPs with formal letter only. Compliance with specific RGC / EA regulations not required
Loan documents (PAM/RRP)	Document preparation, approval by ADB	Review & approval of PAM		Loan approval
Detailed engineering design				
Continued stakeholder disclosure & consultation		IA/PIU lead	ES support to PMIS	As per PCP (2012) ³ stakeholder disclosure and consultations continue throughout construction phase coincident with initiation of GRM.
Update EMPs		Support to ES	Lead by ES	Approval of updated EMP by EA and ADB
Initiation of Cambodia environmental DD		EA leads with oversight from MOE		DOE approved CAM IEE or IEIA follows independently

³ ADB Public Communication Policy (2012)

Design and Implementation	Environmental DD and Approvals			Milestones & Notes
	ADB / PPTA	Cambodia	PMIS / Contractor	
Tendering / contract award				
EMPs included in tender documents		Lead by EA/IU	Support by ES	
Tenders let and bids prepared		Lead by EA	Contractor drafts CEMP	CEMPs prepared and included in contractor bids
Construction packages	Input from ADB		CEMPs reviewed by ES/PMIS	Construction package awards
Construction & supervision				
Implementation of mitigation and monitoring plans		Support from IU/PIU	By contractor with support from ES	CEMP implemented by contractor, other aspects of EMP overseen by ES
Continued stakeholder disclosure and consultation		IA/PIU lead	Support from ES	As part of GRM
Monitoring reporting	To ADB	IA/PIU lead preparation of regular reports to ADB	Support from ES	Reports provide input for review missions

12. The Department of Environment (DOE) is the provincial agency which oversees environmental management of Sihanoukville. The DOE with district staff provide direction and support for environmental protection-related matters including application of the Law on Environmental Protection and Natural Resources Management, enacted by National Assembly, 1996, promulgated by Preah Reach Kram/NS/RKM-1296/36; and environmental standards

13. The ADB provides guidance to EA/PSC with any issues related to EMP and reviews quarterly reports on EMP activities compiled and submitted by the EA which are disclosed on ADB website pursuant to ADB Policy on Public Communication (2011).

A. Worker and Community Health and Safety

14. In 2003 the International Labour Organization (ILO) created the New Global Strategy for Occupational Safety and Health (OSH). Based on the OSH⁴, the Ministry of Labour and Vocational Training (MLVT) through the Department of Occupational Safety & Health is developing the Occupational Safety and Health Master Plan (OSHM; 2009-2013) of Cambodia.

15. The emerging OSHM, *inter alia*, addresses worker and public safety in the construction and operation of small-medium enterprises and notably rural roads. The EA/PSC as supported by the IUs must obtain and implement the directives of the OSH Master Plan. The pertinent associated law and directives is the Labour Law of Cambodia (1997) with specific reference to chapter VIII governing health and welfare of workers and the public.

⁴ ILO. 2009. Asean-Oshnet, Occupational Safety and Health Practices.

16. To supplement the OSHM the IFC/World Bank Environment, Health, and Safety Guidelines (2007) should also be consulted the IFC EHS guidelines currently provide the international standard for worker and public safety.

17. ADB assists the PSC with timely guidance at each stage of project implementation following agreed implementation arrangements and reviews all documents that require ADB approval including environmental safeguards.

B. Regulatory Framework for Sihanoukville Subproject Components

18. Regulations and guidelines that apply to the construction of the new WWTP, and renovated landfill in Sihanoukville are summarized in Table 3. The current environmental standards for Cambodia are provided in Annex 2. See the IEE for complete the legal and regulatory framework for environmental management in Sihanoukville province.

Table 3: Regulations and guidelines applicable to subproject.

Solid Waste Management
<ul style="list-style-type: none"> • Law on Environmental Protection and Natural Resources Management, enacted by National Assembly, 1996, promulgated by Preah Reach Kram/NS/RKM-1296/36; <ul style="list-style-type: none"> ○ Sub-decree on Water Pollution Control (1999): <ul style="list-style-type: none"> - Annex 4: Water quality standards for public water & biodiversity; ○ Sub-decree on Solid Waste Management, No 36 ANRK/BK (1999): • Directive for Managing Health Wastes in the Kingdom of Cambodia (MOH, 2008).

III. SUMMARY OF POTENTIAL IMPACTS

19. The potential impacts of the Sihanoukville subproject from the IEE are summarized in Table 4. Potential impacts concern the civil works during the construction phase of the subproject. The short-term disturbances of the construction and civil works activities will be noise, dust, reduced access, increased traffic and risk of traffic accidents, worker and public safety, soil erosion, and solid and liquid waste can be managed and mitigated.

Table 4: Summary of potential environmental impacts and mitigations of subproject

Pre-construction Phase
<ul style="list-style-type: none"> • No resettlement or land compensation
Construction Phase
<p><u>Upgraded drainage, and renovated landfill.</u></p> <ul style="list-style-type: none"> • Disturbances & impacts from civil works such as reduced and/or blocked public access to areas, disrupted business and recreation, noise, dust caused by increased truck traffic and heavy equipment use, soil and surface water pollution caused by equipment operation and

maintenance, public and worker accidents, increased traffic congestion & traffic accidents, land erosion, localized drainage and flooding problems, solid waste and domestic pollution from worker camps, and communicable disease and community problems caused by migrant workers.

Upgraded Drainage

- Street disruptions caused trench method of drainage upgrades minimized by starting and completing finite sections of drains.
- Disturbances to public area from enhancements minimized with disclosure of construction schedules for resident and business planning

Operation Phase

Solid Waste Management

- Groundwater quality contamination from renovated landfill avoided with regular monitoring of groundwater quality with site bore wells, and from sufficient O&M to maintain landfill in good working order

Improved Drainage

- Flooding events prevented with regular cleaning and maintenance of upgraded drains.

A. Public Consultation

20. The stakeholder consultation strategy that was developed for the IEE will be continued with the start of the pre-construction phase of the subproject. The first step will be the disclosure of the draft IEE to the affected stakeholders that were consulted to obtain their review and comment.

1. Follow-up Consultation

21. As indicated in the IEE, the primary concern of the public and stakeholders of the subproject were disturbances during construction phase of the subproject components. These issues will be reviewed during follow-up consultations throughout the pre-construction, construction, and operation of the completed subproject components.

IV. MITIGATION PLAN

22. The mitigation measures of the EMP are presented in the mitigation plan for the subproject in Table 5. Following the structure of the IEE, the mitigation plan is organized by the three development phases of the subproject defined by the pre-construction; construction; and the post construction operational phase. The mitigation plan addresses the environmental issues and concerns raised at the stakeholder meetings.

23. The mitigation plan combines common construction phase impacts of the renovated existing landfill, and improved drainage for which single mitigation measures are prescribed. In this way redundant mitigation measures are not re-stated numerous times. However, impacts and required mitigations specific to a subproject component are identified. Or, common mitigations that are particularly important for a subproject component are underscored. The mitigation plan identifies potential impacts, required mitigations, responsible parties, location, timing, and indicative costs. The mitigation plan is decidedly comprehensive in order for it to be easily updated at the detailed design phase to fully address the potential impacts of the final subproject designs.

Table 5: Environmental impact mitigation plan

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
<i>Pre-Construction, Detailed Design Phase</i>								
Confirmation of no required resettlement, relocations, & compensation	No negative environmental impacts	1. Affected persons well informed well ahead of subproject implementation.	All affected persons in subproject areas	Before project implemented	See resettlement plans	See resettlement plan	EA/IA	Resettlement committees
Disclosure, & engagement of community	No community impacts	2. Initiate Information Disclosure and Grievance process of IEE	For all construction sites.	Beginning of project	Quarterly	No marginal cost ⁶	PMU	PIU
Government approvals	No negative impact	3. Notify DOE of subproject initiation to complete EA requirements, and obtain required project permits and certificates.	Entire subproject	Before construction	As required	No marginal cost	PIU/DoE	DoE
Detailed designs of subproject,	Minimize negative environmental impacts	4. Work with PMIS ⁷ to complete detailed designs of the, landfill renovations, and upgraded drainage. Ensure the following measures are included: a) identification of spill management prevention plans, and emergency response plans for all construction sites; b) no disturbance or damage to culture property and values; c) no, or minimal disruption to village water supplies along access roads, utilities, and electricity with contingency plans for unavoidable disruptions; d) no, or minimal disruption to normal pedestrian and vehicle traffic along all road segments with contingency alternate routes; e) for residential areas include specific plan to notify & provide residents and merchants of construction activities & schedule to minimize disruption to normal commercial and residential activities.	Final siting	Before construction initiated	Once with detailed designs documents	No, marginal cost	PMIS	IA/PPIU
Update EMP	Positive environmental impacts	5. Review and finalize draft TOR for required groundwater study at existing landfill site. Contact potential consultants in Phnom Penh. 6. Identify any new potential environmental impacts of	All sites	Before construction initiated	Once with detailed designs documents		PMIS	PMU/PIU

⁵ Costs will need to be updated during detailed design phase.

⁶ No marginal cost indicates that costs to implement mitigation are to be built into cost estimates of bids of contractors

⁷ PMIS is detailed design and supervision consultant.

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		<p>subproject and include in EMP.</p> <p>7. Update mitigation measures and monitoring requirements of EMP where necessary to meet detailed designs, and to protect affected environments.</p> <p>8. Submit updated EMP with new potential impacts to ADB to review.</p> <p>9. Develop individual management subplans for: a) Construction drainage; b) Erosion; c) Noise and Dust; d) Contaminated Spoil Disposal; e) Solid and Liquid Waste Disposal; f) Construction & Urban Traffic; g) Utility and Power Disruption; h) Worker and Public Safety; i) Tree and Vegetation Removal and Site Restoration; j) Construction Materials Acquisition, Transport, & Storage, and k) Cultural chance finds.</p>						
Create awareness of physical cultural resources in area	No negative environmental impact	10. Dept of Tourism to review potential locations of physical cultural resources, and explain possible PCR to contractors and PMIS	All subproject areas	Before construction begins	Once	No marginal cost	DoT	DOT/PIU
UXO survey, & removal	Injured worker or public	11. Ensure Government is consulted for UXO, and clears areas where necessary	All construction sites.	Beginning of subproject	Once	See Monitoring Plan below	PMU/PIU	Government
Obtain & activate permits and licenses	Prevent or minimize impacts	12. Contractors to comply with all statutory requirements set out by Government for use of construction equipment, and operation construction plants such as concrete batching.	For all construction sites	Beginning of construction	Once	No marginal cost	PMIS	PIU & contractors
Develop bid documents	No negative environmental impact	<p>13. Ensure updated EMP is included in contractor tender documents, and that tender documents specify requirements of CEMP must be budgeted.</p> <p>14. Specify in bid documents that contractor must have experience with implementing EMPs, or provide staff with the experience.</p>	All subproject areas	Before construction begins	Once for all tenders	No marginal cost	PMIS	PIU
Capacity development	No negative environmental impact	<p>15. Develop and schedule training plan for (PIU/SO) to be able to fully implement EMP, and to manage implementation of mitigation measures by contractors.</p> <p>16. Create awareness and training plan for contractors whom will implement mitigation measures.</p>	All subproject areas	Before construction begins	Initially, refresher later if needed	No marginal cost	PMIS	PMIS
Recruitment of workers	Spread of sexually transmitted	17. Use local workers as much as possible thereby reducing number of migrant worker	All work forces.	Throughout construction phase	Worker hiring stages	No marginal cost	PMU/PIU	Contractor's bid documents

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
	disease							
Construction Phase of Renovations to Existing Landfill, and Upgraded Drainage								
Initiate EMP & sub-plans,	Prevent or minimize impacts	18. Initiate updated EMP & CEMP including individual management sub-plans for different potential impact areas that are completed in pre-construction phase (see sub-plan guidance below).	For all construction sites	Beginning of construction	Once	No marginal cost	PMIS	PIU & contractors
Worker camps	Pollution and social problems	19. Locate worker camps away from human settlements. 20. Ensure adequate housing and waste disposal facilities including pit latrines and garbage cans. 21. A solid waste collection program must be established and implemented that maintains a clean worker camps 22. Locate separate pit latrines for male and female workers away from worker living and eating areas. 23. A clean-out or infill schedule for pit latrines must be established and implemented to ensure working latrines are available at all times. 24. Worker camps must have adequate drainage. 25. Local food should be provided to worker camps. Guns and weapons not allowed in camps. 26. Transient workers should not be allowed to interact with the local community. HIV/Aids education should be given to workers. 27. Camp areas must be restored to original condition after construction completed.	All worker camps	Throughout construction phase	Monthly	No marginal cost	PMIS/PIU	contractor
Training & capacity	Prevent of impacts through education	28. Implement training and awareness plan for PIU/SO and contractors.	PIU office, construction sites	Beginning of construction	After each event	No marginal cost	PMIS	PMIS/PIU
DBST production, and application (if used)	Air pollution, land and water contamination, and traffic & access problems,	29. Piles of aggregates at sites should be used/or removed promptly, or covered and placed in non-traffic areas 30. Stored DBST materials well away from all human activity and settlements, and cultural (e.g., schools, hospitals), and ecological receptors. Bitumen production and handling areas should be isolated. 31. Contractors must be well trained and experienced with the production, handling, and application of bitumen. 32. All spills should be cleaned immediately and handled as per hazardous waste management plan, and according to Government regulations. 33. Bitumen should only be spread on designated road beds, not on other land, near or in any surface waters,	For all construction areas.	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		<p>or near any human activities.</p> <p>34. Bitumen should not be used as a fuel.</p>						
Implement spoil management subplan	Contamination of land and surface waters from excavated spoil, and construction waste	<p>35. Uncontaminated spoil to be disposed of in Government -designated sites, which must never be in or adjacent surface waters. Designated sites must be clearly marked and identified.</p> <p>36. Spoil must not be disposed of on sloped land, near cultural property or values, ecologically important areas, or on/near any other culturally or ecologically sensitive feature.</p> <p>37. Where possible spoil should be used at other construction sites, or disposed in spent quarries or borrow pits.</p> <p>38. A record of type, estimated volume, and source of disposed spoil must be recorded.</p> <p>39. Contaminated spoil disposal must follow Government regulations including handling, transport, treatment (if necessary), and disposal.</p> <p>40. Suspected contaminated soil must be tested, and disposed of in designated sites identified as per Government regulations.</p> <p>41. Before treatment or disposal contaminated spoil must be covered with plastic and isolated from all human activity.</p>	All excavation areas	Throughout construction phase	Monthly	See Monitoring Plan for contaminated soil analyses	PMIS & PIU & DoE	contractor
Implement solid and liquid construction waste sub-plan	Contamination of land and surface waters from construction waste	<p>42. Management of general solid and liquid waste of construction will follow Government regulations, and will cover, collection, handling, transport, recycling, and disposal of waste created from construction activities and worker force.</p> <p>43. Areas of disposal of solid and liquid waste to be determined by Government.</p> <p>44. Disposed of waste should be catalogued for type, estimated weigh, and source.</p> <p>45. Construction sites should have large garbage bins.</p> <p>46. A schedule of solid and liquid waste pickup and disposal must be established and followed that ensures construction sites are as clean as possible.</p> <p>47. Solid waste should be separated and recyclables sold to buyers in community.</p> <p><u>Hazardous Waste</u></p> <p>48. Collection, storage, transport, and disposal of</p>	All construction sites and worker camps	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU & DoE	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		<p>hazardous waste such as used oils, gasoline, paint, and other toxics must follow Government regulations.</p> <p>49. Wastes should be separated (e.g., hydrocarbons, batteries, paints, organic solvents)</p> <p>50. Wastes must be stored above ground in closed, well labeled, ventilated plastic bins in good condition well away from construction activity areas, all surface water, water supplies, and cultural and ecological sensitive receptors.</p> <p>51. All spills must be cleaned up completely with all contaminated soil removed and handled with by contaminated spoil sub-plan.</p>						
Implement noise and dust sub-plan	Dust Noise	<p>52. Regularly apply wetting agents to exposed soil and construction roads.</p> <p>53. Cover or keep moist all stockpiles of construction aggregates, and all truck loads of aggregates.</p> <p>54. Minimize time that excavations and exposed soil are left open/exposed. Backfill immediately after work is completed.</p> <p>55. As much as possible restrict working time between 07:00 and 17:00. In particular are activities such as pile driving.</p> <p>56. Maintain equipment in proper working order</p> <p>57. Replace unnecessarily noisy vehicles and machinery.</p> <p>58. Vehicles and machinery to be turned off when not in use.</p> <p>59. Construct temporary noise barriers around excessively noisy activity areas where possible.</p>	All construction sites.	Fulltime	Monthly	No marginal cost	PMIS & PIU	contractor
Implement utility and power disruption sub-plan	Loss or disruption of utilities and services such as water supply and electricity	<p>60. Develop carefully a plan of days and locations where outages in utilities and services will occur, or are expected.</p> <p>61. Contact local utilities and services with schedule, and identify possible contingency back-up plans for outages.</p> <p>62. Contact affected community to inform them of planned outages.</p> <p>63. Try to schedule all outages during low use time such between 24:00 and 06:00.</p>	All construction sites.	Fulltime	Monthly	No marginal cost	PMIS & PIU & Utility company	contractor
Implement tree and vegetation	Damage or loss of trees, vegetation, and	<p>64. Contact provincial forestry department for advice on how to minimize damage to trees and vegetation</p> <p>65. Restrict tree and vegetation removal to within RoWs.</p>	All construction sites.	Beginning and end of subproject	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
removal, and site restoration sub-plan	landscape	66. Within RoWs minimize removals, and install protective physical barriers around trees that do not need to be removed. 67. All RoWs to be re-vegetated and landscaped after construction completed. Consult provincial forestry department to determine the most successful restoration strategy and techniques. Three trees should be replanted for each tree that has to be removed.						
Implement erosion control sub-plan	Land erosion	68. Berms, and plastic sheet fencing should be placed around all excavations and earthwork areas. 69. Earthworks should be conducted during dry periods. 70. Maintain a stockpile of topsoil for immediate site restoration following backfilling. 71. Protect exposed or cut slopes with planted vegetation, and have a slope stabilization protocol ready. 72. Re-vegetate all soil exposure areas immediately after work is completed.	All construction sites	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Implement worker and public safety sub-plan	Public and worker injury, and health	73. Proper fencing, protective barriers, and buffer zones should be provided around all construction sites. 74. Sufficient signage and information disclosure, and site supervisors and night guards should be placed at all sites. 75. Worker and public safety guidelines Government should be followed. See draft Occupational Safety & Health Master Plan of Ministry of Labor & Vocational Training (MLVT)). 76. Population near blast areas should be notified 24 hrs ahead, and evacuated well before operation. Accepted Government blast procedures and safety measures implemented. 77. Speed limits suitable for the size and type of construction vehicles, and current traffic patterns should be developed, posted, and enforced on all roads used by construction vehicles in Sihanoukville. 78. Standing water suitable for disease vector breeding should be filled in. 79. Worker education and awareness seminars for construction hazards should be given at beginning of construction phase, and at ideal frequency of monthly. A construction site safety program should be developed and distributed to workers.	All construction sites.	Fulltime	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		80. Appropriate safety clothing and footwear should be mandatory for all construction workers. 81. Adequate medical services must be on site or nearby all construction sites. 82. Drinking water must be provided at all construction sites. 83. Sufficient lighting be used during necessary night work. 84. All construction sites should be examined daily to ensure unsafe conditions are removed.						
Civil works	Degradation of water quality & aquatic resources	85. Protective coffer dams, berms, plastic sheet fencing, or silt curtains should be placed between all earthworks and nearby surface waters. 86. Erosion channels must be built around aggregate stockpile areas to contain rain-induced erosion. 87. Earthworks should be conducted during dry periods. 88. All construction fluids such as oils, and fuels should be stored and handled well away from surface waters. 89. No waste of any kind is to be thrown in surface waters. 90. No washing or repair of machinery near surface waters. 91. Pit latrines to be located well away from surface waters. 92. No unnecessary earthworks in or adjacent to water courses. 93. No aggregate mining from rivers or lakes. 94. All irrigation canals and channels to be protected the same way as rivers, streams, and lakes	All construction sites	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Civil works	Degradation of terrestrial resources	95. All construction sites should be located away forested or all plantation areas as much as possible. 96. No unnecessary cutting of trees. 97. All construction fluids such as oils, and fuels should be stored and handled well away from forested and plantation areas. 98. No waste of any kind is to be discarded on land	All construction sites	Throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Implement construction and urban traffic sub-plan	Traffic disruption, accidents, public injury	99. Schedule construction vehicle activity during light traffic periods. Create adequate traffic detours, and sufficient signage & warning lights. 100. Post speed limits, and create dedicated construction vehicle roads or lanes. 101. Inform community of location of construction traffic areas, and provide them with directions on how to best co-exist with construction vehicles on their roads.	All construction sites	Fulltime	Monthly	No marginal cost	PMIS & PIU	contractor

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
		102. Demarcate additional locations where pedestrians can develop road crossings away from construction areas. 103. Increase road and walkway lighting.						
Implement construction drainage sub-plan	Loss of drainage & flood storage	104. Provide adequate short-term drainage away from construction sites to prevent ponding and flooding. 105. Manage to not allow borrow pits and quarries to fill with water. Pump periodically to land infiltration or nearby water courses. 106. Install temporary storm drains or ditches for construction sites 107. Ensure connections among surface waters (ponds, streams) are maintained or enhanced to sustain existing storm water storage capacity. 108. Protect surface waters from silt and eroded soil.	All areas with surface waters	Design & construction phases	Monthly	No marginal cost	PMIS & PIU	contractor
Civil works: cultural chance finds sub-plan	Damage to cultural property or values, and chance finds	109. As per detailed designs all civil works should be located away from all cultural property and values. DoT identified potential sites and types of PCR in pre-con phase. 110. Chance finds of valued relics and cultural values should be anticipated by contractors. Site supervisors should be on the watch for finds. 111. Upon a chance find all work stops immediately, find left untouched, and PIU notified to determine if find is valuable. Culture section of DoT notified by telephone if valuable. 112. Work at find site will remain stopped until DoT allows work to continue.	All construction sites	At the start , and throughout construction phase	Monthly	No marginal cost	PMIS & PIU	contractor
Post-construction Operation of Renovated Landfill								
Improved garbage collection and transport	Increased risk of accident or injury.	130. Enforce well marked speed limits along road where needed, and educate local villages on road safety.	Existing collection and access roads	Fulltime	Biannual	O&M	DPWT	
	Increased air pollution & noise	131. Ensure vehicles maintained in proper working condition		Periodic checks				
Operation of renovated landfill	Contamination of groundwater	132. Groundwater wells installed during groundwater study should be maintained and used to monitor influence of renovated landfill on groundwater quality	At existing landfill	Throughout live span of landfill	Biannual	O&M	DPWT	
Post-construction Operation of Upgraded Drains								
Operation of	Periodic back-	133. Improved drains must be regularly cleaned and	Along all	Before/after	Biannual	O&M	DPWT	

Subproject Activity	Potential Environmental Impacts	Proposed Mitigation Measures	Location	Timing	Activity Reporting	Estimated Cost ⁵ (\$)	Responsibility	
							Supervision	Implementation
drains	up and local flooding	surfaced to maintain design capacity flows	upgraded drains	rainy season				

V. MONITORING PLAN

24. The environmental monitoring plan for the EMP is provided in Table 6. The monitoring plan focuses on all three phases (pre-construction, construction, post-construction operation) of the subproject components, and consists of environmental indicators, the sampling locations and frequency, method of data collection, responsible parties, and estimated costs. The purpose of the monitoring plan is to determine the effectiveness of the impact mitigations, and to document any unexpected positive or negative environmental impacts of the subproject. Table 2 summarizes the responsibilities for monitoring during the construction-implementation of the subproject.

A. Environmental Standards for Subproject Components

25. Environmental standards for ambient water quality for Cambodia are found in Annex 2. The environmental standards provided by the Environmental, Health and Safety Guidelines of the IFC/World Bank (2007) (e.g., ambient air quality and noise) should be followed to supplement standards that are not provided by the Government.

26. An independent environmental monitoring consultant (EMC) will be required to implement the environmental monitoring program. The EMC will be responsible for the sampling of environmental parameters that must be analyzed in a laboratory. The SO and EO will coordinate with the EMC. The PMIS/PIU will provide logistical support to the EMC where necessary for the implementation of environmental monitoring plan.

B. Performance Monitoring

27. Performance monitoring is required to assess the overall performance of the EMP. A project performance monitoring system will be developed by the EA for the entire subproject. Select indicators of major components of the environment that will be affected primarily by the construction phase are drawn from the mitigation and monitoring plans and summarized in Table 7.

VI. REPORTING

28. Regular reporting on the implementation of mitigation measures and on monitoring activities during construction phase of the subproject is required. Reporting is the responsibility of PIU and should be conducted in conjunction with regular meetings with stakeholders as part of the continuation of stakeholder communications. The mitigation and monitoring plans (Tables 5 and Table 6) summarize proposed timing of reporting. A report on environmental monitoring and implementation of EMP will be prepared quarterly for the EA/PSC by the IA. The IA report will compile monthly reports provided by the EO of contractor, the reports of the EMC on monitoring, and input from the ES of the PMIS. The IA report will also be sent to the DOE and to the PSC for consolidation and transmission to ADB quarterly.

29. The reports will assess all indicators measured with the monitoring plan of EMP including performance monitoring indicators (Table 7), and will include relevant Government environmental quality standards. Templates for the monitoring reports to be prepared by the EO, PIU, and EMC will be developed by the ES of the PMIS at detailed design. Annex 3 provides a monitoring report template for the PIU that the PIU with assistance from the PMU and PMIS must complete and attach as part of regular PIU reporting to the PMU/IA.

Table 6: Environmental monitoring plan

ENVIRONMENTAL EFFECTS MONITORING							
Environmental Indicators	Location	Means of Monitoring	Frequency	Reporting	Responsibility		Estimated ⁸ Cost (USD)
					Supervision	Implementation	
<i>Pre-construction Phase – Update Baseline Conditions</i>							
Where needed update baseline on sensitive receptors (e.g., cultural property & values, schools or hospitals, critical habitat)	A) Town centre	Contact DOE, community consultations	Once	Once	PMU/PIU	Environmental Monitoring Consultant	\$1,000.
A) Qualitative air quality: dust, noise, wind, and vibration levels B) Water table depth and groundwater quality (see groundwater study TOR in Appendix E IEE)	A): Town centre B): At existing landfill site	Using field and analytical methods approved by DoE.	One day and one night measurement during rainy & dry seasons.	One baseline supplement report before construction phase starts	PIU	Environmental Monitoring Consultant	A) \$1,000. B) \$30,000
Inventory of present and past land uses that could cause contaminated soil.	Possible contaminated lands at all excavation sites	Using field and analytical methods approved by DoE.	Once	Once	PIU	Environmental Monitoring Consultant	\$500.
Construction Phase of all Subproject Components							
Analysis of soil quality (heavy metals (As, Cd, Pb, oil & grease, hydrocarbons).	Possible contaminated lands at all excavation sites	Using field and analytical methods approved by DoE.	Once if needed	Once	PIU	Environmental Monitoring Consultant	\$2,000.
A) Qualitative air quality: dust, noise, wind, temperature, and vibration levels	A): Baseline sites of pre-construction phase.	A: Using field and analytical methods approved by DoE. Include visual observations of	A): Quarterly during construction periods	Monthly		A):	

⁸ Estimated costs will need to be updated with the EMP at detailed design stage.

ENVIRONMENTAL EFFECTS MONITORING

Environmental Indicators	Location	Means of Monitoring	Frequency	Reporting	Responsibility		Estimated ⁸ Cost (USD)	
					Supervision	Implementation		
B) Analysis of soil quality (heavy metals (As, Cd, Pb, Hg, Mn) and hydrocarbons. C) Domestic (worker) and construction solid waste inside & outside construction sites including worker camps. D) Public comments and complaints E) Incidence of worker or public accident or injury	B) At sites where contaminated soil is suspected. C) All construction sites and worker camps	dust and noise from contractor & public reports. C) Visual observation D) Information transferred by telephone hotline number posted at all construction sites.	Daily visual records B) Once at start of excavations C) Monthly		PIU	Monitoring Consultant	A: \$1,000./yr C: \$0.0	
							(E & F) & daily observations:	
	D) Using hotline number placed at construction areas E) At all construction areas		E) regular reporting by contractors/PIU	D) Continuous public input E) Continuous		PMU/PIU	contractor	D: \$1,000./yr E: \$0.0
Operation of Renovated Landfill								
Groundwater quality (see groundwater study in Appendix E of IEE)	Bore wells at landfill.	Using field and analytical methods approved by DoE.	Biannually for 5 years	Biannual		DPWT	\$2000. /yr	
Traffic accidents	Access roads.	Regular record keeping.	Continuously	For each event		DPWT	\$0.0	

Table 7. Performance monitoring indicators for Sihanoukville subproject

Major Environmental Component	Key Indicator	Performance Objective	Data Source
Pre-construction Phase			
Public Consultation and Disclosure	Affected public and stakeholders	Meetings with stakeholders contacted during IEE & new stakeholders convened for follow-up consultation and to introduce grievance mechanism	Minutes of meeting, and participants list
EMP	Updated EMP	All stakeholders contacted during IEE re-contacted for follow-up consultation	EMP
Bid Documents	Requirements of EMP (CEMP) ⁹	EMP appended to bidding documents with clear instructions to bidders for CEMP	Bid documents
Training of PMU/PIU/SO	Training course(s) & schedule	By end of preconstruction phase, required course(s) that will be delivered are designed and scheduled	Course(s) outline, participants, and schedule
Construction Phase			
All subproject areas	Critical habitat, rare or endangered species <i>if present</i>	All <i>present</i> critical habitat and R & E species if unchanged, and unharmed	Monitoring by EMC ¹⁰
Groundwater quality	Heavy metals, coliform bacteria, TDS, H ₂ S, BOD ₅ , TN, NH ₃ , TP, nutrient forms of N & P ¹¹	Government environmental standards and criteria met	Monitoring by EMC
Air quality	Dust, noise, vibration	Levels never exceed pre-construction baseline levels	EMC & contractor monitoring reports,
Soil quality	Solid and liquid waste	Rigorous program of procedures and rules to collect and store all waste from construction camps and sites practiced.	Contractor and EMC monitoring reports
Hazardous materials and waste	Oil, gasoline, grease, alum, chlorine, soda	Rigorous program of procedures to manage and store all waste from construction camps and sites practiced.	Contractor and EMC monitoring reports
Public and worker safety	Frequency of injuries	Adherence to Government policy and site-specific procedures to prevent accidents ¹²	Contractor reports
Cultural property	Incidence of damage or complaints	No valued cultural property, or unearthed valuable relic is harmed in any way	Public input, contractor reports, public input, EMC reports
Traffic	Frequency of disruptions and/or blocked roadways	Disruptions, stoppages, or detours are managed to absolute minimum.	Public input, contractor reports, EMC reports
Operation of Renovated Landfill			

⁹Contractor Environmental Management Plan developed from EMP in contractor bidding document

¹⁰Environmental Monitoring Consultant hired to assist implementation of Environmental Monitoring Plan

¹¹ See Annex 2 for environmental standards, analyzed by laboratory facilities in Phnom Penh.

¹² MLVT's new Occupational Safety & Health Master Plan needs to be applied , or IFC World Bank EHS (2007)

Major Environmental Component	Key Indicator	Performance Objective	Data Source
Groundwater quality	Heavy metals, coliform bacteria, TDS, H ₂ S, BOD ₅ , TN, NH ₃ , TP, nutrient forms of N & P	No deviation from background levels, compliance with standards Appendix 2	DPWT/DOE
Public safety	Incidence of traffic accidents on access roads	No deviation from baseline frequency	DPWT

VII. ESTIMATED COST OF EMP

30. The marginal costs for implementing the EMP are primarily for environmental monitoring because the costs for implementing impact mitigation measures during the construction phase are included with the construction costs in contractor bid documents.

31. From Table 6 the preliminary costs for the implementation of the EMP for the passenger pier development in Sihanoukville are summarized in Table 8. These costs include per diem technician fees. Note that a margin of cost uncertainty/contingency to the total EMP cost has been added. These costs include per diem technician fees.

32. An estimated budget of \$30,000 is allocated for the groundwater study including bore hole construction at the new and old landfill sites (Appendix E of IEE). An estimated budget of \$10,000 is required for capacity building and training for environmental management for PIU/PMU in conjunction with other capacity development activities of the subproject. The costs will need to be reviewed and updated by the PMIS in conjunction with the PIU during the pre-construction phase.

Table 8: Estimated costs for environmental monitoring plan of EMP

Activity Type	Estimated Cost (USD)
Pre-construction Phase	
Updating Environmental Baseline	
cultural receptors	\$1,000
environmental quality	\$2,500
groundwater study at landfills and WWTP	\$30,000
Construction Phase	
environmental quality	\$4,000
public consultation	\$2,000
Post-construction Operation Phase	
environmental quality	\$10,000
public input	\$0.0
Training and capacity development	\$10,000
Total	\$59,500

VIII. EMERGENCY RESPONSE PLAN

33. The Contractor must develop emergency or incident response procedures during construction. In the operational phase the operator/civil authorities will have responsibility for any emergencies or serious incidents. The construction phase should ensure:

- i) Emergency Response Team (ERT) of the Contractor as initial responder;
- ii) The District fire and police departments, emergency medical service, the Department of Public Health (DPH), collectively referred to as the External Emergency Response Team (EERT), as ultimate responders.

34. The Contractor will provide and sustain the required technical, human and financial resources for quick response during construction.

Table 9: Roles and responsibilities in emergency incident response

Entity	Responsibilities
Contractor Team (ERT)	<ul style="list-style-type: none"> - Communicates / alerts the EERT. - Prepares the emergency site to facilitate the response action of the EERT, e.g., vacating, clearing, restricting site. - When necessary & requested by the EERT, lends support / provides assistance during EERT's response operations.
External Emergency Response Team (EERT)	<ul style="list-style-type: none"> - Solves the emergency/incident
Contractor Resources	<ul style="list-style-type: none"> - Provide and sustain the people, equipment, tools and funds necessary to ensure Subproject's quick response to emergency situations. - Maintain good communication lines with the EERT to ensure prompt help response & adequate protection, by keeping them informed of subproject progress.

35. The ERT will be led by the Contractor's senior engineer (designated ERTL) on site with a suitably trained foreman or junior engineer as deputy. Trained first-aiders and security crew will be the core members of the ERT.

36. The Contractor will ensure that ERT members are physically, technically and psychologically fit for their emergency response roles and responsibilities.

37. Prior to the mobilization of civil works, the Contractor, through its Construction Manager, ERTL, in coordination with the PSC/PIU, will meet with the ultimate response institutions to discuss the overall construction process, including, but not limited to:

- i) Subproject sites;
- ii) construction time frame and phasing;
- iii) any special construction techniques and equipment that will be used; i
- iv) any hazardous materials that will be brought to and stored in the construction premise and details on their applications and handling/management system;
- v) the Contractor's Emergency Management Plan
- vi) names and contact details of the ERT members

38. The objective of this meeting is to provide the ultimate response institutions the context for:

- i) their comments on the adequacy of the respective Emergency Management Plans
- ii) their own assessment of what types, likely magnitude and likely incidence rate of potential hazards are anticipated
- iii) the arrangements for coordination and collaboration.

39. To ensure effective emergency response, prior to mobilization of civil works, the Contractor will:

- i) set up the ERT;
- ii) set up all support equipment and facilities in working condition
- iii) made arrangements with the EERT;
- iv) conducted proper training of ERT members, and encouraged and trained volunteers from the work force;
- v) conduct orientation to all construction workers on the emergency response procedures and facilities, particularly evacuation procedures, evacuation routes, evacuation assembly points, and self-first response, among others; and
- vi) conduct drills for different possible situations.

40. To sustain effective emergency response throughout subproject implementation an adequate budget shall be provided to sustain the capabilities and efficiency of the emergency response mechanism, the emergency response equipment, tools, facilities and supplies. Drills and reminders will take place regularly, the former at least every two months and the latter at least every month.

A. Alert Procedures

41. Means of communicating, reporting and alerting an emergency situation may be any combination of the following: (i) audible alarm (siren, bell or gong); (ii) visual alarm (blinking/rotating red light or orange safety flag); (iii) telephone (landline); (iv) mobile phone; (v) two-way radio; and (vi) public address system/loud speakers. Some rules relative to communicating/alerting will be:

- (i) Whoever detects an emergency situation first shall immediately :
 - call the attention of other people in the emergency site,
 - sound the nearest alarm, and/or
 - report/communicate the emergency situation to the ERT.
- (ii) Only the ERTL and, if ERTL is not available, the Deputy ERTL are authorized to communicate with the EERT. Exceptional cases to this rule may be necessary and should be defined in the Emergency Management Plans.
- (iii) When communicating/alerting an emergency to the EERT, it is important to provide them with at least: (i) the type of emergency situation; (ii) correct location of the emergency; (iii) estimated magnitude of the situation; (iv) estimated persons harmed; (v) time it happened; (vi) in case of a spill, which hazardous substance spilled; and (vii) in case of fire and explosion, what caused it. Such details would allow the EERT to prepare for the appropriate response actions.

For an effective reporting/alerting of an emergency situation:

- (i) The names and contact details of the relevant persons and institutions should be readily available in, or near to, all forms of communication equipment, and strategically posted (at legible size) in all Subproject sites and vehicles:
 - Most relevant construction/operations staffs namely, the ERTL, Deputy ERTL, first-aiders, supervising engineers, foremen
 - EERT institutions/organizations
 - Concerned village authority/ies
 - PIU Office, SS
- (ii) All subproject sites should have good access to any combination of audible and visual alarms, landline phones, mobile phones and two-way radio communication at all times.
- (iii) Contractor's construction vehicles should also be equipped with the appropriate communication facilities.

B. Emergency Response Situations

45. The following tables suggest general procedures that will be refined in the final EMP during detailed design, and described in more detail in the Emergency Management Plans of the Contractor.

Table 10: Evacuation procedure

Procedure	Remarks
<ul style="list-style-type: none"> • Move out as quickly as possible as a group, but avoid panic. 	<ul style="list-style-type: none"> • All workers/staff, sub-contractors, site visitors to move out, guided by the ERT.
<ul style="list-style-type: none"> • Evacuate through the directed evacuation route. 	<ul style="list-style-type: none"> • The safe evacuation shall have been determined fast by the ERTL/Deputy ERTL & immediately communicated to ERT members.
<ul style="list-style-type: none"> • Keep moving until everyone is safely away from the emergency site and its influence area. 	<ul style="list-style-type: none"> • A restricted area must be established outside the emergency site, all to stay beyond the restricted area.
<ul style="list-style-type: none"> • Once outside, conduct head counts. 	<ul style="list-style-type: none"> • Foremen to do head counts of their subgroups; ERTL/Deputy ERTL of the ERT.
<ul style="list-style-type: none"> • Report missing persons to EERT immediately. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL to communicate with the EERT.
<ul style="list-style-type: none"> • Assist the injured in evacuation & hand them over to the ERT first-aiders or EERT medical group 	<ul style="list-style-type: none"> • ERT to manage injured persons to ensure proper handling.
<ul style="list-style-type: none"> • If injury warrants special care, DO NOT MOVE them, unless necessary & instructed/directed by the EERT. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL communicates with EERT to get instructions/directions in handling the injured.

Table 11: Response procedure during medical emergency

Procedure	Remarks
<ul style="list-style-type: none"> • Administer First Aid regardless of severity immediately. 	<ul style="list-style-type: none"> • Fundamentals when giving First Aid: <ul style="list-style-type: none"> - Safety first of both the rescuer and the victim. - Do not move an injured person unless: <ul style="list-style-type: none"> - victim is exposed to more danger when left where they are, e.g., during fire, chemical spill - it would be impossible for EERT to aid

Procedure	Remarks
	<ul style="list-style-type: none"> victims in their locations, e.g., under a collapsed structure - instructed or directed by the EERT. • First Aid to be conducted only by a person who has been properly trained in giving First Aid.
<ul style="list-style-type: none"> • Call the EERT emergency medical services &/or nearest hospital. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL or authorized on-site emergency communicator
<ul style="list-style-type: none"> • Facilitate leading the EERT to the emergency site. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL to instruct: <ul style="list-style-type: none"> - an ERT member on-site to meet EERT in access road/strategic location. He/she shall hold orange safety flag to get their attention & lead them to site. - Other ERT members to clear access road for smooth passage of the EERT.
<ul style="list-style-type: none"> • If applicable, vacate site & influence area at once, restrict site, suspend work until further notice. 	<ul style="list-style-type: none"> • Follow evacuation procedure.

Table 12: Response procedure in case of fire

Procedure	Remarks
<ul style="list-style-type: none"> • Alert a fire situation. 	<ul style="list-style-type: none"> • Whoever detects the fire shall immediately: <ul style="list-style-type: none"> - call the attention of other people in the site, - sound the nearest alarm, and/or - Foreman or any ERT member among the construction sub-group contacts the fire department (in this case it should be agreed on that it is alright for any ERT member in the sub-group to alert the fire department) - report/communicate the emergency situation to the ERTL/Deputy ERTL.
<ul style="list-style-type: none"> • Stop all activities/operations and evacuate. 	<ul style="list-style-type: none"> • All (non-ERT) workers/staff sub-contractors, site visitors and concerned public to move out to safe grounds following the evacuation procedure.
<ul style="list-style-type: none"> • Activate ERT to contain fire/control fire from spreading. 	<ul style="list-style-type: none"> • Guided by the training they undertook, ERT members assigned to mitigate the fire shall assess their own safety situation first before attempting to control fire spread.
<ul style="list-style-type: none"> • Call the nearest fire & police stations &, if applicable, emergency medical services. 	<ul style="list-style-type: none"> • When alerting the EERT, ERTL will give the location, cause of fire, estimated fire alarm rating, any injuries.
<ul style="list-style-type: none"> • Facilitate leading the EERT to the emergency site. 	<ul style="list-style-type: none"> • ERTL/Deputy ERTL to instruct: <ul style="list-style-type: none"> - an ERT member to meet the EERT in the access road or strategic location and lead them to the site. He/she shall hold the orange safety flag to get their attention and lead them to the site. - some ERT members to stop traffic in, & clear, the access road to facilitate passage of the EERT.
<ul style="list-style-type: none"> • ERT to vacate the site as soon as their safety is assessed as in danger. 	<ul style="list-style-type: none"> • Follow appropriate evacuation procedure.

IX. INSTITUTIONAL CAPACITY REVIEW AND NEEDS

46. Currently there is little experience and capacity for environmental assessment and management amongst national counterparts responsible for the implementation of the EMP, i.e., the DPWT/PMU in Sihanoukville province. No dedicated environmental staff exist in the DPWT and thus the PIU. The PMIS with assistance from the safeguards specialists of the subproject will develop and deliver training courses to the PIU/PMU staff responsible for the implementation of the subproject. The purpose of the course(s) is to strengthen the ability of the PIU/PMU to oversee implementation of the EMP by construction contractors, and the EMC. The safeguards specialists, who will be full-time environmental member of the PIU, as well as the EO of the contractor, should attend training courses as required. Costs for training should be included with costs for implementation of the EMP.

47. Training on the implementation of an EMP should address two thematic areas. The first area should be principles environmental management focused on the potential impacts of subproject activities on the natural and social environment. The second area should be environmental safeguard requirements of the ADB and Government, with specific reference to the EMP.

ANNEX 1: INDICATIVE TORS FOR ENVIRONMENTAL SPECIALISTS OF PMIS

International Environmental Specialist. With assistance from the national environmental specialist the international consultant will be responsible for updating the subproject EMP at detailed design, and assisting the PIU with overall environmental management of the implementation of the subproject in Sihanoukville. The consultant will: (i) update environmental management plan (EMP) for the subproject in Sihanoukville to ensure that EMP addresses the detailed designs and engineering of the subproject. Updates to EMP include mitigation and monitoring plans, budget, and capacity development needs of executing agency (EA and IA (DPWT)); (ii) with national consultant design comprehensive training plan for safeguards officer/PIU and on principles of EIA, and the purpose, content, and roles and responsibilities for implementation of updated EMPs highlighting environmental issues of subprojects; (iii) ensure that all relevant safeguards of the EMPs are adequately addressed in the bidding documents (instruction to bidders), and in the evaluation criteria for awarding contracts; (iv) Coordinate and work with the PIU to ensure that contractors finalize their respective site-specific CEMPs based on the updated EMP and the actual site conditions; (v) oversee the implementation of all safeguards of the EMP relating to construction phase activities including handling of construction spoil and waste, water and air quality protection, public nuisance impacts (noise, dust, traffic, blocked access, workers, and camps), and public safety; (vi) Coordinate with the DPWT to finalize the groundwater monitoring program and landfill closure program for the new and old landfills; (vii) coordinate with the DPWT on all relevant environmental regulatory compliance issues (e.g. noise and dust from construction sites, sanitation in workers campsite etc); (viii) prepare ToR(s) for survey, detection, and removal of unexploded ordnance (UXO) at all civil works sites. Ensure that EA and/or IA consult Government authorities to assist with TOR development and implementation; (ix) with PIU, prepare TORs for the follow-up interviews and consultations with the same affected stakeholder and local residents contacted during the PPTA on issues and concerns arising during project construction. Of particular concern is upgrades to access roads; (x) prepare TOR(s) for external national environment monitoring consultant (EMC) for conducting water and air quality sampling, and laboratory analyses for the monitoring plans for the provincial EMPs; (xi) coordinate with DPWT to address vehicle traffic issues; (xii) advise PIU on environment-related concerns arising during subproject construction, and recommend corrective measures; (xiii) with DPWT ensure dissemination to stakeholders the results of environment quality monitoring and implementation of safeguards, especially among households or small businesses near the civil construction works areas; (xiv) assist EA and IA prepare a table of contents for regular reports IA must submit to the EA on implementation of EMPs, environmental, issues, and corrective actions; (xv) assist PIU prepare simple report template for construction contractors to report monthly on mitigation activities, and environmental issues that occur during construction phase; and (xvi) prepare a quarterly status report on implementation of EMPs, environmental issues, and public safety protection to be submitted through the PIU and EA to the DPWT and ADB. The consultant should have an advanced university degree the environmental sciences and at least 7 years experience implementing and managing environmental assessment of infrastructure projects in southeast Asia countries (preferably Cambodia) including: a) understanding of ADB and national environmental safeguard requirements; b) experience working with and supervising the activities of provincial and national environmental management agencies with environmental safeguards; and c) designing and delivering training and capacity development programs to provincial environment, subproject implementing units.

National Environmental Specialist. Provide assistance to the international environmental specialist including acquisition of information new information to update the subproject EMP at detailed design, and work with the PIU with overall environmental management of the implementation of the subproject in Sihanoukville. The national consultant will assist with: (i) updating environmental management plan (EMP) for subproject in Sihanoukville to ensure that EMP addresses the detailed designs and engineering of subproject; (ii) deliver initial training to DPWT/PMU on the purpose, content, and roles and responsibilities for implementation of updated EMP; (iii) ensure relevant safeguards of the EMP are addressed in the bidding documents in accurate local language and in evaluation criteria for awarding contracts; (iv) help PIU to ensure that contractors prepare their respective site-specific plans based on the updated EMP and the actual site conditions; (v) help the international consultant oversee the implementation of all safeguards of the EMP relating to construction phase activities including handling of construction spoil and waste, water and air quality protection, public nuisance impacts (noise, dust, traffic, blocked access, workers, and camps), and public safety; (vi) assist coordination with the DPWT on all relevant environmental regulatory compliance issues (e.g. noise and dust from construction sites, sanitation in workers campsite etc); (vii) with PIU prepare TORs for the follow-up interviews and consultations with the same affected stakeholder and local residents contacted during the PPTA on issues and concerns arising during project construction. Of particular concern is upgrades to access roads; (viii) assist DPWT to address vehicle traffic issues; (ix) with the international consultant advise the PIU on environment-related concerns arising during subproject construction, and recommend corrective measures; (x) with PIU ensure dissemination to stakeholders the results of environment quality monitoring and implementation of safeguards, especially among households or small businesses near the civil construction works areas; (xi) assist with all reporting for the EMP. The consultant should have a university degree in the environmental sciences and at least 5 years with environmental assessment of infrastructure projects in Cambodia including: a) understanding of ADB and national environmental safeguard requirements; b) experience working with international consultants; and c) delivering training and capacity development programs to subproject implementing units.

ANNEX 2: ENVIRONMENTAL STANDARDS FOR CAMBODIA

From Government Sub-decree on Water Pollution Control (1999)
<http://www.wepa-db.net/policies/law/cambodia/02.htm>

Table 1. Effluent standard for pollution sources discharging wastewater to public water areas or sewer access

No	Parameters	Unit	Allowable limits for pollutant substance discharging to	
			Protected public water area	Public water area and sewer
1	Temperature	°C	< 45	< 45
2	pH		6 – 9	5 - 9
3	BOD5 (5 days at 200 C)	mg/l	< 30	< 80
4	COD	mg/l	< 50	< 100
5	Total Suspended Solids	mg/l	< 50	< 80
6	Total Dissolved Solids	mg/l	< 1000	< 2000
7	Grease and Oil	mg/l	< 5.0	< 15
8	Detergents	mg/l	< 5.0	< 15
9	Phenols	mg/l	< 0.1	< 1.2
10	Nitrate (NO3)	mg/l	< 10	< 20
11	Chlorine (free)	mg/l	< 1.0	< 2.0
12	Chloride (ion)	mg/l	< 500	< 700
13	Sulphate (as SO4)	mg/l	< 300	< 500
14	Sulphide (as Sulphur)	mg/l	< 0.2	< 1.0
15	Phosphate (PO4)	mg/l	< 3.0	< 6.0
16	Cyanide (CN)	mg/l	< 0.2	< 1.5
17	Barium (Ba)	mg/l	< 4.0	< 7.0
18	Arsenic (As)	mg/l	< 0.10	< 1.0
19	Tin (Sn)	mg/l	< 2.0	< 8.0
20	Iron (Fe)	mg/l	< 1.0	< 20
21	Boron (B)	mg/l	< 1.0	< 5.0
22	Manganese (Mn)	mg/l	< 1.0	< 5.0
23	Cadmium (Cd)	mg/l	< 0.1	< 0.5
24	Chromium (Cr)+3	mg/l	< 0.2	< 1.0
25	Chromium (Cr)+6	mg/l	< 0.05	< 0.5
26	Copper (Cu)	mg/l	< 0.2	< 1.0
27	Lead (Pb)	mg/l	< 0.1	< 1.0
28	Mercury (Hg)	mg/l	< 0.002	< 0.05
29	Nickel (Ni)	mg/l	< 0.2	< 1.0
30	Selenium (Se)	mg/l	< 0.05	< 0.5
31	Silver (Ag)	mg/l	< 0.1	< 0.5
32	Zinc (Zn)	mg/l	< 1.0	< 3.0
33	Molybdenum (Mo)	mg/l	< 0.1	< 1.0
34	Ammonia (NH3)	mg/l	< 5.0	< 7.0
35	DO	mg/l	> 2.0	> 1.0

36	Polychlorinated Biphenyl	mg/l	< 0.003	< 0.003
37	Calcium	mg/l	< 150	< 200
38	Magnesium	mg/l	< 150	< 200
39	Carbon tetrachloride	mg/l	< 3	< 3
40	Hexachloro benzene	mg/l	< 2	< 2
41	DTT	mg/l	< 1.3	< 1.3
42	Endrin	mg/l	< 0.01	< 0.01
43	Dieldrin	mg/l	< 0.01	< 0.01
44	Aldrin	mg/l	< 0.01	< 0.01
45	Isodrin	mg/l	< 0.01	< 0.01
46	Perchloro ethylene	mg/l	< 2.5	< 2.5
47	Hexachloro butadiene	mg/l	< 3	< 3
48	Chloroform	mg/l	< 1	< 1
49	1,2 Dichloro ethylene	mg/l	< 2.5	< 2.5
50	Trichloro ethylene	mg/l	< 1	< 1
51	Trichloro benzene	mg/l	< 2	< 2
52	Hexachloro cyclohexene	mg/l	< 2	< 2

Remark: The Ministry of Environment and the Ministry of Agriculture, Forestry and Fishery shall collaborate to set up the standard of pesticides which discharged from pollution sources.

Table 2: Water Quality Standard in public water areas for bio-diversity conservation

I. For River			
No	Parameter	Unit	Standard Value
1	pH	mg/l	6.5 – 8.5
2	BOD5	mg/l	1 – 10
3	Suspended Solid	mg/l	25 – 100
4	Dissolved Oxygen	mg/l	2.0 - 7.5
5	Coliform	MPN/100ml	< 5000
II. Lakes and Reservoirs			
No	Parameter	Unit	Standard Value
1	pH	mg/l	6.5 – 8.5
2	COD	mg/l	1 – 8
3	Suspended Solid	mg/l	1 – 15
4	Dissolved Oxygen	mg/l	2.0 - 7.5
5	Coliform	MPN/100ml	< 1000
6	Total Nitrogen	mg/l	– 0.6
7	Total Phosphorus	mg/l	0.005 – 0.05
III. Coastal Water			
No	Parameter	Unit	Standard Value
1	pH	mg/l	7.0 – 8.3
2	COD	mg/l	2 – 8
3	Dissolved Oxygen	mg/l	2 - 7.5
4	Coliform	MPN/100ml	< 1000

5	Oil content	mg/l	0
6	Total Nitrogen	mg/l	- 1.0
7	Total Phosphorus	mg/l	0.02 – 0.09

Table 3. Water Quality Standard in public water areas for public health protection

No	Parameter	Unit	Standard Value
1	Carbon tetrachloride	µg/l	< 12
2	Hexachloro-benzene	µg/l	< 0.03
3	DDT	µg/l	< 10
4	Endrin	µg/l	< 0.01
5	Dieldrin	µg/l	< 0.01
6	Aldrin	µg/l	< 0.005
7	Isodrin	µg/l	< 0.005
8	Perchloroethylene	µg/l	< 10
9	Hexachlorobutadiene	µg/l	< 0.1
10	Chloroform	µg/l	< 12
11	1,2 Trichloroethylene	µg/l	< 10
12	Trichloroethylene	µg/l	< 10
13	Trichlorobenzene	µg/l	< 0.4
14	Hexachloroethylene	µg/l	< 0.05
15	Benzene	µg/l	< 10
16	Tetrachloroethylene	µg/l	< 10
17	Cadmium	µg/l	< 1
18	Total mercury	µg/l	< 0.5
19	Organic mercury	µg/l	0
20	Lead	µg/l	< 10
21	Chromium, valent 6	µg/l	< 50
22	Arsenic	µg/l	< 10
23	Selenium	µg/l	< 10
24	Polychlorobiohenyl	µg/l	0
25	Cyanide	µg/l	< 0.005

ANNEX 3: MONITORING REPORT TEMPLATE FOR PROJECT IMPLEMENTATION UNIT

Safeguards Monitoring Report

This report is to be completed by the PIU with assistance from the PMIS and PMU. The report forms part of the regular reporting of PIU to PMU and ultimately to the EA and ADB.

1. Introduction and Project Overview

Project Number and Title:		
Safeguards Category	Environment	B
	Indigenous Peoples	C
	Involuntary Resettlement	C
Reporting period:		
Last report date:		
Key sub-project activities since last report:	<p><i>This section can include, among others, the following:</i></p> <ul style="list-style-type: none"> • <i>Activities of PIU/PMU</i> • <i>Progress of work (% physical completion)</i> • <i>Changes of surrounding environment</i> • <i>Status of permits / consents</i> 	
Report prepared by:		

2. Environmental Performance Monitoring

a. Summary of Compliance with EMAP Requirements (Environmental Performance)

Monitoring Requirements	Compliance Status (Yes, No, Partial)	Comment or Reasons for Non-Compliance	Issues for Further Action
<i>Use tabled performance monitoring indicators of EMP</i>			

b. Issues for Further Action

Issue	Required Action	Responsibility and Timing	Resolution
Old Issues from Previous Reports			
<i>List of monitoring or mitigation measures or activities not completed</i>			

<i>(last column of previous table)</i>			
New Issues from This Report			

c. Other activities

- Other issues not covered by mitigation or monitoring plans of EMP
- Any additional environmental monitoring required (e.g., air quality, water sampling)

3. Occupational, Health and Safety (OHS) Performance Monitoring

a. OHS for worker

Issue	Required Action	Responsibility and Timing	Resolution
Old Issues from Previous Reports			
New Issues from This Report			

b. Public Safety

Issue	Required Action	Responsibility and Timing	Resolution
Old Issues from Previous Reports			

New Issues from This Report			

4. Information Disclosure and Socialization including Capability Building

Prepare brief summary of the information below where applicable

- Field visits conducted (sites visited, dates, persons met)
- Public consultations and meetings conducted (date; time; location; agenda; number of participants disaggregated by sex and ethnic group, not including project staff; Issues raised by participants and how these were addressed by the project team)
- Training conducted (nature of training, number of participants disaggregated by gender and ethnicity, date, location, etc.)
- Press/Media releases
- Material development/production (e.g., brochure, leaflet, posters)

5. Grievance Redress Mechanism

Summary:

- Number of new grievances, if any, since last monitoring period: _____
- Number of grievances resolved: _____
- Number of outstanding grievances: _____

Type of Grievance	Details (Date, person, address, contact details, etc.)	Required Action, Responsibility and Timing	Resolution
Old Issues from Previous Reports			
New Issues from This Report			

6. Conclusion

- Important results from the implementation of mitigation and monitoring of EMP
- Recommendations to improve EMP implementation

7. Attachments

- Consents / permits
- Monitoring data (water quality, air quality, etc.)
- Photographs
- Maps