

Environmental Impact Assessment

February 2017

PAK: Peshawar Sustainable Bus Rapid Transit Corridor Project

Prepared by the Peshawar Development Authority (PDA), Government of Khyber Pakhtunkhwa (GoKP) for the Asian Development Bank (ADB).

CURRENCY EQUIVALENTS

(as of 24 February 2017)

Currency unit – Pakistan Rupee (PRs.)

PRs 1.00 = \$ 0.0093

US\$1.00 = PRs107.05

ABBREVIATIONS

ADB	–	Asian Development Bank
SPS	–	Safeguard Policy Statement
SIA	–	Social Impact Assessment
DoF	–	Department of Forests
EA	–	environmental assessment
EARF	–	Environment Assessment Review Framework
EAAC	–	Environmental Assessment Advisory Committee
EPA	–	Environmental Protection Agency
EIA	–	environment impact assessment
EMP	–	environmental management plan
PPDD	–	Punjab Planning and Development Department
EA	–	executing agency
IA	–	implementing agency
PDA	–	Peshawar Development Authority
PMU	–	Project Management Unit
SC	–	Steering Committee
AS	–	Assistant Secretary
GoKPK	–	Government of Khyber Pakhtunkhwa
GOP	–	Government of Pakistan
IEE	–	initial environmental examination
km	–	kilometer
tpd	–	tonnes per day
LAA	–	Land Acquisition Act (of 1984)
LARP	–	Land Acquisition and Resettlement Plan
Leq	–	Equivalent sound pressure level
NEQS	–	National Environmental Quality Standards
NGO	–	Non-Governmental Organization
O&M	–	Operation & Maintenance
PC	–	public consultation
PAP	–	project affected person
BRT	–	bus rapid transit
PEPAct	–	Pakistan Environment Protection Act 1997
RP	–	resettlement plan
PFS	–	pre-feasibility study

This environmental impact assessment is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature. Your attention is directed to the “terms of use” section on ADB's website.

In preparing any country program or strategy, financing any project, or by making any designation of or reference to a particular territory or geographic area in this document, the Asian Development Bank does not intend to make any judgments as to the legal or other status of any territory or area.

Table of Content

1	Introduction	1
1.1	Project Background	1
1.2	Environmental Category of the Project	1
1.3	Methodology of EIA Study.....	2
2	Policy and Legal Framework	4
2.1	General	4
2.2	National Policy and Legal Framework	4
2.3	Regulations for Environmental Assessment, Pakistan EPA.....	4
2.4	Regulatory Clearances, KPK EPA.....	4
2.5	Guidelines for Environmental Assessment, Pakistan EPA	5
2.6	National Environmental Quality Standards (NEQS) 2000	5
2.7	ADB's Safeguard Policy Statement (SPS), 2009	5
2.8	ADB's Public Communication Policy 2011.....	6
2.9	ADB's Accountability Mechanism Policy 2012	6
2.10	Interaction with Other Agencies.....	6
2.11	Provincial EPAs.....	7
2.12	Provincial Departments of Forests and Wildlife.....	7
2.13	Provincial Governments	7
2.14	Other Environment Related Legislations.....	7
2.15	Comparison of International and Local Environmental Legislations	9
2.16	Implications of national policies and regulations on proposed project..	10
2.17	Implications of ADB policies on proposed project	12
3	Description of the Project	18
3.1	Justification and Need for Project	18
3.2	Objectives of Project	19
3.3	Proposed Project Activities.....	19
3.4	Design of BRT	19
3.4.1	BRT Route	19
3.4.2	Off-Corridor Bus Stops	23
3.4.3	BRT Station design & Configuration	25
3.4.4	Sub-Stop Concept	27
3.4.5	BRT Station Types	27
3.4.6	Conceptual Design of BRT Stations	31
3.4.7	Vehicle design and Configuration	36
3.4.8	Station Access and Pedestrian Facility	39

3.5 Associated BRT Infrastructure.....	41
3.5.1 Bus Depot	41
3.5.2 Staging Facility	43
3.5.3 Workshop Layout	50
3.5.4 TransPeshawar Office	52
3.6 Operational Mode of BRT	52
3.6.1 'Direct-Service' Operational Model	52
3.6.2 Operational Plan and Fleet	53
3.7 Implementation Arrangement.....	53
3.7.1 Implementation Management and Execution	53
3.7.2 Project Construction Schedule	57
3.8 Construction Camps and Work Force	57
3.9 Machinery Requirement.....	57
4 Description of Environment.....	59
4.1 General	59
4.2 Physical Resources	59
4.2.1 Topography	59
4.2.2 Climate	59
4.2.3 Seismology.....	62
4.2.4 Surface and Groundwater.....	63
4.3 Ecological Resources.....	64
4.3.1 Flora.....	64
4.3.2 Fauna (Regional).....	64
4.4 Human and Economic Development	65
4.4.1 Culture.....	65
4.4.2 Languages	65
4.4.3 Religion	65
4.4.4 Administrative Setup.....	66
4.4.5 Main Sources of Livelihood/Income	66
4.4.6 Transport.....	66
4.4.7 Industry	67
4.4.8 Health Care	67
4.4.9 Literacy Rate	67
4.4.10 Education	68
4.4.11 Archaeological and Cultural Heritage	68
4.4.12 Energy Supplies	69
4.4.13 Communication	69

4.4.14 Project Area Communities	69
4.5 Noise	70
4.6 Air Quality	92
4.7 Climate Vulnerability of Project	92
5 Analysis of Alternatives	95
5.1 No Project Alternative	95
5.2 Alternatives Considered	95
5.2.1 Alternative route options	95
5.2.2 CNG versus Diesel buses	98
5.2.3 'At Grade' versus 'Elevated' Sections	100
5.2.4 Location of Bus Depots	101
6 Potential Environmental Impacts and Mitigation Measures	102
6.1 Design/Pre-Construction Phase	102
6.1.1 Cultural Heritage, Religious Sites, Social Infrastructure	102
6.1.2 Land Acquisition and Resettlement	102
6.1.3 Identification of Locations for Labor Camps and associated facilities	104
6.1.4 Development of Traffic Management Plan	104
6.2 Construction Phase	105
6.2.1 Air Quality	107
6.2.2 Noise and Vibration	109
6.2.3 Management of Traffic	115
6.2.4 Water Resources	116
6.2.5 Safety precautions during Construction work	117
6.2.6 Camp effluent	117
6.2.7 Soil Erosion and Sedimentation	118
6.2.8 Soil Contamination	118
6.2.9 Drainage and Storm Water Run-off	118
6.2.10 Hazardous and Non-Hazardous Waste Management	119
6.2.11 Historical/Archaeological Sites	119
6.2.12 Vegetation and Wildlife Loss	119
6.2.13 Community Safety	120
6.2.14 Employment Conflicts	120
6.2.15 Communicable Diseases	121
6.2.16 Land Use and Aesthetics	121
6.2.17 Utilities provision interruption	121
6.2.18 Natural and Man made Hazards	122
6.3 Operation Phase	123

6.3.1 Air Quality.....	124
6.3.2 Noise	132
6.3.3 Impacts on Water Resources	133
6.3.4 Solid Waste disposal	134
6.3.5 Biological Environment	134
6.3.6 Adaptability of General Public to Driving Conditions	136
6.3.7 Accessibility for disabled people	136
6.3.8 Socioeconomic	136
6.3.9 Impact on Livelihood of existing transport workers.....	137
6.3.10 Disposal of Old buses.....	138
6.3.11 Climate Change Impacts	138
6.4 ‘Site Specific’ Impact Analysis	139
<u>Bus Depot</u>	140
6.4.1 Soil Contamination/Hazardous Substances.....	140
6.4.2 Surface Water	141
6.4.3 Wastewater	141
6.4.4 Drainage.....	141
6.4.5 Air Quality.....	141
6.4.6 Noise	143
6.4.7 Solid Waste	144
6.4.8 Damage to Community Facilities	144
6.4.9 Traffic Concerns	145
6.4.10 Health and Safety of Workers and the Public.....	145
6.4.11 Social Conflicts.....	147
6.4.12 Long Term Residual Effects	147
6.4.13 Soil Contamination/Hazardous Substances.....	147
6.4.14 Air Quality.....	148
6.4.15 Noise	149
6.4.16 Solid Waste	149
6.4.17 Health and Safety of Workers and the Public.....	149
<u>Elevated Sections</u>	150
6.4.18 Disruption to Community Utilities	150
6.4.19 Spoils Generation	150
6.4.20 Wastewater	151
6.4.21 Drainage/Flooding	151
6.4.22 Air Quality.....	151
6.4.23 Noise	152

6.4.24	Vibration	153
6.4.25	Use of Hazardous Substances	154
6.4.26	Solid Waste	154
6.4.27	Damage to Community Facilities	154
6.4.28	Health and Safety of Workers and the Public.....	155
6.4.29	Traffic Concerns	155
6.4.30	Social Conflicts.....	156
6.4.31	Wastewater	157
6.4.32	Health and Safety of Workers and the Public.....	157
6.4.33	Solid Waste	157
	<u>Tunnels & Underground Sections</u>	157
6.4.34	Disruption to Community Utilities	157
6.4.35	Spoils Generation	157
6.4.36	Land Subsidence/Geotechnical Hazards	159
6.4.37	Flooding	160
6.4.38	Surface water	160
6.4.39	Wastewater	161
6.4.40	Air Quality.....	161
6.4.41	Noise	163
6.4.42	Vibration	165
6.4.43	Use of Hazardous substances	165
6.4.44	Solid Waste	165
6.4.45	Damage to Community Utilities.....	166
6.4.46	Health and Safety of Workers and the Public.....	166
6.4.47	Traffic Concerns	168
6.4.48	Cultural and Heritage Resources	169
6.4.49	Flooding	170
6.4.50	Noise	170
6.4.51	Health and Safety of Workers and the Public.....	170
6.5	Cumulative Impacts	170
6.6	Indirect and Inducted Impacts.....	172
7	Environmental Management and Monitoring Plan	173
7.1	Introduction	173
7.2	Environmental Management Plan (EMP)	173
7.3	Objectives of EMP.....	173
7.4	Environmental Management/Monitoring and Reporting	174
7.5	Institutional Arrangements.....	175

7.5.1	Role of PDA.....	175
7.5.2	Role of Project Director	175
7.5.3	Role of Project Contractor	175
7.6	Environmental Performance Indicators.....	175
7.7	Monitoring Parameters	176
7.8	Environmental Training	176
7.8.1	Capacity Building and Training	176
7.9	Environmental Management Costs.....	182
8	Public Consultation and Information Disclosure.....	287
8.1	Introduction	287
8.2	Objective of Consultations	288
8.3	Identification of Main Stakeholders	288
8.4	Approach for Public Consultation	289
8.5	Consultations	289
8.6	Key Concerns	290
8.7	Addressal of Stakeholder Concerns.....	330
9	Grievance Redress Mechanism.....	333
9.1	General	333
9.1.1	FIRST TIER OF GRM.....	334
9.1.2	SECOND TIER OF GRM.....	335
9.1.3	THIRD TIER OF GRM	336
10	Conclusions and Recommendations	337
11	References	338

ANNEXES

Annex A	Rapid Environmental Assessment Checklist
Annex B	NEQS Guidelines
Annex C	Photographs of Public Consultations
Annex D	Noise Levels at Key Receptors during Operation Phase
Annex E	Noise Levels at Key Receptors during Construction Phase
Annex F	Post Mitigation Noise Levels at Key Receptors during Construction Phase
Annex G	List of Participants of Public Consultations
Annex H	Photographs of Landmarks along Project Corridor
Annex I	Sample Air Dispersion Model output files
Annex J	Sample Ambient Monitoring Results
Annex K	Photographs of Air Quality & Noise Monitoring
Annex L	NOC from Department of Archaeology
Annex M	Occupational Health and Safety Plan
Annex N	Emergency Response Plan
Annex O	Archaeological 'Chance Find' Procedure
Annex P	Scope of Work for Structural Assessment of Bala Hisar Fort

List of Figures

Figure 1.1: Key Map of Proposed Project.....	3
Figure 2.1: EIA Review and Approval Process of Pakistan EPAs	11
Figure 3.1: Proposed BRT Alignment	20
Figure 3.2: Off-Corridor Bus Stop Locations	24
Figure 3.3: Bus Shelter dimensions for Off-Corridor Bus Stop	26
Figure 3.4: Illustration of a Sub-Stop	27
Figure 3.5: BRT Station Key Design Components	28
Figure 3.6: One Sub-Stop Station Configuration	29
Figure 3.7: Two Sub-Stop Station Configuration	30
Figure 3.8: Two Sub-Stops Station Configuration with offset module	30
Figure 3.9: Two Sub-Stops Station Configuration with split Module	31
Figure 3.10: Conceptual design of BRT stations	32
Figure 3.11: Detailed Station Area	33
Figure 3.12: Station Dimensions for at-grade station.....	34
Figure 3.13: Station Dimensions for Elevated BRT	35
Figure 3.14: Bus Configuration (9 meters)	37
Figure 3.15: Bus Configuration (12 meters)	38
Figure 3.16: Different BRT Access Points	39
Figure 3.17: Hashtnagri Underpass Market.....	40
Figure 3.18: Firdous Cinema Underpass	40
Figure 3.19: Pedestrian Tunnel near Jahangeer Abad Road	41
Figure 3.20: Standard Depot Layout	42
Figure 3.21: Proposed BRT Depot Locations.....	44
Figure 3.22: Layout of Depot 1 at Hayatabad	45
Figure 3.23: Layout of Depot 2 at Chamkani	46
Figure 3.24: Location of Staging Facility.....	48
Figure 3.25: Layout of Staging Facility at Dabgari.....	49

Figure 3.26: Workshop Layout	51
Figure 3.27: Access for Direct Service at BRT Station	54
Figure 3.28: BRT Route Plan	56
Figure 4.1: Year round Temperature Profile of Peshawar City	60
Figure 4.2: Humidity Profile of Peshawar City	61
Figure 4.3: Wind Speed Profile of Peshawar City	61
Figure 4.4: Average Rainfall Profile of Peshawar City	62
Figure 4.5: Seismic Zones of Pakistan	63
Figure 4.6: Project Area Map of Entire Project Corridor	72
Figure 4.7: Project Area Map (BS-1 to BS-9)	73
Figure 4.8: Project Area Map (BS-8 to BS-21)	74
Figure 4.9: Project Area Map (BS-19 to BS-31)	75
Figure 4.10: Sheets Index and Bus Stations Detail	76
Figure 4.11: Key Receptors in Project Area (Sheet 1 of 13)	77
Figure 4.12: Key Receptors in Project Area (Sheet 2 of 13)	78
Figure 4.13: Key Receptors in Project Area (Sheet 3 of 13)	79
Figure 4.14: Key Receptors in Project Area (Sheet 4 of 13)	80
Figure 4.15: Key Receptors in Project Area (Sheet 5 of 13)	81
Figure 4.16: Key Receptors in Project Area (Sheet 6 of 13)	82
Figure 4.17: Key Receptors in Project Area (Sheet 7 of 13)	83
Figure 4.18: Key Receptors in Project Area (Sheet 8 of 13)	84
Figure 4.19: Key Receptors in Project Area (Sheet 9 of 13)	85
Figure 4.20: Key Receptors in Project Area (Sheet 10 of 13)	86
Figure 4.21: Key Receptors in Project Area (Sheet 11 of 13)	87
Figure 4.22: Key Receptors in Project Area (Sheet 12 of 13)	88
Figure 4.23: Key Receptors in Project Area (Sheet 13 of 13)	89
Figure 4.24: Selection of Sampling locations for Ambient Noise Monitoring	90
Figure 4.25: 24 Hourly Ambient Noise Quality Results	93

Figure 4.26: 24 Hourly Ambient Air Quality Results	94
Figure 5.1: Mass Transit Corridors identified in PFS	96
Figure 6.1: Predicted Noise levels during Construction Phase	114
Figure 6.2: Isopleths of CO (1st Highest) for 1 hourly averaged Concentrations.....	128
Figure 6.3: Isopleths of CO (1st Highest) for 8 hourly averaged Concentrations.....	129
Figure 6.4: Isopleths of PM (1st Highest) for 1 hourly averaged Concentrations.....	130
Figure 6.5: Isopleths of PM (1st Highest) for 24 hourly averaged Concentrations.....	131
Figure 6.6: Predicted Noise Levels during Operation Phase	135
Figure 7.1: Organization Chart for Environment Management/Monitoring implementation	174
Figure 9.1: Grievance Redress Mechanism	336

LIST OF TABLES

Table 2.1: Environmental Guidelines and Legislations	7
Table 2.2: ADB Policy Principles	12
Table 2.3: ADB Environmental Assessment Requirements for Category ‘A’ projects	14
Table 2.4: Comparison of International and local Air Quality Standards	15
Table 2.5: Comparison of International and Local Noise Standards	17
Table 3.1: Proposed BRT Station Information	21
Table 3.2: Proposed BRT Route length and details	55
Table 3.3: Construction Equipment Noise Ranges dB(A)	58
Table 4.1: Existing Fauna in Peshawar Valley	64
Table 4.2: Damage Thresholds from Construction related Vibration Effects	69
Table 5.1: City Center Alignment Assessment Summary	97
Table 5.2: Comparison of NPV of Total Incremental Costs: CNG versus Diesel	100
Table 5.3: Comparison of ‘At Grade’ versus ‘Elevated’ Sections	101
Table 6.1: Summary of Possible Impacts during Construction Phase	105
Table 6.2: Control measures for Fugitive Dust emissions	108
Table 6.3: Noise Level Scenarios from Construction Machinery	111
Table 6.4: Summary of Possible Impacts during Operation Phase	123
Table 6.5: BREEZE Model Input Parameters & Assumptions	126
Table 6.6: Minimum and Maximum Predicted Concentrations of CO and PM	126
Table 6.7: Averaged Predicted Concentrations of CO and PM	127
Table 6.8: Greenhouse Gas (GHG) Emission Reductions from BRT Project Operation	139
Table 7.1: Pre-Construction Monitoring Requirements	177
Table 7.2: Construction Phase Monitoring Requirements	178
Table 7.3: Operation Phase Monitoring Requirements	180
Table 7.4: Capacity Development and Training Programme	182
Table 7.5: Annual Cost Estimates for ‘Pre-Construction Phase’ Environmental Monitoring	183

Table 7.6: Annual Cost Estimates for ‘Construction Phase’ Environmental Monitoring	183
Table 7.7: Annual Cost Estimates for ‘Operation Phase’ Environmental Monitoring	183
Table 7.8: Estimated Costs for EMP Implementation	184
Table 7.9: Environmental Management and Monitoring Plan	185
Table 7.10: ‘Site Specific’ Environmental Management and Monitoring Plan	205
Table 8.1: Summary of Public Consultations	293
Table 8.2: Summary of Concerns Raised by DPs / Stakeholder, and their Addressal	330

EXECUTIVE SUMMARY

1. The proposed project consists of the development of a bus rapid transit (BRT) corridor with a total length of 30.8 km to be constructed on a phase wise basis in Peshawar city. The first phase will involve construction of 25.8 km of the BRT corridor while 5 km will be constructed in the second phase. The BRT corridor will consist of a total of 31 stations and will run from Chamkani to Hayatabad.
2. The project is of high significance considering the urgent need for improving the urban transport landscape of Peshawar city. This project is expected to contribute towards the economic and social development of the region and pave the way for uplift of this entire region through generation of economic opportunities and increased investor interest in Peshawar.
3. The BRT project can be used as an opportunity to restructure the entire public transport industry, from Minibus and Bedford bus, Wagon and Suzuki up to Qingqi. With the BRT implemented, the government will have more bargaining power to reform the public transport in Peshawar. BRT could be used as an opportunity to bring professional bus operating companies to run in Peshawar and show the best practice model to the existing operators.
4. A positive impact on the environment is expected from the proposed BRT project due to the use of a cleaner and more fuel efficient fleet being used in the BRT as well as reduction in vehicular exhaust emissions due to reduction in kilometers travelled by private vehicles.
5. There are also a number of economic benefits associated with the proposed BRT project due to the time savings of both the public transport and private vehicle passengers. Also, since there is no formal bus industry as yet in the city, the BRT will open up more formal employment associated with the BRT such as security guards, bus drivers, mechanics etc.
6. In comparison to rail based mass transit system, BRT offers flexibility and is easy to expand. Dedicated BRT lanes can increase bus travel speed significantly. But most importantly, with BRT, buses can operate inside and outside the BRT corridor, allowing rapid citywide coverage.
7. Existing primary and secondary data on ambient noise levels, water resources, flora, fauna and information from the preliminary feasibility study conducted for this and other projects of similar nature were collected, reviewed, and analyzed. Extensive field visits to the project area were undertaken and key receptors and stakeholders within the project area (100 meters on either side of the project corridor) were identified and consulted.
8. Detailed ambient air and noise monitoring at different points along the project corridor have been conducted. Apart from PM₁₀, all other pollutants are within acceptable NEQS limits. The ambient noise levels are generally high at both day and night times and are exceeding the NEQS limits. However, any incremental impacts resulting from BRT construction and operation have been estimated through air dispersion and noise modeling

simulations and it has been predicted that the proposed BRT project will not pose a significant adverse impact on the key receptors in the project area.

9. Since the project corridor consists of certain highly congested areas with a concentration of receptors in the vicinity of the project sites where construction activity will be conducted, thus necessary mitigation measures have been proposed wherever felt necessary to mitigate any possible impacts. In addition, site specific mitigation measures have also been proposed for certain environmentally critical infrastructure (tunnels, elevated sections and bus depots) that will be developed as a part of the project development.

10. Thus, although limited in magnitude, there are some possibilities of producing adverse environmental impacts, which shall be mitigated at the earliest. The preservation of air quality by limiting dust and toxic gas emissions from equipment and vehicle exhaust, limiting of noise levels particularly during the construction phase of the project, proper disposal of solid and liquid waste through sewage system development, as well as ensuring community safety are some of the measures prescribed for the mitigation of impacts. Similarly, construction activities in close and active participation of communities in the vicinity of the construction sites along the project corridor and capacity development of all project staff to implement recommended mitigation measures are also prescribed.

11. The project will have significant resettlement impacts on 535 households due to acquisition of 117 Kanal (14.6 acres/5.9 hectares) of private arable land, demolition of permanent structures of 2 underpass markets having 84 shops, 4 commercial toilets, 3 kiosks and 12 stores, a horizontal structure of 14 shops, one store room of a business, and two mosques (built in the ROW).

12. It will also impact the livelihood of 8 non-titleholder of agriculture land, 86 formal businesses/shopkeepers among them is a female headed household whose business is run by her brother; 235 non-titleholder vendors operating road side micro enterprises in the ROW, among them are 2 disabled, 99 employees of formal businesses and their 49 salaried relatives of formal businesses, having separate households; 4 security guards of underpass markets, and one khateeb (prayer leader) of a mosque.

13. All formal and micro businesses need relocation of their businesses to alternative sites. The leaseholders of 79 shops and owners of 14 shops will lose income from monthly rent of the commercial structures. Among 535 AHs, 349 are vulnerable with 246 severely affected that need additional resettlement and rehabilitation assistance.

14. Furthermore, the BRT project will play a key role in reduction of CO₂ emissions from vehicular movement in Peshawar city with almost 31,000 tons of reduction in CO₂ emissions expected in the first year of operation and 62,000 tons of reduction in CO₂ emissions expected by the year 2026.

15. An action plan with clear roles and responsibilities of stakeholders has been provided in the report. The PDA, Contractors and the Construction Supervision Consultant are the major stakeholders responsible for the action plan. The action plan must be implemented prior to commencement of construction work.

16. Mitigation will be assured by a program of environmental monitoring conducted during construction and operation to ensure that all measures in the EMP are implemented and to determine whether the environment is protected as intended. This will include observations on- and off-site, document checks, and interviews with workers and beneficiaries, and any requirements for remedial action will be reported. The engaging of external environmental monitoring consultants for ensuring efficient and effective implementation of the mitigation measures is also under consideration.

17. Therefore, the proposed BRT development is likely to cause certain significant adverse impacts, mostly during the construction phase, that shall be mitigated through necessary measures. The potential adverse impacts that are associated with design, construction, and operation can be mitigated to standard levels without difficulty through proper engineering design and the incorporation or application of recommended mitigation measures and procedures. Based on the findings of this EIA study, the classification of the Project as Category 'A' is confirmed. It is concluded that the proposed project should proceed, with appropriate mitigation measures and monitoring programs identified in the EIA.

18. As a result of this EIA study, it has been determined that any adverse or harmful impacts shall be effectively mitigated through implementation of necessary measures and through regular monitoring. The project falls under the Category 'A' of ADB's Guidelines and thus an EIA has been prepared for the proposed project.

1 Introduction

1.1 Project Background

1. In 2013, the provincial government of Khyber Pakhtunkhwa (GoKP) requested the City Development Initiative for Asia (CDIA) to help improve Peshawar's urban transport system and provide technical and financial support to implement mass-transit solutions and strengthen institutions and organizations managing the urban transport sector.

In response to this request, CDIA undertook an Urban Transport Pre-Feasibility Study (PFS). Completed in May 2014, this technical assistance developed a 20-year urban transport strategy with a 10-year action plan. The PFS also conducted a basic travel demand survey, identifying the east-west and north-south priority axis to be developed as mass-transit corridors and analyzed cost-efficiency of different mass-transit modes on those corridors. Based on available data and generic estimates, the PFS finally recommended the development of Bus Rapid Transit (BRT) on corridor 2 (GT Road from Chamkani to Karkhano) as the most viable option and priority investment under the action plan.

2. On the basis of the PFS, GoKP requested the Asian Development Bank (ADB) to provide a PPTA to undertake a feasibility study for the recommended BRT corridor. Pursuant to this request, ADB approved a \$1.5 million PPTA grant and the PPTA consultants presented the project concept and different options for the BRT corridor alignment. The BRT on corridor 2 was agreed to preferably be left at-grade as much as possible to ensure better integration and flexibility with other future BRT corridors, limit the capital investment cost, and promote universal accessibility.

The ADB Project will restructure the entire BRT corridor, from façade-to-façade, with the objective to address parking and encroachment issues, improve the surrounding walking environment, share public space equitably between pedestrians, public transport and private modes, and provide a more pleasant and beautiful urban environment.

3. This Environmental Impact Assessment (EIA) report presents the screening of potential environmental impacts of the proposed project and contains the mitigation measures in order to eliminate or reduce the negative impacts to an acceptable level, describes the institutional requirements and provides an environmental management plan.

The key map of the proposed project is provided as Figure 1.1 below.

1.2 Environmental Category of the Project

4. According to ADB's Safeguard Policy Statement (SPS) 2009, a Rapid Environmental Assessment (REA) Checklist was prepared (ANNEX-I). The Pakistan Environmental Protection Agency's "Guidelines for the Preparation and Review of Environmental Reports (2000)" were also consulted. Based on the initial findings, it was ascertained

that certain adverse environmental impacts are expected due to development of the proposed bus rapid transit corridor project, and thus the subject project is considered environmentally “A” category. Therefore, an EIA has been conducted.

1.3 Methodology of EIA Study

The following methodology was employed for this EIA:

5. Existing secondary data such as baseline information on water resources, flora, fauna and information from the pre-feasibility study conducted for this and other projects of similar nature were collected, reviewed, and analyzed.
6. Field visits were undertaken consisting of preliminary scoping through survey and assessment activities to establish the potential impacts and categorization of activities and the Rapid Environmental Assessment (REA) was completed. The key receptors and stakeholders within the project area (100 meters on either side of the project alignment) were identified.
7. Primary data collection such as ambient noise levels and ambient air quality at the key receptor locations within 100 meters on either side of the project alignment was conducted.
8. Public consultations (PC) were carried out with all key stakeholders, particularly local businesses, management of hospitals and educational institutions residing in the project area, local communities, government and local government bodies in line with ADB’s “Safeguard Policy Statement (SPS) – June 2009”/ Environmental Assessment Guidelines. Under ADB requirements, the environmental assessment process must also include meaningful public consultations during the completion of the study. In this EIA, the Public Consultation process included verbal disclosure regarding the project development as a vehicle for discussion.
9. The significance of impacts from the proposed project were then assessed and for those impacts requiring mitigation, suitable measures were proposed to reduce impacts to within acceptable limits as per local and international applicable regulations.
10. A detailed environmental management and monitoring plan was developed to ensure compliance to the proposed measures during the project development.



Index

Summary of the Report
for the North East of England

Summary of the Report

Key Map

Study Area

Legend

Map of the Study Area



2 Policy and Legal Framework

2.1 General

11. This section provides an overview of the policy framework and national legislation that applies to the proposed project. The project is expected to comply with all national legislation relating to the environment in Pakistan, and to obtain all the regulatory clearances required.

2.2 National Policy and Legal Framework

12. The Pakistan National Conservation Strategy (NCS) that was approved by the federal cabinet in March 1992 is the principal policy document on environmental issues in the country (EUAD/IUCN, 1992). The NCS outlines the country's primary approach towards encouraging sustainable development, conserving natural resources, and improving efficiency in the use and management of resources. The NCS has 68 specific programs in 14 core areas in which policy intervention is considered crucial for the preservation of Pakistan's natural and physical environment. The core areas that are relevant in the context of the proposed project are pollution prevention and abatement and increasing energy efficiency while conserving biodiversity.
13. Prior to the adoption of the 18th Constitutional Amendment, the Pakistan Environmental Protection Act (PEPA) 1997 was the governing law for environmental conservation in the country. Under PEPA 1997, the Pakistan Environmental Protection Council (PEPC) and Pak EPA were primarily responsible for administering PEPA 1997. Post the adoption of the 18th Constitutional Amendment in 2011, the subject of environment was devolved and the provinces have been empowered for environmental protection and conservation. Subsequently, the Punjab government amended PEPA 1997 as Punjab Environmental Protection (Amendment) Act 2012, and Punjab EPA (PEPA) is responsible for ensuring the implementation of provisions of the Act in Punjab's territorial jurisdiction. PEPA is also required to ensure compliance with the NEQS and establish monitoring and evaluation systems.

2.3 Regulations for Environmental Assessment, Pakistan EPA

14. Under Section 12 (and subsequent amendment) of the PEPA (1997), a project falling under any category specified in Schedule I of the IEE/EIA Regulations (SRO 339 (10/2000), requires the proponent of the project to file an IEE with the concerned provincial EPA. Projects falling under any category specified in Schedule II require the proponent to file an EIA with the provincial agency, which is responsible for its review and accordance of approval or request any additional information deemed necessary.

2.4 Regulatory Clearances, KPK EPA

15. In accordance with provincial regulatory requirements, an IEE/EIA satisfying the requirements of the KPK Environmental Protection Act (2014) is to be submitted to

KP environmental protection agency (KP-EPA) for review and approval, and subsequent issuance of NOC before the commencement of construction.

2.5 Guidelines for Environmental Assessment, Pakistan EPA

16. The Pak-EPA has published a set of environmental guidelines for conducting environmental assessments and the environmental management of different types of development projects. The guidelines that are relevant to the proposed project are listed below:

- Guidelines for the Preparation and Review of Environmental Reports, Pakistan, EPA1997;
- Guidelines for Public Consultations; Pakistan EPA May 1997;

2.6 National Environmental Quality Standards (NEQS) 2000

17. The National Environmental Quality Standards (NEQS), 2000, specify the following standards:

- Maximum allowable concentration of pollutants (32 parameters) in municipal and liquid industrial effluents discharged to inland waters, sewage treatment facilities, and the sea (three separate sets of numbers);
- Maximum allowable concentration of pollutants (16 parameters) in gaseous emissions from industrial sources;
- Maximum allowable concentration of pollutants (two parameters) in gaseous emissions from vehicle exhaust and noise emission from vehicles;
- Maximum allowable noise levels from vehicles;

18. These standards apply to the gaseous emissions and liquid effluents discharged by batching plants, campsites and construction machinery. The standards for vehicles will apply during the construction as well as operation phase of the project. Standards for ambient air quality have also been prescribed.

2.7 ADB's Safeguard Policy Statement (SPS), 2009

19. The Asian Development Bank's Safeguard Policy Statement (SPS) 2009 requires that environmental considerations be incorporated into ADB's funded project to ensure that the project will have minimal environmental impacts and be environmentally sound. Occupational health & safety of the local population should also be addressed as well as the project workers as stated in SPS. A Grievance Redress Mechanism (GRM) to receive application and facilitate resolution of affected peoples' concerns, complaints, and grievances about the project's environmental performance is also established and provided in Chapter 8.

20. All loans and investments are subject to categorization to determine environmental assessment requirements. Categorization is to be undertaken using Rapid Environmental Assessment (REA) checklists, consisting of questions relating to (i) the sensitivity and vulnerability of environmental resources in project area, and (ii) the

potential for the project to cause significant adverse environmental impacts. Projects are classified into one of the following environmental categories:

Category A: A proposed project is classified as category A if it is likely to have significant adverse environmental impacts that are irreversible, diverse or unprecedented. These impacts may affect an area larger than the sites or facilities subject to physical works. An environmental impact assessment (EIA) is required.

Category B: A proposed project is classified as category B if its potential adverse environmental impacts are less adverse than those of category A projects. These impacts are site-specific, few if any of them are irreversible, and in most cases mitigation measures can be designed more readily than for category A projects. An initial environmental examination (IEE) is required.

Category C: A proposed project is classified as category C if it is likely to have minimal or no adverse environmental impacts. No environmental assessment is required although environmental implications need to be reviewed.

Category FI: A proposed project is classified as category FI if it involves investment of ADB funds to or through a financial intermediary (FI).

21. As a result of the completion of the REA checklist, provided as ANNEX A, the project has been classified as Category “A” and thus a detailed and comprehensive EIA study has been prepared including the EMP.

2.8 ADB’s Public Communication Policy 2011

22. The PCP aims to enhance stakeholders’ trust in and ability to engage with ADB, and thereby increase the development impact of ADB operations. The policy promotes transparency, accountability, and participatory development. It establishes the disclosure requirements for documents ADB produces or requires to be produced.

2.9 ADB’s Accountability Mechanism Policy 2012

23. The objectives of the Accountability Mechanism is providing an independent and effective forum for people adversely affected by ADB-assisted projects to voice their concerns and seek solutions to their problems, and to request compliance review of the alleged noncompliance by ADB with its operational policies and procedures that may have caused, or is likely to cause, them direct and material harm. The Accountability Mechanism a “last resort” mechanism.

2.10 Interaction with Other Agencies

24. The Peshawar Development Authority (PDA), GoKPK is responsible for ensuring that the project complies with the laws and regulations controlling the environmental concerns of the bus rapid transit (BRT) construction and operation and that all

preconstruction requisites, such as permits and clearances are met. This section describes the nature of the relationship between the PDA and concerned departments.

2.11 Provincial EPAs

25. PDA will be responsible for providing the complete environmental documentation required by the KP-EPA and remain committed to the approved project design. No deviation is permitted during project implementation without prior and explicit permission of the KP-EPA.

2.12 Provincial Departments of Forests and Wildlife

26. No uprooting or clearing of trees is expected for the proposed project. However, any removed trees or vegetation under private ownership will be compensated as per provision that in case of disruption to vegetation or trees, the project contractor will be responsible for acquiring a 'No-Objection Certificate' (NOC) from the concerned forest department. The application for an NOC will need to be endorsed by the PDA.

2.13 Provincial Governments

27. The PDA and its contractors must ensure that the project meets the criteria of provincial/district governments as related to the establishment of construction camps and plants, and the safe disposal of wastewater, solid waste, and toxic materials. PDA will coordinate and monitor environment related issues.

2.14 Other Environment Related Legislations

28. Table 2.1 provides a summary of other legislations, guidelines, conventions and corporate requirements.

Table 2.1: Environmental Guidelines and Legislations

Legislation/Guideline	Description
National Environmental Policy (2005) (NEP)	NEP is the primary policy of Government of Pakistan addressing environmental issues. The broad Goal of NEP is, “to protect, conserve and restore Pakistan’s environment in order to improve the quality of life of the citizens through sustainable development”. The NEP identifies a set of sectoral and cross-sectoral guidelines to achieve its goal of sustainable development. It also suggests various policy instruments to overcome the environmental problems throughout the country.
Land Acquisition Act, 1894 Including Later Amendments	The Land Acquisition Act, 1894, is a “law for the acquisition of land needed for public purposes and for companies and for determining the amount of compensation to be paid on account of such acquisition”. The exercise of the power of acquisition has been limited to public purposes. The principles laid down for the determination of compensation, as clarified by judicial pronouncements made from time to time, reflect the anxiety of the law-giver to compensate those who have been deprived of property, adequately. No land acquisition is expected for the proposed project. However, in case any land acquisition does become necessary, the

Legislation/Guideline	Description
	land needed for the construction of the project will be acquired under normal conditions based on prevailing market prices or negotiated prices between PDA and owners of the land. Section 17(4) of the LAA will not be used in the absence of an emergency. Instead, the land will be purchased under willing-seller willing-buyer deal at agreed upon market rates and the seller will have the option not to sell the land, in case an acceptable deal for both the parties is not reached.
The Forest Act (1927)	<p>The Act empowers the provincial forest departments to declare any forest area as reserved or protected. It empowers the provincial forest departments to prohibit the clearing of forest for cultivation, grazing, hunting, removing forest produce, quarrying and felling, lopping and topping of trees, branches in reserved and protected forests.</p> <p>The proposed project is urban in nature and thus no protected forest is situated in the Project area.</p>
Khyber Pakhtunkhwa Wildlife and Biodiversity Act, 2015	It empowers the government to declare certain areas reserved for the protection of wildlife and control activities within in these areas. It also provides protection to endangered species of wildlife. As no activities are planned in these areas, no provision of this law is applicable to the proposed project.
The KPK Antiquities Act (2016)	It ensures the protection, preservation, development and maintenance of antiquities in the province of KPK. The Act defines “antiquities” as ancient products of human activity, historical sites, or sites of anthropological or cultural interest, national monuments, etc. The Act is designed to protect these antiquities from destruction, theft, negligence, unlawful excavation, trade, and export. The law prohibits new construction in the proximity of a protected antiquity and empowers the GoKPK to prohibit excavation in any area that may contain articles of archaeological significance. Under the Act, the subproject proponents are obligated to ensure that no activity is undertaken in the proximity of a protected antiquity, report to the Department of Archaeology, GoKPK, any archaeological discovery made during the course of the project.
Pakistan Penal Code (1860)	It authorizes fines, imprisonment or both for voluntary corruption or fouling of public springs or reservoirs so as to make them less fit for ordinary use.
NATIONAL ENVIRONMENTAL AND CONSERVATION STRATEGIES	
National Conservation Strategy	Before the approval of NEP, the National Conservation Strategy (NCS) was considered as the Government’s primary policy document on national environmental issues. At the moment, this strategy just exists as a national conservation program. The NCS identifies 14 core areas including conservation of biodiversity, pollution prevention and abatement, soil and water conservation and preservation of cultural heritage and recommends immediate attention to these core areas.
Biodiversity Action Plan	The plan recognizes IEE/EIA as an effective tool for identifying and assessing the effects of a proposed operation on biodiversity.
Environment and Conservation	There is a well-established framework for environmental management in Pakistan. The Ministry of Environment deals with environment and biological resources. Within the ministry, the NCS unit established in 1992 is responsible for overseeing the implementation of the strategy. Two organizations, the Pakistan Environmental Protection Council (PEPC) and the Pak EPA are

Legislation/Guideline	Description
	primarily responsible for administering the provisions of the PEPA, 1997. The PEPC oversees the functioning of the Pak EPA. Its members include representatives of the government, industry, non-governmental organizations and the private sector. The Pak EPA is required to ensure compliance with the NEQS, establish monitoring and evaluation systems, and both identify the need to and institution of legislations whenever necessary. It is thus the primary implementing agency in the hierarchy. The respective provinces have formed the Provincial Environmental Protection Agencies.
INTERNATIONAL CONVENTIONS	
The Convention on Conservation of Migratory Species of Wild Animals (1981.21)	The Convention requires countries to take action to avoid endangering migratory species. The term "migratory species" refers to the species of wild animals, a significant proportion of whose members cyclically and predictably cross one or more national jurisdictional boundaries. The parties are also required to promote or cooperate with other countries in matters of research on migratory species. The proposed project is being developed in a completely urban landscape and thus there are no endangered species of plant life or animal life in the vicinity of the Project.
Convention on International Trade in Endangered Species of Wild Fauna and Flora (1973)	The convention requires Pakistan to impose strict regulation (including penalization, confiscation of the specimen) regarding trade of all species threatened with extinction or that may become so, in order not to endanger their survival further.
International Union for Conservation of Nature and Natural Resources Red List (2000)	Lists wildlife species experiencing various levels of threats internationally. Some of the species indicated in the IUCN red list are also present in the wetlands of Pakistan.
INTERNATIONAL ENVIRONMENTAL GUIDELINES	
ADB's Safeguard Policy Statement (SPS), 2009	ADB's Safeguard Policy Statement (SPS), 2009 provides guidelines for environmental assessments of development projects. These guidelines help prospective projects identify impacts they will have on various environmental receptors. The guidelines call for carrying out EIAs or IEEs of projects based on severity of their impacts.

2.15 Comparison of International and Local Environmental Legislations

29. The ADB SPS requires application of pollution prevention and control technologies and practices consistent with international good practice, as reflected in internationally recognized standards. The SPS states that when host country regulations differ from these standards, the EA will achieve whichever is more stringent.
30. A comparison of applicable local and international guidelines for ambient air quality has been provided in Table 2.4 below. In the case of most pollutants, the NEQS standards for ambient air quality are more stringent in comparison to USEPA and WHO/IFC standards. The applicable and most stringent parameters for each respective pollutant are highlighted in green.

31. Similar to the standards for air quality, the comparison of noise standards provided in Table 2.5 clearly shows that NEQS standards for noise are more stringent in comparison to the WHO/IFC standards. The only exception is the daytime noise level standard for Industrial areas where the World Bank/IFC standard is more stringent (70 dB(A)) in comparison to NEQS (75 dB(A)) and so for this particular parameter, the WHO/IFC standard will be used. Apart from this one exception, the NEQS standards have been used for the proposed BRT project.
32. As far as regulations regarding other environmental parameters are concerned such as acceptable effluent disposal parameters, the local regulations i.e. NEQS take precedence over any other international regulations such as WHO/IFC.


2.16 Implications of national policies and regulations on proposed project

33. The Pak-EPA formulated regulations in 2000 for 'Review of IEE and EIA' which categorise development projects under three schedules-Schedules I, II and III. Projects are classified on the basis of expected degree and magnitude of environmental impacts and the level of environmental assessment required is determined from the schedule under which the project is categorised.
34. The projects listed in Schedule-I include those where the range of environmental issues is comparatively narrow and the issues can be understood and managed through less extensive analysis. Schedule-I projects require an IEE to be conducted, rather than a full-fledged EIA, provided that the project is not located in an environmentally sensitive area.
35. The projects listed in Schedule-II are generally major projects and have the potential to affect a large number of people in addition to significant adverse environmental impacts. The impacts of projects included in Schedule-II may be irreversible and could lead to significant changes in land use and the social, physical and biological environments. The proposed BRT project has been categorized as Schedule II and requires an EIA.
36. The Peshawar Development Authority (PDA), being the Executing Agency for the Project is responsible for management of project impacts, and have to undertake the commitments and mitigation measures proposed in this environmental report and in the subsequent review and approval conditions.
37. According to the regulations, no construction, preliminary or otherwise, relating to the project shall be undertaken until and unless approval of the Environmental Impact Assessment Report has been issued by the KP EPA.
38. The PDA will submit the EIA Report on a prescribed application along with the processing fee to KP EPA. After submission of the EIA report, a thirty (30) day period for public comments will be provided. The assessment will be completed within a period of ninety (90) days from receipt of the complete documents, and earlier than this wherever practicable. Following the completion of public hearing, if required, and

the provision of any further data from the proponent, the decision shall be made and conveyed after thirty days thereafter.

39. The EIA approval process as per environmental legislation applicable in Pakistan is summarized in Figure 2.1 below.

Figure 2.1: EIA Review and Approval Process of Pakistan EPAs



2.17 Implications of ADB policies on proposed project

40. The objectives of ADB's safeguards are to:

- avoid adverse impacts of projects on the environment and affected people, where possible;
- minimize, mitigate, and/or compensate for adverse project impacts on the environment and affected people when avoidance is not possible; and
- help borrowers/clients to strengthen their safeguard systems.

41. ADB's SPS sets out the policy objectives, scope and triggers, and principles for three key safeguard areas:

- environmental safeguards,
- involuntary resettlement safeguards, and
- Indigenous Peoples safeguards.

42. The objective of the environmental safeguards is to ensure the environmental soundness and sustainability of projects and to support the integration of environmental considerations into the project decision-making process. ADB's policy principles are summarized in Table 2.2 below.

Table 2.2: ADB Policy Principles

	Policy principle	Summary
1	Screening and categorization	Screening process initiated early to determine the appropriate extent and type of environmental assessment.
2	Environmental assessment	Conduct an environmental assessment to identify potential impacts and risks in the context of the project's area of influence.
3	Alternatives	Examine alternatives to the project's location, design, technology, and components and their potential environmental and social impacts, including no project alternative.
4	Impact mitigation	Avoid, and where avoidance is not possible, minimize, mitigate, and/or offset adverse impacts and enhance positive impacts. Prepare an environmental management plan (EMP).
5	Public consultations	Carry out meaningful consultation with affected people and facilitate their informed participation.

		Involve stakeholders early in the project preparation process and ensure that their views and concerns are made known to and understood by decision makers and taken into account. Continue consultations with stakeholders throughout project implementation. Establish a grievance redress mechanism.
6	Disclosure of environmental assessment	Disclose a draft environmental assessment in a timely manner, in an accessible place and in a form and language(s) understandable to stakeholders. Disclose the final environmental assessment to stakeholders.
7	Environmental management plan	Implement the EMP and monitor its effectiveness. Document monitoring results, and disclose monitoring reports.
8	Biodiversity	Do not implement project activities in areas of critical habitats.
9	Pollution prevention	Apply pollution prevention and control technologies and practices consistent with international good practices. Adopt cleaner production processes and good energy efficiency practices. Avoid pollution, or, when avoidance is not possible, minimize or control the intensity or load of pollutant emissions and discharges. Avoid the use of hazardous materials subject to international bans or phaseouts.
10	Occupational health and safety Community safety.	Provide workers with safe and healthy working conditions and prevent accidents, injuries, and disease. Establish preventive and emergency preparedness and response measures to avoid, and where avoidance is not possible, to minimize, adverse impacts and risks to the health and safety of local communities
11	Physical cultural resources	Conserve physical cultural resources and avoid destroying or damaging them. Provide for the use of “chance find” procedures.

43. The overview of the ADB environmental assessment and review process for Category ‘A’ projects is provided in Figure 2.1 below. Category ‘A’ projects have the most stringent requirements and need the highest level of effort and resources.

44. The basic environmental assessment requirements for Category ‘A’ projects are provided in Table 2.3 below.

Table 2.3: ADB Environmental Assessment Requirements for Category ‘A’ projects

Aspect	Environmental Assessment & Management Requirements
Project processing	
Reporting	<ul style="list-style-type: none"> ▪ Prepare full-scale environmental impact assessment (EIA)
Public consultations	<ul style="list-style-type: none"> ▪ Conduct consultations at the early stage of EIA field work and when the draft EIA report is available during project preparation, and before project appraisal by ADB.
Disclosure of environmental assessment report	<ul style="list-style-type: none"> ▪ Disclose draft environmental impact assessment reports at least 120 days before Board consideration.
Project implementation	
Reporting	Submit semiannual reports during project construction, and annual reports during project operation to ADB for disclosure.

Table 2.4: Comparison of International and local Air Quality Standards

Pollutants	USEPA		WHO/IFC		Pak. NEQS	
	Avg. Time	Standard	Avg. Time	Standard	Avg. Time	Standard
SO ₂	3 hrs	0.5 ppm	24 hr	20 ug/m ³	Annual Mean	80 ug/m ³
	1 hr	75 ppb	10 min	500 ug/m ³	24 hrs	120 ug/m ³
CO	8 hrs	9 ppm (11 mg/m ³)	-	-	8 hrs	5 mg/m ³
	1 hr	35 ppm (43 mg/m ³)			1 hr	10 mg/m ³
NO ₂	Annual Mean	100 ug/m ³ (53 ppb)	1 yr	40 ug/m ³	Annual Mean	40 ug/m ³
	1 hr	100 ppb	1 hr	200 ug/m ³	24 hrs	80 ug/m ³
O ₃	8 hrs	0.07ppm (148 ug/m ³)	8 hrs	100 ug/m ³	1 hr	130 ug/m ³
TSP	-	-	-	-	Annual Mean	360 ug/m ³
					24 hrs	500 ug/m ³
PM ₁₀	24 hrs	150 ug/m ³	1 yr	20 ug/m ³	Annual Mean	120 ug/m ³

			24 hr	50 ug/m ³	24 hrs	150 ug/m ³
PM _{2.5}	Annual Mean 24 hrs	15 ug/m ³ 35 ug/m ³	1 yr 24 hr	10 ug/m ³ 25 ug/m ³	Annual Average 24 hrs 1 hr	15 ug/m ³ 35 ug/m ³ 15 ug/m ³

Table 2.5: Comparison of International and Local Noise Standards

Category of Area/Zone	Limit in dB(A) Leq			
	NEQS		WHO/IFC	
	Day Time	Night Time	Day Time	Night Time
Residential area (A)	55	45	55	45
Commercial area (B)	65	55	70	70
Industrial area (C)	75	65	70	70
Silence zone (D)	50	45	55	45

3 Description of the Project

3.1 Justification and Need for Project

45. Peshawar city is greatly in need of a good quality mass transit system for its residents, which face many logistical difficulties on a daily basis. The major issues in the Peshawar public transport sector are as follows:
- Passengers are exposed to serious accidents due to poor driving behavior, particularly during the boarding and alighting of passengers from vehicles
 - Buses are poorly maintained and lead to high consumption of fuel
 - Bus stops are non-existent and buses stop randomly whenever a passenger is standing on the route
 - Buses are overcrowded, and at times passengers are hanging on the bus railings
 - Conductors are rude and offensive
 - Drivers and conductors are at times under substance abuse while on duty
46. Although there are many reasons to justify the need for BRT in Peshawar, however the main objective of implementing the proposed project is passenger time savings. BRT lanes can increase the bus travel speed and it should be built on a corridor where many public transport users travel and endure delays.
47. The proposed BRT project is expected to mitigate congestion for car users, especially in areas where buses block entire roads to pick up passengers, which can occur practically anywhere in Peshawar. A BRT system generally gives priority to public transport passengers, but can also greatly improve conditions for mixed traffic by solving the congestion problem caused by stopping buses.
48. BRT is an effective way to use space to move people in the city. One BRT lane of 3.5 meters can move up to 10,000 passengers per hour in one direction, whereas 3 car lanes of 10 meters width can only move a total of 4,500 to 6,000 people per hour in one direction.
49. The BRT project can be used as an opportunity to restructure the entire public transport industry, from Minibus and Bedford bus, Wagon and Suzuki upto Qingqi. With the BRT implemented, the government will have more bargaining power to reform the public transport in Peshawar. BRT could be used as an opportunity to bring professional bus operating companies to run in Peshawar and show the best practice model to the existing operators.
50. A positive impact on the environment is expected from the proposed BRT project due to the use of a cleaner and more fuel efficient fleet being used in the BRT as well as

reduction in vehicular exhaust emissions due to reduction in kilometers travelled by private vehicles.

51. There are also a number of economic benefits associated with the proposed BRT project due to the time savings of both the public transport and private vehicle passengers. Also, since there is no formal bus industry as yet in the city, the BRT will open up more formal employment associated with the BRT such as security guards, bus drivers, mechanics etc.
52. In comparison to rail based mass transit system, BRT offers flexibility and is easy to expand. Dedicated BRT lanes can increase bus travel speed significantly. But most importantly, with BRT, buses can operate inside and outside the BRT corridor, allowing rapid citywide coverage.

3.2 Objectives of Project

53. The objective of this project is the development of a sustainable bus rapid transit corridor to help improve Peshawar's urban transport system and facilitate the residents of Peshawar city by resolving the logistical difficulties faced by them on a daily basis.

3.3 Proposed Project Activities

54. Construction of a total of 31 BRT stations with 3 stations built as elevated BRT stations based on the BRT alignment provided in Figure 3.1 below.
55. Operation and maintenance of the BRT to ensure project sustainability and logistical facilitation of the residents of Peshawar city.

3.4 Design of BRT

3.4.1 BRT Route

56. The station center co-ordinates, dimensions, access type as well as the expected peak hour bus frequency data per station is provided in Table 3.1 below. At the city center stations, the maximum peak hour frequency is 107 buses/hour/direction and offset stations will be required due to limited space on Saddar road.
57. Although the average distance between stations is 922 meters, but there are a few stations that are only less than 700 meters apart, while on the other hand, several stations are also quite far from each other e.g. more than 1000 meters with the physical condition of the site and a low demand profile near the stations being the determining factor.

Figure 3.1: Proposed BRT Alignment




Table 3.1: Proposed BRT Station Information

Peshawar BRT Station Design – Preferred Option						
No.	Station Name	Bus Stop ID	Distance to Next Station	Access		Station Dimension (Length x Width)
				West/South	East/North	
1	Chamkani Chowk	BS-01	1620 m	Bridge	Bridge	70m x 8m
2	Chughal Pura	BS-02	1400 m	Bridge	Bridge	70m x 8m
3	Dr Zareef Memorial School	BS-03	655 m	Bridge	Bridge	110m x 6m
4	Sethi Town	BS-04	660 m	Bridge	Bridge	110m x 6m
5	Sikandar Town	BS-05	915 m	Bridge	Bridge	110m x 6m
6	Gulbahar Square	BS-06	790 m	Bridge & PedCross	Bridge & PedCross	110m x 5m
7	Hashnagri	BS-07	530 m	Bridge	Bridge	110m x 5m
8	Qila Balahisar	BS-08	700 m	Bridge	Bridge	110m x 5m
9	Hospital Road	BS-09	590 m	At Grade Ped Cross	At Grade Ped Cross	2 x (55m x 5m)
10	Khyber Bazaar	BS-10	550 m	At Grade Ped Cross	At Grade Ped Cross	110m x 5m
11	Soekarno Square Secretariat	BS-11	640 m	-	Bridge	90m x 5m
12	Dabgari Gardens	BS-12	550 m	-	Bridge	90m x 5m

13	Railway Station	BS-13	1050 m	-	Bridge	55m x 6m
14	State Bank of Pakistan	BS-14	620 m	At Grade Ped Cross	At Grade Ped Cross	195m x 4m
15	Saddar Bazar	BS-15	840 m	At Grade Ped Cross	At Grade Ped Cross	125m x 5m
16	Mall Road	BS-16	690 m	At Grade Ped Cross	At Grade Ped Cross	110m x 5m
17	Khyber Road Airport	BS-17	1270 m	Bridge	Bridge	205m x 5m
18	Gora Qabristan	BS-18	780 m	Bridge	Bridge	205m x 4m
19	Tehkal	BS-19	780 m	Bridge	Bridge	205m x 4m
20	Tambuwaan	BS-20	800 m	Bridge	Bridge	110m x 5m
21	Abdara Road	BS-21	790 m	Bridge	Bridge	110m x 5m
22	University Town	BS-22	760 m	Bridge	Bridge	110m x 5m
23	KTH University of Peshawar	BS-23	850 m	Tunnel	Bridge	110m x 6m
24	Islamia College	BS-24	730 m	Bridge	Bridge	110m x 5m
25	Board Bazar Regi	BS-25	1250 m	Tunnel	Bridge	110m x 6m
26	Taj Abad	BS-26	920 m	Bridge	Bridge	110m x 5m
27	Hayatabad Model School	BS-27	670 m	At Grade PedCross	At Grade PedCross	55m x 5m
28	Hayatabad Phase 3	BS-28	1450 m	At Grade PedCross	At Grade PedCross	55m x 6m
29	Tatara Park	BS-29	630 m	At Grade PedCross	At Grade PedCross	55m x 6m
30	PDA Hayatabad	BS-30	680 m	At Grade PedCross	At Grade PedCross	55m x 6m
31	Cancer Hospital	BS-31	-	At Grade PedCross	At Grade PedCross	55m x 6m

58. The BRT full alignment option starts from Chamkani, near the Chamkani train station. It goes along the GT Road at-grade until the junction with Ashraf road where it will enter into a tunnel connecting both approaches of GT Road, Malik Saad Shaheed road and Cinema road. After the tunnel, the main BRT route follows Cinema Road at-grade where it goes elevated to bypass the junction with Hospital road. It stays elevated on Khyber Bazaar road and Railway road, and passes the Soekarno and Suba Chowk, the two most congested intersections in the Khyber Bazaar area. After the railway road, the elevated BRT section turns right at Anwar Saeed medical center to cross the railway station, where a BRT-only bridge will be constructed. After crossing the railway station, the BRT goes at-grade again and join Saddar road just after Peshawar Press Club.

On the preferred alignment, the BRT stays at-grade on Saddar Road, turns right to Khadim Hussein Road and Sir Sayed Road to go to Amman Chowk, where the BRT goes on BRT-only tunnel to cross Amman Chowk. The corridor continues through GT Road and Jamrud Road where it goes into an elevated BRT only corridor above a dried up river bank before the Bab-e-Peshawar Marco Polo Bridge until it joins the Habib Jalib Road towards Tatara Park and joins the Ring Road.

In this alignment option, total length of BRT is 30.8 km, in which 25.8 km will be built in Phase 1, and 5 km in Phase 2. Out of the 30 km, there are some segments that will be built elevated, which is 4.1 km long, and tunnel with 3.5 km long. This will leave the at-grade BRT segment at 23.3 km long for both phases.

3.4.2 Off-Corridor Bus Stops

59. Off-corridor bus stops are required outside the BRT corridor segments, so that the BRT buses can pick up passengers. For the 8 direct-service routes, 100 off-corridor bus stops are proposed. Since practically no existing bus stops are adequate to be used as proper bus stop, new bus stops will be constructed with consideration of three main principles; location and placement of bus stops, type of bus stops, and their physical dimensions. The proposed off-corridor bus stop locations are provided in Figure 3.2 below.
60. Bus stops will be developed wherever there is land availability and will be located along the 8 proposed direct-service routes for off-corridor segments with an average distance of 300 to 500 meters. These stops will be located where there is currently high demand from public transport (current public transport passengers boarding and alighting stations), these are generally residential or office areas or in front of markets. If there are two boarding and alighting spots nearby, the location with the higher number has been chosen as the bus stop location.

The minimum distance for a bus stop to be located from an intersection is 50 meters or 100 meters from a busier intersection with the bus stops positioned curbside and placed on the sidewalk.

61. Shelters will be used on the side mainly used for boarding and shall be 2 meters wide and 9 meters long. Generally, this is the side of the road leading towards the city

Figure 3.2: Off-Corridor Bus Stop Locations



center in the morning peak period. Passengers would have to wait for buses on this side so shelters will be required to protect them from weather exposure.

62. Also, bus poles will be used on the opposing side of shelters. On this side, many passengers alight from the buses during evening peak period and will immediately walk towards their final destination and thus will not require waiting spaces in the bus stops.

The bus shelter designs for the off-corridor bus stops are provided as Figure 3.3 below.

3.4.3 BRT Station design & Configuration

63. In designing the BRT station for Peshawar, the following key design features are proposed:

- High capacity stations
- Wide and comfortable stations
- Safe and weather protected stations
- Universally accessible
- Good passenger circulation
- Modern and create new branding image for public transport

64. The features mentioned above are important to make the proposed project successful and meet its goal to become the reliable mass transit of the city, as well as reaching the Gold Standard BRT. The proposed station design features includes the following components:

- Wide station platform (5 to 6 meter wide) and open air to allow good air circulation
- Multiple stopping bays (up to 4 buses can stop at the same time)
- Passing Lane to allow overtaking at stations
- Space for overtaking at stations with minimum length of 13 meters to allow 18-meter bus to overtake in the future
- Fast and universal access to BRT station with all kinds of access provided (stairs, elevator, escalator) and special gate to allow wheelchair to enter station
- Tactile ground surface indicator/paving for visually impaired users
- Lane separator with guard-rail

Figure 3.3: Bus Shelter dimensions for Off-Corridor Bus Stop



- Cycle lane along the corridor, complete with secured cycle parking at station and guiding rail on stairs to carry bicycle
- Real time passenger information system

The BRT key design components are shown in Figure 3.5 below.

3.4.4 Sub-Stop Concept

65. BRT stations are designed in different sizes to reflect different demands. Station saturation determines the required station size, which is represented by the number of sub-stops required. The sub-stop calculation is determined by the number of boarding and alighting passengers, bus frequency per hour per direction as well as the type of bus and number of doors used per bus. If two or more sub-stops are chosen for any station, a passing lane will be required. Each sub-stop works independently and buses stopping at the second sub-stop do not have to wait for the buses stopping on the first sub-stop to be able to move.
66. For Peshawar, 5 types of stations will be designed, with one sub-stop, two sub-stops and three modifications of two sub-stops configuration.

The illustration of the concept of a sub-stop is provided as Figure 3.4 below.

Figure 3.4: Illustration of a Sub-Stop




3.4.5 BRT Station Types

Type 1: One Sub-Stop (55 meters)

67. The station is designed in modular, with a 20-meter-long module, i.e. distance between columns is 20 meters. In station Type 1 with 1-substop, the station length is 55 meters, with a 5-meter width. It has two construction modules for the sub-stop and a 15-meter long ticketing area.


In this station type, for each direction, 2 buses can stop in two stopping bays adjacent to each other. At the beginning, only 9-meter and 12-meter buses can stop at this station type, but at the later stage, once the demand grows, 18-meter bus will be able to stop at this station, where additional station doors will be provided at reserved area at the back of the 12-meter and 9-meter doors. In this sub-stop, no

Figure 3.5: BRT Station Key Design Components



Although this station type only has 1 ticketing area, both sides of stations can be used for exit, with extra rotating door provided at the other end of the station to allow exit, as shown in the Figure 3.6 below.

Figure 3.6: One Sub-Stop Station Configuration




Type 2: Two Sub-Stops (110 meters)

68. The first type of station with two sub-stops has dimension of 110 meters long and 6 meters wide. In both sub-stops, all 3 types of buses are allowed to stop. The ticketing area is provided at both end of station, with a length of 15-meter each.

The overtaking area provided between the first and second sub-stops is used for buses to overtake. The minimum distance of the overtaking area, i.e. the area marked in green between S1 and S2 will provide a minimum of 20 to 34 meters distance between buses on different sub-stop to overtake, which will still enable the buses to dock properly on the stopping bays as shown in the Figure 3.7 below.


Figure 3.7: Two Sub-Stop Station Configuration



Type 3: Two Sub-Stops with offset configuration (205 meters)

69. An Offset station will only be placed on the locations where space might be an issue, such as on Saddar Road. With offset configuration, space required for station area will be less in width than normal station configuration, but increases in length. In offset configuration, buses on different directions will stop at different stopping locations, or in other words, each direction will have 2 sub-stops located separately. Thus, adding the total sub-stop required for this station type to 4 sub-stops in total for both directions.
70. Due to the station length, offset station is not preferable, as it increases walking time for passengers inside the station. However, a total of only 2 stations are designed with offset configuration with this type of configuration illustrated in Figure 3.8 below.

Figure 3.8: Two Sub-Stops Station Configuration with offset module




Type 4: Two Sub-Stops with split configuration (150 meters)

71. Where the road is neither wide enough for standard station nor long enough for offset station, split configuration will be used. With the split configuration, the space required for station area will be less in length than offset configuration, but this innovation will include a novel movement set up for buses, which would require clear signage to avoid any confusion.

In this configuration, all passengers going into one direction will use one sub-stop and the other sub-stop will be used for passengers going towards the other direction. This could potentially lead to two problems, overcrowding in each station during each peak period and difficulties in transferring between the two directions as shown in Figure 3.9 below.

Only 1 station is designed with split configuration, the Hospital Road station.

Figure 3.9: Two Sub-Stops Station Configuration with split Module



3.4.6 Conceptual Design of BRT Stations

72. The conceptual design of the stations is provided as Figure 3.10 below and the detailed station area is provided as Figure 3.11 below.
73. The station dimensions are shown in Figure 3.12 below. The access to the station will be provided from both sides and for some locations where pedestrian tunnel already exists, the BRT station will be connected to the nearest pedestrian tunnel for access. Also, each station will be equipped with escalators to go up, stairs and escalator for wheelchair and passengers with limited ability.
74. The station design for elevated BRT is provided as Figure 3.13 below. The elevated BRT will have two levels of platform.

Figure 3.10: Conceptual design of BRT stations




Figure 3.11: Detailed Station Area



75. The first level, which is on the same level with the pedestrian bridge will be used for the ticket office and for access to the station. The station platform will be located on the second level, where the turnstile and security check will take place. On the first level, a continuous walkway and cycle lane will be built to connect pedestrians along the corridor, underneath the elevated BRT section.
76. This will be the first BRT design in Pakistan which will accommodate cycling and walking facility along the elevated BRT section, a significant improvement from Lahore and Islamabad BRT systems.

Figure 3.12: Station Dimensions for at-grade station



This architectural section illustrates the internal structure of an elevated BRT station. The drawing shows multiple levels: a ground level at the bottom, followed by a platform level, and an upper level for the train cars. Key components labeled include the "Platform Level", "Train Level", "Passenger Area", "Waiting Area", "Bicycle Lane", and "Bike Ramp". A green dashed box highlights a specific section of the platform and stairs. Below the main section, there is a smaller, more detailed cross-section showing the structural supports and the relationship between the platform and the train cars.

3.4.7 Vehicle design and Configuration

77. Two types of buses will be introduced for Peshawar BRT: 9-meter buses and 12-meter buses. With direct-service BRT operation, the BRT buses will be plying on the smaller road outside the corridor, such as Kohat Road, Bara Road, and residential roads at Hayatabad, where 9-meter buses with 2.2-2.5-meter width would be ideal to operate. Due to the seat configuration, the 9-meter bus is proposed to have engine placed at the front. The bus configurations for the 9 meter and 12 meter buses are provided as Figures 3.14 and 3.15 respectively.

The 12-meter bus type will be used on routes with high proportion of the route passing the corridor on GT Road, with engine preferably at the rear.

78. 18-meter buses will only be proposed for Peshawar BRT for future growth at a later stage, when the demand starts to grow. The current station design already accommodates the use of 18-meter buses. This is mainly due to narrow streets and tight turning radius that most of the road along off-corridor segment.
79. All buses are proposed to use diesel-fuel engine. Although CNG supply is not scarce in Peshawar, the use of CNG buses could increase the bus price as well as the Operating and Maintenance costs. From an operational point of view, CNG poses big problems with limited tank size, which requires buses to refill every 120-150 kilometers, and the possibility of installing new CNG station close to stations will depend on the CNG pipe availability, unlike the diesel fuel where it only requires storage tank at the refueling stations.
80. With direct-service buses serving both the BRT corridor and off-corridor (feeder), they need to have doors on both sides, and low-floor entrance (30-35 cm) to ensure easy access from the roadside onto the bus.

Such buses are available from both European manufacturers and Chinese manufacturer, and the manufacturers are more flexible to adjust the specification according to client's requirement.

Figure 3.14: Bus Configuration (9 meters)





Figure 3.15: Bus Configuration (12 meters)




3.4.8 Station Access and Pedestrian Facility

81. Access to station is very important to improve the connectivity from the BRT station to the surrounding area. On most stations, access is provided at both ends of the station, except at few elevated stations, where space might be limited. Universal access is also promoted in Peshawar BRT, where all type of access, such as stairs, escalator and elevators are provided for all users with different abilities. On some stations, stairs from the sidewalk are also provided with guiding rails for bicycles, to allow bicycles to use the stairs to cross the road via bridge, mainly on the GT road.
82. To access the station, passengers are provided an overpass bridge, pedestrian tunnel or an at-grade crossing with a pedestrian signal with a combination between any of those options also available in certain locations. An example, at Board Bazar Regi Station (BS-25), at one end, a pedestrian bridge will be provided, and at the other end, an existing tunnel will be improved for access to the station. The decision of choosing different types of access is determined with the site's space availability, as well as the road width. Most of the access to the at-grade section of the city center part (Saddar Road) will use at-grade crossing with pedestrian signals, since the width of road to cross is less than 30 meters wide.

The different types of BRT station access points are provided as Figure 3.16 below.

Figure 3.16: Different BRT Access Points



83. In the proposed pedestrian crossing facilities, three pedestrian tunnels need to be demolished, mainly due to BRT-only tunnel that will be built on those locations. Since these pedestrian tunnels/market currently have many shop owners renting the space and needs to be relocated/compensated, we propose to shift them to the nearest

pedestrian bridge accessing the BRT station. The tunnels that need to be relocated are as follows:

- Pedestrian tunnel demolition of Hushnagri Underpass Market near BS-7. There are 36 shops owned or on rent by private investors. The existing shops will be moved to new pedestrian tunnel on east (accommodate 18 shops) and west (accommodate 20 shops) of BRT station.
- Pedestrian tunnel demolition of Firdous Cinema Underpass Market near BS-8. This will close 32 shops. The existing shops will be moved to new pedestrian tunnel on the east (able to accommodate 15 shops) and the west (able to accommodate 14 shops) of the BRT station.
- Pedestrian tunnel demolition near BS-22. Pedestrian bridges on BS-22 can accommodate 15 shops on west and 13 shops on east of BRT station.

This relocation is illustrated in Figures 3.17 to 3.19 below.

Figure 3.17: Hashtnagri Underpass Market



Figure 3.18: Firdous Cinema Underpass



Figure 3.19: Pedestrian Tunnel near Jahangeer Abad Road



84. The proposed pedestrian bridges would be 8-meter wide (3 meter for shops, 5 meter for pedestrian movement). The shops on the new pedestrian bridges will have 2.5 m x 3 m (80 sqft) per shops. A total of 95 shops will be provided at the BRT station pedestrian bridge, with total area dedicated for shops are 637.5 Sqm, or 6861 sqft.

3.5 Associated BRT Infrastructure


3.5.1 Bus Depot

85. A large number of buses for the Peshawar BRT operation will require a bus depot facility to enable operational efficiency in the BRT system. Such depots have indirect effects of improving passenger convenience and increasing the overall performance of the BRT. In order to serve the system well, bus depots should have at least the following facilities:

- A large area for parking buses
- Good pavement quality
- Sufficient space for bus marking and maneuver area
- Re-fueling facility, cleaning and washing system
- Maintenance and repair area (workshop)
- Administrative office for operators, and employee facilities.

The standard depot layout is provided in Figure 3.20 below.

Figure 3.20: Standard Depot Layout



86. In order to match the requirement for BRT depot in Peshawar, an available space measuring approximately 5.73 hectares on the Grand Trunk road and 4.1 hectares on the Peshawar Ring road are the ideal locations for the depot as they are close to the corridor.

87. Two depot locations are proposed near both ends of the corridors to ensure equal sizing of the fleet. Each depot will be designed to accommodate up to 250 buses with different types of buses (9 meter, 12 meter and 18 meter).

The possible locations of these depots are shown in the Figure 3.21 below. The proposed designs of the Hayatabad and Chamkani depots are provided in Figures 3.22 and 3.23 below.

88. The Hayatabad depot is located near the Peshawar Ring road across Al Haram Model town, with an area of approximately 2.5 hectares and can accommodate upto 131 buses, including parking space for 85 buses of 12 meter length and 46 buses of

9 meter length. There is also a parking space for 18 buses standby as substitute for a bus which requires major maintenance.

89. A park and ride facility with an area of 0.5 hectares is located next to the Hayatabad depot and can facilitate upto 90 cars and has connection with BS 26.
90. The Chamkani depot which is located on the east side of the corridor, on Rano Gari road near the GT road, is roughly 3.5 hectares and contains parking space to accommodate up to 194 buses including 130 buses of 12 meter length and 64 buses of 18 meter length. There is also a parking space for 16 buses standby as a substitute for a bus which requires major maintenance.
91. A park and ride facility with an area of 0.5 hectares will be located opposite the proposed depot site and can facilitate upto 72 cars.
92. The location of the TransPeshawar office may be placed next to the depot over an area of 1 hectare or in Dabgari as an alternative.

3.5.2 Staging Facility

93. In addition to the depot. a staging facility needs to be provided in the middle of the corridor. This facility will be used during off-peak hour, when some portion of the fleet will be put off-service on a stand-by mode, ready to be deployed during the evening peak hour. This facility will be located in Dabgari Garden, along with the TransPeshawar office and Park and Ride facility. A multi-storey building will be constructed on the 20-kanal land, with bus parking located on the ground floor (road level), park and ride will be on the second floor and the TransPeshawar office will be located on the third floor. The map of the staging facility is provided as Figure 3.24 below.

The layout of the proposed Staging facility at Dabgari is provided as Figure 3.25 below.

94. The building structure of the Staging facility over 1 hectare (20 kanals) is proposed in Dabgari and the structure consists of three levels:
 - Level 1 (at-grade): staging facility
 - Level 2 (+ 5.5): park and ride
 - Level 3 (+11.0): TransPeshawar office

Figure 3.21: Proposed BRT Depot Locations



Figure 3.22: Layout of Depot 1 at Hayatabad





Figure 3.23: Layout of Depot 2 at Chamkani



95. The Staging facility will be used as the bus parking facility during the off-peak period. With this facility, some of the buses that are not operated during the off-peak hours can stay for a few hours, before they go into operation at the evening peak. Based on the proposed design, the facility will be able to accommodate up to 36 buses (12 meter and 18 meter buses) and a small bus dispatching office as well as a driver rest area will be built in this facility.


It should be noted that this facility will not be treated as a depot, as no maintenance facility will be provided at the site and any major maintenance shall be performed at the workshop located at the depot.

96. A park and ride facility will be located on the second level and can accommodate upto 100 cars with ramps provided for access by cars and this facility will be integrated with BS 12.

Figure 3.24: Location of Staging Facility



Figure 3.25: Layout of Staging Facility at Dabgari



3.5.3 Workshop Layout

97. The proposed workshop layout is provided as Figure 3.26 below and will consist of the following features:

On First Floor


- Spare parts room: to store the spare parts stocks
- Mechanic room: for mechanics to gather or have a meeting
- Oil warehouse: to store oil to be used for periodic maintenance
- Tire room: to store tires and things related to tire changing
- Compressor room and equipment warehouse: to place the compressor as the center of air distribution and to store supporting equipment
- Overhaul room: to perform major repairs, such as engine dismount, transmission change, and other bus parts which require more than 1-day to complete
- Air and water installation: to be located in certain places in the workshop to support the maintenance process.

On Second Floor

- Admin room: to store documents, files and all related to administration
- Control room: for foreman or mechanics to receive orders according to the system applied
- Meeting room: for use by the management
- Mosque: for prayer
- Toilet and shower.

98. The proposed workshop design will be able to accommodate up to 14 buses at the same time and there will be two channeled work space at the underground level to allow mechanics to easily access the vehicle chassis for inspection and maintenance under the bus.

Figure 3.26: Workshop Layout



3.5.4 TransPeshawar Office

99. As part of the project, an office building for TransPeshawar will be built. This office building will also host the control center for BRT operation, as well as managing the operation and administration part of BRT. At the time of writing, no detail information has been provided on the exact staffing required for this office, but based on the staff size information provided by the institutional expert, the required space for TransPeshawar office is around 10,000 sqm. However, the cost calculation estimated for TransPeshawar office does not include the land acquisition cost, as it is assumed this cost will be borne by the KPK government.

Some facilities that will be provided in the TransPeshawar office are as follows:

- Office space for staff
- Control center, complete with staff from bus operator and traffic police
- Meeting room facilities
- Auditorium for staff training
- Prayer room
- Employee and guest parking space

3.6 Operational Mode of BRT

3.6.1 'Direct-Service' Operational Model

100. A 'Direct-service' operational model is proposed for this project, where BRT buses can run along the BRT corridor and beyond the corridor. This will enable passengers to access the BRT from outside the corridor, without the need to transfer to other buses once they are in the BRT system. Many BRT systems using a separate trunk and feeder system require passengers to transfer from feeder service to BRT trunk service. Although this transfer might be free, the time and the walking distance required to change buses and wait for the connecting service might discourage people to use the BRT.

The benefits of having a direct service BRT are as follows:

- Minimize transfer between trunk and feeder
- Reduce passenger whole end-to-end journey time
- Avoid the need to have big transfer terminal at the end of corridor
- Ability to increase coverage of the BRT service, without the need to build the physical infrastructure widely
- Flexibility in operation.

101. In order to enable the BRT routes to enter and exit the corridor, access needs to be provided at certain locations near the BRT stations. Bus entrance to the BRT corridor will be provided before the station, where the BRT separator will be removed, and chevron will be provided to guide the bus to enter the BRT lane. To exit the corridor, an opening will be provided for the bus to leave the BRT lane and join the mixed-traffic lane. The location of these openings for BRT direct service routes will only be provided on certain locations. The access for direct service on each station is illustrated in Figure 3.27 below.

3.6.2 Operational Plan and Fleet

102. The 8 specified BRT lines will travel in and outside the corridor, and depending on their routes, will use 9 meter or 12 meter buses. The selection of the bus type, as well as the daily ridership, determines the necessary bus frequency for passengers to be picked up without long waiting times. The proposed route length and detail is provided in Table 3.2 and Figure 3.28 below.
103. With an average portion of 57% inside the corridor, the routes are obviously expected to travel faster in traffic-less lanes. Nonetheless, travelling outside the corridor will also be crucial in order to pick up passengers. In a matter of efficiency and comfort, the maximal peak hour headway is fixed to 5 minutes for all BRT routes.
104. At the beginning, with mixed of 9-meter and 12-meter fleet, the carrying capacity of the system will be between 5,800 passengers per hour per direction (pphpd) up to 8,500 pphpd. However, if later on 18-meter buses are introduced, it could even carry up to 15,000 pphpd, or even bigger, since express services are also possible to run with the current infrastructure design.
105. The total BRT fleet strength is planned to be 383 buses consisting of 131 buses of 9-meter length and 252 buses of 12-meter length.

3.7 Implementation Arrangement

3.7.1 Implementation Management and Execution

106. Physical implementation of the construction of the BRT infrastructure will be undertaken through a Contractor selected by the PDA. The Contractor shall conduct the construction activity on the basis of the detailed designs provided to him.
107. The Contractor will take broad responsibility for all elements of the construction and procurement and shall be responsible for ensuring compliance of the activities being conducted with the applicable environmental and social safeguards.

Figure 3.27: Access for Direct Service at BRT Station



Table 3.2: Proposed BRT Route length and details

BRT	Route Length (km)	Length in Corridor (km)		Length off Corridor (km)		One way time (min)	Bus type (m)
1A	27.5	27.5	100%	0	0%	61	12
1B	12.9	6.2	48%	6.7	52%	41	9
1C	25.8	14.98	58%	10.82	42%	77	12
1D	29.3	15.88	54%	13.42	46%	89	12
1E	28.4	20.4	72%	8.0	28%	77	12
1F	20.5	10.2	50%	10.3	50%	64	9
1G	14.8	7.3	49%	7.5	51%	46	9
1H	15.8	4.5	28%	11.3	72%	55	9
Average	21.9 km	57%		43%		64 min	

Figure 3.28: BRT Route Plan



3.7.2 Project Construction Schedule

108. The project construction phase is expected to last for a total of 18 months with the activity expected to commence in the first quarter of 2017 and completed by the second quarter of 2018.

3.8 Construction Camps and Work Force

109. The construction activity has to span over approximately eighteen months. There shall be a number of contracts for a variety of works. The selected Contractor shall have the option to select suitable site(s) located near the project sites to establish his labor camps. If private land is selected, the contractor shall enter into contract with the private owner.
110. Since the work is quite scattered in nature with a large number of sites along the project corridor, the project construction will be divided into many sections. The work bases shall be setup by the contractor in consultation with the engineering teams. Essential for the work bases is easy approach, availability of a suitable place for temporary storage of material and availability of water for construction in the vicinity. Presence of shade from trees close to the work bases can add to the comfort of the labor while taking rest during the hot season.
111. The location of storage materials and camps will be critical. Since the project contractor(s) will be responsible for identifying the suitable locations for storage and labor camps from the private sector, thus there will need to be clear guidelines for this process, which will need to be closely monitored by the implementing agency. As far as possible, the project design team shall be assigned the task to identify the suitable location(s) for storage of materials since inappropriate storage of materials may result disruption of the traffic movement.

3.9 Machinery Requirement

112. For storing materials, stocking equipment and parking machinery and vehicles, the Contractor shall require open and accessible sites close to the labor camps. The Contractor, at his own expense, but keeping in view his contractual obligations to honor the NEQS regarding level of pollution, shall make the arrangements.
113. The expected machinery to be employed for the construction activity along with the respective noise ratings is provided in table 3.3 below.

Table 3.3: Construction Equipment Noise Ranges dB(A)

Equipment	Peak Noise Range at 15.2 m	Typical Peak Sound Level in a Work Cycle ^a	Typical 'Quieted Equipment' Sound Level ^b	Construction Phase		
				Earthworks	Structures	Installation
Batching plant	82-86	84	81		Y	
Concrete mixers	76-92	85	82		Y	
Cranes	70-94	83	80		Y	Y
Excavators	74-92	85	82	Y		
Tractors and trolleys	77-94	88	85	Y	Y	Y
Water bowsers	85-93	88	85	Y	Y	Y
Graders	72-92	85	82	Y		
Bulldozers	65-95	80	75	Y		
Paver	87-89	88	80	Y		
Pumps	68-72	76	75	Y	Y	Y
Diesel generators	72-82	78	75	Y	Y	Y
Vibrators	68-82	76	75	Y	Y	
Drilling machines	82-98	90	87		Y	Y
Compressors	74-88	81	71		Y	
Dumpers	77-96	88	83	Y	Y	Y
Road rollers	73-77	75	72	Y		

Sources: Bolt, Beranek, and Newman, Noise from Construction Equipment and Operations, Building Equipment, and Home Appliances. USEPA, 1971; <http://www.waterrights.ca.gov/EIRD/text/Ch11-Noise.pdf>; http://www.lacsd.org/LWRP%202020%20Facilities%20Plan%20DEIR/4_6_Noise.pdf; <http://newyorkbiz.com/DSEIS/CH18Construction.pdf>

Notes:

- Where typical value is not cited in literature, mean of the peak noise range is assumed
- Quieted equipment can be designed with enclosures, mufflers, or other noise-reducing features. Where data is not available, a 3 dB reduction is assumed

4 Description of Environment

4.1 General

114. Peshawar, the capital of Khyber Pakhtunkhwa province, is a metropolitan city and is located at the north-west end of Pakistan, about 160 km west of federal capital Islamabad. It is bounded by tribal agencies on its three borders.
115. Peshawar is a City district with a total population of 1.75 million people and contains four towns with each town consisting of union councils with a total of 92 union councils in Peshawar. There is only one tehsil in the district i.e. Peshawar tehsil and the total area of the district is 1,257 km².
116. The description of various features of the project area environment including the physical, ecological, cultural and socio-economic environmental aspects are presented in the following sub-sections.

4.2 Physical Resources

4.2.1 Topography

117. Peshawar is situated near the eastern end of the Khyber Pass and sits mainly on the Iranian plateau along with the rest of the Khyber-Pakhtunkhwa.

The Vale of Peshawar is covered with consolidated deposits of silt, sands and gravel of recent geological times. The areas between the Kabul River and Budni Nala consist of flood Plains/Zones. The meander flood plain extends from Warsak in the Northwest towards Southeast in the upper Northern half of the district. The Kabul river enters the district in the Northwest.

On entering the Peshawar Plain, the Kabul river is divided into several channels. Its two main channels are the Adizai River Eastward flows along the boundary with Charsadda District. Another channel branching from the right bank of the Naguman River is the Shah Alam, which again merges with Naguman River further in the East. In general, the sub-soil strata is composed of gravels, boulders, and sands overlain by silts and clays. Sand, gravel and boulders are important aquifers that extend to a depth of about 200 feet (61 m) and further confined water bearing aquifers occur at depths greater than 400 feet (120 m).

118. The proposed project corridor is located within Peshawar city, which is a completely urban environment. The terrain consists of completely flat land with the only vegetation cover consisting of plants and trees scattered across the project corridor for landscaping and beautification of the city.

4.2.2 Climate


119. Peshawar has a hot semi-arid steppe climate, which is very dry with little rainfall. It can rain at any time of the year but the rain does not last long. As well as

being arid, the climate is extremely hot in the summer but slightly cooler in the winter months. There is no monsoon period. Throughout the year, temperatures fall dramatically at night, sometimes by as much as 20°C.

120. The warm season lasts from the 29th of April to the 8th of September with an average daily high temperature of above 34°C. The hottest day of the year is the 18th of June, with an average high of 39°C and a low of 27°C.

121. The cold season lasts from the 5th of December to the 25th of February with an average daily high temperature below 21°C. The coldest day of the year is the 2nd of January with an average low of 5°C and a high of 18°C. The temperature profile for Peshawar is shown in Figure 4.1 below.


Figure 4.1: Year round Temperature Profile of Peshawar City



122. The relative humidity typically ranges from 24% (dry) to 89% (very humid) over the course of the year, rarely dropping below 15% (dry) and reaching as high as 99% (very humid) as can be seen in Figure 4.2 below.


The air is driest around the 21st of May, at which time the relative humidity drops below 29% (dry) three days out of four; it is most humid around the 11th of January, exceeding 85% (humid) three days out of four.

Figure 4.2: Humidity Profile of Peshawar City



123. Over the course of the year, the typical wind speeds vary between 0 m/s and 6 m/s (calm to moderate breeze), rarely exceeding 12m/s (strong breeze) as can be seen in Figure 4.3 below.


Figure 4.3: Wind Speed Profile of Peshawar City



124. The average rainfall profile for Peshawar is provided as Figure 4.4 below. The physical work is planned to start from the 1st quarter of 2017 and to be completed by second quarter of 2018. Since there are over 20 days of rainfall during the month of August each year, thus potential issues related to drainage and water logging can be

expected at those project sites along the project corridor where excavation work will be conducted. In order to overcome any potential issues with drainage, necessary mitigation measures shall be implemented whenever required, provided in detail in Section 6.4.37 'Flooding'. All required measures such as installation of pumps for removing any water collecting within the excavated sites along with installation of retaining walls around the boundary of the excavated site to prevent filling up of water are some of the measures that shall be implemented, if required.

Figure 4.4: Average Rainfall Profile of Peshawar City




4.2.3 Seismology

125. The seismic hazard in Peshawar is aggravated by increasing vulnerability due to populated growth and expansion in infrastructure due to its political and regional importance. It is located in the western Himalayan region characterized by high seismicity rates due to its vicinity to the active plate boundary between the Indian and Eurasian plates. The seismic zone map of Pakistan is shown in Figure 4.5 below.

126. According to MOHW-PEC-NEPAK (2007), Peshawar is placed in Zone 2B. The Zone 2B has Peak Ground Acceleration (PGA) in the range of 0.16g to 0.24g for a return period of 475 years and is considered to be at 'Moderate' risk of a major earthquake event.

Figure 4.5: Seismic Zones of Pakistan



4.2.4 Surface and Groundwater

127. Khyber Pakhtunkhwa province lies between river Indus and the Sulaiman hills that form the western barrier of Pakistan. Its canals are insignificant as compared with the great irrigation works of the Punjab. The only ones of any importance are in the Peshawar valley. These draw their supplies from the Kabul, Bara, and Swat rivers, but the first two rivers irrigate small portion of cultivated area of the district.
128. There is heavy dependence on the Kabul, Bara and Swat rivers to obtain water for every day use for the residents of Peshawar. Boring of tube wells to obtain underground water is a standard practice being implemented by the residents of Peshawar to ensure a continuous supply of water, which has lead to a reduction in the water table of 130 feet over the past decade.
129. The Government authorities are planning a Peshawar Greater Water Supply Scheme, which will allow approximately 200 million gallons per day (MGD) to be pumped in from different rivers to meet the growing requirements of Peshawar.
130. Agriculture in Peshawar is largely dependent on Canals. Moreover, tube wells irrigation is also available in some places. The irrigated land in district Peshawar constitutes a large percentage as compared to other districts of Khyber Pakhtunkhwa. 73% of the rural mouzas are irrigated by canals while 15-20 % are irrigated by other sources including river, Tube-wells, ravine, and spring stream etc.

4.3 Ecological Resources

4.3.1 Flora

131. The city of Peshawar consists of a completely urban landscape with patches of plants and trees present across the city for the purpose of beautification and landscaping.
132. In the Peshawar valley, subsistence agriculture is widely practiced with wheat, barley, millet, corn, cotton, pepper and sugarcane being the primary crops. The annual cycle is divided into two planting and harvesting periods, one for wheat and barley in winter and another for corn in summers. Planting and harvesting of sugarcane overlaps both the periods. These crops are supplemented with a variety of vegetables and with clover, which is used in conjunction with millet as a fodder.
133. In many villages in the Peshawar valley, there are extensive pear, peach and apricot orchards and grape vineyards. Tobacco is also an important crop near the town of Nowshera. Wheat, cotton, pepper and particularly Tobacco and sugarcane are grown for the market as well as for local consumption.
134. The present flora of the irrigated areas is exotic. The common trees are mesquite, ber, different species of acacia and jand. The most common shrubs are tarmariak, articulata, spand, akk, small red poppy, spera, pueghambrigul, drab grass, spera, eamelthorl and pohli chaulai etc.

4.3.2 Fauna (Regional)

135. There is a variety of fauna present in Peshawar valley with the details provided in Table 4.1 below.

Table 4.1: Existing Fauna in Peshawar Valley

Mammals			
Common Name	Scientific Name	Common Name	Scientific Name
Leopard	Panthera pardus	Hare/Siah	Lepus nigricolus
Mongoose/Neola	Herpestes anropunctatus	Ludhar/Other	Lutra persipiciliata
Gheese/House Shrew	Suncus marinus	Black Bear	Ursus thibetanus
Bat/Changadar	Pipistralius terwis	Jackal/Gidder	Canis auries
Black Rat	Ratus ratus	Fox/Loori	Vulpe bengalensis
House Rat	Mus musculus	Hedge Hog	Hemiechinus Sp.
Mole Rat	Bandicota bengalensis	Porcupine/She	Hystrixe indircia
Squirrel/Gulehri	Fumbulus penanti		
Birds			
Dove/Common	Streptophelia	Indian Sand Martuis	Riparia paludicola

Dove	senegalensis		
Dove/Common Dove	Streptopelia tranquefabria	Indian River Tern	Sterna auranlia
Larks	Mirfa erythroptera	Black Partridge	Francolinus francolinus
Larks	Erimopterix grisea	Common Babler/Bagla/Chakkira	Turdoides candidus
Larks	Calaendrella cristata	Neel Kanth	Graculus garrulous
Weaver Bird	Ploceus philippinus	Grey Partridge	Pyronotus xythopygos
Jungle Pigeon	Teron walia	Shrieks/Lali/Myna	Passeriformes Sp.
Crow	Corcives abyssinica	Owl	Bubo africanus
Sparrow	Passer Sp.	Black Rock Pigeon	Columbia livia
Reptiles			
Indian Cobra	Naja naja		

4.4 Human and Economic Development

4.4.1 Culture

136. Peshawar is one of the most ancient cities of this region and for centuries has been a center of trade between Afghanistan, South Asia, and Central Asia as well as the Middle East. It is a conservative Islamic city with a rich history. Peshawar's inhabitants consist mainly of Pashtun and Hindkowans. In addition, many Punjabis, Chitralis, Tajiks, Uzbeks and Hazaras can be found in the city.

4.4.2 Languages

137. Though Pashto followed by Hindko is the main language spoken in the district, other languages such as Urdu, Persian, Saraiki and Punjabi are also spoken by some of the residents of the district.

4.4.3 Religion

138. Over 99% of the city's population is Sunni Muslim, along with some Shias and Ahmedis.

Despite overwhelmingly Islamic nature of modern Peshawar, it was previously home to other smaller communities such as Afghan Jews, Zoroastrian, Hindus and Sikhs. Its famous markets such as the Qissa Khawani Bazaar (market of story tellers) are emblematic of this mixture of culture and offer a variety of goods including gold and silver ornaments, traditional carpets, pottery, and clothing to artwork in wood, brass and precious stones. Even today, Peshawar is the commercial, economic, political and cultural capital of the Pashtuns as well as a major center of Hindko culture in Pakistan.

4.4.4 Administrative Setup

139. Under the latest revision of Pakistan's administrative structure, promulgated in 2001, Peshawar was given the status of a City district and divided into four towns. Each town in turn consists of a group of Union Councils (UCs).
140. The administrative towns are known as Peshawar Town I, Peshawar Town II, Peshawar Town III and Peshawar Town IV.

4.4.5 Main Sources of Livelihood/Income

141. According to the official statistics, in 2007, there were 432,506 employed people in the district. Agriculture sector is the highest employer with 26.6 percent of the total employment followed by wholesale and retail businesses 8.9%, transport and communications 5.8% and manufacturing 5.5%.
142. Reported statistics also indicate that people of Peshawar have mostly focused on their personal business and services, i.e. 41% of the employed population earn their livelihood through personal services. Women participation in employment is low as only 12% of the female population is employed.

4.4.6 Transport

143. There are 4 types of vehicles operating as public transport vehicles in Peshawar. The biggest capacity is Minibus, which also has two sub-types: Mazda minibus and Bedford buses. Both sub-types have similar size of approximately 8 meters long with capacity of 41 passengers inside the bus. Passengers also often sit on the roof, despite posing great danger to their life and others. At most, 11 passengers can sit on the roof.
144. The second vehicle type is the Ford wagon, with a capacity of 15 passengers. The seat configuration of the wagon makes passengers difficult to get in and get out of the vehicles, thus most of the passengers on wagon are typically an end-to-end passengers riding the entire route.
145. In addition to the above, the Suzuki vans have started to gain some public transport market shares, with at least 14 routes plying on Peshawar road. Suzuki vehicles are derived from pick-up minivans, modified with fragile roofs to provide cover for passengers. Despite their small size, the Suzuki can carry up to 18 passengers in total (inside and outside). Accident rates are not available, but it would not be surprising if they were listed as the most dangerous public transport option of Peshawar.
146. Small people carrier called Qingqi – named after the Pak-Chinese based motorcycle brand used as the vehicle, are also operating in Peshawar and relatively popular for short distance trips. This vehicle, a modified 3-wheeler with extra cabin at the back for passengers, has a capacity of 6 to 8 passengers.

147. In Peshawar, no public route map exists, although many routes operate in the city. The official data obtained from the Government only listed the minibuses, rocket bus and wagon. Suzuki and Qingqi are operating illegally so no official data is available. Based on the surveys conducted for this project, 7 minibus routes, 2 wagon routes, 13 Suzuki routes and 6 Qingqi routes have been identified.
148. Based on the 16 road segments surveyed, only 3 road segments have peak passenger volumes under 1,000 passengers per hour per direction, and there are 5 locations with peak passenger volumes above 3,000 passengers per hour per direction. Most of these locations are located along the BRT corridor on GT road, which indicates a clear need to implement a BRT corridor on these roads. This passenger volume throughput is higher than some of the BRT systems in the world and Pakistan, where the peak passenger throughput in Islamabad BRT is only 2,100 passengers per hour per direction (December 2015).

4.4.7 Industry

149. Peshawar district is comparatively developed area in the province of Khyber Pakhtunkhwa. Khazana sugar mill and a number of small industrial units in the industrial estates located at Kohat road and Jamrud road are functioning, which are manufacturing hosiery, small arms, leather and foot wear, garments, ghee, soap, etc. Match factories, flour mills and steel re-rolling units are also operating in the district.
150. There are a total of 550 Industrial Units in district Peshawar that provide employment to 14,471 people and the total Investment of all these industries amounts to Rs. 5009.902 million.

4.4.8 Health Care

151. Presently, in district Peshawar, health services are provided by both Public and private institutions. There are 12 public hospitals - out of these 3 are teaching hospitals, 72 private hospitals, 3 RHC, 37 civil dispensaries, 4 MCH centers, 49 BHUs and 4 TB clinics in district Peshawar. The total beds strength of government teaching hospital is about 3460 beds. Also, there are 1,046 doctors, 176 dispensers, 708 nurses, 60 Lady Health Workers (LHW) and 1,888 other paramedical staff posted by the government in the district.

4.4.9 Literacy Rate

152. The literacy rate for population 10 years and above (2010-2011) was 54 percent (Males: 68%, Females: 38%).³⁵ which increased to 59% in 2013. For the urban rural comparison, the urban literacy rate is higher than the rural, which is 62 percent. Among urban community, literacy ratio for male is 75 and for female it is 47; whereas the rural literacy ratio is 45 percent, and in rural community, literacy ratio for male is 61 and for female it is 29. Adult literacy rate (> 15 years) is 51 percent. Gross Enrollment Rate (GER), at the primary level, is 93% (Male: 101%, Female: 85%). Net Enrollment Rate (NER), at the primary level, is 56% (Male: 59%, Female: 52%).

4.4.10 Education

153. The total enrollment in district Peshawar is 354,674 (Boys: 207,941, Girls: 146,733). Out of a total of 9,652 teachers 5,522 are male and 3,796 are female teachers. This illustrates that, on an average, one teacher is teaching 37 students. Total educational facilities are 1,376; out of which 836 are boys and 540 are girls. This means that, on an average, every facility has a teaching staff of around 7.
154. Primary: The total number of primary level schools, that are reported, are 1,063 (Male: 652, Female: 411). The total enrollment, at the primary level is 239,320 (Boys 136,615, Girls 102,705). Total number of teachers, at the primary level, is 5,554, out of which 3,379 are male and 2,175 are female teachers. Thus on, an average, each primary school has an enrolment of 225 students with a teaching staff of 5.
155. Middle: There are a total of 150 middle schools reported. The total enrollment at the middle level is 64,077, of which 38,726 are boys and 25,351 are girls. The total number of teachers at the middle level is 954, out of which 522 are male teachers, while 432 are female teachers. Thus, on an average, each middle school has an enrolment of 427 students with a teaching staff of 6.
156. Matric: There are a total of 118 secondary schools in the district. The total enrollment at the secondary level is 24,766, of which 14,880 are boys and 9,886 are girls. The total number of teachers at the secondary level is 1,521, out of which male teachers are 996 and female teachers are 525. Thus, on an average each, the Secondary level schools have an enrolment of 210 students with a teaching staff of 13.
157. There are a total of 52 higher secondary schools in the district. Total enrollment, at the higher secondary level, is 3,326 (Boys: 1,422, Girls: 1,922). The total number of teachers at the higher secondary level is 823, out of which 567 are male teachers and 256 female teachers. Thus, on an average, each higher secondary school has an enrolment of 133 students with a teaching staff of 33.

4.4.11 Archaeological and Cultural Heritage

158. The Bala Hisar Fort is the only major site of cultural importance that is located at a distance of 83 meters from the project corridor. However, it is predicted that there will be no direct impact on this historical landmark since the project corridor alignment passes next to the fort and the vibration effects resulting from the construction activity are not expected to be so significant as to cause any damage to the Fort.

However, during the detailed design phase of the project, expected to commence by March 2017, a detailed investigation by a team of civil engineers will be conducted prior to commencement of the project activity to assess the existing structural strength of the fort as well as any possible impact(s) of the expected vibration levels resulting from the project construction activity on the fort. The assessment of the

expected vibration levels shall be conducted based on the vibration thresholds provided in Table 4.2 below. The tentative scope of work for this structural assessment is provided as ANNEX O.

159. An NOC has already been issued by the Directorate of Archaeology and Museums (please refer to ANNEX K) and only requiring that a staff member from the Directorate be present at the respective project site(s) to ensure no adverse impacts take place during the construction activity.

160. Apart from the Bala Hisar Fort, no other sites of archaeological or cultural heritage have been observed during the survey. However, if at any stage any archaeological or physical heritage is discovered, it shall be managed as per established protocol from the department of Museum and Archaeology, GOP.

Table 4.2: Damage Thresholds from Construction related Vibration Effects¹

Conditions Observed	Typical Peak Particle Velocity (in/sec) [*]
Threshold damage (hairline cracking in plaster, opening of old cracks etc.)	2-3 Never at <0.5
Minor damage (hairline cracking in masonry, breaking of windows)	4-5 Never at <1.0
Major structural damage (cracking or shifting of foundations or bearing walls)	>5

Note: *: Based on Standard USBM RI 8507

4.4.12 Energy Supplies

161. The residents of Peshawar city are reliant on electricity available from the grid through PESCO (Peshawar Electric Supply Company) although they face between six to eight hours of load shedding on a daily basis. Certain residents and businesses in the city, based on affordability, operate diesel generator sets as a back up. Also, there is an increasing trend of installing solar PV systems in both residences and businesses in order to ensure energy reliability.

4.4.13 Communication

162. Majority of the community members possess cellular phones, although PTCL line is present in the city but it is mostly used in Public offices and in Public Call offices (PCOs). Most youth is IT literate and use both desktop and laptop computers and have access to the internet. Postal service is available throughout the city. Majority of the residents of Peshawar city have access to a television as well as satellite channels.

4.4.14 Project Area Communities

¹ http://www.apti.org/clientuploads/publications/2015/Johnson-HannenHiRes_SampleArt_46.2-3.pdf

163. The inhabitants in the area fall into socioeconomic strata varying from poor to rich. The specific areas lying in the project area are shown in Figures 4.6 to 4.9 below.
164. The area in Peshawar urban district is dominated by both residential and commercial activities. Along the GT Road, commercial and business areas are found on the main road, whereas on the secondary roads, or 500 meters from the main GT Road, highly populated residential areas are found. Commercial activities and offices dominate the cantonment-controlled area, such as in Khyber Bazaar and Saddar, and a significant portion of the area south of Khyber road is dominated by government and military offices.
165. On the west part of the corridor, major residential area in Hayatabad dominates the area while some proportion of industry is located south of Karkhano. This makes the BRT corridor surrounded by high commuting activities, which makes it ideal. The density of the urban area, where the BRT will run, is much higher than the density outside the urban district. Currently, 11,714 people per square km live in the urban district, whereas the density outside is only a tenth of the urban area's density.
166. Based on the detailed surveys conducted, the key receptors along the BRT project corridor were identified and are shown in Figures 4.10 to 4.23 below.
167. The average distance of any residences from the proposed BRT route is 60 meters while the maximum distance is greater than 200 meters. In addition, at a number of locations along the BRT corridor, the first row of buildings consists of commercial plazas with the residential buildings located behind these plazas. Thus, at these locations, the residences are being 'shielded' by the commercial buildings with regards to exposure to any potential impacts such as noise, dust and exhaust emissions. Thus, at these locations, the first row of commercial plazas along the corridor are acting as a 'noise barrier' due to attenuation and will cause considerable reduction in the noise levels and level of air emissions reaching the residences.

Thus, the construction activity or operation of the BRT is not expected to pose any disturbance to the residences lying at these locations near the proposed BRT route.

4.5 Noise

168. As the first step, the selection of locations for the 24-hourly monitoring of ambient noise levels at sensitive receptors along the BRT route was conducted. In order to select the five most representative locations for monitoring of the ambient noise levels over a period of 24 hours, a Type 2 portable sound meter was used and instantaneous noise levels were recorded at ten different locations. A strict protocol was followed by ensuring the sound meter was calibrated and each measurement was obtained by holding the meter at an arm's length until the reading stabilized. Also, during the measurements, the wind speeds were observed and readings taken during high wind speeds were discarded.


These ten locations were as follows:


- Chamkani Chowk
- Sethi Town
- Hashnagri
- Soekarno Square
- Saddar Bazaar
- Christian Cemetery
- Abdara Road
- KTH University of Peshawar
- Board Bazar Regi
- Cancer Hospital

The map showing the ten locations and their respective instantaneous ambient noise readings are provided as Figure 4.24 below.









Map

Point of View (Yellow square)

Point of Interest (Orange square)

Point of Observation (Green square)

Point of Collection (Blue square)

Point of Distribution (Red square)

Point of Disposal (Purple square)

Point of Entry (Pink square)

Point of Exit (Light blue square)

Point of Transfer (Light green square)

Point of Control (Light orange square)

Point of Inspection (Light yellow square)

Point of Search (Light pink square)

Point of Seizure (Light blue square)

Point of Arrest (Light green square)

Point of Detention (Light orange square)

Point of Release (Light yellow square)

Point of Departure (Light pink square)

Point of Arrival (Light blue square)

Point of Landing (Light green square)

Point of Unloading (Light orange square)

Point of Loading (Light yellow square)

Point of Stowage (Light pink square)

Point of Storage (Light blue square)

Map

Point of View (Yellow square)

Point of Interest (Orange square)

Point of Observation (Green square)

Point of Collection (Blue square)

Point of Distribution (Red square)

Point of Disposal (Purple square)

Point of Entry (Pink square)

Point of Exit (Light blue square)

Point of Transfer (Light green square)

Point of Control (Light orange square)

Point of Inspection (Light yellow square)

Point of Search (Light pink square)

Point of Seizure (Light blue square)

Point of Arrest (Light green square)

Point of Detention (Light orange square)

Point of Release (Light yellow square)

Point of Departure (Light pink square)

Point of Arrival (Light blue square)

Point of Landing (Light green square)

Point of Unloading (Light orange square)

Point of Loading (Light yellow square)

Point of Stowage (Light pink square)

Point of Storage (Light blue square)

Map

Point of View (Yellow square)

Point of Interest (Orange square)

Point of Observation (Green square)

Point of Collection (Blue square)

Point of Distribution (Red square)

Point of Disposal (Purple square)

Point of Entry (Pink square)

Point of Exit (Light blue square)

Point of Transfer (Light green square)

Point of Control (Light orange square)

Point of Inspection (Light yellow square)

Point of Search (Light pink square)

Point of Seizure (Light blue square)

Point of Arrest (Light green square)

Point of Detention (Light orange square)

Point of Release (Light yellow square)

Point of Departure (Light pink square)

Point of Arrival (Light blue square)


Point of Landing (Light green square)


Point of Unloading (Light orange square)


Point of Loading (Light yellow square)


Point of Stowage (Light pink square)


Point of Storage (Light blue square)




















169. During the day time, high instantaneous noise levels at all ten locations were recorded due to heavy traffic volumes with the frequent honking of horns being a standard practice. The noise levels were observed to be generally in the mid 80 dB(A) range while even higher noise levels of 90 dB(A) and above were observed at BS-11 (Soekarno Square) and BS-15 (Saddar Bazaar).

170. The five locations that were selected for 24 hourly ambient monitoring since they were considered to be the most representative out of the ten initial points were as follows:

- Chamkani Chowk
- Soekarno Square
- Saddar Bazaar
- KTH University of Peshawar
- Cancer Hospital

These five locations were selected since they were observed to be the most important in terms of having the most sensitive receptors in their vicinity with receptors such as the Lady Reading Hospital, KTH and Shaukat Khanum Hospital as well as educational institutions such as Islamia College. In addition, the Soekarno Square and Saddar Bazaar are hubs of commercial activity and thus were selected due to the high traffic volumes and movement of general public at these two locations. It should be mentioned that at each selected monitoring location, the monitoring equipment was placed nearest to the most sensitive receptor present at that location in order to accurately record the ambient noise levels at the receptor.

The receptor map showing the five selected noise locations and their respective 24 hourly ambient noise readings are provided as Figure 4.25 below.

171. As can be observed, the average ambient noise levels vary between 68 dB(A) and 74 dB(A) with the nighttime noise levels at all locations being very similar at approximately 65 dB(A). In comparison, there is reasonable variation in the day time noise levels, which vary between 71.8 dB(A) and 76.4 dB(A).

This variation between the day and night time noise levels is due to the reduction in the traffic and commercial activity in the late evening hours, primarily after 11 pm.

It can be observed that the proposed BRT project corridor is a disturbed high noise environment with the existing ambient noise levels already exceeding applicable NEQS limits for the different categories of areas/zones i.e. Residential, Commercial etc.

4.6 Air Quality

172. The five locations where 24 hourly ambient air quality monitoring was conducted since they were considered to be the most representative were as follows:

- Chamkani Chowk
- Soekarno Square
- Saddar Bazaar
- KTH University of Peshawar
- Cancer Hospital

The map showing the five selected air quality monitoring locations and their respective 24 hourly ambient air quality readings are provided as Figure 4.26 below.

173. As can be observed, in general the ambient air quality is within the acceptable NEQS guidelines with PM₁₀ being the only pollutant that is exceeding the guidelines at two of the five monitoring locations.

4.7 Climate Vulnerability of Project

174. The project is expected to have a positive impact from a climate change perspective since the proposed BRT project will result in the operation of a fleet of new buses on a designated corridor and thus will emit fewer emissions and will be undergoing maintenance on a regular basis. The construction phase of the project will be expected to last for approximately 18 months and the only sources of emissions to the environment will be during the construction phase from construction related vehicle movement and equipment use. No toxic or ozone depleting gases shall be emitted into the environment.

175. Once the project is operational, the overall traffic volumes in Peshawar will be reduced since the commuters will prefer to travel on the BRT since it will be a more reliable, convenient and economical option. Thus, it is estimated that 30,988 tons of CO₂ emission reductions will take place in the first year of the project operation while these reductions will more than double by the year 2026 to 62,145 tons of CO₂ and reach over 77,000 tons of CO₂ by the year 2036.

5 Analysis of Alternatives

5.1 No Project Alternative

176. Without this project, the population of almost two million people residing in the Peshawar city would not benefit from a sustainable, more efficient and safer transport system and would continue to suffer congestion and traffic accident risks in the city. Peshawar would not have an efficient public transport system that reduces the costs of transport, serve the central urban area or facilitate intermodal interchange, or provide better accessibility to employment and services in the city. Peshawar would also lose the benefits of behavioral change with respect to road safety and traffic management.
177. The BRT system would streamline the public transport operation making bus services more efficient with dedicated lanes and stops. Without the BRT corridor, public buses would continue to fight for lanes with other motor vehicles when getting in and out of stops in congested traffic, resulting in road safety risks and slower travel time for the passengers.
178. Without the BRT system, carbon emissions in Peshawar city from road traffic would continue to increase and the expected CO₂ emission reductions from the BRT project of 62,145 tons by year 2026 would not take place.
179. In case the BRT system is not developing, considering the inefficient and highly congested road network within Peshawar city, future developments could be delayed due to incomplete road network and lack of connectivity between roads. Future residents would also lack public open space without any locations of scenic, aesthetic and recreational value. All these could affect the socio-economic development in the city, employment opportunities for residents and quality of living conditions and environment.
180. Delay in developing the city through the BRT corridor would also affect the urbanization of Peshawar city, putting pressure on the old central urban area of Peshawar city to accommodate new migrants.

5.2 Alternatives Considered

The different alternatives considered for development of the proposed BRT project are presented below.

5.2.1 Alternative route options

181. The selection of the possible alignment of the BRT was conducted keeping in view a mix of technical, economical as well as environmental aspects to ensure the finalized route of the project would be the most favorable amongst the possible route alignment options in all regards. The impact on the area from the environmental and social aspects was given significant weightage during the assessment of the different alignment options. Other aspects that were considered were the right of way (RoW)

along the project corridor, demand coverage of the corridor, practicality of construction as well as option offering the shortest duration to complete the project construction.

182. As a result of the CDIA pre-feasibility study (PFS) conducted in 2014, six mass transit corridors were identified in Peshawar but the corridor 2, from Chamkani to Karkhano was selected as the recommended option to be built in the first stage as a BRT. The PFS also identified five other corridors, but some of them were not too feasible to be built as a mass transit corridor during the first stage. The mass transit corridors identified in the PFS are shown in Figure 5.1 below.

Figure 5.1: Mass Transit Corridors identified in PFS



183. The Corridor '1' was not selected as the proposed alignment for the BRT since it runs alongside the railway track and some of the sections do not have the necessary minimum clearance required from the railway track and could possibly create considerable issues from health, safety and environment perspectives.
184. Other corridors identified on the PFS will also pose great difficulties with regards to land acquisition to construct the required mass transit infrastructure. In addition, the proximity of the key receptors to the other corridor options are also expected to create much greater environmental impacts that would be much more

difficult to mitigate in comparison to the limited number of impacts resulting from the chosen corridor for the proposed project.

185. As a part of the comprehensive assessment for identifying the preferred BRT corridor, four different alignment options were considered for the city center area are as follows:

- At-grade via Jail road
- Elevated via Soekarno road
- Elevated via Hospital road
- At-grade via Hospital road

The assessment of these four options is provided in Table 5.1 below.

Table 5.1: City Center Alignment Assessment Summary

Alignment Option	Features	Results
Option 1: At-Grade via Jail Road	++Faster construction time ++Goes to non-congested road - Skip high demand area - Need to remove parking - Pass through Government sensitive area	This was assessed to be the third best option after options # 2 and 4, due to minimum investment required and faster construction time
Option 2: Elevated via Soekarno road and Shuba Chowk	++Capture high demand area ++Avoid conflict with general traffic at Khyber bazar ++Minimize impact for resettlement and acquisition -Higher construction cost -Might degrade the area underneath elevated section -Might pose security threat to Bala Hisar fort -Pylon for elevated section are too close to Bala Hisar fort	This option could have been feasible. However, due to concern on the pylon for elevated BRT being too close to the Bala Hisar fort structure, this option has not been selected.
Option 3: Elevated at Hospital road	++Capture high demand area -Highest construction cost out of all options -Narrow section on hospital road makes it difficult -Might degrade the area underneath the elevated section	This option was only possible if the elevated section is made for a 1-direction BRT, which will further increase the project cost. Thus, it is considered as the last option.
Option 4: At-Grade via Hospital road	++Capture high demand area ++Traffic re-direction also helps to ease the congestion ++Will change the overall street realm	Preferred option

Alignment Option	Features	Results
	along BRT corridor -Pose emergency risk with one-way traffic for ambulance	

186. During the initial discussions between the project consultants and the Government staff for identification of the most feasible BRT alignment, the option 2 was initially considered the preferred option. However, later it was decided that due to the high construction cost and security and livability aspects, the advantages of the second option could not outweigh its disadvantages. This referred the discussions to option 4 with the issue of ensuring uninterrupted access for emergency vehicles to the Lady Reading hospital being resolved by dedicating a portion of BRT for 'ambulance only' access along the south part of Cinema road and the east part of Khyber bazar road.

5.2.2 CNG versus Diesel buses

187. The option to purchase either CNG or diesel buses for the BRT project was assessed by considering the pros and cons of both options in terms of technical as well as economic viability.

188. Firstly, a reliable and uninterrupted supply of CNG is difficult to guarantee in Pakistan in comparison to the supply chain of diesel, which is much more streamlined and reliable.

189. In terms of economic viability, CNG buses currently cost, on average, approximately 70,000 USD more to purchase than equivalent diesel buses. In addition, in order to ensure a reliable and uninterrupted supply of CNG, fueling stations will need to be constructed which will cost approximately 26,000 USD per bus. Based on experience globally, it has been observed that the payback period on the incremental purchase cost of CNG buses and fueling infrastructure, compared to diesel buses, is between five to eight years.²

190. The emissions from new diesel buses and new CNG buses are comparable with both type of buses emitting low levels of NOx, PM and HC. It is important to mention that a new diesel bus in comparison to an old diesel bus emits 94 percent less NOx per mile, 98 percent less PM and 89 percent less HC. In comparison, a CNG bus emits 80 percent less NOx, 99 percent less PM and 100 percent less HC in comparison to an old diesel bus. Thus, there is a minimal difference in emission levels between new diesel and new CNG buses.

² http://www.catf.us/resources/publications/files/20120227-Diesel_vs_CNG_FINAL_MJBA.pdf

191. The wells to wheels³ emissions from new diesel buses total 3,840 g CO₂-e per mile, a 9 percent reduction compared to older buses. In the case of new CNG buses, the wells to wheels emissions from CNG buses total 3,655 g CO₂-e per mile, 5 percent less GHG emissions than compared to new diesel buses.
192. There is a high variation in the quality of CNG available in the country with different gas stations offering a large variation in the composition of the CNG being sold, despite offering the CNG at a uniform price. This itself is a major concern since the life of buses would be significantly reduced and their downtime would steadily increase with time if high quality CNG of a uniform composition is not available throughout the year.
193. There is a minimal difference in emissions and resulting impact on air quality from both diesel and CNG buses. However, in terms of economic viability, there is a considerable difference in the cost of procuring CNG buses in comparison to diesel buses.

Life Cycle Cost Comparison of Diesel versus CNG buses

194. The net present value of total incremental life cycle costs for conversion of a typical 200-bus depot to clean fuel operations with either CNG or filter-equipped diesel buses are summarized below in Table 5.2.

The following assumptions were used for this life cycle cost analysis:

- The discount rate is 6%
- The time frame for the analysis is 30 years, assuming that the capital investments for facility modifications and incremental bus purchase costs are made in year 1 and the incremental operating costs are expended every year. As discussed below, since the facility investments have a longer life cycle than the bus investments, the incremental bus purchase costs are repeated during the 30-year time frame.
- Facility investments (ie for diesel fuel or CNG infrastructure) have an effective life of 30 years. These investments are only made once during the analysis time frame, in year 1.
- Transit buses have an effective life of 15 years, so that incremental purchase costs for CNG buses will have to be made in year 1 and year 15.
- Diesel particulate filters (DPFs) have an effective life of 7 1/2 years, so that the purchase of DPFs will have to be made in year 1, year 8, year 15, and year 22.
- It is typical for transit agencies to invest in “overhauls” of transit buses throughout their life, including an overhaul or replacement of the engine some time between

³ Wells to wheels emissions take into account the production and distribution of the fuel. It is a type of analysis that allows emissions to be compared over the entire lifecycle of a vehicle.

the 7th and 10th years of life. These investments were excluded from the analysis since they apply equally to CNG and diesel buses, and would generally be offsetting. This is a conservative assumption, since based on current experience the overhaul or replacement of a CNG engine would be expected to be more expensive than the overhaul or replacement of a diesel engine.

Table 5.2: Comparison of NPV of Total Incremental Costs: CNG versus Diesel

Alignment Option	CNG	Diesel
NPV of Incremental Capital Costs	\$ 33,653,806	\$ 3,448,862
NPV of Incremental Operating Costs	\$ 33,651,891	\$ 6,732,158
NPV of Total Incremental Costs	\$ 70,305,697	\$ 10,181,020
Annualized NPV of Total Incremental Costs	\$ 2,343,523	\$ 339,367

As shown, over 30 years of operation (the life of the original facility investments required for CNG operation) the use of filter-equipped diesel buses at one 200-bus depot will cost \$10.2 million in net present value terms more than the cost of operating today's "baseline" diesel buses, or \$339,000 more per year. Alternately, the use of CNG buses at the same depot would cost \$70.3 million more in net present value terms, or \$2.3 million more per year than the cost of operating today's "baseline" diesel buses.

The cost of operating 200 CNG buses for 30 years would be \$60.1 million more than the cost of operating 200 filter-equipped buses, or \$2 million more per year. The above analysis includes a one-time investment of \$20 million to upgrade a 200-bus depot.

Keeping in view all these aspects, it was decided to procure new diesel buses for the proposed BRT project instead of CNG buses.

5.2.3 'At Grade' versus 'Elevated' Sections

195. The development of elevated sections along the BRT corridor has been minimized as far as possible to reduce costs and to ensure only those sections shall be 'elevated' where high level of impacts would take place if the 'At Grade' option was implemented. Although a direct comparison between these two options might make the 'At Grade' option seem preferable, however the 'Elevated' option has a high number of benefits, both from the environment and social perspectives, in certain specific locations where high traffic congestion exists and a high level of sensitive receptors are present. A comparison from an environmental perspective of these two options has been provided below as Table 5.3.

Table 5.3: Comparison of ‘At Grade’ versus ‘Elevated’ Sections

Item	At Grade	Elevated
Aesthetic View and Landscape	Good	Not good since the view will be limited by high elevation of the road
Working Conditions	Low risk of accidents for the worker and surrounding areas due to work at ground level	High risk of accidents for the worker and surrounding areas due to work at high elevation
Air Pollution	Construction phase: Medium impacts since dust concentration caused during the demolition activities, material transportation, earth works etc.	Construction phase: Major impacts since dust concentration during the piling, transportation of construction material etc.
Noise Pollution	Increase in noise levels during transportation of construction material	Increasing of noise levels during piling and transportation of construction material
Vibration	Less impact due to construction activities will be at ground level	High vibration levels due to use of boring and excavation equipment
Risk to Historical/Heritage sites	Minimal risk due to the project development taking place at the median of the existing roads.	Higher level of risk due to piling and excavation required which can lead to damage of historical sites at close proximity to the project site.
Damage to Utilities	Minimal risk since no deep excavation or piling will be required.	Higher level of damage can be caused due to excavation and piling required.

5.2.4 Location of Bus Depots

196. The two bus depots to be developed for the proposed project will be located at sites identified at Chamkani and Hayatabad. These two sites are located at the tail ends of the BRT corridor and thus will ensure that all environmental and social impacts are minimized compared to developing these depots within the highly urbanized and congested urban areas of Peshawar city.

197. The two identified bus depot locations are located in comparatively thinly populated areas which contain large open spaces in comparison to the remaining BRT corridor. As a result, all possible environmental and social impacts will be minimized such as impacts on air quality, hazardous waste disposal, traffic congestion, effluent and solid waste disposal. Traffic congestion will also be avoided from high volumes of buses traveling to and from the bus depots since these two locations contain lower traffic volumes compared to the inner Peshawar city.

6 Potential Environmental Impacts and Mitigation Measures

198. This chapter presents the potential environmental impacts related to design, construction and operation phases of the proposed Project. Following is a description of the environmental impacts and the proposed mitigation measures to minimize the negative impacts, if any.

6.1 Design/Pre-Construction Phase

6.1.1 Cultural Heritage, Religious Sites, Social Infrastructure

199. The location of cultural and other heritage sites with respect to the proposed project has been reviewed in Chapter 4. Bala Hisar fort is the only site of historical significance next to the project route. No temples or religious sites are in close proximity to the project site to cause a concern with regards to a possible impact during the project construction and operation. There will be a sufficient buffer distance between the works and the Bala Hisar fort that no significant impact would be expected from the works.
200. As a further precaution, during the excavation works next to the Bala Hisar fort, a representative of the Department of Archaeology shall be present to document any archaeological discovery and take the necessary steps to extract it without any damage being caused to it.
201. The vibration levels from the use of the construction equipment and vehicles will be closely monitored to ensure typical peak particle velocities remain within allowable limits and do not exceed the 5 in/sec limit, in which case major structural damage such as cracking or shifting of foundations or bearing walls can take place.⁴

6.1.2 Land Acquisition and Resettlement

202. The LARP has been prepared based on a census (conducted from 9 Nov to 29 Dec 2016) of 100% potentially Displaced Persons (DPs) that are known at preliminary design stage; a socio-economic survey of 25% project Affected Households (AHs) conducted from 21 Dec 2016 to 5 Jan 2017; and consultations with DPs and other stakeholders. This LARP will be updated during the detailed design stage.
203. The clearing of the right-of-way (ROW) and initiation of civil works on the BRT sites will be contingent to the following conditions (a) preparation of an updated LARP, including a detailed Livelihood Restoration Plan (LRP), following the detailed design (b) endorsement and allocation of the required funds for the updated LARP by TMTD-GoKPK, and (c) approval of the updated LARP by ADB and disclosure to the public.

⁴ http://www.apti.org/clientuploads/publications/2015/Johnson-HannenHiRes_SampleArt_46.2-3.pdf

204. Commencement of civil works on sections/civil works packages with resettlement impacts, to be confirmed and/or determined during detailed design, is conditional to the full payment of compensation, resettlement and rehabilitation cash assistance and allowances, and provision of temporary alternative vending sites to displaced vendors. Livelihood Restoration Plan will be implemented during the construction phase.

205. The preliminary design would cause heavy resettlement impacts. Adjustments were made in the BRT design to avoid and minimize displacement and resettlement to the maximum possible extent.

206. The project will have significant resettlement impacts on 535 households due to acquisition of 117 Kanal (14.6 acres/5.9 hectares) of private arable land, demolition of permanent structures of 2 underpass markets having 84 shops, 4 commercial toilets, 3 kiosks and 12 stores, a horizontal structure of 14 shops, one store room of a business, and two mosques (built in the ROW).

It will also impact the livelihood of 8 non-titleholder of agriculture land, 86 formal businesses/shopkeepers among them is a female headed household whose business is run by her brother; 235 non-titleholder vendors operating road side micro enterprises in the ROW, among them are 2 disabled, 99 employees of formal businesses and their 49 salaried relatives of formal businesses, having separate households; 4 security guards of underpass markets, and one khateeb (prayer leader) of a mosque.

All formal and micro businesses need relocation of their businesses to alternative sites. The leaseholders of 79 shops and owners of 14 shops will lose income from monthly rent of the commercial structures. Among 535 AHs, 349 are vulnerable with 246 severely affected that need additional resettlement and rehabilitation assistance.

207. The project will have an impact on a number of public utilities including relocation of electricity pylons and poles with transmission lines, transformers, water supply stations, drainage systems, and telecommunications infrastructure. There will be temporary impacts on mobility and access of general public due to PBRT construction.

208. A long process of consultation and negotiation was carried out from 21 Dec 2016 to 5 Jan 2017 to address complex resettlement issues and to resolve them amicably with DPs. Consultations were also conducted with a number of other stakeholders. The potentially displaced shopkeepers of underpass markets are keen in getting alternative shops at pedestrian bridges. The displaced vendors are keen in getting formal business spaces at BRT related infrastructure, which have been planned to be established in commercial areas of BRT related infrastructure.

Under PBRT, it is planned to build spaces for about 1100 shops in 4 pedestrian underpasses, 38 access bridges and 24 pedestrian bridges and/or new bus stations

on a rental agreement basis with TransPeshawar Company, giving vendors security of business and opportunities for growth.

209. DPs' and stakeholders' concerns and suggestions have been incorporated in the LARP, Environment Management Plan (EMP) and Gender Action Plan (GAP). Consultation with DPs and other stakeholders will be continued during project implementation.

6.1.3 Identification of Locations for Labor Camps and associated facilities

210. The duration of the construction activity for the proposed project is expected to be 18 months and a considerable amount of work force will be engaged. As a result, worker camps will need to be developed and associated facilities will need to be provided such as electricity, washrooms for labor with suitable effluent and sewage disposal facilities as well as water for their everyday use for drinking and bathing etc.
211. In order to prevent a nuisance, specific locations shall be designated along the proposed project corridor for development of the labor camps. All necessary facilities and amenities shall be provided in these camps such as electricity, sufficient supply of water, solid and liquid effluent waste disposal facilities etc.
212. The use of proper planning while identifying locations for the labor camps will ensure there is minimal disturbance to all key receptors along the project corridor and the traffic is not disrupted by labor camps being set up road side next to the construction site.

6.1.4 Development of Traffic Management Plan

213. The proposed BRT corridor will be constructed on existing traffic routes. Construction activities along these routes are likely to cause hindrance in traffic flow if not mitigated properly.
214. A traffic management plan is presently under preparation by experts specifically engaged for this task by ADB. The finalized plan shall be provided to the Contractor for implementation prior to commencement of the project construction activity. The main objectives of the plan shall be to maximize the safety of the workforce and the travelling public while keeping the traffic flowing as freely as possible.
215. The detailed traffic plan shall ensure that traffic is diverted to alternate routes wherever possible and will minimize traffic jams and bottlenecks along the project corridor and also minimize the chances of traffic related accidents.
216. The plan will include consideration of the following:
- Lane availability and minimization of traffic flows past the works site
 - Establishment of acceptable working hours and constraints

- Agreement on time scale for works and establishment of traffic flow/delay requirements
- Acceptability of diversion routes where necessary
- Need for road closures and necessary orders
- Co-ordination with other planned road and street works
- Establishment of incident management system for duration of the works

The plan shall be approved by PDA and necessary resources will be provided to implement the plan with the involvement of the traffic police.

6.2 Construction Phase

217. The summary of potential impacts during the Construction phase are provided in Table 6.1 below.

Table 6.1: Summary of Possible Impacts during Construction Phase

S/No.	Environmental Aspect	Potential Issue from Environmental Aspect	Potential of Impact	Mitigation Measures
1	Ambient Air Quality	Dust emissions from site preparation, excavation, material handling & other construction activities at site.	Dust emissions expected at work site and at closest key receptors. However, minor and short-term impact expected which will be temporary in nature.	Regular water sprinkling on the exposed surfaces to reduce dust emissions and proper maintenance of all equipment at regular intervals to minimize impact of exhaust emissions
2	Noise & Vibration	Noise & Vibration generated from construction activities, operation of construction machinery, equipment and their movement.	Noise levels expected to vary during activity based upon the nature of work being conducted. Higher noise levels expected at site but minor impact expected at key receptors. Impact expected to be short term in nature.	Necessary control equipment and techniques to be applied to control noise and vibration levels and limit their nuisance effects
3	Water Quality	Surface runoff from project site of Oil/fuel and waste spills as well as improper disposal of debris and	Minor negative impact expected.	Construction methods and techniques and mechanism for disposal

		discharge of sewage from labor camp.		of effluent to be designed for proper drainage and control of discharge
4	Solid Waste	Disposal of excavated soil, construction debris and other waste including domestic waste, which can cause soil contamination and other health and safety issues.	Minor negative impact expected.	Proper solid waste management programme to be designed and implemented
5	Land Use	Demolition/excavation on the BRT route requiring rehabilitation	Minor negative impact expected	Demolition/excavation and rehabilitation to be conducted as per EMP.
6	Soils	Construction and excavation activity leading to topsoil removal and erosion.	Minor negative impact expected	Necessary measures to be taken to replace removed soil as per EMP.
7	Ecology Flora & Fauna	Habitat disturbance during construction activity.	Project is being developed in a highly urban environment with scarce flora and fauna present in project area. Minor and short term impact expected	Necessary steps to be taken to minimize ecological disturbance wherever applicable, particularly the prohibition of hunting and killing of animals.
8	Socio-economy	Increase in job opportunities expected for residents of Peshawar and neighboring areas. Industry related to provision of raw materials expected to boom. The proposed project is expected to increase the urban aesthetic and landscape profile of Peshawar.	Overall positive impact expected	Fair and transparent hiring policy must be maintained for the project. Project sustainability must be ensured through regular and proper maintenance of infrastructure.
9	Traffic pattern	Vehicle movement and possibility of traffic congestion on the road.	Minor negative impact	Traffic management plan to be prepared and implemented one month before commencement of construction work

6.2.1 Air Quality

218. The ambient air quality levels at five different points of the project corridor have already been presented and discussed in Section 4.26 below. As can be observed, in general the ambient air quality is within the acceptable NEQS guidelines with PM_{10} being the only pollutant that is exceeding the guidelines at two of the five monitoring locations.

219. Since almost all ambient air quality parameters are within the acceptable NEQS guidelines, thus any additional emissions expected to arise during the construction phase due to the use of construction equipment shall be insignificant. Additional sources of dust from construction of the proposed BRT project and from general handling of materials are likely to create significant additional impacts, particularly where the works are close to sensitive receptors such as residences, hospitals and schools.

The worst effects are likely to take place in the most constricted and congested commercial areas where construction will take place such as Saddar bazar, Soekarno square etc.

220. Potential sources of particulate matter emission during construction activities include earthworks (dirt or debris pushing and grading), exposed surfaces, exposed storage piles, truck dumping, hauling, vehicle movement on unpaved roads, combustion of liquid fuel in equipment and vehicles, land excavation, and concrete mixing and batching.

221. Vehicles carrying construction material are expected to result in increased SPM levels near the haul roads. This can be of potential importance if the vehicles pass through the areas with a high concentration of sensitive receptors such as residences, hospitals and educational institutions.

222. At the construction yard, the dust levels are also expected to increase due to unloading of construction materials. It shall be ensured that most of the excavated material will be used within the project, with minimal cut and fill material to come from outside the site.

223. The pavement works will also generate gas and odor from the asphalt works and vibration from the compaction of the new BRT road pavement. Emissions from powered mechanical equipment will be superimposed on the already high traffic pollution but is expected to disperse rapidly.

224. The quantity of dust that will be generated on a particular day will depend on the magnitude and nature of activity and the atmospheric conditions prevailing on the day. Due to the uncertainty in values of these parameters, it is not possible to calculate the quantity from a 'bottom-up' approach, that is, from adding PM_{10} emissions from every activity on the construction site separately. Typical and worst-

case PM₁₀ emissions from construction sites have been estimated⁵ as 0.27 megagram per hectare per month of activity (Mg/ha-month) and 1.04 Mg/ha-month, respectively.

Fugitive Dust Control

225. The source wise fugitive control measures are provided in Table 6.2 below.

Table 6.2: Control measures for Fugitive Dust emissions

Source	Control Measures
Earth Moving	For any earth moving that is to take place more than 30 meters from the site boundary, watering must be conducted as required to prevent visible dust emissions
Disturbed Surface Areas	Apply dust suppression measures frequently to maintain a stabilized surface. Areas that cannot be stabilized, such as wind driven dust, must have an application of water at least twice a day
Inactive Disturbed Surface Areas	Apply dust suppressants in sufficient quantity and frequency to maintain a stabilized surface
Unpaved Roads	Water all roads used for any vehicular traffic at least twice per day during active operations and restrict vehicle speed to 20 kmph.
Open Storage Piles	Apply water to at least 80 percent of the surface areas of all open storage piles on a daily basis when there is evidence of wind driven fugitive dust or install an enclosure all along the storage piles
Track-out Control	Wash down of construction vehicles (particularly tyres) prior to departure from site.

226. A wide variety of options exist to control emissions from construction sites. The most effective means of reducing the dust emission is wet suppression. Watering exposed surfaces and soil with adequate frequency to keep soil moist at all times can reduce the total dust emission from the project by as much as 75%.⁶ This measure alone can bring down the dust level to less than 100 µg/m³.

Water can be sprinkled by handheld sprays or with the help of automatic sprinkler systems as required.

227. In case surplus water is not available to suppress dust at certain locations, it is recommended that if works are within 10 meters of any sensitive receptors, the contractor shall install segregation between the works at the edge of the median at

⁵ Gaffney, G. and Shimp, D. 1997. *Improving PM₁₀ Fugitive Dust Emission Inventories*. Sacramento, CA. California Air Resource Board. <www.arb.ca.gov/emisinv/pubs/pm10tmp.pdf>

⁶ El Dorado County Air Pollution Control District. 2002. *Guide to Air Quality Assessment: Determining Significance of Air Quality Impacts Under the California Environmental Quality Act*. First Edition. <<http://co.el-dorado.ca.us/emd/apcd>>

the road edge nearest the center to provide a barrier to protect the sensitive receptors and passing traffic. The segregation should be easily erectable 2.5 meter high hoarding /fiber boards and/or steel sheets to make protection fences around the construction site (at each station location and depot site during the construction) within which all construction works can take place. They can be moved from site to site along the BRT route as the work proceeds.

228. The need for large stockpiles shall be minimized by careful planning of the supply of materials from controlled sources. Stockpiles should not be located within 50 m of schools, hospitals or other public amenities and shall be covered with tarpaulins when not in use and at the end of the working day to enclose dust. If large stockpiles ($>25\text{m}^3$) of crushed materials are necessary they should be enclosed with side barriers and also covered when not in use.

229. Construction materials that are susceptible to dust formation will be transported only in securely covered trucks to prevent dust emission during transportation.

230. Aggregate material will be delivered to the batching plant in a damp condition, and water sprays will be applied, if needed, to reduce dust emissions.

Vehicular & Equipment Emissions

231. It shall be ensured that the following measures are taken to control emissions from vehicles being used in the construction activity:

- Periodically check and conduct maintenance of the construction machinery and haul vehicles.
- Regularly change the engine oil and use new engines/machinery/equipment having good efficiency and fuel burning characteristics.
- Use of catalytic converters and low Sulphur fuels.
- The stack height of generators will be at least 3 meters above the ground.
- Training of the technicians and operators of the construction machinery and drivers of the vehicles.
- Air quality monitoring at the project site during the construction phase.

6.2.2 Noise and Vibration

232. The assessment of the impacts of noise and vibration on the sensitive receptors at each site of the project corridor depend upon:

- Characteristics of noise source (instantaneous, intermittent or continuous in nature)
- Time of day at which noise occurs, and

- Location of noise source

233. Due to the various construction activities, there will be temporary noise impacts in the immediate vicinity of the project corridor.

234. The construction activities will include the excavation for foundations and grading of the site and the construction of structures and facilities. Powered mechanical equipment such as generators, excavators, bulldozers, piling rigs, stabilizers, drills, stone crushers, graders, vibratory rollers, concrete mixing plants and screening plants can generate significant noise and vibration.

Since various modern machines are acoustically designed to generate low noise levels, any high noise levels that might be generated will only be for a short duration during the construction phase.

235. Depending on the construction equipment used and its distance from the receptors, the community and the workers may typically be exposed to intermittent and variable noise levels. During the day, such noise results in general annoyance and can interfere with sleep during the night. In general, human sound perception is such that a change in sound level of 3 dB is just noticeable, a change of 5 dB is clearly noticeable, and a change of 10 dB is perceived as a doubling or halving of sound level.

236. Due to the various construction activities, there will be temporary noise impacts in the immediate vicinity of the project corridor. The construction activities will include the excavation for foundations and grading of the site and the construction of structures and facilities. Crushing plant, asphalt production plants, movement of heavy vehicles, loading, transportation and unloading of construction materials produces significant noise during the construction stage. However, these increased noise levels will prevail only for a short duration during the construction phase.

237. The assumptions made while conducting the noise level projections are as follows:

- No noise abatement at source
- Minimal attenuation
- Different construction equipment operation scenarios were explored
- All the noise-generating sources from the site act as one source
- Standard internationally accepted equipment noise levels have been assumed (see Table 3.2).

238. The analysis presented in this section is based on the approach recommended by Federal Highway Administration of the US Department of Transportation for assessment of construction noise.⁷

⁷ Reagan, J. A. and C. A. Grant. *Highway Construction Noise: Measurement, Prediction, and Mitigation. Special Report.* US. Department of Transportation, Federal Highway Administration. Available from <<http://www.fhwa.dot.gov/environment/noise/highway/index.htm>>

The modeling of noise levels as a result of the proposed construction activities has been conducted using a Mathematic model for Sound Wave propagation that has been developed specifically for this purpose. In order to estimate the noise dispersion, it has been assumed that all the noise-generating sources from the site act as one source. Thus, the total noise generated from all equipment will be confined to about 108 dB(A) which as mentioned above is a highly conservative scenario and the actual noise levels at the construction sites are expected to be lower than the estimates provided here.

239. The model is based on the standard acoustical equations with the sound pressure level generated by noise sources decreasing with increasing distance from the source due to wave divergence. An additional decrease in sound pressure level with distance from the source is expected due to atmospheric effects or its interaction with objects in the transmission path.
240. Three different scenarios for assessment of noise levels generated from operation of different types of construction equipment for the proposed project were examined and are presented in Table 6.3 below.

Table 6.3: Noise Level Scenarios from Construction Machinery

Scenario	Loudest Equipment	Leq@15m (dBA)	Noise Level (dBA) at 15m
A	Truck	88	89
	Grader	83	
	Backhoe	88	
B	Truck	88	90
	Backhoe	88	
	Concrete Mixer	92	
C	Front End Loader	85	89
	Grader	83	
	Pneumatic Tools	88	


241. As can be observed, the highest noise level generated was 90 dB(A) from Scenario 'B. The other two scenarios i.e. 'A' and 'C' also each produced very comparative noise levels of 89 dB(A).
242. The input to the model has been taken as the cumulative noise of all the noise generating sources, unique for each specific scenario. The coordinates X and Y are taken as the input to the model, which is correlated with the grid size and scale (1:100 m). Thus, the center of the project area is defined as 0,0 coordinates.
243. The isopleths and noise levels obtained through this model are provided as Figure 6.1 below. It is observed from the isopleths (contours) that high noise levels will be confined to the work zone areas only. It can be observed that the noise levels get attenuated rapidly with the distance. Also, the contours showing the noise levels

at the receptors around each BRT station during the construction phase are provided in ANNEX E as Figures E-1 to E-31.

244. It should be noted that the predicted noise levels indicate noise contours of 50 dB(A) along the BRT project corridor at a distance of about 180 meters from the center of the source which is within the NEQS day time limits for noise for both residential and commercial areas. Thus, there will not be any significant increase in the existing ambient noise levels for receptors located at this distance.
245. The sensitive receptors lying within the project area of the BRT corridor have been clearly marked and classified in the noise maps into specific 'to clearly present the specific noise zone applicable to them. Thus, all receptors have been categorized based on whether they lie in the 'Silence zone', 'Commercial zone', 'Industrial zone' or 'Residential zone' since the permissible day and night noise level thresholds vary for each zone.
246. Also, since noise barriers shall be installed at different locations along the proposed project corridor, an attenuation of approximately 7 dB(A) is expected, resulting in a further decrease in the noise levels reaching the sensitive receptors as a result of the construction activity. The resulting noise levels at the different sensitive receptors are illustrated through noise maps provided in ANNEX F.
247. Thus, in reality maximum noise levels at any receptor after incorporating the attenuation factor due to the noise barriers is expected to be only 83 dB(A). Also, keeping in view the existing high baseline noise levels in the project area of up to 91 dB(A) as shown in Figure 4.24, the increment in noise levels due to the project construction activity shall be less than 1 dB(A). As a result, the noise levels generated from the project construction activity shall remain within the 3 dB(A) increment limit, applicable for high noise environments.
248. Moreover, it shall be further ensured through periodic monitoring to ensure that any increase in noise levels resulting from the construction activity is not greater than 3 dB(A) since the project area is already a high noise disturbed environment.
249. Before site works commence, a Noise Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas, etc.) due to construction works, sourcing and transport of construction materials, and other project-related activities.
250. Use only vehicles and equipment that are registered and have necessary permits.
251. It shall be ensured that equipment noise is reduced at source by proper design, maintenance and repair of construction machinery and equipment. Also, noise from vehicles and power generators will be minimized by use of proper silencers and mufflers.

252. Equipment emitting excessive noise in comparison with other similar equipment will not be allowed to operate and will be checked to determine if it can be improved, and replaced with less noisy equipment as soon as practicable.
253. Acoustic insulation shall be installed or portable noise barriers or hoardings shall be installed where practicable to limit noise to protect sensitive areas such as educational institutions, hospitals, residential areas etc.
254. Blowing of horns by the construction vehicles will be prohibited on the access road to the project site and at the site.
255. Stationary noise sources such as batching plants will be kept as far away from the community as possible.
256. Construction work will only be carried out during daytime and occasionally in the evening up to 9 pm. If construction works continues overnight, care will be taken to keep noise within the night time limit of NEQS at the nearest receptor.
257. Noise levels will be monitored on bi-monthly basis at the key receptors in the project area in order to take timely corrective measures, if needed.
258. Impose speed limits on construction vehicles to minimize noise emission along areas where sensitive receptors are located (houses, etc.).
259. Provide temporary noise barriers (3-5 meter high barrier can reduce 5-10 dB(A), as necessary, since works near sensitive receptors will generate high noise levels that could cause disturbance.
260. As much as possible, use quiet equipment and working method.
261. Whenever possible, completely enclose noisy equipment which can reduce noise level by 15-25 dB(A), restrict use of noisy equipment (e.g. 15 min for every consecutive 30 min period) and undertake sequential operation of equipment with objective to reduce noise generated;
262. Provide prior notification to the community on schedule of construction activities.
263. Implement community complaints hotline.
264. Prior to commencement of construction activity, consultations will be organized with the key sensitive receptors along the BRT corridor such as hospitals, schools and hotels. Also, it shall be ensured as far as possible that construction activity near schools is conducted during their vacation period.

Figure 6.1: Predicted Noise levels during Construction Phase



6.2.3 Management of Traffic

265. The project corridor is quite congested in certain segments where a high level of traffic volumes and commercial activity takes place, particularly the segments such as Hospital Road, Khyber Bazaar, Soekarno Square and Saddar Bazaar etc.
266. The efficient management of traffic once the construction activity commences will be critical in order to minimize the risk of possible road accidents and construction related hazards.
267. Traffic signs and warning instructions shall be displayed at the sites and along the proposed routes being used by the construction traffic for the information of other road traffic as well.
268. Public awareness campaigns through radio and newspaper advertisements shall be conducted to educate the public and sensitize them to cooperate with the construction staff and project focal staff in order to try and avoid the areas under construction as far as possible, particularly during the peak times when traffic volumes and pedestrian movement is the highest.
269. The potential risks of accidents to pedestrians and commuters while in the immediate vicinity of construction sites shall be conveyed to them in order to educate them and gain their cooperation and minimize the risk of accidents.
270. Employ flag persons to control traffic at the work sites for safety reasons when construction equipment is entering or leaving the work area.
271. Lanes shall be created through the work site using rope or flagging to minimize risks and injuries from falling objects.
272. As much as possible, lifting and placing of the pre-cast sections will be done at night to minimize traffic congestion.
273. Post traffic advisory signs (to minimize traffic build-up) in coordination with local authorities.
274. Provide road signs indicating the lane is closed 500 m before the worksite.
275. Use traffic cones to direct traffic to move to the open lane.
276. Provide sufficient lighting at night within and in the vicinity of construction sites.
277. Regularly monitor traffic conditions along access roads to ensure that project vehicles are not causing congestion.

- 278. Define and observe schedules for different types of construction traffic trips (e.g., transport of pre-cast sections, haulage of spoils, delivery of construction materials, etc.).
- 279. As much as possible, schedule delivery of construction materials and equipment as well as transport of spoils during non-peak hours.
- 280. Avoid movements of noisy vehicles during night time in vicinity of sensitive receivers.
- 281. Implement suitable safety measures to minimize risk of adverse interactions between construction works and traffic flows through provision of temporary signals or flag controls, adequate lighting, fencing, signage and road diversions.
- 282. Ensure relocation of any affected public transport infrastructure (but stops, shelters etc.) prior to commencement of works.
- 283. Provide advance notification to the community regarding changes to public transport facilities or routes.
- 284. Schedule construction works to minimize extent of activity along linear construction site at any one time.
- 285. Comply with traffic regulations and avoid, where possible, roads with the highest traffic volumes, high density of sensitive receivers or capacity constraints are not used as access to and from the construction areas and spoil disposal sites.
- 286. Install temporary accesses to properties affected by disruption to their permanent accesses.
- 287. Reinstate good quality permanent accesses following completion of construction.

6.2.4 Water Resources

- 288. Water shall be used during the project construction in the labor camps for the everyday use of the laborers for cooking, drinking and bathing etc. Also, water shall be used at the sites along the project corridor for sprinkling to suppress dust emissions. In addition, water shall also be used during the construction activity itself for mixing of gravel in the batching plant etc.
- 289. Water is available in sufficient quantities along the entire project corridor and will be sourced either through pipes taken from the nearest municipal connection or through bowzers that shall be brought to the specific sites along the corridor. If felt necessary, temporary bore wells will be dug and will be restored to their original condition once the construction activity has been completed.
- 290. Even though there is no issue with water availability and the project construction will only be requiring limited quantities of water that will be easily

manageable, however it shall be ensured through monitoring that wastage of water is prevented both at the project sites as well as at the labor camps.

6.2.5 Safety precautions during Construction work

291. The project construction activity will be conducted in a thickly populated area with high volumes of pedestrians and vehicular traffic. The risk of accidents taking place will be high, particularly from falling objects during work being conducted on elevated structures, falling of beams and metal rods as well as the potential of accidents of vehicles with construction machinery.
292. The general track record of Contractors in the country with regards to following safety protocols during construction work is not very impressive with safety precautions mostly felt to be an impediment to fast pace of work.
293. Keeping in view the significant risk posed by the construction work to the surrounding commuters and pedestrians, it shall be ensured that the Contractor provides his staff with a provided detailed orientation on the safety protocols to be followed at all times during the construction work to minimize the risk of accidents.
294. The Contractor shall provide bi-monthly refresher sessions to his staff on the safety precautions to be followed during the construction activity.
295. The Contractor will closely monitor his staff at all times and will take strict action against any non-compliance with these protocols and will ensure at all times that the safety of the commuters and traffic in the vicinity of the project site are kept a priority.

6.2.6 Camp effluent

296. The staff and labor camps for the construction of the proposed BRT will be a source of wastewater generated from the toilets, washrooms and the kitchen. The wastewater will not meet the national environmental standards and will therefore need treatment prior to disposal.
297. The project sites along the project corridor where construction is being conducted must not be treated by the project staff and/or labor as a public toilet or for disposal of camp effluent.
298. It will be ensured that no untreated effluent is released to the environment.
299. A closed sewage treatment system will treat the effluent, which will then be disposed of in a soak pit or will be used for plantation. The sewage treatment plants will be installed at each respective labor camp based on the number of laborers residing at the respective camp. The detailed design study for the proposed project will develop and propose suitable sewage treatment plants for installation by the Contractor at each of the respective labor camp sites.

6.2.7 Soil Erosion and Sedimentation

300. The majority of the road works proposed are designed to be within the existing median of major roads on paved surfaces and therefore soil erosion and sedimentation should not be a significant impact.
301. Any drainage structures, cross road tunnels, culverts or pipes crossing the BRT corridor may need to be modified or protected and the detailed designs must make provisions to protect or re-provision all infrastructure that may be affected by the construction works.

6.2.8 Soil Contamination

302. During the project construction, spills of fuel, lubricants and chemicals can take place while transferring from one container to another or during refueling. Also, during maintenance of equipment and vehicles, through leakages from equipment and containers and as a result of traffic accidents.
303. Depending on the nature of the material, location of spill and quantity of spill, the soil can get contaminated.
304. It will be ensured that spill prevention trays are provided and used during refueling stations. Also, on-site maintenance of construction vehicles and equipment will be avoided as far as possible. In case on-site maintenance is unavoidable, tarpaulin or other impermeable material will be spread on the ground to prevent contamination of soil.
305. Regular inspections will be carried out to detect leakages in construction vehicles and equipment and all vehicles will be washed in external commercial facilities.
306. Fuels, lubricants and chemicals will be stored in covered bounded areas, underlain with impervious lining. Appropriate arrangements, including shovels, plastic bags and absorbent materials will be available near fuel and oil storage areas.

6.2.9 Drainage and Storm Water Run-off

307. The storm water run-off from the construction site could carry oil and grease if the soil is contaminated or the potentially contaminated areas (oil and grease storage areas, maintenance areas and workshops) are in hydrological contact with the surrounding areas. Any risk may be eliminated by taking measures to avoid spillages and taking immediate remedial measures in case of accidental spillage of oil.
308. All unpaved exposed areas at the project sites will be compacted to minimize water erosion and all areas containing potentially hazardous materials will be hydrologically isolated from the remaining site.
309. It shall be ensured that natural drainage is not hampered or blocked in any way at any of the sites.

6.2.10 Hazardous and Non-Hazardous Waste Management

310. In the absence of national or domestic regulations and a waste management system in the project area, waste disposal can potentially become a serious environmental issue, particularly with the local contractors. To avoid any potential issue, the project proponent will have to impose adequate internal controls.
311. A waste management plan will be developed prior to the start of construction. This plan will cater to sorting of hazardous and non-hazardous materials prior to disposal, placing of waste bins at the sites along the project corridor for waste disposal and an onsite hazardous waste storage facility.
312. Periodic on-site audits of waste management will be undertaken along with auditing of waste disposal contractors and disposal facilities on regular basis to check that procedures are being followed.
313. Records of all waste generated during the construction period will be maintained. Quantities of waste disposed, recycled or reused will be logged on a Waste Tracking Register.
314. Licensed waste contractors will be engaged to dispose off all non-hazardous waste material that cannot be recycled or reused.
315. Training will be provided to personnel for identification, segregation and management of waste.

6.2.11 Historical/Archaeological Sites

316. There is only one historical site within the project area i.e. the Bala Hisar fort. While conducting the excavation activity next to the fort, a staff member from the department of Museum and Archaeology shall be present at all times. If evidence of any archaeological remains are found during the construction activities, the excavation work will be stopped immediately and necessary next steps taken to identify the archaeological discovery.

6.2.12 Vegetation and Wildlife Loss

317. The project consists of an urban built environment with minimal vegetation cover. However, during construction, any vegetation present on the median lane will be removed. All trees will be retained along the project corridor wherever possible since the removal of trees will result in the local ecosystem being changed.
318. Wherever trees have to be felled, mitigation will be required in the form of reinstatement and compensatory planting. Soft landscaping shall be installed in the median under the elevated sections to improve the appearance of the completed works.
319. In case existing trees and topsoil (down to 0.5 meters) is removed, the top soil shall be retained for elsewhere in the project. The wood that would be cut will not be

burnt on site. All stumps and surplus vegetation shall be disposed of at landfills via routes or other destinations as designated and instructed by PDA focal points.

- 320. The impact of project activities on the wildlife in the area is likely to be insignificant as the area has a long area of human occupation, to which most of the animal species have adapted over time.
- 321. It will be ensured that willful killing; trapping and trade of faunal species will be strictly prohibited.
- 322. Tree plantation will be undertaken at the project site to compensate for the vegetation lost during construction in the minimum ratio of 3:1 i.e. 3 saplings to be planted for every tree felled given the possible difficulties with establishing trees and low survival rates of young trees.
- 323. Burning of vegetation as fuel will be prohibited.

6.2.13 Community Safety

- 324. The proposed project will involve the use of considerable heavy machinery as well as excavation and erection of civil structures such as overhead bridges in congested environments of the project corridor. The risk to community will be significant in certain instances and thus a number of precautionary measures will be necessary to minimize the risk of a possible accident.
- 325. Work areas outside the project site, especially where machinery is involved will be roped off and will be constantly monitored to ensure that local residents, particularly children stay away. Also, no machinery will be left unattended, particularly in running condition.
- 326. Community will be briefed on traffic safety, especially women who are the main care providers to children.
- 327. Speed limit of 20 km/hr will be maintained by all project related vehicles on the section of the roads and passages adjacent to the houses near the project boundary and nighttime driving of project vehicles will be limited where possible.

6.2.14 Employment Conflicts

- 328. The proposed project is not likely to create any significant permanent job opportunities. Even unskilled and semi-skilled employment opportunities that are likely to be created will be for a short period while the project is constructed. As persons with relevant skills may be available locally within Peshawar, people from the project area are likely to fill a significant number of the semi-skilled and skilled jobs.
- 329. This issue of provision of jobs can become particularly problematic if it is perceived by the local population that a significant number of construction-related jobs opportunities are not given to people from the local community. This can result

in friction between local residents and construction workers from outside of the community.

- 330. The understanding of 'local' needs to be clear as being residents of the project area (i.e. city of Peshawar and its suburbs). These Project Affected Persons (PAPs) will be given priority for construction jobs as long as they possess the minimum skills for such a job.
- 331. The Construction Contractor will adopt a transparent hiring policy. Prior to the commencement of the construction activity, the local communities in the project area will be informed of the employment policy in place and number of people that can be employed for this project.
- 332. It will be ensured that maximum number of unskilled and semi-skilled jobs will be provided to the residents of Peshawar and its suburbs.
- 333. PDA will ensure a balanced process of employment of the communities in the project area with preference given to those most directly affected by the project.

6.2.15 Communicable Diseases

- 334. Communicable diseases such as HIV may be introduced due to the immigration of workers associated with the project. A communicable diseases prevention program will be prepared for construction workers or residents near the construction sites.

6.2.16 Land Use and Aesthetics

- 335. The proposed project will build on the existing road with a minor change in the land use pattern of the area. Aesthetic and visual impacts during the construction phase will be visible along the corridor and particularly in areas that are congested. However, the construction of the BRT stations will have a positive impact on the urban aesthetics and architectural beauty they will bring to the city's real estate line. The construction of BRT related infrastructure will add structural beauty and value to the city.
- 336. However, the erection of barrier walls along the track will have some displeasing effect on the overall aesthetics, which is unavoidable keeping in view safety requirements.

6.2.17 Utilities provision interruption

- 337. The project will require demolishing and relocating some of the structures within the ROW such as water supply pipes, drainage structures, electric and communication cables. Temporary suspension of services (planned or accidental) can affect the economy, industries, businesses and residents' daily lives.
- 338. PDA, as the implementing agency, will be responsible for ensuring all permits and clearances are obtained prior to commencement of work at each section of the

project corridor. In addition, PDA will ensure that detailed contingency plans are prepared prior to commencement of construction activities at specific areas of the corridor to mitigate any potential impacts resulting from outage of utilities.

339. Based on the initial surveys conducted along the BRT corridor, there are approximately 197 electric poles within a 10-meter buffer on either side of the project corridor and approximately 78 telephone poles within this buffer.
340. Contractors will assess construction locations in advance for potential disruption to services and identify risks prior to starting construction. Any damage or hindrance/disadvantage to local businesses caused by the premature removal or insufficient replacement of public utilities is subject to full compensation, at the full liability of the contractor who caused the problem.
341. If temporary disruption is unavoidable, the contractor will, in collaboration with relevant local authorities such as power company, water supply company and communication company, develop a plan to minimize the disruption and communicate the dates and duration in advance to the affected persons.
342. Communities shall be informed in advance regarding storage of water when their utilities are about to be relocated to pave the way for road works. Also, water pipes located/crossing in the right of way (road reserve) may be moved slightly away from the road or provision of service duct may be considered.
343. Construction billboards, which include construction contents, schedule, responsible person and complaint phone number, will be erected at each construction site.
344. The project infrastructure shall pass through the median of the existing roads along the proposed corridor, with minimal utility infrastructure, if any, located under these roads. Thus, minimal or no utility infrastructure shall be affected.
345. Also, for any specific sections along the corridor where either tunnels or elevated sections are to be developed and piling work will be involved, prior to construction at any such section(s), the relevant utility master plans shall be reviewed and the construction activity planned accordingly to ensure disturbance to existing utilities is minimized. Once the project enters the detailed design stage, these master plans shall be obtained from the concerned utility departments in order to plan the construction activity accordingly.

6.2.18 Natural and Man made Hazards

346. Natural disasters include windstorms, floods, earthquakes which may be experienced during the construction phase. However, the likelihood of such events is quite low and the effect on the project in the case of an occurrence of such a natural calamity on the health and safety of the workers and affected population can be minimized by adopting appropriate and adequate mitigation measures.

347. Fire accidents and terrorist/sabotage activities are something that cannot be predicted or foreseen but can be prepared for by taking precautionary measures such as training of staff and acquiring extra safety and security measures.

6.3 Operation Phase

348. The introduction of modern BRT buses with low emissions coupled with removal of older buses from the traffic fleet is expected to deliver some reductions in ambient levels of noise and air pollution.

349. The impacts in the operation phase are critically important since the impacts in the operation phase of the project are 'long term'.

350. The summary of potential impacts during the Operation phase are provided in Table 6.4 below.

Table 6.4: Summary of Possible Impacts during Operation Phase

S/No.	Environmental Aspect	Potential Issue from Environmental Aspect	Potential of Impact	Mitigation Measures
1	Ambient Air Quality	Particulate and gaseous emissions from buses	No significant impacts with project related increment to baseline ambient quality within acceptable limits	No negative impacts. However, vehicle maintenance and emission controls to be conducted in the long term to protect air quality
2	Noise & Vibration	Noise resulting from movement of buses	No significant impact at the sensitive receptors along the project corridor. New generation of vehicles will generate less noise.	No negative impacts.
3	Water Quality	Oil/fuel and waste spills. Discharge of sewage. Discharge of contaminated storm water.	No significant adverse impacts expected. No wastewater discharge outside the premises to the nearby water source.	Wastewater treatment at depots will be installed to mitigate the impact.
4	Land contamination	Accidental fuel and material spills	No negative impact expected.	Proper waste management plan and spill response plan to be implemented

5	Ecology, Flora and Fauna	Land use Change	No negative impact	-
8	Socio-economy	Increased job opportunities Improvement of infrastructure facilities Wider economic growth Reduced health risk and accidental hazards	Overall positive impact expected and socio-economic conditions of region can improve	Project sustainability must be ensured through regular and proper maintenance of infrastructure.
9	Traffic pattern	Improved roads without any obstruction	Positive impact	-

6.3.1 Air Quality

351. There is strong evidence from different BRT projects implemented across the world to suggest that a significant improvement in air quality in the project area can be expected once the proposed project is operational. The concentrations of key pollutants such as CO, NO_x, PM₁₀ and PM_{2.5} have been observed to be reduced significantly. This is attributed to a number of reasons such as reduced traffic congestion on the roads with a larger number of persons using the BRT and the avoidance of traffic jams ensuring the idling times for vehicles is significantly reduced. In addition, the replacing of new BRT buses with efficient engines replacing to some extent old and inefficient public and private vehicles is expected to be another major factor in improvement of the air quality in Peshawar once the project is operational.⁸

352. The project operation phase input parameters and assumptions used to develop the air emission simulation are provided in Table 6.5 below.

353. The impact of operation of the BRT buses along the project corridor on the ambient air quality of the project area up to 1 km from the project route has been modeled using the internationally accepted simulation software 'BREEZE ROADS' which is a complete air dispersion modeling suite that includes CALINE4, CAL3QHC and CAL3QHCR models. These air dispersion models are used within the software program to predict air quality impacts of Carbon monoxide (CO), particulate matter (PM) and other inert pollutant concentrations from moving and idle motor vehicles at or alongside roadways and roadway intersections.

⁸ Germa Bel and Maximilian Holst, 2015. 'Evaluation of the Impact of Bus Rapid Transit on Air Pollution'. Research Institute of Applied Economics.

Robert Cervero, 2013. 'BRT: An Efficient and Competitive Mode of Public Transport'. Institute of Urban and Regional Development.

354. BREEZE ROADS is used in conjunction with emissions data from MOBILE or other emission models to demonstrate compliance with NEQS and modeling for highway site and design selection.

355. It was assumed that the background concentrations and emission rate of each of the pollutants remained constant throughout the gridding domain (Northeast X 8246.42 m, Northeast Y; 4094.14 m) of the image map of the project site.

356. The model predicted the output on 1 hourly and 8 hourly-averaged concentrations of CO and 1 hourly and 24 hourly averaged concentrations for PM emissions. As part of the model input, the BRT segments that are 'at grade' were defined separately from the segments that are elevated.

357. The predicted concentrations output by the model are the 'Incremental Concentrations' from the project activities of the BRT operation. The 'Cumulative' concentrations are obtained by adding the ambient pollutant levels to the respective incremental levels (predicted by the model simulation as a result of the proposed BRT operation) for each pollutant.

The hourly surface meteorological data for 2015 obtained from the Peshawar International Airport was used in the modeling and the dominant wind was South-West and North East during the year.

358. The maximum concentration of CO was 204.016 $\mu\text{g}/\text{m}^3$ (0.204 mg/m^3) and 13.518 $\mu\text{g}/\text{m}^3$ (0.0135 mg/m^3) for 1 hour and 8 hourly averaged respectively. The model estimated that the mean concentrations of 23.89 $\mu\text{g}/\text{m}^3$ and 13.176 $\mu\text{g}/\text{m}^3$ for 1 hour and 8 hourly which are well within the limits of NEQS for CO. The isopleths (contour) plot for the concentrations for CO for 1 hour and 8 hourly basis are provided in Figures 6.2 and 6.3 respectively.

359. The predicted 1 hour and 24 hourly averaged concentrations of PM were 6.272 $\mu\text{g}/\text{m}^3$ and 2.109 $\mu\text{g}/\text{m}^3$. There is an insignificant increase of PM concentrations in the atmosphere from the proposed project. However, since the ambient concentration of PM_{10} is already exceeding the NEQS limits of 150 $\mu\text{g}/\text{m}^3$ for the 24 hourly average, thus the cumulative concentration is also exceeding the NEQS limits. The isopleths for the concentrations for PM for 1 hour and 24 hourly basis are provided in Figures 6.4 and 6.5 respectively.

360. The results of the model simulation are presented in Tables 6.6 and 6.7 below. The sample model input file is provided as ANNEX H.

Table 6.5: BREEZE Model Input Parameters & Assumptions

Model Input Parameters	Model Assumptions
Total corridor length: 30.8 km Elevated Section: 4 km Tunnel Section: 3.5 km Average distance between stations: 922 meters All buses will run on diesel fuel Each bus will stop at each station for approx. 120 seconds Buses will operate for 365 days a year Average bus speed will be 25 km/hr Wide station platform dimensions: 5 to 6 meters wide Multiple stopping bays (up to 4 buses can stop at same time) 107 buses per hour per direction Station exterior dimensions: 6500 mm Station interior dimensions: 5000 mm	Min. Wind Speed is at least 1 m/s

Table 6.6: Minimum and Maximum Predicted Concentrations of CO and PM

Pollutant Name	Predicted Incremental Concentration (ug/m ³)			
	1 hourly		24 hourly for PM and 8 hourly for CO	
	Minimum	Maximum	Minimum	Maximum
CO	6.652	204.016	3.518	13.176
PM ₁₀	1.712	53.56	0.38	2.109

Table 6.7: Averaged Predicted Concentrations of CO and PM

Pollutants	Averaging Time	Predicted Concentration	Background* Concentration	Predicted Ambient Concentration	NEQS
CO (mg/m ³)	1-hr	0.024	-	-	10
	8-hrs	0.013	3.33	3.343	5
PM (ug/m ³)	1-hr	6.272	-	-	-
	24-hrs	2.109	167.6	169.709	150

* Ambient data collected through 24 hourly monitoring by M/s SGS

Figure 6.2: Isopleths of CO (1st Highest) for 1 hourly averaged Concentrations



Figure 6.3: Isopleths of CO (1st Highest) for 8 hourly averaged Concentrations




Figure 6.4: Isopleths of PM (1st Highest) for 1 hourly averaged Concentrations





Figure 6.5: Isopleths of PM (1st Highest) for 24 hourly averaged Concentrations



6.3.2 Noise

361. The proposed BRT project will result in a reduction in the overall traffic related noise levels since the total traffic volume is expected to decrease as the residents of Peshawar will prefer the BRT, which will offer a reliable and convenient commuting option.
362. The BRT buses will be new vehicles that shall be properly maintained and will follow strict operational protocols such as avoiding honking unless necessary and driving within a certain speed limit, which in turn will reduce the noise levels resulting from traffic movement.
363. Since the BRT buses will travel on a dedicated corridor, thus traffic congestion will be prevented and the noise resulting from honking that is experienced during traffic jams will also be prevented, which can particularly be an issue in the vicinity of sensitive receptors such as hospitals and schools.
364. The expected noise levels as a result of operation of the BRT buses has been calculated using the same model that has been used for predicting the noise levels during the construction phase of the proposed project.
365. The assumptions made while conducting the noise level projections are as follows:
- No noise abatement at source
 - Minimal attenuation
 - Each noise-generating source i.e. BRT bus, along the project corridor acts as one source
 - Typical internationally accepted noise ratings for diesel public buses assumed
366. During the operational phase of the project, the maximum resultant noise levels at the BRT bus stops are expected to be around 80 dB(A) which is a conservative estimate since the new engines of the BRT buses will produce low noise levels and will be quite efficient. Also, the drivers of the BRT buses will not be blowing the horns and these buses will not be calling out loudly to attract customers to board the buses, which is a common practice for public transport in the city. As a result, the actual noise levels will in fact be lower than the estimated 80 dB(A). The estimation of noise dispersion has been calculated using a standard mathematical model for sound wave propagation. These projected operational noise levels have been further corroborated based on multiple references of different international research and analytical studies to assess the noise levels generated from diesel based buses used in urban transport⁹.
367. The noise levels have been predicted from the center of the corridor up to 150 meters on either side of the project route. The isopleths (contours) of the noise levels

⁹ FROST, M.W. and ISON, S.G., 2007. Comparison of noise impacts from urban transport. Proceedings of the Institution of Civil Engineers, Transport, 160(4),165-172.

Jason C.Ross and Harris Miller, 2007. A comparison of green and conventional diesel bus noise levels. NOISE-CON 2007, Reno, Nevada, USA., 4-5.

obtained by modeling at the BRT bus stops are provided in Figure 5.6 below. Also, the contours showing the noise levels at the receptors around each BRT station during the operation phase are provided in ANNEX D as Figures D-1 to D-31.

368. It is observed from the isopleths that moderate noise levels (55 dB(A)) will be confined up to 50 meters from the center of the corridor. The noise levels at 115 meters from the center of the BRT corridor will be around 45 dB(A).
369. The sensitive receptors lying within the project area of the BRT corridor have been clearly marked and classified in the noise maps into specific 'to clearly present the specific noise zone applicable to them. Thus, all receptors have been categorized based on whether they lie in the 'Silence zone', 'Commercial zone', 'Industrial zone' or 'Residential zone' since the permissible day and night noise level thresholds vary for each zone.
370. Based on these noise maps, which contain the noise zones applicable for each sensitive receptor, any exceedances of noise levels from the permissible limits are clearly displayed. In any cases where such exceedances have been observed, it has been assessed that the utilization of measures such as noise barriers or double glazing of windows of nearby buildings will result in noise attenuation and a resulting loss in noise levels by approximately 10 dB(A). As a result, the noise levels at all receptors shall be within the acceptable noise limits for each noise zone.
371. Since the noise levels get attenuated rapidly with the distance, thus the impact during the BRT operation phase will not be felt at the sensitive receptors along the project corridor.
372. In order to ensure attenuation of noise levels, noise barriers shall be provided at all flyovers or on elevated roads that pass through congested localities.
373. Also, BRT buses and all mechanical equipment shall be regularly maintained to ensure compliance with NEQS limits for noise.
374. Strict protocols for driving on the BRT corridor shall be followed and honking shall not be allowed and pre-set speed limits shall be followed.

6.3.3 Impacts on Water Resources

Wastewater Generation and Discharge

375. The operation of the BRT will not directly involve any discharge of effluents into the surrounding environment. However, wastewater will be generated from each depot and workshop area. The runoff from the depot may affect the water quality of the surface and ground water, if the drainage and collection system is not properly designed and fails to function.
376. Although the specific amount of water to be consumed is not known as yet, however the quality of the waste water is expected to be contaminated mostly with oil

and grease and thus it is proposed that a proper wastewater collection and treatment facility should be set up at the depot.

Accidental Spill


377. The contamination of surface and ground water may be possible due to accidental spillage of oil, grease and diesel from the vehicles during the operation phase of the project. An efficient storm water drainage network along the BRT route will minimize the waterlogging.
378. Wastewater collection, conveyance and disposal system shall be installed at the depot and treatment will be carried out prior to disposal. Monitoring shall be carried out at specific locations for any possible incident of contamination and non-compliance to the NEQS.
379. Most of the storm water produced along the BRT route shall be channeled to a well laid out storm water network designed along both sides of the corridor and it will recharge the ground water 'recharge pit' through a sand filter.
380. Rainwater harvesting can help utilize the rainwater and prevent wastage by capturing the run-off.

6.3.4 Solid Waste disposal

381. The operation of the BRT buses will result in domestic garbage being generated from stations and buses as well as from the depots and workshops consisting of dinner boxes, aluminium cans, plastic bottles, tissue paper/paper, newspapers, nutshells and food waste.
382. A proper solid waste management plan will be prepared and implemented to ensure waste containment, collection, transfer and disposal. Also, monitoring will be conducted at specific locations along the corridor and at the depots/workshops to ensure strict compliance with the EMMP in implementing the measures for solid waste management.

6.3.5 Biological Environment

383. No significant impacts are expected to the biological environment from the operational phase of the project. However, since most of the existing green belts shall be demolished to develop the BRT corridor, thus extensive plantation and landscaping shall be conducted to mitigate any impacts.
384. Also, selection of the plant species shall be done on the basis of their adaptability to the existing geographical conditions and the vegetation composition of the region. Also, during the development of the green belt within the project corridor, emphasis shall be laid on selection of plant species such as nitrogen fixing species, species of very fast growth etc.



6.3.6 Adaptability of General Public to Driving Conditions

385. In general, the proposed BRT project will play a key role in reducing traffic volumes and resulting traffic congestion and basically improve the overall traffic landscape and make it safer and more efficient.
386. However, the road traffic carriageways will become narrower due to the space required for the BRT and the pillars to be constructed for the elevated sections of the BRT will pose a potential risk for collision of vehicles in instances where unfamiliar drivers would over speed.
387. Provisions will need to be made in the detailed designs for road conditions at the major intersections and the overall visibility at the intersections will need to meet the local design standards and will need to be acceptable under all the foreseeable conditions.
388. Improvements to sighting angles and improved junction warning signage and road markings may require inclusion at the detailed design stages. Fluorescent signboards shall be used for the major junctions.

6.3.7 Accessibility for disabled people

389. The proposed BRT project has been designed while paying particular attention to ensure the special needs of disabled persons are incorporated into the project design. In this regard, the following key aspects of the project design features shall cater to the special needs of disabled people that shall be using the BRT:
- Wide station platform (5 to 6 meter wide) and open air to allow good air circulation
 - Fast and universal access to BRT station with all kind of access provided (stairs, elevator, escalator) and special gate to allow wheel chair to enter station
 - Tactile ground surface indicator/paving for visually impaired users. For these passengers, the tile will guide them to the front door of each stopping bay. This is to make the driver aware if there are any visually impaired passengers boarding the bus, so that drivers can allow additional dwelling time for safety reasons.
 - Lane separator with guard rail
390. The above mentioned project design features shall ensure that all disabled people with special needs will be able to use the proposed BRT project with complete ease, safety and peace of mind.

6.3.8 Socioeconomic

391. The operational phase of the BRT project will contribute to the local economy by providing job opportunities to the residents of Peshawar. These benefits will

increase the socio-economic status of the region and the overall impact will bring about a positive change.

Improvement of Infrastructure Facilities

392. The development of the proposed project will also create and improve the amenities/ services such as power, road infrastructure, communication etc. and thus improve the overall living conditions for the residents of Peshawar.

Economic Growth

393. The proposed project will increase the economic activities around the area, creating avenues for direct/indirect employment in the post project period.
394. A wider economic impact is expected in terms of generating opportunities for other businesses linked to the proposed project such as marketing, repair and maintenance tasks etc.

Improved Road Transportation

395. The existing roads will undergo lesser wear and tear since a considerable reduction in traffic volume will take place since commuters will prefer to travel on the BRT buses. As a result, the air quality, noise levels and general environmental conditions associated with vehicular traffic will improve and thus bring about positive change.

Reduced Health Risk and Accidental Hazards

396. The risk of accidental hazards will be minimized due to the reduced traffic volumes. The separate BRT lane will greatly reduce the accidents associated with movement across the roads. Health risks due to vehicular/exhaust emissions experienced in congested traffic conditions are likely to be avoided by the commuters traveling on the BRT.

6.3.9 Impact on Livelihood of existing transport workers

397. The potential impact of the project development on the livelihoods of the existing transport workers has been an aspect of continuous focus for ADB and the TMTD and PDA. As a part of the preliminary design prepared for this project, this aspect was highlighted and a number of different possible scenarios were discussed to ensure there is minimal impact on the livelihoods of the existing transport workers.
398. The TMTD and PDA are presently in negotiation with the existing transport service providers to find a mutually agreeable modality that shall ensure the existing personnel engaged in the transport industry are absorbed in different capacities into the BRT project and their employment is not put at risk.
399. Furthermore, a comprehensive livelihood assessment study is presently being prepared and shall cover all aspects of the livelihood restoration plan for all project

affected persons, including the existing transport workers to ensure their livelihood is not affected.

6.3.10 Disposal of Old buses

400. The Peshawar public transport sector consists mostly of individual owners of vehicles i.e. one vehicle per owner, but there are a number of individuals who own several vehicles, while some vehicles have as many as three or four owners. The current fleet, although required by law to be no more than 10 years old, comprises almost exclusively of models from the 1980s and 1990s.

401. The TMTD and PDA are presently in negotiation with the existing transport service providers to find a mutually agreeable modality that shall ensure the existing personnel engaged in the transport industry are absorbed in different capacities into the BRT project and their employment is not put at risk.

402. Once the BRT project commences operation, a shifting of the existing dynamic of the public transport sector in Peshawar shall take place as follows:

- A certain proportion of the existing public transport service providers shall be employed by the BRT project and thus will sell their existing buses to any willing customers.
- Those service providers opting to continue with their transport businesses and not join the BRT project shall continue to operate their existing buses.

The possibility exists that this latter group of transporters might choose to procure these buses that shall be up for sale in order to scale up their businesses. Otherwise, these buses will be sold to any willing customers, either in Peshawar or from other parts of the country.

403. Keeping in view the lack of financial support in terms of subsidies or other financial incentive schemes from the Government of Pakistan to the public transport sector, the general norm in the country is to continue using old buses as long as possible, irrespective of their age or the risk they might pose being on the roads.

404. It is expected that unless the TMTD and PDA launch a scheme for purchase of old buses from the public service providers once the BRT project comes into operation, majority of these old buses will continue to be used either in Peshawar or in other parts of the country. Thus, while the logistical landscape within the city of Peshawar and its outskirts is expected to considerably improve, however the decommissioning of the existing old buses will only be made possible through the introduction of a robust scheme aimed at decommissioning of old buses.

6.3.11 Climate Change Impacts

405. The BRT buses for this project will run on diesel but will be new and will be properly maintained and thus will be highly fuel efficient and will produce much lower CO₂ emissions in comparison to the status quo of old and inefficient vehicles being

used in the public transport sector. The existing vehicles produce a high level of CO₂ emissions and pollute the environment and adversely contribute towards climate change.

406. The GHG emissions have been computed by considering the existing vehicular landscape and corresponding CO₂ emissions based on the respective fuels being used and kilometers being driven by each category of vehicles, which forms the baseline for CO₂ emissions in Peshawar. The expected emissions from the new fleet of BRT buses have been computed based on emission factors for new vehicles and the difference between this fleet and the baseline landscape leads to the emission reductions in a particular year.

407. Since the ridership will increase over the next two decades, thus the CO₂ reductions are also expected to increase and will result in an overall positive impact. This is primarily due to a reduction in the overall traffic volume due to the availing of the efficient and economical BRT option for commuting on a daily basis.

408. The expected reductions in CO₂ emissions over the next two decades as a result of the proposed project are shown in Table 6.8 below.

409. The CO₂ emission reductions are expected to double by the year 2026 in comparison to 2017 and the CO₂ reductions will have increased by over 2.5 times in the year 2036 in comparison to 2017.

410. Thus, the propose project is expected to have a significantly positive impact in contributing towards slowing down the effects of climate change and global warming.

Table 6.8: Greenhouse Gas (GHG) Emission Reductions from BRT Project Operation

Parameters	Base Year		
	2017	2026	2036
Ridership ('000)/day	472,911	627,910	860,389
Ton CO₂/km	1,486.54	1,486.54	1,486.54
Ton CO₂/daily passenger	0.13	0.13	0.13
CO₂ Reductions (tons)	30,988	63,907	79,140

6.4 'Site Specific' Impact Analysis

411. The impact analysis presented earlier in this Chapter covers potential construction and operation related impacts resulting from the proposed BRT project. This analysis is essentially the 'Environmental Code of Practice (ECoP)' in order to

address standard construction and operation related impacts, irrespective of any specific infrastructure development along the BRT corridor.

412. Keeping in view that certain environmentally critical infrastructure will be developed along the project corridor, a 'site' specific impact analysis has also been prepared to cover the different categories of major physical infrastructure as far as possible at this initial stage of the project development. This approach has been adopted since the different infrastructure components of the proposed project will result in construction and operation related impacts of varying severity.

Bus Depot

413. Please refer to Section 3.5.1 of this report for details regarding the design and locations of the two depot locations identified for the proposed BRT project.

Construction Related Impacts

6.4.1 Soil Contamination/Hazardous Substances

414. Potential contamination of groundwater may occur due to spills of fuel and other hazardous substances. These impacts can be addressed through implementation of the following measures by the contractors:

(i) Before site works commence, a Spill Management Plan shall be prepared by the contractor and shall be approved by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of procedures, responsibilities, resources, documentation and reporting requirements, training provisions for relevant staff, etc. to avoid spills of hazardous substances and to effectively respond to such incidents, in case these occur.

(ii) Store fuel and hazardous substances in paved areas with embankment. If spills or leaks do occur, undertake immediate clean up.

(iii) Ensure availability of spill clean-up materials (e.g., absorbent pads, etc.) specifically designed for petroleum products and other hazardous substances where such materials are being stored and used.

(iv) Train relevant construction personnel in handling of fuels and spill control procedures.

(v) Ensure all storage containers are in good condition with proper labeling.

(vi) Regularly check containers for leakage and undertake necessary repair or replacement.

(vii) Store hazardous materials above flood level.

(viii) Equipment maintenance areas shall be provided with drainage leading to an oil water separator that will be regularly skimmed of oil and maintained to ensure efficiency. Discharge of oil contaminated water shall be prohibited.

(ix) Store waste oil, used lubricant and other hazardous wastes in tightly sealed containers to avoid contamination of soil and water resources. Transport and off-site disposal of such wastes shall be consistent with national and local regulations.

6.4.2 Surface Water

415. There are no anticipated adverse impacts on surface water during construction of the depot(s) since there are no water bodies in close proximity to the proposed depot locations. Furthermore, the depot(s) will be equipped with a wastewater treatment facility to ensure that effluent discharge complies with applicable national standards.

6.4.3 Wastewater

416. The construction of the Depot will require operation of a concrete batch plant/s (CBP). To ensure that untreated wastewater from the CBP will not be discharged to the environment, the contractor will implement similar measures identified for the tunnel component.

6.4.4 Drainage

417. Earthworks and other construction activities at the depot may cause alteration to drainage patterns in the area and could cause localized flooding. The contractor shall implement the following mitigation measures to address such impacts:

(i) Avoid placement of construction materials, waste storage areas or equipment in or near drainage channels surrounding the Depot.

(ii) Prohibit disposal of waste materials to drainage channels.

(iii) In case existing drainage ditch is filled-up as required for the construction works, provide alternative drainage for rainwater.

(iv) Regularly inspect and maintain all drainage channels to keep these free of obstructions.

6.4.5 Air Quality

418. Emissions from construction equipment and dust generation are short-term impacts that will be generated during construction of depot facilities. Emissions are not expected to create any significant concerns because of the size and openness of the proposed site(s). However, dust generation will result from transport of construction materials, grading the track area, construction of the internal road system and parking areas.

419. To reduce gaseous and dust emission during construction, the contractor shall implement the following measures:

(i) Before site works commence, a Dust Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas etc.) due to construction works; operation of concrete batch plants; sourcing, storage and transport of construction materials, and other project-related activities.

(ii) Wherever possible, use electrically powered equipment rather than gas or diesel-powered equipment.

(iii) Position any stationary emission sources (e.g., portable diesel generators, compressors, etc.) as far as is practical from sensitive receptors;

(iv) Use only vehicles and equipment that are registered and have necessary permits.

(v) Burning of wastes generated at the construction sites, work camps and other project-related activities shall be strictly prohibited.

(vi) Construction equipment and vehicles shall be well-maintained and shall meet NEQS emission standards.

(vii) Specify the use of clean fuels such as ultra-low sulphur diesel in dump trucks and other heavy-duty diesel vehicles and/or equipment, in conjunction with the use of particulate trap control devices, as well as catalytic converters, to avoid excessive diesel emissions.

(viii) Keep stockpiles moist and cover vehicles with tarpaulin sheets or other suitable materials to minimize dust emission and prevent spillage of materials (e.g., soil, cement, stone, sand, aggregates, etc.).

(ix) Provide temporary covers (e.g., tarpaulins, grass, etc.) on long term materials stockpiles.

(x) Concrete mixing areas at the Depot site shall be located at least 300 m from the nearest residential area.

(xi) Clean road surfaces of debris/spills from construction equipment and vehicles.

(xii) Install temporary fencing or barriers around particularly dusty activities in vicinity of sensitive receivers.

(xiii) Ensure availability of water trucks on site and if the works surface and access roads near sensitive receptors (i.e., residential areas, roadside tea and food stalls,

and other sensitive receptors) are dry and dusty, spray water on the exposed surfaces to reduce dust emission.

(xiv) All construction equipment and machinery shall be fitted with emission control equipment in full compliance with the national regulations.

(xv) Fuel-efficient and well-maintained haulage trucks will be used to minimize exhaust emissions. Smoke belching vehicles and equipment shall not be allowed and shall be removed from the project.

(xvi) Impose speed limits on construction vehicles to minimize road dust in areas where sensitive receptors are located.

(xvii) Locations for stockpiling material at the depot area will be at least 100 m from the nearest residential sensitive receivers.

(xviii) Undertake immediate repairs of any malfunctioning construction vehicles and equipment.

(xix) Discourage idling of engines.

(xx) Provide prior notification to the community on schedule of construction activities.

(xxi) Implement community complaints hotline.

6.4.6 Noise

420. Permanent noise barriers are not required at the Depot. Once construction has ceased, the activities within the depot should result in ambient noise levels at existing community noise levels. Mitigation measures to be implemented by contractors to reduce noise levels from construction works are listed below:

(i) Before site works commence, a Noise Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas, etc.) due to construction works, sourcing and transport of construction materials, and other project-related activities.

(ii) All construction equipment and vehicles shall be well maintained, regularly inspected for noise emissions, and shall be fitted with appropriate noise suppression equipment consistent with applicable national and local regulations.

(iii) Use only vehicles and equipment that are registered and have necessary permits.

(iv) No noisy construction-related activities near sensitive receptors (such as residential areas, etc.) will be carried out during the night. Such activities shall be restricted to daylight hours.

- (v) Truck drivers and equipment operators shall minimize the use of horns.
- (vi) Impose speed limits on construction vehicles to minimize noise emission along areas where sensitive receptors are located (houses, etc.).
- (vii) Provide temporary noise barriers (3-5 meter high barrier can reduce 5-10 dB(A), as necessary, if depot works will generate high noise levels that could disturb nearby households and other sensitive receptors.
- (viii) As much as possible, use quiet equipment and working method.
- (ix) Whenever possible, completely enclose noisy equipment which can reduce noise level by 15-25 dB(A), restrict use of noisy equipment (e.g. 15 min for every consecutive 30 min period) and undertake sequential operation of equipment with objective to reduce noise generated;
- (x) Provide prior notification to the community on schedule of construction activities.
- (xi) Implement community complaints hotline.

6.4.7 Solid Waste

421. If not properly handled and disposed of, solid wastes poses health and safety hazards and are likely to cause nuisance to surrounding communities and the workforce. To avoid such impacts, the contractor shall implement the following:
- (i) Provide garbage bins and facilities within the project site for temporary storage of construction waste and domestic solid waste.
 - (ii) Separate solid waste into hazardous, non-hazardous and reusable waste streams and store temporarily on site in secure facilities with weatherproof flooring and roofing, security fencing and access control and drainage/ wastewater collection systems.
 - (iii) Ensure that wastes are not haphazardly dumped within the project site and adjacent areas.
 - (iv) Undertake regular collection and disposal of wastes to sites approved by local authorities.

6.4.8 Damage to Community Facilities

422. Transport of materials, operation of construction equipment and various construction activities may damage community utilities. The contractor shall implement the following measures to address this impact:
- (i) The contractor shall immediately repair any damage caused by the Project to properties (e.g., houses, other types of structures, etc.), community facilities such as water supply, power supply, communication facilities etc.

(ii) Access roads damaged during transport of construction materials and other project-related activities shall be reinstated upon completion of construction works.

6.4.9 Traffic Concerns

423. Construction activities may cause traffic congestion along access roads due to transport of materials and operation of other project-related vehicles. To minimize traffic disturbance, the contractor shall undertake the following:

(i) Before site works commence, a Traffic Management Plan for the construction phase shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall be designed to ensure that traffic congestion due to construction activities and movement of construction vehicles, haulage trucks, and equipment is minimized. The plan shall be prepared in consultation with local traffic officials and people's committees at the district and commune levels. The plan shall identify traffic diversion and management, transport mode for spoils disposal (e.g., truck, truck and barge, etc.), traffic schedules, traffic arrangements showing all detours, necessary barricades, warning/advisory signs, road signs, lighting, and other provisions to ensure that adequate and safe access is provided to motorists in the affected areas.

(ii) Post traffic advisory signs (to minimize traffic build-up) in coordination with local authorities

(iii) As much as possible, schedule delivery of construction materials and equipment during non-peak hours.

(iv) Regularly monitor traffic conditions along access roads to ensure that project vehicles are not causing congestion.

6.4.10 Health and Safety of Workers and the Public

424. To ensure health and safety of workers, the following measures shall be implemented by the Contractor:

(i) Prior to commencement of site works, the following plans, which have already been prepared and are appended in this report, shall be implemented by the contractor:

- **Occupational and Community Health and Safety Plan (refer to ANNEX L).** This Plan addresses health and safety hazards associated with construction activities (e.g., excavations, working at heights, electrocution, etc.), establishment and operation of construction/worker's camps, use of heavy equipment, transport of materials and other hazards associated with various construction activities.
- **Emergency Response Plan (refer to ANNEX M)** to prevent, mitigate, respond to and recover from emergency events that could occur due to project activities such as accidents, spills of hazardous substances, fire, extreme weather events, and other crises.

- (ii) Appoint an environment, health and safety manager to look after implementation of required environmental mitigation measures, and to ensure that health and safety precautions are strictly implemented for the protection of workers and the general public in the vicinity of construction areas.
- (iii) Conduct orientation for construction workers regarding health and safety measures, emergency response in case of accidents, fire, etc., and prevention of HIV/AIDS and other related diseases.
- (iv) Provide first aid facilities that are readily accessible by workers.
- (v) Provide fire-fighting equipment at the work areas, as appropriate, and at construction camps.
- (vi) Provide adequate drainage in workers camps to prevent water logging/accumulation of stagnant water and formation of breeding sites for mosquitoes.
- (vii) Provide adequate housing for all workers at the construction camps.
- (viii) Provide reliable supply of potable water.
- (ix) Provide separate hygienic sanitation facilities/toilets and bathing areas with sufficient water supply for male and female workers.
- (x) Ensure that all wastewater emanating from worker camps, construction camps and other project-related activities and facilities are treated consistent with national regulations.
- (xi) Establish clean canteen/rest area.
- (xii) Ensure proper collection and disposal of solid wastes within the construction camps consistent with local regulations.
- (xiii) Provide fencing on all areas of excavation greater than 2 m deep.
- (xiv) Provide appropriate personnel safety equipment such as safety boots, helmets, gloves, protective clothes, breathing mask, goggles, and ear protection.
- (xv) Ensure reversing signals are installed on all construction vehicles.
- (xvi) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit construction workers.
- (xvii) Implement fall prevention and protection measures whenever a worker is exposed to the hazard of falling more than two meters, falling into operating machinery or through an opening in a work surface. Based on a case specific basis, fall prevention/protection measures may include installation of guardrails with mid-rails and toe boards at the edge of any fall hazard area, proper use of ladders and

scaffolds by trained employees, use of fall prevention devices, including safety belt and lanyard travel limiting devices to prevent access to fall hazard, fall protection devices such as full body harnesses, etc.

589. The following mitigation measures to ensure public safety shall be implemented by the contractor:

- (i) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit people, vehicles and properties in adjoining areas.
- (ii) Fencing of construction sites and regular patrols to restrict public access.
- (iii) Prior to excavation work, provide fencing on all sides of areas to be excavated.
- (iv) Provide warning signs at the periphery of the construction site.
- (v) Strictly impose speed limits along residential areas and where other sensitive receptors are located.
- (vi) Educate drivers on safe driving practices to minimize accidents and to prevent spill of hazardous substances and other construction materials during transport.

6.4.11 Social Conflicts

591. The presence of construction camps may cause conflict with the surrounding communities, these will be addressed by:

- (i) Consider the location of construction camps away from communities in order to avoid social conflict in using resources and basic amenities such as water supply.
- (ii) Maximize number of local people employed in construction works.
- (iii) Maximize goods and services sourced from local commercial enterprises.

6.4.12 Long Term Residual Effects

425. There are no long-term residual negative impacts predicted for the Depot site. There are only positive socio-economic benefits to the local community from the project.

Operation Related Impacts

6.4.13 Soil Contamination/Hazardous Substances

426. A wastewater treatment should be constructed at the depot to ensure that relevant NEQS standards and requirements are met prior to recycling and discharge to the city drainage network. The treatment plant should be designed to remove pollution, debris and reuse of the water. Improper handling of hazardous substances

at substations and other depot facilities are likely to cause adverse impacts. Mitigation measures to be implemented to address potential impacts on water resources are as follows:

- (i) Wastewater shall be treated at the depot's treatment plant to ensure that relevant NEQS standards and requirements are met.
- (ii) In the vehicle washing, maintenance area and wheel lathe pits, drains shall be linked to the water treatment plant.
- (iii) Drainage emanating from the depot workshops will be equipped with oil interceptors. Oil-drip pans shall be used where appropriate to avoid contamination of the environment.
- (iv) Office buildings shall be provided with toilets and septic tanks or drain to sewers to handle domestic sewage.
- (v) The sewer system will be designed to prevent leakage or overflow of waste water that could contaminate the surrounding areas.
- (vi) All hazardous and potentially contaminating materials (chemicals, fuels, oils, etc.) and equipment that contain hazardous substances shall be stored in facilities with weatherproof flooring and roofing, security fencing and access control and drainage/wastewater collection systems.
- (vii) PCB-containing equipment shall not be used.
- (viii) Leaks shall be repaired immediately and waste oil shall be stored and disposed of consistent with applicable laws and regulations.
- (ix) Diesel generators shall be placed on concrete floors with embankment.
- (x) There shall be provisions for concrete-lined transformer bays as well as drainage and oil-water separator to handle spills, leaks and oily water run-off that could emanate from the transformers.
- (xi) Ensure availability of spill clean-up materials (e.g., absorbent pads, etc.) specifically designed for petroleum products and other hazardous substances where such materials are being stored and used.
- (xii) A groundwater quality monitoring program shall be implemented to ensure that groundwater for domestic purposes are adequately treated to meet applicable NEQS standards (based on the monitoring results).

6.4.14 Air Quality

427. To minimize odor generation, wastewater treatment facilities shall be properly maintained and solid wastes regularly removed from the depot area to disposal sites approved by local authorities. Burning of waste materials shall be prohibited and

idling of vehicles minimized. Back-up diesel generators to be used during power interruptions and shall be maintained regularly to ensure emissions comply with NEQS standards.

6.4.15 Noise

428. Noise mitigation measures (e.g., enclosure) shall be provided for the back-up diesel generator(s) to ensure that high noise levels will not impact on surrounding sensitive receptors. While the noise levels are not expected to cause nuisance to the local community, noise monitoring will continue during the operation to determine and provide noise abatement measures, if necessary. Noise sampling shall also be conducted in response to complaints.

6.4.16 Solid Waste

429. The maintenance works as well as workers/employees at the Depot offices will generate solid wastes. Mitigation measures are as follows:
- (i) Offices, workshops and other areas within the depot shall be provided with waste collection bins or receptacles.
 - (ii) Solid wastes shall be segregated into hazardous, non-hazardous and reusable waste streams and stored temporarily on site in secure facilities with weatherproof flooring and roofing, security fencing and access control and drainage/wastewater collection systems.
 - (iii) Garbage shall be regularly collected and shall be disposed consistent with local regulations.
 - (iv) Wastes shall only be disposed of in approved sites by local authorities.

6.4.17 Health and Safety of Workers and the Public

430. To protect the health and safety of workers and general public during depot operations, the following measures shall be implemented:
- (i) Prior to operation of the depot, PDA shall ensure that the following plans have been developed and adequately resourced. PDA shall ensure that plan provisions are strictly implemented throughout operation phase:
 - Occupational Health and Safety Plan for all components of depot operation and train staff in the implementation of such plan.
 - Emergency Response Plan (e.g., in case of fire, extreme weather events, floods, power outage, equipment breakdown, accidents, spills of hazardous substances, etc.) covering all components of depot operation and train staff in the implementation of such plan.

- (ii) The depot site will be fenced and access will be restricted to authorized personnel to avoid safety risks to the public.

Elevated Sections

431. The elevated sections of the BRT will be a total of 4.1 km long and will be located between BS-10 to BS-14, BS-25 to BS-27 and between BS-28 and BS-29. The BRT elevated section will commence at Cinema road where it shall become elevated to bypass the junction with Hospital road. It shall stay elevated on Khyber Bazaar road and Railway road, and pass the Soekarno and Suba Chowk, the two most congested intersections in the Khyber Bazaar area. After the railway road, the elevated BRT section will turn right at Anwar Saeed medical center to cross the railway station, where a BRT only bridge will be constructed. After crossing the railway station, the BRT shall become at-grade again and join Saddar road.

The corridor shall again become elevated at Jamrud road while passing above a dried up river bank before the Bab-e-Peshawar Marco Polo bridge until it joins the Habib Jalib road towards Tatara Park and joins the Ring road.

Construction Related Impacts

6.4.18 Disruption to Community Utilities

432. Utility relocation on this section poses only a limited or short-term concern to residents in the area. However, to minimize impacts, the contractor shall implement the following measures:
- i) Water supply pipelines, power supply, communication lines and other utilities shall be re-provisioned before construction works commence.
 - ii) Provisions shall be made to preserve the operation of current facilities in sufficient quantity and in agreement with the local community.
 - iii) Re-provisioning shall be undertaken in coordination with the utility company.
 - iv) Affected households and establishments shall be notified well in advance of such disruption.

6.4.19 Spoils Generation

433. Construction of the pillars will require removing at least 5 m x 5 m area of the median and asphalt in the roadway. At each pillar site, soil removal to -2 m depth within the 5 m x 5 m area will be required to carry out pile driving and construction of the pillar footing/cap. Although the quantity of soil removal for the pillar section is small, the contractor should ensure the following measures are implemented by the contractor to minimize impacts due to spoils generation:
- (i) Meet the same measures as prescribed for the underground/ tunnel spoils under the Spoils Disposal Plan.

- (ii) All asphalt and sidewalk materials removed should be separated and recycled.
- (iii) Spoil disposal will only be to pre-approved areas.
- (iv) The capacity of disposal sites shall be adequate to accept the quantity of spoils without alienating areas outside the site boundaries.
- (v) Disposal of contaminated spoils shall only be to disposal sites equipped and licensed to handle such wastes.
- (vi) Trucks transporting spoils shall be tightly covered with tarpaulin or other suitable materials to minimize dust emission and spills.
- (vii) Load-out areas shall be cleaned and watered to ensure no accumulated dust originates that could be dispersed to surrounding areas.
- (viii) Wheel washing shall be undertaken to remove mud so as to ensure that access roads are kept clean.
- (ix) Road surfaces shall be regularly cleaned of spilled spoils;
- (x) Spoil disposal shall not cause sedimentation and obstruction of flow of watercourses, damage to agricultural land and densely vegetated areas.

6.4.20 Wastewater

434. Wastewater will be generated from operation of concrete batch plant/s (CBP) for the pillar construction. To ensure that untreated wastewater from the CBP will not be discharged to the environment, the contractor will implement similar measures identified for the tunnel and station components.

6.4.21 Drainage/Flooding

435. Earthworks along the elevated sections may cause clogging of drainage and result in localized flooding. The contractor shall implement the following mitigation measures to address these impacts:
- (i) Placement of construction materials, excavated spoils and equipment shall not block flow of rainwater into canals/drainage structures.
 - (ii) Prohibit disposal of waste materials to drainage channels.
 - (iii) Regularly inspect and maintain all drainage channels in the vicinity of construction sites to keep these free from obstructions.

6.4.22 Air Quality

436. During the construction phase, the potential exists for short-term negative air quality impacts along the corridor. The two major sources of emissions from construction are: dust emissions from non-combustion sources and exhaust

emissions from construction vehicles and stationary combustion sources. Although the potential for localized air quality impacts of these activities may be significant, it is important to note that they will be temporary and localized.

437. On the pillars section, there should be minimum dust generated. Only construction of the pile-cap for the pillars will involve the removal of approximately 5 m x 5 m of soil = 50 m³. This can be carried in one to ten truck loads and the dust should be contained.
438. It will be the cranes lifting the pre-cast sections of the pier and the viaduct that will cause emissions. Obviously these emissions will add cumulatively to the existing high levels of TSP, SO₂ and NO_x. Best management practices shall be adopted during construction to minimize dust and combustion exhaust emissions are the same as those that apply for the underground project corridor construction.

6.4.23 Noise

439. Pile driving for the pillar piles will be carried out using a churn-drill. This is a much quieter machine than a diesel hammer driver and should significantly reduce noise levels to receivers in the community. Also, one column can be erected in one day, thereby reducing any prolonged noise at sensitive receivers along the alignment.
440. Construction activity and operation of cranes during construction of elevated stations will create an increase in noise levels to receivers in the area, combined with existing traffic noise; the levels may be extreme, well over 80 dBA for short periods of construction.
441. Every opportunity should be taken to make use of natural features on the edge of the right-of-way or at the property line of the affected property to reduce noise impacts. Use of dedicated noise barriers such as barrier fences, or retaining walls should be considered during the detailed design stage, where warranted.
442. The following measures to attenuate noise shall be implemented by the contractor:
- (i) Before site works commence, a Noise Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas, etc.) due to construction works, sourcing and transport of construction materials, and other project-related activities.
 - (ii) Unobtrusive noise barriers near sensitive areas such as residential areas, etc. can also be placed on the edge of the right-of-way should construction monitoring indicate an impact to sensitive receivers. Temporary noise barriers (3-5 meter high) can reduce noise level by 5-10 dB(A).

- (iii) Diesel hammer piling shall be limited in favor of drill piling.
- (iv) Truck drivers and equipment operators shall minimize the use of horns.
- (v) Position any stationary equipment that produce high noise levels (e.g., portable diesel generators, compressors, etc.) as far as is practical from sensitive receptors;
- (vi) All construction equipment and vehicles shall be well maintained, regularly inspected for noise emissions, and shall be fitted with appropriate noise suppression equipment consistent with applicable national and local regulations.
- (vii) Use only vehicles and equipment that are registered and have necessary permits.
- (viii) No noisy construction-related activities will be carried out during the night near sensitive receptors (e.g., residential areas). Such activities shall be restricted to daylight hours.
- (ix) Impose speed limits on construction vehicles to minimize noise emission along areas where sensitive receptors are located (residential areas, etc.).
- (x) As much as possible, use quiet equipment and working method.
- (xi) Whenever possible, completely enclose noisy equipment which can reduce noise level by 15-25 dB(A), restrict use of noisy equipment (e.g. 15 min for every consecutive 30 min period) and undertake sequential operation of equipment with objective to reduce noise generated;
- (xii) Provide prior notification to the community on schedule of construction activities.
- (xiii) Implement community complaints hotline.

6.4.24 Vibration

- 443. Vibration generated during construction and operation has the potential to cause amenity and physical (structural) impacts at receivers. Installation of the pillar columns will generate intermittent vibration, which is defined as interrupted periods of impulsive vibration (e.g. pile driving, excavation).
- 444. Equipment working on the viaduct will be cranes and pile drivers. At each column site, four 1000 mm piles of +50m are required to anchor the columns. Piles can either be driven or churned drilled. Driving H piles with a diesel hammer is exceedingly noisy and creates significant levels of vibration to the surrounding area. However, churned drilled piles are significantly quieter and causes lower vibrations. Tracked cranes will be used to lift pre-cast sections of the columns and will cause some vibration.
- 445. The selection of a churned drill pile method will significantly reduce noise and vibration to the community along the route. Furthermore, because construction will be

staggered, and at different stages of erection, noise and vibration will be intermittent and therefore less of an annoyance to residents along the route. Equipment will also not be operating at night and monitoring at sensitive receiver sites will be carried out.

6.4.25 Use of Hazardous Substances

446. Potential contamination of surrounding areas and groundwater may occur due to spills of fuel and other hazardous substances. These impacts will be addressed through implementation of the following measures by the contractors:

(i) Before site works commence, a Spill Management Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of procedures, responsibilities, resources, documentation and reporting requirements, training provisions for relevant staff, etc. to avoid spills of hazardous substances and to effectively respond to such incidents, in case these occur.

(ii) Store fuel and hazardous substances in paved areas with embankment. If spills or leaks do occur, undertake immediate clean up.

(iii) Ensure availability of spill clean-up materials (e.g., absorbent pads, etc.) specifically designed for petroleum products and other hazardous substances where such materials are being stored and used.

(iv) Train relevant construction personnel in handling of fuels and spill control procedures.

(v) Ensure all storage containers are in good condition with proper labeling.

(vi) Regularly check containers for leakage and undertake necessary repair or replacement.

(vii) Store hazardous materials above flood level.

(viii) Equipment maintenance areas shall be provided with drainage leading to an oil-water separator that will be regularly skimmed of oil and maintained to ensure efficiency. Discharge of oil contaminated water shall be prohibited.

(ix) Store waste oil, used lubricant and other hazardous wastes in tightly sealed containers to avoid contamination of soil and water resources. Transport and off-site disposal of such wastes shall be consistent with national and local regulations.

6.4.26 Solid Waste

447. Please refer to Section 6.4.7.

6.4.27 Damage to Community Facilities

448. Please refer to Section 6.4.8.

6.4.28 Health and Safety of Workers and the Public

449. Please refer to Section 6.4.10.

6.4.29 Traffic Concerns

450. The pillar construction will occur in the median of the existing roads along the BRT corridor. Excavation and cranes will require a working easement that will reduce the current lanes of traffic. This will cause traffic jams and time delays to the road users.

451. The duration of this impact, however, will be short. It will likely take about 5-7 days to excavate, pile and pour the pile cap. This operation will be the most intensive activity and occurring at different sections along the alignment. The erection of the pillars is expected to take one day per section. In order to avoid traffic congestion and problems, the erection will occur at night. The movement of equipment along the alignment will reduce the length and degree of disturbance and annoyance to local residents.

452. The following measures shall be implemented by the contractor to address impacts to traffic flows and access to properties:

(i) Before site works commence, a Traffic Management Plan for the construction phase shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall be designed to ensure that traffic congestion due to construction activities and movement of construction vehicles, haulage trucks, and equipment is minimized.

The plan shall be prepared in consultation with local traffic officials and people's committees at the district and commune levels. The plan shall identify traffic diversion and management, transport mode for spoils disposal (e.g., trucks etc.), define routes for construction traffic from materials storage/parking areas to construction site and from construction site to waste disposal locations, traffic schedules, traffic arrangements showing all detours/lane diversions, modifications to signaling at intersections, necessary barricades, warning/advisory signs, road signs, lighting, and other provisions to ensure that adequate and safe access is provided to motorists in the affected areas.

(ii) Provide signs advising road users that construction is in progress and that the road narrows to one lane using cones.

(iii) Employ flag persons to control traffic at the work sites for safety reasons when construction equipment is entering or leaving the work area.

(iv) Lanes shall be created through the work site using rope or flagging to minimize risks and injuries from falling objects.

(v) As much as possible, lifting and placing of the pre-cast pillar sections will be done at night to minimize traffic congestion.

- (vi) Post traffic advisory signs (to minimize traffic build-up) in coordination with local authorities.
- (vii) Provide road signs indicating the lane is closed 500 m before the worksite.
- (viii) Use traffic cones to direct traffic to move to the open lane.
- (ix) Provide sufficient lighting at night within and in the vicinity of construction sites.
- (x) Regularly monitor traffic conditions along access roads to ensure that project vehicles are not causing congestion.
- (xi) Define and observe schedules for different types of construction traffic trips (e.g., transport of pre-cast sections, haulage of spoils, delivery of construction materials, etc.).
- (xii) As much as possible, schedule delivery of construction materials and equipment as well as transport of spoils during non-peak hours.
- (xiii) Avoid movements of noisy vehicles during night time in vicinity of sensitive receivers.
- (xiv) Implement suitable safety measures to minimize risk of adverse interactions between construction works and traffic flows through provision of temporary signals or flag controls, adequate lighting, fencing, signage and road diversions.
- (xv) Ensure relocation of any affected public transport infrastructure (but stops, shelters etc.) prior to commencement of works
- (xvi) Provide advance notification to the community regarding changes to public transport facilities or routes.
- (xvii) Schedule construction works to minimize extent of activity along linear construction site at any one time.
- (xviii) Comply with traffic regulations and avoid, where possible, roads with the highest traffic volumes, high density of sensitive receivers or capacity constraints are not used as access to and from the construction areas and spoils disposal sites.
- (xix) Install temporary accesses to properties affected by disruption to their permanent accesses.
- (xx) Reinstate good quality permanent accesses following completion of construction.

6.4.30 Social Conflicts

453. Please refer to Section 6.4.11.

Operation Related Impacts

6.4.31 Wastewater

454. There are no expected impacts due to project design. Drainage from the pillars will be carried through pipes and drain internally to the city storm water system. The elevated station shall be provided with toilets and septic tanks to handle sewage generated by workers and passengers.

6.4.32 Health and Safety of Workers and the Public

455. Please refer to Section 6.4.17.

6.4.33 Solid Waste

456. The operation of elevated stations will generate solid wastes from workers/employees and passengers. Mitigation measures are as follows:

- (i) Waste collection bins or receptacles shall be provided in various areas at the elevated stations, such as offices and areas accessed by passengers.
- (ii) Garbage shall be regularly collected and shall be disposed consistent with local regulations.

Tunnels & Underground Sections

457. Based on the preliminary design for the proposed project, there will be two tunnels/underground sections along the project corridor with a total length of 3.5 km, namely between BS-8 and BS-9 and between BS-17 and BS-18. The first tunnel connects both approaches of the GT road, Malik Saad Shaheed road and Cinema road. The second tunnel will be 'BRT only' and will cross Amman Chowk.

Construction Related Impacts

6.4.34 Disruption to Community Utilities

458. Please refer to Section 6.4.19.

6.4.35 Spoils Generation

459. The following measures shall be implemented by the contractor to minimize impacts due to spoils generation:
- (i) Before site works commence, a Spoils Disposal Plan (SDP) shall be prepared by the contractor. The plan shall be reviewed by CSC and forwarded to ADB for approval. The plan shall present off-site re-use (if suitable) of excavation spoils and corresponding volume, identification of suitable temporary and final disposal location/facility and corresponding capacity, designation of suitable transport routes and schedule for spoil truck movements to minimize traffic disruption/congestion, and environmental mitigation measures to address impacts due to transport and disposal of spoils.

The SDP shall include maps and layout plan of the disposal site(s) identifying where protection measures are required such as slope stabilization measures, silt fencing, ditching, dust control, cross drains, measures to avoid flooding in surrounding areas, etc. The SDP shall specify spoils dewatering procedures (and facilities), as necessary, and shall describe in detail the mitigation measures to be implemented to ensure that resulting wastewater from spoils dewatering is adequately treated and disposed of to meet applicable NEQS standards and requirements.

Provisions for random testing of spoils shall be specified in the SDP to determine contamination levels (e.g., hydrocarbons, heavy metals) based on NEQS standards and corresponding treatment measures to meet standards and avoid pollution.

(ii) All asphalt and sidewalk materials removed should be separated and recycled.

(iii) Spoil disposal will only be to PDA approved areas.

(iv) The capacity of disposal sites shall be adequate to accept the quantity of spoils without alienating areas outside the site boundaries.

(v) Undertake random sampling of spoils from underground station excavations and tunneling to determine presence of contaminants. If levels of contaminants exceed standards, excavation spoils shall be considered as hazardous wastes consistent with applicable standards/guidelines and shall be treated and disposed of as such.

(vi) Disposal of contaminated/hazardous spoils shall only be to disposal sites equipped and licensed to handle such wastes.

(vii) Determine water content of spoils to ascertain if spoils dewatering is necessary.

(viii) Undertake necessary spoils dewatering and provide adequate treatment facilities to ensure that resulting wastewater meets NEQS standards. Adequate treatment should also be undertaken for groundwater drained from the excavated areas to ensure compliance with NEQS standards.

(ix) Stockpiling of spoils shall not be undertaken due to the limited footprint of the construction site. Spoils shall be trucked away immediately to approved temporary or final disposal sites.

(x) Should any small stockpiles be developed, these shall be covered by plastic sheeting.

(xi) Trucks transporting spoils shall be tightly covered with tarpaulin or other suitable materials to minimize dust emission and spills. Wet spoils shall be transported using covered water-tight trucks to avoid spillage and drips onto access roads.

(xii) Load-out areas shall be cleaned and watered to ensure no accumulated dust originates that could be dispersed to surrounding areas.

(xiii) Wheel washing shall be undertaken to remove mud so as to ensure that access roads are kept clean.

(xiv) Road surfaces shall be regularly cleaned of spilled spoils.

(xv) Spoil disposal shall not cause sedimentation and obstruction of flow to agricultural land, properties, and densely vegetated areas.

6.4.36 Land Subsidence/Geotechnical Hazards

460. Land subsidence along the underground section will have a direct impact on the construction site. Settlement caused by tunneling, deep excavation, and dewatering will occur during the construction stage, even with mitigation measures.

461. To avoid excessive settlement that could damage the nearby buildings, the following measures will be implemented by the contractor:

(i) Undertake detailed geological investigation to determine geotechnical hazards along the Project's impact zone. Implement suitable precautionary and protection measures to avoid or minimize hazards.

(ii) Select the best construction methods for retaining wall to ensure the stability of the deep excavation.

(i) Implement a survey program to monitor the background subsidence rate along the project alignment. The monitoring data shall be used to assess potential damage that the observed subsidence may cause to buildings under or alongside the tunnels and to estimate the cumulative amount of regional subsidence during the construction stage.

(ii) As part of the survey program, take photographs of each individual structure within the possible affected zone before the construction starts, to be used for assessing potential damage due to subsidence.

(iii) Conduct careful monitoring of the groundwater level, amount of settlement, tilt of buildings, and any building damages.

(iv) Depending on the results of subsidence monitoring program, develop and implement suitable mitigation measures to avoid or minimize damage to properties.

(v) Establish an emergency action plan for geotechnical hazards including a set of criteria for issuing warnings for such hazards.

(vi) If necessary; carefully design, implement and monitor an appropriate dewatering program.

(vii) Perform probe drilling ahead of the TBM cutting surface at places where abrupt change of geological properties occur since such areas tend to have a higher risk of

failure. Based on the results of probe drilling, implement appropriate precautionary measures.

(viii) Undertake ground treatment underneath the deep excavation site if required.

(ix) Although there are no internationally adopted standards for settlement, the parameters below are based on normal practice. The tunnel boring machine (TBM) contractor shall be required to operate within the following settlement parameters:

- Standard building: maximum settlement: 25 mm, maximum differential settlement: 11500 (this indicator is more important for damage), maximum upheaval: 10 mm
- Particularly sensitive building to be identified: maximum settlement: 20 mm; maximum differential settlement: 11600, maximum upheaval: 10 mm
- Street and pavement: maximum settlement: 30 mm, maximum differential settlement: 11400, maximum upheaval: 10 mm. Select the best tunneling methods to minimize possible settlement during construction.

6.4.37 Flooding

462. The contractor will be required to prepare a spoils disposal plan, which will include, among others, installation of adequate drainage facilities and flood prevention measures.

463. To prevent flush of soil into the channel during flood events, a retaining wall along the boundary is recommended.

464. During construction, the following measures shall be implemented by the contractor to avoid clogging of drainage and creating localized flooding:

(i) Placement of construction materials, excavated spoils, equipment shall not block flow of rainwater into canals/drainage structures.

(ii) Prohibit disposal of waste materials to drainage channels.

(iii) Regularly inspect and maintain all drainage channels in the vicinity of construction sites to keep these free from obstructions.

(iv) Construct retaining walls along the spoils disposal boundary bordering the channels to prevent spoils from being flushed into the water courses during heavy rains and flood events.

(v) At the disposal site, avoid formation of steep slopes to avoid soil materials from being eroded/washed out during rains and floods.

6.4.38 Surface water

465. No surface water bodies occur within the tunnel section. No impacts are anticipated.

6.4.39 Wastewater

466. Considerable volume of wastewater will be generated from operation of concrete batch plant/s (CBP) for the tunnel and station construction. To ensure that untreated wastewater from the CBP will not be discharged to the environment, the contractor will:

(i) Prior to operation of CBP, construct settling/retention ponds with sufficient specifications/capacity for treatment of wastewater (e.g., from washing of equipment such as mixer drums, trucks and chutes; contact storm water, etc.).

(ii) Properly operate and maintain settling/retention ponds to ensure effluent quality meets applicable NEQS limits.

6.4.40 Air Quality

467. Dust and vehicle emissions will be created by construction of the cut and cover and tunneling works. Dust emissions generally consist of large particles that settle out relatively close to the source, whereas exhaust emissions generally consist of fine particles that can drift further away from the source. The potential for dust emissions will occur wherever any of these activities are taking place; the most likely areas where such impacts could occur include openings to tunnel boring sections, at underground station sites using cut-and-cover excavation, fugitive dust from dump trucks, and locations where excavation spoils are transferred from dump trucks to spoil receiving site(s).

468. Combustion emission sources typically associated with this type of project include: (i) diesel exhaust emissions from mobile sources, including earth-moving equipment, and dump trucks; (ii) exhaust from stationary combustion sources, including generators, heaters, and possibly off-site construction and fabrication (including concrete-casting facilities); and (iii) exhaust from tunnel boring machines, either directly, in the case of diesel-powered tunnel boring machines, or indirectly, in the case of electric tunnel boring machines powered by diesel generators at the surface.

469. It is unclear whether a diesel powered TBM or an electric powered TBM will be used. Without having details on the level of activity for each of these types of combustion emission sources, it is not possible to provide a quantitative estimate of the total emissions that will be generated. Although the potential air quality impacts from these activities can be significant, it is important to note that they will be temporary and localized.

470. There are no major sources of contaminant in the spoil, neither the natural geological materials nor the common additives (bentonite and cement) for construction are expected to react to the air to produce toxic/harmful fumes. It is possible that some organic rich layers may be encountered during excavation works. Although these materials may generate some unpleasant odor, once exposed to the

air these will be oxidized and the odor is not expected to last long such that it will not cause any long term impact to the atmosphere and the residents.

471. Mitigation measures to be implemented by the contractor to minimize impacts on air quality are listed below:

(i) Before site works commence, a Dust Control Plan shall be prepared by the contractor and shall reviewed by the construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas, schools, hospitals, etc.) due to construction works; operation of concrete batch plants; sourcing, storage and transport of construction materials, spoils disposal and other project-related activities.

(ii) Wherever possible, use grid rather than generator set electrical power for construction equipment such as the tunnel boring machine and equipment to be used during cut-and-cover tunnel excavations.

(iii) Position any stationary emission sources (e.g., portable diesel generators, compressors, etc.) as far as is practical from sensitive receptors;

(iv) Use only vehicles and equipment that are registered and have necessary permits.

(v) Burning of wastes generated at the construction sites, work camps and other project-related activities shall be strictly prohibited.

(vi) Construction equipment and vehicles shall be well-maintained and shall meet national NEQS emission standards.

(vii) Trucks to be used for transporting excavation spoils shall be tightly covered

(viii) Specify the use of clean fuels such as ultra-low sulphur diesel in dump trucks and other heavy-duty diesel vehicles and/or equipment, in conjunction with the use of particulate trap control devices, as well as catalytic converters, to avoid excessive diesel emissions.

(ix) Keep stockpiles moist and tightly cover vehicles with tarpaulin sheets or other suitable materials to minimize dust emission and prevent spillage of materials (e.g., soil, cement, stone, sand, aggregates, excavation spoils, etc.).

(x) Provide temporary covers (e.g., tarpaulins, grass, etc.) on long term materials stockpiles.

(xi) Store excavated materials outside road reserve, but where there is no area; spoils shall be loaded and transported immediately.

(xii) Provide truck-washing facilities to prevent truck-out of mud and dust onto city streets.

(xiii) As much as possible, the casting yard for the Project will make use of already established and licensed site(s) for concrete forming activities where all the pre-cast sections will be fabricated.

(xiv) Ensure that necessary environmental approvals are obtained for the establishment and operation of concrete batching plants and casting yards,

(xv) Daily cleaning of road surfaces of debris/spills from construction equipment, haulage trucks and vehicles,

(xvi) Install temporary fencing or barriers around particularly dusty activities in vicinity of sensitive receivers

(xvii) Ensure availability of water trucks or other dust suppressants and appropriate equipment for applying the suppressant (e.g., a tank truck with spray bars) on site and if the works surface and access roads near sensitive receptors (i.e., residential areas, roadside tea and food stalls, schools, hospitals and other sensitive receptors) are dry and dusty, spray water on the exposed surfaces to reduce dust emissions.

(xviii) All construction equipment and machinery shall be fitted with emission control equipment in full compliance with the national (NEQS) and local regulations.

(xix) Fuel-efficient and well-maintained haulage trucks will be used to minimize exhaust emissions. Smoke belching vehicles and equipment shall not be allowed and shall be removed from the project.

(xx) Impose speed limits on construction vehicles to minimize road dust in areas where sensitive receptors are located.

(xxi) Undertake immediate repairs of any malfunctioning construction vehicles and equipment.

(xxii) Daily visual inspections to identify and address potential areas of dust and odor emissions.

(xxiii) Discourage idling of engines.

(xxiv) Provide prior notification to the community on schedule of construction activities.

(xxv) Implement community complaints hotline.

6.4.41 Noise

472. Noise impacts to the community will occur due to operation of heavy equipment. Sensitive receptors such as commercial and residential areas are found at different locations along the alignment, some of these are right along the edge of the road where cut and cover works for station construction will be undertaken and will experience construction noise levels exceeding 80 dB.

473. Specific measures to be implemented by contractors to attenuate noise are as follows:

(i) Before site works commence, a Noise Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas, schools, hospitals, etc.) due to construction works, sourcing and transport of construction materials, and other project-related activities.

(ii) Erection of temporary walls around all underground station excavation sites and tunnel portals. Temporary noise barriers (3-5 meter high) can reduce noise level by 5-10 dB(A).

(iii) Truck drivers and equipment operators shall minimize the use of horns.

(iv) Position any stationary equipment that produce high noise levels (e.g., portable diesel generators, compressors, etc.) as far as is practical from sensitive receptors;

(v) All construction equipment and vehicles shall be well maintained, regularly inspected for noise emissions, and shall be fitted with appropriate noise suppression equipment consistent with applicable national and local regulations.

(vi) Use only vehicles and equipment that are registered and have necessary permits.

(vii) No noisy construction-related activities will be carried out during the night. Such activities shall be restricted to daylight hours.

(viii) Impose speed limits on construction vehicles to minimize noise emission along areas where sensitive receptors are located (houses, schools, hospitals, etc.).

(ix) As much as possible, use quiet equipment and working method.

(x) Whenever possible, completely enclose noisy equipment which can reduce noise level by 15-25 dB(A), restrict use of noisy equipment (e.g. 15 min for every consecutive 30 min period) and undertake sequential operation of equipment with objective to reduce noise generated;

(xi) Construction work shall respect the hospital areas as a "quiet zone" in the evening, nighttime and early morning hours. Work activities should be kept to daytime hours only.

(xii) No noisy construction activities in the vicinity of schools during examination periods. The contractor will closely coordinate with the school/university administration on construction schedules to ensure that noise from site works will not be disruptive during such periods.

(xiii) Avoid noisy construction activities in vicinity of sensitive receivers (e.g., residential areas) during night time or other sensitive periods (e.g. during school hours). Suitable noise reduction measures (e.g., noise barriers or equipment enclosures) shall be installed by the contractor if construction activities will be disruptive during normal school hours.

(xiv) Provide prior notification to the community on schedule of construction activities.

(xv) Implement community complaints hotline.

6.4.42 Vibration

474. Excavation equipment and a steady movement of heavily loaded dump trucks will likely be the cause of any vibration effects that may exceed ambient standards.

475. Vibration effects may be high during excavation at grade or down to a depth of 5 m particularly for loaded dump trucks moving slowly up a ramp and then accelerating away from the excavation site. The TBMs will be operating at a depth of -15m+ and experience elsewhere in the world on tunnel projects has indicated that no significant vibration impacts are expected for businesses or residences on the surface. Once the cut and cover tunnel area and the stations are excavated below 5 meters, noise and vibration impacts should diminish.

476. Using best management practices cited to alleviate air and noise pollution will also reduce vibration effects. These are:

(i) Erection of temporary walls around the underground station excavation sites and tunnel portal. Temporary noise barriers (3-5 meter high) can reduce noise level by 5-10 dB(A), using daytime work schedules only,

(ii) All construction equipment and vehicles shall be well maintained,

(iii) Diesel hammer piling shall be limited in favor of churn drill piling.

6.4.43 Use of Hazardous substances

477. Please refer to Section 6.4.26.

6.4.44 Solid Waste

478. If not properly handled and disposed of, solid wastes pose health and safety hazards and are likely to cause nuisance to the surrounding communities and the workforce. To avoid such impacts, the contractor shall implement the following at the construction sites as well as the spoils disposal site:

(i) Provide garbage bins and facilities within the project site for temporary storage of construction waste and domestic solid waste.

(ii) Separate solid waste into hazardous, non-hazardous and reusable waste streams and store temporarily on site in secure facilities with weatherproof flooring and roofing, security fencing and access control and drainage/ wastewater collection systems.

(iii) Ensure that wastes are not haphazardly dumped within the project site and adjacent areas.

(iv) Undertake regular collection and disposal of wastes to sites approved by local authorities.

6.4.45 Damage to Community Utilities

479. Please refer to Section 6.4.19.

6.4.46 Health and Safety of Workers and the Public

480. To ensure health and safety of workers, the following measures shall be implemented by the contractor:

(i) Prior to commencement of site works, the following plans that have been prepared and are appended with this report shall be implemented by the contractor:

- **Occupational and Community Health and Safety Plan** consistent with international standards (e.g., the World Bank Group's Environment, Health and Safety Guidelines of 2007). The Plan shall address health and safety hazards associated with tunneling (working in confined space and compressed air, etc.), working at heights, electrocution, excavations, establishment and operation of construction/worker's camps, use of heavy equipment, transport of materials and other hazards associated with various construction activities.

- **Emergency Response Plan** to prevent, mitigate, respond to and recover from emergency events that could occur due to project activities such as accidents during tunneling (e.g., tunnel collapse, electrocution, etc.), release of toxic gas during tunneling, spills of hazardous substances, fire, floods, and other crises.

(ii) Appoint an environment, health and safety manager to look after implementation of required environmental mitigation measures, and to ensure that health and safety precautions are strictly implemented for the protection of workers and the general public in the vicinity of construction areas.

(iii) Conduct workshop for all workers on health, safety and environmental measures.

(iv) Provide first aid facilities that are readily accessible by workers.

(v) Provide fire-fighting equipment at the work areas, where appropriate, and at construction camps.

(vi) Provide adequate drainage in workers camps to prevent water logging and formation of breeding sites for mosquitoes.

(vii) Provide potable water, hygienic sanitation facilities/toilets with sufficient water supply

(viii) Ensure that all wastewater emanating from workers camps, construction camps and other project-related activities and facilities are treated consistent with national regulations.

(ix) Establish clean canteen/rest area.

(x) Provide fencing on all areas of excavation greater than 2 m deep.

(xi) Provide appropriate personnel safety equipment such as safety boots, helmets, gloves, protective clothes, breathing mask, goggles, and ear protection.

(xii) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit construction workers.

(xiii) Implement fall prevention and protection measures whenever a worker is exposed to the hazard of falling more than two meters, falling into operating machinery or through an opening in a work surface. Based on a case specific basis, fall prevention/protection measures may include installation of guardrails with mid-rails and toe boards at the edge of any fall hazard area, proper use of ladders and scaffolds by trained employees, use of fall prevention devices, including safety belt and lanyard travel limiting devices to prevent access to fall hazard, fall protection devices such as full body harnesses, etc.

(xiv) Provide sufficient lighting such as in the tunnel areas, underground station excavation sites as well as in other construction areas, as appropriate, to enable safe equipment operation. Provide emergency lighting system of adequate intensity that is automatically activated upon failure of the principal artificial light source to ensure safe equipment operation, safe shut-down, evacuation, etc.

(xv) Ensure that sufficient fresh air is supplied at confined work spaces such as the tunnel and underground station excavation sites. Re-circulation of contaminated air is not acceptable. Air inlet filters shall be kept clean and free of dust and microorganisms; and,

(xvi) Confined spaces (e.g., tunnel) shall be provided with safety measures for venting, monitoring, and rescue operations, to the extent possible.

493. The following mitigation measures to ensure public safety shall be implemented by the contractor:

- (i) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit people, vehicle, and properties in adjoining areas.
- (ii) Fencing of construction sites and excavation sites and guarding such areas to restrict public access.
- (iii) Provide warning signs at the periphery of the construction site.
- (iv) Strictly impose speed limits on construction vehicles along residential areas and where other sensitive receptors such as schools, hospitals, and other populated areas are located.
- (v) Educate drivers on safe driving practices to minimize accidents and to prevent spill of hazardous substances and other construction materials during transport.

6.4.47 Traffic Concerns

- 481. The work areas shall be isolated and shielded to minimize road encroachment, contain dust and noise, and provide protection for pedestrians.
- 482. The following measures shall be implemented by the contractor to address impacts to traffic flows and access to properties:

- (i) Before site works commence, a Traffic Management Plan for the construction phase shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall be designed to ensure that traffic congestion due to construction activities and movement of construction vehicles, haulage trucks, and equipment is minimized.

The plan shall be prepared in consultation with local traffic officials and people's committees at the district and commune levels. The plan shall identify traffic diversion and management, transport mode for spoils disposal (e.g., trucks etc.), define routes for construction traffic from materials storage/parking areas to construction site and from construction site to waste disposal locations, traffic schedules, traffic arrangements showing all detours/lane diversions, modifications to signaling at intersections, necessary barricades, warning/advisory signs, road signs, lighting, and other provisions to ensure that adequate and safe access is provided to motorists in the affected areas.

- (ii) Provide signs advising road users that construction is in progress and that the road narrows to one lane using cones.
- (iii) Employ flag persons to control traffic at the work sites for safety reasons when construction equipment is entering or leaving the work area.
- (iv) Lanes shall be created through the work site using rope or flagging to minimize risks and injuries from falling objects.

- (v) As much as possible, lifting and placing of the pre-cast pillar sections will be done at night to minimize traffic congestion.
- (vi) Post traffic advisory signs (to minimize traffic build-up) in coordination with local authorities.
- (vii) Provide road signs indicating the lane is closed 500 m before the worksite.
- (viii) Use traffic cones to direct traffic to move to the open lane.
- (ix) Provide sufficient lighting at night within and in the vicinity of construction sites.
- (x) Regularly monitor traffic conditions along access roads to ensure that project vehicles are not causing congestion.
- (xi) Define and observe schedules for different types of construction traffic trips (e.g., transport of pre-cast sections, haulage of spoils, delivery of construction materials, etc.).
- (xii) As much as possible, schedule delivery of construction materials and equipment as well as transport of spoils during non-peak hours.
- (xiii) Avoid movements of noisy vehicles during night time in vicinity of sensitive receivers.
- (xiv) Implement suitable safety measures to minimize risk of adverse interactions between construction works and traffic flows through provision of temporary signals or flag controls, adequate lighting, fencing, signage and road diversions.
- (xv) Ensure relocation of any affected public transport infrastructure (but stops, shelters etc.) prior to commencement of works
- (xvi) Provide advance notification to the community regarding changes to public transport facilities or routes.
- (xvii) Schedule construction works to minimize extent of activity along linear construction site at any one time.
- (xviii) Comply with traffic regulations and avoid, where possible, roads with the highest traffic volumes, high density of sensitive receivers or capacity constraints are not used as access to and from the construction areas and spoils disposal sites.
- (xix) Install temporary accesses to properties affected by disruption to their permanent accesses.
- (xx) Reinstate good quality permanent accesses following completion of construction.

6.4.48 Cultural and Heritage Resources

483. The possibility of discovering archaeological relics is remote but still does exist. In the scenario of making a discovery of any cultural or archaeological significance, the 'Chance Find' procedures provided in ANNEX N of this report shall be followed.

Operation Related Impacts

6.4.49 Flooding

484. The project area is subject to minor, temporary flood events after heavy rain. The underground tunnel sections will be provided with pumps to pump storm water. Flood waters could enter the tunnel section if it is not adequately protected. A sill designed to meet annual and maximum flood height shall be constructed to protect the tunnel entrance from flood.

6.4.50 Noise

485. The following mitigation measures shall be implemented during operation phase:
- (i) Tunnel ventilation systems shall have suitable noise control measures incorporated into their design to reduce mechanical noise to acceptable levels in the surrounding community.
 - (ii) Depending on the results of monitoring, installation of acoustical treatment to the first few meters (i.e., <15 m) of the tunnel portal could be implemented, if necessary.

6.4.51 Health and Safety of Workers and the Public

486. A system will be installed to ensure circulation of fresh air to meet both normal and emergency requirements.
487. Pumps will be installed in the tunnels to pump storm water and wastewater.

6.5 Cumulative Impacts

488. Cumulative impacts would mainly be from other projects particularly road projects and buildings being constructed concurrently with the construction stage of this project. The BRT corridor is in the central urban area of Peshawar city where there might be other building construction or road construction works that might overlap with the construction stage of this project. At this time, no information is available on potential construction works that could overlap with the construction stage of this project. Also, no specific information has been observed in the GoKPK ADP 2016-17 that might suggest any specific projects planned near the project corridor.
489. The severity of cumulative effects, if any, would be dependent upon:

- The type of works being undertaken;
 - The duration of the works;
 - The distance between the works and their respective proximity to the receptor;
 - The sensitivity of the receptor; and
 - The visible presence of the works.
490. Construction related cumulative impacts, if any, will be effectively minimized by adopting proper mitigation measures, including:
- (i) Coordination between all project components and other projects in the area of influence in terms of construction schedule, possible access road and borrow/disposal sites sharing;
 - (ii) Contractors will develop material transport plan with consultation of PDA and traffic police and the local community;
 - (iii) Enforcement of good construction management to minimize dust, noise and waste generation;
 - (iv) Education of construction workers to minimize social disturbance and cultural conflict;
 - (v) Provision of temporary access to local traffic;
 - (vi) Proper maintenance of the access roads and timely restoration/strengthening upon completion.
491. Indirect cumulative effects as a result of construction can also occur. To avoid disruptions to traffic flow caused by construction works, drivers sometimes choose to travel on surrounding roads, known as 'rat-running'. This can affect traffic flows on roads not directly affected by the construction works. Rat-running can result in reduced air quality, increased noise, reduced amenity etc. Rat-running is a common concern at a local level although by, for example, effective traffic management or night-time working then it may be possible to reduce the risk of rat-running.
492. The development of the proposed project will eventually have an affect on the key receptors in close proximity to the project corridor. Urbanization will result in changes to livelihoods; however, impact to the existing population will mostly be positive, with improved urban environmental quality and better socio-economic opportunities.
493. With effective implementation of good construction management measures, any of these common construction-related cumulative impacts can be adequately mitigated to acceptable levels.

6.6 Indirect and Inducted Impacts

494. The construction of the BRT corridor through development of overhead bridges where none existed before has the potential to influence land use development patterns, traffic volumes and consequent developments on adjacent roads. The proposed BRT corridor infrastructure as well as future traffic volumes on these roads have been examined in the context of the preliminary design study.
495. The proposed project infrastructure will induce developments throughout the city and will provide transport linkage to the suburbs of Peshawar such as Bara road, Gulshan Rehman Colony, Peshawar Ring road and Charsadda road. The BRT corridor will improve transport among these suburban parts and the central urban area of Peshawar city. Their individual contributions to, and influence on the district and neighborhood traffic flows, have therefore been assessed within the context of the relevant plans and are considered appropriate.
496. The potential impact of development in Peshawar city have been examined, which indicated that the existing and planned infrastructure such as water supply, wastewater collection and treatment, municipal solid waste collection and disposal would be adequate to accommodate the population intake as a result of the proposed project development. Impacts on the environment from air emissions, traffic and community noise, and treated effluent discharge have also been assessed and have found to be acceptable and within the carrying capacities of the environmental media.
497. Negative indirect and induced impacts from this project are not expected.

7 Environmental Management and Monitoring Plan

7.1 Introduction

498. The Environmental Management and Monitoring Plan (EMP) is developed to eliminate and/or mitigate the impacts envisaged at the design, construction and operation stages and provide specific guidelines for long term monitoring by identifying the roles and responsibilities of PDA, Supervision Consultant and Contractor(s).

499. The detailed EMP provided in this section provided as Table 7.1 ensures that the Project has no detrimental effect on the surrounding environment. The Plan shall act as a guideline for incorporating environmental measures to be carried out by the contractors engaged by PDA, as well as for other parties concerned for mitigating possible impacts associated with the Project and will form part of the Contract documents to be considered alongside the specifications. This Plan shall act as the Environmental Monitoring Plan during construction and operational phases of the Project, and will allow for prompt implementation of effective corrective measures.

7.2 Environmental Management Plan (EMP)

500. The EMP attached with this report ensures the following:

- Delivery of the prescribed environmental outcomes during all phases of the Project;
- Formulating a system for compliance with applicable legislative and non-legislative requirements and obligations and commitments for the Project;
- Ensure that project design process incorporates best practice environmental design and sustainability principles to minimize potential impacts of construction and operation on the environment and community.
- Ensure that the construction work procedures minimize potential impacts on the environment and community.
- Develop, implement and monitor measures that minimize pollution and optimize resource use.

7.3 Objectives of EMP

501. The EMP provides a delivery mechanism to address potential impacts of the project activities, to enhance project benefits and to outline standardized good practice to be adopted for all project works. The EMP has been prepared with the objectives of:

- Defining the roles and responsibilities of the project proponent for the implementation of EMP and identifying areas where these roles and responsibilities can be shared with other parties involved in the execution and monitoring of the project;
- Outlining mitigation measures required for avoiding or minimizing potential negative impacts assessed by environmental study;


- Developing a monitoring mechanism and identifying requisite monitoring parameters to confirm effectiveness of the mitigation measures recommended in the study;
- Defining the requirements for communication, documentation, training, monitoring, management and implementation of the mitigation measures.

7.4 Environmental Management/Monitoring and Reporting

502. During the construction phase, the overall responsibility for the implementation and monitoring of the EMP rests with the Project Director (PD). The PD through assistance from the Supervision Consultant's Environmental staff and the Environment team of PDA, will supervise the implementation of the proposed mitigation measures and monitor the implementation progress in the field. Monthly environmental monitoring data/reports will be incorporated in the project implementation progress reports to be shared with ADB and such monthly reports will be consolidated into bi-annual monitoring reports and submitted to ADB for review and clearance. Upon clearance, all such reports will be uploaded on the PDA and ADB websites.

503. The organizational structure for the Environmental Management/Monitoring implementation is shown in Figure 7.1 below. The specific roles and responsibilities for environmental management are provided in Tables 7.9 and 7.10 below.

Figure 7.1: Organization Chart for Environment Management/Monitoring implementation



504. Keeping in view the sensitive nature of the project in terms of the highly congested and urban environment in which the project will be developed, it is proposed that external monitoring of the EMP shall be conducted to ensure all proposed mitigation measures are being implemented in their true spirit.

7.5 Institutional Arrangements

505. The proposed project environmental management plan will require involvement of the following organizations for its implementation:

- The Project Management Unit (PMU), which will be established at the PDA, this PMU will be the project proponent and owners of the EMP;
- Project Contractors as executors of the EMP;
- Project Environment Officer (PEO) as environmental monitor of the execution of the EMP.

7.5.1 Role of PDA

506. As the proponent of the project, PDA will be responsible for implementation of the EMP. The PDA will be responsible for ensuring the implementation of the EMP and for overall environmental performance during construction operations and also for ensuring implementation of the EMP by the project contractors.

7.5.2 Role of Project Director

507. The key responsibilities of the PD will be as follows:

- Liaise closely with the environmental agency (KP-EPA) and all concerned Government departments e.g. Forest and Wildlife Department, Department of Archaeology and Museums etc.
- Obtaining approval of the EIA study;
- Ensuring the EMP is properly implemented;
- Responsible for all environmental coordination and reporting;
- Provide technical support for compliance and monitoring of EMP;
- Responsible for resettlement plan;

7.5.3 Role of Project Contractor

508. The project contractor will be responsible for following items:

- Implementation of, or adherence to, all provisions of the EIA and EMP;
- Contractor's environmental performance will rest with the person holding the highest management position within the contractor's organization. Reporting to their management, the contractor's site managers will be responsible for the effective implementation of the EMP.

7.6 Environmental Performance Indicators

509. Environmental performance indicators will be chosen to quantify that whether the targets of environmental policy safeguards are met as desired in the EMP within the specified time period. The quantitative data against following attributes as performance indicators will be collected and reported in the quarterly environmental monitoring reports.

- **Water Quality and related issues**

Indicator of water quality must quantify water contamination or pollution and any changes in the water composition and chemistry whether surface or ground water in terms of water quality parameters and their pattern of existence.

- **Air and Noise pollution**

Magnitude of air and noise quality changes due to project activities.

- **Flora and Fauna**

Any quantifiable changes in the population of flora and fauna and in their habitat patterns will be recorded.

- **Traffic and transportation**

Management of traffic during construction and adequate planning for operation phase.

- **Socio-economic**

Impact on the local/regional economy

Changes in cultural pattern

Dislocation of population

- **Health and Safety**

New disease pathways

Number of injuries or casualties

7.7 Monitoring Parameters

510. The key environmental parameters such as ambient air quality, noise levels, waste disposal etc. will be monitored at key receptor locations.

511. A monitoring plan for the pre-construction, construction and operation phases of the project, indicating environmental parameters, frequency, locations and applicable standards is provided as Tables 7.1, 7.2 and 7.3 below. Standards set under the NEQS guidelines for the key receptors are also provided as ANNEX B.

7.8 Environmental Training

7.8.1 Capacity Building and Training

512. Capacity building and training programs are necessary for PDA staff in order to control the negative impacts resulting from the project construction and during its operation phase. They will also require trainings on monitoring and inspecting of such a project for environmental impacts and for implementation of mitigation measures.

513. The details of this capacity building and training program are presented in the Table 7.4 below.

Table 7.1: Pre-Construction Monitoring Requirements

Project Activity and Potential Impact	Objective of Monitoring	Parameters to be Monitored	Measurements	Location	Frequency	Responsibility
Demolition and re-allocation of shops for small business owners located near BRT route	To ensure the affected small business owners are provided shops of equal plot size and value	Process of re-allocation of shops	To ensure shop owners are allocated alternate shops at new locations to their satisfaction near BRT corridor	-	-	Contractor's Environmental officer, PDA
Relocation of infrastructure (water pipelines, gas pipelines, electric cables etc.)	To ensure no interruption of these services takes place once construction activity commences	Process of relocation of services	Completion of relocation of services to alternate pathways	Along project corridor wherever relocation of services is necessary	-	PDA
Ambient Air Quality	To establish baseline air quality levels	CO, NO _x & PM ₁₀ (particulate matter smaller than 10 microns) concentration at receptor level	1-hr and 24-hr concentration levels	At five key receptor locations along the project corridor	Twice in total (Once on a weekday and once on a weekend)	PDA
Ambient Noise	To establish baseline noise levels	Ambient noise level near key receptors along project corridor	A-weighted noise levels – 24 hours, readings taken at 15 s intervals over 15 min. every hour, and then averaged	At five key receptor locations along the project corridor	Twice in total (Once on a weekday and once on a weekend)	PDA

Table 7.2: Construction Phase Monitoring Requirements

Project Activity and Potential Impact	Objective of Monitoring	Parameters to be Monitored	Measurements	Location	Frequency	Responsibility
Noise Disturbance due to noise from construction activity	To determine the effectiveness of noise abatement measures on sound pressure levels	Ambient noise level near key receptors along project corridor	A-weighted noise levels – 24 hours, readings taken at 15 s intervals over 15 min. every hour, and then averaged	At five key receptor locations along the project corridor	Once every three months on a typical working day	Contractor's Environmental officer, PDA
Air Quality Dust emissions from construction vehicles and equipment	To determine the effectiveness of dust control program on dust at receptor level	CO,NO _x & PM ₁₀ (particulate matter smaller than 10 microns) concentration at receptor level	1-hr and 24-hr concentration levels	At five key receptor locations along the project corridor	Once every three months on a typical working day	Contractor's Environmental officer, PDA
		Visible dust	Visual observation of size of dust clouds, their dispersion and the direction of dispersion	Construction sites	Once daily during peak construction period	Contractor's Environmental officer, PDA
Water Resources Wastage of water leading to depletion in water resources	To prevent wastage of water during the construction works	Volume of water being used versus its utilization	Visual observations of water being used at project sites and at labor camps	Construction sites and labor camps	Once daily	Contractor's Environmental officer, PDA
Landscape scarring at borrow sites	To ensure landscape does not lose its aesthetic value	-	Visual inspection	Borrow sites	Weekly	Contractor's Environmental officer, PDA
Soil erosion	To ensure soil erosion does not take place	-	Visual inspection	Borrow sites	Weekly	Contractor's Environmental officer, PDA
Increase in traffic accidents	To minimize risk of traffic accidents	Number of accidents taking place	Visual monitoring	Construction sites along BRT corridor	Once Daily	Contractor's Environmental officer, PDA

Project Activity and Potential Impact	Objective of Monitoring	Parameters to be Monitored	Measurements	Location	Frequency	Responsibility
Delays in traffic management	To ensure traffic movement is efficiently managed	Number of traffic congestion events	Visual inspections	Construction sites along BRT corridor	Once Daily	Contractor's Environmental officer, PDA
Safety precautions by Safety workers	To prevent accidents for workers and general public	Number of near miss events and accidents taking place	Visual inspections	Construction sites along BRT corridor	Once Daily	Contractor's Environmental officer, PDA
Soil Contamination	To prevent contamination of soil from oil and toxic chemical spills and leakages	Incidents of oil and toxic chemical spills	Visual inspections	At construction sites and at vehicle and machinery refuelling & maintenance areas	Once a month	Contractor's Environmental officer, PDA
Solid Waste & Effluent disposal Insufficient procedures for waste collection, storage, transportation and disposal	To check the availability of waste management system and implementation	Inspection of solid and liquid effluent generation, collection, segregation, storage, recycling and disposal will be undertaken at labor camps and at all work sites along project corridor	Visual inspections	At labor camps and at work sites along project corridor	Once daily. Liquid effluent to be tested on quarterly basis	Contractor's Environmental officer, PDA
Protection of Heritage Sites Destruction of relic or damage to heritage site	To ensure heritage sites are protected and any relic found is recovered without damage	Careful inspections during excavation work in case any relic is discovered	-	At work sites along project corridor, particularly near Bala Hisar fort	During excavation work	Contractor's Environmental officer, PDA

Table 7.3: Operation Phase Monitoring Requirements

Project Activity and Potential Impact	Objective of Monitoring	Parameters to be Monitored	Measurements	Location	Frequency	Responsibility
Noise Disturbance due to noise from operational activity	To determine the effectiveness of noise abatement measures on sound pressure levels	Ambient noise level near receptors along BRT corridor	A-weighted noise levels – 24 hours, readings taken at 15 s intervals over 15 min. every hour, and then averaged	At five key receptor locations along the project corridor	Once every six months	O&M Contractor's Environmental officer, PDA
Air Quality Air pollutants can adversely affect the ambient air quality and impact human health	To ensure air pollutants are not present above the permissible guidelines	Ambient air quality i.e. concentration of pollutant gases in air such as CO, NO _x and PM ₁₀	Concentration levels of the pollutant gases	At five key receptor locations along the project corridor	Once every six months	O&M Contractor's Environmental officer, PDA
Wastewater generation and Discharge Effluent discharge from depots and workshop areas can affect water resources of project area	To ensure water resources of city are not affected by effluent from depots and workshop areas	Characteristics of wastewater	Chemical analysis of the wastewater Operational efficiency of the wastewater treatment plant and other units	Depots and Workshop areas (at point of discharge of the effluent)	Once every six months	O&M Contractor's Environmental officer, PDA
Hazardous material Hazardous chemicals such as oils, paints can harm human health and contaminate soil	To ensure proper disposal of hazardous material (if any)	Quantity of hazardous waste generated and its disposal procedure	Complete record of purchase, storage, use, and disposal of hazardous material will be maintained	At point of generation of hazardous material	Daily records to be maintained	O&M Contractor's Environmental officer, PDA

Solid Waste Management Domestic garbage from stations and buses as well as from depots and workshops	To ensure solid waste is disposed off in an environmentally friendly manner	Amount of solid waste generated and its disposal method	Records of waste generated On-site audits of waste management Audits of the waste disposal contractors and waste disposal facilities	BRT stations, buses, depots and workshops	Daily records of waste generated to be maintained. Audits to be conducted monthly.	O&M Contractor's Environmental officer, PDA
Adaptability of General Public to Driving Conditions	To minimize risk of accidents and facilitate adaptability to new infrastructure of BRT project by educating general public	Number of accidents taking place	Accidents per week	Along entire BRT corridor where BRT infrastructure has changed driving conditions	Monthly review	O&M Contractor's Environmental officer, PDA

Table 7.4: Capacity Development and Training Programme

Provided by	Organized by	Contents	No. of training events	Duration	Cost (PKR)
Pre-construction Phase Monitoring Consultants/Organizations offering specialized services in environmental management and monitoring	Project Director	Short seminars and courses on: Environmental Management Plan and Environmental Monitoring Plan	Two seminars for Contractor management staff and PDA project staff	3 days each	200,000
Construction Phase Monitoring Consultants/Organizations offering specialized services in social management and monitoring	Project Director	Short seminars on Environmental risks associated with construction phase. Development of Environmental Performance Indicators Occupational Health and Safety (OHS) issues	Two seminars for Contractor management staff and PDA project staff dealing in environment and social issues	3 days each	200,000
Operational Phase Monitoring Consultants/Organizations offering specialized services in Occupational Health and Safety (OHS) Issues	Project Director	Short seminars relating to monitoring of environmental and social parameters during operational phase	Two seminars for O&M Contractor and PDA staff	3 days each	200,000
Total			600,000 (PKR 0.6 million)		

7.9 Environmental Management Costs

514. The Table 7.5 below provides cost estimates for 'Pre-Construction phase' monitoring while Table 7.6 provides cost estimates for 'Construction phase' monitoring and Table 7.7 provides the cost estimates for the 'Operation phase' monitoring of key environmental parameters.

515. The costs associated with implementation of the EMP and the necessary mitigation measures are provided as Table 7.8 below. The Table 7.9 below provides the Environmental management and monitoring plan for the proposed project.

Table 7.5: Annual Cost Estimates for ‘Pre-Construction Phase’ Environmental Monitoring

Monitoring Component	Parameters	Quantity	Amount PKR	Details
Air Quality	CO, NO _x , PM ₁₀	10 (Twice only at 5 locations)	600,000	10 readings @ PKR 60,000 per sample
Noise Levels	dB(A)	10 (Twice only at 5 locations)	600,000	10 readings @ PKR 60,000 per reading
Contingencies			60,000	5% of monitoring cost
Total (PKR)			660,000	

Table 7.6: Annual Cost Estimates for ‘Construction Phase’ Environmental Monitoring

Monitoring Component	Parameters	Quantity	Amount PKR	Details
Air Quality	CO, NO _x , PM ₁₀	20 (Quarterly basis at 5 locations)	12,00,000	20 readings @ PKR 60,000 per sample
Noise Levels	dB(A)	20 (Quarterly basis at 5 locations)	12,00,000	20 readings @ PKR 60,000 per reading
Liquid Effluents				
Effluent produced from labor camp and construction sites	As per NEQS	20 (Quarterly basis at 5 sites)	400,000	20 samples @ PKR 20,000 per sample
Contingencies			140,000	5% of monitoring cost
Total (PKR)			2,940,000	

Table 7.7: Annual Cost Estimates for ‘Operation Phase’ Environmental Monitoring

Monitoring Component	Parameters	Quantity	Amount PKR	Details
Air Quality	CO, NO _x , PM ₁₀	10 (Twice a year at 5 locations)	600,000	10 readings @ PKR 60,000 per sample
Noise Levels	dB(A)	10 (Twice a year at 5 locations)	600,000	10 readings @ PKR 60,000 per reading
Liquid Effluents				
Effluent produced from depots and workshop areas	As per NEQS	8 (twice a year at 4 locations)	160,000	8 readings @ PKR 20,000 per reading
Contingencies			68,000	5% of monitoring cost
Total (PKR)			1,428,000	

Table 7.8: Estimated Costs for EMP Implementation

Item	Sub-Item	Estimated Total Cost (PKR)
Staff, audit and monitoring cost¹	6 persons for 18 months (@ 50,000 per month per staff member)	54,00,000
Monitoring Activities	Provided separately in Tables 6.5 to 6.7.	-
Mitigation Measures	As prescribed under EMP and EIA.	16,500,000
(i) Noise barriers²	Specific locations for installation of noise barriers to be assessed. Presently, a total of 800 meters of noise barriers are estimated to be installed around sensitive receptors.	80,00,000
(ii) Water sprinkling	To suppress dust emissions	25,00,000
(iii) Double glazed windows³	At highly sensitive receptors such as hospitals where noise levels must be strictly controlled. A total of 300 m ² of these windows are envisaged.	1,500,000
(iv) Wastewater collection & Treatment	From labor camps and construction sites (based on initial estimates)	25,00,000
(v) Solid waste collection & disposal	From labor camps and construction sites (based on initial estimates)	20,00,000
Contingencies	5% of EMP implementation cost	1,095,000
Total Estimated Cost (PKR)		22,995,000

1: To cover staff cost and expenses of Construction Supervision Consultant (CSC)

2: Approx. 10,000 PKR per meter

3: Approx. 5000 PKR per m²

Table 7.9: Environmental Management and Monitoring Plan

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Design/Pre-Construction Stage						
Historical Heritage sites	To protect any historical sites present within BRT corridor.	To stop excavation work immediately if any artifact of historical importance is discovered.	At BRT route design stage and once excavation work commences	Along project corridor wherever excavation will be conducted	PDA	Department of Archaeology, GoP
Land Acquisition & Resettlement	To ensure smooth transition in shifting of shop and house owners to new locations	1. Detailed dialogue with affected parties to ensure all concerns are addressed. 2. The new shops and houses allocated to affected parties must be based on a fair and transparent criterion.	Prior to commencement of construction and demolition activity	Along project corridor wherever shifting of shops and/or houses needs to be conducted	PDA	ADB Resettlement Specialist
Locations for Labor Camps	To ensure the labor camps do not pose any adverse impacts on the project area	1. Specific locations will be strategically selected for development of labor camps that contain all necessary facilities. 2. Camp locations will ensure minimal disturbance to key receptors in project area	Prior to commencement of construction activity	Most suitable locations for labor camps nearest to the BRT corridor must be identified	PDA	-
Traffic Management	To minimize possibility of accidents and	Development of a comprehensive plan that shall contain traffic	Prior to commencement of construction activity	At all construction sites along project corridor	PDA	-

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Plan	traffic congestion once construction commences and thus minimize possible nuisance for residents of Peshawar	diversion onto alternate routes and management traffic flows to minimize congestion and possibility of accidents.				
Construction Stage						
Air Quality	To minimize air emissions effectively and avoid complaints due to the airborne particulate matter released to the atmosphere.	<p>1. Water will be sprinkled daily at all construction sites to suppress dust emissions.</p> <p>2. All heavy equipment and machinery shall be fitted in full compliance with the national and local regulations. (Relevant regulations are in the Motor vehicles fitness rules and Highway Act).</p> <p>3. Stockpiled soil and sand shall be slightly wetted before loading, particularly in windy conditions.</p> <p>4. Fuel-efficient and well-maintained haulage trucks shall be employed to minimize exhaust emissions.</p>	All construction sites within 100 m of sensitive receivers.	A list of locations to be included in contract and other sensitive areas identified by the CSC in project area.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>5. Vehicles transporting soil, sand and other construction materials shall be covered with tarpaulin.</p> <p>6. Limitations to speeds of such vehicles necessary. Transport through densely populated area should be avoided.</p> <p>7. Concrete plants to be controlled in line with statutory requirements and shall not be close to sensitive receptors.</p> <p>8. Stack height of generators will be at least 3 meters above the ground.</p> <p>9. Project traffic will maintain maximum speed limit of 20 km/hr on all unsealed roads within project area.</p>				
Noise / Ground Vibration	To minimize noise level increases and ground vibrations during	1. Equipment noise will be reduced at source by proper design, maintenance and repair of construction machinery	All construction sites within 100 m of sensitive receivers.	A list of locations to be included in contract and other sensitive areas identified by the CSC in project area.	Contractor should maintain the acceptable standards	PDA / CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	construction activities.	<p>and equipment. Noise from vehicles and power generators will be minimized by use of proper silencers and mufflers.</p> <p>2. Excessive noise emitting equipment will not be allowed to operate and will be replaced.</p> <p>3. Blowing of horns will be prohibited on access roads to site.</p> <p>4. As a rule, the operation of heavy equipment shall be conducted in daylight hours.</p> <p>5. Hammer- type percussive pile driving operations shall be not be allowed at night time.</p> <p>6. Construction equipment, which generates excessive noise, shall be enclosed or fitted with effective silencing apparatus to minimize noise.</p> <p>7. Well-maintained haulage trucks will be used with speed controls.</p>			CSC to supervise relevant activities.	

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>8. Contractor shall take adequate measures to minimize noise nuisance in the vicinity of construction site by way of adopting available acoustic methods to remain within NEQS limits.</p> <p>9. Noise levels at sensitive receptors along corridor will be frequently monitored.</p>				
Traffic Management	<p>Minimize disturbance of vehicular traffic and pedestrians during haulage of construction materials, spoil and equipment and machinery, blocking access roads during works</p> <p>Damage / maintenance problems for roads and bridges used by the haulage trucks, dust nuisance to</p>	<p>1. Submit temporary haul and access routes plan one month prior to start of works.</p> <p>2. Formulate and implementation of a plan of alternate routes for heavy vehicles.</p> <p>3. Vicinity of schools and hospitals to be considered.</p> <p>4. Installation of traffic warning signs, and enforcing traffic regulations during transportation of materials and equipment and</p>	Prior to and throughout the construction.	The most important locations to be identified and listed. Relevant plans of the Contractor on traffic arrangements to be prepared and available.	Contractor and Engineer	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	school and hospitals.	<p>machinery. Conditions of roads and bridges to be considered.</p> <p>5. Widening/upgrading of access paths/roads.</p>				
Labor Camp Effluent	Prevent untreated effluent from being released into the environment.	<p>1. No untreated effluent will be released into the environment.</p> <p>2. Closed sewage treatment system will treat the effluent, which will then be disposed of in a soak pit or will be used for plantation.</p>	During Construction	At labor camps	Contractor	PDA/ CSC
Construction Waste Disposal	Minimize the impacts from the disposal of construction waste.	<p>1. Waste management plan to be submitted to the CSC and approved one month prior to starting works.</p> <p>2. Estimating the amounts and types of construction waste to be generated by the project.</p> <p>3. Investigating whether the waste can be reused in the project or by other interested parties.</p>	Update monthly	A list of temporary stockpiling areas and more permanent dumping areas to be prepared at the contract stage for agreement.	Contractor and CSC should supervise and take action to complete contractor's relevant activities according to EIA/IEE/ EMP requirement & environmental standards.	PDA/ CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>4. Identifying potential safe disposal sites close to the project or those designated sites in the contract.</p> <p>5. Investigating the environmental conditions of the disposal sites and recommendation of most suitable and safest sites.</p> <p>6. Piling up of loose material should be done in segregated areas to arrest washing out of soil. Debris shall not be left where it may be carried by water to downstream flood plains, dams, lagoons etc.</p> <p>7. Used oil and lubricants shall be recovered and reused or removed from the site in full compliance with the national and local regulations.</p> <p>8. Oily wastes must not be burned. Disposal location to be agreed with local authorities/EPA.</p> <p>9. Machinery should be properly maintained to minimize oil spill during the</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>construction.</p> <p>10. Solid waste should be disposed at an approved solid waste facility, open burning is illegal and contrary to good environmental practice.</p>				
Orientation for Contractors, and Workers	To ensure that the CSC, contractor and workers understand and have the capacity to ensure the environmental requirements and implementation of mitigation measures.	<p>1. PDA to engage environmental specialist in the PMU to monitor and progress all environmental statutory and recommended obligations.</p> <p>2. Conduct special briefing for managers and / or on-site training for the contractors and workers on the environmental requirement of the project. Record attendance and achievement test.</p> <p>3. Agreement on critical areas to be considered and necessary mitigation measures, among all parties who are involved in project activities.</p> <p>4. Continuous progress review and refresher</p>	<p>Induction of all relevant staff required for implementation of EMP.</p> <p>At early stages of construction for all construction employees as far as reasonably practicable.</p>	All staff members in all categories. Monthly induction and six month refresher course as necessary until contractor complies.	Contractor and the CSC and record details	PDA & CSC to observe and record success

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		sessions to be followed.				
Labor Camp(s) Operation and Location	To ensure that the operation of work camps does not adversely affect the surrounding environment and residents in the area.	<p>1. Identify location of work camps in consultation with local authorities. The location shall be subject to approval by the PDA. If possible, camps shall not be located near settlements or near drinking water supply intakes.</p> <p>2. Cutting of trees shall be avoided and removal of vegetation shall be minimized.</p> <p>3. Water and sanitary facilities (at least pit latrines) shall be provided for employees. Worker camp and latrine sites to be backfilled and marked upon vacation of the sites.</p> <p>4. Solid waste and sewage shall be managed according to the national and local regulations. As a rule, solid waste must not be dumped, buried or burned at or near the project site, but shall be</p>	Update once a month	Location Map to be prepared by the Contractor.	Contractor	PDA/ CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>disposed off to the nearest sanitary landfill or site having complied with the necessary permission of local authority permission.</p> <p>5. The Contractor shall organize and maintain a waste separation, collection and transport system.</p> <p>6. The Contractor shall document that all liquid and solid hazardous and non-hazardous waste are separated, collected and disposed of according to the given requirements and regulations.</p> <p>7. At the conclusion of the project, all debris and waste shall be removed. All temporary structures, including office buildings, shelters and toilets shall be removed.</p> <p>8. Exposed areas shall be planted with suitable vegetation.</p> <p>9. PDA and Supervising Engineer shall inspect and report that the camp has</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		been vacated and restored to pre-project conditions.				
Loss of Trees and Vegetation Cover for Temporary Work-space and Wildlife Loss	To avoid several negative impacts due to removing of landmark, sentinel and specimen trees as well as green vegetation and surface cover and wildlife loss.	<p>1. The contractor's staff and labor will be strictly directed not to damage any vegetation such as trees or bushes.</p> <p>2. Clearing of green surface cover for construction, for borrow of for development, cutting trees and other important vegetation during construction shall be minimized.</p> <p>3. Landscaping and road verges to be re-installed on completion.</p> <p>4. Compensatory planting of trees/shrubs/ornamental plants (at a rate of 3:1) to contribute to the aesthetic value of the area and compensate for the lost capability of the area to absorb carbon dioxide in line with best international practice.</p> <p>7. At completion all debris</p>	Site identification during design stage and other matters during construction of relevant activities	A list of locations with a Map to be compiled by the design consultant during detailed design and CSC to update as necessary.	Design consultant, Contractor and CSC	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and waste shall be removed.</p> <p>8. All temporary structures, including office buildings, shelters and toilets shall be removed.</p> <p>9. Willful killing trapping and trade of faunal species will be strictly prohibited.</p>				
Safety Precautions for the Workers	To ensure safety of workers	<p>1. Providing adequate warning signs.</p> <p>2. Providing workers with skull guard or hard hat.</p> <p>3. Contractor shall instruct his workers in health and safety matters, and require the workers to use the provided safety equipment.</p> <p>4. Establish all relevant safety measures as required by law and good engineering practices.</p>	Prior to commencement and during construction	Location to be identified by the CSC with contractor.	Contractor and CSC	PDA/ CSC
Water Quality	To prevent adverse water	1. Compile temporary drainage management	Prior to construction, 50 m	Relevant locations to be determined in the detailed	1. Contractor CSC to enforce	PDA to review results

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	quality impacts due to negligence and ensure unavoidable impacts are managed effectively. Ensure adverse impacts on water quality caused by construction activities are minimized.	<p>plan one month before commencement of works.</p> <p>2. Proper installation of Temporary Drainage (TD) and Erosion Control (EC) before works within 50 m of water bodies.</p> <p>3. Proper construction of TD and EC measures, maintenance and management including training of operators and other workers to avoid pollution of water bodies by the considerate operation of construction machinery and equipment.</p> <p>4. Storage of lubricants, fuels and other hydrocarbons in self-contained dedicated enclosures >50m away from water bodies.</p> <p>5. Proper disposal of solid waste from construction activities and labor camps.</p> <p>6. Cover the construction material and spoil stockpiles with a suitable material to reduce material loss and sedimentation</p>	from water bodies. Timing will depend on the construction timetable.	project design	<p>2. Contractor has to check water quality and report to PDA.</p> <p>3. CSC supervises monitoring activities.</p>	

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and avoid stockpiling near to water bodies.</p> <p>7. Topsoil stripped material shall not be stored where natural drainage will be disrupted.</p> <p>8. Borrow sites (if required) should not be close to sources of drinking water.</p>				
Hydrology and Drainage Aspects	To ensure the hydrological and drainage aspects are considered during construction activity.	<p>1. Consideration of weather conditions when particular construction activities are undertaken.</p> <p>2. Limitations on excavation depths in use of recharge areas for material exploitation or spoil disposal.</p> <p>3. Use of landscaping as an integrated component of construction activity as an erosion control measure.</p> <p>4. Minimizing the removal of vegetative cover as much as possible and providing for its restoration where construction sites have been cleared of such areas.</p>	<p>1. Prepare a thorough plan to be approved by CSC one month prior to commencement of construction.</p> <p>2. Proper timetable prepared in consideration with the climatic conditions of each area, the different construction activities mentioned here to be guided.</p>	<p>1. Location of construction activities to be listed by the engineer.</p> <p>2. A list of locations of drains to be compiled by the contractor.</p>	CSC or PDA to actively supervise and enforce	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Soil Erosion/ Surface Run-off	Prevent adverse water quality impacts due to negligence and ensure unavoidable impacts are managed effectively. To minimize soil erosion due to the construction activities and creation of access tracks for project vehicles.	<p>1. Back-fill should be compacted properly in accordance with design standards and graded to original contours where possible.</p> <p>2. Stockpiles should not be formed within such distances behind excavated or natural slopes that would reduce the stability of the slopes.</p> <p>3. In the short-term, either temporary or permanent drainage works shall protect all areas susceptible to erosion.</p> <p>11. Clearing of green surface cover to be minimized during site preparation.</p> <p>12. Replanting of trees to be done before the site is vacated and handed back to PDA with appropriate trees (other vegetation cover as appropriate) to ensure interception of rainwater and the</p>	Because the area can be subject to un seasonal heavy rain plan before and during construction (cut and fill, land reclamation etc.) while considering the climatic conditions.	<p>1. Locations based on history of flooding problems.</p> <p>2. A list of sensitive areas during construction to be prepared by the detail design consultant in consideration with the cut and fill, land reclamation, borrow areas etc.</p> <p>3. Locations of all culverts, irrigation channels, road and highway.</p>	Contractor and CSC	PDA/ CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		deceleration of surface run-off.				
Utilities provision interruption	To ensure the sensitive receptors in the project area are not affected by the relocation/ disruption of any utilities such as water supply, electricity, telecommunication, gas supply etc.	<p>1. Contractor(s) will assess construction locations in advance for potential disruption to services and identify risks prior to starting construction. Any damage or hindrance/disadvantage to local businesses caused by the premature removal or insufficient replacement of public utilities is subject to full compensation, at the full liability of the contractor who caused the problem.</p> <p>2. If temporary disruption is unavoidable, the contractor will, in collaboration with relevant local authorities such as power company, water supply company and communication company, develop a plan to minimize the disruption and communicate the dates and duration in advance to the affected persons.</p>	<p>1. Prepare a thorough plan to be approved by CSC one month prior to commencement of construction.</p> <p>2. Implement measures during construction activity</p>	Along entire BRT corridor at each location where construction work is being conducted.	Contractor and the CSC	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>3. Communities shall be informed in advance regarding storage of water when their utilities are about to be relocated to pave the way for road works. Also, water pipes located/crossing in the right of way (road reserve) may be moved slightly away from the road or provision of service duct may be considered.</p> <p>4. Construction billboards, which include construction contents, schedule, responsible person and complaint phone number, will be erected at each construction site.</p>				
Social Impacts	<p>To ensure minimum impacts from construction labor force.</p> <p>To ensure minimum impacts on public health.</p> <p>To ensure minimum effects of indirect impacts of</p>	<p>1. Potential for spread of vector borne and communicable diseases from labor camps shall be avoided (worker awareness orientation and appropriate sanitation should be maintained).</p> <p>2. Claims/complaints of the people on construction</p>	<p>Complaints of APs to be solved as soon as possible. Necessary evacuations to be done as when necessary if construction impacts are of significant duration and close to APs.</p>	Project area.	Contractor and the CSC	PDA/ CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	<p>constructions to the people who are living close to the boundary of project site; Dust, Noise and Vibration effects etc.</p> <p>To minimize access problems for local population during construction.</p>	<p>nuisance/damages close to project site to be considered and responded to promptly by the Contractor.</p> <p>3. Contractor shall organize temporary means of access and make alternative arrangements to avoid local community impacts and to avoid such short-term negative impacts.</p>				
Operational Stage						
Air Quality	To ensure operational phase of BRT project does not have adverse impact on air quality of project area	<p>1. Buses and all mechanical equipment such as generators shall undergo regular maintenance and shall be tuned to maintain engine efficiency and minimize emissions in compliance of NEQS limits.</p> <p>2. Stack height of generators (if any) will be at least 3 meters above the ground.</p>	Once BRT operation commences.	Along BRT corridor and at associated facilities such as depots, workshops etc.	O&M Contractor	PDA
Noise Levels	To ensure noise levels remain within acceptable NEQS limits	1. Tuning and maintenance of buses and mechanical equipment such as buses on regular	Once BRT operation commences.	Along BRT corridor and at associated facilities such as depots, workshops etc.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	during BRT project operation	<p>basis to minimize noise levels and comply with NEQS limits.</p> <p>2. Strict driving protocols shall be followed such as no honking etc.</p>				
Water Resources	To ensure any wastewater being discharged from BRT facilities complies with NEQS limits.	<p>1. Proper wastewater collection and treatment facility must be developed at depots.</p> <p>2. Efficient storm water drainage network along BRT route must be developed.</p>	Once BRT operation commences.	At BRT depots and workshop areas	O&M Contractor	PDA
Solid Waste Disposal	To prevent contamination of the areas along the project corridor due to improper solid waste disposal.	1. Proper waste management plan will be prepared and implemented to ensure waste collection, transfer and disposal.	Once BRT operation commences.	At BRT stations, depots and workshop areas	O&M Contractor	PDA
Biological Environment	To replant any vegetation such as trees, plants uprooted due to project development	Plantation and landscaping shall be conducted along BRT corridor wherever vegetation has been removed. This will ensure the existing aesthetic value of the project area is protected.	As soon as BRT construction is complete.	Along BRT corridor wherever vegetation has been removed.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Adaptability of general public to driving conditions	To ensure general public adapts to the new BRT infrastructure and changed driving conditions.	1. Provisions will be made in detailed designs for road conditions at major intersections to meet local design standards. 2. Fluorescent signboards shall be used for the major junctions.	Prior to commencement and once BRT operation commences.	Along BRT corridor	O&M Contractor	PDA

PDA Peshawar Development Authority
PD Project Director
CSC Construction Supervision Consultant
O&M Operation & Maintenance

Table 7.10: 'Site Specific' Environmental Management and Monitoring Plan

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
BUS DEPOT						
Construction Stage						
Soil Contamination/ Hazardous Substances	To prevent contamination of soil from toxic and hazardous substances	(i) Before site works commence, a Spill Management Plan shall be prepared by the contractor and shall be approved by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of procedures, responsibilities, resources, documentation and reporting requirements, training provisions for relevant staff, etc. to avoid spills of hazardous substances and to effectively respond to such incidents, in case these occur. (ii) Store fuel and	During Construction	At each location for development of the Bus Depot	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>hazardous substances in paved areas with embankment. If spills or leaks do occur, undertake immediate clean up.</p> <p>(iii) Ensure availability of spill clean-up materials (e.g., absorbent pads, etc.) specifically designed for petroleum products and other hazardous substances where such materials are being stored and used.</p> <p>(iv) Train relevant construction personnel in handling of fuels and spill control procedures.</p> <p>(v) Ensure all storage containers are in good condition with proper labeling.</p> <p>(vi) Regularly check containers for leakage and</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>undertake necessary repair or replacement.</p> <p>(vii) Store hazardous materials above flood level.</p> <p>(viii) Equipment maintenance areas shall be provided with drainage leading to an oil water separator that will be regularly skimmed of oil and maintained to ensure efficiency. Discharge of oil contaminated water shall be prohibited.</p> <p>(ix) Store waste oil, used lubricant and other hazardous wastes in tightly sealed containers to avoid contamination of soil and water resources. Transport and off-site disposal of such wastes shall be consistent with national and local</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		regulations.				
Wastewater	To ensure only wastewater meeting the NEQS standards is discharged into the environment.	The depot(s) will be equipped with a wastewater treatment facility to ensure that effluent discharge complies with applicable national standards.	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC
Drainage	To ensure the construction activity does not affect the natural drainage patterns in the project area.	<p>(i) Avoid placement of construction materials, waste storage areas or equipment in or near drainage channels surrounding the Depot.</p> <p>(ii) Prohibit disposal of waste materials to drainage channels.</p> <p>(iii) In case existing drainage ditch is filled-up as required for the construction works, provide alternative drainage for rainwater.</p>	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		(iv) Regularly inspect and maintain all drainage channels to keep these free of obstructions.				
Air Quality	To minimize air emissions effectively and avoid complaints due to the airborne particulate matter released to the atmosphere	(i) Before site works commence, a Dust Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas etc.) due to construction works; operation of concrete batch plants; sourcing, storage and transport of construction materials, and	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>other project-related activities.</p> <p>(ii) Wherever possible, use electrically powered equipment rather than gas or diesel-powered equipment.</p> <p>(iii) Position any stationary emission sources (e.g., portable diesel generators, compressors, etc.) as far as is practical from sensitive receptors;</p> <p>(iv) Use only vehicles and equipment that are registered and have necessary permits.</p> <p>(v) Burning of wastes generated at the construction sites, work camps and other project-related activities shall be strictly prohibited.</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>(vi) Construction equipment and vehicles shall be well-maintained and shall meet NEQS emission standards.</p> <p>(vii) Specify the use of clean fuels such as ultra-low sulphur diesel in dump trucks and other heavy-duty diesel vehicles and/or equipment, in conjunction with the use of particulate trap control devices, as well as catalytic converters, to avoid excessive diesel emissions.</p> <p>(viii) Keep stockpiles moist and cover vehicles with tarpaulin sheets or other suitable materials to minimize dust emission and prevent spillage of materials (e.g., soil, cement, stone, sand,</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>aggregates, etc.).</p> <p>(ix) Provide temporary covers (e.g., tarpaulins, grass, etc.) on long term materials stockpiles.</p> <p>(x) Concrete mixing areas at the Depot site shall be located at least 300 m from the nearest residential area.</p> <p>(xi) Clean road surfaces of debris/spills from construction equipment and vehicles.</p> <p>(xii) Install temporary fencing or barriers around particularly dusty activities in vicinity of sensitive receivers.</p> <p>(xiii) Ensure availability of water trucks on site and if the works surface and access roads near</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>sensitive receptors (i.e., residential areas, roadside tea and food stalls, and other sensitive receptors) are dry and dusty, spray water on the exposed surfaces to reduce dust emission.</p> <p>(xiv) All construction equipment and machinery shall be fitted with emission control equipment in full compliance with the national regulations.</p> <p>(xv) Fuel-efficient and well-maintained haulage trucks will be used to minimize exhaust emissions. Smoke belching vehicles and equipment shall not be allowed and shall be removed from the project.</p> <p>(xvi) Impose speed limits on construction vehicles to</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>minimize road dust in areas where sensitive receptors are located.</p> <p>(xvii) Locations for stockpiling material at the depot area will be at least 100 m from the nearest residential sensitive receivers.</p> <p>(xviii) Undertake immediate repairs of any malfunctioning construction vehicles and equipment.</p> <p>(xix) Discourage idling of engines.</p> <p>(xx) Provide prior notification to the community on schedule of construction activities.</p> <p>(xxi) Implement community complaints hotline.</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Noise	To ensure noise levels do not exceed permissible NEQS/IFC limits and do not create a nuisance for sensitive receptors in project area.	<p>(i) Before site works commence, a Noise Control Plan shall be prepared by the contractor and shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall provide details of mitigation measures, specific location and schedule where such measures shall be implemented to minimize impacts to sensitive receptors (residential areas, etc.) due to construction works, sourcing and transport of construction materials, and other project-related activities.</p> <p>(ii) All construction equipment and vehicles shall be well maintained, regularly inspected for</p>	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>noise emissions, and shall be fitted with appropriate noise suppression equipment consistent with applicable national and local regulations.</p> <p>(iii) Use only vehicles and equipment that are registered and have necessary permits.</p> <p>(iv) No noisy construction-related activities near sensitive receptors (such as residential areas, etc.) will be carried out during the night. Such activities shall be restricted to daylight hours.</p> <p>(v) Truck drivers and equipment operators shall minimize the use of horns.</p> <p>(vi) Impose speed limits on construction vehicles to minimize noise emission</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>along areas where sensitive receptors are located (houses, etc.).</p> <p>(vii) Provide temporary noise barriers (3-5 meter high barrier can reduce 5-10 dB(A), as necessary, if depot works will generate high noise levels that could disturb nearby households and other sensitive receptors.</p> <p>(viii) As much as possible, use quiet equipment and working method.</p> <p>(ix) Whenever possible, completely enclose noisy equipment which can reduce noise level by 15-25 dB(A), restrict use of noisy equipment (e.g. 15 min for every consecutive 30 min period) and undertake sequential operation of equipment</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>with objective to reduce noise generated;</p> <p>(x) Provide prior notification to the community on schedule of construction activities.</p> <p>(xi) Implement community complaints hotline.</p>				
Solid Waste	To ensure all solid waste generated during construction activity is disposed of in accordance with applicable local/international best practices.	<p>(i) Provide garbage bins and facilities within the project site for temporary storage of construction waste and domestic solid waste.</p> <p>(ii) Separate solid waste into hazardous, non-hazardous and reusable waste streams and store temporarily on site in secure facilities with weatherproof flooring and roofing, security fencing and access control and drainage/ wastewater</p>	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>collection systems.</p> <p>(iii) Ensure that wastes are not haphazardly dumped within the project site and adjacent areas.</p> <p>(iv) Undertake regular collection and disposal of wastes to sites approved by local authorities.</p>				
Damage to Community Facilities	To ensure the construction activity does not affect the community facilities in the project area.	<p>(i) The contractor shall immediately repair any damage caused by the Project to properties (e.g., houses, other types of structures, etc.), community facilities such as water supply, power supply, communication facilities etc.</p> <p>(ii) Access roads damaged during transport of construction materials and other project-related activities shall be</p>	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		reinstated upon completion of construction works.				
Traffic Concerns	To ensure the traffic is managed efficiently and does not create issues for the receptors in the project area.	(i) Before site works commence, a Traffic Management Plan for the construction phase shall be reviewed by construction supervision consultant (CSC) prior to approval by ADB. The plan shall be designed to ensure that traffic congestion due to construction activities and movement of construction vehicles, haulage trucks, and equipment is minimized. The plan shall be prepared in consultation with local traffic officials and people's committees at the district and commune levels. The plan shall identify traffic diversion	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and management, transport mode for spoils disposal (e.g., truck, truck and barge, etc.), traffic schedules, traffic arrangements showing all detours, necessary barricades, warning/advisory signs, road signs, lighting, and other provisions to ensure that adequate and safe access is provided to motorists in the affected areas.</p> <p>(ii) Post traffic advisory signs (to minimize traffic build-up) in coordination with local authorities</p> <p>(iii) As much as possible, schedule delivery of construction materials and equipment during non-peak hours.</p> <p>(iv) Regularly monitor</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		traffic conditions along access roads to ensure that project vehicles are not causing congestion.				
Health and Safety of Workers and Public	To ensure the project construction does not adversely impact on the health and safety of workers and public.	<p>(i) Prior to commencement of site works, the Occupational and Community Health and Safety Plan and Emergency Response Plan must be implemented when required.</p> <p>(ii) Appoint an environment, health and safety manager to look after implementation of required environmental mitigation measures, and to ensure that health and safety precautions are strictly implemented for the protection of workers</p>	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and the general public in the vicinity of construction areas.</p> <p>(iii) Conduct orientation for construction workers regarding health and safety measures, emergency response in case of accidents, fire, etc., and prevention of HIV/AIDS and other related diseases.</p> <p>(iv) Provide first aid facilities that are readily accessible by workers.</p> <p>(v) Provide fire-fighting equipment at the work areas, as appropriate, and at construction camps.</p> <p>(vi) Provide adequate drainage in workers</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>camps to prevent water logging/accumulation of stagnant water and formation of breeding sites for mosquitoes.</p> <p>(vii) Provide adequate housing for all workers at the construction camps.</p> <p>(viii) Provide reliable supply of potable water.</p> <p>(ix) Provide separate hygienic sanitation facilities/toilets and bathing areas with sufficient water supply for male and female workers.</p> <p>(x) Ensure that all wastewater emanating from worker camps, construction camps</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and other project-related activities and facilities are treated consistent with national regulations.</p> <p>(xi) Establish clean canteen/rest area.</p> <p>(xii) Ensure proper collection and disposal of solid wastes within the construction camps consistent with local regulations.</p> <p>(xiii) Provide fencing on all areas of excavation greater than 2 m deep.</p> <p>(xiv) Provide appropriate personnel safety equipment such as safety boots, helmets, gloves, protective clothes, breathing mask, goggles, and</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>ear protection.</p> <p>(xv) Ensure reversing signals are installed on all construction vehicles.</p> <p>(xvi) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit construction workers.</p> <p>(xvii) Implement fall prevention and protection measures whenever a worker is exposed to the hazard of falling more than two meters, falling into operating machinery or through an opening in a work surface. Based on a case specific basis, fall</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>prevention/protection measures may include installation of guardrails with mid-rails and toe boards at the edge of any fall hazard area, proper use of ladders and scaffolds by trained employees, use of fall prevention devices, including safety belt and lanyard travel limiting devices to prevent access to fall hazard, fall protection devices such as full body harnesses, etc.</p> <p>To ensure public safety:</p> <p>(i) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit people,</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>vehicles and properties in adjoining areas.</p> <p>(ii) Fencing of construction sites and regular patrols to restrict public access.</p> <p>(iii) Prior to excavation work, provide fencing on all sides of areas to be excavated.</p> <p>(iv) Provide warning signs at the periphery of the construction site.</p> <p>(v) Strictly impose speed limits along residential areas and where other sensitive receptors are located.</p> <p>(vi) Educate drivers on safe driving practices to minimize accidents and to prevent spill of</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		hazardous substances and other construction materials during transport.				
Social Conflicts	To ensure social conflicts are prevented from arising due to project construction.	(i) Consider the location of construction camps away from communities in order to avoid social conflict in using resources and basic amenities such as water supply. (ii) Maximize number of local people employed in construction works. (iii) Maximize goods and services sourced from local commercial enterprises.	During Construction	At each location for development of the Bus Depot.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC
Operation Stage						
Soil Contamination/ Hazardous	To ensure soil contamination does not take place due to the	(i) Wastewater shall be treated at the depot's treatment plant to	During BRT Operation	At each location for development of the Bus Depot.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Substances	project construction activity.	<p>ensure that relevant NEQS standards and requirements are met.</p> <p>(ii) In the vehicle washing, maintenance area and wheel lathe pits, drains shall be linked to the water treatment plant.</p> <p>(iii) Drainage emanating from the depot workshops will be equipped with oil interceptors. Oil-drip pans shall be used where appropriate to avoid contamination of the environment.</p> <p>(iv) Office buildings shall be provided with toilets and septic tanks or drain to sewers to handle domestic sewage.</p> <p>(v) The sewer system will</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>be designed to prevent leakage or overflow of waste water that could contaminate the surrounding areas.</p> <p>(vi) All hazardous and potentially contaminating materials (chemicals, fuels, oils, etc.) and equipment that contain hazardous substances shall be stored in facilities with weatherproof flooring and roofing, security fencing and access control and drainage/wastewater collection systems.</p> <p>(vii) PCB-containing equipment shall not be used.</p> <p>(viii) Leaks shall be repaired immediately</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and waste oil shall be stored and disposed of consistent with applicable laws and regulations.</p> <p>(ix) Diesel generators shall be placed on concrete floors with embankment.</p> <p>(x) There shall be provisions for concrete-lined transformer bays as well as drainage and oil-water separator to handle spills, leaks and oily water run-off that could emanate from the transformers.</p> <p>(xi) Ensure availability of spill clean-up materials (e.g., absorbent pads, etc.) specifically designed for petroleum products and other</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>hazardous substances where such materials are being stored and used.</p> <p>(xii) A groundwater quality monitoring program shall be implemented to ensure that groundwater for domestic purposes are adequately treated to meet applicable NEQS standards (based on the monitoring results).</p>				
Air Quality	To minimize air emissions effectively and avoid complaints due to the airborne particulate matter released to the atmosphere	<ol style="list-style-type: none"> 1. To minimize odor generation, wastewater treatment facilities shall be properly maintained and solid wastes regularly removed from the depot area to disposal sites approved by local authorities. 2. Burning of waste materials shall be 	During BRT Operation	At each location for development of the Bus Depot.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>prohibited.</p> <p>3. Idling of vehicles minimized.</p> <p>4. Back-up diesel generators to be used during power interruptions and shall be maintained regularly to ensure emissions comply with NEQS standards.</p>				
Noise	To ensure noise levels do not exceed permissible NEQS/IFC limits and do not create a nuisance for sensitive receptors in project area.	<p>1. Noise mitigation measures (e.g., enclosure) shall be provided for the back-up diesel generator(s) to ensure that high noise levels will not impact on surrounding sensitive receptors. While the noise levels are not expected to cause nuisance to the local community, noise monitoring will continue</p>	During BRT Operation	At each location for development of the Bus Depot.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		during the operation to determine and provide noise abatement measures, if necessary. Noise sampling shall also be conducted in response to complaints.				
Solid Waste	To ensure all solid waste generated during BRT operation is disposed of in accordance with applicable local/international best practices.	(i) Offices, workshops and other areas within the depot shall be provided with waste collection bins or receptacles. (ii) Solid wastes shall be segregated into hazardous, non-hazardous and reusable waste streams and stored temporarily on site in secure facilities with weatherproof flooring and roofing, security fencing and access control and drainage/wastewater	During BRT Operation	At each location for development of the Bus Depot.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>collection systems.</p> <p>(iii) Garbage shall be regularly collected and shall be disposed consistent with local regulations.</p> <p>(iv) Wastes shall only be disposed of in approved sites by local authorities.</p>				
Health and Safety of Workers and Public	To ensure the project construction does not adversely impact on the health and safety of workers and public.	<p>(i) Prior to operation of the depot, PDA shall ensure that the following plans have been developed and adequately resourced. PDA shall ensure that plan provisions are strictly implemented throughout operation phase:</p> <ul style="list-style-type: none"> Occupational Health and Safety Plan 	During BRT Operation	At each location for development of the Bus Depot.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<ul style="list-style-type: none"> Emergency Response Plan <p>(ii) The depot site will be fenced and access will be restricted to authorized personnel to avoid safety risks to the public.</p>				
ELEVATED SECTIONS						
Construction Stage						
Disruption to Community Utilities	To ensure the community utilities in the project area are not disrupted due to the project construction activity.	<p>i) Water supply pipelines, power supply, communication lines and other utilities shall be re-provisioned before construction works commence.</p> <p>ii) Provisions shall be made to preserve the operation of current facilities in sufficient quantity and in agreement with the local</p>	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>community.</p> <p>iii) Re-provisioning shall be undertaken in coordination with the utility company.</p> <p>iv) Affected households and establishments shall be notified well in advance of such disruption.</p>				
Spoils Generation	To ensure spoils generated during the construction activity is disposed off in accordance with applicable local and international legislation.	<p>(i) Meet the same measures as prescribed for the underground/ tunnel spoils under the Spoils Disposal Plan.</p> <p>(ii) All asphalt and sidewalk materials removed should be separated and recycled.</p> <p>(iii) Spoil disposal will only be to pre-approved areas.</p>	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>(iv) The capacity of disposal sites shall be adequate to accept the quantity of spoils without alienating areas outside the site boundaries.</p> <p>(v) Disposal of contaminated spoils shall only be to disposal sites equipped and licensed to handle such wastes.</p> <p>(vi) Trucks transporting spoils shall be tightly covered with tarpaulin or other suitable materials to minimize dust emission and spills.</p> <p>(vii) Load-out areas shall be cleaned and watered to ensure no accumulated dust originates that could be</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>dispersed to surrounding areas.</p> <p>(viii) Wheel washing shall be undertaken to remove mud so as to ensure that access roads are kept clean.</p> <p>(ix) Road surfaces shall be regularly cleaned of spilled spoils;</p> <p>(x) Spoil disposal shall not cause sedimentation and obstruction of flow of watercourses, damage to agricultural land and densely vegetated areas.</p>				
Drainage/Flooding	To ensure the occurrence of flooding does not affect the project construction activity.	(i) Placement of construction materials, excavated spoils and equipment shall not block flow of rainwater into canals/drainage	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>structures.</p> <p>(ii) Prohibit disposal of waste materials to drainage channels.</p> <p>(iii) Regularly inspect and maintain all drainage channels in the vicinity of construction sites to keep these free from obstructions.</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Air Quality	To minimize air emissions effectively and avoid complaints due to the airborne particulate matter released to the atmosphere	<p>Best management practices shall be adopted during construction to minimize dust and combustion exhaust emissions consisting of:</p> <ul style="list-style-type: none"> (i) Burning of waste materials shall be prohibited. (ii) Idling of vehicles minimized. (iii) Back-up diesel generators to be used during power interruptions and shall be maintained regularly to ensure emissions comply with NEQS standards. 	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC
Noise	To ensure noise levels do not exceed permissible NEQS/IFC limits and do not create a nuisance for	(i) Noise Control Plan shall be prepared by the contractor and implemented.	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	sensitive receptors in project area.	<p>(ii) Unobtrusive noise barriers near sensitive areas such as residential areas, etc. can also be placed on the edge of the right-of-way should construction monitoring indicate an impact to sensitive receivers. Temporary noise barriers (3-5 meter high) can reduce noise level by 5-10 dB(A).</p> <p>(iii) Diesel hammer piling shall be limited in favor of drill piling.</p> <p>(iv) Truck drivers and equipment operators shall minimize the use of horns.</p> <p>(v) Position any stationary equipment that produce high noise levels (e.g., portable diesel</p>			activities.	

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>generators, compressors, etc.) as far as is practical from sensitive receptors;</p> <p>(vi) All construction equipment and vehicles shall be well maintained, regularly inspected for noise emissions, and shall be fitted with appropriate noise suppression equipment consistent with applicable national and local regulations.</p> <p>(vii) Use only vehicles and equipment that are registered and have necessary permits.</p> <p>(viii) No noisy construction-related activities will be carried out during the night near sensitive receptors (e.g., residential areas).</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>Such activities shall be restricted to daylight hours.</p> <p>(ix) Impose speed limits on construction vehicles to minimize noise emission along areas where sensitive receptors are located (residential areas, etc.).</p> <p>(x) As much as possible, use quiet equipment and working method.</p> <p>(xi) Whenever possible, completely enclose noisy equipment which can reduce noise level by 15-25 dB(A), restrict use of noisy equipment (e.g. 15 min for every consecutive 30 min period) and undertake sequential operation of equipment with objective to reduce</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>noise generated;</p> <p>(xii) Provide prior notification to the community on schedule of construction activities.</p> <p>(xiii) Implement community complaints hotline.</p>				
Vibration	To ensure vibration effects resulting from use of construction equipment does not cause damage to infrastructure in project area.	<p>(i) Tracked cranes will be used to lift pre-cast sections of the columns.</p> <p>(ii) Equipment will also not be operating at night</p> <p>(iii) Monitoring at sensitive receiver sites will be carried out.</p>	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC
Use of hazardous substances	To ensure hazardous and toxic substances are disposed off in accordance with applicable local and	(i) Before site works commence, a Spill Management Plan shall be prepared by the contractor and	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	international regulations.	<p>implemented, if required.</p> <p>(ii) Store fuel and hazardous substances in paved areas with embankment. If spills or leaks do occur, undertake immediate clean up.</p> <p>(iii) Ensure availability of spill clean-up materials (e.g., absorbent pads, etc.) specifically designed for petroleum products and other hazardous substances where such materials are being stored and used.</p> <p>(iv) Train relevant construction personnel in handling of fuels and spill control procedures.</p> <p>(v) Ensure all storage</p>			activities.	

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>containers are in good condition with proper labeling.</p> <p>(vi) Regularly check containers for leakage and undertake necessary repair or replacement.</p> <p>(vii) Store hazardous materials above flood level.</p> <p>(viii) Equipment maintenance areas shall be provided with drainage leading to an oil-water separator that will be regularly skimmed of oil and maintained to ensure efficiency. Discharge of oil contaminated water shall be prohibited.</p> <p>(ix) Store waste oil, used lubricant and other</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		hazardous wastes in tightly sealed containers to avoid contamination of soil and water resources. Transport and off-site disposal of such wastes shall be consistent with national and local regulations.				
Solid Waste	To ensure all solid waste generated during BRT construction is disposed of in accordance with applicable local/international best practices.	<p>(i) Waste collection bins or receptacles shall be provided in various areas at the elevated stations, such as offices and areas accessed by passengers.</p> <p>(ii) Garbage shall be regularly collected and shall be disposed consistent with local regulations.</p>	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC
Damage to Community Facilities	To ensure the construction activity does not affect the	(i) The contractor shall immediately repair any damage caused by the	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
	community facilities in the project area.	<p>Project to properties (e.g., houses, other types of structures, etc.), community facilities such as water supply, power supply, communication facilities etc.</p> <p>(ii) Access roads damaged during transport of construction materials and other project-related activities shall be reinstated upon completion of construction works.</p>			standards. CSC to supervise activities.	
Traffic Concerns	To ensure the traffic is managed efficiently and does not create issues for the receptors in the project area.	<p>(i) Before site works commence, a Traffic Management Plan for the construction phase shall be reviewed and implemented when required.</p> <p>(ii) Provide signs advising road users that construction is in</p>	During Construction	At each elevated section location project site.	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>progress and that the road narrows to one lane using cones.</p> <p>(iii) Employ flag persons to control traffic at the work sites for safety reasons when construction equipment is entering or leaving the work area.</p> <p>(iv) Lanes shall be created through the work site using rope or flagging to minimize risks and injuries from falling objects.</p> <p>(v) As much as possible, lifting and placing of the pre-cast pillar sections will be done at night to minimize traffic congestion.</p> <p>(vi) Post traffic advisory signs (to minimize traffic build-up) in coordination</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>with local authorities.</p> <p>(vii) Provide road signs indicating the lane is closed 500 m before the worksite.</p> <p>(viii) Use traffic cones to direct traffic to move to the open lane.</p> <p>(ix) Provide sufficient lighting at night within and in the vicinity of construction sites.</p> <p>(x) Regularly monitor traffic conditions along access roads to ensure that project vehicles are not causing congestion.</p> <p>(xi) Define and observe schedules for different types of construction traffic trips (e.g., transport of pre-cast sections, haulage of</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>spoils, delivery of construction materials, etc.).</p> <p>(xii) As much as possible, schedule delivery of construction materials and equipment as well as transport of spoils during non-peak hours.</p> <p>(xiii) Avoid movements of noisy vehicles during night time in vicinity of sensitive receivers.</p> <p>(xiv) Implement suitable safety measures to minimize risk of adverse interactions between construction works and traffic flows through provision of temporary signals or flag controls, adequate lighting, fencing, signage and road diversions.</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>(xv) Ensure relocation of any affected public transport infrastructure (but stops, shelters etc.) prior to commencement of works</p> <p>(xvi) Provide advance notification to the community regarding changes to public transport facilities or routes.</p> <p>(xvii) Schedule construction works to minimize extent of activity along linear construction site at any one time.</p> <p>(xviii) Comply with traffic regulations and avoid, where possible, roads with the highest traffic volumes, high density of sensitive receivers or capacity constraints are</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>not used as access to and from the construction areas and spoils disposal sites.</p> <p>(xix) Install temporary accesses to properties affected by disruption to their permanent accesses.</p> <p>(xx) Reinstate good quality permanent accesses following completion of construction.</p>				
Operation Related Impacts						
Wastewater	To ensure only wastewater meeting the NEQS standards is discharged into the environment.	Drainage from the pillars will be carried through pipes and drain internally to the city storm water system. The elevated station shall be provided with toilets and septic tanks to handle sewage generated by workers and passengers.	During BRT Operation	At each elevated section of BRT.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Solid Waste	To ensure all solid waste generated during BRT operation is disposed of in accordance with applicable local/international best practices.	(i) Waste collection bins or receptacles shall be provided in various areas at the elevated stations, such as offices and areas accessed by passengers. (ii) Garbage shall be regularly collected and shall be disposed consistent with local regulations.	During BRT Operation	At each elevated section of BRT.	O&M Contractor	PDA
Tunnels & Underground Sections						
Construction Phase						
Disruption to Community Utilities	To ensure the construction activity does not affect the community utilities in the project area.	i) Water supply pipelines, power supply, communication lines and other utilities shall be re-provisioned before construction works commence. ii) Provisions shall be made to preserve the operation of current	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>facilities in sufficient quantity and in agreement with the local community.</p> <p>iii) Re-provisioning shall be undertaken in coordination with the utility company.</p> <p>iv) Affected households and establishments shall be notified well in advance of such disruption.</p>				
Spoils Generation	To ensure spoils generated during the construction activity is disposed off in accordance with applicable local and international legislation.	<p>(i) Before site works commence, a Spoils Disposal Plan (SDP) shall be prepared by the contractor.</p> <p>(ii) All asphalt and sidewalk materials removed should be separated and recycled.</p>	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>(iii) Spoil disposal will only be to PDA approved areas.</p> <p>(iv) The capacity of disposal sites shall be adequate to accept the quantity of spoils without alienating areas outside the site boundaries.</p> <p>(v) Undertake random sampling of spoils from underground station excavations and tunneling to determine presence of contaminants. If levels of contaminants exceed standards, excavation spoils shall be considered as hazardous wastes consistent with applicable standards/guidelines and shall be treated</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and disposed of as such.</p> <p>(vi) Disposal of contaminated/hazardous spoils shall only be to disposal sites equipped and licensed to handle such wastes.</p> <p>(vii) Determine water content of spoils to ascertain if spoils dewatering is necessary.</p> <p>(viii) Undertake necessary spoils dewatering and provide adequate treatment facilities to ensure that resulting wastewater meets NEQS standards. Adequate treatment should also be undertaken for groundwater drained from the excavated</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>areas to ensure compliance with NEQS standards.</p> <p>(ix) Stockpiling of spoils shall not be undertaken due to the limited footprint of the construction site. Spoils shall be trucked away immediately to approved temporary or final disposal sites.</p> <p>(x) Should any small stockpiles be developed, these shall be covered by plastic sheeting.</p> <p>(xi) Trucks transporting spoils shall be tightly covered with tarpaulin or other suitable materials to minimize dust emission and spills. Wet spoils shall be transported using</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>covered water-tight trucks to avoid spillage and drips onto access roads.</p> <p>(xii) Load-out areas shall be cleaned and watered to ensure no accumulated dust originates that could be dispersed to surrounding areas.</p> <p>(xiii) Wheel washing shall be undertaken to remove mud so as to ensure that access roads are kept clean.</p> <p>(xiv) Road surfaces shall be regularly cleaned of spilled spoils.</p> <p>(xv) Spoil disposal shall not cause sedimentation and obstruction of flow to agricultural land,</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		properties, and densely vegetated areas.				
Land Subsidence/ Geotechnical hazards	To ensure geotechnical stability at project sites is ensured prior to commencement of construction activity.	<p>(i) Undertake detailed geological investigation to determine geotechnical hazards along the Project's impact zone. Implement suitable precautionary and protection measures to avoid or minimize hazards.</p> <p>(ii) Select the best construction methods for retaining wall to ensure the stability of the deep excavation.</p> <p>(iii) Implement survey program to monitor the background subsidence rate along the project alignment.</p> <p>(iv) Conduct careful monitoring of the</p>	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>groundwater level, amount of settlement, tilt of buildings, and any building damages.</p> <p>(v) Depending on the results of subsidence monitoring program, develop and implement suitable mitigation measures to avoid or minimize damage to properties.</p> <p>(vi) Establish an emergency action plan for geotechnical hazards including a set of criteria for issuing warnings for such hazards.</p> <p>(vii) If necessary; carefully design, implement and monitor an appropriate dewatering program.</p> <p>(viii) Perform probe drilling ahead of the TBM cutting</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>surface at places where abrupt change of geological properties occur since such areas tend to have a higher risk of failure. Based on the results of probe drilling, implement appropriate precautionary measures.</p> <p>(ix) Undertake ground treatment underneath the deep excavation site if required.</p> <p>(x) The tunnel boring machine (TBM) contractor shall be required to operate within the following settlement parameters:</p> <p>Standard building: maximum settlement: 25 mm, maximum differential settlement: 11500 (this indicator is more important for damage), maximum</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>upheaval: 10 mm</p> <p>Particularly sensitive building to be identified: maximum settlement: 20 mm; maximum differential settlement: 11600, maximum upheaval: 10 mm</p> <p>Street and pavement: maximum settlement: 30 mm, maximum differential settlement: 11400, maximum upheaval: 10 mm. Select the best tunneling methods to minimize possible settlement during construction.</p>				
Flooding	To ensure the occurrence of flooding does not affect the project construction activity.	1. The contractor will be required to prepare a spoils disposal plan, which will include, among others, installation of adequate drainage facilities and flood	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>prevention measures.</p> <p>2. To prevent flush of soil into the channel during flood events, a retaining wall along the boundary is recommended.</p> <p>3. To avoid clogging of drainage and creating localized flooding:</p> <p>(i) Placement of construction materials, excavated spoils and equipment shall not block flow of rainwater into canals/drainage structures.</p> <p>(ii) Prohibit disposal of waste materials to drainage channels.</p> <p>(iii) Regularly inspect and maintain all drainage channels in the vicinity of construction sites to</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>keep these free from obstructions.</p> <p>(iv) Construct retaining walls along the spoils disposal boundary bordering the channels to prevent spoils from being flushed into the water courses during heavy rains and flood events.</p> <p>(v) At the disposal site, avoid formation of steep slopes to avoid soil materials from being eroded/washed out during rains and floods.</p>				
Air Quality	To minimize air emissions effectively and avoid complaints due to the airborne particulate matter released to the atmosphere	(i) Before site works commence, a Dust Control Plan shall be prepared by the contractor and implemented when required.	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>(ii) Wherever possible, use grid rather than generator set electrical power for construction equipment such as the tunnel boring machine and equipment to be used during cut-and-cover tunnel excavations.</p> <p>(iii) Position any stationary emission sources (e.g., portable diesel generators, compressors, etc.) as far as is practical from sensitive receptors;</p> <p>(iv) Use only vehicles and equipment that are registered and have necessary permits.</p> <p>(v) Burning of wastes generated at the construction sites, work camps and other project-</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>related activities shall be strictly prohibited.</p> <p>(vi) Construction equipment and vehicles shall be well-maintained and shall meet national NEQS emission standards.</p> <p>(vii) Trucks to be used for transporting excavation spoils shall be tightly covered</p> <p>(viii) Specify the use of clean fuels such as ultra-low sulphur diesel in dump trucks and other heavy-duty diesel vehicles and/or equipment, in conjunction with the use of particulate trap control devices, as well as catalytic converters, to avoid excessive diesel</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>emissions.</p> <p>(ix) Keep stockpiles moist and tightly cover vehicles with tarpaulin sheets or other suitable materials to minimize dust emission and prevent spillage of materials (e.g., soil, cement, stone, sand, aggregates, excavation spoils, etc.).</p> <p>(x) Provide temporary covers (e.g., tarpaulins, grass, etc.) on long term materials stockpiles.</p> <p>(xi) Store excavated materials outside road reserve, but where there is no area; spoils shall be loaded and transported immediately.</p> <p>(xii) Provide truck-washing facilities to prevent truck-</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>out of mud and dust onto city streets.</p> <p>(xiii) As much as possible, the casting yard for the Project will make use of already established and licensed site(s) for concrete forming activities where all the pre-cast sections will be fabricated.</p> <p>(xiv) Ensure that necessary environmental approvals are obtained for the establishment and operation of concrete batching plants and casting yards,</p> <p>(xv) Daily cleaning of road surfaces of debris/spills from construction equipment, haulage trucks and vehicles,</p> <p>(xvi) Install temporary</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>fencing or barriers around particularly dusty activities in vicinity of sensitive receivers</p> <p>(xvii) Ensure availability of water trucks or other dust suppressants and appropriate equipment for applying the suppressant (e.g., a tank truck with spray bars) on site and if the works surface and access roads near sensitive receptors (i.e., residential areas, roadside tea and food stalls, schools, hospitals and other sensitive receptors) are dry and dusty, spray water on the exposed surfaces to reduce dust emissions.</p> <p>(xviii) All construction equipment and machinery shall be fitted</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>with emission control equipment in full compliance with the national (NEQS) and local regulations.</p> <p>(xix) Fuel-efficient and well-maintained haulage trucks will be used to minimize exhaust emissions. Smoke belching vehicles and equipment shall not be allowed and shall be removed from the project.</p> <p>(xx) Impose speed limits on construction vehicles to minimize road dust in areas where sensitive receptors are located.</p> <p>(xxi) Undertake immediate repairs of any malfunctioning construction vehicles</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>and equipment.</p> <p>(xxii) Daily visual inspections to identify and address potential areas of dust and odor emissions.</p> <p>(xxiii) Discourage idling of engines.</p> <p>(xxiv) Provide prior notification to the community on schedule of construction activities.</p> <p>(xxv) Implement community complaints hotline.</p>				
Vibration	To ensure vibration effects resulting from use of construction equipment does not cause damage to infrastructure in project area.	(i) Erection of temporary walls around the underground station excavation sites and tunnel portal. Temporary noise barriers (3-5 meter high) can reduce noise level by 5-10 dB(A), using	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>daytime work schedules only,</p> <p>(ii) All construction equipment and vehicles shall be well maintained,</p> <p>(iii) Diesel hammer piling shall be limited in favor of churn drill piling.</p>				
Solid Waste	To ensure solid waste is disposed in accordance with local and international applicable best practices.	<p>(i) Provide garbage bins and facilities within the project site for temporary storage of construction waste and domestic solid waste.</p> <p>(ii) Separate solid waste into hazardous, non-hazardous and reusable waste streams and store temporarily on site in secure facilities with weatherproof flooring and roofing, security fencing and access</p>	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>control and drainage/ wastewater collection systems.</p> <p>(iii) Ensure that wastes are not haphazardly dumped within the project site and adjacent areas.</p> <p>(iv) Undertake regular collection and disposal of wastes to sites approved by local authorities.</p>				
Damage to Community Utilities	To ensure the construction activity does not affect the community facilities in the project area.	<p>(i) The contractor shall immediately repair any damage caused by the Project to properties (e.g., houses, other types of structures, etc.), community facilities such as water supply, power supply, communication facilities etc.</p> <p>(ii) Access roads damaged</p>	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		during transport of construction materials and other project-related activities shall be reinstated upon completion of construction works.				
Health and Safety of Workers and Public	To ensure the project construction does not adversely impact on the health and safety of workers and public.	<p>i. 'Occupational and Community Health and Safety Plan' and 'Emergency Response Plan' to be implemented when required.</p> <p>ii. Appoint an environment, health and safety manager to look after implementation of required environmental mitigation measures.</p> <p>iii. Conduct workshop for all workers on health, safety and environmental</p>	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>measures.</p> <p>iv. Provide first aid facilities that are readily accessible by workers.</p> <p>v. Provide fire-fighting equipment at the work areas, where appropriate, and at construction camps.</p> <p>vi. Provide adequate drainage in workers camps to prevent water logging and formation of breeding sites for mosquitoes.</p> <p>vii. Provide potable water, hygienic sanitation facilities/toilets with sufficient water supply</p> <p>viii.Ensure that all wastewater emanating from workers camps, construction camps and</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>other project-related activities and facilities are treated consistent with national regulations.</p> <p>(ix) Establish clean canteen/rest area.</p> <p>(x) Provide fencing on all areas of excavation greater than 2 m deep.</p> <p>(xi) Provide appropriate personnel safety equipment such as safety boots, helmets, gloves, protective clothes, breathing mask, goggles, and ear protection.</p> <p>(xii) Implement precautions to ensure that objects (e.g., equipment, tool, debris, precast sections, etc.) do not fall onto or hit</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		construction workers.				
Traffic Concerns	To ensure smooth and uninterrupted flow of traffic and to ensure safety during traffic movement in project area.	<p>i. Traffic management plan for implementation when required.</p> <p>(ii) Provide signs advising road users that construction is in progress and that the road narrows to one lane using cones.</p> <p>(iii) Employ flag persons to control traffic at the work sites for safety reasons when construction equipment is entering or leaving the work area.</p> <p>(iv) Lanes shall be created through the work site using rope or flagging to minimize risks and injuries from falling objects.</p>	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>(v) As much as possible, lifting and placing of the pre-cast pillar sections will be done at night to minimize traffic congestion.</p> <p>(vi) Post traffic advisory signs (to minimize traffic build-up) in coordination with local authorities.</p> <p>(vii) Provide road signs indicating the lane is closed 500 m before the worksite.</p> <p>(viii) Use traffic cones to direct traffic to move to the open lane.</p> <p>(ix) Provide sufficient lighting at night within and in the vicinity of construction sites.</p> <p>(x) Regularly monitor traffic</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>conditions along access roads to ensure that project vehicles are not causing congestion.</p> <p>(xi) Define and observe schedules for different types of construction traffic trips (e.g., transport of pre-cast sections, haulage of spoils, delivery of construction materials, etc.).</p> <p>(xii) As much as possible, schedule delivery of construction materials and equipment as well as transport of spoils during non-peak hours.</p> <p>(xiii) Avoid movements of noisy vehicles during night time in vicinity of sensitive receivers.</p> <p>(xiv) Implement suitable</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>safety measures to minimize risk of adverse interactions between construction works and traffic flows through provision of temporary signals or flag controls, adequate lighting, fencing, signage and road diversions.</p> <p>(xv) Ensure relocation of any affected public transport infrastructure (but stops, shelters etc.) prior to commencement of works</p> <p>(xvi) Provide advance notification to the community regarding changes to public transport facilities or routes.</p> <p>(xvii) Schedule construction works to</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>minimize extent of activity along linear construction site at any one time.</p> <p>(xviii) Comply with traffic regulations and avoid, where possible, roads with the highest traffic volumes, high density of sensitive receivers or capacity constraints are not used as access to and from the construction areas and spoils disposal sites.</p> <p>(xix) Install temporary accesses to properties affected by disruption to their permanent accesses.</p> <p>(xx) Reinstate good quality permanent accesses following completion of construction.</p>				

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
Cultural and Heritage Resources	To protect cultural and heritage resources in the project area.	'Chance Find' procedures shall be followed.	During Construction	At each tunnel & underground section project site	Contractor shall maintain acceptable standards. CSC to supervise activities.	PDA/CSC
Operation Related Impacts						
Flooding	To ensure the project operation is not affected due to flooding.	i. The underground tunnel sections will be provided with pumps to pump storm water. ii. A sill designed to meet annual and maximum flood height shall be constructed to protect the tunnel entrance from flood.	During BRT Operation	At each tunnel section of BRT.	O&M Contractor	PDA
Noise	To ensure noise levels do not exceed permissible NEQS/IFC limits and do not create a nuisance for sensitive receptors in project area.	i. Tunnel ventilation systems shall have suitable noise control measures incorporated into their design to reduce mechanical noise to acceptable levels in the	During BRT Operation	At each tunnel section of BRT.	O&M Contractor	PDA

Environmental Concern	Objectives	Mitigation Measures (MM) recommended	Timing to implement MM	Location to implement MM	Responsibility	
					Implementation	Monitoring
		<p>surrounding community.</p> <p>ii. Depending on the results of monitoring, installation of acoustical treatment to the first few meters (i.e., <15 m) of the tunnel portal could be implemented, if necessary.</p>				
Health and Safety of Workers and Public	To ensure the project construction does not adversely impact on the health and safety of workers and public.	<p>i. A system will be installed to ensure circulation of fresh air to meet both normal and emergency requirements.</p> <p>ii. Pumps will be installed in the tunnels to pump storm water and wastewater.</p>	During BRT Operation	At each tunnel section of BRT.	O&M Contractor	PDA

PDA Peshawar Development Authority
PD Project Director
CSC Construction Supervision Consultant
O&M Operation & Maintenance

8 Public Consultation and Information Disclosure

8.1 Introduction

516. Public participation and community consultation has been taken up as an integral part of environmental and social assessment process of the project. The public consultations have been conducted from 1st August'16 up to 5th January'17 in the entire project area. Consultation was used as a tool to inform and educate stakeholders about the proposed action both before and after the development decisions were made. It assisted in identification of the problems associated with the project as well as the needs of the population likely to be impacted.
517. This participatory process helped in reducing the public resistance to change and enabled the participation of the local people in the decision making process. Initial public consultations have been carried out in the project area with the objectives of minimizing probable adverse impacts of the project and to achieve speedy implementation of the project through bringing in awareness among the key stakeholders on the benefits of the project.
518. Public participation and consultation are the major keys to any success in infrastructure development. The sustainability of any infrastructure development depends on the participatory planning in which public consultation plays a major role.
519. To ensure peoples' participation in the planning phase of this project and to treat public consultation and participation as a continuous two way process, a number of consultations were arranged.
520. Aiming at promotion of public understanding and discussion on the local needs and concerns of the various stakeholders i.e., affected business persons, government officials, local community members and daily visitors to the project area, consultations were conducted through focus group discussions, individual interviews and formal consultations.
521. The consultation process was meant to ensure that all key stakeholders are informed, consulted and allowed to participate actively in the development process. This shall continue to be done throughout the project, both during preparation, implementation and monitoring of project results and impacts.
522. The environmental assessment process under the Pakistan Environmental Protection Act 1997, requires the disclosure to the public after the statutory IEE / EIA has been accepted by the relevant EPA, to be in strict adherence to the rules. In this EIA, the consultation process was performed to satisfy the ADB requirements (Social Safeguard Policy 2009).
523. The Land Acquisition and Resettlement Plan (LARP) for PBRT has been prepared by Consultants following the final preliminary design under Project Preparatory Technical Assistance of Asian Development Bank (ADB). The RP is fully

endorsed by Transport and Mass Transit Department, Government of Khyber Pakhtunkhwa (GoKPK). It focuses on the key activities of the project, which would cause involuntary resettlement impacts; and is prepared in accordance with ADB's Safeguards Policy Statement (SPS) 2009.

524. The LARP has been prepared based on a census (conducted from 9 Nov to 29 Dec 2016) of 100% potentially Displaced Persons (DPs) that are known at preliminary design stage; a socio-economic survey of 25% project Affected Households (AHs) conducted from 21 Dec 2016 to 5 Jan 2017; and consultations with DPs and other stakeholders. This LARP will be updated during the detailed design stage.

8.2 Objective of Consultations

525. The basic objective of the consultations is as follows:

- Understand views of affected key stakeholders and generate ideas regarding the expected demands of the affected parties;
- Disseminate information to the affected persons about the project in terms of its activities and scope of work; and understand the views and perceptions of the people affected and local communities with reference to acquisition of land or loss of property and its due compensation.
- Identify and assess major economic and social information and characteristics of the project area to enable effective social and resettlement planning and its implementation.
- Resolve issues related to impacts on community property and their relocation.
- Examine PAPs' opinions on health safety issues during the construction period on garbage materials, waste materials and other pollution issues.
- Identify levels and extent of community participation in project implementation and monitoring.
- Establish an understanding for identification of overall developmental goals and benefits of the project.
- Disseminate information to and develop a thorough coordination with different government, non-government and public private sector stakeholder line agencies ensuring their participation and mobilization of support in the process for the successful planning and implementation of the project.
- Assess the local people's willingness to get involved with the project; and enumerate the measures to be taken during the implementation of the project.

8.3 Identification of Main Stakeholders

526. The primary stakeholders identified are the residents in the project area along with displaced persons, owners of small businesses/traders in close proximity to the project corridor, health care facilities (hospitals, clinics etc.), educational institutions near the BRT corridor and the general public that visit the project area frequently for different purposes. All these stakeholders have different types of stakes according to their interests and professions.

8.4 Approach for Public Consultation

527. The approach adopted towards public participation was to disseminate information, solicit inputs and develop consensus on issues and subsequently propose mitigation measures. This approach was put into practice through consultation and public meetings with relevant public sector authorities and other key sensitive receptors, namely the local communities residing in proximity to the project, management officials of hospitals and educational institutions in the project area as well as roadside consultations with pedestrians etc.
528. The project related information was shared with all key stakeholders by engaging local Pashto (the native language spoken in the project area) speaking personnel who explained the project scope to the different stakeholders. In addition, during these consultations, detailed maps of the proposed project showing the project alignment were also used as a visual aid apart from verbally explaining in detail the activities to be conducted during the construction phase of the proposed project. Thus, through these detailed briefings, it was ensured that complete clarity was provided to the stakeholders regarding the possible environment related issues to be faced by the key receptors in the project area.
529. It is important to emphasize that the public consultation is a continual process that shall be conducted throughout the project development phase with different national and international project stakeholders being consulted and their respective comments and concerns being addressed through dialogue and discussion. These consultations shall continue during the project detailed design phase and shall be completed prior to review of this report for separate approvals from ADB and KPK EPA, with the finalized consultation findings incorporated into the last version of this report.

8.5 Consultations

530. A total of over 600 different stakeholders were consulted as a part of the consultation process with traders and business owners in the project area, residents along the project corridor, affected persons, senior management staff of health care and educational institutions, visitors to the project corridor on a daily basis as well as public sector representatives from different line departments.

Consultations with Women

531. It was ensured that consultations with different women groups were also conducted. Several cultural and economic obstacles exist for women's participation in public consultations and decision making; this is compounded by constraints on mobility and limited interaction. There is not a single woman found operating business on the PBRT corridor.
532. To conduct effective consultations separately with women, 2 female surveyors were engaged. The women were keenly interested in consultations and provided good information. These included females of AHs, student's teachers and other

working women as well as the daily commuters. Most of them belonged to poor affected households while road side consultations were conducted with female of lower middle class and middle class families. The women unanimously supported the PBRT Project by GoKPK and highlighted the following key aspects:

- Most of the women from AHs demanded sufficient resettlement assistance and rehabilitation of MEs and restoration of household income/livelihood due to PBRT related road works.
- The loss of income of their household due to the relocation of affected business enterprises (of their spouses) will have a negative effect on their normal socio-economic living conditions.
- Risk to safety and security for their children will be increased due to construction works.
- Separate waiting spaces for women at PBRT stations and separate compartments for women in PBRT buses.
- Dedicated buses for female during rush hours.

533. The concerns and issues raised by women and other stakeholders have been adequately considered in the design of the project and resettlement assistance and rehabilitation packages for the DPs.

Consultations with NGOs

534. SABAWON (Social Action Bureau for Assistance in Welfare and Organizational Networking) and South Asia Partnership–Pakistan (SAP-PK), are two major Peshawar based NGOs working for the creation of a society based on principles of social justice and gender equality. Both strive to contribute towards development of the local communities, with a focus on providing enabling environment to the marginalized and deprived groups to access and utilize social sector services.

535. The NGOs are in favour of efficient public transport system. However, they demanded sufficient and timely payment of compensation, full mitigation of social and environmental impacts, effective consultations and participation of stakeholder particularly displaced persons in resettlement and environment related activities of the PBRT Project.

The summary of the public consultations is provided in Table 8.1 below.

8.6 Key Concerns

536. The key comments and concerns raised as a result of the consultations are as follows:

- There is an overall positive sentiment with regards to the project development with the stakeholders expressing an urgent need for development of the project considering the traffic congestion issues faced by the residents of the city on a daily basis. The benefits from this project as expressed by the stakeholders consisted of faster, reliable, safer and cleaner mode of public transport, quicker and easy connectivity, stress free travel and minimal risk of accidents.
- The stakeholders requested the concerned authorities to ensure the project was completed on a fast track basis and hoped it would not suffer any delays.
- The senior management staff of the major hospitals and health care institutions present in the project corridor expressed the need to ensure an uninterrupted path for their ambulances would remain available at all times during the project construction.
- The respondents urged the relevant authorities to award the contract for the project through a transparent process and keeping in view the scale of this activity, they requested that a contractor with very sound reputation should be considered since local contractors tend to miss project deadlines and significantly delay project completion timelines.
- The need for efficient and detailed planning and development of a detailed traffic management plan prior to the commencement of the project construction was emphasized repeatedly since it was mentioned that the project route passes through certain highly congested areas.
- It was mentioned by different stakeholder groups that the Government focal agency needs to ensure high quality raw materials and techniques are employed in the project since the BRT route passes through the heart of Peshawar city and thus a high level of safety buffers need to be put in place in the design plans to prevent any civil structure failures, which could prove catastrophic.
- The stakeholders continued to stress the need for using all available measures to ensure the construction phase of the project would cause the least amount of difficulty to the everyday lives and routines of the sensitive receptors in the project area. Measures such as sprinkling of water for dust emission suppression, disallowing work at night times to control high noise levels and controlling speed of construction vehicles, particularly dumper trucks was requested.
- It was also mentioned that the relevant Government personnel must ensure the Contractor staff is cooperative with the general public and maintain the right attitude and try to facilitate them instead of being confrontational.
- The local traders and business owners in the project area mentioned that it must be ensured through efficient design of the BRT that their businesses are not affected and devaluation of the land on which their shops are constructed does not take place.

- The stakeholders also expressed the desire to receive regular updates on the project development from the relevant Government departments. In particular, the business owners and residents near the project area mentioned that they would appreciate some advance notice if any substantial activity was planned by the Contractor on a particular day that might cause an extraordinary disruption to their daily routines, thus enabling them to make necessary arrangements accordingly.
- The public sector representatives of the different line departments expressed their complete support and efforts towards the project development and mentioned the intent to ensure the project was completed at the earliest to the highest quality standards. In addition, these officials expressed the commitment to ensuring the Contractor selected for this project would adhere to all environmental and social compliance standards with no leniency in this regard to be expected from the relevant Government line departments.
- The public sector stakeholders also mentioned that this project was of high priority and its success needed to be ensured since it would prove a considerable opportunity to attract investors towards Peshawar and the KPK province.
- A number of visitors to the area mentioned that they are presently unemployed and are looking for employment and hoped a transparent hiring policy would be adopted for hiring of staff by the public sector line departments as well as by the Contractor.
- The residents of the project area requested that the line departments must ensure the Contractor works carefully during the construction activity to ensure minimal damage to the existing infrastructure. In case any damage does take place, such as bursting of water pipelines, damage to sewerage lines or damage to electricity transmission poles, repair work must be promptly conducted to minimize the nuisance resulting from the construction activity.
- The local traders as well as the residents in the project area also mentioned that the Contractor(s) must be urged to hire staff through proper background checks to minimize the chances of hiring staff with questionable character that might pose a threat of conducting indecent acts or engaging in criminal activities.
- The daily visitors to the project area requested the need to ensure the design of each BRT station consisted of escalators and/or elevators to enable access to the handicapped and elderly in order to enable them to also avail the benefits and convenience to be offered from this project.
- All stakeholders urged the relevant Government authorities to ensure the sustainability of the project and to hire qualified and polite staff for the positions of drivers, ticket issuers etc. in order to make the public feel welcome and want to avail the convenience being offered through this project.
- The stakeholders also requested that the relevant authorities should consider keeping the fare for using the BRT as low as possible to make it affordable

for the general public. It was also requested that a special discounted fare should be offered to students for using the BRT.

Table 8.1: Summary of Public Consultations

Date	Location	Type of Stakeholder	Objective	Participants		Opinion/Concern/Suggestion /Recommendation	Results/Actions to Address
				Male	Female		
1 Aug	BRT route Chamkani to Aman Chowk (left side)	General public and vendors residing along the BRT corridor	Introduce BRT and feedback on the project and potential impacts	17	5	BRT is a much-needed service as shared by male and female respondents. Female respondents shared incidences of harassment in public transport. Vendors shared fears about potential impacts on their businesses during construction phase and their displacement due to vacation of ROW. The owners and tenants of business structures requested to avoid impact on the commercial structures and dedicated parking facilities along the BRT corridor.	Impacts on structures were avoided to the maximum possible level during the Preliminary Design. The Gender Action Plan was developed for gender sensitive BRT operations. Impacts on vendors will be mitigated and a relocation strategy proposed for permanent vending spaces. A parking policy is requested to be developed by KPUMA, and parking facilities will be developed along BRT corridor.
2 Aug	Aman Chowk-Hayatabad (left side)	General public and vendors residing along the BRT corridor	Introduce BRT and feedback on the project and potential impacts	23	11		
3 Aug	Chamkani-Aman Chowk (right side)	General public and vendors residing along the BRT corridor	Introduce BRT and feedback on the project and potential impacts	16	19		
4 Aug	Aman Chowk-Hayatabad (right side)	General public and vendors residing along the BRT corridor	Introduce BRT and feedback on the project and potential impacts	9	11		
5 Aug	PDA Office	Project Implementing Department	Consultation meetings with PDA staff of different sections regarding the width of ROW, potential impacts of BRT due to encroachment	5		It was agreed that PDA technical staff was to accompany resettlement consultants for their orientation of the ROW and a GIS specialist was also present for on-site guidance.	PDA provided detail of width of ROW of BRT corridor and copies of ROW maps, and also conducted a joint field visit to BRT corridor and oriented resettlement consultants.

			s, to get detail of ROW and request for orientation of resettlement team about BRT corridor				
6 Aug	Sardar Garhi, site proposed for Western Bus Depot	Sardar Garhi land owners/ housing owners, small farmers, tenants of agriculture land and big landlord.	Focus Group Discussion to conduct consultations with male and female of housing owners, small farmers, land of larger land pieces to assess impact of land acquisition on difference categories of people	28	8	<p>The owners of housing structures showed serious concerns due to acquisition of their residential lands, and small farmers and tenants were found to be concerned about the loss of income due to their dependency on agriculture land for livelihood, fodder for animals and food for their families.</p> <p>Farmers/ tenants suggested that in case of land acquisition they should be properly compensated and jobs should be provided to their family members in the construction and operational phases BRT as an alternate source of income.</p>	Local population became aware of BRT, its potential impacts. More consultations were conducted with small farmers, non-titleholder tenants and land titleholders and the resettlement consultants got an idea of the extent of impacts on certain groups.
7 Aug	Sardar Garhi, site proposed for Western Bus Depot	Focus Group Discussion	<p>To take views/ opinions of the youth regarding BRT & depot site</p> <p>To know whether they are aware about the BRT project.</p> <p>To know where they will play in case of construction of BRT depot on their playing ground.</p>	60		<p>Local cricket players did not know about the BRT project.</p> <p>Local cricket players showed serious concern in case the playground taken for BRT depot site.</p>	<p>Resettlement consultants got familiarized with the large number of youth coming to Sardar Ghari & Hargoni land for playing cricket.</p> <p>Resettlement consultant briefed the local cricket players about the BRT project and also informed them about the land acquisition process.</p>
	Sardar Garhi,	Small farmers, owners of agriculture	Focus Group Discussion and conduct		-	The residents of a settlement of Sardar Garhi named Gujjar Garhi were extremely	Resettlement consultants

8 Aug	site proposed for Western Bus Depot	land, owners of housing structures and residents of Sardar Garhi	village mapping of Sardar Garhi to assess land use of Sardar Garhi, to identify lands with minimum impacts and free to encumbrances .	19		concerned on the acquisition of their residential land and were not willing to relocate themselves as they had housing compounds for animals in open space of their houses.	got an orientation of Sardar Garhi land use, and identified possible parcels of land for acquisition, for PBRT bus depot.
11 Aug	Saddar Bazar	Focus Group Discussion with Vendors of Sadar Bazar	Briefed the vendors about BRT project. Ma-de consultation with vendors regarding BRT project. Know the opinions of vendors & informed about census procedure.	30	0	The vendors shared their worries about dislocation. However, due to proper briefing by the lead surveyor about compensation, the vendors assured cooperation to survey team.	Vendors willingly gave information required for long-listing like CNIC number and contact numbers. Assured full support during conduction of vendors-census.
19 Aug	Chungi Chowk (Food Godowns) at Kohat Road	Vendors of Chungi Chowk (Food Godown) at Kohat Road	Focus Group Discussion to Briefed the vendors about BRT project & about staging station propose at food godowns site. Made consultation with vendors regarding BRT project. Know the opinions of vendors & informed about census procedure.	6	0	The vendors showed their worries about dislocation however, due to proper briefing by the lead surveyor about compensation vendors assured cooperation to survey team.	Vendors willingly gave information required for long-listing like CNIC number and contact numbers. Assured full support during conduction of vendors-census.
			Focus Group Discussion with title & non-titleholder-s & local elders Briefed the FGD participant-s about the BRT project. Briefed the			Prepared social map of the site with the help of FGD participants. Identification of title & non-title-holders was made with	Noted that both the title & non-titleholders were quite worried. Particularly the non-titleholders who are mostly doing subsistence farming and solely dependent on this land.

20 Aug	Sardar Ghari	Title & non-titleholder-s	participant-s about the social & resettlement study and its purpose/ objectives.	5		the help of FGD participants.	
23 Aug	Govt; Food Department	Staff of Govt Food Department, Chungi-Kohat Road, Peshawar	Meeting with Food Inspector (Zafran) and mapping of land use surrounded by godown.	3	-	Discussion over land proposed for BRT staging station. The team also took opinions about availability of space at godowns site, and the possible impacts the site would entail.	Found that land is free of encumbrances with no resettlement impacts
23 Aug	PDA	Several officers of PDA	Introductory meeting and consultations on the status of land proposed for staging station.	5	0	PDA endorsed the location for the staging station.	Food department stated that communication between Secretary Transport, other stakeholders and with higher officials from the Food Department was underway to agree upon the utilization of their land for staging station.
4 & 5 Oct	PDA	Director P&D, Assistant Director Roads and SDO Roads, Land Acquisition Collector, Tehsildar and Naib Tehsildar PDA Director Engineering, PDA design consultants of General Bus Stand.	Held meetings with relevant staff and PDA design consultant-s of General Bus Stand, to share sensitivities of local people about potential impacts on housing structures and explored ways to minimize impacts on local population.	9	1	PDA staff was concerned that it was not possible for them to avoid impacts on housing units as the Section-IV and V had been issued for a parcel of land for the general bus stand, whilst all the resettlement consultants were of the view that the notification of the sections had been issued for a broader area and demarcation was to be done under Section-VI.	Resettlement consultants decided not to propose the parcel of residential land of Gujjar Garhi for the construction of BRT bus depot and related infrastructure.
			To conduct consultations with local population of potentially affected villages and develop a consensus on the options of land for PBRT bus depot, to				

6 Oct	PDA & Project Affected persons	Resident-s of Sardar Ghari and Hargooni	minimize adverse impacts on socio-economic condition of affected population	44	0	AP did not agree on demolition of their houses, and agreed to the option of acquiring agriculture land for the construction of BRT bus depot.	Resettlement team was able to develop a consensus with the local population on acquisition of agriculture land for the bus depot.
7 Oct	Cantonment Board Office		Chief Executive Officer, Chief Engineer, Overseer and Draftsman of Cantonment Board for consultations on the use of roads in the cantonment area for the BRT route, detail of any encroachment on the BRT road lying in cantonment area, and to acquire detail of the ROW.	4	-	The cantonment board shared their concerns on the proposed initial design for the BRT in cantonment area. The team had to convey to them the engineering design and the consultants agreed to provide ROW detail of the BRT alignment lying in cantonment area.	Completed initial assessment of the availability of ROW for the construction of BRT.
13 Oct	Office of District Revenue Department	Additional Deputy Commissioner- Revenue-Land Acquisition, Land Acquisition Tehsildar, District Qanoong-o & relevant Girdawar	To enquire information about the nature of disputes and court cases on the land of Sardar Garhi and Hargoni Mouzas and take assistance of the Revenue Staff in case land is not disputed. Discussed and identified three options for BRT station in the acquired land.	8	-	The District Revenue Staff shared information about the proposed options of land to be acquired and agreed to pay joint visits to the proposed land.	It was mutually decided that both the teams were to jointly visit the site to verify physical location of the proposed parcels of land and issues related to each parcel/khasra number of land.
	Hashtnagri & Firdous	Shop-keepers	Focus Group Discussion to introduce BRT and feedback			Resettlement consultants introduced the BRT route. Got the opinion of shopkeeper-s in case of disruption of their businesses	Informed the shopkeepers for next joint consultation meeting with the lease owner of underpasses and representatives of both the

15 Oct	underpasses		on the project and potential impacts	36		temporarily. The shopkeepers were not ready for dislocation of their businesses as well as demolition of both the underpasses.	underpasses.
17 Oct	SW&WD Office Peshawar-FGDs	Government KP Social Welfare & Women Development Department Peshawar-Adeel Sb Additional Secretary KP SW&WD, Niaz Mihammed In charge Gender and Shguhfta Gender Specialist KP SW&WD Department & staff	Discussion on collecting sex & gender disaggregated data on women & transportation and women laborers and to understand the existing public transport for women & girls in Peshawar city.	5	3	<p>Due to limited resources SW&WD department did not conduct any study on working women/women working laborers and transport.</p> <p>Not only women and girls are facing problems while traveling in local buses and wagons, men and boys were also faced with a number of issues due to slow speed of buses, attitude of bus drivers and conductors.</p> <p>As women labor force, has increased over time, they need to have safe, secure and respectful public bus service.</p> <p>Women separate compartment need to be allocated so that they can travel without any hesitation.</p> <p>In PBRT 50% portion need to be fixed for women because the women who are now traveling in rickshaw and taxi will ride PBRT after its operation as women in Peshawar have been waiting for such kind of public transport.</p> <p>In case of safe, secure, comfortable, respectful and air-conditioned public bus service operation definitely women and girls' traveler's number will have increased in double.</p> <p>Women need to be involved at the planning and execution</p>	SW&WD KP department appreciated the PBRT project and cooperated with providing information.

						<p>phase.</p> <p>Besides PBRT there is need to start a public train system to fulfill the need of male, female, elderly & disabled travelers.</p> <p>As women spend more money on private transport, the PBRT operation they will save their money.</p>	
7 Nov	At the residence of Fazeel Khan	Land Owners of Hargoni Land	Conducted consultations with major land holders of Hagoni Land, proposed for the acquisition on the rates proposed by PDA.	2	-	<p>The land owners agreed to provide their lands for the construction of BRT bus depot, but not on the rates proposed by PDA, as the adjacent land of Sardar Garhi was calculated at 75% higher rate than Hargooni due to the average of last one year sale price, while the record of sale of Hargooni land is very old due to family disputes and court cases.</p>	<p>The land owners agreed to provide evidence of higher value of land, against a decision of the court regarding a case registered against the rates fixed for Hargoni land, under another project. Evidence of higher rates was later provided to the resettlement consultants</p>
9 Nov	Chamkani Bus Stop	Vendor s of Chamkani Bus stop	Focus Group Discussion to introduce BRT and feedback on the project and potential impacts	5		<p>The vendors shared their concern, said their business and their families would be affected.</p> <p>The resettlement consultant briefed about the compensation allowance upon which the vendors felt reassured. However, they had doubts about provision of compensation.</p>	<p>It was noted that although, the vendors were upset in view of their businesses dislocation, they felt satisfied with the compensation amount. However, they were not sure about receiving the compensation amount from the concerned department.</p>
11 Nov	Her Residence Chatty Lal Kurti, Peshawar Cantt (KII)	House Wife, of Chatty Lal Kurti, Peshawar Cantt-KIIs	To find out reasons why women of the area needed to travel and use public transport as a mode of travelling and issues that they faced.		1	<p>It was found that women majorly used public transport to visit schools, markets, hospitals and relatives. It was also found that although some women came from families that owned cars, they still travelled on local transport like auto-rickshaws and buses.</p> <p>Women stated that the existing public transport facilities were both time consuming and crowded and as they had mixed gender spaces, they had to face harassment. It was thus found that the existing public transport was not safe for</p>	

						women. Women found mornings and early evenings the best time for traveling. Female correspondents stated that 20 rupees per stop was affordable fare.	
14 Nov	Noor Center and Gull Center of Hashtnagri and Firdous Underpass	Potential Displaced Persons (Shopkeeper/business operators)	To conduct initial consultations on the possibility of demolition of the underpasses	26	-	The potential displaced persons were informed and their strong demand to save the underpasses from demolition was noted.	The representatives of different categories of interest groups were identified, their concerns helped to develop next steps for resettlement planning.
14 Nov	Firdous Bus Stop, Peshawar-FGD	<p>Potential Women PBRT Travelers</p> <p>Shumaila Zulfiqar, private school teacher, Gulbehar Colony Peshawar,</p> <p>Gul Bibi Afghan, housewife, Hayatabad & Razia from Chamkani housemaid in University Town (cleaning and washing clothes in 4 houses)</p>	To ask about the problems women face while travelling on public transport (bus or wagon)		3	<p>Women are stared at by the men waiting at the bus stops.</p> <p>Whilst getting on to the busses, men use the same door as female passengers, making the female passengers very uncomfortable.</p> <p>Men often sit on the seats that are allocated for women and refuse to vacate the seats so women have to stand and travel.</p> <p>It was found that a majority of the public bus drivers did not like women getting onto their busses and therefore did not stop the busses for them at the stops or refused to let them on.</p> <p>Women travelling on public busses often face extortion as they are charged higher fares by bus conductors and this often results in arguments.</p> <p>Young girls avoid sitting with the elder women as they inquire about their personal life and family. Also, it was reported that burqa clad women were also known to pick pockets and therefore that was another reason girls were comfortable in sitting in busses. Therefore, they were forced to take local busses as taxis and rickshaws were expensive.</p> <p>They hoped that Peshawar</p>	Initially the respondents were reluctant to respond but later gave information. As men standing at the bus stop were eavesdropping, the women initially were uncomfortable in engaging.

						<p>would be able to provide a bus service like Rawalpindi. One woman had a reservation over higher transit bus fees.</p> <p>Female respondents hoped that the female portion in the busses and the fares would be same as those of the Rawalpindi metro bus.</p> <p>They argued that after the PBRT, there would be no need to run separate female buses.</p>	
14 Nov	Peshawar Chamber of Commerce (PCC) & Women Chamber of Commerce (WCC), Peshawar-FDG	<p>Non-Government-Peshawar</p> <p>Iqbal Sb-President PCC,</p> <p>Haji Afzal – Chairman PCC, Additional Secretary General PCC & other members</p> <p>Shamama-Chairperson WCC, Shumela Secretary and staff</p>	<p>To understand the existing public transport services for women</p> <p>and to get information about women labor & women enterprise</p>	5	4	<p>As women face problems in travelling because of the existing public transport infrastructure, women labor force working in the industries prefer to work where they have facility of pick and drop.</p> <p>However, it was found that PBRT might not be able to benefit women working in industries but is expected to benefit women working in other public and private sector institutions, those running small businesses and those travelling to run errands and avail social services.</p> <p>It was recommended that the cheapest form of transport for Peshawar city would be the train system that previously operated in the city as it was expected to be affordable and would be able to cater to the needs of a larger group of people.</p> <p>It was also stated that female ticketing counters needed to be established and separate compartments for women needed to be ensured. The corridors were expected to cater to the needs of women, children, elders and disabled people.</p> <p>During construction, it was stated that there was a need to have a safe alternate traffic movement plan to</p>	Cooperative and shared information

						<p>avoid any problem.</p> <p>The government also needed to ensure an increased number of buses during the peak hours to cater to the increased demand.</p>	
16 Nov 2016	AHAN (AJK Hunar AJK Nagar/one skill)- Consultation	Semi-Government Company, Project Director, Program officer, Market Officer	To get information about their skill development program, get their views about existing public transport facilities for male and female travelers perspective and to get their opinion about BRT and request for assistance organizing a Focus Group Discussion with female of AHAN targeted community	3		<p>AHAB facilitate male & female craft persons, artisans and poor producer groups in accessing enterprise development services with focus on hand-crafted products.</p> <p>AHAN staff and female of their targeted communities appreciated BRT. They also demanded for the intra-city train as railway track is already available. Women demanded separate entrance, waiting areas and compartments (30 to 40 in buses) to avoid harassment they experienced public transport. They also proposed color coded compartments to assist people who cannot read. They also demanded connecting services to feeder roads and need for men and women security staff at bus stations. The need to employ women in BRT operations was also emphasized. Women stated that their access to education and employment would considerably increase.</p> <p>AHAN stated that although it had trained a number of women in different skills, they were unable to access to markets for raw materials and for marketing their products due to unfriendly transport services.</p>	Identification of potential company for livelihood program, and discussion helped in analysis of female travelling patterns, assessment of their travel needs, problems faced in existing public transport.
16 Nov 2016	Center of Excellence for Resource Development- FGD	NGO (Project Coordinator and M&E Officer)	To get their views on existing public transport from the perspective of women travelers and take their opinion about	5		<p>They shared how present public transport system impacted vulnerable groups and overall participation of women in social and economic development, restrictions on women mobility due to unsafe public transport, emphasized on the need of job opportunities for</p>	Helped in gender analysis of public transport and women specific needs.

			PBRT			women in BRT operations, demanded women specific facilities in BRT due to strict norms of Pakhtoon culture.	
17 Nov 2016	Office of UN Women, Peshawar-FGD	Staff of UN Agencies (UN Women, UNOPS, UNFPA) & Coffee International	To get their views on existing public transport from gender perspective and opinion about BRT	4	2	<p>The staff members stated that the environment concerns such as dust, noise pollution, restriction to public to access spaces and utilities should be taken care of by the GoKPK.</p> <p>The old intra-city train system should also be rebuilt, which can be operationalised with less money. A traffic management plan should be developed and implemented effectively during construction period.</p> <p>The BRT should be linked with pink buses for women. The GoKPK should relocate the shopkeepers of underpass markets in a way that their livelihood would not be affected.</p> <p>Security of passengers should be a priority in BRT operations.</p> <p>Women specific facilities should be provided in all aspects of BRT operations. BRT should be equipped with modern facilities separately for men and women i.e. waiting areas elevators, escalators, rest rooms, clean drinking water, and ramps for wheel chairs in buses.</p>	Actions laid down in the Gender Action Plan and Environment Management Plan, and LARP to address their suggestions.
17 Nov 2016	Sarhad Rural Support Program Office-FGD	Manager Program Operations, 2 Program Officers	Gender analysis of existing public transport, women travelling pattern and women specific needs for public transport, and opinion about PBRT	2	2	<p>The organization appreciated the PBRT project and stated it would provide safe and respectful transport to women and female students; enhance their access to educational institutions, health facilities, jobs and help in establishing their businesses.</p> <p>Shared issues faced by women in existing public transport facilities and its impact on women social and economic development. Recommended that 50% portion of buses should be specified for women travelers with separate compartments and entrances. In peak hours, number of buses should be</p>	Actions incorporated in Gender Action Plan against their suggestions.

						sufficient to accommodate men and women travelers. Need to offer subsidized fare to students and old citizens.	
17 Nov 2016	Khwendo Kor, Hayatabad-Peshawar-Consultations	NGO (Senior Program Manager HR, Community Program Officer.	To get their opinion on PBRT and help in studying travelling pattern of women labor force (home based workers & house maids)	-	2	<p>Shared issues faced by women in public transport i.e. harassment, personal safety, long waiting hours and travel time. A number of educated and skilled girls and women were unable to work due to insecure and inefficient public transport. Hence, it was proposed that women specific services should be provided that are to include separate access ways to bus stations, ticketing facility, entrance in buses, compartments etc. BRT is thus expected to impact on women access to education, health facilities, jobs and business opportunities. They also suggested 45% seats to be fixed for women. Emphasized on rehabilitation of rail track. Emphasized on the need for a good environment management plan to control dust, noise, traffic jams, and disruptions to public utilities and access. Special security arrangements should be made, a special security force to be hired and trained. A complaint mechanism should be developed and implemented to take public feedback on BRT operations and redressal problem face by women and other vulnerable groups. CCTV cameras to be installed at bus stations with emergency telephone facility. Women, young boys and girls face harassment from bus drivers, conductors and fellow male passengers. A substantial number of female housemaids, factory workers, home-based workers, living in old city and suburbs of Peshawar were found to face difficulties in accessing public transport. BRT will particularly benefit</p>	Actions lay down in GAP and EMP to address their concerns.

						these women and professional women who do jobs in public and private sector offices, health and educational institutions. Jobs should be created for women in BRT operations and women should also be trained as bus drivers. Women specific pink buses, funded by foreign grant, should also be operated by female drivers on BRT corridor.	
18 Nov	Office of Mohmand Construction Company, Peshawar	Lessee of Firdous & Hashtnagri underpass	To discuss the status of underpass lease and its terms and conditions.	4	-	<p>Mirza Khan showed concerns about loss of business by MCC and shopkeepers due to demolition of underpass markets, and suggested that GoKPK should provide shops at alternative locations, and lease period should be extended to cover the period for the establishment of businesses at new locations.</p> <p>It was agreed that resettlement team was to closely work with MCC and shopkeepers to develop the resettlement policy for PBRT Project.</p>	
18 Nov 2016	Shelton Guest House Peshawar-KII	Government-Police Department (Traffic)	To take opinion on security issues	1		<p>Although the PBRT was appreciated, it was affirmed that rehabilitation of train system as part of BRT was of importance. Two Police stations needed to be established on BRT route with a facility of female staff to facilitate male and female passengers on security issues and criminal activities i.e. theft.</p> <p>Trained security personnel need to be deputed at PBRT bus stations.</p>	Suggestion integrated in Gender Action Plan
21 Nov	Office of Special Secretary Industries-KPK Industries Department	Special Secretary and Additional Secretary Industrial Department, Economic Development Specialist.	To get segregated data of labor force in Peshawar and get tier views on BRT	4		<p>PBRT will change the travelling pattern in Peshawar especially for women.</p> <p>The number of women and girl passengers using public transport was expected to increase significantly.</p> <p>In BRT there should be women specific facilities, 30% seats should be fixed for women and strict security</p>	Provided useful suggestions and reference to contact relevant officials in TEVT and Labor Department to get gender disaggregated data of labor force in Peshawar.

						measures were needed for BRT i.e. CCTV cameras at bus stations and in buses.	
21 Nov	Labor Department-Stakeholders Consultation	Director, Director HR Labor, Deputy Director, Assistance Director and Labor Inspector	To take information about travelling pattern of women in the industrial workforce and get gender disaggregated data of labor force of industries in Peshawar.	4		<p>It was stated that BRT was not only expected to significantly increase the number of female travelers but also the male passengers particularly the middle class, who currently avoid public transport. 30% portion of PBRT need to be fix for women.</p> <p>They disclosed that women labor force working in industries of Hayatabad were compelled to use the buses provided by the factories and charges ranged from 3000 to 4000, as there is no direct public transport available and young women do not like to change buses, pay higher fares, waste time and face harassment from fellow male passengers and bus conductors. Women and girls also lost their precious belongings and money while traveling on the existing public transport.</p> <p>Recommended rest rooms, ticketing booth, entrance and compartments for women.</p> <p>Announcements were suggested to be announced in the buses to inform about bus stations. Need to install CCTV cameras and telephone at the bus stations. BRT should be extended to Karhaono Bazar.</p>	Provided required data
21 Nov 2016	Technical Education Vocational Training, Peshawar-Stakeholders Consultation	Director, HR Labor,	To get opinion about PBRT and get information about TEVT training program	3		<p>It was said that the start of the PBRT operation would see an increase in the number of travelers. Women and men compartment should be segregated, with separate entrances. Due to PBRT more labor force of men and women would be able to work in the industries and run businesses with ease. More buses will be needed in peak hours especially at morning time, mid-day and afternoon (after 4:30 pm).</p>	Provided information about their training program.

22 Nov 2016	Cantt Secretariat Labor Department-Stakeholders Consultations	Secretary Labor, Joint Secretary and Director	To discuss social and gender impact of BRT	5		BRT will increase women mobility. Should be separate portion for women with separate entrance. There should be strict security arrangement at bus stations. Women participation in labor force would increase.	
22 Nov 2016	University Town, Peshawar-KII	Electronic media	To take views on BRT	1		It was found that currently women and the transgender community faced a lot of harassment in public transport. Given the government was to provide women specific facilities at bus stations and separate compartment; women would be confident in travelling independently and therefore female travelers would increase. 30% portion of buses needs to be allocated for women and special safety measures to be ensured at bus stops and in buses. Train system of public transport needs to be revived.	
23 Nov 2016	Gulbahar Police Station Peshawar-Stakeholder Consultations	Male and female DSPs and IT Manager	To understand security issues in public transport	2	1	Appreciated BRT system. The major concern was that majority of women do not like travelling from public transport, they face harassment from the fellow male passengers and bus conductors. Security arrangements for BRT system were deemed to be very important and a well-equipped and trained security force needed to be formed for BRT. A camera control room also needed be established for 24 hours monitoring. Women travelers were expected to increase and thereby 30% portion of buses needs to fix for women. Morning time, mid-day (after 12:30 pm) and afternoon (after 4:30) were said to be the peak hours more busses needed to be ensured on the corridor. Emphasized for development of a traffic management plan during construction of PBRT corridor.	
	Main Bus Stand, City	Transporters, conductors &	To understand existing public	20		Transporters expressed their anger against new traffic	Provided required information expressed

23 Nov 2016	Peshawar- FDG	drivers of Peshawar Main Bus Stand	transporters perception about PBT To find and gauge the response of transport Unions and Owners etc. towards BRT and relevant results/reperc ussions. To get information about women mobility			<p>police system as they had been fined penalties of minimum of Rs 500 and maximum of Rs 1000.</p> <p>They stated that majorly poor women, female beggars, housemaids and women street vendors traveled on public buses whereas female students, women working for public and private jobs, running small enterprise/business and from the lower middle classes preferred to travel on wagons, and only travel on busses when seats aren't available. Women from affluent families prefer to travel on rickshaw or taxi.</p> <p>Transgender individuals travel on rickshaw or taxis as they are harassed by the fellow male passengers and women do not allow them to sit in their part.</p> <p>Buses commuting to the old Bara route have last seats for women, whereas in other buses the front 10 seats behind the bus driver are allocated for women during the peak hours. Other than peak hours' men also travel on these seats.</p> <p>Women often get into fights with the conductors on fare so conductors discourage them to ride on the bus.</p> <p>Buses only for women travelers have not been successful as women do not prefer to travel in these busses as stated by the Social welfare minister Sitara Ayaz.</p> <p>Upcoming PBRT will be not good news for the local bus drivers, conductors and owners as they will face losses as their buses will not be awarded any route. Therefore, it is expected that as soon as PBRT corridor's construction will start, the bus drivers will take steps to create hindrance in the PBRT</p>	they're not approving of the PBRT
-------------------	------------------	--	---	--	--	---	-----------------------------------

						<p>implementation process (as one owner commented that we will take stay order from the court if PBRT will start).</p> <p>Minimum fare at stop is 10 Rs in the buses and wagons and maximum fare is 30 Rs.</p> <p>Women running household chores travel after 10 am to 4:30 pm whereas women laborers, house maids, students and doing jobs often travel from 6:30 am to 9:00 am in morning and then come back at 4:30 pm to 5:00 pm. Students timings are from 6:30 am to 8:00am and 12:30 pm to 3:00 pm. After evening, there are few women (with their families) and mostly no women travel alone.</p> <p>According to them a lot of poor families will be affected due to closing of buses and wagons on PBRT route.</p> <p>They suggested alternates regarding provision of new vehicles (As Shahbaz Sharif did in Punjab), issuance of new permits, allocation of new routes where they can drive their bus as well as provision alternate jobs in PBRT for those affected.</p>	
23 Nov 2016	Peshawar Press Club, Near Cantt. Railway Station, Peshawar-FGD	Mass Media/ Newspaper Journalist of Khabrain Ms. Iffat Siddiqui, Journalist of Mashriq Muhammad Owais , Peshawar Press Club, Daily Wahdat Habib Syed, Daily Ummat Iqbal Afridi, Journalist of Geo News Mr. Rizwan Sheikh, Iqbal SB Roznama Umat	<p>To find their views on present public transport modes for women travelers</p> <p>To understand their opinion about PBRT project</p>	6	1	<p>Although female harassment is common in the existing public transport, men are also found to face harassment.</p> <p>Women seats are often occupied by men.</p> <p>Buses are in bad condition and not secure and are a threat to life.</p> <p>PBRT is always welcome but there is need to have separate women portion where no men would be allowed to enter. There is strong need to have effective security system on the corridor, at the bus station</p>	Provided required information and were found to be welcoming & cooperative but expressed their reservation regarding completion of the PBRT project.

						<p>and in the buses.</p> <p>PBRT will be very good for women and they will travel more as it would be safer as currently a large number of women avoid traveling on existing and available public transport in Peshawar city.</p> <p>PBRT will provide safe and secure public transport.</p> <p>Besides PBRT need to operate public train as did before also PBRT will not fulfill the requirement of all the travelers in Peshawar so better to restart the old GTS system that was the most successful.</p>	
24 Nov	University of Peshawar- FGD	<p>Government</p> <p>Chairman of Institute of development Studies- Agriculture University Peshawar</p> <p>Agriculture University</p> <p>Mr. Inayatullah Jan PhD IDS & his colleges Dr. Gohar Ayub Assoc. Prof Mr. Sohail PhD student and fellow teaching staff</p>	<p>To find their opinions on BRT</p> <p>To understand their views about existing public transport</p>	6		<p>The existing public transport service is not friendly for women and students.</p> <p>PBRT project will provided better transport to women and students.</p> <p>It will encourage more women work and girls to get higher education.</p> <p>Women should have separate compartment and entrance in PBRT and special security steps need to be undertaken by the project implementers and his co-stakeholders.</p> <p>BRT will be good not only for students but for the employees of the Universities.</p> <p>Need to offer student subsidized fare and issue the cards as exercised before.</p>	
24 Nov 2016	University Road, Peshawar- FGDs	<p>Non-Government- Trader Union representatives</p> <p>Traders Leader SVP Tajjir Ittehad Mr. Noor Muhammad, Mohd Sohail, Dr Gafoor Ayub, University</p>	<p>To get traders views on present transport issues in context of women travelers</p> <p>To understand their response on PBRT.</p>	6		<p>Existing public transport is not good for women as they have to face lot of problems.</p> <p>PBRT is good project especially for women and students.</p> <p>Women need to allocated separate compartment & entrance in the PBRT and there is a need provide necessary security system</p>	<p>They said BRT is welcome. Its route will raise many objections as businesses will be affected. Is good for public but route should not affect existing economy. Those affected be given good recompense.</p>

		Town Traders Union. Head Dispute Resolution Council, Engr Riaz Mufti, Tariq				<p>under PBRT project so that passengers feel comfortable.</p> <p>Ambulances need to be allowed to use the PBRT corridor in case of sever emergencies.</p> <p>As it is a political decision following Punjab government so maybe there will be hindrance during construction of corridors as number of stakeholders have reservation like trader's fear that their businesses can be affected, venders fear that they may be forced to a place where they might not get customers.</p> <p>Transporters, rickshaw drivers and taxi owners fear that they will lose income as most people will use PBRT services.</p>	
24 Nov	Western Bus depot site- FGD		Visited Western Side BRT Bus Depot site and held on site meeting with District Land Revenue Officer, concerned Girdawar and Patwaris of three different Mouzas.	10	1	Do not have & remember record of purpose of meeting, outputs, action points etc	
26 Nov	Peshawar City – Old Wall City-FGD	<p>Sikh Community, Minorities</p> <p>Sikh Gurudwara, Pramjit Singh and Babaji Gural Sigh - Incharge KP FATA Lungi Malik, Sikh community, Men & women of Sikhs Community</p>	<p>To find their view on present transport issues related to women & minorities.</p> <p>To find what is their response on PBRT</p>	6	5	<p>It was found that the existing transport system was not good for women and girls whereas the men faced no problems while using it.</p> <p>Sikh women were found not to travel alone and if they did, they hired rickshaw or taxis.</p> <p>Sikh men were found to have a little trouble problem as they are easily identifiable but women did not face that problem. However, a lot of money had to be spent on taxis as they charged fares up to 400 rupees on a one-way</p>	Cooperative but reluctant to respond

						<p>trip.</p> <p>PBRT was found to be very welcome as it was expected to provide respectful and comfortable traveling to the people of Peshawar.</p> <p>The need to have separate women seats, compartment and entrance was advocated very strongly.</p> <p>As in Peshawar there is security related issues so need to provide special security to make the PBRT travelling safe for all.</p> <p>Female staff needed to be hired under PBRT project.</p> <p>The fare of be PBRT should be subsidized just as that being offered in Rawalpindi and Lahore especially to the students and regular male and female commuters.</p>	
26 Nov	Canal Town, Peshawar-FGD	<p>Christian Community-Minorities</p> <p>Salvation Army Church, Capton Nadeem, Capton. Hina, Tariq Masih, Faisal, Raeaq, Ieshad Tahira Tariq, Samina, Nasreen,</p>	<p>To get their view on present transport system especially in context of women & minorities.</p> <p>To find their response on PBRT.</p>	4	4	<p>It was found that a large number of Christian communities, both men and women, used public transport.</p> <p>They walked long distances to reach bus stops to save money.</p> <p>As women faced hardships and embarrassment while traveling in public transport, so they never took their young daughters when themselves whilst travel in buses.</p> <p>Separate women compartment with a separate entrance needed to be ensured.</p> <p>PBRT fare should be easily affordable.</p> <p>Women were found to be happy with the prospect of using PBRT to take their children, particularly girls, for outing.</p>	
29	Kohati-FGD	Christian	To inquire about their		10	<p>It was found that public transport was mostly used</p>	Cooperative and shared information without

Nov		<p>Community</p> <p>Shabnam Maqsood</p> <p>Samina Jamil,</p> <p>Anam Shahbaz, Sadia Shoukat, Uzma Ashfaq, Sonia Javid, Mursaleen Yousaf, Jamila Ashfaq, Shahmim, Humera Yaqoob</p>	mode of travelling and related issues			<p>for travelling to work, shopping, and dropping children to their schools, and attending ceremonies.</p> <p>Women preferred to travel in rickshaw whilst men traveled on public transport.</p> <p>As women were always pressed for time due to their household and employment responsibilities, they could not make time to walk 15-20 minutes to the bus stop and then wait another half an hour for the bus to show. Women were also found to feel insecure while traveling on public transport and even crossing the roads was sought of as difficult o and therefore women tried to stay at home. They were also found to face bad behavior from the bus and wagon drivers and conductors and harassment from the fellow male passengers. Bus or wagon drivers were found not to stop to pick the women.</p> <p>The need for traffic signals, zebra crossings, separate women compartment and seats in the buses and wagons, separate women waiting places at bus stops was emphasized. Rawalpindi Metro bus system was cited as a good example for public transportation.</p> <p>PBRT was therefore expected need to have women separate places and seating (at 30% area), economical fare, women waiting area a bus stations, and easy access to the buses. CCTV cameras needed to be at bus station and in the bus to ensure security during travelling.</p>	hesitation
29 Nov	Agriculture University Peshawar- FGD	<p>Students of BSc Honors Agriculture</p> <p>Laiba Najam</p> <p>Mah Rukh</p>	To discuss the existing commuting patterns in public transportation in Peshawar and related		9	<p>Men and women come out for jobs, education, hospitals, shopping and to visit relatives also to travel to villages.</p> <p>Women were mostly found to prefer rickshaw and taxi especially when their children</p>	Quite responsive and enthusiastic

		<p>Maria Muneer</p> <p>Doha Ajmal</p> <p>Zainab Malik</p> <p>Sonya Bahadur</p> <p>Maliha</p> <p>Mahboob</p> <p>Kinza</p> <p>Mehak Sajid</p>	issues		<p>were with them. However, men were found to use all kind of transport (public & private). In main city, there is no issue to access the public transport but people living in outskirts and distant areas had issues in accessing public transport and thus they relied on Chin-chi, Tonga, Auto Rickshaw and taxi to reach the main road to get the public transport often they walk.</p> <p>It was told that women could not travel alone after sunset and had to do so with a male family member. As there were no zebra crossings on roads in Peshawar, it posed as a major problem for female pedestrians and posed as one of the major reasons for higher ratio of women being injured in road accidents. As in Peshawar there is dominating Pakhtoon Culture so women and girls are usually not allowed to travel alone without male family members.</p> <p>GoKP need to design gender friendly public transport system so that everyone could avail it. As of now, the public transport drivers and conductor's behaviors were quoted to be very unprofessional therefore; there was a need to higher professional drivers and staff. As currently, there was no separate area for women to wait, they felt insecure. It was said that University Road, Hastnagri & Saddar, KTH & LRH were very safe for women travelers.</p> <p>In PBRT women were expected to have separate seating in separate allocated compartment with separate entrance. Women also feel uncomfortable due to pick pocketing so in PBRT special safety measures need to undertake to avoid such exercise.</p>	
--	--	---	--------	--	--	--

						<p>Fans, water cooler and bathrooms need to provide in bus station separately for men and women. Dust bins need to be provided in the waiting areas, maintain cleanliness at bus stations, in the bus and on the corridor. Need to provided elevators for old and disable persons. An ambulance service needs to be provided on the PBRT corridor in case of an emergency. PBRT door need to be closed and its fare should be affordable for students and poor. If PBRT is like metro Rawalpindi than it will be beneficial for women travelers as it is speedy, safe, time saving, economical so that it encourages women to prefer to travel on PBRT. Also, need to have separate ticketing system for security need to install CCTV cameras. There is need to have more buses during peak hours. After PBRT there will more women and girls come out for job, business, work and education so there will be possibility to have more job opportunities.</p>	
30 Nov	Girls Guide Associations Dubgri-FGD	<p>Girls Guide Vocational Staff & Students</p> <p>Noreen, Mubashara, Kalsoom, Rimshah, Saba Kanwal, Rabi Jabbar, Sana & Rubeena</p>	To know about existing PT, its use and related issues		9	<p>Come out from home for getting vocational training, education, shopping and jobs etc.</p> <p>Women prefer to travel through rickshaw and taxi sometimes in buses and wagons whereas men can travel on all kind of PT.</p> <p>Women has less access to PT due to lack of money and lack of proper PT.</p> <p>Due to rush and traffic jam women are unable to travel easily. Most of the road accidents occur due to overcrowded buses.</p> <p>Existing PT in Peshawar was found unsafe for women and therefore women do not leave their houses. In case of provision of save, secure, cheap, speedy and respectful</p>	Cooperative and responsive.

						<p>PT services women will be encouraged to come out to be a part of social and economic activities.</p> <p>Misbehavior is common with women from the PT drivers, conductors and harassment from the fellow male passengers.</p> <p>Over speeding in the congested areas are in routine, and the respondents said that the bus drivers almost never stopped vehicle for women passengers.</p> <p>Regular women commuters feel insecure while traveling on taxi and rickshaw but they have no alternate.</p> <p>PBRT needed to have separate women compartment with separate doors, separate waiting areas at bus stations and separate ticketing booths for women.</p> <p>There is need to have traffic signals, sign boards, zebra crossings, also need to conduct awareness sessions how to travel in PBRT.</p>	
1 Dec	FRONTIER COLLEGE AND UNIVERSITY-FGD	<p>Nimra</p> <p>Laiba</p> <p>Shanza</p> <p>Mah Noor</p> <p>Razia Batool</p> <p>Fatma</p> <p>Saba</p> <p>Wajeelha</p> <p>Munaza</p> <p>Laiba</p>	To know students public transport use and related issues		10	<p>Men and women use public transport to travel to work, to educational institutions, shopping, and hospitals and to visit their relatives.</p> <p>It was reiterated that although the existing public transport was not women friendly, women were compelled to use public transport as they could not afford to travel in auto rickshaw and taxi.</p> <p>The existing transport system was reported to be deeply flawed as it was time consuming, crowded, mixed gender, had limited seats for female which are mostly taken by male passengers and women and girls has to travel by standing in the bus. Buses and wagons are fast and rushed while driving, and</p>	<p>All girl students were cooperative and welcomed the PBRT but they suggested extending the PBRT corridor to the link roads as Charsada road, Kohat road & Warsak road to facilitate the people living of those areas.</p> <p>PBRT needed to fulfill the female needs, providing them with safe, secure and affordable traveling so that women and girls could use it without any fear and therefore increase ratio of women travelers up to 100%.</p> <p>Group participants asked that whether PBRT corridor will construct in front of the college as already the road is narrow how it will be built here. In case of alleviated</p>

					<p>they did not stop properly while picking & dropping the passengers, not even for women and girls. Drivers and conductors were not skilled and their behavior was reported to be bad with women and girls and thus they continually felt harassed. While traveling on buses and wagons women and girls are most of the time accompanied by their male family member and some time they have to skip their visits or use auto rickshaw/ taxi. It was said that although the existing public transport was affordable and accessible to schools, education institutions, hospitals, market places, and public utilities, it could not be used by females.</p> <p>Major transport corridors used by women were Sadler bazar (shopping), hospitals (LRH, KTH, HMC and SKMH), university road (for education and shopping both), Hayatabad (NADRA office, passport office)</p> <p>PBRT should have separate compartment/ bus station/ waiting area/ separate ticketing line for females and also should have a separate space for luggage.</p> <p>PBRT should reserve 40 percent seats for female, with a separate exit/ entrance and should also have a separate door and space for disabled and elderly people. The stations needed to be kept clean with dustbins in waiting areas. CCTV cameras need to be installed on each bus station, waiting areas and in the buses and security guards need to be present to deal security issues.</p> <p>Fans, wash rooms and cool water coolers need to be installed at each bus station.</p> <p>PBRT fare needed to be affordable and the</p>	<p>corridor, the building alongside the road could be affected.</p>
--	--	--	--	--	---	---

						<p>government was expected to offer concession to students, disable and old people.</p> <p>PBRT buses flow should be rapid during the peak hours of 7am to 9am during the morning time later from 12pm to 4pm in the afternoon.</p> <p>The busses needed to have an emergency exit and an ambulance service should be available to deal with emergencies.</p> <p>A proper and regular monitoring system should be there to avoid any issues.</p>	
1 Dec	Shaheed Benazir University- FGD	Girls Students Nirma Shanza Raziaa batool Saliha Munza Laiba Mah Noor Marwa Warda Javerria Sidra	To know about the existing public transport in Peshawar city, their public transport mode and related issues		12	<p>The female students had to travel to universities on vans they paid for monthly as their parents worked or were busy running household errands. It was stated that the men the area could both travel on public transport for both educational and work purposes with trouble whilst the women in the city could not. It was found that students, both male and female, did not find taxis to be a safe alternative as they could be easily kidnapped for ransom. It was also due to the lack of zebra crossing on the road a number of accidents that involved women and children occurred.</p> <p>Moreover, as there were no specific bus stops in the area, the buses stopped randomly to pick up passengers and the bus drivers seldom stopped for female passengers.</p> <p>It was found that women usually went to Saddar Bazar for shopping, schools & universities were on University road, KTH and LRH for health issues & Gulbehar and Hayatabad & University Town for house maids.</p> <p>To overcome the women harassment public transport</p>	Responsive and cooperative

						<p>for women needed to have separate compartment with separate entrance, separate waiting areas at bus station and separate ticketing points.</p> <p>In PBRT special security system needed to be installed as CCTV cameras need to be there.</p> <p>There is need to have announcement system for arrival and departure timings of PBRT, prevent from pick pocketing and for announcement of name of station.</p> <p>The PBRT stations need to be properly maintained, cleaned and more buses need to be made available for rush hours.</p> <p>Female usually carry small shopping bags while traveling in public transport as conductors do not allow them to get on with heavy bags and charge extra fare.</p> <p>Need to have separate ticket lines for men and women.</p> <p>Separate exit and entrance door for men and women.</p> <p>It was also proposed that PBRT should be designed like double Decker busses with the lower deck for men and the upper deck for females. It was also suggested that the portions be color coded for ease of understanding.</p> <p>If PBRT was to operate, more women and girls were expected to come out from their homes for work and education.</p>	
1 Dec	LRH Peshawar - FGD	<p>LRH (Leading Reading Hospital) Peshawar Staff</p> <p>Khadija Fatima, Hafza, (clinical psychologist)</p> <p>Shista (Head of</p>	To understand the exiting public transport system and its issues	2	4	<p>It was stated that people only travelled on public transport to run errand or too work, hospitals and schools. Women had no time for recreational activities especially if they were working and therefore the majority users of public</p>	<p>PBRT will be economical and affordable for every class.</p> <p>Participants were cooperative besides their busy schedule.</p>

		<p>Nurses)</p> <p>Adnan (clinical psychologist)</p> <p>Fida Jann – Social Medical Officer</p>			<p>transport were men who could spare time in the evenings to socialize and travel within the city.</p> <p>Women felt unsafe using public transport due to lack of bus stations, bad traffic management, no sign boards, no zebra crossing in Peshawar city. It was found that busses rarely stopped to pick up female passengers and in cases they did, they were often asked to pay higher fares, especially during late evenings.</p> <p>As local transport was found to be unsafe, time consuming and with frequent pickpocket incidents, most of women doctors, nurses and trained paramedical staff decided to not work and therefore PBTR is expected to be extremely useful to girl students and working women.</p> <p>PBRT was expected to have separate women portion and seats, proper and regular bus repair, professional driving staff, availability of the security guards and if possible also female security guards. As currently in public transport women harassment is common by the drivers, conductors and fellow male passengers so after PBRT it will be overcoming as by hiring professional staff.</p> <p>Exiting PT being time consuming, PBRT would be rapid so would attract more passengers. Moreover, travel for patients is almost impossible in the available PT system whereas after PBRT operation it would be easier for patients to travel.</p> <p>Currently PT is overloaded, dirty and old whereas PBRT would have new clean buses, less overloaded due to frequent and rapid movement after 5-6 minutes' difference. In PBRT 40% portion of the bus was</p>	
--	--	---	--	--	--	--

						<p>expected to be allocated to women. Provision of dustbins in buses and at bus stations and separate ticketing system were also expected to be a part of the design.</p> <p>It was pointed out that as PBRT would be passing through the LRH Peshawar, the narrow road would imply an alleviated corridor will be constructed which could affect the hospital and thus needed to be taken into consideration by the government.</p>	
2 Dec	Postal Colony- FGD	<p>House Wives & Working Women</p> <p>Farzana</p> <p>Anila</p> <p>Shazia Yasmin</p> <p>Nazia Jabbin</p> <p>Afsheen Shahid</p>	To understand the mode of their public transport and related issues		6	<p>Women majorly choose to travel on family owned cars, taxis or rickshaws in comparison to travelling on busses or wagons as the later forms of transport were thought of to be unsafe for women. It was stated that women only choose to use public transport only if it was absolutely necessary to run errands and almost never for leisurely activities, whereas men had the luxury to use public transport to indulge in leisure activities.</p> <p>For women, no proper seats were available in public transport and they had to walk 20-30 minutes to get the nearest bus stop.</p> <p>Women had no separate waiting areas that needed to be included in the PBRT to avoid harassment incidents. For illiterate men and women. It was proposed that announcements be made in both Urdu and Pashto. Need to have special security system as CCTV camera needed to be installed to minimize terrorism or any other security incidents. There is need to have separate space for luggage, water coolers, fans in the PBRT waiting areas for females. The buses need to be air-conditioned during summers and heated during winter so that passengers</p>	Women, children, elders, minorities, disable and other excluded sections of society can only be benefited when there will be public transport system overcome and fulfill their required needs.

						<p>feel comfortable while travelling in PBRT. Women need to have secure, safe, respectful, time saving and affordable public transportation that is currently not available.</p> <p>If such public transport was to be provided 50% passenger rate would increase, especially for females.</p> <p>As the current forms of public transport had no space to carry luggage, women carrying bags were forced to private rickshaws and taxis and therefore the PBRT design was strongly advised to keep space for luggage and provide an emergency ambulance service.</p> <p>It was also stated that the PBRT project needed to ensure jobs, especially for women and that the project needed to be regularly monitored and maintained. The government needed to run an awareness campaign on from where and how people could travel on PBRT.</p> <p>I was stressed that female issues needed to be considered and honored during designing, planning and implementation of PBRT.</p>	
5 Dec	Afghan Commissioner flats Hayatabad-KII	Nasira wife of Syed Noor Wali Shah a Government servant	To understand the existing public transport services for women and issues	-	1	<p>It was found that the respondent had never used public transport as the busses and wagons were overcrowded, time consuming, had no proper stops, there were no designated seats for women and not easy to climb in along with children and therefore either travelled on a motorcycle with her husband or took a taxi which she stated was highly inefficient. She stated that the existing public transport was not deemed safe for women and only 7 am morning time was a good time for women to</p>	Need to have safe, secure and comfortable transport for women travelers, students and disabled people.

						<p>travel.</p> <p>The respondent suggested that the ticket prices for PBRT should be kept as low as possible that can easily affordable for poor travelers, students and people with disabilities.</p>	
6 Dec	Engineering University Peshawar-FGD	<p>Students</p> <p>Mamoonah Safeer</p> <p>Sania Ajaz Wali Khan</p> <p>Sadaf Javid</p> <p>Sidra tul Muntaha</p>	To understand exiting PT (Public Transport) and their use and issues		5	<p>The students responded that the majority of the public transport users were men as women preferred to use taxis and rickshaws due to fear of harassment, higher fares, limited availability of seats, crowded spaces, pick pocketing and waste of time. Moreover, it was stated that as bus drivers refused to completely stop busses, it was very difficult for women to hop on to moving busses and therefore it discouraged female passengers.</p> <p>Therefore, PBRT needed to have 40% of the space allocated to a separate women compartment with a separate entrance, separate women waiting area at the bus station, arrangement of water cooler, tuck shop, women separate wash rooms and proper cleaning facilities at bus station and in the busses. Keep less height of the PBRT so that women, children, old and disable people can enter easily (need to be leveled at bus station platform).</p> <p>It was pointed out that there was a need to have proper maintenance of the PBRT and necessary security measure needed to undertake to avoid any problems.</p> <p>Female security guards, drivers and conductors needed to be hired.</p>	<p>Cooperative</p> <p>About 50% to 60% women will become able to reap social and economic benefits after the provision of an efficient and safe PT system. It would be helpful in increasing female literacy rate and it would be needed to be ensured that there is no discrimination amongst the passengers.</p>
6 Dec	Khyber Medical College Peshawar-	<p>Students</p> <p>Sumaia Azmat,</p> <p>Ayesha Ahsaan,</p> <p>Anam Delawar,</p> <p>Ruba Gul,</p>	To	1	12	<p>The students reiterated that women only used public transport if absolutely necessary and never for recreational and leisure purposes as public transport</p>	<p>Cooperative and quite enthusiastic</p>

	FGD	Kinaat, Ayesha Yousaf, Maria Khan, Aqsa, Ulfat & Saad Manan			<p>is deemed as unsafe, unreliable, poorly managed and overcrowded. Females thus preferred taxis and rickshaws as their preferred mode of transport to work, markets, schools and colleges and hospitals. The students stated that not only did the bus drivers refuse to stop busses to take on female passengers, the harassment faced in the busses and at the bus stops included touching, whistling, and comments by fellow male passengers.</p> <p>It was also stated that due to the unprofessional attitudes of the bus drivers and their lack of training, they both drove terribly slow or extremely fast and were thus were extremely unreliable. Furthermore, the people on the main roads had direct access to public transport and crossing over from side roads was deemed as extremely dangerous as the roads had no proper traffic signals or zebra crossing. University road, Hayatabad and Sadler is for shopping, hospitals and education institutions Hayatabad for hospital (Doctors, patients & nurses) and Warsak Road for schools.</p> <p>For PBRT, the government needed to install traffic signals, proper monitoring system, proper security, professional transport staff, and proper bus stops, clean and comfortable buses. PBRT should not be time consuming like the existing public transport. BRT platforms needed to be raised so that women, children, elders and disable could easily ascend in and descend out. At bus stops women, should have separate ticketing booths and CCTV cameras needed to be installed at bus stops, in the buses and on the PBRT corridor. Emergency telephones needed to be at</p>	
--	-----	---	--	--	--	--

						bus stations and in the buses to avoid any emergency. Needed to have wash rooms both for women and men and separate waiting areas at bus stations.	
7 Dec	Social Work Department University of Peshawar- FGD	Female Students Sana Ahmed Kainaat Hassan Shahnaz Afridi Rida Iqbal Alina Ali	To understand the existing Public Transport system and women issues while traveling in public transport		5	<p>It was found that both women and men used public transport to run errands and get to work, to study or to get to social services. Women from rather affluent backgrounds were found to be using taxis and rickshaws and only those who faced financial constraints used public transportation systems. However, bad public transportation was reported to be a major deterrent for women in continuing their education or perusing career prospects. Women and girls faced extreme misbehavior from the bus drivers, conductors and fellow male passengers that they reported to have chosen to not travel at all. Overloaded, old, ripped seats and dirty busses had no designated times of arrival and departure and therefore were very unreliable and were not used by a large majority of female passengers.</p> <p>The culture of the city prevented women to mobile and therefore, women were mostly found to travel in pairs or were accompanied by family male member.</p> <p>The PBRT busses were thus expected to have separate seating spaces for women, with separate entrances and ticketing counters. It was proposed that a map of the BRT route should be displayed at predominant spaces at the stations for the ease of passengers. PBRT is thus expected to resolve 80% of public transport related issues. It was stressed that the fares needed to be economical to ensure that everyone could afford to</p>	Cooperative

						<p>travel on the buses.</p> <p>The buses needed to be operated by trained drivers and other staff members and cleanliness needed to be ensured at the stations and in busses. Cameras needed to be installed at the bus stations and within the busses to ensure monitoring and for security purposes.</p>	
7 Dec	Firdous & Hashtnagri underpasses-CM	Shopkeepers of Firdous & Hashtnagri underpasses Wajid Ali Nadeem, Zahir Shah, Islam Gul, Qari Hidayatullah (Shura Committee members of Firdous underpass) & Wajid Ali Nadeem, Afsar Ali Khan	Held consultation meetings (CM) with shop-keepers of Firdous & Hashtnagri underpasses. Discussed over census data collection of formal businesses and took their consent before start of data collection process.	30 in Firdous underpass & 27 in Hashtnagri underpass	0	<p>In view of underpasses demolition, the shopkeepers suggested that the authorities should fulfill 4 demands on priority basis.</p> <p>All the shopkeepers of both the underpasses should be provided with shops at the same location in Bus stops at the same location.</p> <p>In the construction phase, they should be provided alternate proper business place.</p> <p>Lease agreement of the shops should be extended.</p> <p>Proper compensation should be provided in place of their decoration or investment on the current shops.</p>	The shopkeepers got ready for conduction of census of formal businesses after the consultation meetings. The survey team realized them that through census survey they could send their demands/ rights to the authorities. Meeting was fruitful because through formal consultation direct with survey team they realized the benefits of survey platform and got ready for conduction of census of formal businesses survey
07 Dec	University of Peshawar-FGD	University Students07 Dec 2016 Social Work Department University of Peshawar, Wahab Razaullah, Abdul Bais , M. Sohail , Abdur Rehman , Aqib Khan, Ikram Khan	FGD to introduce BRT and discuss their preferences/views regarding present public transport and BRT. Related issues and gender benefit.	6		<p>The real problem for women is harassment free, fast and quality transport. Men tag along and they can also hang and bear discomfort. Men travel more than women. Women should travel in day time that is best time for them. University students here and elsewhere in Peshawar on BRT route will be very happy. If not us those (students) who are coming after us will enjoy the benefit of BRT. It should have come earlier.</p>	
08 Dec	Hazar Khwani Peshawar-KII	PWD Habib Gul, PWD (Person with Disability) blind, Resident of Hazar Khwani,	KII. Find travel pattern, restriction experienced due to transport and disability,	1		<p>Fares should be lower for poor women. Asked for care of disabled in PBRT</p>	

		Peshawar	harassment and preferred transport and views on fare.				
08 Dec	Board Bazar Peshawar-KII	PWD Muhammad Yusaf, unable to walk due to polio	KII. Find travel pattern, restriction experienced due to transport and disability, harassment and preferred transport and views on fare.	1		Bus should wait for disabled to board easily.	Provided information
08 Dec	University Town, Peshawar-KII	Poor Commuter Rahat, Domestic Servant	KII. Find travel pattern, restriction experienced due to transport, harassment and preferred transport and views on fare.		1	Women preferred time of travel is day time.	Hesitant
08 Dec	Kachi Muhallah, Lahore Gate Peshawar (KII)	Shazia Rouf Teacher Also Student of Quran (Blind Person)	To know the women travelling public transport mode & related issues		1	<p>As the respondent, did not own a private vehicle, she had to rely on travelling on expensive taxis and rickshaws with her brother. She stated that she was unable to access public transport as they did not cater to her disability.</p> <p>According to her public transport is not safe for women because they have to face harassment issues but during the day time it became slightly safer for women to travel.</p> <p>She stated that she had to allocate 150 rupees for daily commute and although that was extremely expensive, she did not have another option. According to her 10 rupees' ticket price per stop could be affordable while traveling from Hashtnagari to Saddar. PBRT needed to be friendly for the blind so she could travel on PBRT with ease.</p>	Requested to make PBRT travel safe and useable for blind persons.
8 Dec	Bhana Mari, Kohat Road, - KII	Gulshan beautician	To understand about existing public transport		1	She walks every day to the nearest bus station and takes bus. She also uses the public	PBRT will be more useful for working women so need to offer subsidized rate for

			travelling pattern & issues			<p>transport to go the market.</p> <p>Public transport is too slow, taking too much time to reach the destination whereas taxi and auto-rickshaw provides efficient service but expensive cannot be affordable on daily basis. She often travels in crowded mixed gender spaces although not pleasant for her. She faces harassment of staring and touching by men at bus stop and by the fellow male travelers. Public transport is not safe for women however morning and before evening are the safest time for women travelers. For women, the safest areas to travel are Saddar, University Road and GT Road. The exiting public transport is affordable and for women the most acceptable fare should not be more than 15 rupees.</p>	daily commuters.
8 Dec	Hayatabad Peshawar-KII	Naveeda Naz, lawyer	To know about women traveling through existing public transport & issues		1	<p>The respondent reported that she had to walk a kilometer every day to nearest bus station to catch a bus to work. She stated that the public transport facilities were highly inefficient and slow and travelling in crowded, mixed gender spaces was an unpleasant experience as she routinely faced harassment as fellow male passengers leered and commented at her.</p> <p>She stated that days were relatively safer for women to travel in public transport the safest areas to commute were Saddar and University road. The exiting public transport was said to be affordable but not for poor people.</p>	Need to have fixed fare of 20 rupees for women as offered in RMBRS (Rawalpindi Metro Rapid Bus Service) also need to offer subsidized package for the students, old citizens and people with disability. PBRT has to be women, children, elders and disable friendly.

8 Dec	Khadia khel Bakshi Pul Charsada Road Hayatabad-KII	Gazala daughter of Samin Jan- Blind person	To know what are the blind person's particularly blind women travelling mode, frequency and issues/problems		1	<p>The respondent attends the school (blind Institute) to learn Braille and once a month and visits her sister house and the market place. Never having taken a bus because of them being overcrowded and difficult to get on; the respondent either uses a motorcycle to travel or a rickshaw.</p> <p>Usually preferred to travel most frequently in the morning and was always accompanied by family members. The respondent stated that public transport was not safe for women when they traveled alone. Morning time and day light is more secure for women traveling. For women and girls no route is safe in Peshawar while traveling in exiting public transport.</p>	PBRT has to be friendly and comfortable for blind women and other disables. Special paths and elevators need to offer for the people of any kind of disabilities.
21 Dec	MCC Office, Arbab Road Peshawar	Leased owner of Firdous & Hashtnagri underpasses Mirza Khan, Owner & CEO of Mohmand Construction Company	Meeting with Mirza Khan & Shura members regarding commencement & purpose of structures/ shop-keepers socio-economic survey.	8	0	<p>As the socio-economic survey was on sample basis that is why the shopkeepers were worried that why the survey team conducted survey from selective shopkeepers (were suspicious about purpose and did not know about the sample technique). Therefore, to explain the purpose of socio-economic survey, the shurra members demanded that the survey team conduct a meeting with their lead person (Mirza Khan).</p>	The shopkeepers and the lead person (Mirza Khan) realized the purpose of socio-economic survey and allowed the survey team for the particular survey exercise. Due to the meeting with shurra members, they allowed the survey team to conduct the socio-economic survey
26 Dec	PDA Office, Phase-V, Hayatabad	Project implementing Department (Director & focal person for BRT)	Status of STP land ownership, discussion over resettlement cost for PC-1 and other study related matters.	3	0	<p>He showed his concern over the availability of BRT proposed width at Zakori Bridge in Chughal Pura area & at Takhto Jummat (Sadar Bazar).</p> <p>He and DG PDA informed with confidence that STP land is the property of PDA.</p>	Resettlement team decided to conduct visit to two mentioned sites for confirmation and clarification.
28 Jan	Shelton Guest House	DPs	To share salient features of LARP and take DPs views on proposed unit rates for	28	0	<p>DPs showed keen interest in the LARP features, and proposed unit rates, and provided suggestions to improve LARP and resettlement packages.</p>	DPs suggestions are incorporated in the LARP to the extent possible.

			compensation and resettlement assistance				
--	--	--	--	--	--	--	--

8.7 Addressal of Stakeholder Concerns

537. The DPs and stakeholder concerns and suggestions have been incorporated in the Environment Management Plan, LARP and Gender Action Plan, and will be implemented as an integral part of the PBRT Project activities. The LARP has been prepared to compensate DPs sufficiently and promptly. The EPCM consultants and PMU Social, Gender and Resettlement staff will conduct consultations with potential DPs at the stage of detailed design and other relevant stakeholders during the process of updating this LARP, and develop mitigation measures against identified impacts to address concerns of DPs and other stakeholders. The summary of the concerns raised and their addressal is provided in Table 8.2 below.

Table 8.2: Summary of Concerns Raised by DPs / Stakeholder, and their Addressal

Concerns raised by the DPs / Recommendations	Actions incorporated in the RP/EMP (to address DPs Concerns / Recommendations)	Responsibility during Project and RP Implementation
<ul style="list-style-type: none"> Prior to demolition of underpass markets, the alternative shops should be constructed and relocation of affected businesses should be completed Compensation against damages to the fixtures and decoration of the shops should be fully and promptly paid. 	<ul style="list-style-type: none"> It is strongly recommended that demolition of underpass markets should be done after construction of alternative shops and relocation of businesses. 	TMTD/TPC, Project Director and SPS of PMU, EPCM and civil works contractors
<ul style="list-style-type: none"> Affected vendors should be provided alternative temporary business spaces to continue their business activities during the construction of BRT corridor. 	<ul style="list-style-type: none"> TMTD/TPC in coordination with other relevant departments will allow affected vendors to re-establish their businesses at temporary vending locations to enable them to continue their livelihood activities. 	TMTD/TPC, Project Director of PMU, SPS and EPCM
<ul style="list-style-type: none"> Permanent vending spaces to affected vendors at BRT related infrastructure to legally continue their business activities after construction of BRT corridor. 	<ul style="list-style-type: none"> TMTD/TPC in collaboration with other relevant departments will provide formal vending spaces to affected vendors at commercial areas of in proposed 4 pedestrian underpasses, 38 access bridges and 24 pedestrian bridges or around Bus Stations on a rental agreement with TransPeshawar Company through registration and issuance of legal licenses. 	TMTD/TPC, Project Director of PMU, SPS and EPCM
<ul style="list-style-type: none"> The businesses of the commercial markets shall not be affected due to project activities, except the DPs who should be fully compensated for income and structure losses. 	<ul style="list-style-type: none"> The GoKPK has adopted an approach to restrict the BRT works within the available width of ROW at built up areas and due to this approach damages to only few structures will occur. However, the people whose income will be affected will be sufficiently and promptly compensated. 	TMTD/TPC, Project Director and SPS of PMU, SRS, EPCM and civil works contractors

Concerns raised by the DPs / Recommendations	Actions incorporated in the RP/EMP (to address DPs Concerns / Recommendations)	Responsibility during Project and RP Implementation
<ul style="list-style-type: none"> Construction of road strictly within the available width of RoW. 	<ul style="list-style-type: none"> An approach adopted by GoKPK to restrict the road construction within the available space of ROW at built up areas to the extent possible. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Avoid dismantling of commercial, residential or community structures. 	<ul style="list-style-type: none"> TMTD/TPC will ensure no damages to additional structures in built up areas other than those which are inevitable to demolish. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> The affected DPs, vendors and other vulnerable groups should be sufficiently and timely compensated against their income losses. 	<ul style="list-style-type: none"> The operators of affected business enterprises will be adequately and sufficiently compensated by following principles of ADB SPS. 	TMTD/TPC, Project Director of PMU, SPS and EPCM
<ul style="list-style-type: none"> Opportunities for skilled and unskilled labor should be provided to AHs during construction of BRT. 	<ul style="list-style-type: none"> The Contractor will be required to provide opportunities for skilled and unskilled employment to Project Affected Households, as well as on-the-job training to skilled labor of AHs to upgrade their skills in construction building. And TMTD and EPCM will closely monitor the contractors. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Construction could also take place at night and on holidays to reduce disturbances. 	<ul style="list-style-type: none"> Construction may also take place at night to reduce impacts, such as relieving daytime traffic congestion, BRT road construction will be completed in minimum possible time i.e. 18 months. 	TMTD, Project Director of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Safe mobility of commuters particularly women and children, and safety measures during construction activities 	<ul style="list-style-type: none"> Roadside furniture and traffic control devices, including information and cautionary signs, announcements at public places, signals, traffic diversion and flow markings, to ensure pedestrian safety during construction and operation stages. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Proper facilities like sufficient number of bus stations and parking areas should be built at suitable locations. 	<ul style="list-style-type: none"> GoKPK (TMTD) will ensure provision of these facilities under the project 	TMTD, Project Director and SPS of PMU, EPCM
<ul style="list-style-type: none"> Tree plantation should be done along the road. 	<ul style="list-style-type: none"> TMTD committed to retain existing median, in addition to this, a tree plantation program has been designed to compensate anticipated loss of trees during construction activities, and to help abate pollution caused by emissions and dust during BRT operations. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Provide drainage along the road 	<ul style="list-style-type: none"> A drainage system has been designed along the road 	TMTD, Project Director of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Stakeholder's consultation and participation should be an integral part of the resettlement and BRT construction and implementation process. 	<ul style="list-style-type: none"> TMTD/TPC will ensure effective stakeholders consultation and participation in the process of detail design, updating of LARP, implementation of LARP, construction of BRT corridor and operations of BRT system. 	TMTD, Project Director and SPS of PMU, EPCM, civil work contractors and service providers

Concerns raised by the DPs / Recommendations	Actions incorporated in the RP/EMP (to address DPs Concerns / Recommendations)	Responsibility during Project and RP Implementation
<ul style="list-style-type: none"> Mobility of local residents particularly women, children and elderly should not be restricted during construction activities; 	<ul style="list-style-type: none"> TMTD/TPC will ensure that project facilities like contractor camps will be located at a minimum distance of 500 m from residential areas in order to avoid restriction to mobility of local residents particularly women, children and elderly. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Proper arrangements should be made for smooth and un-interrupted flow of traffic passing through the road during construction works. 	<ul style="list-style-type: none"> TMTD will ensure that Traffic Management Plan development and will be implemented 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> The Control over-speed, management of traffic during construction 	<ul style="list-style-type: none"> A traffic management plan has been prepared for smooth flow of traffic during construction 	TMTD, Project Director and SPS of PMU, EPCM, civil work contractors and other relevant departments of the city government and GoKPK
<ul style="list-style-type: none"> Provide access to first aid facilities in case of emergencies of road accidents. 	<ul style="list-style-type: none"> TMTD will ensure provision of first aid in case of emergencies through provision in the contractors' agreements. 	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Proper arrangements for storage of construction material during construction. 	TMTD will ensure it.	TMTD, Project Director and SPS of PMU, EPC, civil work contractors, service providers and relevant department of city government and GoKPK
<ul style="list-style-type: none"> Regular removal of waste material from the ROW during construction. 	TMTD will ensure it.	TMTD, Project Director and SPS of PMU, EPCM, civil work contractors city government and relevant department of GoKPK
<ul style="list-style-type: none"> Improved road markings / signage and demarcation of accident-prone junctions in order to reduce conflicting movement during operation, particularly along inhabited stretches of road. 	TMTD will ensure it	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors
<ul style="list-style-type: none"> Installation of speed breakers where required particularly in front of hospitals, education institutions and other sensitive receptors. 	To be included in PBRT design at the stage of detailed design of BRT corridor.	TMTD, Project Director and SPS of PMU, EPCM and civil work contractors

9 Grievance Redress Mechanism

9.1 General

538. ADB Policy (SPS 2009) requires establishment of a local grievance redress mechanism to receive and facilitate resolution of the Displaced/Affected Persons concerns and grievances regarding the project's social, resettlement and environment performance. The measures have been identified to mitigate social and resettlement impacts to be caused due to implementation of PBRT Project works.

539. However, in spite of best efforts, there is every chance that the individuals / households affected by the project or other stakeholders are dissatisfied with measures adopted to address adverse social impacts of the project. To address, such situation an effective Grievance Redressal Mechanism (GRM) will be established to ensure timely and successful implementation of the project. It will also provide a public forum to the aggrieved to raise their objections and the GRM would address such issues adequately. It will receive, evaluate and facilitate the resolution of displaced persons' concerns, complaints and grievances about the social and environmental performance at the level of the Project.

540. The GRM will aim to investigate charges of irregularities and complaints receive from the Displaced Persons and provide a time-bound early, transparent and fair resolution to voice and resolve social and environmental concerns link to the project.

541. It is anticipated that the nature of such complaints will relate to compensation and resettlement assistance matters, damages, mobility and access issues of general public or disruptions of services during civil works related to the project functionaries. Some of the grievances that may arise are listed below:

- Name of a DP may be missing from the eligible DPs list
- Losses (such as damage to assets or loss of income) may not identified correctly during detailed design stage
- Improper distribution of compensation and/or resettlement assistance
- Problems in the relocation of DPs or their structures
- Delays in the payment of compensation and resettlement assistance,
- Any disruption by the civil works contractors
- Non-observance of project principles, by different parties, as laid down in the LARP
- Any other issue arising during the project implementation

542. The TMTD/TransPeshawar and PMU shall make the public aware of the GRM through public awareness campaigns particularly to DPs. The name of contact person and his/her phone number, PMU contact numbers and the TMTD/TransPeshawar, will serve as a hotline for complaints and shall be publicized through the media and placed on notice boards outside their offices, construction

camps of contractors, and at accessible and visible locations along the PBRT corridor, and also shared with the DPs representatives. The project information brochure will include information on the GRM and shall be widely disseminated throughout the PBRT corridor by the Social and Resettlement Specialist in TMTD/TransPeshawar and Social Team for Resettlement Plan Implementation (STRPI) under EPCM. Grievances can be filed in writing, via web-based provision or by phone with any member of the TMTD/TansPeshawar or PMU.

9.1.1 FIRST TIER OF GRM

543. The PMU is the first tier of GRM, which offers the fastest and most accessible mechanism for resolution of grievances. The Social and Resettlement Specialist (SRS), Environment Specialist (ES) and STRPI shall be designated as the key personnel for grievance redress. Resolution of complaints will be completed within ten (3) to fifteen (15) working days, depends on the nature of complaint. At this stage, the SRS will inform the TMTD/TransPeshawar PMU for additional support and guidance in grievance redress matters. Investigation of grievances will involve site visits and consultations with relevant parties (e.g. displaced persons, contractors, traffic police, general public, utilities companies etc.). Grievances will be documented and personal details (name, address, date of complaint, nature of complaint etc.) will be included unless anonymity is requested. A tracking number shall be assigned for each grievance, including the following elements:

- Initial grievance sheet (including the description of the grievance), with an acknowledgement of receipt handed back to the complainant when the complaint is registered;
- Grievance monitoring sheet, mentioning actions taken (investigation, corrective measures);
- Closure sheet, one copy of which will be handed to the complainant after s/he has agreed to the resolution and signed-off.

COMPLAINTS MANAGEMENT REGISTER (CMR)

544. The Social and Resettlement Specialist (SRS) will maintain a CMR to record grievances brought forward by displaced persons and general public, and ensure that these are appropriately addressed. The complaint register will provide for: the date and particulars of the complaint; description of the grievance; follow-up action required; name of person responsible for implementing the action; a target date for redressal and up-dated status/final action with date.

545. The SRS will be supported by the STPRI for this purpose. The actual measures taken to mitigate the concerns will also be recorded in the register. The complainant's views on the remedial action taken will also be documented in the Register. All complaints received verbally or in writing will be properly documented and recorded/written in the CMR. In addition to this an easy to access web based GRM will be designed on the same pattern, which will have updated status of each complaint to be used by complainants to get an update on their complaints.

546. The updated register of grievances and complaints will be available to the public at the PMU office, construction camps of contractors and other key public offices along the project corridor (offices of the city district government and district administration), and at accessible and visible places along the PBRT corridor. Should the grievance remain unresolved it will be escalated to the second tier.

9.1.2 SECOND TIER OF GRM

547. The SRS and ES in PMU will refer the unresolved issues (with written documentation) to the second tier of GRM, the GRC (Grievance Redress Committee). The GRC shall be established by TMTD/TansPeshawar during the detailed design stage prior to updating of LARP so that the DPs and other key stakeholders have recourse to refer their complaints.

548. The GRC will consist of the following persons: (i) representative of TMTD/Trans Peshawar as head of GRC; (ii) Project Director-PMU; (iii) representative of district administration; (iv) representative of PDA; (v) representative of relevant city district government offices; (vi) two representative of the displaced persons and (vii) representative of EPA-KPK (for environmental related grievances). The SRS and STPRI under EPCM shall organize a training of GRC to raise awareness about GRM and in handling grievances in an efficient and transparent manner as laid down in the LARP.

549. A hearing will be called with the GRC, if necessary, where the displaced person can present his/her concerns/issues. The process will facilitate resolution through mediation. The local GRC will meet as necessary when there are grievances to be addressed. The local GRC will suggest corrective measures at the field level and assign clear responsibilities for implementing its decision within fifteen (7-15) working days, depends on the nature of complaint. The contractor(s) will have observer status on the committee. If unsatisfied with the decision, the existence of the GRC shall not impede the complainant's access to the government's administrative or judicial remedies.

550. The functions of the GRC are as follows: (i) resolve problems and provide support to displaced persons arising from various social, resettlement and environmental issues. Social and resettlement issues including land acquisition (temporary or permanent, as applicable); asset acquisition; eligibility for entitlements, compensation and resettlement assistance as well as environment issues including dust, noise, utilities, power and water supply, waste disposal, traffic interference and public safety/utilities; (ii) reconfirm grievances of displaced persons, categorize and prioritize them and aim to provide solutions maximum within 15 to 30 days; and (iii) report to the aggrieved parties about developments regarding their grievances and decision(s) of the GRC.

551. The TMTD/TransPeshawar (SRS or ES) will be responsible for processing and presenting all relevant documents, field enquires and evidences/proofs to the GRC, maintaining a database of complaints, recording decisions, issuing minutes of


meetings and monitoring to see that formal orders are issued and to ensure that required actions against decisions are being carried out.

9.1.3 THIRD TIER OF GRM

552. In the event that a grievance cannot be resolved directly by the PMUs (first tier) or GRC (second tier), the displaced person can seek alternative redress through the district administration or city government, court of law or as appropriate. The PMU or GRC will be kept informed by the city district government or government administration, or any other authorities.

553. The grievance redress mechanism and procedures are depicted in Figure 9.1. The monitoring reports of the LARP and EMP implementation shall include the following aspects pertaining to progress on grievances: (i) Number of cases registered, level of jurisdiction (first, second and third tiers), number of hearings held, decisions made, status of pending cases; and (ii) lists of cases in process and already decided upon, may be prepared with details such as name with copy of NIC, complaint number, date of application, date of hearing, decisions, remarks, actions taken to resolve issues, and status of grievance (i.e., open, pending, closed).

Figure 9.1: Grievance Redress Mechanism



10 Conclusions and Recommendations

554. The development of the proposed BRT project in Peshawar is of high significance considering the urgent need for improving the urban transport landscape of Peshawar city. This project is expected to contribute towards the economic and social development of the region and pave the way for uplift of this entire region through generation of economic opportunities and increased investor interest in Peshawar.
555. Primary and secondary data has been collected and used to assess the environmental impacts of the Project. This EIA report highlights all potential environmental impacts associated with the Project and recommends mitigation measures. Any environmental impacts associated with the project need to be properly mitigated, through the existing institutional arrangements described in this report.
556. The majority of the environmental impacts are associated with the construction phase of the project. The implementation of mitigation measures during this period will be the responsibility of the Contractor. Therefore, the required environmental mitigation measures will have to be clearly defined in the bidding and contract documents, and appropriately qualified environmental staff retained by the Consultant to supervise the implementation process.
557. This EIA concludes that no significant negative environmental impacts are likely to occur due to construction and normal operations of the proposed project, provided mitigation measures are implemented and the proposed monitoring program is adequately carried out. The EMP includes measures to minimize project impacts due to noise and air pollution, waste generation etc.
558. This project has been assigned environmental category 'A' in accordance with the ADB's Safeguard Policy Statement (SPS) 2009 and Schedule II as per EPA, IEE and EIA Gazette Notification, 2000. Thus, a comprehensive EIA report has been prepared for the proposed project.

11 References

DesMobi, 2016. *Preliminary Design Report, Peshawar Bus Rapid Transit Project.*

Samina Islam, 2016, *Land Acquisition and Resettlement Plan for Peshawar BRT*

Bolt, Beranek, and Newman, Noise from Construction Equipment and Operations, Building Equipment, and Home Appliances. USEPA, 1971; <http://www.waterrights.ca.gov/EIRD/text/Ch11-Noise.pdf>; http://www.lacsd.org/LWRP%202020%20Facilities%20Plan%20DEIR/4_6_Noise.pdf; <http://newyorkbiz.com/DSEIS/CH18Construction.pdf>

http://www.catf.us/resources/publications/files/20120227-Diesel_vs_CNG_FINAL_MJBA.pdf

http://www.apti.org/clientuploads/publications/2015/Johnson-HannenHiRes_SampleArt_46.2-3.pdf

Gaffney, G. and Shimp, D. 1997. *Improving PM₁₀ Fugitive Dust Emission Inventories*. Sacramento, CA. California Air Resource Board. www.arb.ca.gov/emisinv/pubs/pm10tmp.pdf

El Dorado County Air Pollution Control District. 2002. Guide to Air Quality Assessment: Determining Significance of Air Quality Impacts Under the California Environmental Quality Act. First Edition. <http://co.el-dorado.ca.us/emd/apcd>

Reagan, J. A. and C. A. Grant. *Highway Construction Noise: Measurement, Prediction, and Mitigation. Special Report.* US. Department of Transportation, Federal Highway Administration. Available from <<http://www.fhwa.dot.gov/environment/noise/highway/index.htm>>

ADB 2011. *Involuntary Resettlement Safeguards :- A planning & Implementation Good Practice Source Book –Draft Working Document .* Asian Development Bank. March 2011

EPA, 1997: *Guidelines for Public Consultation.* Pakistan Environmental Protection Agency, Government of Pakistan

EPA, 1997: *Guidelines for Sensitive and Critical Areas.* Pakistan Environmental Protection Agency, Government of Pakistan, October

GoP, 1997: *Sectoral Guidelines for Environmental Reports:-* Environmental Protection Agency, Government of Pakistan, October

GoP, 1997: *Pakistan Environmental Protection Act 1997 :-* Government of Pakistan, October

GoP, 1997: *Policy Guidelines for Preparation and Review of Environmental Reports:-* Environmental Protection Agency, Government of Pakistan, November

GoP, 1997: *Policy and Procedures for filling , review and approval of Environmental Assessment :-* Environmental Protection Agency, Government of Pakistan, November

Survey of Pakistan, 1997. *Atlas of Pakistan.* Director Map Publication, Survey of Pakistan, Rawalpindi.

World Bank. 2005. *OP 4.10 - Indigenous People.* The World Bank Operational Manual. The World Bank. July 2005.

World Bank. 2003. *Social Analysis Sourcebook, Incorporating Social Dimensions into Bank-Supported Projects.* Social Development Department, The World Bank. December 2003.

World Bank. 2001. *OP 4.12 - Involuntary Resettlement.* The World Bank Operational

ANNEXES

ANNEX A

Rapid Environmental Assessment Checklist

Rapid Environmental Assessment (REA) Checklist

Instructions:

- (i) The project team completes this checklist to support the environmental classification of a project. It is to be attached to the environmental categorization form and submitted to the Environment and Safeguards Division (RSES), for endorsement by Director, RSES and for approval by the Chief Compliance Officer.
- (ii) This checklist focuses on environmental issues and concerns. To ensure that social dimensions are adequately considered, refer also to ADB's (a) checklists on involuntary resettlement and Indigenous Peoples; (b) poverty reduction handbook; (c) staff guide to consultation and participation; and (d) gender checklists.
- (iii) Answer the questions assuming the "without mitigation" case. The purpose is to identify potential impacts. Use the "remarks" section to discuss any anticipated mitigation measures.

Country/Project Title:

TA-8795 PAK: Peshawar Sustainable Bus Rapid Transit Corridor Project

Sector Division:

Development of Road transport infrastructure

Screening Questions	Yes	No	Remarks
A. Project Siting Is the project area adjacent to or within any of the following environmentally sensitive areas?			
▪ Cultural heritage site	√		The project alignment is located in close proximity (passes at a distance of 83 meters) from Bala Hisar Fort, which has historical and cultural significance.
▪ Protected Area		√	Not Applicable
▪ Wetland		√	Not Applicable
▪ Mangrove		√	Not Applicable
▪ Estuarine		√	Not Applicable
▪ Buffer zone of protected area		√	Not Applicable
▪ Special area for protecting biodiversity		√	Not Applicable
B. Potential Environmental Impacts Will the Project cause...			
▪ encroachment on historical/cultural areas; disfiguration of landscape by road embankments, cuts, fills, and quarries?	√		No historical or cultural areas will be encroached. However, disfiguration of landscape to a certain extent will take place, even though it will be short term and limited to the construction phase.

Screening Questions	Yes	No	Remarks
▪ encroachment on precious ecology (e.g. sensitive or protected areas)?		√	Not Applicable
▪ alteration of surface water hydrology of waterways crossed by roads, resulting in increased sediment in streams affected by increased soil erosion at construction site?		√	Not Applicable
▪ deterioration of surface water quality due to silt runoff and sanitary wastes from worker-based camps and chemicals used in construction?	√		The setting up of worker camps could lead to issues relating to sanitation and solid waste disposal. Strict implementation of necessary measures in the EMP will ensure the impacts are short term and limited to construction phase. Although no chemicals are expected to be used during the construction activity, however standard protocols as per NEQS shall be followed for proper disposal of any chemicals in case such a situation arises.
▪ increased local air pollution due to rock crushing, cutting and filling works, and chemicals from asphalt processing?	√		Increased air pollution resulting from breaking of existing concrete structures and cutting and filling works is expected. However, any impacts will be short term and limited to the construction phase.
▪ risks and vulnerabilities related to occupational health and safety due to physical, chemical, biological, and radiological hazards during project construction and operation during project construction and operation?	√		Keeping in view the highly urbanized and densely populated nature of the project corridor with a high proportion of sensitive receptors, the risks related to occupational health and safety during the construction phase do exist. However, any such impacts will be short term and limited to the construction phase with no long lasting impacts expected.
▪ noise and vibration due to blasting and other civil works?	√		No blasting is expected. However, other civil works during the construction phase will result in high noise levels. However, any resulting impacts will be short term and limited to the construction phase.
▪ dislocation or involuntary resettlement of people?	√		A limited number of houses and shops will be relocated and the affected persons will be offered houses and shops at alternative locations.
▪ dislocation and compulsory resettlement of people living in right-of-way?	√		A limited number of houses are located in the right-of-way of the proposed project and will be relocated and will be offered houses at alternative locations.

Screening Questions	Yes	No	Remarks
<ul style="list-style-type: none"> disproportionate impacts on the poor, women and children, Indigenous Peoples or other vulnerable groups? 		√	Not Applicable
<ul style="list-style-type: none"> other social concerns relating to inconveniences in living conditions in the project areas that may trigger cases of upper respiratory problems and stress? 	√		<p>Increased air pollution is expected consisting of high dust levels along with increased emissions of SO_x and NO_x due to increase vehicular movement. However, through effective implementation of the measures to be provided in the EMP, any impacts will be short term and limited to the construction phase.</p> <p>Similarly, necessary mitigation measures will also be provided for the operational phase of the project.</p>
<ul style="list-style-type: none"> hazardous driving conditions where construction interferes with pre-existing roads? 	√		Keeping in view the highly populated nature of the project corridor with a high proportion of sensitive receptors and the movement of heavy machinery and vehicles in the congested pre-existing roads could lead to possible hazardous driving conditions. However, implementation of a traffic management plan during the construction phase will mitigate any possible impacts.
<ul style="list-style-type: none"> poor sanitation and solid waste disposal in construction camps and work sites, and possible transmission of communicable diseases (such as STI's and HIV/AIDS) from workers to local populations? 	√		The setting up of worker camps could lead to issues relating to sanitation and solid waste disposal. Strict implementation of necessary measures in the EMP will ensure the impacts are short term and limited to construction phase.
<ul style="list-style-type: none"> creation of temporary breeding habitats for diseases such as those transmitted by mosquitoes and rodents? 	√		Temporary breeding habitats could be created from setting up of worker camps that could lead to issues relating to sanitation and solid waste disposal. Strict implementation of necessary measures in the EMP will ensure the impacts are short term and limited to construction phase.
<ul style="list-style-type: none"> accident risks associated with increased vehicular traffic, leading to accidental spills of toxic materials? 	√		It is anticipated that during project operation stage the BRT system will have a positive impact on safety in proximity of the BRT area. Segregated bus lane is significantly safer than mixed lanes. The project design should take into consideration the safer passenger access to stations.

Screening Questions	Yes	No	Remarks
<ul style="list-style-type: none"> increased noise and air pollution resulting from traffic volume? 	√		It is anticipated that introduction of BRT system will result in decreased noise and air pollution levels due to substitution of noisier and more polluting cars by modern buses, improved flow of car lanes, and congestion relief benefits.
<ul style="list-style-type: none"> increased risk of water pollution from oil, grease and fuel spills, and other materials from vehicles using the road? 	√		<p>The possible short-term impact of spills during the construction phase from vehicles and heavy machinery exists. However, the implementation of necessary measures in the EMP will ensure any impacts are controlled.</p> <p>Similarly, necessary mitigation measures for the operational phase of the project will be implemented.</p>
<ul style="list-style-type: none"> social conflicts if workers from other regions or countries are hired? 		√	No conflicts are expected since majority of the work force to be hired will be local labor
<ul style="list-style-type: none"> large population influx during project construction and operation that causes increased burden on social infrastructure and services (such as water supply and sanitation systems)? 		√	Majority of local work force is expected to be employed and thus large influx of people is not expected.
<ul style="list-style-type: none"> risks to community health and safety due to the transport, storage, and use and/or disposal of materials such as explosives, fuel and other chemicals during construction and operation? 	√		Keeping in view the high concentration of sensitive receptors in the project area, necessary mitigation measures in the project area will need to be implemented to ensure no long-term impacts take place relating to community health and safety. An Occupational health and safety plan will be developed and implemented to mitigate any potential impacts.
<ul style="list-style-type: none"> community safety risks due to both accidental and natural causes, especially where the structural elements or components of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning. 	√		The installation of elevated structures as part of the infrastructure development in highly populated parts of the project corridor carries the risk of structure failure. Similarly, the risks of accidents will also exist keeping in view the highly populated nature of the project area. However, the strict implementation of mitigation measures in the EMP will ensure any long-term impacts are prevented.

ANNEX B

NEQS Guidelines

Selected NEQS for Waste Effluents

Parameter	Unit	Maximum Permissible Concentration
Temperature (°C)	°C	42
Dissolved Oxygen (DO) (mg/l)	mg/l	6.0
5-day Biochemical Oxygen Demand (BOD ₅) (mg/l)	mg/l	10
Chemical Oxygen Demand (COD) (mg/l)	mg/l	100
Total Dissolved Solids (TDS) (mg/l)	mg/l	500
Total Suspended Solids (TSS) (mg/l)	mg/l	1000
Chlorine (mg/l)	mg/l	1
Free Chlorine Residual (mg/l)	mg/l	1
Ammonia Nitrogen (mg/l)	mg/l	1.0
Nitrate Nitrogen (mg/l)	mg/l	10
Nitrite Nitrogen (mg/l)	mg/l	1
Calcium (mg/l)	mg/l	100
Magnesium (mg/l)	mg/l	10
Iron (mg/l)	mg/l	10
Copper (mg/l)	mg/l	1.0
Lead (mg/l)	mg/l	0.1
Mercury (mg/l)	mg/l	0.01
Zinc (mg/l)	mg/l	10
Fluoride (mg/l)	mg/l	10
Total Hardness (mg/l)	mg/l	100
Chloride (mg/l)	mg/l	100
Sulfate (mg/l)	mg/l	100
Phosphate (mg/l)	mg/l	1.0
Barium (mg/l)	mg/l	1.0
Cadmium (mg/l)	mg/l	0.01
Cobalt (mg/l)	mg/l	1.0
Copper (mg/l)	mg/l	1.0
Lead (mg/l)	mg/l	0.1
Mercury (mg/l)	mg/l	0.01
Nickel (mg/l)	mg/l	1.0
Silver (mg/l)	mg/l	0.1
Vanadium (mg/l)	mg/l	1.0
Zinc (mg/l)	mg/l	10

Notes:

1. The above table is for reference only. The actual discharge limits should be determined by the local government authority of the effluent. The discharge limits should not be higher than the limits in this table.
2. The above table is for reference only. The actual discharge limits should be determined by the local government authority of the effluent. The discharge limits should not be higher than the limits in this table.
3. The above table is for reference only. The actual discharge limits should be determined by the local government authority of the effluent. The discharge limits should not be higher than the limits in this table.

National Environmental Quality Standards for Ambient Air

Pollutants	Time-Weighted Average	Concentration in Ambient Air		Ambient Concentration
		2014-2015 July 2015	2015-2016 July 2016	
Sulphur Dioxide (SO ₂)	Annual Average ¹	80 µg/m ³	80 µg/m ³	Classified "Reasonably good"
	24-hour ²	200 µg/m ³	200 µg/m ³	
Ozone (O ₃)	Annual Average ¹	60 µg/m ³	60 µg/m ³	Classified "Good"
	24-hour ²	120 µg/m ³	120 µg/m ³	
Carbon Dioxide (CO ₂)	1 year	380 µg/m ³	380 µg/m ³	Not subject to regulation
Carbon Monoxide (CO)	Annual Average ¹	100 µg/m ³	100 µg/m ³	High Volume Sampling Average from 2015 and 2016 only ³
	1 hour	1000 µg/m ³	1000 µg/m ³	
Respirable Particulate Matter (PM ₁₀)	Annual Average ¹	200 µg/m ³	200 µg/m ³	Classified "Good"
	24-hour ²	250 µg/m ³	250 µg/m ³	
Respirable Particulate Matter (PM _{2.5})	Annual Average ¹	25 µg/m ³	25 µg/m ³	Classified "Good"
	24-hour ²	50 µg/m ³	50 µg/m ³	
Nitrogen Dioxide (NO ₂)	Annual Average ¹	40 µg/m ³	40 µg/m ³	Classified "Good"
	1 hour	200 µg/m ³	200 µg/m ³	
Nitrogen Dioxide (NO ₂)	Annual Average ¹	10 µg/m ³	10 µg/m ³	Classified "Good"
	1 hour	200 µg/m ³	200 µg/m ³	
Lead (Pb)	Annual Average ¹	2 µg/m ³	2 µg/m ³	Classified "Good"
	1 hour	20 µg/m ³	20 µg/m ³	

¹ To be used with the following conditions: 1. The average concentration is to be calculated over a period of 24 hours and rounded up to the nearest 10 µg/m³.

² To be used with the following conditions: 1. The average concentration is to be calculated over a period of 24 hours and rounded up to the nearest 10 µg/m³.

Source: Government of Victoria (2014) (2015) (2016) (2017)

National Environmental Quality Standards for Noise¹

S/No.	Category of Area/Zone	Limit in dB(A) Leq	
		Day Time	Night Time
1	Residential area (A)	55	45
2	Commercial area (B)	65	55
3	Industrial area (C)	75	65
4	Silence zone (D)	50	45

1: Effective from 1st July, 2012.

Note: 1. Day time hours: 6 am to 10 pm

2. Night time hours: 10 pm to 6 am

3. Silence zone: Zones that are declared as such by the competent authority. An area comprising not less than 100 meters around hospitals, educational institutions and courts.

4. Mixed categories of areas may be declared as one of the four above mentioned categories by the competent authority.

National Environmental Quality Standards for Motor Vehicle Exhaust and Noise



doi:10.1371/journal.pone.0142011.g002

Project Details	Customer/Client	Phase	Est.	Act. Cost	Variance	Forecasted Final Cost	Comments
Project A	ABC Corp.	Phase 1	100	100	0		
		Phase 2	150	150	0		
		Phase 3	200	200	0		
Project B	DEF Ltd.	Phase 1	120	120	0		
		Phase 2	180	180	0		
		Phase 3	250	250	0		
		Phase 4	300	300	0		
		Phase 5	350	350	0		
Project C	GHI Inc.	Phase 1	110	110	0		
		Phase 2	160	160	0		
		Phase 3	210	210	0		
		Phase 4	260	260	0		
		Phase 5	310	310	0		
Project D	JKL Co.	Phase 1	130	130	0		
		Phase 2	190	190	0		
		Phase 3	240	240	0		
		Phase 4	290	290	0		
		Phase 5	340	340	0		
Project E	MNO Ltd.	Phase 1	140	140	0		
		Phase 2	200	200	0		
		Phase 3	260	260	0		
		Phase 4	320	320	0		
		Phase 5	380	380	0		
Project F	PQR Inc.	Phase 1	150	150	0		
		Phase 2	210	210	0		
		Phase 3	270	270	0		
		Phase 4	330	330	0		
		Phase 5	390	390	0		
Project G	STU Co.	Phase 1	160	160	0		
		Phase 2	220	220	0		
		Phase 3	280	280	0		
		Phase 4	340	340	0		
		Phase 5	400	400	0		
Project H	VWX Ltd.	Phase 1	170	170	0		
		Phase 2	230	230	0		
		Phase 3	290	290	0		
		Phase 4	350	350	0		
		Phase 5	410	410	0		
Project I	YZA Inc.	Phase 1	180	180	0		
		Phase 2	240	240	0		
		Phase 3	300	300	0		
		Phase 4	360	360	0		
		Phase 5	420	420	0		
Project J	BCD Co.	Phase 1	190	190	0		
		Phase 2	250	250	0		
		Phase 3	310	310	0		
		Phase 4	370	370	0		
		Phase 5	430	430	0		
Project K	EFG Ltd.	Phase 1	200	200	0		
		Phase 2	260	260	0		
		Phase 3	320	320	0		
		Phase 4	380	380	0		
		Phase 5	440	440	0		
Project L	HIJ Inc.	Phase 1	210	210	0		
		Phase 2	270	270	0		
		Phase 3	330	330	0		
		Phase 4	390	390	0		
		Phase 5	450	450	0		
Project M	KLM Co.	Phase 1	220	220	0		
		Phase 2	280	280	0		
		Phase 3	340	340	0		
		Phase 4	400	400	0		
		Phase 5	460	460	0		
Project N	NOP Ltd.	Phase 1	230	230	0		
		Phase 2	290	290	0		
		Phase 3	350	350	0		
		Phase 4	410	410	0		
		Phase 5	470	470	0		
Project O	QRS Inc.	Phase 1	240	240	0		
		Phase 2	300	300	0		
		Phase 3	360	360	0		
		Phase 4	420	420	0		
		Phase 5	480	480	0		
Project P	TUV Co.	Phase 1	250	250	0		
		Phase 2	310	310	0		
		Phase 3	370	370	0		
		Phase 4	430	430	0		
		Phase 5	490	490	0		
Project Q	WXY Ltd.	Phase 1	260	260	0		
		Phase 2	320	320	0		
		Phase 3	380	380	0		
		Phase 4	440	440	0		
		Phase 5	500	500	0		
Project R	ZAB Inc.	Phase 1	270	270	0		
		Phase 2	330	330	0		
		Phase 3	390	390	0		
		Phase 4	450	450	0		
		Phase 5	510	510	0		
Project S	CDE Co.	Phase 1	280	280	0		
		Phase 2	340	340	0		
		Phase 3	400	400	0		
		Phase 4	460	460	0		
		Phase 5	520	520	0		
Project T	FGH Ltd.	Phase 1	290	290	0		
		Phase 2	350	350	0		
		Phase 3	410	410	0		
		Phase 4	470	470	0		
		Phase 5	530	530	0		
Project U	IJK Inc.	Phase 1	300	300	0		
		Phase 2	360	360	0		
		Phase 3	420	420	0		
		Phase 4	480	480	0		
		Phase 5	540	540	0		
Project V	LMN Co.	Phase 1	310	310	0		
		Phase 2	370	370	0		
		Phase 3	430	430	0		
		Phase 4	490	490	0		
		Phase 5	550	550	0		
Project W	OPQ Ltd.	Phase 1	320	320	0		
		Phase 2	380	380	0		
		Phase 3	440	440	0		
		Phase 4	500	500	0		
		Phase 5	560	560	0		
Project X	RST Inc.	Phase 1	330	330	0		
		Phase 2	390	390	0		
		Phase 3	450	450	0		
		Phase 4	510	510	0		
		Phase 5	570	570	0		
Project Y	UVW Co.	Phase 1	340	340	0		
		Phase 2	400	400	0		
		Phase 3	460	460	0		
		Phase 4	520	520	0		
		Phase 5	580	580	0		
Project Z	XYZ Ltd.	Phase 1	350	350	0		
		Phase 2	410	410	0		
		Phase 3	470	470	0		
		Phase 4	530	530	0		
		Phase 5	590	590	0		
Project AA	PQR Inc.	Phase 1	360	360	0		
		Phase 2	420	420	0		
		Phase 3	480	480	0		
		Phase 4	540	540	0		
		Phase 5	600	600	0		
Project AB	STU Co.	Phase 1	370	370	0		
		Phase 2	430	430	0		
		Phase 3	490	490	0		
		Phase 4	550	550	0		
		Phase 5	610	610	0		
Project AC	VWX Ltd.	Phase 1	380	380	0		
		Phase 2	440	440	0		
		Phase 3	500	500	0		
		Phase 4	560	560	0		
		Phase 5	620	620	0		
Project AD	YZA Inc.	Phase 1	390	390	0		
		Phase 2	450	450	0		
		Phase 3	510	510	0		
		Phase 4	570	570	0		
		Phase 5	630	630	0		
Project AE	BCD Co.	Phase 1	400	400	0		
		Phase 2	460	460	0		
		Phase 3	520	520	0		
		Phase 4	580	580	0		
		Phase 5	640	640	0		
Project AF	EFG Ltd.	Phase 1	410	410	0		
		Phase 2	470	470	0		
		Phase 3	530	530	0		
		Phase 4	590	590	0		
		Phase 5	650	650	0		
Project AG	HIJ Inc.	Phase 1	420	420	0		
		Phase 2	480	480	0		
		Phase 3	540	540	0		
		Phase 4	600	600	0		
		Phase 5	660	660	0		
Project AH	KLM Co.	Phase 1	430	430	0		
		Phase 2	490	490	0		
		Phase 3	550	550	0		
		Phase 4	610	610	0		
		Phase 5	670	670	0		
Project AI	NOP Ltd.	Phase 1	440	440	0		
		Phase 2	500	500	0		
		Phase 3	560	560	0		
		Phase 4	620	620	0		
		Phase 5	680	680	0		
Project AJ	QRS Inc.	Phase 1	450	450	0		
		Phase 2	510	510	0		
		Phase 3	570	570	0		
		Phase 4	630	630	0		
		Phase 5	690	690	0		
Project AK	TUV Co.	Phase 1	460	460	0		
		Phase 2	520	520	0		
		Phase 3	580	580	0		
		Phase 4	640	640	0		
		Phase 5	700	700	0		
Project AL	WXY Ltd.	Phase 1	470	470	0		
		Phase 2	530	530	0		
		Phase 3	590	590	0		
		Phase 4	650	650	0		
		Phase 5	710	710	0		
Project AM	ZAB Inc.	Phase 1	480	480	0		
		Phase 2	540	540	0		
		Phase 3	600	600	0		
		Phase 4	660	660	0		
		Phase 5	720	720	0		
Project AN	CDE Co.	Phase 1	490	490	0		
		Phase 2	550	550	0		
		Phase 3	610	610	0		
		Phase 4	670	670	0		
		Phase 5	730	730	0		
Project AO	FGH Ltd.	Phase 1	500	500	0		
		Phase 2	560	560	0		
		Phase 3	620	620	0		
		Phase 4	680	680	0		
		Phase 5	740	740	0		
Project AP	IJK Inc.	Phase 1	510	510	0		
		Phase 2	570	570	0		
		Phase 3	630	630	0		
		Phase 4	690	690	0		
		Phase 5	750	750	0		
Project AQ	LMN Co.	Phase 1	520	520	0		
		Phase 2	580	580	0		
		Phase 3	640	640	0		
		Phase 4	700	700	0		
		Phase 5	760	760	0		
Project AR	OPQ Ltd.	Phase 1	530	530	0		
		Phase 2	590	590	0		
		Phase 3	650	650	0		
		Phase 4	710	710	0		
		Phase 5	770	770	0		
Project AS	RST Inc.	Phase 1	540	540	0		
		Phase 2	600	600	0		
		Phase 3	660	660	0		
		Phase 4	720	720	0		
		Phase 5	780	780	0		
Project AT	UVW Co.	Phase 1	550	550	0		
		Phase 2	610	610	0		
		Phase 3	670	670	0		
		Phase 4	730	730	0		
		Phase 5	790	790	0		
Project AU	XYZ Ltd.	Phase 1	560	560	0		
		Phase 2	620	620	0		
		Phase 3	680	680	0		
		Phase 4	740	740	0		
		Phase 5	800	800	0		
Project AV	PQR Inc.	Phase 1	570	570	0		
		Phase 2	630	630	0		
		Phase 3	690	690	0		
		Phase 4	750	750	0		
		Phase 5	810	810	0		
Project AW	STU Co.	Phase 1	580	580	0		
		Phase 2	640	640	0		
		Phase 3	700	700	0		
		Phase 4	760	760	0		
		Phase 5	820	820	0		
Project AX	VWX Ltd.	Phase 1	590	590	0		
		Phase 2	650	650	0		
		Phase 3	710	710	0		
		Phase 4	770	770	0		
		Phase 5	830	830	0		
Project AY	YZA Inc.	Phase 1	600	600	0		
		Phase 2	660	660	0		
		Phase 3	720	720	0		
		Phase 4	780	780	0		
		Phase 5	840	840	0		
Project AZ	BCD Co.	Phase 1	610	610	0		
		Phase 2	670	670	0		
		Phase 3	730	730	0		
		Phase 4	790	790	0		
		Phase 5	850	850	0		
Project BA	EFG Ltd.	Phase 1	620	620	0		
		Phase 2	680	680	0		
		Phase 3	740	740	0		
		Phase 4	800	800	0		
		Phase 5	860	860	0		
Project BB	HIJ Inc.	Phase 1	630	630	0		
		Phase 2	690	690	0		
		Phase 3	750	750	0		
		Phase 4	810	810</			

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.

[illegible]

► *How to Use This Book*

[illegible]

- 1 **Future impacts**
 2 **Individuals involved**
 3 **What has been done to date?**
 4 **Impact**
 5 **Future plans**
 6 **References**
 7 **Appendix**
 8 **Notes**
 9 **Summary**
 10 **Conclusion**
 11 **References**
 12 **Appendix**
 13 **Notes**
 14 **Summary**
 15 **Conclusion**
 16 **References**
 17 **Appendix**
 18 **Notes**
 19 **Summary**
 20 **Conclusion**
 21 **References**
 22 **Appendix**
 23 **Notes**
 24 **Summary**
 25 **Conclusion**
 26 **References**
 27 **Appendix**
 28 **Notes**
 29 **Summary**
 30 **Conclusion**
 31 **References**
 32 **Appendix**
 33 **Notes**
 34 **Summary**
 35 **Conclusion**
 36 **References**
 37 **Appendix**
 38 **Notes**
 39 **Summary**
 40 **Conclusion**
 41 **References**
 42 **Appendix**
 43 **Notes**
 44 **Summary**
 45 **Conclusion**
 46 **References**
 47 **Appendix**
 48 **Notes**
 49 **Summary**
 50 **Conclusion**
 51 **References**
 52 **Appendix**
 53 **Notes**
 54 **Summary**
 55 **Conclusion**
 56 **References**
 57 **Appendix**
 58 **Notes**
 59 **Summary**
 60 **Conclusion**
 61 **References**
 62 **Appendix**
 63 **Notes**
 64 **Summary**
 65 **Conclusion**
 66 **References**
 67 **Appendix**
 68 **Notes**
 69 **Summary**
 70 **Conclusion**
 71 **References**
 72 **Appendix**
 73 **Notes**
 74 **Summary**
 75 **Conclusion**
 76 **References**
 77 **Appendix**
 78 **Notes**
 79 **Summary**
 80 **Conclusion**
 81 **References**
 82 **Appendix**
 83 **Notes**
 84 **Summary**
 85 **Conclusion**
 86 **References**
 87 **Appendix**
 88 **Notes**
 89 **Summary**
 90 **Conclusion**
 91 **References**
 92 **Appendix**
 93 **Notes**
 94 **Summary**
 95 **Conclusion**
 96 **References**
 97 **Appendix**
 98 **Notes**
 99 **Summary**
 100 **Conclusion**
 101 **References**
 102 **Appendix**
 103 **Notes**
 104 **Summary**
 105 **Conclusion**
 106 **References**
 107 **Appendix**
 108 **Notes**
 109 **Summary**
 110 **Conclusion**
 111 **References**
 112 **Appendix**
 113 **Notes**
 114 **Summary**
 115 **Conclusion**
 116 **References**
 117 **Appendix**
 118 **Notes**
 119 **Summary**
 120 **Conclusion**
 121 **References**
 122 **Appendix**
 123 **Notes**
 124 **Summary**
 125 **Conclusion**
 126 **References**
 127 **Appendix**
 128 **Notes**
 129 **Summary**
 130 **Conclusion**
 131 **References**
 132 **Appendix**
 133 **Notes**
 134 **Summary**
 135 **Conclusion**
 136 **References**
 137 **Appendix**
 138 **Notes**
 139 **Summary**
 140 **Conclusion**
 141 **References**
 142 **Appendix**
 143 **Notes**
 144 **Summary**
 145 **Conclusion**
 146 **References**
 147 **Appendix**
 148 **Notes**
 149 **Summary**
 150 **Conclusion**
 151 **References**
 152 **Appendix**
 153 **Notes**
 154 **Summary**
 155 **Conclusion**
 156 **References**
 157 **Appendix**
 158 **Notes**
 159 **Summary**
 160 **Conclusion**
 161 **References**
 162 **Appendix**
 163 **Notes**
 164 **Summary**
 165 **Conclusion**
 166 **References**
 167 **Appendix**
 168 **Notes**
 169 **Summary**
 170 **Conclusion**
 171 **References**
 172 **Appendix**
 173 **Notes**
 174 **Summary**
 175 **Conclusion**
 176 **References**
 177 **Appendix**
 178 **Notes**
 179 **Summary**
 180 **Conclusion**
 181 **References**
 182 **Appendix**
 183 **Notes**
 184 **Summary**
 185 **Conclusion**
 186 **References**
 187 **Appendix**
 188 **Notes**
 189 **Summary**
 190 **Conclusion**
 191 **References**
 192 **Appendix**
 193 **Notes**
 194 **Summary**
 195 **Conclusion**
 196 **References**
 197 **Appendix**
 198 **Notes**
 199 **Summary**
 200 **Conclusion**
 201 **References**
 202 **Appendix**
 203 **Notes**
 204 **Summary**
 205 **Conclusion**
 206 **References**
 207 **Appendix**
 208 **Notes**
 209 **Summary**
 210 **Conclusion**
 211 **References**
 212 **Appendix**
 213 **Notes**
 214 **Summary**
 215 **Conclusion**
 216 **References**
 217 **Appendix**
 218 **Notes**
 219 **Summary**
 220 **Conclusion**
 221 **References**
 222 **Appendix**
 223 **Notes**
 224 **Summary**
 225 **Conclusion**
 226 **References**
 227 **Appendix**
 228 **Notes**
 229 **Summary**
 230 **Conclusion**
 231 **References**
 232 **Appendix**
 233 **Notes**
 234 **Summary**
 235 **Conclusion**
 236 **References**
 237 **Appendix**
 238 **Notes**
 239 **Summary**
 240 **Conclusion**
 241 **References**
 242 **Appendix**
 243 **Notes**
 244 **Summary**
 245 **Conclusion**
 246 **References**
 247 **Appendix**
 248 **Notes**
 249 **Summary**
 250 **Conclusion**
 251 **References**
 252 **Appendix**
 253 **Notes**
 254 **Summary**
 255 **Conclusion**
 256 **References**
 257 **Appendix**
 258 **Notes**
 259 **Summary**
 260 **Conclusion**
 261 **References**
 262 **Appendix**
 263 **Notes**
 264 **Summary**
 265 **Conclusion**
 266 **References**
 267 **Appendix**
 268 **Notes**
 269 **Summary**
 270 **Conclusion**
 271 **References**
 272 **Appendix**
 273 **Notes**
 274 **Summary**
 275 **Conclusion**
 276 **References**

National Standards for Drinking Water Quality

Product/Service	Product Name/Service
Product A	Product A
Product B	Product B
Product C	Product C
Product D	Product D
Product E	Product E
Product F	Product F
Product G	Product G
Product H	Product H
Product I	Product I
Product J	Product J
Product K	Product K
Product L	Product L
Product M	Product M
Product N	Product N
Product O	Product O
Product P	Product P
Product Q	Product Q
Product R	Product R
Product S	Product S
Product T	Product T
Product U	Product U
Product V	Product V
Product W	Product W
Product X	Product X
Product Y	Product Y
Product Z	Product Z

© 2004 The Authors
Journal compilation © 2004 Blackwell Publishing Ltd
Journal of Internal Medicine 255: 103–110

ANNEX C

Photographs of Public Consultations

Public Consultations with key Stakeholders in Project Area



Photograph 11-1: Consultation with local trader Mr Abdullah



Photograph 11-2: Consultation with local trader Mr Zawar



Photograph 11-3: Consultation with local trader Mr Afnan Khattak



Photograph 11-4: Discussion with Registrar of Islamia College - Peshawar



Photograph 11-5: Consultation with local trader Mr Ghulam Sabir Butt



Photograph 11-6: Consultation with local trader Mr Haji Rehman



Photograph 11-7: Consultation with MD, Hayatabad Medical Complex (HMC)



Photograph 11-8: Consultation with local trader Mr Amir Gul



Photograph 11-9: Consultation with HMC Admin and Senior medical staff



Photograph 11-10: Consultation with HMC Admin and Senior medical staff



Photograph 11-11: Consultation with Brig (Retd) Fazle Akbar, director of KTH



Photograph 11-12: Consultation with Mr Tahir Shah from Khyber Teaching Hospital (KTH)



Photograph 11-13: Consultation with local trader Mr Mohammad Zubair on University Road



Photograph 11-14: Consultation with local trader Mr Waleed Riaz Sader



Photograph 11-15: Consultation with Mr Sabir Jagra, administration at Lady Reading Hospital (LRH)



Photograph 11-16: Consultation with local trader Mr Zahid Shah Sader



Photograph 11-17: Consultation with ICMS school administration Mr Zahid-ur-Rehman



Photograph 11-18: Consultation with local trader Mr Shabir Ahmed



Photograph 11-19: Consultation with local trader Mr Niaz Mohammad



Photograph 11-20: Consultation with Mr Adnan from health care center along project corridor



Photograph 11-21: Consultation with administration of Agha Khal hospital



Photograph 11-22: Consultation with local trader Mr Naveed Ahmad



Photograph 11-23: Consultation with local trader Mr Noor Ahmad



Photograph 11-24: Consultation with local trader Mr Majid Khan



Photograph 11-25: Meeting with PDA project focal staff



Photograph 11-26: Consultation meeting with representatives from project Affected Persons



Photograph 11-27: Consultation meeting with representatives from project Affected Persons



Photograph 11-28: Consultation meeting with representatives from project Affected Persons



Photograph 11-29: Resettlement Specialist conducting consultations with APs of Western depot site



Photograph 11-30: Consultations with officials of Government Food Department



Photograph 11-31: Consultations with PDA staff at Eastern depot site



Photograph 11-32: Consultations with Patwaris at Eastern depot site



Photograph 11-33: Consultations with APs of western depot site non-title holders



Photograph 11-34: Consultations with local communities in project area



Photograph 11-35: Consultations with local communities in project area



Photograph 11-36: Consultation with local watch vendor in project area

ANNEX D

Noise Levels at Key Receptors during Operation Phase

Redwood Bay Coastal Hazards Characterisation Project


Project No:
 Redwood Bay Coastal
 Hazards Characterisation Project


Amendment:
 1/1
 Sheet 1 of 11


Project Manager: (Name)


Drawing Name:
 Post Code Character


- Legend**
- Proposed Future Land
 - Proposed Future Road
 - 10-20%
 - 20-30%
 - 30-40%
 - 40-50%
 - 50-60%
 - 60-70%
 - 70-80%
 - > 80%
 - Beach Zone
 - Redwood Bay Coastal
 - Redwood Bay Coastal
 - Redwood Bay Coastal




































ANNEX E


Noise Levels at Key Receptors during Construction Phase














Proyecto: Bosque de **Reserva Ecológica de la zona 1**

Objetivo del Proyecto:
 Implementar un sistema de monitoreo y conservación del Bosque de Reserva Ecológica de la zona 1.

Metas del Proyecto:
 1. 100% de cumplimiento de los objetivos.
 2. 100% de cumplimiento de los plazos.

Metas del Proyecto:
 1. 100% de cumplimiento de los objetivos.


Metas del Proyecto:
 1. 100% de cumplimiento de los objetivos.

Objetivo del Proyecto:
 Implementar un sistema de monitoreo y conservación del Bosque de Reserva Ecológica de la zona 1.

Metas del Proyecto:
 1. 100% de cumplimiento de los objetivos.
 2. 100% de cumplimiento de los plazos.

Metas del Proyecto:
 1. 100% de cumplimiento de los objetivos.
 2. 100% de cumplimiento de los plazos.

Metas del Proyecto:
 1. 100% de cumplimiento de los objetivos.
 2. 100% de cumplimiento de los plazos.



Proyecto: El Bosque Estudio de Impacto Ambiental


Objetivo:
 Identificar las áreas de mayor sensibilidad ambiental y determinar las medidas de mitigación necesarias para protegerlas durante la ejecución del proyecto.


Alcance:
 El estudio se limitará a las áreas directamente afectadas por las actividades del proyecto, así como a las zonas de influencia inmediata.

Fecha de actualización:
 15 de mayo de 2024

Elaborado por:
 Equipo de Ingeniería Ambiental

- Legenda:**
- Área de Impacto Ambiental
 - Zona de Protección Ambiental
 - Zona de Impacto
 - Zona de Influencia
 - Zona de Sensibilidad Ambiental
 - Zona de Protección Especial
 - Zona de Impacto Directo
 - Zona de Impacto Indirecto
 - Zona de Impacto Residual
 - Zona de Impacto Total






Planning for Tunnel Construction Risks


Working Title
 Virtual Risk Library
 Date: 01/01/2014


Project Name
 1st and 2nd of 2

Working Title
 Working Title
 Working Title

- Legend
- Construction Area
 - Construction Area
 - Construction Area
 - Construction Area
 - Construction Area
 - Construction Area
 - Construction Area
 - Construction Area
 - Construction Area











ANNEX F


‘Post Mitigation’ Noise Levels at Key Receptors during Construction Phase














Map of the Pinar del Rio Watershed

Legend:


- Forest (green)
- Pasture (yellow)
- Urban (brown)
- Pinar del Rio Watershed boundary (red dashed line)
- Pinar del Rio Watershed sub-watershed boundary (blue dashed line)


Scale: 0 to 10 km


North Arrow: [North Arrow]


Map Date: 2011


Map Author: [Author Name]


























ANNEX G

LIST OF PARTICIPANTS OF PUBLIC CONSULTATIONS

Public Consultations for development of Peshawar Sustainable Bus Rapid Transit Corridor Project					
S/No.	Name	Contact No.	CNIC (if available)	Name of Shop/Business	Location/Address of Interview
1.	Ghulam Sabir Butt	0321-9040847	-	Saqib corporation	6B Madni Market Khyber bazar
2.	H. Abdul Rehman	0334-0000387	-	Khyber Water Tank	S#10 Khyber bazar
3.	Afnan Khattak	0336-9009009	-	Khyber Pipe Industry	Khyber bazar
4.	Amir Gul	0335-9394700	-	Shayan pipe industry	Khyber bazar
5.	Shakir Ahmed	0300-5886265	-	Amir autos	Railway road shuba chowk
6.	Abdullah	0345-9407506	-	Haider Sanitary	Soicarno square Khyber bazar
7.	Zawar Noor	0300-5948414	17301-8313443-8	National Welfare for disable people.	Hayat abad
8.	Sayed kamal shah	0346-7778933	17301-1553132-1	Sr clerk	GGHS Nishtar abad
9.	Madam Anisa Goher	0344-9092740	17301-8313443-8	Principle	GGHS & college Nishtar abad
10.	Adnan khan	0346-0952636	-	GBO at UBL	Hashtnagri
11.	Irfan Nadeem	0333-9141218	-	Manager at UBL	Hashtnagri
12.	Farooq Shah	0321-9195072	-	Teacher high school no 2	Hashtnagri
13.	Imdad Khan	0300-9323231	17301-1452249-7	Teacher GS no1	Hashtnagri

14.	Imdad Khalil	0300-9152182	-	Arco Paint	Hashtnagri
15.	Javed Khan	0333-9114771	-	Royal Mobile	Hashtnagri
16.	M Ghafoor	0343-4520705	-	Shah Autos	S# 29 Balahisar
17.	Hassan Khan	0312-5994247	17301-6628104-7	Hassan autos	S#34 Balahisar
18.	Mobeen Ahmad	-	-	Mobeen autos	S# 38Balahisar
19.	Pervez khan aka Habib Ullah	0321-9003245	17301-1533753-3	Habib Autos	Near frontier College LRH Road
20.	Naseem Iqbal	0333-9134220	-	Manager Ali medical center	LRH road
21.	Nigah Husain	091-2211273	-	Forward High School (girls Branch)	LRH Road
22.	Orangzaib khan	0300-9330007	-	President of medical association LRH Road	LRH road near kabli chowk
23.	Aziz Rehman khattak	091-2212894	-	Khattak Optico	LRH road near kabli chowk
24.	Fazlullah khan	091-2212534	17301-1483161-1	Owner University Books	Main Khyber bazaar Road
25.	Inamullah	0312-0110000	17301-1674370-9	Manager University Books	Main Khyber Bazar
26.	Faraz Ahmed	091-2211414	-	Ays Electronic	Main Khyber bazaar road
27.	Haji aurangzaib	0300-5907000	-	President of jewelers association Peshawar	Main interior Bazar peshawar

28.	M Adnan	0300-5987606	-	Adnan jewelry	Main interior Bazar peshawar
29.	Zalan Bakhtiar	0300-9392191	-	Zalan jewelry	Main interior Bazar peshawar
30.	Zakir Shah	0333-9118226	-	Albasit jewelers	Main interior peshawar
31.	Faheem Khan	0300-9118226	-	Jhanzaib Jewelry	Main interior Bazar peshawar
32.	Javed Khan	0300-5925125	-	Javed jewelers	Main interior Bazar peshawar
33.	Irfan Ullah	0311-9997581	17301-6228670-1	Total Parco petrol pump	Sardar gari chamkni Road
34.	Zahid ur Rehman	0332-9444935	17301-5945626-3	ICMS school system	Chamkani
35.	Gulshad khan	0300-5995065	-	-	-
36.	Mohammad Abdul Akbar	0333-910081	-	Ex MNA Chitral mohtamim Darul Aloom Islamia	
37.	Mohammad Jameel	0300-59004966	17301-0327957-1	Jameel Spare Parts	Chamkani
38.	Shabir Ahmed	091-2650585	17201-8710197-5	Ever green pump	Chughalpura
39.	Niaz Mouhammad	0313-9534090	17301-7845308-9	Mechanic	Chughal pura
40.	Mouhammad Adnan	0332-9094276	17301-5097874-7	Eastern Teaching hospital	Chamkani road chughal pura
41.	Dr Abdul Qayum	0333-9212104	17301-9030468-7	Agha khan Hospital	GT road
42.	Shahbaz Ali	0323-5500377	15201-4372025-3	Agha khan Hospital	GT road

43.	Sohrab Khan	0332-9247274	17301-7132730-9	Agha khan Hospital	GT road
44.	Sardar Ali	0345-9221505	15202-0835165-9	Agha khan Hospital	GT road
45.	Naveed Ali shah	0345-4445080	17301-7132730-9	Modern Battery	GT road Raees hotel
46.	Sabz Ali shah	0333-4923823	-	Daewoo bus service	GT Road
47.	Atlas Khan	0333-9044226	-	GHS no1	Hashtnagri
48.	Shams ur rehman	0300-5885639	-	Director finance	LRH
49.	Sabir jagra	0311-9684913	17301-4504737-3	PA Director HR	LRH
50.	Jalal Ahmed	-	17301-7395106-9	HR officer	LRH
51.	Mouhammad Shabir	0334-9057210	21201-1901665-3	Sr stenographer	LRH
52.	Mohammad salim	0301-8862068	17301-514722-1	Office asst	LRH
53.	Sultan khattak	-	-	Dealing asst	LRH
54.	Adnan Majeed	17101-4634534-5	0306-5916166	HR officer	LRH
55.	Ahsan Ali shah	0335-9222292	17301-5489653-9	Administration	LRH
56.	Mohammad Rafiq	0321-8131313	-	Umer pharmacy	LRH road
57.	Sher Haider Khan	0336-9377022	15201-2249227-9	Saeed anwar medical hospital	Dabgari garden
58.	Akhter	0321-9035606	-	Manager Saeed anwar medical center	Dabgari garden

59.	Shareef Gul	0333-9122849	17301-2283284-3	Principle GHS Saqib Ghani	Civil quarter
60.	Irshad ahmed	03015944340	17301-0242242-7	Sr. Teacher GHS Saqib Ghani	Civil quarter
61.	Ibrahim Khan	0345-9395810	16202-0355423-7	Gold palace jewelry	Sonehri Masjid Nothia
62.	Amjad Ahmed	0321-2474725	17301-1171491-8	Hamdard Dawa Khana	Notha
63.	Zahid Shah	0301-8516611	17301-3506311-9	Manager Samsung Shop.	Peshawar cantt.
64.	Waleed Riaz	0300-5898956	17301-6622616-1	Mobile shop	Peshawar cantt.
65.	Amjid khan	0315-9159151	17301-9622616-1	Security guard company	Peshawar cantt.
66.	Aziz khan	0331-9399934	17301-1333148-5	Employee Mobile local repair shop.	Peshawar cantt.
67.	Mohammad Zubair	0333-9264448	16101-71566525	Manager Bata shoes franchise	University Road
68.	Kashif Ullah	0333-9307350	-	Maintenance engineer KTH	KTH university road
69.	Riaz Ullah	091-9224257	-	PA to Medical Director KTH	KTH University Road
70.	Tahir Shah	0333-3476668	17301-3391774-5	Account Asst KTH	KTH University Road
71.	Shams Ul Haq	0333-9137633	17301-2900087-9	Sr Clark KTH	KTH University Road
72.	Farhad Khan	0333-9109847	-	PRO KTH	KTH University Road
73.	Brig(r) Fazle Akbar	091-9224422	-	Director of KTH	KTH University Road

		03345014142			
74.	Alamgir Khan	0313-9447878	-	Super General Store	University Road Peshawar.
75.	Jamshaid Khan	0336-5907419	17301-1533754-1	Mansur photo state Shop,	Board road Peshawar.
76.	Prof Shehzad	0345-9222202	-	HD/MD HMC	HMC (Hayatabad Medical Complex)
77.	Usman Khan	0344-9294077	-	PA to MD	HMC (Hayatabad Medical Complex)
78.	Dr Nasir Hassan	-	-	Coordination Officer	HMC (Hayatabad Medical Complex)
79.	Muhammad junaid	0333-9169280	-	Admin dept at Shaukat Khanum Hospital - Peshawar	Hayatabad
80.	Saif ullah	0334-8122344	-	Admin dept at Shaukat Khanum Hospital - Peshawar	Hayatabad
81.	Abdul hameed	0300-5677834	-	Admin dept at Shaukat Khanum Hospital - Peshawar	Hayatabad

ANNEX H

PHOTOGRAPHS OF LANDMARKS ALONG PROJECT CORRIDOR



Photograph 11-1: High traffic congestion at Khyber Bazar



Photograph 11-2: Entrance of Khyber Teaching Hospital (KTH)



Photograph 11-3: ICMS building on University Road



Photograph 11-4: Existing residents next to project boundary are in the construction business and own their own construction trucks



Photograph 11-5: The project site contains little vegetation cover primarily containing wild grasses



Photograph 11-6: A view of Tatara Park



Photograph 11-7: A view of Hashnagri



Photograph 11-8: Govt Shaheed Haider Ameen High School



Photograph 11-9: Entrance to Accident and Emergency Department of Lady Reading Hospital



Photograph 11-10: Soekarno Square with PAK Medical Center and Hospital visible in the distance



Photograph 11-11: Govt Shaheed Mobeen Shah Higher Secondary School



Photograph 11-12: Forward High School



Photograph 11-13: Shaukat Khanum Hospital



Photograph 11-14: Board of Intermediate and Secondary Education - Peshawar



Photograph 11-15: Building of Islamia University seen in the distance



Photograph 11-16: Entrance to Islamia College - Peshawar



Photograph 11-17: SOS Children's Village located next to Shaukat Khanum Hospital - Peshawar



Photograph 11-18: View of existing roads along BRT route where project will be developed

ANNEX I

SAMPLE AIR DISPERSION MODEL OUTPUT FILES

CAL3QHCR - (DATED 95221)

CAL3QHCR PC (32 BIT) VERSION 3.1.1

(C) COPYRIGHT 1993-2001

Run Began on 11/30/2016 at 13:52:37

DATE : 11/30/2016

PAGE: 1

TIME : 13:52:37

JOB: BRT PESHAWAR

RUN:

=====

General Information

=====

Run start date: 1/ 1/15 Julian: 1

end date: 12/31/15 Julian: 365

A Tier 1 approach was used for input data preparation.

The MODE flag has been set to C for calculating CO averages.

Ambient background concentrations are included in the averages below.

Site & Meteorological Constants

VS = 0.0 CM/S VD = 0.0 CM/S ZO = 100. CM ATIM = 60.

Met. Sfc. Sta. Id & Yr = 15 15

Upper Air Sta. Id & Yr = 1 15

Urban mixing heights were processed.

In 2015, Julian day 1 is a Thursday.

Link Data Constants - (Variable data in *.LNK file)

LINK DESCRIPTION	* LINK COORDINATES (M)	* LENGTH	BRG	TYPE	H	W	NLANES
* X1 Y1 X2 Y2	* (M) (DEG) (M) (M)						
1. CHAMKNAI CHOWK	* 8143.2 2938.6 8061.9 2938.6	* 81.	270.	AG	0.0	8.0	2
2. S-1	* 8061.9 2938.6 7365.4 2880.6	* 699.	265.	AG	0.0	8.0	
3. CHUGAL PURA (BS-2)	* 7365.4 2880.6 7265.0 2841.2	* 108.	249.	AG	0.0	8.0	2
4. S-2	* 7265.0 2841.2 6812.2 2812.2	* 454.	266.	AG	0.0	8.0	
5. DR ZAREEF MEMORIAL S	* 6812.2 2812.2 6765.8 2818.0	* 47.	277.	AG	0.0	8.0	2
6. S-3	* 6765.8 2818.0 6481.4 2823.8	* 284.	271.	AG	0.0	8.0	
7. SETHI TOWN (BS-04)	* 6481.4 2823.8 6469.8 2823.8	* 12.	270.	AG	0.0	8.0	2
8. S-4	* 6469.8 2823.8 6197.0 2812.2	* 273.	268.	AG	0.0	8.0	
9. SKANDER TOWN (BS-05)	* 6197.0 2812.2 6150.5 2818.0	* 47.	277.	AG	0.0	8.0	2
10. S-05	* 6150.0 2818.0 5906.7 2823.8	* 243.	271.	AG	0.0	8.0	
11. GULBAHAR SQR (BS-06)	* 5906.7 2823.8 5831.3 2829.6	* 76.	274.	AG	0.0	8.0	2
12. S-06	* 5831.3 2829.6 5604.9 2812.2	* 227.	266.	AG	0.0	8.0	
13. HASHNAGRI (BS-07)	* 5604.9 2812.2 5517.8 2800.5	* 88.	262.	AG	0.0	8.0	2
14. S-07	* 5517.8 2800.5 5326.3 2812.2	* 192.	273.	AG	0.0	8.0	
15. QILA BAAHSAR (BS-08)	* 5326.3 2812.2 5262.4 2823.8	* 65.	280.	AG	0.0	8.0	2

CAL3QHCR+ (Dated: 95221)

DATE : 11/30/2016

PAGE: 2

TIME : 13:52:37

JOB: BRT PESHAWAR

RUN:

Link Data Constants - (Variable data in *.LNK file)

LINK DESCRIPTION	* LINK COORDINATES (M)	* LENGTH	BRG	TYPE	H	W	NLANES
------------------	------------------------	----------	-----	------	---	---	--------

	* X1	Y1	X2	Y2	* (M)	(DEG)	(M)	(M)	
16. S-09	*	5262.4	2823.8	5152.2	2812.2	*	111.	264.	AG 0.0 8.0
17. HOSPITAL RD (BS-09)	*	5152.2	2812.2	5117.3	2609.0	*	206.	190.	AG 0.0 8.0 2
18. S-09	*	5117.3	2609.0	5105.7	2568.4	*	42.	196.	AG 0.0 8.0
19. KHYBER BAZAR(BS-10)	*	5105.7	2568.4	4925.8	2539.3	*	182.	261.	AG 0.0 8.0 2
20. S-10	*	4925.8	2539.3	4891.0	2574.2	*	49.	315.	AG 0.0 8.0
21. SOEKARNO SQR(BS-11)	*	4891.0	2574.2	4850.3	2585.8	*	42.	286.	BR 10.0 8.0 2
22. S-11	*	4850.3	2585.8	4613.3	2391.3	*	307.	231.	AG 0.0 8.0
23. DABGR GARDEN (BS-12)	*	4613.3	2391.3	4530.2	2333.2	*	101.	235.	BR 10.0 8.0 2
24. S-12	*	4530.2	2333.2	4488.7	2297.9	*	54.	230.	AG 0.0 8.0
25. RALWAY STATION (BS-1)	*	4488.7	2297.9	4318.4	2248.1	*	177.	254.	AG 0.0 8.0 2
26. S-13	*	4318.4	2248.1	4198.0	2248.1	*	120.	270.	AG 0.0 8.0
27. STATE BANK (BS-14)	*	4198.0	2248.1	4052.6	2158.8	*	171.	238.	AG 0.0 8.0 2
28. S-14	*	4052.6	2158.8	3880.2	2044.6	*	207.	236.	AG 0.0 8.0
29. SADAR BAZAR (BS-15)	*	3880.2	2044.6	3803.4	1992.6	*	93.	236.	AG 0.0 8.0 2
30. S15	*	3803.4	1992.6	3718.3	1920.0	*	112.	230.	AG 0.0 8.0
31. MALL RD (BS16)	*	3718.3	1920.0	3587.4	2106.9	*	228.	325.	AG 0.0 8.0 2
32. S-16	*	3587.4	2106.9	3483.6	2295.8	*	216.	331.	AG 0.0 8.0
33. KHYBER RD (BS-17)	*	3483.6	2295.8	3633.1	2391.3	*	177.	57.	AG 0.0 8.0 2
34. S-17	*	3633.1	2391.3	3718.3	2459.9	*	109.	51.	AG 0.0 8.0
35. GORA QBRSTAN (BS-18)	*	3718.3	2459.9	3302.9	2542.9	*	424.	281.	AG 0.0 8.0 2
36. S-18	*	3302.9	2542.9	3219.9	2615.6	*	110.	311.	AG 0.0 8.0
37. TEKAL (BS-19)	*	3219.9	2615.6	2966.5	2609.4	*	253.	269.	AG 0.0 8.0 2
38. S-19	*	2966.5	2609.4	2765.1	2611.5	*	201.	271.	AG 0.0 8.0
39. TAMBUIWAN (BS-20)	*	2765.1	2611.5	2646.7	2501.4	*	162.	227.	AG 0.0 8.0 2
40. S-20	*	2646.7	2501.4	2416.2	2368.5	*	266.	240.	AG 0.0 8.0

41. ABDARA RD (BS-21) * 2416.2 2368.5 2358.1 2327.0 * 71. 234. AG 0.0 8.0 2

42. S-21 * 2358.1 2327.0 2187.8 2225.2 * 198. 239. AG 0.0 8.0

43. UNIVRSITY TOWN (BS-2* 2187.8 2225.2 2129.6 2171.2 * 79. 227. AG 0.0 8.0 2

44. S-22 * 2129.6 2171.2 2030.0 2144.2 * 103. 255. AG 0.0 8.0

45. KTH UNI (BS-23) * 2030.0 2144.2 1801.5 2131.8 * 229. 267. AG 0.0 8.0 2

46. S-23 * 1801.5 2131.8 1581.4 2187.8 * 227. 284. AG 0.0 8.0

47. ISLAMI COLLEGE (BS-2* 1581.4 2187.8 1512.9 2204.5 * 71. 284. AG 0.0 8.0 2

48. S-24 * 1512.9 2204.5 1234.6 2204.5 * 278. 270. AG 0.0 8.0

49. BOARD BAZAR (BS-25) * 1234.6 2204.5 1172.3 2196.1 * 63. 262. AG 0.0 8.0 2

50. S-25 * 1172.3 2196.1 964.7 2173.3 * 209. 264. AG 0.0 8.0

51. TAJ AZAD (BS26) * 964.7 2173.3 848.4 1841.0 * 352. 199. BR 10.0 8.0 2

52. S-27 * 848.4 1841.0 823.4 1807.8 * 42. 217. AG 0.0 8.0

53. HYTABAD SCHL (BS-27)* 823.4 1807.8 568.0 1795.4 * 256. 267. AG 0.0 8.0 2

54. S-27 * 568.0 1795.4 391.5 1573.2 * 284. 218. AG 0.0 8.0

55. HYATBAD PHASE (BS-28* 391.5 1573.2 337.5 1517.1 * 78. 224. AG 0.0 8.0 2

56. S-28 * 337.5 1517.1 281.4 1479.7 * 67. 236. AG 0.0 8.0

CAL3QHCR+ (Dated: 95221)



ANNEX J

SAMPLE AMBIENT AIR QUALITY AND NOISE MONITORING RESULTS

41

Order ID	Product Name	Unit Price (\$)	Quantity	Total Price (\$)	Tax Amount (\$)
1001	Apple iPhone 12	1000	1	1000	100
1002	Samsung Galaxy S21	800	2	1600	160
1003	Google Pixel 5	600	1	600	60
1004	Microsoft Surface Pro 9	1200	1	1200	120
1005	Amazon Echo Dot	50	10	500	50
1006	Fitbit Versa 3	200	5	1000	100
1007	Apple Watch Series 7	350	3	1050	105
1008	Sony WH-1000XM4	350	2	700	70
1009	Bose QuietComfort 35 II	300	1	300	30
1010	Logitech MX Master 3	100	5	500	50
1011	Microsoft Office 365	100	1	100	10
1012	Adobe Creative Cloud	100	1	100	10
1013	Google One Storage	100	1	100	10
1014	Apple TV 4K	100	1	100	10
1015	Samsung SmartThings Hub	100	1	100	10
1016	Amazon Fire TV Stick	50	2	100	10
1017	Google Nest Learning Thermostat	200	1	200	20
1018	Philips Hue Light Bulbs	50	4	200	20
1019	TP-Link Smart Switch	50	2	100	10
1020	Ring Video Doorbell	100	1	100	10
1021	Arlo Pro 4 Security Camera	200	1	200	20
1022	Wyze Cam v3	30	5	150	15
1023	Eufy Security Camera	80	2	160	16
1024	Ring Floodlight Cam	150	1	150	15
1025	Arlo Pro 4 Floodlight	150	1	150	15
1026	Google Home Mini	50	2	100	10
1027	Amazon Echo Show 5	100	1	100	10
1028	Apple HomePod mini	100	1	100	10
1029	Samsung SmartThings Motion Sensor	30	3	90	9
1030	Google Nest Protect Smoke Detector	100	1	100	10
1031	Philips SmartThings Motion Sensor	30	3	90	9
1032	TP-Link Kasa Smart Plug	20	5	100	10
1033	Amazon Smart Plug	20	5	100	10
1034	Google Nest Wifi Router	100	1	100	10
1035	TP-Link Deco Mesh Router	100	1	100	10
1036	Netgear Orbi Mesh Router	200	1	200	20
1037	Linksys Velop Mesh Router	150	1	150	15
1038	Amazon Echo Plus	100	1	100	10
1039	Apple HomeKit Secure Base	100	1	100	10
1040	Samsung SmartThings Gateway	100	1	100	10
1041	Google Nest Hub	100	1	100	10
1042	Amazon Echo Studio	100	1	100	10
1043	Apple HomePod (2nd gen)	100	1	100	10
1044	Samsung SmartThings TV	100	1	100	10
1045	Google Nest Audio	100	1	100	10
1046	Amazon Echo (4th gen)	100	1	100	10
1047	Apple HomePod (1st gen) - Space Gray	100	1	100	10
1048	Samsung SmartThings Energy Monitor	100	1	100	10
1049	Google Nest Learning Thermostat - Black	200	1	200	20
1050	Philips Hue White and Ambiance Light Bulbs	50	4	200	20
1051	TP-Link Kasa Smart Dimmer Switch	50	2	100	10
1052	Amazon Smart Dimmer Switch	50	2	100	10
1053	Google Nest Wifi 5E Router	100	1	100	10
1054	TP-Link Deco M4 Mesh Router	100	1	100	10
1055	Netgear Orbi 9600 Mesh Router	200	1	200	20
1056	Linksys Velop Mesh Router - White	150	1	150	15
1057	Amazon Echo Show 15	100	1	100	10
1058	Apple HomePod mini - Red	100	1	100	10
1059	Samsung SmartThings Floodlight	100	1	100	10
1060	Google Nest Protect - White	100	1	100	10
1061	Philips SmartThings Floodlight	100	1	100	10
1062	TP-Link Kasa Smart Plug - White	20	5	100	10
1063	Amazon Smart Plug - White	20	5	100	10
1064	Google Nest Wifi 5E Router - White	100	1	100	10
1065	TP-Link Deco M4 Mesh Router - White	100	1	100	10
1066	Netgear Orbi 9600 Mesh Router - Black	200	1	200	20
1067	Linksys Velop Mesh Router - Black	150	1	150	15
1068	Amazon Echo Show 10	100	1	100	10
1069	Apple HomePod mini - Blue	100	1	100	10
1070	Samsung SmartThings Floodlight - White	100	1	100	10
1071	Google Nest Protect - Black	100	1	100	10
1072	Philips SmartThings Floodlight - White	100	1	100	10
1073	TP-Link Kasa Smart Plug - Black	20	5	100	10
1074	Amazon Smart Plug - Black	20	5	100	10
1075	Google Nest Wifi 5E Router - Black	100	1	100	10
1076	TP-Link Deco M4 Mesh Router - Black	100	1	100	10
1077	Netgear Orbi 9600 Mesh Router - White	200	1	200	20
1078	Linksys Velop Mesh Router - White	150	1	150	15
1079	Amazon Echo Show 8	100	1	100	10
1080	Apple HomePod (1st gen) - White	100	1	100	10
1081	Samsung SmartThings Floodlight - Black	100	1	100	10
1082	Google Nest Protect - Black	100	1	100	10
1083	Philips SmartThings Floodlight - Black	100	1	100	10
1084	TP-Link Kasa Smart Plug - White	20	5	100	10
1085	Amazon Smart Plug - White	20	5	100	10
1086	Google Nest Wifi 5E Router - White	100	1	100	10
1087	TP-Link Deco M4 Mesh Router - White	100	1	100	10
1088	Netgear Orbi 9600 Mesh Router - Black	200	1	200	20
1089	Linksys Velop Mesh Router - Black	150	1	150	15
1090	Amazon Echo Show 15	100	1	100	10
1091	Apple HomePod mini - Red	100	1	100	10
1092	Samsung SmartThings Floodlight	100	1	100	10
1093	Google Nest Protect - White	100	1	100	10
1094	Philips SmartThings Floodlight	100	1	100	10
1095	TP-Link Kasa Smart Plug - White	20	5	100	10
1096	Amazon Smart Plug - White	20	5	100	10
1097	Google Nest Wifi 5E Router - White	100	1	100	10
1098	TP-Link Deco M4 Mesh Router - White	100	1	100	10
1099	Netgear Orbi 9600 Mesh Router - Black	200	1	200	20
1100	Linksys Velop Mesh Router - Black	150	1	150	15
Average Commission:		44.1		\$4,410	\$441

Average Observed Concentrations of Priority Pollutants

1.00 mg/L: Maximum allowable concentration
 0.50 mg/L: Maximum allowable concentration
 0.25 mg/L: Maximum allowable concentration
 0.125 mg/L: Maximum allowable concentration

Location	Area	Monitoring Station	Unit	Average Concentration	Maximum Allowable Concentration
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L
Wastewater Treatment Plant	Wastewater	Wastewater Treatment Plant	mg/L	0.10	1.00 mg/L

1.00 mg/L: Maximum allowable concentration
 0.50 mg/L: Maximum allowable concentration
 0.25 mg/L: Maximum allowable concentration
 0.125 mg/L: Maximum allowable concentration

1.00 mg/L: Maximum allowable concentration

Residual Oil Quality

Blend: **100% Fuel Oil**
 Fuel Oil Type: **1**
 Fuel Oil Grade: **1**
 Fuel Oil Color: **1**

Item	Unit	Value	Unit	Value	Unit
1	kg	1000	kg	1000	kg
2	kg	1000	kg	1000	kg
3	kg	1000	kg	1000	kg
4	kg	1000	kg	1000	kg
5	kg	1000	kg	1000	kg
6	kg	1000	kg	1000	kg
7	kg	1000	kg	1000	kg
8	kg	1000	kg	1000	kg
9	kg	1000	kg	1000	kg
10	kg	1000	kg	1000	kg
11	kg	1000	kg	1000	kg
12	kg	1000	kg	1000	kg
13	kg	1000	kg	1000	kg
14	kg	1000	kg	1000	kg
15	kg	1000	kg	1000	kg
16	kg	1000	kg	1000	kg
17	kg	1000	kg	1000	kg
18	kg	1000	kg	1000	kg
19	kg	1000	kg	1000	kg
20	kg	1000	kg	1000	kg
21	kg	1000	kg	1000	kg
22	kg	1000	kg	1000	kg
23	kg	1000	kg	1000	kg
24	kg	1000	kg	1000	kg
25	kg	1000	kg	1000	kg
26	kg	1000	kg	1000	kg
27	kg	1000	kg	1000	kg
28	kg	1000	kg	1000	kg
29	kg	1000	kg	1000	kg
30	kg	1000	kg	1000	kg
31	kg	1000	kg	1000	kg
32	kg	1000	kg	1000	kg
33	kg	1000	kg	1000	kg
34	kg	1000	kg	1000	kg
35	kg	1000	kg	1000	kg
36	kg	1000	kg	1000	kg
37	kg	1000	kg	1000	kg
38	kg	1000	kg	1000	kg
39	kg	1000	kg	1000	kg
40	kg	1000	kg	1000	kg
41	kg	1000	kg	1000	kg
42	kg	1000	kg	1000	kg
43	kg	1000	kg	1000	kg
44	kg	1000	kg	1000	kg
45	kg	1000	kg	1000	kg
46	kg	1000	kg	1000	kg
47	kg	1000	kg	1000	kg
48	kg	1000	kg	1000	kg
49	kg	1000	kg	1000	kg
50	kg	1000	kg	1000	kg
51	kg	1000	kg	1000	kg
52	kg	1000	kg	1000	kg
53	kg	1000	kg	1000	kg
54	kg	1000	kg	1000	kg
55	kg	1000	kg	1000	kg
56	kg	1000	kg	1000	kg
57	kg	1000	kg	1000	kg
58	kg	1000	kg	1000	kg
59	kg	1000	kg	1000	kg
60	kg	1000	kg	1000	kg
61	kg	1000	kg	1000	kg
62	kg	1000	kg	1000	kg
63	kg	1000	kg	1000	kg
64	kg	1000	kg	1000	kg
65	kg	1000	kg	1000	kg
66	kg	1000	kg	1000	kg
67	kg	1000	kg	1000	kg
68	kg	1000	kg	1000	kg
69	kg	1000	kg	1000	kg
70	kg	1000	kg	1000	kg
71	kg	1000	kg	1000	kg
72	kg	1000	kg	1000	kg
73	kg	1000	kg	1000	kg
74	kg	1000	kg	1000	kg
75	kg	1000	kg	1000	kg
76	kg	1000	kg	1000	kg
77	kg	1000	kg	1000	kg
78	kg	1000	kg	1000	kg
79	kg	1000	kg	1000	kg
80	kg	1000	kg	1000	kg
81	kg	1000	kg	1000	kg
82	kg	1000	kg	1000	kg
83	kg	1000	kg	1000	kg
84	kg	1000	kg	1000	kg
85	kg	1000	kg	1000	kg
86	kg	1000	kg	1000	kg
87	kg	1000	kg	1000	kg
88	kg	1000	kg	1000	kg
89	kg	1000	kg	1000	kg
90	kg	1000	kg	1000	kg
91	kg	1000	kg	1000	kg
92	kg	1000	kg	1000	kg
93	kg	1000	kg	1000	kg
94	kg	1000	kg	1000	kg
95	kg	1000	kg	1000	kg
96	kg	1000	kg	1000	kg
97	kg	1000	kg	1000	kg
98	kg	1000	kg	1000	kg
99	kg	1000	kg	1000	kg
100	kg	1000	kg	1000	kg

Residual Oil Quality

1000

1000

Average Cost of Construction of Priority Power Lines

Project:
 Sampling Year:
 District:
 District Head Office:
 District Office:

Category	Year	Sampling Period	Cost	Cost per Kilometer	Remarks
1. Transmission Lines	2018	2018-2019	1000	1000	1000
2. Distribution Lines	2018	2018-2019	500	500	500
3. Substation (11kV)	2018	2018-2019	1000	1000	1000
4. Substation (33kV)	2018	2018-2019	1000	1000	1000
5. Substation (66kV)	2018	2018-2019	1000	1000	1000
6. Substation (132kV)	2018	2018-2019	1000	1000	1000
7. Substation (220kV)	2018	2018-2019	1000	1000	1000
8. Substation (330kV)	2018	2018-2019	1000	1000	1000
9. Substation (500kV)	2018	2018-2019	1000	1000	1000
10. Substation (765kV)	2018	2018-2019	1000	1000	1000

1. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 2. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 3. The cost of construction of priority power lines is calculated based on the cost of materials and labor.

1. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 2. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 3. The cost of construction of priority power lines is calculated based on the cost of materials and labor.

1. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 2. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 3. The cost of construction of priority power lines is calculated based on the cost of materials and labor.

1. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 2. The cost of construction of priority power lines is calculated based on the cost of materials and labor.
 3. The cost of construction of priority power lines is calculated based on the cost of materials and labor.

February 2014

Year	Population (millions)	Urban Population (millions)	Urban % of Total	Urban % of World	Urban % of Africa
1950	1.0	0.1	10%	1%	10%
1955	1.1	0.1	9%	1%	10%
1960	1.2	0.1	8%	1%	10%
1965	1.3	0.1	7%	1%	10%
1970	1.4	0.1	7%	1%	10%
1975	1.5	0.1	7%	1%	10%
1980	1.6	0.1	6%	1%	10%
1985	1.7	0.1	6%	1%	10%
1990	1.8	0.1	6%	1%	10%
1995	1.9	0.1	5%	1%	10%
2000	2.0	0.1	5%	1%	10%
2005	2.1	0.1	5%	1%	10%
2010	2.2	0.1	5%	1%	10%
2015	2.3	0.1	4%	1%	10%
2020	2.4	0.1	4%	1%	10%
2025	2.5	0.1	4%	1%	10%
2030	2.6	0.1	4%	1%	10%
2035	2.7	0.1	4%	1%	10%
2040	2.8	0.1	4%	1%	10%
2045	2.9	0.1	4%	1%	10%
2050	3.0	0.1	4%	1%	10%

FOR FURTHER INFORMATION:

What Is a Social Network?



Year	Country	Population (millions)	GDP (billions USD)	Life expectancy (years)
2010	USA	308	14.7	78.4
2011	USA	311	15.1	78.6
2012	USA	314	15.5	78.8
2013	USA	317	15.9	79.0
2014	USA	320	16.3	79.2
2015	USA	323	16.7	79.4
2016	USA	326	17.1	79.6
2017	USA	329	17.5	79.8
2018	USA	332	17.9	80.0
2019	USA	335	18.3	80.2
2020	USA	338	18.7	80.4
2021	USA	341	19.1	80.6
2022	USA	344	19.5	80.8
2023	USA	347	19.9	81.0
2024	USA	350	20.3	81.2
2025	USA	353	20.7	81.4
2026	USA	356	21.1	81.6
2027	USA	359	21.5	81.8
2028	USA	362	21.9	82.0
2029	USA	365	22.3	82.2
2030	USA	368	22.7	82.4
2031	USA	371	23.1	82.6
2032	USA	374	23.5	82.8
2033	USA	377	23.9	83.0
2034	USA	380	24.3	83.2
2035	USA	383	24.7	83.4
2036	USA	386	25.1	83.6
2037	USA	389	25.5	83.8
2038	USA	392	25.9	84.0
2039	USA	395	26.3	84.2
2040	USA	398	26.7	84.4
2041	USA	401	27.1	84.6
2042	USA	404	27.5	84.8
2043	USA	407	27.9	85.0
2044	USA	410	28.3	85.2
2045	USA	413	28.7	85.4
2046	USA	416	29.1	85.6
2047	USA	419	29.5	85.8
2048	USA	422	29.9	86.0
2049	USA	425	30.3	86.2
2050	USA	428	30.7	86.4
2051	USA	431	31.1	86.6
2052	USA	434	31.5	86.8
2053	USA	437	31.9	87.0
2054	USA	440	32.3	87.2
2055	USA	443	32.7	87.4
2056	USA	446	33.1	87.6
2057	USA	449	33.5	87.8
2058	USA	452	33.9	88.0
2059	USA	455	34.3	88.2
2060	USA	458	34.7	88.4
2061	USA	461	35.1	88.6
2062	USA	464	35.5	88.8
2063	USA	467	35.9	89.0
2064	USA	470	36.3	89.2
2065	USA	473	36.7	89.4
2066	USA	476	37.1	89.6
2067	USA	479	37.5	89.8
2068	USA	482	37.9	90.0
2069	USA	485	38.3	90.2
2070	USA	488	38.7	90.4
2071	USA	491	39.1	90.6
2072	USA	494	39.5	90.8
2073	USA	497	39.9	91.0
2074	USA	500	40.3	91.2
2075	USA	503	40.7	91.4
2076	USA	506	41.1	91.6
2077	USA	509	41.5	91.8
2078	USA	512	41.9	92.0
2079	USA	515	42.3	92.2
2080	USA	518	42.7	92.4
2081	USA	521	43.1	92.6
2082	USA	524	43.5	92.8
2083	USA	527	43.9	93.0
2084	USA	530	44.3	93.2
2085	USA	533	44.7	93.4
2086	USA	536	45.1	93.6
2087	USA	539	45.5	93.8
2088	USA	542	45.9	94.0
2089	USA	545	46.3	94.2
2090	USA	548	46.7	94.4
2091	USA	551	47.1	94.6
2092	USA	554	47.5	94.8
2093	USA	557	47.9	95.0
2094	USA	560	48.3	95.2
2095	USA	563	48.7	95

100



www.pearsoned.com



Multi-Level Uncertainty

Model: **Automated**
 Data set: **Automated**
 Data set: **Automated**

Level	Parameter	Value	Unit	Value
1	1.0	1.0	1.0	1.0
2	1.0	1.0	1.0	1.0
3	1.0	1.0	1.0	1.0
4	1.0	1.0	1.0	1.0
5	1.0	1.0	1.0	1.0
6	1.0	1.0	1.0	1.0
7	1.0	1.0	1.0	1.0
8	1.0	1.0	1.0	1.0
9	1.0	1.0	1.0	1.0
10	1.0	1.0	1.0	1.0
11	1.0	1.0	1.0	1.0
12	1.0	1.0	1.0	1.0
13	1.0	1.0	1.0	1.0
14	1.0	1.0	1.0	1.0
15	1.0	1.0	1.0	1.0
16	1.0	1.0	1.0	1.0
17	1.0	1.0	1.0	1.0
18	1.0	1.0	1.0	1.0
19	1.0	1.0	1.0	1.0
20	1.0	1.0	1.0	1.0
21	1.0	1.0	1.0	1.0
22	1.0	1.0	1.0	1.0
23	1.0	1.0	1.0	1.0
24	1.0	1.0	1.0	1.0
25	1.0	1.0	1.0	1.0
26	1.0	1.0	1.0	1.0
27	1.0	1.0	1.0	1.0
28	1.0	1.0	1.0	1.0
29	1.0	1.0	1.0	1.0
30	1.0	1.0	1.0	1.0
31	1.0	1.0	1.0	1.0
32	1.0	1.0	1.0	1.0
33	1.0	1.0	1.0	1.0
34	1.0	1.0	1.0	1.0
35	1.0	1.0	1.0	1.0
36	1.0	1.0	1.0	1.0
37	1.0	1.0	1.0	1.0
38	1.0	1.0	1.0	1.0
39	1.0	1.0	1.0	1.0
40	1.0	1.0	1.0	1.0
41	1.0	1.0	1.0	1.0
42	1.0	1.0	1.0	1.0
43	1.0	1.0	1.0	1.0
44	1.0	1.0	1.0	1.0
45	1.0	1.0	1.0	1.0
46	1.0	1.0	1.0	1.0
47	1.0	1.0	1.0	1.0
48	1.0	1.0	1.0	1.0
49	1.0	1.0	1.0	1.0
50	1.0	1.0	1.0	1.0
51	1.0	1.0	1.0	1.0
52	1.0	1.0	1.0	1.0
53	1.0	1.0	1.0	1.0
54	1.0	1.0	1.0	1.0
55	1.0	1.0	1.0	1.0
56	1.0	1.0	1.0	1.0
57	1.0	1.0	1.0	1.0
58	1.0	1.0	1.0	1.0
59	1.0	1.0	1.0	1.0
60	1.0	1.0	1.0	1.0
61	1.0	1.0	1.0	1.0
62	1.0	1.0	1.0	1.0
63	1.0	1.0	1.0	1.0
64	1.0	1.0	1.0	1.0
65	1.0	1.0	1.0	1.0
66	1.0	1.0	1.0	1.0
67	1.0	1.0	1.0	1.0
68	1.0	1.0	1.0	1.0
69	1.0	1.0	1.0	1.0
70	1.0	1.0	1.0	1.0
71	1.0	1.0	1.0	1.0
72	1.0	1.0	1.0	1.0
73	1.0	1.0	1.0	1.0
74	1.0	1.0	1.0	1.0
75	1.0	1.0	1.0	1.0
76	1.0	1.0	1.0	1.0
77	1.0	1.0	1.0	1.0
78	1.0	1.0	1.0	1.0
79	1.0	1.0	1.0	1.0
80	1.0	1.0	1.0	1.0
81	1.0	1.0	1.0	1.0
82	1.0	1.0	1.0	1.0
83	1.0	1.0	1.0	1.0
84	1.0	1.0	1.0	1.0
85	1.0	1.0	1.0	1.0
86	1.0	1.0	1.0	1.0
87	1.0	1.0	1.0	1.0
88	1.0	1.0	1.0	1.0
89	1.0	1.0	1.0	1.0
90	1.0	1.0	1.0	1.0
91	1.0	1.0	1.0	1.0
92	1.0	1.0	1.0	1.0
93	1.0	1.0	1.0	1.0
94	1.0	1.0	1.0	1.0
95	1.0	1.0	1.0	1.0
96	1.0	1.0	1.0	1.0
97	1.0	1.0	1.0	1.0
98	1.0	1.0	1.0	1.0
99	1.0	1.0	1.0	1.0
100	1.0	1.0	1.0	1.0

Model: **Automated**
 Data set: **Automated**
 Data set: **Automated**

Model: **Automated**
 Data set: **Automated**
 Data set: **Automated**

Model: **Automated**
 Data set: **Automated**
 Data set: **Automated**

Model: **Automated**
 Data set: **Automated**
 Data set: **Automated**

ANNEX K

PHOTOGRAPHS OF AMBIENT AIR QUALITY AND NOISE MONITORING



Photograph 11-1: SGS technician conducting ambient noise monitoring



Photograph 11-2: Ambient air quality parameters being shown on handheld meter



Photograph 11-3: SGS mobile van containing all equipment for ambient monitoring



Photograph 11-4: SGS mobile van conducting ambient monitoring in Peshawar



Photograph 11-5: SGS mobile van conducting ambient monitoring in Peshawar



Photograph 11-6: SGS mobile van conducting ambient monitoring in Peshawar



Photograph 11-7: SGS mobile van conducting ambient monitoring in Peshawar



Photograph 11-8: SGS technician conducting ambient air quality monitoring



Photograph 11-9: SGS mobile van conducting ambient monitoring in Peshawar

ANNEX L

No Objection Certificate (NOC) issued from Directorate of Archaeology



DEPARTMENT OF AGRICULTURE AND ANIMAL WELFARE
GOVT. OF KHYBER PAKHTUNKHWA, PESHAWAR

[Signature]
23-7-18

Mr. [Name]

[Signature]

Mr. [Name]
[Address]
[City]

1.

The enclosed
[Text]
[Text]

SAFETY AND SECURITY OF PERSONS

[Text]
[Text]
[Text]
[Text]

[Signature]
[Text]
[Text]

ANNEX M

Occupational Health and Safety Plan

Occupational Health and Safety covers all personnel working under the project and will be in line with the World Bank EHS guidelines on health and safety.

The Occupational Health and Safety program will aim to ensure that the workplace is safe and healthy by: addressing the hazards and risks at the workplace; outlining the procedures and responsibilities for preventing, eliminating and minimizing the effects of those hazards and risks; identifying the emergency management plans for the workplace or workplaces; and, specifying how consultation, training and information are to be provided to employees at various workplaces.

Some of the risks/hazards associated with workplaces are due to working close to or at sites associated with the various project construction activities. Other risks associated with the project construction phase include risk of increase of vector borne and other different diseases.

The following sections will be implemented during the construction phase to address and ensure workers' health and safety.

a. Screening and regular unannounced checking of workers.

As per the procedure for hiring workers, all contractors and labor agencies are required to make all prospective workers undergo medical tests to screen for diseases and sicknesses, prior to selection and employment of any worker. The contractor is also responsible for ensuring that no worker who has a criminal record is employed at the project site. It will be ensured that all workers undergo medical tests to screen diseases at source and at sites in consultation with the designated Health Officer.

In addition to this, the Project Management will also undertake sudden, unannounced checks on workers to look for diseases such as HIV, STDs, and hepatitis. If such cases are detected, the contractor will be required to immediately release the worker from the site (as this indicates that proper screening was not conducted).

b. Minimizing hazards and risks at the workplace.

To ensure safety at all work sites, the following will be carried out:

- i. Installation of signboards and symbols in risky and hazardous areas, to inform workers to be careful.
- ii. Construction of barricades around construction sites and deep excavated pits, to cordon off and deter entry of unauthorized personnel and workers into these areas.
- iii. Providing a safe storage site/area for large equipment such as power tools and chains, to

prevent misuse and loss.

iv. Proper Housekeeping: Ensuring that materials are all stacked, racked, blocked, interlocked, or otherwise secured to prevent sliding, falling, or collapse. Brick stacks will not be more than 7 feet in height and for concrete blocks they will not be more than 6 feet high.

v. Removing all scrap timber, waste material and rubbish from the immediate work area as the work progresses.

vi. Where scaffolds are required, ensuring that each scaffold or its components shall be capable of supporting its own weight and at least 4 times the maximum intended load applied or transmitted to it. The platform/scaffold plank shall be at least 15 inches wide and 1.5 inches thick. The rope should be capable of supporting at least 6 times the maximum intended load applied or transmitted to that rope. Pole scaffolds over 60 feet in height shall be designed by a registered professional engineer and shall be constructed and loaded in accordance with that design. Where scaffolds are not provided, safety belts/safety nets shall be provided;

vii. Ensure that all ramps or walkways are at least 6 feet wide, having slip resistance threads and not inclined more than a slope of 1 vertical and 3 horizontal.

viii. Stacking away all excavated earth at least 2 feet from the pit to avoid material such as loose rocks from falling back into the excavated area and injuring those working inside excavated sites.

ix. Constructing support systems, such as bracing to adjoining structures that may be endangered by excavation works nearby.

x. Only a trained electrician to construct, install and repair all electrical equipment to prevent risks of electrical shocks and electrocution.

xi. Install fire extinguishers and/or other fire-fighting equipment at every work site to prepare for any accidental fire hazards.

c. Provision of Personal Protective Equipment

Risks to the health and safety of workers can be prevented by provision of Personal Protective Equipment (PPEs) to all workers. This will be included in the construction cost for each Contractor. Depending on the nature of work and the risks involved, contractors must provide without any cost to the workers, the following protective equipment:

i. Helmet shall be provided to all workers, or visitors visiting the site, for protection of the

head against impact or penetration of falling or flying objects.

ii. Safety belt shall be provided to workers working at heights (more than 20 ft) such as roofing, painting, and plastering.

iii. Safety boots shall be provided to all workers for protection of feet from impact or penetration of falling objects on feet.

iv. Ear protecting devices shall be provided to all workers and will be used during the occurrence of extensive noise.

v. Eye and face protection equipment shall be provided to all welders to protect against sparks.

vi. Respiratory protection devices shall be provided to all workers during occurrence of fumes, dusts, or toxic gas/vapor.

vii. Safety nets shall be provided when workplaces are more than 25 feet (7.5 m) above the ground or other surfaces where the use of ladders, scaffolds, catch platforms, temporary floors or safety belts is impractical.

The specific PPE requirements for each type of work are summarized below.

Table M.1 PPE Requirement List

Type of Work	PPE
Elevated work	Safety helmet, safety belt (height greater than 20 ft), footwear for elevated work.
Handling work safety	Helmet, leather safety shoes, work gloves.
Welding and cutting work	Eye protectors, shield and helmet, protective gloves.
Grinding work	Dust respirator, earplugs, eye protectors.
Work involving handling of chemical substances	Dust respirator, gas mask, chemical-proof gloves. Chemical proof clothing, air-lined mask, eye protectors.
Wood working	Hard hat, eye protectors, hearing protection, safety footwear, leather gloves and dust respirator.
Blasting	Hard hat, eye and hearing protection.
Concrete and masonry work	Hard hat, eye protectors, hearing protection, safety footwear, leather gloves and dust respirator.
Excavation, heavy equipment, motor graders,	Hard hat, safety boots, gloves, hearing protection.

and bulldozer operation	
Quarries	Hard hat, eye protectors, hearing protection, safety footwear, leather gloves and dust respirator.

d. Procedures to Deal with Emergencies such as Accidents, Sudden Illness and Death of Workers

First aid kits will be made available at all times throughout the entire construction period by the respective contractors. This is very important, because most work sites will be at some distance from the nearest hospital. In addition to the first aid kits, the following measures should be in place:

- i. Provision of dispensaries by the individual EPC contractor.
- ii. A vehicle shall be on standby from the Project Office so that emergency transportation can be arranged to take severely injured/sick workers to the nearest hospital for immediate medical attention.
- iii. A designated Health Officer/worker for the Project will be identified as a focal person to attend to all health and safety related issues. This employee's contact number will be posted at all work sites for speedy delivery of emergency services. The focal person shall be well versed with the medical system and facilities available at the hospital.
- iv. Communication arrangements, such a provision of radios or mobile communication for all work sites, for efficient handling of emergencies, will be made.

e. Record Maintenance and Remedial action

The Project Management will maintain a record of all accidents and injuries that occur at the work site. This work will be delegated by the contractor to the site supervisor and regularly reviewed every quarter by project management. Reports prepared by the contractor shall include information on the place, date and time of the incident, name of persons involved, cause of incident, witnesses present and their statements. Based on such reports, the management can jointly identify any unsafe conditions, acts or procedures and recommend for the contractor to undertake certain mitigative actions to change any unsafe or harmful conditions.

f. Compensation for Injuries and Death

Any casualty or injury resulting from occupational activities should be compensated as per the local labor laws of Pakistan. Where compensation is sought by the injured party, proper procedures for documentation of the case will be followed, including a detailed report on the

accident, written reports from witnesses, report of the examining doctor and his/her recommendation for treatment. Each individual contractor will be responsible for ensuring compensation for the respective workers.

g. Awareness Programs

The Project management will undertake awareness programs through posters, talks, and meetings with the contractors to undertake the following activities:

- i. Dissemination sessions will clarify the rights and responsibilities of the workers regarding interactions with local people (including communicable disease risks, such as HIV/AIDS), work site health and safety, waste management (waste separation, recycling, and composting), and the illegality of poaching.
- ii. Make workers aware of procedures to be followed in case of emergencies such as informing the focal health person who in turn will arrange the necessary emergency transportation or treatment.

h. Nomination of a Health and Safety Focal Person

Within each site (especially if different sites are being implemented by different contractors), a Health and Safety Focal Person will be appointed. The Terms of Reference for the focal person will mainly be as follows:

- i. Function as the focal person/representative for all health and safety matters at the workplace;
- ii. Responsible for maintaining records of all accidents and all health and safety issues at each site, the number of accidents and its cause, actions taken and remedial measures undertaken in case of safety issues;
- iii. Be the link between the contractor and all workers and submit grievances of the workers to the contractor and instructions/directives on proper health care and safety from the contractors back to the workers;
- iv. Ensure that all workers are adequately informed on the requirement to use Personal Protective Equipment and its correct use;
- v. Also responsible for the first aid kit and making sure that the basic immediate medicines are readily available.

ANNEX N

Emergency Response Plan

N.1 PURPOSE

The purpose of this Emergency Response Procedure is to provide measures and guidance for the establishment and implementation of emergency preparedness plans for the Bus Rapid Transit Project. The aim of the Emergency Response Procedure is to:

- (i) Ensure all personnel and visitors to the office/job sites are given the maximum protection from unforeseen events.
- (ii) Ensure all personnel are aware of the importance of this procedure to protection of life and property.

N.2 EMERGENCY PREPARATION AND RESPONSE MEASURE SCOPE

The emergency management program is applied to all Project elements and intended for use throughout the Project life cycle. The following are some emergencies that may require coordinated response.

- (i) Construction Accident
- (ii) Road & Traffic Accident
- (iii) Hazardous material spills
- (iv) Structure collapse or failure
- (v) Trauma or serious illness
- (vi) Sabotage
- (vii) Fire
- (viii) Environmental Pollution
- (ix) Loss of person
- (x) Community Accident

N.3 RESPONSIBILITIES

The detailed roles and responsibilities of certain key members of the Emergency Response team available to assist in emergency are provided in Table M.1 below.

Table N.1 Emergency Response Team

Action Group	Responsibility
Emergency Coordinator	<ul style="list-style-type: none"> ▪ Overall control of personnel and resources. ▪ The Emergency Coordinator will support and advise the Site Safety Supervision as necessary. ▪ Serves as public relations spokes persons, or delegates to some staff member the responsibility for working with news media regarding any disaster or emergency. Also assure proper coordination of news release with appropriate corporate staff or other designated people.
Site Safety Supervision (Emergency Commander)	<ul style="list-style-type: none"> ▪ Overall responsibility for activating emergency plan and for terminating emergency actions. ▪ Be alternative of emergency response chairpersons. ▪ Disseminates warnings and information as required to ensure all people in the immediate area have been warned and evacuated either by alarms or by word of mouth. ▪ Supervise the actions of the Emergency Response Team to ensure all persons are safe from the danger. ▪ Notify outside authorities if assistance is required. ▪ Carries the responsibility for coordinating actions including other organizations in accordance with the needs of the situation. ▪ Ensure maximum co-operation and assistance is provided to any outside groups called to respond to an emergency. ▪ Establish and appoint all emergency organization structure and team. ▪ Assures adequate delegation of responsibilities for all key positions of assistants on the Project to assist with any foreseeable emergency. ▪ Ensure resources available to purchase needed emergency response equipment and supplies. ▪ Assures that all persons on the Emergency Response Team aware and fully understand their individual responsibilities for implementing and supporting the emergency plan. ▪ Establish the emergency drill schedule of all identified emergency scenarios, track the status and evaluate the emergency. ▪ The Emergency Commander shall ensure that senior management personnel have been reported of the emergency as soon as practical after the event.
Security Team	<ul style="list-style-type: none"> ▪ Ensure that the exit route is regularly tested and maintained in good working order. ▪ Maintain station at the security gate or most suitable location to secure the area during any emergency such that only authorized personnel and equipment may enter, prevent access to the site of unauthorized personnel. ▪ Assist with strong/activation of services during an emergency. ▪ Ensure vehicles and obstructions are moved to give incoming emergency vehicles access to the scene, if ambulance or emergency services are attending the site, ensure clear access and personnel are located to direct any incoming emergency service to the site of emergency.

Rescue & Medical Team	<ul style="list-style-type: none"> ▪ Protect the injured from further danger and weather. ▪ Provide treatment to the victim(s) to the best of their ability by first aid and then transfer to hospital. ▪ Remain familiar with the rescue activities and rescue apparatus. ▪ Assist outside medical services personnel when they arrive
General Administration Team	Response to support any requested general facilities for assisting Emergency Response Team in their work.
Government Relation Team	<ul style="list-style-type: none"> ▪ Coordinate with local government on a matter of concerned in the emergency response plan to liaise with local officers in their affair for support Emergency Response Team. ▪ Coordinate emergency plan with the government authorities, local community.
Environment Team	In case of emergency related to the environmental pollution such as the chemical spill, oil spill into the ambient, the environment team will support the technical advice to control and mitigate the pollution until return to the normal situation.
Department Heads	<ul style="list-style-type: none"> ▪ Call up of personnel into the safe location for protective life and property. ▪ Take immediate and appropriate action while Emergency Response Team is being mobilized. ▪ Keep in touch with the Emergency Commander ▪ Control and supervise operators and contractors on the implementation of this procedure, with consultation with Safety Team as necessary. ▪ Provide and maintain emergency equipment of their responsible areas.
Other Staff and Employees	<ul style="list-style-type: none"> ▪ All other staff and employees will remain at their workstations or assembly point unless directed otherwise from Emergency Response Team. ▪ Each supervisor will ensure that all members of his work group are accounted for and keep in touch with each of their Department Head.

N.4 PROCEDURE

Emergency situation and injuries to person can occur at any time or place either on Project site or elsewhere. The most two common types of emergencies on site are fire and serious accident.

Figure N.1 Emergency Procedure for Fire



Figure N.2 Emergency Procedure for Serious Accident

APPENDIX

In the event of injuries of persons, the first person on the scene should take the following actions:

1. Establish communication for police and ambulance. It is essential to provide the location of the accident point.

2. Assess the potential of developing fire situation. Evacuate people from such area.

3. Report directly to Third Aid or Emergency Services, when receiving the above point and directly give the following information:

- Your name and the name of the site
- The location of the injured person(s)
- The number of persons injured
- The nature of the injuries, if known
- Other measures taken or to be taken

4. Make the injured persons secure and comfortable as possible

5. Treat the victims, if injuries

6. Remove the injured persons

N.5 COMMUNICATION WITH AUTHORITIES / PRESS AT SITE

In the event of an accident or incident, only senior staff is permitted to give factual information to the authorities for resource of liability exposure. The press must be avoided politely, at all costs, with the terse comment that “the matter is under investigation and relevant information when available will be provided by our Head Office” Do not ever give your opinion or story.

First Aid Persons

Upon advice of medical emergency, make immediate assessment to response required and if necessary, advise security to summon ambulance or medical assistance, the qualified first aid attendant should also,

- Provide treatment to the victim(s) to the best of his/her ability.
- Ensure the safety of victims by ceasing any work activity in the area.
- Protect the injured from further danger and weather.
- Assist medical services personnel when they arrive.

General Administration Team


Upon advice of medical emergency, maintain contact with first aid personnel and summon ambulance if required.

Security Team

- If ambulance or emergency services are attending the site, ensure clear access and personnel are located to direct vehicle closest to the scene.
- Prevent access to the site of unauthorized personnel (press, etc.).

Emergency Coordinator

- The Emergency Coordinator shall assist emergency personnel at the scene as required through allocation of company resources.
- The Emergency Coordinator shall ensure next-of-kin are properly notified as soon as possible and give whatever company support and assistance is necessary to assist them bundle the situation
- The Emergency Coordinator shall ensure that senior management personnel are advised of the emergency as soon as practical after the event.



Project management is a process of planning, organizing, and controlling resources to achieve specific goals and objectives.

N.5 INCIDENT AND ACCIDENT REPORT

[illegible]

Subtotal: 1700 out of 2000 points. Missing answers at this stage:

Subtotal: 1700 out of 2000 points. Missing answers at this stage:

Section 1: Multiple Choice (please select one correct or best answer) (1000 points)

QUESTION (1000 POINTS)	ANSWER (1000)
1. Which of the following is not a type of project?	1. Project of a new building
2. Which of the following is not a type of project?	2. Project of a new building
3. Which of the following is not a type of project?	3. Project of a new building
4. Which of the following is not a type of project?	4. Project of a new building
5. Which of the following is not a type of project?	5. Project of a new building
6. Which of the following is not a type of project?	6. Project of a new building
7. Which of the following is not a type of project?	7. Project of a new building
8. Which of the following is not a type of project?	8. Project of a new building
9. Which of the following is not a type of project?	9. Project of a new building
10. Which of the following is not a type of project?	10. Project of a new building
11. Which of the following is not a type of project?	11. Project of a new building
12. Which of the following is not a type of project?	12. Project of a new building
13. Which of the following is not a type of project?	13. Project of a new building
14. Which of the following is not a type of project?	14. Project of a new building
15. Which of the following is not a type of project?	15. Project of a new building
16. Which of the following is not a type of project?	16. Project of a new building
17. Which of the following is not a type of project?	17. Project of a new building
18. Which of the following is not a type of project?	18. Project of a new building
19. Which of the following is not a type of project?	19. Project of a new building
20. Which of the following is not a type of project?	20. Project of a new building

Section 2: Multiple Choice (please select one correct or best answer) (1000 points)

QUESTION (1000 POINTS)	ANSWER (1000)
1. Which of the following is not a type of project?	1. Project of a new building
2. Which of the following is not a type of project?	2. Project of a new building
3. Which of the following is not a type of project?	3. Project of a new building
4. Which of the following is not a type of project?	4. Project of a new building
5. Which of the following is not a type of project?	5. Project of a new building
6. Which of the following is not a type of project?	6. Project of a new building
7. Which of the following is not a type of project?	7. Project of a new building
8. Which of the following is not a type of project?	8. Project of a new building
9. Which of the following is not a type of project?	9. Project of a new building
10. Which of the following is not a type of project?	10. Project of a new building
11. Which of the following is not a type of project?	11. Project of a new building
12. Which of the following is not a type of project?	12. Project of a new building
13. Which of the following is not a type of project?	13. Project of a new building
14. Which of the following is not a type of project?	14. Project of a new building
15. Which of the following is not a type of project?	15. Project of a new building
16. Which of the following is not a type of project?	16. Project of a new building
17. Which of the following is not a type of project?	17. Project of a new building
18. Which of the following is not a type of project?	18. Project of a new building
19. Which of the following is not a type of project?	19. Project of a new building
20. Which of the following is not a type of project?	20. Project of a new building

Section 3: Multiple Choice (please select one correct or best answer) (1000 points)

Section 4: Multiple Choice (please select one correct or best answer) (1000 points)

The above information is provided by:			
Name:		Signature:	
The above information is provided by:			
Name:			
Address:		Date:	
The above information is provided by:			
Name:			
Address:			
Date:			

ANNEX O

Archaeological ‘Chance Find’ procedure

Background

The purpose of this document is to address the possibility of archaeological deposits becoming exposed during ground altering activities within the project area and to provide protocols to follow in the case of a chance archaeological find to ensure that archaeological sites are documented and protected as required.

The KPK Antiquities Act, 2016, protects archaeological sites, whether on Provincial Government owned or private land. They are non-renewable, very susceptible to disturbance and are finite in number. Archaeological sites are an important resource that is protected for their historical, cultural, scientific and educational value to the general public and local communities. Impacts to archaeological sites must be avoided or managed by development proponents. The objectives of this 'Archaeological Chance Find Procedure' are to promote preservation of archaeological data while minimizing disruption of construction scheduling. It is recommended that due to the moderate to high archaeological potential of some areas within the project area, all on site personnel and contractors be informed of the Archaeological Chance Find Procedure and have access to a copy while on site.

Potential Impacts to Archaeological Sites

Developments that involve excavation, movement, or disturbance of soils have the potential to impact archaeological materials, if present. Activities such as road construction, land clearing, and excavation are all examples of activities that may adversely affect archaeological deposits.

Relevant Legislation

It ensures the protection, preservation, development and maintenance of antiquities in the province of KPK. The Act defines "antiquities" as ancient products of human activity, historical sites, or sites of anthropological or cultural interest, national monuments, etc. The Act is designed to protect these antiquities from destruction, theft, negligence, unlawful excavation, trade, and export. The law prohibits new construction in the proximity of a protected antiquity and empowers the GoKPK to prohibit excavation in any area that may contain articles of archaeological significance. Under the Act, the subproject proponents are obligated to ensure that no activity is undertaken in the proximity of a protected antiquity, report to the Department of Archaeology, GoKPK, any archaeological discovery made during the course of the project.

Remedies and Penalties

The KPK Antiquities Act, 2016 provides for heritage inspection or investigation orders, temporary protection orders, civil remedies and penalties to limit contraventions. These powers provide:

“A contravention of any provision of this Act or the rules shall, where no punishment has been specifically provided be punishable with rigorous imprisonment for a term which may extend to two years, or with fine up to rupees ten hundred thousand, or with both. ”

Archaeological ‘Chance Find’ Procedure

If you believe that you may have encountered any archaeological materials, stop work in the area and follow the procedure below:

The following ‘chance-find’ principles will be implemented by the contractor throughout the construction works to account for any undiscovered items identified during construction works:

- (i) Workers will be trained in the location of heritage zones within the construction area and in the identification of potential items of heritage significance.
- (ii) Should any potential items be located, the site supervisor will be immediately contacted and work will be temporarily stopped in that area.
- (iii) If the site supervisor determines that the item is of potential significance, an officer from the department of Archaeology (DoA), GoKPK will be invited to inspect the site and work will be stopped until DoA has responded to this invitation.
- (iv) Work will not re-commence in this location until agreement has been reached between DoA and PDA as to any required mitigation measures, which may include excavation and recovery of the item.
- (v) A precautionary approach will be adopted in the application of these procedures.

Detailed Procedural Steps

- If the Director, department of Archaeology receives any information or otherwise has the knowledge of the discovery or existence of an antiquity of which there is no owner, he shall, after satisfying himself as to the correctness of the information or knowledge, take such steps with the approval of the Government, as he may consider necessary for the custody, preservation and protection of the antiquity.
- Whoever discovers, or finds accidentally, any movable antiquity shall inform forth with the Directorate within seven days of its being discovered or found.
- If, within seven days of his being informed, the Director decides to take over the antiquity for purposes of custody, preservation and protection, the person discovering or finding it shall hand it over to the Director or a person authorized by him in writing.
- Where the Director decides to take over an antiquity, he may pay to the person by whom it is handed over to him such cash reward as may be decided in consultation with the Advisory Committee.

- If any person, who discovers or finds any movable antiquity contravenes the provisions of the Act, he shall be punishable with imprisonment for a term which may extend to five (05) years, or with fine not less than fifteen hundred thousand rupees or with both and the Court convicting such person shall direct that the antiquity in respect of which such contravention has taken place shall stand forfeited to Government.
- The Director or any officer authorized by him with police assistance may, after giving reasonable notice, enter into, inspect and examine any premises, place or area which or the sub-soil of which he may have reason to believe to be, or to contain an antiquity and may cause any site, building, object or any antiquity or the remains of any antiquity in such premises, place or area to be photographed, copied or reproduced by any process suitable for the purpose.
- The owner or occupier of the premises, place or area shall afford all reasonable opportunity and assistance to the Director.
- No photograph, copy of reproduction taken or made shall be sold or offered for sale except by or with the consent of the owner of the object of which the photograph, copy or the reproduction has been taken or made.
- Where substantial damage is caused to any property as a result of the inspection, the Director shall pay to the owner thereof reasonable compensation for the damage in consultation with the Advisory Committee.
- If the Director after conducting an inquiry, has reasonable grounds to believe that any land contains any antiquity, he may approach the Government to direct the Revenue Department to acquire such land or any part thereof and the Revenue Department shall thereupon acquire such land or part under the Land Acquisition Act, 1894 (I of 1894), as for a public purpose.

ANNEX P

Scope of Work for Structural Assessment of Bala Hisar Fort

Preservation of archaeological handmade is a very relevant task for structural engineers, which are often responsible for safety of ancient constructions and design of interventions aimed basically to mitigate structural damages, rather than strongly improve structural performances of constructions, as for ordinary structures. Concept of mitigation of structural damages is only recently applied to structural restoration; in fact, many interventions made on archaeological constructions in the past were very invasive, operated directly on the structure changing its appearance and original resistant mechanisms.

Thus, evaluation of present structural performances of ancient constructions is very complex and must be based on an accurate review of former interventions and an analysis of actual structural mechanisms governing the behaviour of the construction.

Strategy for Structural Assessment

The strategy of the proposed investigations has been developed according to the following scheme:

- **Step 1:** Evaluation of the present conditions of the structure by means of an accurate geometrical survey taking into account the main constructional aspects;
- **Step 2:** Evaluation of deficiencies by means of the survey of crack pattern;
- **Step 3:** Identification of original works and effects of former structural interventions of restoration;
- **Step 4:** Evaluation of the mechanical and physical properties of materials used in the construction;
- **Step 5:** Advanced non-destructive tests on the structure to describe internal conditions of massive blocks and eventual additional constraints.