

Initial Environmental Examination

Main Report (Parts 1 to 10)
Project Number: 48404-004
July 2020

PAK: Central Asia Regional Economic Cooperation
Corridor Development Investment Program (Tranche 2)

Shikarpur–Rajanpur Section of N55

CURRENCY EQUIVALENTS

(as of 2 June 2020)

Currency unit	–	Pakistan Rupee/s (PRe/PRs)
PRe1.00	=	\$0.0061
\$1.00	=	PRs164.25

UNIT CONVERSIONS

1 gallon	–	3.785 liter
1 gallon/day	–	0.00455 m ³ /day
1 m ³ /day	–	0.041 m ³ /hour
1 cusec	–	28.31 liters
1 kilometer	–	1,000 meters
1 foot	–	12 inches
1 acre	–	4,046.8 meter ²

ABBREVIATIONS

AAD	–	average annual daily
AADT	–	average annual daily traffic
AASHTO	–	American Association of State Highway and Transportation
AASHTO ASM	–	American Association of State Highway and Transportation Officials
ABC	–	aggregate base course
ACBC	–	asphaltic concrete base course
ACW	–	additional carriageway
ACWC	–	asphaltic concrete wearing course
ADB	–	Asian Development Bank
AKM	–	avenue kilometer
APHA	–	American Public Health Association
AP	–	affected person
ASR	–	air sensitive receiver
ASTM	–	American Society of Testing Materials
BDL	–	below detection limit
BHU	–	basic health unit
BOD	–	bio-chemical oxygen demand
BP	–	Bank Policy
°C	–	degree Centigrade/Celsius
CAREC	–	Central Asia Regional Economic Corridor
CC	–	construction contractor
CO	–	carbon monoxide
COD	–	chemical oxygen demand
CSR	–	composite schedule rates

dB (A)	–	decibel
DCR	–	district census report
DC	–	design consultant
DD	–	deputy director
DMC	–	developing member countries
DO	–	dissolved oxygen
EA	–	environmental assessment
EE	–	environmental engineer
EIA	–	environmental impact assessment
EMP	–	environmental management plan
EPA	–	Environment Protection Agency
EPD	–	Environment Protection Department
EPO	–	Environmental Protection Ordinance
ESR	–	Environmental Sensitive Receiver
FCC	–	Forest Conservation Committee
FI	–	financial intermediary
GHG	–	greenhouse gas
GOP	–	Government of Pakistan
GRC	–	grievance redress committee
GRM	–	grievance redress mechanism
HSIP	–	Highway Sector Improvement Program
IEE	–	initial environmental examination
ILO	–	International Labor Organization
km	–	kilometer
kph	–	kilometer per hour
LAC	–	land acquisition collector
LAeq	–	equivalent continuous sound level, 'A weighting' = correction by factors that weight sound to correlate with the sensitivity of the human ear to sounds at different frequencies
m	–	meter
MFF	–	multitranche financing facility
MGDs	–	Millennium Development Goals
MVE	–	motor vehicle examiner
NEQS	–	National Environmental Quality Standards
NESPAK	–	National Engineering Services Pakistan
NGO	–	nongovernment organization
NHA	–	National Highways Authority
NO	–	nitrogen oxide
NOC	–	no-objection certificate
NSL	–	natural surface level
NSR	–	noise sensitive receiver
NTC	–	National Trade Corridor
OP	–	operational policy
OSHA	–	Occupational Safety and Health Administration
PAP	–	project affected person
PEPA	–	Pakistan Environmental Protection Act
PEPC	–	Pakistan Environmental Protection Council
PM	–	particulate matter
PNCS	–	Pakistan National Conservation Strategy
POP	–	persistent organic pollutant

PPAF	–	Pakistan Poverty Alleviation Fund
PPC	–	Pakistan Penal Code
PRC	–	People's Republic of China
RE	–	resident engineer
REA	–	rapid environmental assessment
ROW	–	right-of-way
SC	–	supervision consultant
SMART	–	self-monitoring and reporting tool
SO	–	sulfur oxide
SPS	–	Safeguard Policy Statement
SSEMP	–	site specific environmental management plan
TA	–	technical assistance
TOR	–	terms of reference
TSS	–	total suspended solids
UBC	–	Uniform Building Code
UC	–	Union Council
UNFCCC	–	United Nations Framework Convention on Climate Change
USEPA	–	United States Environmental Protection Agency
WHO	–	World Health Organization

This initial environmental examination is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature. Your attention is directed to the “terms of use” section of this website.

In preparing any country program or strategy, financing any project, or by making any designation of or reference to a particular territory or geographic area in this document, the Asian Development Bank does not intend to make any judgments as to the legal or other status of any territory or area.

TABLE OF CONTENTS

LIST OF TABLES.....	xi
LIST OF FIGURES	xii
SECTION 1: EXECUTIVE SUMMARY	1
1.1 Need Purpose and Proposed Action	1
1.2 Requirement of Environmental Approval	1
1.3 Project Description.....	2
1.4 Project Alternatives.....	2
1.5 Description of the Environment	2
1.6 Public Involvement & Grievance Redress Mechanism	4
1.7 Anticipated Impacts and Mitigation Measures	4
1.8 Environmental Management Plan	6
1.9 Climate Smart Development.....	7
1.10 Conclusion	7
SECTION 2: INTRODUCTION OF THE PROJECT	8
2.1 Purpose of Project	8
2.2 Proposed Project	8
2.3 Purpose of IEE	8
2.4 Scope of IEE	9
2.5 Project Categorization	9
2.6 Study Area	9
2.7 Project Management/Consultants	9
2.8 Methodology of IEE	9
SECTION 3: POLICY, LEGAL AND ADMINISTRATIVE FRAMEWORK	11
3.1 Requirement of Environmental Approval	11
3.2 National Policy and Legal Framework.....	11
3.3 ADB's Safeguard Policy Statement, 2009.....	15
3.4 Safeguard Requirements-1: Environment.....	15
3.5 Administrative Framework	15
3.6 Comparison of Environmental Quality Standards	16
SECTION 4: PROJECT DESCRIPTION	20
4.1 Rational of the Project	20
4.2 Location of Project	20
4.3 The Project.....	20
4.4 Duration of the Project:	23
4.5 Geometric Design of the Proposed Additional Carriageway	23
4.6 Embankment Design	26
4.7 Traffic Count and Projection	26
4.8 Construction Logistics.....	28
4.9 Construction Materials	28
4.10 Construction Equipment	29
4.11 Personnel Required	29
SECTION 5: DESCRIPTION OF THE ENVIRONMENT	32
5.1 Physical Environment	32
5.1.1 Geology and Soil	32
5.1.2 Topography and Land Use	32
5.1.3 Climate and Air Quality	32
5.1.4 Water Resources	34
5.1.4 Natural Hazards	41
5.1.5 Noise	43

5.1.6 Environmental Sensitive Receptors	43
5.2 Biological Environment	48
5.2.1 Flora of the Area	48
5.2.2 Conservation and Protection Status	48
5.2.3 Faunal Species in project area	50
5.3 Socioeconomic Profile	51
5.3.1 Demographic Characteristics	51
5.3.2 Social Characteristics	52
5.3.3 Economic Characteristics	53
5.3.4 Historical and Archeological Characteristics	54
SECTION 6: ANALYSIS OF ALTERNATIVES	56
6.1 Alternative I: No-Action Alternative	56
6.2 Alternative II: Additional 2-Lane at N-55 Alignment as proposed	56
6.3 Alternative III: Rehabilitation of existing 2-Lanes at N-55 Alignment	57
6.4 Selected Option:	57
6.5 Technological Alternatives	57
SECTION 7: ANTICIPATED ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES ..	59
7.1 Environmental Consequences	59
7.2 Screening of Potential Environmental Impacts	59
7.3 Positive Impacts of the Project	64
7.4 Pre-Construction/Design Phase	64
7.4.1 Physical Environment	64
7.4.1.1 Topography	64
7.4.1.2 Change in Hydrologic Regime	64
7.4.2 Ecological Environment	64
7.4.2.1 Removal of Roadside Trees	64
7.4.3 Social Environment	65
7.4.3.1 Land Acquisition, Infrastructure and Resettlement	65
7.4.3.2 Changes in Land Value	66
7.4.3.3 Physical Cultural Resources	66
7.4.3.4 Public Utilities	66
7.5 Construction Phase	67
7.5.1 Physical Environment	67
7.5.1.1 Disruption of Existing Public Utilities/ Infrastructure	67
7.5.1.2 Soil erosion and Contamination	67
7.5.1.3 Borrow/Open Pits	67
7.5.1.4 Air Pollution Control	68
7.5.1.9 Impacts of construction of bridges	71
7.5.1.10 Disposal of Mucking Material	72
7.5.1.11 Traffic Management	72
7.5.1.15 Occupational Health and Safety	73
7.5.1.16 Storage of Chemicals and Dangerous Goods	74
7.5.1.17 Fire Prevention/ Emergency Preparedness	74
7.5.2 Ecological Environment	75
7.5.2.1 Biodiversity Conservation	75
7.5.3 Social Environment	76
7.5.3.1 Construction Camps/Camp Sites	76
7.5.3.2 Cultural Conflicts	77
7.5.3.3 Physical Cultural Resources	77
7.5.3.4 Economic Activity	77
7.5.3.5 Community Health and Safety	77

7.6	Anticipated Impacts during Operational Phase	78
7.6.1	Physical Environment	78
7.6.1.1	Water pollution	78
7.6.2	Ecological Environment	79
7.6.2.1	Biodiversity Conservation and Natural Resource Management	79
7.6.3	Social Environment	79
7.6.3.1	Road Safety	79
7.6.3.2	Less Wear and Tear of Vehicles	80
7.6.3.3	Community Development	80
7.6.3.4	Accessibility	80
	SECTION 8: ENVIRONMENTAL MANAGEMENT PLAN	81
8.1	Environmental Management	81
8.2	Institutional Responsibilities	81
8.2.1	EALS (NHA)	81
8.2.2	Project Implementation Unit (PIU)	82
8.2.3	Asian Development Bank.	82
8.2.4	Construction Supervision Consultant (CSC)	83
8.2.5	Contractor	83
8.2.6	Third Party Environmental Monitoring Contractors	83
8.3	Staffing Requirement	83
8.4	Reporting and Feedback Mechanism	84
8.5	Environmental Technical Assistance and Training Plan	84
8.6	Summary of Environmental Management Plan	85
8.7	Environmental Monitoring Requirements	101
8.7.1	Pre-construction Ambient Environment Monitoring	101
8.8	Environmental Management Plan Indicative Cost	109
	SECTION 9 PUBLIC PARTICIPATION, CONSULTATION AND INFORMATION DISCLOSURE .	
	110
9.1	Stakeholder Identification and Analysis	110
9.2	Methods Adopted for Stakeholder Engagement	110
9.3	Stakeholder's Concerns and Priorities	110
9.4	Information Disclosure	118
9.5	Grievance Redress Mechanism (GRM)	118
9.5.1	First Level of GRM	119
9.5.2	Second Level of GRM	119
9.5.3	Third Level of GRM	120
9.5.4	Constitution and Function of the GRC	120
9.5.5	Type of Grievances to be expected	121
	SECTION 10 CONCLUSION	123

LIST OF TABLES

Table 3.1: Summary of Applicable Laws, Policies and Conventions at National & International Level.....	11
Table 4.1: Detail of Structures to be constructed	23
Table 4.2: Summarized Total Traffic Projections by Type of Vehicles	27
Table 7.1: Characterization of Environmentally Potential Impacts for Construction Phase	60
Table 7.2: Characterization of Environmentally Potential Impacts for Operation Phase	61
Table 7.3: Environmental Impacts Evaluation Matrix during the Construction Phase.....	62
Table 7.4: Environmental Impacts Evaluation Matrix during the Operational Phase	63
Table 8.1: Reporting Requirements.....	84
Table 8.2: Training of Institutions involved in Environmental Compliance	85
Table 8.3: Environmental Management Plan	86
Table 8.4: Ambient Environment Baseline Sampling	101
Table 8.5: Environmental Monitoring Plan	102
Table 8.6: Environmental Management Plan Indicative Cost	109
Table 9.1: Public Involvement Process	111
Table 9.2: Departmental Consultation	115
Predicted Noise Level for Sensitive Receptors Located at the Distance of 40 meters	183

LIST OF FIGURES

Figure 4.1: Location map of the Project Area.....	21
Figure 4.2: Alignment Map of Shikarpur- Rajanpur Section ACW	22
Figure 4.3: Alignment of Kashmore Bypass	22
Figure 4.4 (a) : Typical Cross Section for Additional Carriageway	24
Figure 4.4 (b) : Typical Cross Section for New Construction	25
Figure 5.1: Land-use map of the Study Area	39
Figure 5.2: Hydrological map of Project Area	40
Figure 5.3: Seismic Zoning Map of Pakistan	41
Figure 5.4: An Overview of the Flood Extent in 2010	42
Figure 5.5- a: Environmental Sensitive Recptors (Rajanpur to Kahsmore)	46
Figure 5.5-b: Environmental Sensitive Recptors (Kahsmore to Shikarpur)	47
Figure 5.6: Showing Existing Reserved/Conserved Forest Area.....	49
Figure 9.2: Flow Chart of the Proposed Grievance Redress Mechanism	121

SECTION 1: EXECUTIVE SUMMARY

1.1 Need Purpose and Proposed Action

1. In order to improve trade and commerce in global markets and improve the connectivity with Central Asian Countries, it is imperative to have a regional approach and good relation with neighboring countries. This is the prime objective of the Central Asia Regional Economic Corridor (CAREC) Program to improve and extend the corridor to the neighboring countries.
2. These Corridors within Pakistan will interconnect surrounding countries acting as a regional hub in order to promote regional integration and intra-and inter-regional trade. CAREC include eleven states and six corridors.
3. Corridors 5 and 6 which are north-south national corridors on the west side of the Indus River running through Pakistan. The Government of Pakistan (GoP) is upgrading and rehabilitating CAREC transport corridor 5 & 6 to improve regional connectivity.
4. Through the National Highway Authority (NHA) of Pakistan, the GoP plans to implement CAREC Corridor Development Investment Program (CAREC CDIP) with financial assistance from ADB through a Multi-tranche Financing Facility (MFF).
5. Pakistan's National Indus Highway 55 (N-55) offers the shortest north-south bound CAREC spin-off transport corridor through Pakistan to link landlocked Afghanistan, Central Asia, and Xinjiang province of the People's Republic of China (PRC) with the Arabian Sea ports at Karachi and Gwadar.
6. It starts at M-9 near Petaro in Sindh Province, traverses through southern part of Punjab Province and terminates at N-5 near Peshawar in Khyber Pakhtunkhwa Province. The total length of the highway is 1264 km. Currently the N-55 is mostly a two-lane single carriageway which is in very poor condition and requires upgrading to 4-lane dual carriageway to sustain the presumed future traffic loads from CAREC countries.
7. Tranches 1 and 2 entail the construction of an additional 2-lane carriageway along the existing 2-lane carriageway, while Tranche 3 involves the rehabilitation of an existing two-lane carriageway (or financed by GoP). Most of the works will follow the existing NHA ROW. However, this will also include proposed improvements in vertical or horizontal alignment of the road in some sections and construction of bypass roads along selected urban centers.
8. The proposed project, construction of additional 2 lane along the existing 2 lane carriageway of N-55 from Shikarpur to Rajanpur included in Tranche 2 of MMF, is located in Sindh and Punjab Provinces of Pakistan.
9. Total length of the project is approximately 221.95 kilometers (383-604 km range) and it runs through the localities of Shikarpur, Kandhkot, Bakhsha Pur, Rahimabad Laro, Faizo Laro, Khanpur, Karam Pur, Kashmore. Rojhan, Ghoos Pur, Kotla Nasir and Rajanpur.

1.2 Requirement of Environmental Approval

10. According to Pakistan Environmental protection Agency (Review of IEE and EIA) Regulations 2000 of Pakistan Environmental Protection Act (PEPA), the proposed project falls under category D (Transport) of Schedule II, which requires EIA before commencement of construction.

11. An IEE study is also required as per ADB's "Safeguard Policy Statement", 2009, for category B projects where the proposed action falls.

1.3 Project Description

12. The proposed alignment runs on the right bank of Indus through the provinces of Sindh and Punjab in Pakistan. It passes through the localities of Shikarpur, Kandhkot, Khanpur, Ghouspur Kashmore, Rujhan and Rajanpur. This section of the highway is a part of CAREC Corridor 6.
13. The proposed highway is planned to be constructed as 2-Lane additional carriageway (ACW) adjacent to the existing 2-Lane facility from Shikarpur to Rajanpur including Kashmore Bypass, thus making the whole facility as 4-lane highway. It includes new bridges and cross-drainage structures on ACW. The total length of alignment from Shikarpur to Rajanpur is 221.95 kilometers (km 383-604).
14. For the construction purpose the alignment (221.95 km) has been divided in three sections including:
- i. Shikarpur- Kandhkot Section - 62.42 km
 - ii. Kandhkot- Kashmore Section – 58.78 km
 - iii. Kashmore- Rajanpur Section – 100.75 km
15. Additional carriageway will be designed at the first stage and improvement/rehabilitation will be executed in second stage by the GoP or through Tranche 3; however, Improvement/ Rehabilitation is not the part of Tranche -II.
16. Kashmore bypass will be constructed for dual carriageway with the length of 11.9 kilometer to avoid the traffic congestion in the city. This will cross the Pat Feeder Canal emerging from Guddo Barrage on River Indus.
17. The details of structure to be constructed for the corridor from Shikarpur – Rajanpur section is given as under:

Sr. No.	Type of Structure	Numbers
1	Culverts	500
2	Bridges/Flyovers	31
3	Underpasses/Cattle creeps	19

1.4 Project Alternatives

18. As the Project involves construction of additional carriageway along the existing N 55, three alternatives were studied including Alternative-I "No Project Option" Alternative-II "Dualization of Existing Carriageway by constructing of Additional Carriageway and Alternative-III "Rehabilitation of existing 2-Lanes at N-55 Alignment".
19. Taking in to account the socioeconomic and environmental benefits and extending the benefits to regional level and connectivity with the Central Asian region, alternative II, dualization of N 55 as CAREC Corridor 6 is the best choice.

1.5 Description of the Environment

20. The existing environment in and around the project area has been studied with respect to the physical, biological and socio-economic conditions.

21. In the province of Punjab, the additional carriageway of existing N-55 alignment will pass through agricultural cultivated fields and some barren land of Rajanpur district. While in Sindh province the area in the surrounding of alignment is water logged and saline near Shikarpur section, and rice and sugarcane cultivated field and linear plantation of tree species between the stretch of Shikarpur and Kashmore Districts.
22. The Indus Plain essentially forms the western extension of Indo-Gangetic Plain, and has been made up of the silt brought by the Indus and its numerous tributaries, such as Jhelum, Chenab, Ravi and Sutlej on the east bank, and Kabul, Kurram, Tochi, and others on the west bank. The Indus Plain is known for its agricultural fertility and cultural development throughout history.
23. The Project Area is located in Seismic Zone 2A, on the seismic zoning map of Pakistan, where 2A represents peak horizontal ground acceleration from 0.08 to 0.16g. An earthquake of magnitude 5 hit Sindh on May 9, 2014.
24. The climate of the Study Area is broadly hot and dry summer, mild winter and rainfall in monsoon. The highest recorded temperature is 52.8 °C (127.0 °F), and the lowest recorded temperature is -3.9 °C (25.0 °F). The mean Annual Precipitation is 110.40 mm.
25. Major water bodies in the Study Area include the Indus River, Kalri Baghar canal. Groundwater table varies from 3 to 20 meter and of saline nature with Total Dissolved Solids (TDS) ranging from 3000 to 4000 mg/ liter which is not fit for human consumption. However, along the River and canals the water is sweet for drinking purpose due to infiltration of surface water. Some wetlands were observed near the evaporation pond formed by the disposal of wastewater from the Guddo power plant and seasonal flood.
26. Project area is flooded by the Indus River which also carries flood water from the other four rivers of Pakistan including Satluj, Ravi, Jhelum and Chenab. These four rivers are tributaries of the Indus and their confluence is at the location of Punjnad. The Indus River has been responsible for 12 of the major floods in Pakistan including the floods of 1950, 1955, 1956, 1973, 1976, 1978, 1988, 1992, 1995, 1997, 2005, 2010 and 2012.
27. The total population of district Rajanpur, Shikarpur and Kashmore stood at 1,995,958, 1,231,481, 1,089,000 respectively during 2017 and the average household size ranges from 5.5 to 6.0 persons in these districts. Siraiiki is the predominant language being spoken in the district Rajanpur; while, Sindhi is spoken in the District Kashmore and Shikarpur. Urdu and Balochi are the other languages spoken in the project area.
28. The project area being part of the lower Indus basin, the climate of the tract is semi-arid, sub-tropical, the original flora of the area consists of tropical thorn forest type vegetation, in which thorny, usually hard wooded species and predominated acacia species being particularly characteristic. Approximately 228 privately owned plants of various species will be cut due to construction of additional carriageway. The trees have usually short boles and low branching crowns, which rarely meet except on exceptionally favorable spots. The usual-height of tree is 6-10m.
29. Environmental Monitoring locations have been identified for ambient air, noise and water quality monitoring. However, due to the lock down and travel restrictions imposed by the government due to the Covid-19 pandemic, monitoring could not be conducted. Currently hiring of EPA approved environmental laboratory is in progress and will be finalized in the first week of June 2020, after which monitoring will be initiated accordingly. The results will be incorporated in the report after completion of the process.

30. No threatened or endemic plant species are present in the Study Area. None of the plant species observed was endemic, their distribution is not limited to any specific site or habitat type, and the distribution is widespread.

1.6 Public Involvement & Grievance Redress Mechanism

31. During the field survey, significant efforts were made to identify the possible categories of stakeholders and their stakes. Various types of stakeholders identified were the villagers, local residents, government officials, shop owners, public representative, NGO's and general public. All the stakeholders had different types of stakes according to their perception about the project. Majority of the public responded in favor of the project considering the regional level connectivity, uplift of economy, increased land value, better access to the other cities of the country, control on accidents, and ease for the drivers and time saving.
32. In order to receive and facilitate the solution of affected people's (AP) concerns, complaints and grievances about the Project's environmental performance, a three-tier grievance redress mechanism (GRM) including local level and project level of grievance redress systems will be established. The GRM will address the APs' concerns and complaints proactively and promptly, using an understandable and transparent process that is gender responsive, culturally appropriate, and readily accessible to all segments of the APs at no costs and without retribution.
33. Grievance Redress Committee (GRC) will be established at local level, and at project level the displaced persons have been advised to constitute displaced person committees. The AP who is not satisfied with the decision of the GRC will have the right to take the grievance to next higher level, i.e. Environment, Afforestation, Land and Social (EALS) at National Highway Authority (NHA) Head Quarter (HQ) for its redress or to the appropriate judicial forum. All efforts will be made to redress grievances through the project GRM. However, aggrieved people have the right to access the country's judicial system as and when they require.

1.7 Anticipated Impacts and Mitigation Measures

Anticipated Impacts:

34. The proposed construction of the Road will have both positive and negative impacts during the construction and operational phases, for which proper mitigation measures are necessary. Following is the list of anticipated potential impacts during the construction phase of the project:
- Cutting of trees/bushes falling within the proposed corridor and for related facilities;
 - Disturbance to the public movement and in daily routine activities during construction;
 - Access restriction especially during growing and harvesting seasons for land owners and farmers
 - Air and Noise pollution due to the operation of construction machinery. Solid waste generation during construction and leaving the construction waste after completion;
 - Oil spillages from construction machinery, resulting in soil and groundwater contamination;
 - Surface water body (River Indus) contamination by the soil erosion and construction activities; and
 - Relocation of public utilities

35. Following are the potential impacts anticipated to occur both positive and negative during the operational phase of the project:
- Trees and landscape maintenance;
 - Road safety;
 - Pollution prevention and abatement;
 - Community Health and safety.
36. On the positive side, the proposed construction of the road is expected to generate considerable economic activity as new opportunities for skilled/unskilled manpower will be available as maximum efforts will be made to hire local labor/staff. Similarly, the project area would be developed and market value of the land would be increased during the operation phase of the project.

Remedial Measures

37. Mitigation measure would be adopted to avoid, minimize or compensate the potential adverse impacts of the project during pre-construction, construction and operation phase, including:
- SSEMP Preparation: EMP would be the part of contract document for implementation. Contractor will prepare SSEMP at preconstruction stage ensuring the compliance of EMP
 - Air pollution control: Provision of dust masks, and installing the pollution controlling devices such as Electrostatic Precipitator (EP), bughouse filters to asphalt plant, covering of materials and stockpiles, speed limits, cleanup of public roads and best practices for site management
 - Protection of faunal and flora: label all the trees which need to be removed, planting the compensatory trees, grass and sapling aftercare and planting the trees at construction stage not the operation stage.
 - Siting of Related Facilities: Appropriate siting and management of project related facilities such as construction camps, borrow pits, asphalt and batching plants;
 - Resource conservation: procurement of construction materials from approved quarries and crushers. Water Conservation: through recycling for dust suppression, prevention of pipe leakages and wastages of raw materials,
 - Energy Efficiency: best practices to be adopted for energy conservation such as machinery to be shut off while not in use and preservation and track record of raw material
 - Water pollution Control: protection of water quality of River Indus and streams, discharging wastewater through septic tanks of appropriate size, covering the manholes, and well-maintained washing facility
 - Load on existing infrastructure: Avoid the extra load on existing infrastructure/utilities of the local community and the rehabilitation of existing roads used by the contractor
 - Drainage and slope protection: Use of modern techniques for protection of slopes and avoid soil erosion and provision of cut off drains and settling basin to control the surface runoff
 - Workers Health & Safety: eliminating the work place hazards, provision of PPEs, lavatories and showers, equipped kitchen & clean eating areas, first aid kits, drinking water and ambience
 - Community Prevention and Health& Safety: Disease control by avoiding water impounding, restricted access, traffic control, covering the trenches and openings, and no abandoned structures

- GRM: Establishment and effective management of grievance resolution from workers and community. Placement of complaint register and logging of complaint records and action taken
- Noise Control: Identification of Noise Sensitive Receivers (NSRs), Source control, timings of operation and seeking suggestions from community
- Storage of Chemical and Dangerous Goods: Access control, spill control, and storage on hardened and non-permeable surface
- Waste Management: Waste Minimization techniques and recycle and reuse of construction waste material as fill material, good housekeeping practices, proper storage, labelling and containments of hazardous waste and used tire should not be left at site and proper storage of oil rags,
- Fire Prevention and Emergency Preparedness: Placement of Fire Extinguishers, Accident/ Incident Reporting system and Escape route and gathering area should be mapped, displayed, demarcated and not blocked/ obstructed.
- Protection of Cultural and Heritage Sites: Access for the religious and cultural site should not be disturbed due to construction and if any mosque coming in ROW a new mosque should be built in compensation
- Traffic Management Plan: A traffic diversion plan will be set out how the traffic on road and access to highway would be maintained with proper signage. In case of diversions, the speed limits and signs should be mentioned well ahead to guide the road users resulting in smooth traffic flow
- Tree Plantation: start tree plantation and landscaping during construction stage.
- During operation: mitigations involve road maintenance for potholes & mud holes, management of drainage, pedestrian and animal safety, speed control, management of accidental spill and protection of ROW and embankments. Maintenance of sapling and cutting the branches of tree coming on the roadside.

1.8 Environmental Management Plan

38. EMP would be the part of contract documents. The Contractor should be bound to follow the provisions of the contract documents especially about environmental protection and apply good construction techniques and methodology without damaging the environment.
39. Obligation of the contractor, to safeguard, mitigate adverse impacts and rehabilitate the environment should be addressed through environmental provisions in **the FIDIC¹ conditions of contract for construction, MDB harmonized addition- June 2010** and special clauses included in the contract related to environment. FIDIC clause 4.18 (protection of environment), 4.8 (safety procedures), 6.4 (labor laws), 16.3 (cessation of work/remedial work), 2.3 b (employers' personnel), 4.21 (progress report) are important in this regard.
40. Contractor would be responsible for preparation of SSEMP describing the mechanism to comply with the EMP and get it approved from CSC Environmental unit and PIU Environmental unit prior to mobilization.
41. Institutions involved for the executing of EMP would involve: EALS (NHA), Environmental Unit of PIU headed by (GM) CAREC-MMF, Environmental Unit of CSC, Environmental Unit of Contractor, Independent environmental monitoring contractor and EPA Punjab and Sindh

¹<https://www.adb.org/sites/default/files/fidic-gcc-construction.pdf>

42. Reporting and feedback mechanism involve that the contractor's environmental unit will manage the daily activities to be conducted in compliance with the EMP and will be responsible for weekly reporting; while, CSC would be responsible for monthly inspecting and monitoring report. CSC will draft the semiannual environmental monitoring report and finalize with the PIU. PIU will submit that report to EALS for onward submission to ADB. EALS would also submit the periodic reports to EPA as per conditions of environmental approval.
43. It is suggested that provision of the environmental mitigation cost will be made in the total cost of project, for which contractor will be paid on the basis of compliance reports. However, if the contractor fails to comply with the implementation of EMP and submission of the compliance reports, deductions will be made from the payments to the contractor claimed under the heads of environmental components.

1.9 Climate Smart Development

44. Climate change effects would be considered in two aspect:
- **Effect of climate change on the Project:** This could be due to extreme events of temperature change, flood risks, creation of water ponds and wetlands.
 - **Effect of Project on climate change:** This is due to generation of GHG emissions due to onsite site construction activities and processes at the related facilities. Emission of greenhouse gases cause global warming contributing to climatic changes on regional and global scale. Estimated GHG emissions are 176268 (792x222=176268) CO₂tons equivalent²
45. To make the project climate smart development, following mitigation measures should be adopted:
- **Resource conservation:** Avoid the wastage of raw material, leakages of water, oil, fuel, and use the material resistant to weather conditions
 - **Energy Efficiency and Controlling devices:** Use energy efficiency techniques and emission controlling devices. Avoid any unnecessary work and keep the material transportation distance to minimum;
 - **Enforcement of NEQS** applicable to gaseous emissions generated by construction vehicles, equipment and machinery
 - **Green Infrastructure:** provision of eye lands, tree plantations and landscaping

1.10 Conclusion

46. Conclusively, the proposed development will enhance the trade activities on regional basis and provide smooth and safe travelling corridor. This will involve some potential adverse environmental impacts of low to moderate level, which are mostly related to construction stages of the project and are however manageable by properly implementing the EMP and meaning full and timely consultation with the community. No long-term and significant adverse environmental impacts are however envisaged for the operation stage of the project.

²<http://documents.worldbank.org/curated/en/660861468234281955/pdf/696590ESW0P1010UBLIC00GHG0Web0final.pdf>

SECTION 2: INTRODUCTION OF THE PROJECT

2.1 Purpose of Project

47. In order to improve trade and commerce in global markets and improve the connectivity with Central Asian Countries, it is imperative to have a regional approach and good relation with neighboring countries. This is the prime objective of the Central Asia Regional Economic Corridor (CAREC) Program to improve and extend the corridor to the neighboring countries.
48. These Corridors within Pakistan will interconnect surrounding countries acting as a regional hub in order to promote regional integration and intra-and inter-regional trade. CAREC include eleven states and six corridors.
49. Corridors 5 and 6 which are north-south national corridors on the west side of the Indus River running through Pakistan. The Government of Pakistan (GoP) is upgrading and rehabilitating CAREC transport corridor 5 & 6 to improve regional connectivity.
50. Through the National Highway Authority (NHA) of Pakistan, the GoP plans to implement CAREC Corridor Development Investment Program (CAREC CDIP) with financial assistance from ADB through a Multi-tranche Financing Facility (MFF).
51. Pakistan's National Indus Highway 55 (N-55) offers the shortest north-south bound CAREC spin-off transport corridor through Pakistan to link landlocked Afghanistan, Central Asia, and Xinjiang province of the People's Republic of China (PRC) with the Arabian Sea ports at Karachi and Gwadar.
52. It starts at M-9 near Petaro in Sindh Province, traverses through southern part of Punjab Province and terminates at N-5 near Peshawar in Khyber Pakhtunkhwa Province. The total length of the Indus highway is 1264 km. Currently the N-55 is mostly a two-lane single carriageway which is in very poor condition and requires upgrading to 4-lane dual carriageway to sustain the presumed future traffic loads from CAREC countries.

2.2 Proposed Project

53. Tranches 1 and 2 entail the construction of an additional 2-lane carriageway along the existing 2-lane carriageway, while Tranche 3 involves the rehabilitation of an existing two-lane carriageway (or financed by GoP). Most of the works will follow the existing NHA ROW. However, this will also include proposed improvements in vertical or horizontal alignment of the road in some sections and construction of bypass roads along selected urban centers.
54. The proposed project, construction of additional 2 lane along the existing 2 lane carriageway of N-55 from Shikarpur to Rajanpur included in Tranche 2 of MMF, is located in Sindh and Punjab Provinces of Pakistan.
55. Total length of the project is approximately 221.95 kilometers (383-604 km range) and it runs through the localities of Shikarpur, Kandhkot, BakhshaPur, RahimabadLaro, FaizoLaro, Khanpur, KaramPur, Kashmore. Rojhan, GhoosPur, Kotla Nasir and Rajanpur.

2.3 Purpose of IEE

56. The purpose of IEE is as follows:

- To establish the baseline environmental conditions of the project area;

- To identify and assess the possible biophysical and social impacts of the proposed project on its surroundings.
- Recommend measures to avoid/control/mitigate the impacts envisaged in the assessment process
- To develop comprehensive Environmental Management Plan defining framework of mitigation and monitoring mechanism, institutional responsibilities, reporting requirements and budget to implement the recommended mitigation measures.

2.4 Scope of IEE

57. The scope of the IEE includes collection of information of existing conditions related to biophysical and socio-economic environment of the project area to establish the baseline environmental profile through primary and secondary sources including environmental monitoring. It also includes public consultations to address the concerns of public. Identification of sensitive receptors in the area to assess the magnitude and significance of impact will also be conducted. Recommendation of management approaches to eliminate, control or mitigate the identified impact and developing Implementation framework to execute the proposed mitigation measures with defined responsibilities and estimated financial requirement.

2.5 Project Categorization

58. According to ADB's Safeguard Policy Statement (SPS) 2009, the project is classified as category B project as its potential adverse environmental impacts are less adverse. These impacts are site-specific, and can be controlled or mitigated with mitigation measures. Thus, an initial environmental examination (IEE), including an EMP, is prepared for this project.

2.6 Study Area

59. The study area for IEE purpose is considered to be 50 m both sides of the road.

2.7 Project Management/Consultants

60. The proponent of the project is NHA while the Consultant is NESPAK, the addresses are given as under:

a) Proponent Contact Address:

General Manager (EALS)
National Highway Authority (NHA)
27 Mauve Area, G-9/1,
Islamabad
Ph: 051-8351506

b) Consultant Contact Address

National Engineering Services Pakistan (NESPAK) Private Limited
1-C, Block – N, Model Town Extension
Lahore
Tel: 042-99090000

2.8 Methodology of IEE

61. The following methodology was adopted for carrying out the EIA study of the proposed project:

- The meetings and discussions were held to plan the project execution including acquisition of data and identification of sources, determine time schedules and responsibilities to accomplish tasks; the logistics and other supporting needs for the execution of the project.
- Primary and secondary data were collected through field observations, environmental monitoring in the project area, concerned departments were consulted and published materials to establish baseline profile for physical, biological and socio-economic conditions of the area.
 - Data on physical Environment was collected including but not limited to geology, topography, soils, hydrology and drainage, water quality, air quality and noise.
 - The status of the flora and fauna of the study area was determined by an ecological survey, review of literature relevant to the area, and an assessment of terrestrial and aquatic environment.
 - The socioeconomic baseline was established utilizing literature field investigations, census data, structured interviews, maps, reports to generate the data required for description of the existing social environment including demography, education, land use, livelihoods poverty, traffic, transportation and access roads, health, and municipal status, community facilities, recreational activities, archaeological and cultural heritage.
 - Sensitive receptors of environmental impacts were identified along the road alignment.
- The impacts of the project on the physical, biological and socio-economic environment prevalent in the project area were anticipated at the design, construction and operational phases and characterized in relation to identified sensitive receptors of the impacts.
- Adequate mitigation measures were recommended to be incorporated at design stage.
- Implementation framework is also proposed to execute the proposed mitigation measures with defined responsibilities and estimated financial requirement.

2.9 Report Format

62. The structure of the IEE report is given as under:

Section 1	Executive Summary
Section 2	Introduction
Section 3	Policy, Legal and Administrative Framework
Section 4	Project Description
Section 5	Description of the Environment
Section 6	Analysis of Alternatives
Section 7	Anticipated Environmental Impacts and Mitigation Measures
Section 8	Environmental Management Plan (EMP)
Section 9	Public Participation, Consultation and Information Disclosure
Section10	Conclusions
	Appendices

SECTION 3: POLICY, LEGAL AND ADMINISTRATIVE FRAMEWORK

3.1 Requirement of Environmental Approval

63. According to Pakistan Environmental protection Agency (Review of IEE and EIA) Regulations 2000, the proposed project falls under category D (Transport) of Schedule II, which requires EIA before commencement of construction. Also, the projects with total cost of 50 million rupees and above qualify for an EIA and NOC would be required from the provincial EPAs of Sindh as well as Punjab and is in process.
64. An IEE study is also required as per ADB's "Safeguard Policy Statement", 2009, for category B projects where the proposed action falls.

3.2 National Policy and Legal Framework

65. In March 2005, the Government of Pakistan launched its National Environmental Policy, which provides an overarching framework for addressing the environmental issues Pakistan is facing, particularly pollution of freshwater bodies, coastal waters, air pollution, and lack of proper waste management, deforestation, natural disasters and climate change. The Climate Change Division is the responsible authority for environmental protection policy making in Pakistan.
66. Prior to the adoption of the 18th Constitutional Amendment, the Pakistan Environmental Protection Act (PEPA) 1997, was the governing law for environmental conservation in the country. Under PEPA 1997, the Pakistan Environmental Protection Council (PEPC) and Pak EPA were primarily responsible for administering PEPA 1997. Post the adoption of the 18th Constitutional Amendment in 2011, the subject of environment was devolved and the provinces have been empowered for environmental protection and conservation.
67. Summary of the applicable laws, policies and conventions are given in the **Table 3.1**.

Table 3.1: Summary of Applicable Laws, Policies and Conventions at National & International Level

Applicable Laws & Policies	Year	Objectives	Applicability
<i>ADB Policy and Operation Manuals</i>			
Safeguard Policy Statement (SPS 2009)	2009	To Ensure environmentally and socially sustainable projects supported by ADB. ADB will not projects that don't comply with ADB Policy and National Laws of Developing Members Countries (DMCs) ³	Direct
ADB Operational Manuals Bank Policy (BP Section F1/BP) &	2013	To achieve the SPS 2009 objective and deliver the policy principles. ⁴	Direct

³<https://www.adb.org/sites/default/files/institutional-document/32056/safeguard-policy-statement-june2009.pdf>

⁴<https://www.adb.org/sites/default/files/institutional-document/31483/om-f1-20131001.pdf>

Operational Procedure (OP section F1/OP)			
<i>National Laws & Policies</i>			
Sindh Environmental Protection Act	2014	Provide protection, conservation, rehabilitation and improvement of the environment for prevention and control of pollution and sustainable development. ⁵	Direct
Punjab Environmental Protection Act	2014	Provide protection, conservation, rehabilitation and improvement of the environment for prevention and control of pollution and sustainable development ⁶ .	Direct
Pakistan Environmental Protection Agency (Review of IEE/EIA) Regulations, 2000	2000	These regulations provide lists of the projects requiring IEE and EIA. They also briefly describe the preparation and review of environmental reports. Environmental approval required from Two provinces Sindh & Punjab. Project requires EIA under category D (Transport) of Schedule II. ⁷	Direct
National Environmental Quality Standards	2010	Define maximum allowable discharge limits for Air, noise, water and wastewater. ⁸	
Land Acquisition and Resettlement Act, 1894	1894	This law regulates the acquisition of land for public purposes and provides compensation in the form of cash, an alternative land allocation, or through other equitable arrangements (Sec 31). ⁹	Direct
Sectoral Guidelines	1997	Pakistan Environmental Assessment Procedure deals with general guidelines as well as sectorial guidelines for environmental assessment studies. The sectorial guidelines have been given for some categories of projects including road Projects.	Direct
Labor Laws (Amended) Ordinance, 1972.	1972	Construction and operational activities can affect the occupational health of the workers. Quantitative national standards with respect to these aspects are yet to be developed in	Direct

⁵<http://epasindh.gov.pk/>

⁶<http://www.punjablaws.gov.pk/laws/40.html>

⁸www.environment.gov.pk

⁹<http://www.megrevenueadm.gov.in/act/land-acquisition-act-1894.pdf>

		Pakistan. However, guidance in qualitative terms can be obtained from the Labor Laws (Amended) Ordinance, 1972.	
National Environmental Policy	2005	Conservation and efficient use of natural resources and sustainable development	Direct
Canal & Drainage Act	1873	Prevention of pollution of natural or man-made water bodies ¹⁰	Direct
Hazardous Substance Rules	2003	Safe handling of hazardous substances used in any workplace ¹¹	Direct
Factories Act	1934	Regulating the working environment to accommodate the safety and wellbeing of labourers. ¹²	Direct
SMART Rules	2001	Monitoring and reporting of industrial effluents and emissions	Not Applicable
Forest Act	1927	Safeguard of forests on state lands and private lands	Direct
Antiquities Act 1975& Sindh Cultural Heritage (Preservation) Act	1994	Protection of cultural resources in Pakistan	Indirect
Sind Wildlife Protection Act & Punjab Wildlife Protection Act	1972	To protect wildlife and to prevent /regulate hunting of birds and animals	Applicable
<i>International Conventions & Agreements</i>			
Ramsar Convention on Wetlands of International Importance	1971	Conservation and wise use of wetlands and their resources	Applicable
International Union for Conservation of Nature and Natural Resources	1963	Conservation of flora and fauna species that are at risk of extinction from the globe	Not Applicable

¹⁰[http://www.cmsdata.iucn.org/downloads/thecanal and drainage act 1873.pdf](http://www.cmsdata.iucn.org/downloads/thecanal%20and%20drainage%20act%201873.pdf)

¹¹<http://www.fao.org/docstore/pdf/pak64438.pdf>

¹²<http://www.ilo.org/docs/WEBTEXT/35384/64903/E97PAK01.HTM>

Convention on Migratory Species of Wild Animals (CMS)	1983	Protection of migratory species of animals by every state that lives or passes through their national jurisdiction	Indirect
Convention on International Trade in Endangered Species of Wild Fauna and Flora (CITES)		Safe and Sustainable trade of wild animals and plants without threatening to their survival	Indirect
Millennium Development Goals (MDGs)	2000	Development of nations by eradication of social and environmental issues	Indirect
Vienna Convention for the Protection of the Ozone Layer	1992	Vienna Convention for the protection of the Ozone Layer highlights the need to protect the Ozone layer for conserving environment for the present and future generations.	Indirect
United Nations Framework Convention on Climate Change (UNFCCC)	1994	This convention highlights the broad guidelines to protect the Climate of the Planet.	Direct
Basel Convention on the Control of Trans-boundary Movements of Hazardous Wastes and their disposal:	1994	Basel Convention deals with the controlled trans-boundary movement of Hazardous Wastes and their disposal.	Indirect
Stockholm Convention on Persistent Organic pollutants (POPs)	2001	This Convention protects human health and the environment from the harmful impacts of persistent organic pollutants (POPs).	Indirect
Convention Concerning the Protection of the World Cultural and Natural Heritage	1972	cultural heritage and the natural heritage are increasingly threatened with destruction not only by the traditional causes of decay, but also by changing social and economic conditions which aggravate the situation with even more formidable phenomena of damage or destruction.	Currently not applicable as no cultural heritage site in the ROW
International Labor Organization (ILO)		The ILO aims to ensure that it serves the needs of working women and men by bringing together governments, employers and workers to set labor standards develop policies and devise programs.	Applicable

3.3 ADB's Safeguard Policy Statement, 2009

68. ADB's Safeguard Policy Statement consists of three operational policies on the environment, Indigenous People and involuntary resettlement. SPS, 2009 provides information on good practice approaches to implement the safeguards. Overall, this policy provides to avoid, minimize, or mitigate adverse environmental and social impacts, including protecting the rights of those likely to be affected, marginalized by the development process.

3.4 Safeguard Requirements-1: Environment

69. The Safeguard Requirement-1: Environment, of SPS, 2009 states to ensure the environmental soundness and sustainability of projects and to support the integration of environmental considerations into the project decision-making process. Safeguard environmental requirement principal is to conduct an environmental assessment for each developmental proposal to identify potential impacts and then to mitigate all those negative impacts properly. The proposed mitigation measures, monitoring and reporting requirements, institutional arrangements, schedules, cost estimates and performance indicators are to be documented and reflected in the environmental assessment report.

a) Categorization of the Environmental Project

70. According to ADB Safeguard Policy Statement (2009), the project is classified as category "B" and therefore an IEE is required for the project. The process of determining a project's environment category is to prepare a Rapid Environmental Assessment (REA). REA requires the completion of the environmental categorization form prior to the Project initiation. REA uses sector-specific screening checklist, considering the type, size, and location of the proposed project; sensitivity and vulnerability of environmental resources in project area; and the potential for the Project to cause significant adverse environmental impacts. A project is classified as one of the four environmental categories (A, B, C, or FI) based on the most environmentally sensitive component. Categories are as follows:
71. **Category A:** A proposed project is classified as category A if it is likely to have significant adverse environmental impacts that are irreversible, diverse, or unprecedented. These impacts may affect an area larger than the sites or facilities subject to physical works. An environmental impact assessment (EIA), including an environmental management plan (EMP), is required.
72. **Category B:** A proposed project is classified as category B if its potential adverse environmental impacts are less adverse than those of 'category A' projects. These impacts are site-specific, few if any of them are irreversible, and in most cases mitigation measures can be designed more readily than for category A projects. An initial environmental examination (IEE), including an EMP, is required.
73. **Category C:** A proposed project is classified as category C if it is likely to have minimal or no adverse environmental impacts. An EIA or IEE is not required, although environmental implications need to be reviewed.
74. **Category FI:** A proposed project is classified as category FI if it involves the investment of ADB funds to, or through, a financial intermediary.
75. For Category 'B' projects, the final IEE report would be posted on ADB website.

3.5 Administrative Framework

National Highways Authority (NHA)

76. The implementing agency of the proposed project is NHA, Government of Pakistan. The management of NHA will ensure that all the proposed measures are effectively implemented at the design, construction and operational stages.

Environmental Protection Agency of Sindh and Punjab

77. Provincial EPAs will be responsible for reviewing the report, issuing No Objection Certificate (NOC) and overall/broad based monitoring of the proposed project activities.

3.6 Comparison of Environmental Quality Standards

78. As per SPS 2009, following is a brief comparison of US EPA, WHO and Local Environmental Quality Standards for Punjab and Sindh for air noise and drinking water and whichever is more stringent is adopted. Since the stringent standards vary for each parameter, the most stringent one is highlighted and that is used as reference.

79. The national standards for noise in Commercial area is more stringent, thus local standards will be adopted. Similarly, for air WB standards are more stringent except NO₂ and O₃. Drinking water quality standards are similar to WB standards except Zinc and Lead, which will be adopted from WB standards and manganese and Nickel will be adopted from US-EPA.

80. **Table 3.2, 3.3 and 3.4** gives comparison of noise, air and water quality standards.

Table 3.2: Comparison of Noise standards

#	Category of Area	PEQS ¹³		SEQS		WB guidelines ¹⁴		USEPA Standards ¹⁵	
		Day Time	Night Time	Day Time	Night Time	Day Time	Night Time	Indoor	Outdoor
1	Residential Area	55	45	55	45	55	45	45	55
2	Commercial Area	65	55	65	55	70	70	70	70
3	Industrial Area	75	65	75	65	70	70	70	70
4	Silence Zone	50	45	50	45	-	-	-	-

¹³http://www.environment.gov.pk/PRO_PDF/NoisePaperGen.pdf

¹⁴<http://www.ifc.org/wps/wcm/connect/06e3b50048865838b4c6f66a6515bb18/1-7%2BNoise.pdf?MOD=AJPERES>

¹⁵http://www.environment.gov.pk/PRO_PDF/NoisePaperGen.pdf

Table 3.3: Comparison of Air Quality Standards

#	Pollutant	PEQS		SEQS	USEPA		WB	
		Time Weighted average	Concentration standard	Concentration standard	Time weighted average	Concentration standard	Time weighted average	Concentration standard
1	SO ₂	Annual average	80 µg/m ³	80 µg/m ³	Annual arithmetic mean	80 µg/m ³ , (0.030 ppm)	24 Hours	20µg/m ³
		24 hours	120 µg/m ³	120 µg/m ³	24-hours average	365 µg/m ³ , 0.50 ppm	10 minutes	500 µg/m ³
2	NO	Annual average	40 µg/m ³	40 µg/m ³	-	-	-	-
		24 hours	40 µg/m ³	40 µg/m ³	-	-	-	-
3	NO ₂	Annual average	40 µg/m ³	40 µg/m ³	Annual arithmetic mean	100 µg/m ³ , (0.053 ppm)	1 year	40 µg/m ³
		24 hours	80 µg/m ³	80 µg/m ³			1 hour	200 µg/m ³
4	O ₃	1 hour	130 µg/m ³	130 µg/m ³		235 µg/m ³ , (0.12 ppm)		
		-	-	-	8-hours average	157 µg/m ³ , (0.08 ppm)	8 hours daily maximum	100µg/m ³
5	SPM	Annual average	360 µg/m ³	360 µg/m ³	-	-	-	-
		24 hours	500 µg/m ³	500 µg/m ³	-	-	-	-
6	PM ₁₀	Annual average	120 µg/m ³	120 µg/m ³	Annual arithmetic mean	50 µg/m ³	1 year	20µg/m ³
		24 hours	150 µg/m ³	150 µg/m ³	24-hours average	150 µg/m ³	24 hours	50µg/m ³
7	PM _{2.5}	Annual average	15 µg/m ³	40 µg/m ³	Annual arithmetic mean	15 µg/m ³	1 year	10µg/m ³
		24 hours	35 µg/m ³	75 µg/m ³	24-hours average	65 µg/m ³	24 hours	25µg/m ³
		1 hour	15 µg/m ³	15 µg/m ³	-	-	-	-
8	Lead	Annual average	1 µg/m ³	1 µg/m ³	Quarterly average	1.5 µg/m ³	-	-
		24 hours	1.5 µg/m ³	1.5 µg/m ³			-	-
9	CO	8 hours	5 mg/m ³	5 mg/m ³	8-hours Average	10 mg/m ³ , (9 ppm)	-	-
		1 hour	10 mg/m ³	10 mg/m ³	1-hour average	40 mg/m ³ , (35 ppm)	-	-

Table 3.4: Comparison of Drinking Water Quality Standards

#	Parameters	Concentration Standards			
		PEQS (mg/l)	SEQS (mg/l)	WHO (mg/l)	USEPA (mg/l)
Chemical Parameters					
1	Aluminium (Al)	≤ 0.2	≤ 0.2	0.2	0.05-0.02
2	Ammonium (NH3)	-	-	1.5	NS
3	Antimony (Sb)	≤ 0.005	≤ 0.005	0.005	0.006
4	Arsenic (As)	≤ 0.05	≤ 0.05	0.01	0.05
5	Barium (Ba)	0.7	0.7	0.7	2.0
6	Boron (B)	0.3	0.3	0.3	NS
7	Cadmium (Cd)	0.01	0.01	0.003	0.005
8	Chloride (Cl)	< 250	< 250	250	250
9	Chromium (Cr)	≤ 0.05	≤ 0.05	0.05	0.1
10	Copper (Cu)	2	2	1-2	1.0
11	Cyanide (CN)	≤ 0.05	≤ 0.05	0.07	0.2
12	Fluoride (F)	≤ 1.5	≤ 1.5	1.5	2.0-4.0
13	Iron (Fe)	-	-	0.3	0.3
14	Lead (Pb)	≤ 0.05	≤ 0.05	0.01	0.015
15	Manganese (Mn)	≤ 0.5	≤ 0.5	0.1-0.5	0.05
16	Mercury (Hg)	≤ 0.001	≤ 0.001	0.001	0.002
17	Molybdenum (Mo)	-	-	0.07	NS
18	Nickel (Ni)	≤ 0.02	≤ 0.02	0.02	0.1
19	Nitrate (NO ₃)	≤ 50	≤ 0.50	NS	10.0 as N
20	Nitrite (NO ₂)	≤ 3		NS	10.0 as N
21	Selenium (Se)	0.01	0.01	0.01	0.05
22	Silver (Ag)	-	-	NS	0.1
23	Sodium (Na)	-	-	200	20
24	Sulphate (SO ₃)	-	-	250	250
25	Residual Chlorine	0.2-0.5	0.2-0.5	-	-
26	Zinc (Zn)	5.0	5.0	3.0	5.0
Physical Parameters					
27	Color	≤ 15 TCU	≤ 15 TCU	15 cu	15 cu
28	Taste	Non-	Non-	-	-

#	Parameters	Concentration Standards			
		PEQS (mg/l)	SEQS (mg/l)	WHO (mg/l)	USEPA (mg/l)
		Objectionable / Acceptable	Objectionable / Acceptable		
29	Odor	Non- Objectionable / Acceptable	Non- Objectionable / Acceptable	N S	3 TON
30	Turbidity	< 5 NTU	< 5 NTU	5 NTU	0.5-5.0 NTU
31	Total hardness	< 500 mg/l	< 500 mg/l	-	-
32	TDS	< 1000	< 1000	1000	500
33	pH	6.5-8.5	6.5-8.5	6.5-8.5	6.5-8.5
Biological Parameters					
34	E-Coli	Must not be detectable in any 100 ml sample	Must not be detectable in any 100 ml sample	0	0
35	Total Coliforms	Must not be detectable in any 100 ml sample	Must not be detectable in any 100 ml sample	0	0

WHO Environmental Quality Standards and NEQS are attached as **Annex I**.

SECTION 4: PROJECT DESCRIPTION

4.1 Rational of the Project

81. This section of Indus highway (N 55) is the part of CAREC Corridors 6 within Pakistan and will interconnect neighboring countries acting as a regional hub in order to promote regional trade. CAREC include six corridors in eleven states. The Government of Pakistan (GoP) is upgrading and rehabilitating CAREC corridor 6 inside the boundaries of Pakistan to improve regional connectivity. This is the shortest north – south route between Peshawar and Hyderabad.

4.2 Location of Project

82. The proposed alignment runs on the right bank of Indus through the provinces of Sindh and Punjab in Pakistan. Project road starts ahead of junction of N-55 and N-65 (Sukkur - Quetta National Highway) at Shikarpur and traverses through various cities /districts Kandhkot, Khanpur, Ghouspur, Kashmore, Rujhan and terminates at Rajanpur after crossing Rajanpur City. It also passes through various tributaries of River Indus. The alignment passes through two provinces: i.e Punjab and Sindh. The highway is a part of CAREC Corridor 6 as shown in **Figure 4.1**.

4.3 The Project

83. The proposed highway is planned to convert existing 7.3 m wide road section into standard four lane road facility from Shikarpur to Rajanpur including Kashmore Bypass, thus making the whole facility as 4-lane highway. It involves localized improvements in geometric configuration of existing road geometry at locations and extension of existing culverts/bridges. The total length of alignment from Shikarpur to Rajanpur is 221.95 kilometers (km 383-604).
84. For the construction purpose the alignment (221.95km) has been divided in three sections including:
1. Shikarpur- Kandhkot Section - 62.42 km
 2. Kandhkot- Kashmore Section – 58.78 km
 3. Kashmore -Rajanpur Section – 100.75 km
85. Additional carriageway will be designed at the first stage and improvement/rehabilitation will be executed in second stage by the Government of Pakistan; however, Improvement/ Rehabilitation is not the part of Tranche -II. Alignment map revealing the cities, towns and rural settlements along the corridor is given in **Figure 4.2**.
86. The alignment from Shikarpur to Rajanpur passes through plain terrain, where majority of the area is heterogeneous in terms of landscape (mainly including water-logged areas, vegetative land along N-55 highway, commercial structures and arable field).
87. New four lane bypass with a length of 11.9 km is provided for Kashmore city which is a densely populated center to avoid the traffic congestion in the city. This will cross the Pat Feeder Canal emerging from Guddo Barrage on River Indus. Bypass alignment is shown in **Figure 4.3**. Construction of new culverts and bridges will also be involved in the bypass portion. In addition, major junctions i.e: Junction of N-55 & N-65 at Shikarpur, entry of Kandhkot city & entry of Rajanpur city are provided with grade separation by provision of loops/ramps arrangement with combination of underpass.




Figure 4.1: Location map of the Project Area



Figure 4.2: Alignment Map of Shikarpur- Rajanpur Section ACW



Figure 4.3: Alignment of Kashmore Bypass

88. The details of structures to be constructed to dualize the Shikarpur – Rajanpur section is given in **Table 4.1**.

Table 4.1: Detail of Structures to be constructed

Sr. No.	Type of Structure	Numbers
1	Culverts	500
2	Bridges/Flyovers	31
3	Underpasses/cattle Creeps	19

89. Three major canals emerging from Guddo Barrage on River Indus crosses the alignment near Khandh Kot and Kashmore where bridges will be constructed for additional carriageway. A flyover will be constructed on Railway track near Kashmore.

90. Water ponds can be frequently observed on both sides of the highway from Shikarpur to Rajanpur, where special protection work will be required for additional carriageway. All the structures like culverts/bridges and cattle corridors will be extended/rehabilitated. Sharp curves will be addressed, and geometric configuration will be improved keeping in view the TOR requirement and client consent.

4.4 Duration of the Project:

91. The expected duration for construction is about 3 years.

4.5 Geometric Design of the Proposed Additional Carriageway

92. The geometric design of the proposed road Project meets the following criteria:

Geometric design - AASHTO policy on Geometric design of highways & streets -2004
Material & testing - AASHTO – ASM
Pavement Design -AASHTOguideforDesignofPavementStructures1993
Seismic Design - Uniform Building Code (UBC) and seismic zone map of Pakistan
&AASHTO

93. The typical cross section for the Additional carriageway of N 55 is shown in the **Figure4.4 (a) & (b)**.




Figure 4.4 (a) : Typical Cross Section for Additional Carriageway




Figure 4.4 (b) : Typical Cross Section for New Construction

94. The proposed road additional carriageway at N-55 (Indus Highway) shall conform to the following specifications:

Design Speed:

Design Speed for Plain Terrain	: 100 km/hr.
Design speed on few constrains	: 80 Km/hr.

Road Cross Section:

Number of Lanes	: 4 Lanes (Two Additional Lanes& Two already exists)
Lane Width	: 3.65 m

Paved Shoulder:

Inner Shoulder	: 1 m
Outer Shoulder	: 2.5 m to 3.0 m (with 0.5m to 1m earthen rounding)

Road Cross Slope

Carriage Way	: 2 %
Shoulders	: 4%
Proposed Right of Way:	: 20 m for additional carriageway 100 m for bypass

95. The recommended pavement thickness for the additional carriageway is given below:

- Asphaltic Concrete Wearing Course (ACWC): 50 mm
- Asphaltic Concrete Base Course (ACBC) : 160 mm
- Aggregate Base Course (ABC) : 200 mm
- Granular Sub-base (GCB) : 200 mm
- Improved Subgrade : 300 mm (25% CBR)

4.6 Embankment Design

96. In the areas of high-water table, filter cut-off layer shall be provided to protect the pavement structure. It includes the provision of day-lighting drainage gallery at the bottom of pavement over subgrade top. The consultant may allow the filter cut-off to function both as a pavement subgrade and filter cut-off layer. Surface drainage will also be designed properly with defined disposal points with the special considerations. Design CBR for the embankment will be based on NHA specification of 5%, however, if potentially high strength material is available within easy lead of the project vicinity, design CBR value for embankment will be changed in order achieve cost benefit. In case of paddy fields, granular sand to appropriate depth will be provided to arrest the seasonal water ponding.

4.7 Traffic Count and Projection

97. Traffic study to determine AADT at various locations was carried out by the design consultant. The projected traffic was calculated for the period of thirty years and the predicted design levels over the design life of the N-55 are presented in **Table 4.2**.

Table 4.2: Summarized Total Traffic Projections by Type of Vehicles

JACOBABAD CHOWK SHIKARPUR (Start Point)

Both Direction: Shikarpur to Khanpur

Years	Number of Years(n)	VEHICLES													Total Traffic
											TRUCKS				
		Rickshaw	Motor Cycle	Car/Jeep	Pajero	Hiace Wagon	MiniBus	Bus	Loader pick-ups	TRACTOR TROLLY	2-AXLE	3-AXLE	4-AXLE	/5-AXLE &Above	
2017	1 13 26	1255	2855	678	96	28	3	16	163	61	73	31	3	10	5272
2029		1736	4959	908	128	40	4	22	254	82	99	42	4	13	8292
2042		2208	7189	1149	163	52	5	29	360	106	128	55	5	17	11465

ADMORE PUMP AT RAJANPUR ON N-55 (End Point)

Both Directions Rojhan to Rajanpur

Years	Number of Years (n)	VEHICLES													Total Traffic
											TRUCKS				
		Rickshaw	Motor Cycle	Car/Jeep Taxi	Pajerozuki Puck	Hiace Wagon	Mini Bus	Bus	Loader pick-ups	TRACTOR TROLLY	2-AXLE	3-AXLE	4-AXLE	/ 5-AXLE &Above	
2017	1	269	2739	2851	99	168	2	356	139	285	977	1085	258	635	9864
2029	13	373	4758	3819	133	235	3	498	216	384	1316	1461	347	856	14399
2042	26	474	6898	4832	168	305	4	648	306	497	1703	1891	449	1107	19284

98. The traffic categories noted during count survey were: Animal-drawn Vehicles; Cycles; Motorcycles; Rickshaws; Cars/Jeeps/Taxis/Pajeros; Loader Pickups; Hiace, Buses; Mini Buses/Coasters; Tractors/Tractor Trolleys; Trucks 2–Axles; Trucks 3–Axles; Large Trucks/Trailers/4-Axles and above. Traffic forecasts have been made for 30 years. The traffic analysis at start and end point of this section are given in table 4.2. The project is expected to facilitate about 20,000 Annual Average Daily (AAD) vehicles in its design life.

4.8 Construction Logistics

99. The location for project facilities such as Camp sites, material storage yards, equipment yards, workshops, will be selected keeping in view the availability of access to communication and local markets, and an appropriate distance from sensitive areas in the vicinity. Final locations will be selected by the contractor in consent with supervision consultant (SC) after approval from NHA.

100. It is envisaged that the Project will attract about 1500-2000 skilled/unskilled labor for each section. It should be ensured that maximum labor hired would be local who will return home in the evening. However, the majority of the skilled labor working on site is likely to be migrated from other part of the country. It is a contractor's contractual obligation to provide a labor camp and consultants and employer office on site. The location of the labor camps should be at least 500 meters away from the nearby human settlements. They will require services such as electricity, water, sanitation facilities and masonry work. The specific site for these facilities cannot be determined at this stage and would be finalized at the time of contractor's mobilization.

101. The Asphalt and batching plants would be installed at appropriate areas adjacent to the proposed ACW. These facilities should be at least 500 meters away from any human settlement and equipped with emission controlling devices.

102. The municipal solid wastes generated in construction & workers camp will be disposed of at nearest identified location of disposal / landfill sites of local authority under their consent. Lavatories with shower facilities should be provided with sufficient water availability to labor and the wastewater disposal should be through septic tank and soakage pit of the adequate size.

4.9 Construction Materials

103. The materials used in construction of the road for the proposed project would include coarse aggregates (crush), fine aggregates (sand), steel, water, asphalt, reinforcement, cement etc. According to the geotechnical investigation report of the proposed project, crushed base and sub-base materials will consist of a blend of processed aggregates such as crushed stone fragments and rock dust. To meet the grading requirement, blending may also be required. The design CBR for these materials shall be governed by the project specifications.

104. Contractor will decide for sources of construction material and that would be approved by NHA. Aggregate is available at Shahwali and Rohri aggregate quarry; while, sand is available at Sui. Furthermore, the approved list of quarries and borrow pits is given on Composite Schedule Rates (CSR) prepared by NHA for Punjab and Sindh province 2014¹⁶ on these websites:

¹⁶ <http://nha.gov.pk/wp-content/uploads/2018/02/CSR-2014-Punjab.pdf>
<http://nha.gov.pk/wp-content/uploads/2018/02/CSR-2014-Sindh.pdf>

105. The earth required for construction of additional carriageway and alternative routes at the proposed location (Shikarpur to Rajanpur) would be considered at the available government land (demarcated RoW by NHA). If earth is required to be lifted from private own land, then the owner(s) of the land will be duly compensated. Contractor will be responsible to make an agreement with land owner to excavate and restore the borrow area considering the conditions given in Management Plan.

106. Construction material for the proposed project will be required in following quantities:

Subbase: 1.06 million cubic meter

Aggregate base: 0.85 million cubic meter

Asphalt: 1.5 million tons

4.10 Construction Equipment

107. The list of the machinery and the equipment required for the proposed project is provided in **Table 4.3**.

Table 4.3 Machinery and Equipment Requirement

Sr. #	Type of Machinery/ Equipment	Sr. #	Type of Machinery/ Equipment
1	Bulldozer	13	Rollers
2	Excavator	14	Tandem
3	Dump Trucks	15	Vibratory Combination Rubber Mounted Tandem Roller
4	Grader	16	Crane
5	Grader with Scarifier	17	Beam Launching Truss
6	BackHoe	18	Piling Equipment
7	Water Tanker	19	Vibrator for Concrete
8	Front End Loader	20	Road Marking Machine
9	Paver	21	Concrete Batching Plant
10	Power Broom	22	Asphalt Premix Plant
11	Bitumen Pressure Distributor	23	Laboratory with Equipment (1 permanent & 1 mobile)
12	Pug Mill		

4.11 Personnel Required

108. Staff requirements during construction phase of the proposed Project are 206 and 107 for NHA and consultant respectively¹⁷.

109. Man power requirement of NHA for construction is given below:

Designation	No. of Posts	Months
General manager (Construction)	1	36
Project Director (Engineer)	3	36
Deputy Director (Engineer)	3	36
Assistant Director (Engineer)	3	36
Assistant Director (Environment)	3	36

¹⁷ PC-1 of Shikarpur-Rajanpur Section (November, 2019).

Assistant Computer programmer	3	36
Inspector/Supervisor	6	36
Deputy Director (Land)	1	12
Assistant Director (Legal)	3	12
Assistant Director (L & S)	3	12
Land acquisition (collector)	3	12
Qanoongo	9	12
Patwari	15	12
Surveyor	6	36
Accountant	2	36
Superintendent (Admin)	2	36
Account Assistant	2	36
Computer Operator	6	36
Office Assistant	6	36
Stenotypist	3	36
UDC	6	36
LDC	6	36
Driver	30	36
Naib Qasid	6	36
Helper	15	36
Chowkidar	10	36
Sweeper	10	36
Round guard	10	36
PA	30	36

110. Man power requirement for consultant during construction stage:

Designation	No. of Posts	Months
Head office	1	24
Resident Engineer	4	96
Highway Engineer	4	96
Structure Engineer	4	96
Environmental Engineer	4	96
Bridge Engineer	4	96
Material Engineer	4	96
Material Inspectors	8	192

Site Inspectors	16	384
Surveyors	16	384
Lab technicians	8	192
Quantity Surveyors	4	96
Others	30	720

111.The estimated man power requirement for contractor including skilled and unskilled labour is 300.

SECTION 5: DESCRIPTION OF THE ENVIRONMENT

5.1 Physical Environment

5.1.1 Geology and Soil


112. Based on the physical environment and geology, the project area falls in the Indus Basin. The Indus Plain essentially forms the western extension of Indo-Gangetic Plain, and has been made up of the silt brought by the Indus and its numerous tributaries, such as Jhelum, Chenab, Ravi and Sutlej on the east bank, and Kabul, Kurram, Tochi, and others on the west bank.
113. The Indus Plain is known for its agricultural fertility and cultural development throughout history. On the basis of landforms and hydrology, the Indus Plain may be divided into the 'upper' (north) and 'lower' (south) Indus Plains.
114. The Upper Indus Plain (where the project is located) differs from the Lower Indus Plain in that the land surface is divided into several interfluvies, or doabs, by the major tributaries. Area close to Indus River is categorized as loamy and seasonal flooded soil of river plains.

5.1.2 Topography and Land Use

115. The elevation of the Study Area generally ranges between 15 and 45 m above mean sea level. It slopes towards the Indus River which runs along the eastern boundary. There are small sedimentary hills in the western and southwestern side that rise to an elevation of about 100 meters. The western side is gravel plain with very little natural vegetation cover. The eastern half of the is part of the Indus River flood plain.
116. There are two main land uses in the Study Area within around 5-7Km from the proposed dualized section of road. These are the agricultural land in the east and the urban and semi urban areas in the south. The Indus River floodplain has good alluvium soil and has been converted to productive farmlands.
117. Areas important to be considered are water logged and salinity areas, rice and sugarcane cultivated field and linear plantation of tree species of Shikarpur and Kashmore Districts. The land-use map of the study area from Shikarpur to Rajanpur is shown in **Figure 5.1**.

5.1.3 Climate and Air Quality

118. The climate of the project area is broadly described as hot and arid in Rojhan and its closed proximity areas. Particularly Shikarpur and Kandhkot area has a hot desert climate with extremely hot summers and mild winters.
119. The highest recorded temperature is 52.8 °C (127.0 °F), and the lowest recorded temperature is -3.9 °C (25.0 °F). The project area lies in a region where monsoon rainfall is low, and the distinction between the summer and monsoon seasons is not very well marked.
120. The mean Annual Precipitation is 110.40 mm. Even the scarce rainfall is not very distributed, and around 55 – 60% of it occurs within the months of July and August. The rain's effect, on temperature for instance, is minimal. The Dominant wind direction is southwest.
121. Baseline air quality monitoring has been conducted in July 2020 for NO, NO₂, SO₂, PM₁₀, CO and the results are provided in the **Table 5.1**. The criteria for selection of monitoring locations are attached as **Annex II**. Monitoring reports for ambient air, noise, surface water and ground water are attached as **Annex III** whereas monitoring/sampling points are presented in the figure below.



Ambient Air & Noise (A&N) Monitoring		
A&N-01	Residential Area	Shikarpur
A&N-02	Rural Health Centre & Residential Area	Khanpur
A&N-03	Masjid Ali-ul-Murtaza & Residential Area	Kandhkot
A&N-04	Jamia Masjid Qadria & Residential Area	Kashmore
A&N-05	Rural Health Centre & Residential Area	Rojhan
A&N-06	Noorani Masjid & Residential Area	Rajanpur

Table 5.1: Monitoring Results of Ambient Air

Location	Parameter				
	PM ₁₀	CO	NO	NO ₂	SO ₂
Units	µg/m ³	mg/m ³	µg/m ³	µg/m ³	µg/m ³
Duration	24 hrs	8 hrs	24 hrs	24 hrs	24 hrs
Kund Kot	102.6	1.17	13.5	14.9	14.35
Kashmore	103.8	0.98	12.7	14.7	14.02
Rojhan	104.1	1.15	12.36	15.06	14.16
Rajanpur	100.9	1.05	12.88	14.93	13.86
Shikarpur	100.7	1.10	13.72	14.9	13.68
Khanpur	102.8	0.81	11.83	14.10	13.19
SEQS Limit	150	5	40	80	120
IFC Guidelines	50 (24 hour)	-	-	40 (1 year) 200 (1 hour)	20 (24-hour)

122. The results are within prescribed limits of national and international standards for NO₂ and SO₂. PM-10 exceeds values recommended in IFC guidelines. The detailed results are attached as **Annex III**.

5.1.4 Water Resources

a. Surface Water

123. Major water bodies in the Study Area include the Indus River, Kalri Baghar and Desert canal, Kandhkot branch, Choi branch, Umar Wah, and Kadra canal.

124. Water quality in major water bodies has been monitored during July 2020 in sampling points indicated in the figure above and detailed in a table below.

Surface Water (SW) Sampling		
SW-01	Nullah Crossing	Meeral
SW-02	Begari Canal Crossing	Kandhkot
SW-03	Nearby Water Pond	Kandhkot
SW-04	Nearby Water Pond	Near Bakshapur
SW-05	Pat Feeder Distributary Crossing	Kashmore
SW-06	Pat Feeder Canal Crossing	Kashmore
SW-07	Matwah Distributary Crossing	Near Rojhan
SW-08	Kadra Canal Crossing	Near Kot Mithan

The results of the surface water monitoring are given in **Table 5.2**.

Table 5.2: Monitoring Results of Surface Water

Sr. No.	Parameters	Units	PEQS	Kot Mithan, Rajanpur	Rojhan	Kashmore	Bakhshapur Kahsmore	Bakhshapur (2) Kahsmore	Kandhkot	Niaz Hussain Jatoi, Khanpur	Niaz Hussain Jatoi (2), Khanpur
1.	Temperature	°C	---	16	18	19	15	16	18	16	18
2.	pH	--	6 – 9	7.9	7.8	8	7.8	7.9	8.1	7.8	7.9
3.	TDS	mg/L	3500	1963	1854	2167	1993	2087	2371	1934	2130
4.	COD	mg/L	150	135	127	116	124	128	116	127	103
5.	BOD ₅ at 20°C	mg/L	80	71	69	73	76	81	73	83	76
6.	Phenolic Compounds (as Phenols)	mg/L	0.1	0.08	0.06	0.08	0.09	0.06	0.09	0.07	0.003
7.	Chloride	mg/L	1000	261	272	152	143	149	136	129	110
8.	Copper (Cu)	mg/L	1.0	0.86	0.97	0.82	0.67	0.51	0.53	0.41	0.040
9.	Iron (Fe)	mg/L	8.0	0.96	1.03	0.93	0.82	0.73	0.81	0.33	0.25
10.	Lead (Pb)	mg/L	0.5	ND	ND	ND	ND	ND	ND	ND	ND
11.	Manganese (Mn)	mg/L	1.5	0.14	0.093	0.087	0.073	0.067	0.051	0.046	0.037
12.	Sulfate (SO ₄ ²⁻)	mg/L	600	168	142	167	192	162	142	122	114
13.	Zinc (Zn)	mg/L	5.0	0.81	0.9	0.7	0.6	0.09	0.08	0.092	0.089
14.	Silver (Ag)	mg/L	1.0	0.54	0.06	0.09	0.12	0.05	0.06	0.04	0.02
15.	Boron (B)	mg/L	6.0	0.19	0.7	0.05	0.08	0.08	0.16	0.08	0.07
16.	Barium (Ba)	mg/L	1.5	0.13	0.62	0.04	0.034	0.026	0.049	0.056	0.06

The results are within permissible limits except BOD₅ at Niaz Hussain Jatoi, Khanpur.

b. Ground Water

125. Ground water is brackish with TDS value generally higher that's why it is not major source of drinking water in the Study Area. However, along the river and canals the water is sweet for drinking purpose. The depth of groundwater table varies from 3 to 20 m. Hydrological Map is shown in **Figure 5.2**.
126. Water quality in aquifers has been monitored during July 2020 in sampling points indicated in the figure above detailed in a table below.

Ground Water (GW) Sampling		
GW-01	Kundan Mosque & Residential Area	Shikarpur
GW-02	Govt. Higher Secondary School & Residential Area	Khnapur
GW-03	Cadet College	Kandhkot
GW-04	Masjid-e-Bilal & nearby Residential Area	Kashmore
GW-05	Rural Health Centre & Residential Area	Rujhan Chowk
GW-06	Mushtaq Hotel & nearby Residential Area	Rajanpur

127. The results of the Ground water are given in **Table 5.3**.

Table 5.3: Monitoring Results of Ground Water

Sr. No.	Parameters	Units	Limits Values (PEQS)	Rajanpur	Rojhan	Kashmore	Niaz Hussain Jatoi Khanpur	Khanpur	Shikarpur
1.	pH	-	6.5 – 8.5	6.4	6.8	6.1	6.9	5.9	6.3
2.	Taste & Odour	-	Non-Objectionable/ Acceptable	Salty	Non-Objectionable/ Acceptable	Salty	Non-Objectionable/ Acceptable	Salty	Salty
3.	Color	TCU	≤15	9	6	11	5	7	8
4.	Turbidity	NTU	<5 NTU	6	5	7	3	6	5
5.	Total Coliform Bacteria	Number/100mL	---	0	0	0	0	0	0
6.	Fecal Coliform (E. Coli)	Number/100mL	Must not be detectable in any 100 mL sample	0	0	0	0	0	0
7.	Total Dissolved Solids	mg/L	<1000	1694	372	1068	289	942	861
8.	Total Hardness as CaCO ₃	mg/L	<500	267	94	122	59	106	119
9.	Nitrate	mg/L	≤ 50	7.6	4.1	6.7	3.3	4.1	4.7
10.	Nitrite	mg/L	≤ 3	0.85	0.09	0.91	0.0054	0.05	0.06
11.	Ammonia	mg/L		1.94	0.083	1.8	0.057	0.72	0.58
12.	Arsenic (As)	mg/L	≤ 0.05	ND	ND	ND	ND	ND	ND
13.	Antimony (Sb)	mg/L	≤ 0.005	ND	ND	ND	ND	ND	ND

Sr. No.	Parameters	Units	Limits Values (PEQS)	Rajanpur	Rojhan	Kashmore	Niaz Hussain Jatoi Khanpur	Khanpur	Shikarpur
14.	Barium (Ba)	mg/L	0.7	ND	ND	ND	ND	ND	ND
15.	Chloride (as Cl ⁻)	mg/L	<250	194	72	202	56	117	102
16.	Fluoride	mg/L	≤ 1.5	1.1	091	0.98	0.84	0.61	0.49

The results are mostly in compliance with the standards. However, the water at some points is turbid, salty and has higher TDS, and lower pH.




Figure 5.1: Land-use map of the Study Area




Figure 5.2: Hydrological map of Project Area

5.1.4 Natural Hazards

i. Seismology

128. The Project Area is located in Seismic Zone 2A, on the seismic zoning map of Pakistan, where 2A represents peak horizontal ground acceleration from 0.08 to 0.16g. An earthquake of magnitude 5.0 hit Sindh on May 9, 2014. The quake was followed by two aftershocks measuring 4.7 and 4.9 magnitude with epicenters located northeast and northwest of Nawabshah. **Figure 5.3** shows the seismic zoning map of Pakistan with the project area falling under Seismic Zone-2A. The road design must meet the criteria to withstand in seismic zone 2A.




Figure 5.3: Seismic Zoning Map of Pakistan

ii. Floods

129. Project area is flooded by the Indus River which also carries flood water from the other four rivers of Pakistan including Satluj, Ravi, Jehlum and Chenab. These four rivers are tributaries of the Indus and their confluence is at the location of Punjnad. The Indus River has been responsible for 12 of the major floods in Pakistan including the floods of 1950, 1955, 1956, 1973, 1976, 1978, 1988, 1992, 1995, 1997, 2005, 2010 and 2012.
130. The project area of influence (AOI) lies in the floodplain of the river and is constantly susceptible to flooding. The floods of August, 2010 provide a good example of the extent of damage caused by overflowing water. 3781 villages (70 percent of district villages) were flooded and 85 percent of the district area got inundated, blocking 1365 km of roads (85 percent of total roads) for six weeks. **Figure 5.4** shows the areas of Pakistan affected by the floods of 2010.




Figure 5.4: An Overview of the Flood Extent in 2010

5.1.5 Noise

131. Monitoring of the noise baseline in the project area has been conducted together with monitoring of other environmental parameters in July 2020. The map showing the measurement points is shown in Section 5.1.3 and the details in a table below.

Ambient Air & Noise (A&N) Monitoring		
A&N-01	Residential Area	Shikarpur
A&N-02	Rural Health Centre & Residential Area	Khanpur
A&N-03	Masjid Ali-ul-Murtaza & Residential Area	Kandhkot
A&N-04	Jamia Masjid Qadria & Residential Area	Kashmore
A&N-05	Rural Health Centre & Residential Area	Rojhan
A&N-06	Noorani Masjid & Residential Area	Rajanpur

132. Noise monitoring results are given in **Table 5.4**. Day time noise values are within limits whereas nighttime noise values are slightly higher than the limits which may be mainly due to heavy traffic load on existing N-55 road.

Table 5.4: Results of Noise Monitoring

Sr. No.	Locations	Duration	PEQS dB (A)	Results dB (A)
1.	Rajanpur	Day Time	65	63.03
		Night Time	55	61.02
2.	Rojhan	Day Time	65	59.79
		Night Time	55	58.48
3.	Kashmore	Day Time	65	62.89
		Night Time	55	61.58
4.	Kandhkot	Day Time	65	60.89
		Night Time	55	59.58
5.	Khanpur	Day Time	65	60.30
		Night Time	55	58.66
6.	Shikarpur	Day Time	65	58.51
		Night Time	55	56.53

5.1.6 Environmental Sensitive Receptors

133. The sensitive receptors are shown in the **Table 5.1** and a comprehensive map showing environmental sensitive receptors of the project area such as surface water bodies, animal corridor, agricultural land, urban areas, schools, mosques, monuments, dispensaries, etc. is given as **Figure 5.5 (a)**. Tentative locations of these sensitive receptors are shown on the map. The map depicts that the proposed alignment mainly passes through agricultural areas with scattered and thick populated areas. The schools, mosques, monuments and health facilities may be affected during and after the construction of the proposed alignment. The sensitive receptors/structures directly affected by the project are given in **Table 5.5**.

Table 5-5: Environmental Sensitive Receptors and their Sensitivity

Sr. No.	Category	Name/Type of sensitive receptor	Remarks
1	Schools	School Located 20 m to ROW at Miran Pur City Area	Sensitivity due to access, dust, noise and vibrations especially during teaching

Sr. No.	Category	Name/Type of sensitive receptor	Remarks
		School Shamsabad at 100 m distance from the road.	hours during construction phase.
2	Mosques	Jamia Masjid Kotla Nasir (0-10 m) Mosque located at 581 Km at Kot Bahadur Mosque located at 10 m from ROW at Shamsabad Mosque located 20 m away from Baskhsha Pur City Mosques located 10 m away from ROW at Ghoos Pur Area Mosque located at 20 m away from ROW at Karampur area. Mosques located 20 m away from the road alignment at Karam Pur Area. Mosque located 10 m at Khan Pur Area Mosques Located 20 m from ROW at Shikarpur Area	Sensitivity due to noise and vibrations. Exposure to dust and access problems may occur at certain locations during construction phase.
3	Residential Areas	Locality of Kotla Nasir along road (0-5m) Miran Pur City Area at Km 548 Shamsabad	Sensitivity due to noise and vibrations. Exposure to dust and access problems may occur at certain locations during construction phase.
4	Water logged areas/ water ponds	Water pond at Km 581, located at around 18 km to Rajanpur Water Pond Located at 10 m ROW at Basti Bajwa Water logged area (saline water bodies at different locations) at Bakhsha Pur City area Large Area confined with water logging at Goth Nawab Khan Water Logged area at Ghoospur city water logged patches at different locations Shikarpur areas	Sensitive due to increased sedimentation loading from the road and construction activities.
5	Other important areas	Police station Shamsabad 50 m Nomadic area 10-5 m	

Sr. No.	Category	Name/Type of sensitive receptor	Remarks
		Graveyard located adjacent to the existing road at Bakhsha Pur City	
		Monument Kandhkot	
		Police Checkpost along the N-55 highway at Karam Pur Area	
		Police Station at Napar Ghot (Karam Pur) at 20 m	




Figure 5.5- a: Environmental Sensitive Receptors (Rajanpur to Kahsmore)




Figure 5.5-b: Environmental Sensitive Receptors (Kashmore to Shikarpur)

5.2 Biological Environment

5.2.1 Flora of the Area

134. The project area being part of the lower Indus basin the climate of the tract is semi-arid, sub-tropical, the original flora of the area consists of tropical thorn forest type vegetation, in which thorny usually hard wooded species predominate, acacia species being particularly characteristic. The trees have usually short boles and low branching crowns, which rarely meet except on exceptionally favorable spots. The usual-height of tree is 6-10 m.
135. From Shikarpur to Rajanpur section, flora of the project area falls in the scrub Dry Tropical Thorn Forest Zone. This is the natural vegetation of the Indus Basin. It has the capacity to survive and grow in areas with extremely high temperatures and low precipitation. The flora consists of spiny and hard wooded species. Acacia species are the dominant one. The trees usually have short boles and low branching areas. Their usual height is 6-9 meters. The leaves are small, except in a few genera like Salvadoran and Caltrops. Main trees in the Project Area are *Acacia nilotica* (Keekar), *Eucalyptus camaldulensis* (Safaída), *Phoenix dactylifera* (Date Palm), *Dalbergiasissoo* (Shisham). *Azadirachta indica* (Neem), *Salvadoraoleoides* (Peelu) and *Ficus religiosa* (Peepal).
136. Among the grasses; *Aristida depressa* (Lumb), *Eleusine compressa* (Chemmer), *Lasiurus indicus* (Gorkha) and *Saccharum bengalensis* (Kana) are found in the project area.



5.2.2 Conservation and Protection Status

137. No threatened or endemic plant species were observed in the Study Area during the survey nor reported from the literature survey.
138. No threatened or endemic plant species are present in the Study Area. None of the plant species observed was endemic, their distribution is not limited to any specific site or habitat type, and the distribution is widespread.
139. **Figure 5.6** shows the reserved forest along the River Indus: however, these are far away from the alignment and would not be affected.




Figure 5.6: Showing Existing Reserved/Conserved Forest Area

5.2.3 Faunal Species in Project Area

140. Natural fauna of the area is fairly rich and comprises mammals, reptiles and birds etc.

i) Mammals

141. Mammals found in the project area are Jackals (*Canisaureus*). Stray dogs are found in abundance in the project area. Porcupine (*hystrixindica*) is also seen in the area and causes damage to the agricultural crops. Fox (*Vulpusvulpus* and Wild Boar (*Susscrofa*) are also reported in the area. Domestic animals include goats, sheep, cows, buffaloes and camels. Buffaloes are common in Sind. Other mammals in project area include Bat (*Rasperugonastrus*), Squirrel (*Funambuluspennanti*), Mongoose (*Herpestesauiopunctatus*), Hares (*Lepusnigricollis*), and Rats (*Rattusrattus*).

ii) Reptiles

142. Reptiles include snakes like Cobra (*Najanaja*), and rat eater snakes. Small sized lizards are also common sight in the area. These include Spiny Tailed Lizard (*Uromastixhardwickii*), Fringed Toed Sand Lizard (*Acanthodactyluscontoris*), Krait (Snake), *Bungaruscaeruleus*, Sand Boa (Snake), *Eryxjohniand* Desert Monitor lizard *Varnusgriseus*.

iii) Birds

143. The tract is fairly rich as far as avifauna is concerned. Partridges and Quails are seen in the agricultural fields after the harvesting of the Rabi or Kharif crops. Common birds found in the area are Common Mynah (*Aonodotherestrictis*), House Crow (*Corvussplendens*), House Sparrow (*Passer domesticus*), Koel (*Eudynamysscolopacea*), Bulbul (*Pycnontuscafar*), Pigeon(*Columbialivia*), Parrot (*Pisttacakrameri*), Partridge Black (*Francolinus francoinus*), Partridge Grey (*Francolinuspondicerianus*), Quail(*Coturnexcoturnix*), Hoopoe (*Upupaepops*)

144. Common Teal (*Nettapus coromandelianus*), Fish Eagle (*Aquilarapax*), King Fisher (*Alcedoatthis*), Heron (*Ardeapurplea*), Collard Dove (*Streptopelladecaoto*), Little Egrets (*Egrettaagarzetta*).

iv) Fisheries

145. The worlds' largest earth and rock filled dam, Tarbala dam and six barrages (Jinnah, Chashma, Taunsa, Guddu, Sukkur and Kotri) are constructed on Indus River in Pakistan. There are not less than 193 freshwater fish species in Pakistan (Rafique and Khan, 2012). But more than 180 fish species are found in Indus River. Complete picture of the fish diversity and distribution pattern in Indus River and its drainage system need attention. Moreover, there are serious threats to the fish biodiversity of Indus River due to industrial pollution, illegal hunting of fish, extensive deforestation, global warming and westward shifting of its course. However, proposed Project is not posing any impact on aquatic fauna of the Study Area and its vicinity.

146. The fisheries in the project area include the following commercially important fishes *Chitala chitala*, *Cirrhinus mrigala*, *Cirrhinus reba*, *Catla catla*, *Labeo rohita*, and *Labeo gonius*.

Endangered Fauna

i) Birds

147. Birds like Black partridge, (*Francolinus francolinues*), Falcon (*Falco peregrinus*) are now rarely seen in the area as they have been subjected to excessive hunting and catching, on account of their good quality and tasty meat or their commercial value as a prey bird and at present are endangered species but would not be influenced by the project.

ii) Migratory Birds

148. Migratory Birds from Siberia visit the plains of Sindh during winter. Majority of these birds land on major wetlands and pond areas of various head works and major canals including Begari canal and Khirther canal.

iii) Fish Species

149. No endangered fish species were found in the Study Area. However, available fish fauna of the Study Area include *Chitala chitala* (*Chitala ornate*) LC, *Cirrhinus mrigala* VU, *Cirrhinus Reba* LC, *Catla catla* VU, *Labeo rohita* LC and *Labeo gonius* LC.

5.3 Socioeconomic Profile

150. The following section deals with the socio-economic conditions of project area. During the desk study, available literature, reports and documents were studied comprehensively for data collection.
151. The proposed project area falls in the administrative jurisdiction of District Rajanpur and Shikarpur and Kashmore. Rajanpur district falls in the province of Punjab and has three tehsils namely Rajanpur, Rojhan, and Jampur. However, the proposed section of additional carriageway runs through two tehsils Rajanpur and Rojhan. Gorchani, Darishak, Mazari and Tummons are declared as tribal areas of Rajanpur district.
152. Shikarpur District is in Sindh province of Pakistan. And two National Highways (N-65 & N-55) intersect the city of Shikarpur making it the junction points of 4 provinces. Shikarpur was an important place as commanding the trade route through the Bolan Pass, and its merchants have dealings with many towns in central Asia. Shikarpur was a city closed within a fort, that fort had seven gates like Hathi Gate, Lakhi Gate, Hazari gate, Khanpur Gate, Suvi Gate, Wagana Gate, Karan Gate & Noshero Gate
153. The district of Shikarpur is sub-divided into four talukas / tehsils, these are: Garhi Yasin , Khanpur, Lakhi, Shikarpur of which Shikarpur and Khanpur towns are on this section of ACW.
154. Kashmore District is subdivided into three tehsils namely, Kandhkot, Kashmore and Tangwani of which Kashmore and Kandhkot towns are directly located on N55.

5.3.1 Demographic Characteristics

155. The total population of district Rajanpur, Shikarpur and Kashmore stood at 1,995,958, 1,231,481, 1,089,000 respectively and the average household size ranges from 5.5 to 6.0 persons in these districts (census report 2017)
156. Urban population for district Rajanpur is 337,202 and rural is 1,658,756. There are two municipal committees and four Town Committees. And 532 Mauzas, a smallest revenue unit.
157. The rural population of district Shikarpur is 668,000 constituting 76 percent of the total population. The urban population of district Shikarpur is 212 thousand which constitutes 24.1 percent of its total population in other words every fourth persons live an urban area. There are seven (07) urban localities in the district.
158. The population of district Rajanpur is predominantly Muslims i.e. 97.72 percent. The next higher percentage is of Ahmadi with 0.05 percent, followed by scheduled casts 0.03 percent. While other minorities like Christian, Hindu etc. are very small in number.
159. The population of district Shikarpur is predominantly Muslim. They constitute 98.03 percent of the total population. The important minorities are Hindus and Christians who are 1.73 and 0.09 percent respectively.

160. Siraiki is the predominant language being spoken in the district Rajanpur, while Sindhi is spoken in the District Kashmore and Shikarpur. Urdu and Balochi are the other languages spoken in the Project area.
161. The communities in the vicinity along the N-55 corridor follow different traditions / customs. Most of the people living in rural areas of district Rajanpur, wear Kameez and Dhoti (Tehband) and in urban areas Kameez Shalwar. The people are engaged in cultivation, business, employment and labor. In marriages they follow the dictates of Islam. However, watta-satta which is big social evil causing entanglement in most of the families owing to illiteracy. The women situation is not good due to male dominated culture.
162. Shikarpur, after the conquest of Sindh by Muhammad Bin Qasim, the Arabs ruled over Sindh for about three hundred years. During this period, Sukkur close to Shikarpur was the Headquarter of Sindh Province, from where the Islamic teachings flourished throughout Sindh. The custom amongst all Sindhi families of playing drums and Shahnai at least a week before the marriage is universal. Many fairs are held in the districts which are connected with Urs of well-known saints.

5.3.2 Social Characteristics

i) Health & Medical Facilities

163. There is 1 District Headquarter Hospital, 32 Basic Health Units, 6 Rural Health Centers, 2 Dispensaries and 1 Mother & Health Child Centers in district Rajanpur; while, 1 Civil Hospital, 3 Taluka HQ Hospital, 33 BHUs, 6 Govt. Dispensaries, 4 Maternity Homes and Child Health Units, 39 School Health Clinics and 14 District Council Dispensaries in Shikarpur

ii) Educational Institutions

164. Rajanpur has a total of 1,160 government schools out of which 41 percent (480 schools) are for girl students. The district has an enrolment of 148,746 in public sector schools¹⁸. Educational Institutions include 4 Degree Collage, 37 High schools for boys and 19 High schools for girls, 30 Middle school for boys, 26 Middle school for girls, 471 Primary school for boys, 510 Primary school for girls and 9 Community Model schools in the district Rajanpur.
165. A number of educational institutions exist in district Shikarpur. These include 3 Degree Collage, 1 Law collage (private), 2 higher secondary school, 49 high schools, 62 middle schools and 609 primary schools. Besides these institutions there are 507 Mosque schools and 17 Mohalla schools for girls in the district.

iii) Literacy Ratio

166. A person was treated as literate if one can read newspaper or a journal of same standard and could write a simple letter in any language. The literacy is measured as the ratio, in percentage, of literate population to corresponding population aged 10 and over. The literacy ratio¹⁹ in district Rajanpur is 20.7 percent. The literacy ratio for males is 29.0 percent as against 11.3 percent for females.
167. The literacy ratio of district Shikarpur among the population aged 10 years and above is 31.94 percent. The male literacy ratio is higher i.e. 44.95 compared to 18.04 for females. There are sharp differences in the literacy ratios by sex and residing area. The ratio in urban areas is 55.33 compared to only 23.92 in rural areas.

¹⁸ Punjab Annual Schools Census Data 2014-15.

¹⁹ District Census Report 1998

iv) Communication

Railways

168. Good trains are an effective means of transporting bulk of surplus goods from Rajanpur district to other parts of the country. Railway track connects the Rajanpur district on the north with Dera Ghazi Khan, Kot Adu, and Multan while on the west and south-east with Jacobabad, Larkana and Quetta sections.
169. District Shikarpur is connected by railway line with Jacobabad in the north, Larkana in south-west and Sukkur in the south-east. All the talukas of district are well connected with the district HQ with metalled roads. Moreover, Shikarpur is easily accessible by air through Sukkur which is air connected with different cities.

Roads

170. The area has a well-connected road system consisting of National and provincial highways such as N-55, and N-65 connecting to Baluchistan. In addition to that, following are some important roads network of district Rajanpur and District Shikarpur.
- D.G Khan Mittan Kot section Manan Bangla to Kot Mithan
 - Rajanpur-Kashmore road section Kotla Naseer to Kashmore
 - Jampur-Dajal Road
 - Fazilpur to Hajipur
 - Rajanpur to Aqikpur
 - Kot Janu to Kot Tahir
 - KotlaEsan to Shikarpur
 - Kampur to KotlaMughlan to Muhammaddin
 - Shikarpur-Sukkur.
 - Shikarpur-Larkana
 - Shikarpur-Kandhkot. Shikarpur-Jacobabad.

Transportation

171. The main source of transportation in the district Rajanpur is railway and private transportation. The main railway line with double track passes through the entire length. The private transportation is successful in the district and it provides transportation facilities almost for all the areas.

v) Irrigation System and Agriculture

172. The total irrigated area of district Rajanpur comprises 295,034 hectares. Agriculture in Rajanpur depends solely upon canal irrigation namely, Kadra canal, Dajal canal since rainfall is negligible in the region. Rainfall occurs during the monsoon season (July–September). Rajanpur district is famous for cotton and sugarcane crops.
173. District Shikarpur is also irrigated by canals which take off from Sukkur and Guddu barrages. Shikarpur is the mainly rice growing area. The main crops during Rabi are wheat, barley, gram, and pulses. The main crops during Kharif are rice, sugarcane, cotton and jawar etc.

5.3.3 Economic Characteristics

i) Economically Active Population

174. The economically active population is defined as the person working most of the time during the year. The economically active population in district Rajanpur as

enumerated in the last census²⁰ was 25.1 percent of the total population. Of the total male population, 36.0 percent were economically active, while 64.0 percent are not economically active.

175. For Shikarpur, it is 44.76 percent for males compared to only 2.23 for females, resulting in very low overall participation rate. The rural / urban labor force participation rate does not differ much as it is 23.02 percent in rural and 27.60 in urban areas.

ii) Unemployment

176. Unemployment rate is measured as ratio of looking for work and laid off in total economically active population comprising employed, looking for work, laid off and un-paid family helpers, generally representing in percentage. The unemployment rate in the district Rajanpur for male population is 19.3 percent and just 2.2 percent for females.
177. The unemployment rate of district Shikarpur is 9.04 percent. The unemployment rate varies for males and females as well as for rural and urban areas. The unemployment rate is 9.42 for males and 1.04 percent for females.

5.3.4 Historical and Archeological Characteristics

178. There are no remarkable historical buildings in district Rajanpur which can be included in the narration of historical monuments. However, some ancient buildings on the pattern of Mughal architecture are situated in district Rajanpur.
179. The Historic and ancient fort is located nearby the city of Harnand, Jampur, District Rajanpur. Hindu Raja Harnandus and his son "Lok Bhagat" had constructed the Fort of Harnand on the style of Monjodero. The fading signs of the edifice are still there in the forms of derbies and bricks scattered around the old site. Present structure of the Fort a valuable part of our heritage is situated about 25 kilometers west in district Rajanpur. The Fort is spread over an area of 50 acres of land.

i) Hazrat Khawaja Ghulam Farid of Mithankot

180. The tomb of saint poet Hazrat Khawaja Ghulam Farid is situated in Mithankot. Khawaja Ghulam Fareed, a well-known spiritual personality of Indo-Pak and a popular Sufi poet, was born on 3 December in 1845 in Chacharan Shareef, Rahim Yar Khan District. His poetry carried out the message of Islam ethics and social equality among the Muslims. He was only inspired by the eternal teachings of Islam but also had a keen eye on his surroundings. He, therefore, expressed his thoughts and ideas by symbolizing the phenomenon of nature around him with the teaching of Islam. His poetry has been translated into English and is greatly appreciated and admired throughout Pakistan.

ii) Marri

181. Marri is some sort of resort Hill Station in Rajanpur similar to Muree. Its altitude is 4800 ft from sea level with cold weather in summer. Marri is beautiful Hill Station in District Rajanpur South Punjab, Dera Ghazi Khan Division. Beautiful site and newly built road is also seen-able. Visitors can go marri from fazalpur, hajipur, lalgarh road. It is also called Tumman-Gorchani.
182. Contrary to this, there are no remarkable historical places in district Shikarpur. Although, ShahiBagh was known for its thriving vegetation and scented flowers. ShahiBagh had zoo with number of lions, cheetahs, bears and wild boars. These animals were later shifted to Karachi Zoo. Many other public and private gardens and open spaces of Shikarpur have vanished. Recently some water parks have been built around the territories of Shikarpur district, and Shikarpur has some nice restaurants

²⁰ Census Report 1998

to go to and have a nice dinner or lunch which are Kundan Restaurant, A.R Fast Food, and Zaiqa Restaurant etc.

SECTION 6: ANALYSIS OF ALTERNATIVES

183. The following alternatives have been identified and are discussed in further detail below:

- The No-Action Alternative
- The N-55 Alignment as proposed
- Rehabilitation of the existing road

6.1 Alternative I: No-Action Alternative

184. The following positive impacts are anticipated:

- Avoidance of destruction of natural habitats, arable land and affected structures
- Cost saving for the Construction of rehabilitation and dualized portion
- No disturbance to the communities due to construction

185. In case of no action for the proposed alignment, following two consequences will follow; Firstly, due to increased traffic volumes on N-55, the road will deteriorate, resulting in uncomfortable and unsafe driving conditions, deterioration of vehicles and increased accidents. Secondly, due to poor accessibility to the approach nearby areas and other cities area, the probability of time travelling would be high, furthermore the area may become unattractive for investors, which will have a negative effect on economic growth and associated job opportunities.

- Continued delays may be experienced within the inter-provincial areas during morning and evening peak hours;
- High maintenance and fuel costs for motorists using the existing roads in poor condition,
- Loss of potential associated employment opportunities for communities near to alignment.

6.2 Alternative II: Additional 2-Lane at N-55 Alignment as proposed

186. The following positive impacts are anticipated:

- The construction of this alternative will reduce the travel times, from urban centers and residential settlements in rural areas around N-55 other provincial cities, to and from Rajanpur to other parts of Sindh areas;
- Reduced maintenance and fuel costs associated with better quality roads;
- Job opportunities will be created during the construction phase as well as the post-construction phase. It will give local residents the prospect of earning an income to better sustain their families;
- Improved travelling conditions during commute.
- The project area falls in CAREC Corridor 6. The Indus Highway N-55 has a significant importance of the CAREC program. So, by improving this CAREC corridor, regional connectivity and trade via the CAREC Corridors trade and commerce in global markets will be boots-up.

187. The following Negative impacts are possible:

- Occurrence and richness of vegetative land mainly tree densities along the existing alignment and land utilized for orchards and agricultural practices will be affected. Resultantly, bio diversification of the area will be affected
- Relocation of residents whose properties fall within the alignment and the associated project limits;
- Possible contamination of ground and surface water in close proximity the proposed alignment.

- As the area is considered as an important Agro-Ecological zone of different crops. So, cropping patterns due to ecosystem dynamics may be disturbed due to additional 2-Lane carriageway
- The utilities i.e. power transmission lines, gas supply pipes, water supply pipes, telephone cables, telecommunication cables, etc. that will come in ROW, will be properly relocated. Similarly, the built-up properties i.e. Kilns, mosques, houses, shops etc., will be timely relocated to avoid any disruption in work and their compensation will be paid to the Project Affected Persons (PAPs) as per the approved rates of relevant building department.

6.3 Alternative III: Rehabilitation of existing 2-Lanes at N-55 Alignment

188. The following positive impacts are anticipated:

- Lesser destruction of natural habitats, arable land and affected structures
- Cost saving for the construction of dualized portion
- Lesser disturbance to communities due to earlier completion a lesser work

189. Negative impacts will include that the existing road will be unable to cater increased traffic loads on N-55, which may lead to the uncomfortable and unsafe driving conditions and increased accidents. Secondly, due to traffic congestions the commute will be longer and tiresome. More noise and vehicular emissions would be generated. The areas connected by the road may become unattractive for investors, which will have a negative effect on economic growth and associated development and job opportunities.

6.4 Selected Option:

190. Taking in to account the socioeconomic and environmental benefits and extending the benefits to regional level and connectivity with the Central Asian region, alternative 2, dualization of N55 as CAREC Corridor 6 is the best choice.

6.5 Technological Alternatives

191. Asphalt and concrete pavement were considered by detail design team. Priority was given to asphalt for following reasons:

- Less noise during operation compared to concrete
- Less vibration as compared to concrete
- Better visibility of horizontal marking on Asphalt surface
- Recyclable material
- Better efficiency in extreme weather.

Table 6.1: Comparison of Alternatives

Sr. No.	Alternatives	Economical	Environment	Social
				No disturbance to public due to shifting of utilities, land acquisition and resettlement
1.	No-Action Alternative	No cost incurred	No loss of vegetation and habitat Increase in noise and vehicular emission over time due to growth in traffic volumes	Congestion of roads resulting in conflicts Stagnant development and economy due to lesser movement and connectivity
2.	Additional 2-Lane at N-55 Alignment as proposed	Cost incurred	Loss of vegetative land	Land acquisition and resettlement Lesser structures affected
3.	Rehabilitation of existing 2-Lanes at N-55 Alignment	Lesser cost	Lesser destruction of natural habitats Increased noise and vehicular emissions	Lesser disturbance to communities due to earlier completion and lesser work Congestion of roads resulting in conflicts Stagnant development and economy due to lesser movement and connectivity

SECTION 7: ANTICIPATED ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES

7.1 Environmental Consequences

192. This section provides the analysis of the potential impacts during pre-construction/design, construction and operational phases of the proposed project on the physical, biological and socio-economic environment of the project area. Environmental sensitivity of the project area is described through the thematic sensitivity map and evaluation of significance of impacts is carried out through Environmental Matrices. In addition, it also narrates the measures that will mitigate the project's potential environmental impacts. Environmental impacts have been considered not only as they pertain to road ROW, but also to the site associated with the road project.

7.2 Screening of Potential Environmental Impacts

193. Primarily, anticipated impacts have been categorized as direct, indirect and induced impacts. These groups of impacts can be further broken down according to their nature into:

- Positive and negative impact;
- Minor, major and moderate impact;
- Local and widespread impact;
- Temporary and permanent impact;
- Short and long-term impact; and
- Reversible and Irreversible impact.

194. Characterization of Impacts is given both at construction and operation phase in **Table 7.1 & 7.2**. Furthermore, the environmental impact evaluation matrices have also been developed to indicate magnitude of the impacts on different environmental settings for both construction and operational phases (see **Tables 7.3 and 7.4**). The following scale has been used for the evaluation of potential impacts on different environmental settings:

O = Negligible/No Impact
LA = Low Adverse
MA= Medium Adverse
HA = High Adverse
B = Beneficial

195. The criteria used to define the high medium and low adverse impacts are as follows:

Negligible/No Impact: The impact, which has unapparent and negligible influence on natural and socio-economic environment.

Low Adverse Impact: The impact, which has a slight influence on the natural and socio-economic environment.

Medium Adverse Impact: The impact, which can be eliminated/ mitigated after applying the appropriate mitigation measures.

High Adverse Impact: The impact, which can be partially/ but not fully mitigated by applying the mitigation measure.

Positive/Beneficial Impact: The impact, which improve/enhance the natural and socio-economic environment.

Table 7.1: Characterization of Environmentally Potential Impacts for Construction Phase

Environmental Component	Impact Characteristics														
	Direction		Duration		Location		Frequency		Extent		Significance			Reversibility	
	Positive	Negative	Long	Short	Direct	Indirect	Continuous	Intermittent	Wide	Local	Large	Moderate	Small	Reversible.	Irreversible
Topography		•	•		•		•			•			•		•
Surface Water Quality		•		•	•			•	•			•		•	
Groundwater Quality		•		•	•			•	•				•		•
Air Quality		•		•	•			•	•			•		•	
Soil Quality/Erosion		•		•	•			•		•		•		•	
Noise		•		•	•			•		•		•		•	
Flora		•	•		•			•		•	•			•	
Fauna		•		•	•			•		•			•	•	
Disturbance to Public Life		•		•	•			•		•		•		•	
Solid Waste		•		•	•		•			•			•	•	
Land Acquisition		•	•		•		•			•	•				•
Traffic Management		•		•	•			•		•			•	•	
Occupational Health and Safety		•	•		•			•		•		•			•
Lifestyle and Culture	☐		☐		☐		☐		☐			☐			☐

Legend: Negative Impact (•)

Positive Impact (☐)

Table 7.2: Characterization of Environmentally Potential Impacts for Operation Phase

Environmental Component	Impact Characteristics														
	Direction		Duration		Location		Frequency		Extent		Significance			Reversibility	
	Positive	Negative	Long	Short	Direct	Indirect	Continuous	Intermittent	Wide	Local	Large	Moderate	Small	Reversible.	Irreversible
Local Economics	☺		☺			☺	☺		☺		☺				☺
Air Quality		●	●		●		●		●				●	●	
Noise		●	●		●		●		●				●	●	
Flora	☺		☺		☺		☺			☺			☺		☺
Fauna		●	●		●		●			●			●		●
Traffic Situation	☺		☺		☺		☺		☺		☺				☺
Lifestyle and Culture	☺		☺			☺	☺		☺			☺			☺
Community Development	☺		☺		☺		☺		☺		☺				☺

Legend: Negative Impact (●)

Positive Impact (☺)

Table 7.3: Environmental Impacts Evaluation Matrix during the *Construction Phase*

Sr. No.		Physical Environment								Biological Environment		Socioeconomic Environment							
	Environmental Component Project Activities	Topography/Drainage	Soil Quality	Landscape	Surface Water Quality	Groundwater Quality	Landslide/Slope Stability	Air Quality	Noise & Vibration	Flora	Fauna	Health & Safety	Disruption of Public Utilities	Employment	Population Disturbance	Social Disorder	Cultural/Religious Values	Traffic Management	
1	Construction camps, workshops etc.	MA	LA	O	LA	LA	LA	LA	LA	HA	MA	LA	LA	MB	MA	LA	LA	LA	
2	Site clearing	LA	LA	LA	LA	O	LA	LA	LA	HA	MA	LA	LA	MB	LA	O	O	O	
3	Excavation operations at borrow & quarry areas	LA	MA	MA	LA	O	MA	LA	MA	MA	LA	MA	LA	MB	LA	O	LA	LA	
4	Transportation of construction materials	O	LA	O	O	O	LA	LA	MA	O	O	LA	O	LB	LA	O	LA	LA	
5	Open storage of construction materials, fuel etc.	O	HA	O	LA	LA	LA	LA	O	LA	LA	LA	O	O	O	O	O	LA	
6	Solid waste generation	LA	LA	LA	LA	LA	O	MA	O	LA	LA	LA	LA	MB	LA	O	LA	LA	
7	Use of Chemicals	O	MA	O	LA	LA	LA	LA	O	LA	LA	LA	LA	LB	LA	O	O	O	
8	Earthwork operations	MA	MA	MA	LA	O	MA	LA	MA	LA	LA	MA	LA	MB	LA	O	LA	LA	
9	Operation of Asphalt & concrete batching plant	LA	LA	MA	LA	O	MA	MA	MA	LA	LA	MA	LA	MB	LA	O	LA	LA	
10	Crushing Operation	O	LA	LA	MA	O	LA	HA	HA	LA	LA	MA	O	MB	MA	O	LA	LA	
11	Use of generators	O	LA	O	LA	O	LA	MA	MA	LA	LA	LA	O	MB	LA	O	O	LA	
12	Construction of Road	LA	LA	LA	LA	La	LA	LA	LA	LA	LA	LA	MB	MB	LA	LA	LA	LA	

Legend

O - Insignificant / no impact

LA = Low Adverse

MA = Medium Adverse

HA = High Adverse

NA - Not Applicable

LB = Low Beneficial

MB = Medium Beneficial

HB = High Beneficial

Table 7.4: Environmental Impacts Evaluation Matrix during the *Operational Phase*

Sr. No.	Project Activities	Physical Environment								Biological Environment		Socioeconomic Environment				
		Topography	Soil Quality	Landscape	Surface Water Quality	Groundwater Quality	Land Slide/ slope Stability	Air Quality	Noise & Vibration	Flora	Fauna	Public Safety	Employment	Population Disturbance	Economic Activities	Traffic Management
1	Movement of Vehicle	O	O	O	LA	LA	LA	LA	LA	O	LA	LA	MB	O	MB	O
2	Ticketing	O	O	O	O	O	O	O	LA	O	O	O	HB	O	MB	O
3	Generation of surface runoff	O	LA	MB	LA	LA	MA	LA	O	O	O	LA	O	O	O	O
4	Generation of Solid Waste	O	LA	LA	LA	LA	O	LA	O	O	LA	LA	LB	O	O	O
5	Signaling / Traffic Control	O	O	O	O	O	O	LA	O	O	O	O	MB	O	MB	HB
6	Maintenance of Roads	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	MB	LA	MB	LB
7	Generators (Power Supply)	O	O	O	O	O	O	LA	LA	O	LA	O	O	O	O	O
8	Accidental Spill	O	HA	MA	HA	HA	O	HA	O	O	O	HA	O	MA	LA	HA

Legend

O - Insignificant / no impact

LA = Low Adverse

MA = Medium Adverse

NA - Not Applicable

LB = Low Beneficial

MB = Medium Beneficial

7.3 Positive Impacts of the Project

196. Due to the implementation of the proposed project components following benefits will be attained in terms of environmental, social, public health and economic sustainability:

- Smooth flow of traffic;
- Saving of vehicle travel time and vehicle operating costs of commuters;
- Reduction in traffic accidents and casualties by traffic congestions;
- Efficient movement of trade, goods and traffic in relatively shorter time;
- Quicker transports of agricultural products including perishable goods to final destination;
- Reduction in the fuel consumption and transportation cost caused by traffic congestion and bumpy roads;
- Reduction in air emissions from vehicular exhaust especially in case of traffic congestion; and
- Increase in economic growth by providing employment opportunities to the local residents and vendors.

7.4 Pre-Construction/Design Phase

197. Following is the brief description of impacts envisaged and the recommended mitigation measures during Pre-construction and Design Phases.

7.4.1 Physical Environment

7.4.1.1 Topography

198. The topography in the project area will change but only to some extent due to the construction of project related structures such as embankments, bridges, flyovers and interchanges especially during the construction of bypasses to avoid the traffic disruption in cities.

199. Visual changes to the topography will be of permanent but slightly adverse in nature and need no mitigation measures except that the project design should consider aesthetic concerns.

7.4.1.2 Change in Hydrologic Regime

200. The project has an extensive network of drainage channels/ nullahs and tributaries of River Indus. For the crossing of drains and water courses, small bridges and culverts should be constructed, wherever, required

201. Mitigation measure would involve:

- Proper design of bridges on water bodies to accommodate design flows;
- Small bridges will be constructed on drains coming in the ROW;
- Provision of box culverts to control flood damages and provision of safety of embankments; and
- Provision of sufficient sizes of drainage network to take design flows.

7.4.2 Ecological Environment

7.4.2.1 Removal of Roadside Trees

202. Approximately 228 plants of various species belonging to the communities will be cut due to construction of additional carriageway. Most of trees are Acacia (Acacia), Eucalyptus (Eucalyptus), Shisham (Dalbergia sissoo), and Peepal (Ficus religiosa). Trees along the corridor belong to NHA. Mostly, these wood and fruit trees grown in

the NHA owned public ROW, were planted by NHA and are managed through the district forest department. Instead of providing compensation, the lost government trees will be replenished through replantation of new trees as per government policy after implementing the project civil works.

203. Where possible, the design and road construction teams will seek to avoid the cutting of trees. Contractor will identify and label the trees to be cut prior to construction so those can be monitored during construction. Trees will be removed only coming in the road corridor of impact while other trees in the ROW would not be affected. Plants would be transplanted and compensatory trees would be planted maintaining the ratio of 1:8 plants from project budget. Proper compensation will be paid to the owner of trees as recommended in the LARP.

7.4.3 Social Environment

7.4.3.1 Land Acquisition, Infrastructure and Resettlement

204. One of the major project related impact will be the land acquisition for the Project ROW that will result in causing disturbance to the affected residents of the project area.

A summary of affected assets based on LARP of the project is given in **Table 7.5**.

Table 7.5: Affected Assets Based on LARP of the Project

Category of Affected Assets	Unit	Shikarpur-Kandhkot Section		Kandhkot-Kashmore Section		Kashmore-Rajanpur Section	
		Impact Magnit ude	Numb er of DHs	Impact Magnit ude	Numb er of DHs	Impact Magnit ude	Numb er of DHs
Loss of land	Acres	4.3	7	316.9	67	37.34	27
Loss of cropped area	Acres	53.7	126	326.7	115	49.8	94
Loss of trees	Nos.	9	1	28	3	206	39
Affected residential structure	Nos.	51	37	19	24	277	102
Affected commercial structures	Nos.	361	154	379	155	798	450
Renter business operators in affected structures	Nos.	-	233	-	90	-	105
Employees in affected structures	Nos.	-	228	-	-	-	16
Total DHs	-	-	786	-	454	-	833
Affected Community Assets							
Mosques (affected washroom area with no impacts to mosque hall, boundary wall act.)	Nos.	16	Comm unity	11	Comm unity	26	Comm unity
Hand pumps	Nos.	4		2		3	
Village signboards	Nos.	-		-		8	
Graveyards	Nos.	-		-		1	
Affected Public Assets and Infrastructure							
School (Rooms)	No	2	Educat ion Dept.	-	-	-	-
NHA Room	Nos.	2	NHA	1	NHA	-	-
Boundary Walls (School/Hospital/ PTCL/Police Post/Gas Station)	Nos.	4	Educat ion & Health Dept.	4	PTCL/ Police Deptt./ SNGP L	-	-
Police Check post	Nos.	31	Police	7	Police	-	-

Category of Affected Assets	Unit	Shikarpur-Kandhkot Section		Kandhkot-Kashmore Section		Kashmore-Rajanpur Section	
		Impact Magnitude	Number of DHs	Impact Magnitude	Number of DHs	Impact Magnitude	Number of DHs
			Dept.		Deptt		
Roadside passenger waiting sheds	Nos.	7	NHA	2	NHA	7	NHA
Transmission line/ Transformer	Nos.	46	WAPDA	45	WAPDA	-	-
Gas pipeline/ gas supply units	Nos.	1	SSGPL	-	-	1	SNGPL
Tube well managed by (PID)	Nos.	-	-	-	-	1	PID
Village Signboards	Nos.	-	-	-	-	17	NHA
Water Filter Plant	Nos.	-	-	-	-	1	PHED
Mobilink Towers	Nos.	2	Pakistan Mobile Communications Limited	-	-	-	-
Street Lights	Nos.	6	NHA	29	NHA	-	-
Railway Crossing	Nos.	1	Ministry of Railways	-	-	-	-
Source: Land Acquisition and Resettlement Plan of Shikarpur-Rajanpur Road Section (April, 2020)							

205. For the land coming in the ROW, the affected people should be compensated as per provisions of LARPs prepared for these packages of CAREC Corridor N 55.

7.4.3.2 Changes in Land Value

206. The proposed Project is expected to increase the land values, especially, along the bypasses. Landowners will have an opportunity to sell their land on increased prices and start new businesses. This impact will be major positive in nature.

7.4.3.3 Physical Cultural Resources

207. Since no Physical Cultural Resource is falling within the Right of Way (ROW) of the proposed alignment of the Dual carriageway, so there is no need for relocation of such resource. Cultural resources such as graveyards, mosques and shrine are situated in nearby communities and are visited by local people. If any mosque is coming in the ROW that should be relocated.

208. Mitigation measures will include provision of pedestrian corridors near the communities, which have important Physical Cultural Resource.

7.4.3.4 Public Utilities

209. Due to the proposed project, public utilities affected may create disruption of public services and economics. This impact is however temporary and minor negative in nature.

210. Mitigation measures will include:

- Incorporate technical design features to minimize effect on public utilities; and
- All public utilities likely to be affected by the proposed project need to be relocated well ahead of the commencement of construction work.

7.5 Construction Phase

211. Following is the brief description of impacts and their mitigation envisaged during the Construction Phase.

7.5.1 Physical Environment

7.5.1.1 Disruption of Existing Public Utilities/ Infrastructure

212. There may be some disruption to the already existing utilities like electricity poles, underground telephone lines, power transmission lines, water courses, small village roads, etc. in the project area during the construction phase. These impacts are, however, temporary and minor negative in nature.

213. Mitigation measures will include rehabilitation of existing utilities before construction to avoid any inconvenience to the residents of the project area or provide them with alternate arrangement during the construction period.

7.5.1.2 Soil erosion and Contamination

214. Soil erosion may occur on roadside, at contractors' camps and at embankment works as a result of uncontrolled run-off from equipment washing yards, excavation of earth/cutting operations and clearing of vegetation; whereas, contamination of soil may be caused by oil and chemical spills at asphalt plant sites, workshop areas and equipment washing yards. Also, due to unauthorized use of borrow areas and quarries, soil erosion may occur resulting in degradation of landscape. This may limit the future use of land for agricultural purposes. This impact is, however, of temporary and moderate negative in nature.

215. Mitigation measures will include:

- Minimizing the area of soil clearance
- Low embankments will be protected by planting vetiver grass that can flourish in relatively dry conditions;
- High embankments will be protected by providing stone pitching or riprap across embankments. This practice will also be applied across cross-drainage structures where embankments are more susceptible to erosion by water run-off;
- Soil contamination by asphalt will be minimized by placing all containers in a bunded area away from water courses;
- Provision of impervious platform with oil and grease trap for collection of spillages during equipment and vehicle maintenance;
- Provision of secondary containment during handling of lubricants (e.g. provide drip trays);
- Decanting and or controlled disposal of oil and grease as collected at collection tanks of maintenance yard and chemical storage areas;
- Non-bituminous wastes from construction activities will be dumped in approved sites, in line with the legal prescriptions for dumpsites;
- Soil erosion checking measures such as the formation of sediment basins, slope drains with cascading, etc., will be carried out;
- Productive land or land adjacent to agricultural/irrigated land may not be preferred for excavation;
- Non-productive, barren lands in broken terrain, nullahs and publicly recognized waste lands should be given preference for borrowing materials;
- Aggregate required for road construction procured from quarries and river beds will need approval from authorities; and
- Contaminated should be recapped or paved with clean soil up to 1-meter depth.

7.5.1.3 Borrow/Open Pits

216. Borrow/open pits and its excavation activities may result in land disputes, soil erosion, and loss of potential cropland, loss of vegetation, landscape degradation, and damage to road embankments. Borrow/ Open pits may also result in potential sources of mosquito breeding and may prove hazard to human beings, livestock and wildlife. This will also degrade hygienic condition of the project area. This impact is permanent and minor negative in nature.
217. Mitigation measures will include:
- Land record should be checked before signing any contract with locals to borrow soil
 - Careful selection of borrow areas to choose barren land and conversion of borrow pits into fish farms
 - Necessary permits must be obtained for any borrow pits from the competent authorities; and no excavations are allowed within distance of 500 m to ROW;
 - In borrow pits, the depth of the pit will be regulated so that the sides of the excavation will have a slope not steeper than 1:4;
 - Soil erosion along the borrow pit shall be regularly checked to prevent / mitigate impacts on adjacent lands; and
 - In case borrow pits fill with water, measures have to be taken to prevent the creation of mosquito-breeding sites. Pollution Prevention and Abatement.

7.5.1.4 Air Pollution Control

218. Air quality will be affected by fugitive dust emissions from construction machinery, asphalt plants and vehicular traffic. Emissions may be carried over longer distances depending upon the wind speed, direction, horizontal difference in atmospheric pressure, temperature of surrounding air and atmospheric stability.
219. The critical sources of air pollution during the construction phase will be:
- Asphalt plants and concrete batching plant and quarry areas;
 - Traffic diversion routes marked along dirt tracks that generate fugitive dust when in use by vehicular traffic; and
 - Transportation of materials and other construction activities that create dust emissions.
220. During construction, the continuous operation of machinery and movement of heavy trucks and vehicles may generate gaseous emissions and have a moderate negative impact on the surrounding environment. The overall impact on the quality of air during the construction phase will, however, be limited to the project's implementation phase only.
221. Mitigation measures will include:
- **Site management:** Preventive measures against dust should be adopted for on-site mixing and unloading operations. Regular water sprinkling of the Site should be carried out to suppress excessive dust emission(s), open burning of waste should be strictly banned;
 - **Material transport:** all vehicles carrying dusty loads should be covered/ watered over to extent that water should not drop on the main roads during carriage
 - **Power generators and construction machinery:** are important point sources at the construction sites. Proper maintenance and repair are needed to minimize the hazardous emissions;
 - **Asphalt, hot mix and batching Plants:** should be equipped with dust control equipment as a pollution preventive measure such as fabric filters or wet scrubbers or electrostatic precipitator to reduce level of dust emissions. These plant and quarry areas should be located 500 meter away in downwind directions from communities;

- **Stockpiles** location should be downwind from receptors and must be sprayed during material movement. Additional measures such as fencing from higher barrier required when within 300 metres from receptors.
- **NEQS:** applicable to gaseous emissions generated by construction vehicles, equipment and machinery should be enforced during construction works; and

222. The majority of dust problems caused during the construction phase of the project could be effectively mitigated by the implementation of simple procedures by the Contractor including but not limited to the following:

- **Service roads** (used for earthmoving equipment and general transport) should be regularly sprayed with water during dry weather;
- **Excavation work** should be sprinkled with water;
- **PPEs** for Construction workers should be provided with masks for protection against the inhalation of dust;
- **Vehicle speed** in the project area should be prescribed not more than 20 km/ hr. and controlled accordingly; and
- **Monitoring:** Air quality monitoring should be carried out as mentioned in **Table 8.3**.

7.5.1.6 Noise and Vibration Control

223. Noise is the most pervasive environmental problem in the urban areas especially on the road side. Noise is a by-product of human activity, and area of exposure increases as function of mobility and construction activities. Main sources during construction are heavy machinery such as bulldozers, excavators, stabilizers, concrete mixing plant, pneumatic drills, stone crushers asphalt plants and other equipment. The above machinery is expected to generate noise levels that would be severe in the areas whereas previously no roadside construction is carried out such as Kashmore bypass. Noise generated by construction machinery is likely to affect sensitive receptors located within 50 meter of the proposed roadway. This impact is temporary and minor negative in nature.

Construction Noise Modeling

224. For the prediction of noise generated from the machinery used for the construction activities and its effect on the Noise Sensitive Receiver (NSR), a model was developed by performing calculation on the excel sheet.

Methodology

225. Construction equipment sound levels are the sound levels emitted by equipment under actual field operating conditions. Construction equipment operate under two primary modes – mobile and stationary. Mobile equipment such as dozers, scrapers etc., operate in a cycles in which full power is followed by reduced power. Stationary equipment can be subdivided in two groups: one group such as compressor, batching and asphalt plants and generator which operate at constant power while the jack hammers, auger drill, falls into impact machinery with instantaneous sound levels. The following steps were taken to develop the noise model to predict the hourly equivalent noise levels at the site:

- Identification of main construction operation or phases;
- Equipment used to complete each construction phase;
- Determination of the peak noise levels and minimum noise level for a work cycle of equipment;
- Determination of hourly equipment equivalent noise level at the receptor by considering the distance between the receptor and equipment and also the usage factor;

226. Determination of expected cumulative hourly equivalent noise level at the site from different construction operations. Results of the noise modelling are attached as

Annex IV, which shows the projected noise level will be 107 dB(A), 101 dB(A), 98 dB(A), 95 dB(A) and 93(A) for 20m, 40m, 60m, 80m and 100m distances respectively. The results of the modelling show the worst-case scenario when all equipment's are operating at the same time which is least likely to occur. However, the most affected would be the workers and required to use PPES. Identified noise sensitive receptors (NSR) include religious, education institutions, wellbeing facilities and residential areas. National Environmental Quality Standards (NEQs) for Pakistan & WHO Standard²¹ would be followed:

227. Other mitigation measures mentioned below should be taken in order to minimize the impacts of noise in the project area. These measures include, but are not limited to the following:

- **Source Control:** Selection of up-to-date and well-maintained plant or equipment with reduced noise levels ensured by suitable in-built damping techniques or appropriate muffling devices. Operate Compressor or generator with closed doors and idle plants/ equipment should be throttled down or turned off;
- **Timings:** Confining excessively noisy work to normal working hours in the day between 8 a.m. – 6 p.m., as far as possible; Preferably, restricting construction vehicles movement during night-time;
- **PPEs:** Providing the construction workers with suitable hearing protection like ear cap, or earmuffs and training them in their use;
- **Community notification and Consultation:** Inform community prior to noisy operations and get the information regarding the exams in school, prayer timings etc.
- **Siting:** Locating the rock crushing, concrete mixing, semi-finished workshops and materials shipment yards at least 500 m from NSRs including residential areas, particularly schools, hospitals, and nursing homes. Such activity taking place near or through villages will broadcast continuous noise in the 70–80 dB (A) range or above.
- Noise monitoring should be carried out as mentioned in **Table 8.3**

7.5.1.7 Waste and Hazardous Waste

228. Due to construction activities, waste will be generated at construction and contractors camp site. The construction waste will include wastewater, oil spillage from machinery, domestic waste and solid waste etc. The handling and storage of oil, asphalt/bitumen, fuel and various chemical/ additives may be a source of hazardous waste. This will result in unhygienic conditions, health risk to work force and public at the camp site. This impact is temporary and minor negative in nature.

229. Mitigation measures will include:

- **Management:** keep the site clean and tidy e.g. litter free and good housekeeping and disallow the burning of waste
- **Solid waste handling:** Provided storage containers of appropriate size for workers food waste and construction waste. The containers should be properly labelled for food waste, recyclables, and general refuse. The waste should be removed on regularly basis by the licensed contractors.
- **Chemical waste:** oil drums and plants/ equipment should be provided with drip trays as secondary containment and these drips should be free of oil. In case of

²¹Guidelines values are for noise levels measured out of doors. Source: Guidelines for Community Noise, World Health Organization (WHO), 1999. 55 For acceptable indoor noise levels for residential, institutional, and educational settings refer to WHO (1999).

oil spill clean up the spill immediately, store the chemical waste in the labelled container with clear instructions to handle it and should be disposed of by licensed contractor. The oil rags should be stored properly to avoid the fire risks. Oil filter should be collected in a separate container to be placed under the shades and sold out to contractor.

- **Site handover.** Ensure that no debris, spoil or residue of materials should be left at the site and this should be removed before signing of the contract
- **Spoil and Inert waste:** will be disposed of by the contractor on only the sites approved by SC. The best practice is to rehabilitate the land for schools or private land with the willingness of the owner.

7.5.1.8 Water Pollution control

230. Wastewater is anticipated to be generated from the construction camps, wheel washing facilities, asphalt plants and batching plants and from various construction activities. Water ponding and direct discharge to surface water bodies may pose severe consequences.

231. Mitigation measure will include:

- **Wastewater from workshops:** Wastewater effluent from contractor's workshop and equipment washing yards would be passed through gravel/ sand beds to remove oil/ grease contaminants before discharging it into natural streams;
- **Sanitary wastewater:** Sanitary wastewater should be treated through buried septic tank and the capacity of the septic tank should be three times than the generated effluent per day. Manholes onsite should be covered and sealed. Guidelines for sanitary wastewater from IFC/ World Bank may be consulted.
- **Public Roads:** around the site entrance and site hoardings should be kept clean and free of muddy water
- **Road drainage:** provision of retention pound with cascading to drain the road surface runoff.
- **Water ponding at Batching Plants:** Stored water for batching plants should be used or drained during shut of as this will cause water ponding leaving the scum at the top serving as a habitat for mosquitoes and vectors.
- **Canal Water:** Construction debris should not find its way in to canals and washing machinery with the canal water should be prohibited.
- **Water quality monitoring** should be carried out as mentioned in **Table 8.3**

7.5.1.9 Impacts of construction of bridges

232. Due to Drainage works and use of vehicles during construction of bridges construction of bridges, negative impact on flora and fauna from increased sediment loading of streams will occur. Negligence in materials management may pose harm to aquatic flora and fauna from oil, fuel, cement or other substances entering watercourses.

233. Mitigation measures include;

- During the spawning seasons (April-August) the construction activities must be avoided
- An appropriate water management system shall be used during the construction period for instance efficient land drainage and the use of constructed ponds for receiving site runoff to reduce the impact of runoff on nearby watercourses.

- Oil interceptors or drip trays must be in practice especially in vehicle parking areas, and must be inspected and cleaned regularly.

7.5.1.10 Disposal of Mucking Material

234. Inevitable cut and fill earthwork operations will open up scars on the land around the project area. This impact is temporary and minor negative in nature.
235. Mitigation measure will include proper landscaping, which should be given due consideration along with re-establishment of the local/indigenous vegetation. The excavated materials that are unsuitable for use will need to be stored, transported and disposed of appropriately at designated sites.

7.5.1.11 Traffic Management

236. Due to the proposed construction activities, proper traffic management may pose a challenge in the project area, particularly, where the construction of Interchanges, underpasses and Flyover will take place. This impact is temporary and minor negative in nature.
237. Mitigation measures will include:
- Movement of vehicles carrying construction materials should be restricted during the daytime to reduce traffic load on the existing roads;
 - Coordinated planning of traffic diversions by the traffic police and NHA in accordance with the construction program with advance warnings to the affected residents and road users and availability of continuous services of the police in the diversion and control of traffic; and
 - Proper diversion signage with lightening devices at a reasonable distance so that the traffic could easily merge to the lanes open for traffic.

7.5.1.12 Green House Gas (GHG) Emission and Climate Change

238. Climate change effects would be considered in two aspect:
239. Effect of climate change on the Project: This could be due to extreme events of temperature change, flood risks, creation of water ponds and wetlands.
240. **Effect of Project on climate change:** This is due to generation of GHG emissions. The main sources of greenhouse gases (CO₂, CH₄, NO_x etc.) during the construction activities of the proposed Additional Carriageway (ACW) will include both mobile and stationary sources. The mobile source will be the construction and transportation vehicles while the stationary source will be the batching and asphalt plants. Emission of greenhouse gases cause global warming contributing to climatic changes on regional and global scale.
241. Mitigation measures will include:
- **Resource conservation:** Avoid the wastage of raw material, leakages of water, oil, fuel, and use the material resistant to weather conditions
 - **Energy Efficiency and Controlling devices:** Use energy efficiency techniques and emission controlling devices. Avoid any unnecessary work and keep the material transportation distance to minimum;
 - **Enforcement of NEQS** applicable to gaseous emissions generated by construction vehicles, equipment and machinery
 - **Green Infrastructure:** provision of eye lands, tree plantations and landscaping

7.5.1.13 Resource Conservation

242. Almost all the materials to be used in the construction of Additional carriageway are non-renewable and therefore their sustainable use is necessary for the future use. Large quantities of water are used in the construction of concrete structures and in watering the unfinished surfaces. Use of water is of major concern while developing resource conservation strategy. Other construction material like aggregate and sand are locally available and there is no concern of scarcity in future use. Bitumen is not locally produced and its sources are not locally available so its sustainable use is prerequisite.

243. Mitigation measures will include:

- Water conservation: Wastage of water should be controlled through providing proper valves and through controlling pressure of the water and use of water jets and sprays for watering surfaces rather than using overflow system; Water use should not disturb the existing community water supplies and avoid unnecessary equipment washings ;
- Avoid timber use by providing gas cylinders
- Bitumen/ Cement Use: procure and use only the required amount of bitumen/ cement and iron for road construction.

7.5.1.14 Energy Efficiency

244. Use of electricity will be insignificant. Diesel and residual fuel oils will be used to operate construction machinery and asphalt and batching plants. Sustainable use of energy resources is very important not to continue future use but it will also help to reduce air emissions.

245. Mitigation measures will include:

- Ensure adequate insulation to reduce heat loss through batching plants;
- Flue gas monitoring: Regularly monitor CO and CO₂ content of the flue gases to verify that combustion systems are using practical excess air volumes;
- Mechanical Energy losses Control: Regular service of the vehicles and batching plants will reduce the mechanical losses of energy. Maintain clean heat transfer surfaces in asphalt batching plant.

7.5.1.15 Occupational Health and Safety

246. Health risks and workers' safety problems may result at the workplace if the working conditions provide unsafe and/or unfavourable working environment due to storage, handling and transport of hazardous construction material. Workers will be provided with safe and healthy working environment taking into account risks inherent to the particular sector and specific classes of hazards in Project area.

247. Mitigation measures will include to ensure that;

- Installation of warning taps and flags to isolate trenches and active sites
- Detours provision for traffic and watering regularly for dust suppression
- Provision of barricading for excavation, trenches etc.
- Arrangement for onsite traffic control for example use of speed limits, flagman etc.
- Locked areas available for hazardous material
- Fuel storage area should be covered and tanks are properly buried or placed on properly built frame.
- Firefighting system in place at active site and camp site/ workshops
- Provisions of first aid kit and arrangements of the medical practitioner and the contact number displayed for Doctors and ambulances

- Drinking water available at sites and camps in the form of dispenser/ coolers
- Fans/ coolers are available at site and camps for ambience
- Wastewater discharged through Septic tanks
- Sufficient Lavatories and Showers with reasonable quantity of water is available for the workers, campsites and subcontractor campsite
- Potable water of good quality and quantity available at site
- Provisions of clean eating area, gas cylinder, stoves available at site
- Removal of any hazards present of working at high, slip and fall and any chance of struck by objects and moving machinery. The area needs to be confined by warning tape or barricading
- Workers have available the PPEs for head protection, eye protection, face protection, body protection, feet protection, hand protection and properly trained to use it
- Warning signs for speed limit /use of speed control devices at place
- Workplace properly illuminated for work and lighting arrangement at place
- Proper air supply for workers such as fans, cooler etc.
- The sites access restricted to avoid trespassing
- Signboards at place for electrical devices, compressor rooms, material, safety measures, emergency exits, and the signage are according to International Standards?
- Equipment containing hazardous substance properly labelled such as piper color coding and communication of hazard at place
- Power cords and extension cords are protected from traffic by shielding or suspending above traffic areas
- No approach zones established around or under high voltage power lines
- Electrical cords, cables, and hand powers tools are checked for fray or exposed cords
- Welder goggles/ full-face eye shield are provided to the workers involved in Welding / hot works. Additionally, fire extinguishers are at place
- Workers constantly involved in the nature of work involving repetitive motion/ manual handling and if so they must work in revolving shifts.
- Eliminate the chances of biological hazards due to unhygienic conditions such as spread of dengue fever
- Eliminate any Hazards related to contaminated land by oil/ chemical spills etc.?
- The workplace safety instruction at place of work/ workstation.

7.5.1.16 Storage of Chemicals and Dangerous Goods

248. Hazardous material being used for the road construction or used as insecticides if transported, handled and stored improperly may pose a serious threat to the health of workers and community.

249. Mitigation required are as follows:

- Contractor must comply with the conventions such as Basel convention, Stockholm convention for which the country is signatory during the selection of the hazardous material and will follow the hazardous substance rule 2003 for safe work practices
- Must be stored in locked area only accessible to trained staff with clear instructions
- Provision of secondary containment for handling and spill kit/sand/ saw dust should be available in case of spill.

7.5.1.17 Fire Prevention/ Emergency Preparedness

250. Fire is the most common and the dangerous hazard at the campsite and active sites for work and required the following arrangements to be in place:

- Provision of fire extinguishers/ fighting facilities and maintained and not expired. Fire escape route and assembly area must be demarcated and not blocked/ obstructed
- Displaying of emergency contact detail
- Reporting and reviewing of accidents/ incidents for corrective/ preventive actions
- Establishing mechanism to handle catastrophic situation such as flooding during bridge constructions.

7.5.2 Ecological Environment

7.5.2.1 Biodiversity Conservation

a) Flora

251. Due to the proposed Project, a number of trees of different species and belonging to different age groups will be rooted up. The trees coming in the ROW are mostly Phulai, Eucalyptus, Shisham, Kikar etc.
252. Establishment of contractor's camps and warehouses for storage of equipment, material etc. shall involve clearing of vegetation from the area causing a negative impact. During the entire construction period, dust laden polluted air will form a dust film on the leaves, thus blocking sunshine and stomata, thereby hindering photosynthesis process having detrimental effect on the plant health. Also, during the construction activities, the contractor's workers may damage the vegetation including trees (for use as firewood to fulfill the camp's requirements).
253. Mitigation measures will include:
- The indigenous trees most suited to the tract like Neem, kikar, Sheesham, should be re-planted in ROW.
 - An awareness campaign targeted on the neighborhood farmers shall be run to popularize the planting of trees; and organic farming will be encouraged to minimize the use of chemical fertilizers and pesticides;
 - The contractor's staff and labor will be strictly directed not to damage any vegetation such as trees or bushes. They will use the paths and tracks for movement and will not be allowed to trespass through farmlands;
 - Construction vehicles, equipment and machinery will remain confined within their designated areas of movement;
 - Contractor will supply gas cylinders at the camps for cooking purposes and cutting of trees/bushes for fuel will not be allowed;
 - Camp sites and asphalt plants will be established on waste/barren land rather than on forested or agriculturally productive land. However, if such type of land is not available, it will be ensured that minimum clearing of the vegetation is carried out and minimum damage is caused to the trees, under growth and crops; and
 - Compensation for trees required to be cut on account of their coming in the ROW of additional carriageway must be paid to farmers/owners in accordance with market rates.

b) Fauna

254. Due to the implementation of the proposed Additional carriageway Project, the free movement of fauna would be disturbed as the Dual carriageway will restrict their free movement. Another impact on the fauna of the project area will be the probable dislocation of the birds/animals (rodents) from their nests and burrows.
255. Reptiles like snakes and lizards, living in the holes or underground shall either get killed or move to the adjacent areas. Similarly, birds like sparrows, mainas, crows, who have nests on the trees located in the ROW or who frequently visit the project area in search of food shall receive a negative impact and shall have to move to adjoining areas. These trees provide resting and nesting places to the animals and birds, so the cutting of these trees will have negative effect on fauna. However, this impact will be temporary and minor negative in nature.

256. Also, due to the leakages/spills from the construction equipment/machinery the local ponds/water storages and water courses where the animals/birds drink water may get contaminated; thus, affecting/endangering the fauna of the project area. This impact is temporary and minor negative in nature.

257. Mitigation measure will include:

- Plantation of large number of trees along the proposed Additional carriageway to regain the ecological habitat;
- New and good condition machinery with minimum noise will be used in construction;
- Animal corridors must be provided along the whole alignment, wherever necessary;
- Noisy work will not be carried out in night time so that there should be no disturbance to local birds and animals;
- Contractor will ensure that the no hunting, trapping of animal will be carried out during construction;
- Borrow pits will be fenced so that no animal can fall into these;
- The camps will be properly fenced and gated to check the entry of wild animals in search of eatable goods. Similarly waste of the camps will be properly disposed off to prevent the chances of eating by wild animals, which may prove hazardous to them;
- Special measures will be adopted to minimize impacts on wild birds such as avoiding noise generating activities during the critical period of breeding; and
- Alternate nesting facilities shall be tried for those birds disturbed during hatching season.

7.5.3 Social Environment

7.5.3.1 Construction Camps/Camp Sites

258. Due to the camp sites, loss of vegetation and assets on the selected land and dissatisfaction of rehabilitation measures during and after completion of construction phase may occur. However, it will be a temporary and minor negative impact. However, a range of impacts those either remain likely to occur or are unavoidable. For these impacts, mitigation measures have been developed to minimize the likelihood, extent or duration of their occurrence, and any associated adverse effects.

259. Mitigation measures will include:

- Locate camp site 500 meter from communities and 50 meters from scattered residences.
- All efforts during the design stage should be made to minimize the removal of existing macro-plants at camp sites; The contractor(s) will provide plan for removal & rehabilitation of site upon completion; Photographical and botanical inventory of vegetation before clearing the site; and Compensatory plantation to be scheduled when construction works near end.
- No trespassing or animal crossing should be allowed from construction camps by maintaining administrative controls
- Maintain high standards of cleanliness, provision of septic tanks, Lavatories and washing facilities with sufficient quantity of water and this is both for contractual and sub-contractors labor.
- Provide adequately sized solid waste bins/ containers at key locations around the camp and waste should be regularly collected and disposed off
- Fully equipped kitchen with sinks emptying to buried septic tank and provision of gas cylinders
- Build an adequate drainage system leading surface water to a settlement pond of sufficient capacity to control the large quantities of wet season rain and runoff

- Guidance on acceptable behavior in the campsite for workers in and around the campsite and communities.

7.5.3.2 Cultural Conflicts

260. There are chances of arising of issues related to cultural differences/conflict between the Contractor's workforce and the local inhabitants, conflicts arising due to the mix of local and migratory job seekers as the use of local resources and products will be increased. In this situation, local residents may resist Contractor's workforce attitudes, cultural clashes particularly when local/international contractors are engaged, social disturbance and dissatisfaction with employing outsiders, competition for natural resources e.g. with farmers/livestock raisers etc. may arise. This impact is temporary and minor negative in nature.

261. This impact can be mitigated by adopting the following mitigation measures:

- Establishment of formal links with affected communities and avoid damage to crops along the highway;
- Plan for social grievance redress mechanisms (GRM) including the Nazims of Union Councils and community leaders;
- Judicial payment to land affectees and for the leased areas and avoid cutting the link between communities
- Seek assistance from and cooperation with local NGOs;
- Familiarize outside laborers on local etiquettes;
- Local labor should be employed for construction works.

7.5.3.3 Physical Cultural Resources

262. There are no physical cultural resources as listed in UNESCO World Heritage list of archaeological sites coming in the ROW. However, this Indus valley has its own civilization and it was the ancient route for trade. A list is given in section 4.

263. As the project involves excavation work and in case of any accidentally discovered archaeological/ historical heritage during the construction phase, contractor should stop the activities immediately and inform the Supervision Consultant and chance find procedures should be adopted as given in **Annex V**.

7.5.3.4 Economic Activity

264. Due to the construction of the proposed Project, economic activity will be generated in the project area as the laborers and semi-skilled staff will have an opportunity to work in the project area. This will provide them an opportunity to develop their skills and capacities. This is a moderate positive impact.

7.5.3.5 Community Health and Safety

265. The construction activities and vehicular movement at construction sites and access service roads may result in roadside accidents particularly inflicting local communities who are not familiar with presence of heavy equipment. This is a temporary and minor negative impact. Quality of groundwater and surface water resources available in the nearby local communities may be affected due to the construction activities, oil spillage and leakage, roadside accidents etc. The labor works with different transmittable diseases may cause spread out of those diseases in the local residents. The borrow pit areas located near the residential, settlements, may cause accident for the people moving near to those areas.

266. Mitigation measures will include to ensure that

- Grievance Redress mechanism at place with complaint registers at each site
- Awareness raising programs and procedural adaptation to minimize the traffic related accidents of workers and communities

- Maintenance of deterioration of existing roads due to movement of heavy machinery and any rehabilitation work
- No water pounding creating habitat for mosquitoes breeding especially near batching and asphalt plants
- No water quality and quantity disruption affecting communities
- Access restriction by combination of institutional/ administration control to site and camps, by provision of fencing, signage etc.
- Covering of uncovered opening or open trench left creating the fall hazard
- No free access to hazardous material and there is any that must be locked and restricted area sign should be placed
- There should be no chances of Pedestrian interaction with machinery
- Construction activities should not be effecting the business of locals
- Protection of any vector born and communicable diseases among the workers and communities including the current coronavirus pandemic.

267. Covid-19 management plan is attached as **Annex VI**.

7.6 Anticipated Impacts during Operational Phase

268. The anticipated environmental impacts related to the proposed project have been studied for the operational stage of the Project as discussed hereunder.

7.6.1 Physical Environment

7.6.1.1 Water pollution

269. No major adverse impact on groundwater is anticipated during the operational phase with the exception of some occasional oil spills, which may be restricted up to the road surface, however, sometimes the road runoff may be washed into surface water during rains etc.

7.6.1.2 Air & Noise

270. During the operational phase, Improvement in road condition will help reduce traffic related emissions in the short term by allowing a smoother traffic flow. The noise levels are anticipated to increase due to traffic related noise pollution; vibrations from engines and tires and mainly use of pressure horns. This impact is permanent and moderate negative in nature.

O&M Noise Modeling

271. Noise modelling for O&M phase will be done by using GIS software after receiving noise results from the Laboratory.

272. Mitigation measures will include:

- According to monitoring results, additional sound barriers in form of trees and hedges will be discussed with the affected people and planted if agreed;
- Signs for sensitive zones e.g health centers / educational institutions etc. to disallow the use of pressure horns; and
- Speed limit enforcement and penalties against traffic rules violators.
- Ban on the burning of crop residues such as rice and wheat husk along the road to avoid trees from catching fire and driving hazard.

7.6.1.3 Wastes/ Hazardous Waste

273. During operation phase Non-hazardous waste may be generated from road sweepings or small quantities of municipal waste from highway offices. No hazardous

waste is expected to generate in operation phase except during road maintenance works. Transportation of hazardous waste is also expected and must be regulated.

274. Mitigation measures will include:

- Solid Waste generated from offices will be properly disposed off through local solid waste management system;
- Proper labelling of containers, including the identification and quantity of the contents, hazard contact information of containers will be checked at toll plazas;
- Providing the necessary means for emergency response on call 24 hours/day;
- Management of hazardous waste during road maintenance works will be similar as given for construction phase.

7.6.2 Ecological Environment

7.6.2.1 Biodiversity Conservation and Natural Resource Management

a) Flora

275. No negative impacts are envisaged on the flora of the area during the operational phase. However, improper maintenance of the saplings planted against the trees cut for the proposed Project may adversely affect the growth of those saplings which were planted to improve the environmental aesthetics of the project area. Raising of new trees shall render a positive impact on the flora of the area and will also cause a positive impact on the landscape of the area, which shall be of permanent in nature.

276. An awareness campaign targeted on the neighbourhood farmers will be run to popularize the planting of trees; and Organic manuring will be encouraged to minimize the use of pesticides.

b) Fauna

277. The Project activities will bring some negative impacts on the fauna of the project area such as the uneasiness of movement and increased probability of accidents, if the animals/ livestock approach the proposed Dual carriageway. This impact is permanent and minor negative in nature. Noise and air pollution caused due to heavy and fast traffic on Dual carriageway, shall be a source of disturbance to the fauna of the area and especially to the avifauna of the area, which is another minor negative impact.

278. Raising of dense plantation of shady trees on both sides of the Dual carriageway shall provide resting, nestling and roosting habitat to the fauna and especially to the avifauna which is a major positive impact.

279. Provision of underpasses and cattle creeps will facilitate animal movement across the road.

7.6.3 Social Environment

7.6.3.1 Road Safety

280. Enhanced vehicular movement and speed in the long run may result in road safety issues like traffic accidents. This impact is permanent but moderately adverse in nature, since the frequency of accidents may be lowered, but their intensity may be quite severe due to enhanced speeds at which vehicles will move.

281. Mitigation measure will include strict enforcement of speed limits, installation of speed guns and channelization of traffic with respect to categories (heavy vehicle traffic and light vehicle traffic) and enforcement of penalties for the violators.

7.6.3.2 Less Wear and Tear of Vehicles

282. During the operation of the proposed Dual carriageway, lesser wear and tear of the vehicles will occur and it will also result in lesser fuel consumption and decrease in operating cost. This impact is permanent and has a major positive impact.

7.6.3.3 Community Development

283. Improved communication infrastructure will promote new business opportunities. In addition, such an activity will also increase the land value that will benefit the local residents. This impact will be permanent and major positive in nature.

7.6.3.4 Accessibility

284. The road users will have difficulty to access the mosques, schools and land across the road, which was relatively easier with two lanes road. It may cause accident and may lead to serious implications. This impact is major negative and permanent.
285. Mitigation measures include facilitation of the public with underpasses and bridges to connect to various communities in the area as mentioned in **Table 4.1**.

SECTION 8: ENVIRONMENTAL MANAGEMENT PLAN

8.1 Environmental Management

287. The objective of the Environmental Management Plan (EMP) is to address all the major environmental issues and provide framework for the implementation of the proposed mitigation measures during the preconstruction, construction and operational phases of the proposed project. The proper implementation of the EMP will ensure that all the adverse environmental impacts identified in the IEE are adequately mitigated, either totally prevented or minimized to an acceptable level and required actions to achieve those objectives are successfully adopted by the concerned institutions or regulatory agencies. The implementation of EMP should be carefully coordinated with the design and construction program of the project to ensure that relevant mitigation measures are implemented at the appropriate stage and that adequate resources are properly allocated to achieve the desired results.
288. The Contractor will be responsible for the implementation of the proposed Project under the direction of "Supervision Consultant (SC)" and NHA (EALS). The Contractor should be bound to follow the provisions of the contract documents especially about environmental protection and apply good construction techniques and methodology without damaging the environment.
289. Obligation of the contractor, to safeguard, mitigate adverse impacts and rehabilitate the environment should be addressed through environmental provisions in the FIDIC conditions of contract for construction, MDB harmonized addition- June 2010 and special clauses included in the contract related to environment. FIDIC clause 4.18 (protection of environment), 4.8 (safety procedures), 6.4 (labor laws), 16.3 (cessation of work/ remedial work), 2.3 b (employers' personnel), 4.21 (progress report) are important in this regard.

8.2 Institutional Responsibilities

290. NHA (EALS) have separate environment section headed by Director Environment to overall manage the environment related tasks and to guide project preparation, project construction, operation and maintenance work. However, overall responsibility for implementation of EMP falls to the PIU for the Project
291. Institutions involved for the executing of EMP would involve: EALS (NHA), Environmental Unit of PIU headed by (GM) CAREC-MMF, Environmental Unit of CSC, Environmental Unit of Contractor, Independent environmental monitoring contractor and EPA Punjab and Sindh. The institutional framework is shown in **Figure 8.1**.

8.2.1 EALS (NHA)

292. The responsibilities of EALS, NHA as a borrower include:
- Ensuring the Implementation of agreed technical and institutional measures specified in safeguard management plans
 - Monitoring and evaluation of environmental and social impacts and risks associated with the project
 - Review of the safeguard monitoring reports submitted by PIU on the status of the implementation of agreed actions
 - Ensuring the Project Implementation Unit (PIU) submits regular project progress reports to the ADB, with separate safeguards chapter
 - Safeguard report is prepared based on the inputs by contractors and project consultants and PIU dedicated staff's observations
 - Impose penalty and/ or require corrective action in case of non-compliance

- Semiannual reporting to ADB, or more frequently if new issues emerge, or sensitivities occur
- Reporting to EPA as per requirement of NOC
- In case the project is not in compliance with environment and social safeguard GM CAREC, can suspend work and employ the third parties to correct noncompliance.




Figure8.1: Institutional framework for environmental management

8.2.2 Project Implementation Unit (PIU)

293. PIU will be responsible for:

- Depending on availability of environmental expertise in NHA, hiring of environmental specialists
- Ensuring environmental provisions and expertise are covered by supervision consultancy and construction contract
- Supervision and monitoring the implementation of EMP
- Establish regular reporting by supervision consultant and contractor and environmental safeguard as a part of progress report
- Undertaking regular visits to project sites and report to the Bank on the status and any new / unexpected issues
- Follow up with contractors and consultants on environmental compliance and ensure enforcement
- Submission of semi – annual monitoring reports to NHA EALS for review and onward submission to ADB

8.2.3 Asian Development Bank

294. Bank team is responsible for:

- Reviewing the status of implementation of EMP
- Assisting and guiding the Borrower in addressing the issues identified by the supervision

- Conducting periodic site visits and supervision mission for detailed review for projects with significant impacts
- Reviewing of environmental management plan
- The need to improve Borrower's capacity
- Reviewing the periodic safeguard monitoring reports to ensure compliance as planned
- Resolution of grievances, especially, directly received to ADB

8.2.4 Construction Supervision Consultant (CSC)

295. CSC would be responsible for:

- Review and endorsement of SSEMP, and giving the input, if required, to assist contractor
- Review of bi annual environmental monitoring reports by the third-party contractor (Labs)
- Prepare corrective action plan in case of non-compliance
- Review EMP every six month and updating, if required
- Supervision of implementations of EMP and supporting contractor for environmental compliance
- Checking and endorsement of environmental part of method statements
- Preparing the training material and assist or providing the training
- Responding to environmental incidents reported
- Setting Environmental Management and Monitoring System (EMMS) and insurance EMMS in place
- Review and assistance in preparation of bi annual report and all other reports
- Grant approval for all facilities (establishment of camp, asphalt and batching plants, borrow areas) in light of the EMP requirements.
- The CSC's Environment Officer must be hired before construction starts so that the SSEMP is prepared in time

8.2.5 Contractor

296. The contractor will be responsible for:

- Implementation of environmental mitigation measures at preconstruction and construction stage
- Preparation of CEMP describing the mechanism to comply with the EMP and get it approved from CSC Environmental unit and PIU Environmental unit prior to mobilization
- Frequent monitoring and reporting of compliance of EMP
- The Contractor's Environment Officer must be hired before construction starts so that the SSEMP is prepared in time.

8.2.6 Third Party Environmental Monitoring Contractors

297. Environmental monitoring contractor will be responsible to carry out testing for various environmental attributes including air, noise, and water quality on behalf of PIU. The monitoring would be carried out prior to start of work to establish the baseline conditions and the frequent monitoring as specified in the EMP during the construction.

8.3 Staffing Requirement

298. Environmental staff will be required by Contractor, CSC and PIU. GM CAREC will approve the hiring of environmental staff to ensure the hiring of competent staff. Following functionaries with the indicative level of effort (LoE) will be involved in the implementation of EMP during construction:

GM CAREC (Head of PIU)

Project Director (Timely implementation of Project)

EALS NHA

- Director Environment

Environmental Unit of PIU

- Environmental safeguard expert full time
- One additional staff member for each section full time

Environmental unit of CSC

- Team leader (International Environmental Specialist for 4 months on intermittent basis)
- Environmental Specialist for each section (03 Nationals expert full time)

Contractor

- Environment Specialist (Full time)
- HSE Specialist (Full time)
- Environmental Technician (03) (Full time)
- Environmental Management Training Consultant (may be through CSC environment unit or by independent through Lump Sum Contract)

8.4 Reporting and Feedback Mechanism

299. The contractor's environmental unit will manage the daily activities to be conducted in compliance with the EMP and will be responsible for weekly reporting while CSC would be responsible for monthly inspecting and monitoring report. CSC will draft the semiannual environmental monitoring report and finalize with the PIU. PIU will submit that report to EALS for onward submission to ADB (see Table). EALS would also submit the periodic reports to EPA as per conditions of environmental approval.

Table 8.1: Reporting Requirements

Reporting responsibility	Reporting Requirement	Report submitted to
Contractor	Weekly compliance report	CSC
Construction Supervision Consultant (CSC)	Monthly Environmental Compliance Report Semi Annual Environmental Monitoring Report	PIU
PIU	Semi Annual reports	EALS NHA
EALS NHA	Final Environmental report after completion of defect liability period.	ADB, EPA

8.5 Environmental Technical Assistance and Training Plan

300. To raise the level of professional and managerial staff, there is a need to upgrade their knowledge in the related areas. Director Environment (EALS) should play a key role in this respect and arrange the training programs.

301. Training would be required to all the three agencies including contractor, CSC, PIU, to build their capacity with the following objectives:

- Full understanding of the EMP
- Understanding of their responsibilities
- Enhance the capability to undertake their responsibilities

302. There will be three levels of trainings (**Table: 8.2**) and CSS will maintain the training register.

Table 8.2: Training of Institutions involved in Environmental Compliance

Level of Training	Responsibility	Contents
Project Induction	CSC	Overview of environmental policy of Project, Environmental approval conditions, response to environment incidents, PPEs, Environmental receptors, environmental conformances. Sanitation and Healthcare
Tool Box talks	Filed level by Contractor	Environmental aspect of managing waterways crossings, soil erosion and sedimentation control, dust & noise control, wild life protection, safety of workers, waste management etc.
Capacity Building of NHA, PIU, Contractor, and CSC national staff	International consultant to develop the training material and conduction	ADB safeguard Policy. Environmental laws, Monitoring & Evaluation of EMP, EHS guidelines, Standards, Institutional responsibilities, reporting & feed back

8.6 Summary of Environmental Management Plan

303. **Table 8.3** provides the framework for the implementation of environmental management plan during different phases of the proposed project. It portrays impacts, mitigations measures and the responsible organizations for the implementation of the mitigation measures. Where additional costs are required for any mitigation measure it is given in the table:

Table 8.3 Environmental Management Plan

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
Pre- Construction						
Dust and Noise	Entire Road	Consultation with representatives from villages, mosques, schools for the timings to avoid significant impact	Prior to construction Activity	Included in Construction contract cost	Contractor	NHA/ CSC
Flooding	All bridges and culverts especially bridge on Canal emerging from Guddo barrage near Kashmore	All bridges and culverts to be designed not less than the current the current capacity	Prior to construction Activity	Included in Construction contract cost	Design team	NHA
CEMP	Entire road	CEMP Need to be prepared	Prior to construction Activity	Included in Construction contract cost	Contractor	NHA/CSC
Biodiversity Conservation	Entire road	Identification and labelling of tree in RoW to be uprooted and obtain necessary approval	Prior to construction Activity	Included in Construction contract cost	Contractor	
Disposal of excavation spoil and waste pavement	Proposed Disposal Sites	Before starting excavation work and removal of pavement seek approval from CSC of disposal sites meeting the following criteria: Located at distance of 50 m from watercourses No chances for the sedimentation and blockage of nearby water courses for example due to slope failure Not causing damage to crops/ productive area Prefer the sites needs to be improved by filling such as for school, universities, play grounds etc.	Prior to construction Activity	Included in Construction contract cost	Contractor CSC	NHA
Procurement of	Source of	Contractor will ensure that construction material	Prior to			

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
material from illegal source	construction material	such as sand, gravel, aggregates, will be obtained from approved quarries. NHA also listed the approved quarries in provinces in Composite Schedule of Rates (CSR 2014).	construction Activity			
Identification of site for construction camps, asphalt & batching plant and crushers		Follow the following criteria for selection of sites: Site must be 0.5 km away from the localities & cultural sites and 100m away from the existing road; Asphalt, batching and crushing plants must be installed in the downwind direction of residential areas.	Prior to construction at each section		Contractor	NHA/ CSC
Land Acquisition	Throughout the alignment	Mitigation measures will involve careful alignment and route selection by the designer to minimize the impact; and Adequate budget will be provided in the Project cost for the compensation to the affected people as per Land Acquisition Act, 1894 and ADB Safeguard Policy Statement 2009.	Prior to Construction	PKR 2200 M Given in PC-1	Design team	NHA (EALS)
Alignment selection for Bypass		Avoid sharp curves/turns in the design; Assure minimum tree cutting and vegetation clearance during alignment selection; and Selection of the route with minimum dislocation/ resettlement of the structures/residents.	Prior to Construction	Included in detail design cost	Design team	NHA
Construction Stage						
Air Pollution	Entire road and related facilities particularly sensitive areas as mentioned below:	Asphalt plants and batching plants to located at downwind & minimum distance to nearest dwelling of 500 meters and must be equipped with controlling devices such as Electrostatic Precipitator (EP), bughouse filters	Throughout construction	PKR 1800, 000/- For Monitoring Cost for other	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
	<p>Residential Areas near Shikarpur, Kashmore, Rojhan Rajanpur, Khanpur, Kandhkot, etc.</p> <p>Rural Health Centre near Khanpur and Rojhan</p> <p>Masjid Ali-ul-Murtaza at Kandhkot, Jamia Masjid Qadria near Kashmore and Noorani Masjid near Rajanpur, etc.</p>	<p>Generators to be equipped with emission controlling devices and well-maintained generator and machinery</p> <p>Material transport. Dumper trucks carrying earth fill, sand, gravels covered with tarpaulins or other suitable cover</p> <p>Speed limits of 20 km/ hour all kind of vehicles through administrative control and engineering control (signs, bumps, barriers etc.)</p> <p>Debagging of cement in a sheltered area</p> <p>Stockpiles management: Covering/ shading of stock piles and if needed water spraying especially at crusher sites</p> <p>Construction Site management: watering of dusty construction site and material handling routs and demolition work such as trimming activities by using breaker</p> <p>Clean Up: contractor will immediately clean up dusty material or mud left on or around the public road such as by tractor mounted vacuum cleaner</p>		measures included in contract		
Water Quality and Quantity	Construction sites adjacent to water bodies and water source for construction e.g. Nullah Crossing (Meeral), Begari Canal Crossing (Kandhkot), Nearby Water Pond (Kandhkot and	<p>Don't disturb the streams recharging the community water, or used for community</p> <p>Consult with residents to identify well or water source within 50 m project road and demarcation to avoid the damage by machinery</p> <p>To limit the spill of material into water bodies no construction material including soil, spoil, aggregates, chemicals or other material will be stored within 50 meter of the water body</p>	Throughout construction	<p>PKR 270,000/-</p> <p>For surface water quality</p> <p>Cost for other measures included in contract</p>	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
	Bakshapur), Pat Feeder Distributary Crossing (Kashmore), Pat Feeder Canal Crossing (Kashmore), Matwah Distributary Crossing near Rojhan and Kadra Canal Crossing Near Kot Mithan etc.					
Water Pollution Control	Construction camps and active sites especially near sensitive receptors mentioned in water quality and quantity section	<p>Wastewater from workshops: Wastewater effluent from contractor's workshop and equipment washing yards would be passed through gravel/ sand beds to remove oil/ grease contaminants before discharging it into natural streams;</p> <p>Sanitary wastewater: Sanitary wastewater should be treated through buried septic tank and the capacity of the septic tank should be three times than the generated effluent per day. Manholes onsite should be covered and sealed. Guidelines for sanitary wastewater from IFC/ World Bank may be consulted.</p> <p>Public Roads: around the site entrance and site hoardings should be kept clean and free of muddy water</p> <p>Road drainage: provision of retention pound with cascading to drain the road surface runoff.</p> <p>Water ponding at Batching Plants: Stored water for batching plants should be used or drained during shut of as this will cause water ponding leaving the</p>	Throughout construction	PKR 540,000/- For wastewater testing Cost for other measures included in contract	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		scum at the top serving as a habitat for mosquitoes and vectors. Canal Water: construction debris should not find its way in to canals and washing machinery with the canal water should be prohibited.				
Noise Control	Key noise receptor along the road alignment particularly sensitive areas as mentioned below: Residential Areas near Shikarpur, Kashmore, Rojhan Rajanpur, Khanpur, Kandhkot, etc. Rural Health Centre near Khanpur and Rojhan Masjid Ali-ul-Murtaza at Kandhkot, Jamia Masjid Qadria near Kashmore and Noorani Masjid near Rajanpur, etc.	Source Control: well-maintained machinery with exhaust system, enclosures for stationary equipment and operate generators, compressors with door closed, reduce speed limits, turning off or throttled down idle equipment, Timings: Adjust operation timings between 8 a.m. to 6 p.m. Notification: Provide advance warning to community on timings of noisy activities and strictly comply that GRM: establish the mechanism to handle the complaints from communities, maintain register for complaints on sites, and seek suggestions from community	Throughout construction	PKR 576,000/- For noise monitoring	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
Waste Management	Entire Road, camp sites, Workshops, Related facilities	<p>Waste Minimization: Procure the material which have less packaging and the quantity required, recycle and reuse of construction waste material as fill material, concrete meeting grading requirements for drainage layer etc. Good housekeeping practices.</p> <p>Storage and Containments: Provided containers in appropriate size and numbers for construction and hazardous waste</p> <p>Chemical& hazardous Waste: Proper storage and labelling according to hazardous substance rule 2003. Disposed of by licensed contractor, provision of drip trays for oil drum, clean up the spill immediately, store on hardened surface, proper storage of oil rags,</p> <p>Used Tires: Used tires to be sold out to licensed contractor to avoid becoming the habitat for mosquitoes,</p> <p>Spoil and inert Waste: Spoils and inert waste to be disposed of on approved site by CSC in accordance with aggregate. Spoil will not be disposed of to disturb vegetation, rehabilitate and restore the spoil disposal site with agreed plan</p> <p>Municipal Waste: provided the bins to worker for recycling of the MSW and the food waste should not be stored for more than two days and disposed of the nearest dumping site through TMA.</p> <p>Administration: Prohibit the burning of waste & spill from containers and ban the entry of scavengers</p>	Throughout construction	Included In construction cost	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
Storage of Chemicals and dangerous goods	Hazardous Material Storage Site	<p>Access control: Locking of hazardous material storage place and clear instruction on the door based on MSDS and applicable laws.</p> <p>Spill control: secondary containment for oil spillage (drip trays), provision of spill kit/ sand/ saw dust/ for absorbing spill</p> <p>Surface: Storage on hardened/ non permeable surfaces</p>	Throughout construction	Included In construction cost	Contractor	PIU/ CSC
Fire Prevention/ Emergency Preparedness	Active Sites, Workshops, Campsites and related facilities	<p>Fire Extinguishers: Placement and maintenance of fire extinguishers with trainings to use them</p> <p>Accident/ Incident Reporting: system should be in place and reviewed time to time for corrective & preventive actions.</p> <p>Escape Route: Escape route and gathering area should be mapped, displayed, demarcated and not blocked/ obstructed.</p> <p>Emergency Contact Detail: Contact detail for Fire department along with emergency services such as 1122, Edhi Ambulance services, bomb disposal team, police etc. with in-house emergency team should be displayed</p>	Throughout construction	Included In construction cost	Contractor	PIU/ CSC
Protection of Cultural and religious sites	Near the cultural and religious sites	<p>Access: Access for the religious site should not be disturbed due to construction activities as there are many mosques along the road and community should be consulted for extra measures during prayer timings.</p> <p>No listed or protected cultural heritage site is being affected; however, there are some in the vicinity, the access of the locals and visitors coming from</p>	Throughout construction	Included In construction cost	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		far should not be blocked.				
Resource Conservation		Water Conservation: through recycling for dust suppression, prevention of pipe leakages and wastages,	Throughout construction	Included In construction cost	Contractor	PIU/ CSC
Energy Conservation		Energy Conservation: adopting energy conservation best practices, shutting of diesel power plants and equipment while not in use, locating the raw material source to the minimum distance, use gas cylinder to avoid timber, control fuel spill and leakages through piping system, Raw material: Prevent the deterioration and wastage by covering, separation of different raw materials, and regular quantification by track record	Throughout construction	Included In construction cost	Contractor	PIU/ CSC
Occupational Health & Safety	Worksites, Batching plants & Asphalt Plants, Quarry Area, campsite, subcontractor campsite	Workplace Structure: campsites, workshops, semi-finished product area etc. should be structurally stable and to meet severe climatic conditions Lighting: workplace should be properly illuminated with lightening arrangement at place (Minimum Workplace illumination Intensity by IFC/ WB) Safe work Instruction: workplace safety instruction should be at place of work/ workstation according to nature of work Signboards: signboards must be at place for electrical devices, compressors material, emergency exit, pipe color coding, labels according to international standards Electrical Hazard: All electrical cords, cables and hand power tool free from fray or exposed cords and protected from traffic by shielding or	Throughout construction	Included In construction cost	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		<p>suspending above traffic areas. There should be approach zone established around or under high voltage power lines.</p> <p>Drinking and Potable Water: provision of clean drinking water to both direct and contractual labor at all sites in the form of dispensers or in coolers. Potable water must be available in good quantity and quality for all the workers</p> <p>Eating Area: Clean eating area should be available, with gas cylinders, stoves for both direct and contractual labor</p> <p>Lavatories & Showers: There should be sufficient lavatories and showers with reasonable quantity of water. Waste water must be discharged through septic tanks</p> <p>First Aid: provision of first aid kit and arrangements for medical practitioner and ambulance and emergency numbers displayed</p> <p>Air supply and temperature: fan/ cooler/ heaters should be available for all the works according to the weather conditions and nature of work</p> <p>Safe Access: safe access to workers for work and mean of egress in case of emergency and restricted access for trespassers</p> <p>Communication & Trainings: provide OHS training, visitor orientation, New task employee training, Area signage, labeling of equipment, ad communicate hazard codes</p> <p>Physical hazards: revolving shift of workers in case of repetitive motion/annual lifting, elimination of hazards due to working at height, slip & falls,</p>				

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		<p>struck by objects and moving machinery by using of scaffolding, full body harness for height more than 2-meter, warning taps and barricading</p> <p>Chemical hazards: oil/ chemical spill control and capping of contaminated land with at least 1-meter clean soil</p> <p>Biological hazards: Avoid the unhygienic conditions to fight with epidemic diseases such as dengue fever etc.</p> <p>PPEs: workers should have available and trained to use the PPEs for head protection, eye protection, face protection, body protection, feet protection, hand protection, based on nature of work. For welding/ hot work welder goggles/ full face eye shield must be provided with fire extinguisher at place</p> <p>Fuel Storage Area: Fuel storage area should be covered and tanks must be buried or placed on built frame</p>				
Community Prevention, Health and Safety	Active and abandoned site, campsite, Batching and Asphalt Plants	<p>Disease Control: Avoid water poundings creating habitat for mosquitoes breeding, safe measure against vector born/ communicable disease among workers and communities</p> <p>Access restriction: No trespassing and access restriction by combination of institutional and administration control by signage and fencing, locking of hazardous material, demarcating/ fencing of restricted area, avoid interaction of pedestrian and machinery, No grazing animals onsite</p> <p>Load on Infrastructure: avoid use of community road for use of heavy vehicles and repair the</p>	Throughout construction	Included In construction cost	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		<p>damage caused immediately, the use of sewerage system, electricity and gas should not put extra load on community such as load shedding and boiling of gutters</p> <p>Water quality and quantity: Don't disturb the quality and quantity of community water by over extraction and contamination of wells,</p> <p>Uncovered Openings and Abandoned Structures: Cover the openings and trenches creating fall hazards</p> <p>Traffic control: awareness and campaign against road related accidents, flagman, traffic diversion plan on print and live media and signage & illumination, don't leave partially demolished structures</p> <p>GRM: Effective GRM should be at place to resolve grievances of community</p> <p>Business loss: Avoid the business loss by provision of access to exiting gas stations and other commercial and industrial businesses.</p>				
Socioeconomic Issues		Avoid the incidence of conflicts of transitive workforce with community, damage to crops and community structures, cutting the links between communities. Hiring of locals for labors and short contracts such as for plantation, transportation of material etc. Avoid any activity causing access restriction and pay the judicial payments for leased area and restoration of the leased area to original shape during the demobilization.	Throughout construction	Included In construction cost	Contractor	PIU/ CSC
Climate Change		Effects of climate change: Pavement design and material selection taking in to account changes climate variable such as temperature, precipitation	Throughout construction	Included In construction cost	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		and soil moisture. Adequate drainage structures to be resistant to extreme flooding events Effects on Climate: Measures to reduce GHG emissions and fugitive dust. Controlling devices for asphalt and batching plants. avoid wastage of raw material, least material transport distance, green infra-structure including landscape, eye lands, trees				
Protection of Flora and Fauna		Tree Identification: label all the trees which need to be removed Good Practices: For each removed tree, compensatory trees need to be replanted taking in to account some trees would die during initial growing period; Existing nurseries along the road may be contacted for sapling; otherwise, nurseries may be developed near to alignment through local contractors; The community shall be consulted in each community for the type of trees and appropriate season; Sapling Aftercare: engage persons from the community to aftercare the sapling particularly in dry season. The plantation should be started during the construction- not all at the end of construction phase	Throughout construction	Included In construction cost	Contractor	PIU/ CSC
Ecological Displacement		Prevention of displacement of valuable flora from the compensatory land: The land given in compensation to acquired land should not be in area with natural vegetation. The land should be from already cleared off agriculture area.	Throughout construction	-	Contractor	PIU/ CSC
Traffic Management	Throughout construction site	Traffic Management Plan: A traffic diversion plan will be set out how the traffic on road and access to highway would be maintained with proper	Throughout construction	Included In construction cost	Contractor	PIU/ CSC

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		<p>signage. In case of diversions, the speed limits and signs should be mentioned well ahead to guide the road users resulting in smooth traffic flow</p> <p>Speed Limit: At construction the maximum allowable limit should not exceed than 20 km/hr.</p>				
Operation Phase						
Noise Levels & Air Pollution	<p>Main Entry Points/ Interchanges</p> <p>Near noise sensitive receptors as mentioned above in construction phase</p>	Emission standards: Vehicle with black smoke from exhaust should not allow to enter the road. Vehicle must meet the emission standard of EPA	During operation		NHA	NHA
Road Maintenance & Drainage	Throughout the alignment	<p>Drainage Management: Monitor and maintain drainage structures and ditches including culverts. Clean out culverts and side channels when they begin to fill with sediment and lose their effectiveness; Ensure oil and debris should not reach nearby water bodies by using screens, sediment traps, and oil sumps and retrofitting barriers</p> <p>Potholes and mud holes: Fill mud holes and potholes with good quality gravel; remove fallen trees and limbs obscuring roadways; and use water from settling basins and retention ponds for road maintenance.</p>	During operation		NHA	NHA

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
Accidents of hazardous material	Throughout the alignment	In case of any accidental spill, there should be a relevant department in NHA dealing with it in accordance with emergency plan; and A road administration department should be established after the completion of the project which will administrate the transport of hazardous substances.	During operation		NHA/Highway police	NHA
Use and maintenance of equipment	Throughout the alignment	Install concrete pads, drains, and oil/water pits in areas where vehicle and equipment maintenance and fueling will occur regularly along the highway	During operation		NHA /Highway police	NHA
Collusion with pedestrian & animals	Throughout the alignment	Collusion with pedestrians: Pedestrian bridges would be provided and barriers at medians would be provided in urban areas to restrict the pedestrian to come on the road Animal vehicle Collusions: Assigning the animal crossing areas and provision of speed reduction devices with warning signs	During operation		NHA	NHA
Road Safety	Throughout the alignment	Enforcement of speed limits, installation of speed guns and speed checking by motorway police with enforcement of penalties for the violators.	During operation		Highway Police	NHA
Embankment & ROW protection	Throughout the alignment	Road Inspection: regular inspection of road and ancillary structure Prevent plantation within 5 meters of the outer edge of the road shoulder and/ or within 5 meters of the base of slope Prevent the construction of any permanent or temporary structure within 10 meters of the outer edge of the unpaved shoulder and/or within 10 m of the base of any embankment	During operation		Maintenance department of NHA	NHA

Issue	Location	Mitigation Measure	Timings	Estimated Cost	Implemented by	Supervised/ Approved by
		Implement the NHA bylaws for permitting system to protect and manage land use within legal ROW (Regulatory framework and SOPs for preservation and commercial use of ROW 2004)				

8.7 Environmental Monitoring Requirements

304. The Environmental Mitigation and Monitoring Plan provides the framework for the implementation of the mitigating measures and monitoring during the preconstruction, construction and operation phases of the proposed project (**Table 8.4**) whereas **Table 8.5** gives estimate for monitoring of the environmental quality parameters during construction phases of the proposed project.

8.7.1 Pre-construction Ambient Environment Monitoring

305. Environmental Monitoring locations have been identified for Ambient Air, Noise and Water Quality monitoring. The criteria for selection of monitoring locations along with map showing environmental monitoring and sampling points are attached in Section 5.1.3. Environmental monitoring has been conducted in July, 2020 and results of ambient air, noise monitoring and water testing are provided as **Annex III**.

Table 8.4: Ambient Environment Baseline Sampling

Item	Sampling Parameter
Surface Water	Temperature, pH, TDS, BOD, COD, Phenols, Chloride, Copper, Lead, Manganese, Sulphate, Zinc, Silver, Boron, Barium, Iron
Air Quality	CO, NO _x , SO _x , PM ₁₀ ,
Noise	Equivalent Noise Levels in dB (A)
Drinking Water	Color, pH, Turbidity, Total Hardness, TDS, Antimony, Barium, Chloride, Fluoride, Nitrate, Nitrite, Odor & Taste, Arsenic, Total Coliforms, Fecal Coli forms (E.Coli).

Table 8.5: Environmental Monitoring Plan

Environmental Control	Location	Means of Monitoring	Frequency	Responsibility	
				Implementation	Monitoring
Preconstruction – Before Site Preparation					
Initial Community Meetings	Along the Highway & Ancillary sites areas	Method: Consultation & observations Parameters: Consult village leaders, communities, affected people and observe the requirement for signboards required for contract details, contacts of PIU and GRM details	Before site preparation and as required	Contractor	CSC PIU
CEMP by Contractor		Visual checks CSC Records	Before site preparation	Contractor	CSC PIU
Contractor coordinates with Utility Companies	Affected sites	NOCs, Affected communities Interviews	As required Before site preparation	Contractor	CSC PIU
Tree Removal		Labeling of trees to be uprooted- only necessary NOC if required	Before site preparation	Contractor	CSC PIU
Preconstruction – Baseline Monitoring (Project Specific)					
Air Quality	Key Sensitive receptors along the corridor	Method: establish baseline conditions by measuring criteria pollutants Duration: 24 hours continuous monitoring	Once before site Preparation	Contractor will hire an independent certified lab	PIU/ CSC
Water Quality and Quantity	500 meters upstream and 500 meters downstream of major water body crossings	Method: establish baseline conditions Parameters: Temperature, pH, TDS, BOD, COD, Phenols, Chloride, Copper, Lead, Manganese, Sulphate, Zinc, Silver, Boron, Barium, Iron	Once before site preparation	-do-	PIU/ CSC
Noise	Key Noise Sensitive Receptor	Method: Establish project specific baseline conditions at key Noise receptors inside and outside for equivalent noise levels dB (A). Duration: 24 hours continuous monitoring	Once before site Preparation	-do-	PIU/ CSC
Construction Stage – Impact Offset					
Community	Communities	Minutes	Every three	Contractor	PIU/ CSC

Environmental Control	Location	Means of Monitoring	Frequency	Responsibility	
				Implementation	Monitoring
Discussion			months		
Interview with affected people	Where required along the entire strip	Non-Compliance Notices (if any) to the Contractor by CSC after consultation	When required or quarterly	CSC	PIU
Site Preparation & Vegetation Clearance	Construction Corridor (All along the highway)	Visual inspection of loss of vegetation, soil erosion & instability, surface water pollution	Daily or Weekly when required	Contractor	PIU/CSC
Erosion Control	Side slopes of embankments and Stockpiles	Visual inspection of: Occurrence of erosion Drainage arrangements Landscaping & plantation Covered stockpile and dust cover on trucks Complaints log Interviews	At the end of filling activity	Contractor	PIU/CSC
Operation of Borrow and Quarry site	Barrow pits Quarry Area	Visual inspections of: Quarry sites/ borrow areas for change in landscape and creation of water ponds. Fertile layer conservation Photographs (area specified for borrow pits) Complaints and interview with nearby communities about blasting effects on buildings and movement of heavy machinery on public roads	Once before operation for photographs and then on monthly basis	Contractor	PIU/CSC
Material Supply	Material Supply Sites	Inspection of possession of: official approval or valid operating license of primary suppliers (asphalt, cement, quarry and borrow material) Haulage distance Recycling/ reuse	Before the agreement for supply of material is finalized.	Contractor	PIU/CSC
Storage and Handling of materials	Material storage yard/Work area and Construction camps	Visual Inspection of Covered storage facilities Iron bar/ cast Iron placement stands	Monthly	Contractor	PIU/CSC
Traffic Safety	Entire road, Haul roads	Visual inspection of: Signage	Weekly and as needed	Contractor	PIU/CSC

Environmental Control	Location	Means of Monitoring	Frequency	Responsibility	
				Implementation	Monitoring
		Safety barriers Flagmen Temporary bypasses Complaints log Accident records Interview			
Air Pollution Control	Active site near sensitive sites and settlements, Storage Yards Asphalt and Batching Plants	Air Quality Monitoring Mobile Lab Duration: 24 hours continuous monitoring Visual inspection of: Fugitive dust Open burning Sprinkling/ dust suppression techniques Truck covering Covered Stockpiles Visual inspection to ensure asphalt plant equipped with dust controlling devices and located >500 m from residential areas. Dark smoke Speed limits Stockpiles covered	Quarterly	Contractor	PIU/CSC
Noise Control	Near the sensitive sites and settlements	Noise meters Duration: 24 hours continuous monitoring	Quarterly	Contractor	PIU/CSC
	Construction sites	Visual inspection of conditions of equipment, Enclosures Generators and compressors operate with door closed	Weekly	Contractor	PIU/CSC
Wastewater Pollution Control	Active site & Campsite	Visual inspection of Septic tanks and untreated discharge of wastewater to storm water (color, litter, foam) Septic Tank testing (BOD, COD, N, P, Oil & Grease) Kitchen water	Weekly	Contractor	PIU/CSC

Environmental Control	Location	Means of Monitoring	Frequency	Responsibility	
				Implementation	Monitoring
		Washing bays Silt removal facilities Covering of manholes Stagnant water at Batching plants & Asphalt plant			
Surface Water Quality	500 meters upstream and 500 meters downstream of major Water body crossings	Water quality monitoring Parameters: TSS, Temperature, BOD, COD, oil & grease, Turbidity, Lead, Zn, Iron, Nitrate, Phosphate	Quarterly during bridge construction	Contractor	PIU/CSC
Drainage & Sedimentations	Entire road, culverts & drains	Visual inspection	Monthly After precipitation	Contractor	PIU/CSC
Fire Prevention	Active site and camp sites	Visual inspection of Fire extinguishers Escape routes Marked assembly area Displaying of emergency contact detail	Weekly and as required	Contractor	PIU/CSC
Climate Change Resilience	Entire Project	Inspection of: Energy conservation Techniques Emission controlling devices Wastage of raw material Leakages of oil, water, fuel Efficient use of machinery Material resistant to extreme weather Least material transport distance Drainage/ high Risk flooding areas, ponds, wetlands Green Infrastructure; eye lands, Trees, landscape,	Monthly	Contractor	PIU/CSC
Resource Conservation	Active site and campsite workshop, filling station	Visual inspection of: Equipment not in use shut off Oil, fuel, water leakages Gas cylinders to avoid timber Wastage of raw materials Recycling/ Reuse	Monthly	Contractor	PIU/CSC
Storage of Chemicals and	Filling area Workshops	Visual inspection of: Storage with License conditions	Weekly or as required	Contractor	PIU/CSC

Environmental Control	Location	Means of Monitoring	Frequency	Responsibility	
				Implementation	Monitoring
		Workers behavior			
Community safety	Entire Project Area Barrow pits Quarry Areas Asphalt & batching Plants	Complaints register Traffic related accidents record Traffic Diversions Deterioration of existing roads Water ponding Access restriction to camps Uncovered openings/ open trenches Abandoned structures/ Partially demolished Complaints related to vector born disease Interviews with workers & locals	Monthly	Contractor	PIU/CSC
Protection of Fauna & Flora	In the project area	Visual inspection of: Sheep and grazing animals in campsite Use of timber Crops along corridor Animal Corridors Plantation work	Daily	Contractor	PIU/CSC
Cultural and archeological sites	At work sites or graveyards (if shifting required)	Visual inspection & records	Daily, weekly as required	Contractor	PIU/CSC
Socio-economic Issues	Entire project Area	Visual inspection of existing roads deterioration Utilities related complaints Record of conflict incidents Damage to crops and structures Access restriction Leased areas	Monthly	Contractor	PIU/CSC
Training	Entire Project	Training records Interviews with workers Topics: OHS and Emergency Response, Community information	6-Monthly	Contractor	PIU/ CSC
Reinstatement of work-related sites, demobilization,		Visual inspection of: Clear sites Construction waste disposal	Once before sign off	Contractor	PIU/ CSC

Environmental Control	Location	Means of Monitoring	Frequency	Responsibility	
				Implementation	Monitoring
Works Contract Signoff & Handover		Site safety Drainage Landscaping Comparing ancillary site area with photographs taken before start of work			

8.8 Environmental Management Plan Indicative Cost

306. The cost for compliance of EMP and its operation is estimated in the **Table 8.6**.

Table 8.6: Environmental Management Plan Indicative Cost

Item	Cost USD	Remarks
Mitigation Cost		
Environmental Monitoring		
Environmental Monitoring (air, noise and water for baseline) at key points	5,000	Once for air, noise and water for baseline
Environmental Monitoring (air, noise and water during construction stage) at key points	60,000	Quarterly for air, noise and water for 3 years
Training Arrangements (Training will be carried out by CSC)	50,000	Contractor will pay for the Arrangements
Hiring of Staff		
Contractor Environment Specialist	195,000	39 Person months
CSC Environment Specialists (1 International + 3 National)	(130,000 +189000) 319,000	4 person months for international + 26 person months for 3 position ²²
PIU Environment Staff	156,000	39-man months
PIU Grievance Redress Staff	39,000	39-man months
Vehicles	100,000	Lumpsum
Fire extinguishers	4,500	Lumpsum
PPEs	700,000	Lumpsum
Drinking water facilities	5,000	Lumpsum
First Aid	300,000	Lumpsum
Tarpaulin	10,000	Lumpsum
Borrow pits	-	Included in project cost
Disposal area	-	Included in project cost
Subtotal	1,943,500	
Contingency (10 % of total cost)	194,350	
Total Cost	2,137,850	
Note: Environmental Mitigation Cost of PKR 300 M (2.14 M) is included in PC-1		

²²TOR for consultancy services (T-II) Projects

SECTION 9 PUBLIC PARTICIPATION, CONSULTATION AND INFORMATION DISCLOSURE

9.1 Stakeholder Identification and Analysis

307. The stakeholders of a project can vary depending on the details of project. During the field survey, significant efforts were made to identify different stakeholders, both project-affected parties and other interested parties. They included local communities / general public, national and local authorities, neighboring and non-governmental organizations and vulnerable community (women, poor & indigenous) etc. Based on identification, all those stakeholders (individuals & groups) had different concerns and priorities about project impacts, mitigation mechanisms and benefits, and also required different, or separate, forms of engagement.

9.2 Methods Adopted for Stakeholder Engagement

308. The following methods were applied for engagement with project stakeholders in order to capture their concerns, potential risks and priorities regarding project implementation.

- **Interview Survey**
(A structured set of questions from representative sample of PAPs)
- **General / Public Meetings**
(Discussion with community, religious leaders, local government representatives, civil society representatives, politicians and teachers etc.)
- **Rapid Participatory Appraisal**
(Site visit by a multidisciplinary team consisting environmental engineer, environmental scientist, social scientist, ecologist and local community representatives to gather information regarding project site)
- **On-Site Meetings**
(Other interested parties including project proponent or contractor)

9.3 Stakeholder's Concerns and Priorities

309. The first round of stakeholder consultations was conducted in 2018. Identified stakeholders were consulted and their concerns were documented with pictures. Meetings were held with project-interested parties including project staff, government officials, and local communities to predict the nature and scale of risks, challenges and perceived impacts of project. Table 9.1 describes the details of general / public meetings and series of focused group discussions held with different categories of the stakeholders at various locations along with their concerns & priorities raised about proposed project. The pictorial evidences for the consultation is shown in **Plate 9.1**.

Table 9.1: Public Involvement Process

Sr. No.	Date	Venue	Stakeholder Category	No of Participants	Concerns & Comments Raised	Response to Comments
01	17-09-2018	Dhakan Bangla Village	Local & Farming Community	09	<p>It is a good project and it would decrease traffic congestion and facilitate the local inhabitants to cone with other areas.</p> <p>Requested for technical and non-technical employment opportunities to the locals</p> <p>Community representatives were afraid that their businesses may be affected by the proposed development during construction</p> <p>Community representatives were afraid that their existing livelihood may be affected during construction</p>	<p>Contractor will be advised to hire local force on preference basis during construction.</p> <p>Construction activity may be restricted during peak hours of business activity.</p>
02	17-09-2018	Karampur City	Fruit Seller, Shopkeepers , Residents	12	<p>Travelling time to approach other areas will be minimized due to widening of road</p> <p>After its completion, suitable place to be provided for the local inhabitants who are involved in running business of hotels and shops</p> <p>Ensure the other possible suitable locations to run business along the Indus Highway</p>	<p>Compensation to be paid in a timely manner to manage the business and for relocation, if requires</p>

03	18-09-2018	Ghoospur Village	Farmers, laborer	11	<p>Privacy of local people will be disturbed due to construction work</p> <p>Impacts on health due to exposure of noise and dust particles</p> <p>Livelihood will be disturbed, in case of loss of agriculture land and businesses around the Indus highway</p> <p>Affected structures to be compensated prior to the construction activities</p> <p>Alternative routes or designed to be changed at areas where structures and mosques are falling within the dualized sections.</p>	<p>Project site will be fenced with corrugated iron sheets/ temporary noise barriers to minimize the level of noise and dust near the mosques.</p> <p>Construction machinery will be parked in adequate locations away from the sensitive areas to minimize the impacts related to the noise.</p> <p>Prayer timings would be consulted with the communities</p> <p>Efforts would be made to avoid graveyards, shrines, and religious or cultural sites if any close to alignment</p>
04	18-09-2018	Shikarpur City	Local Community	15	<p>Farmers will have better and rapid access for transportation of their agricultural products</p> <p>Existing cropping patterns will be disturbed due to intervention of construction machinery and labors</p> <p>Orchard growing areas adjacent to the existing alignment will be</p>	<p>There will be provision of fair replacement cost if any of land or land based asset will be disturbed owing to project implementation.</p> <p>Contractor will be responsible for not interrupting the water supply lines of communities during construction activity.</p>

05	20-9-2018	Karachi Office- EPA	Director, EPA	02	<p>affected, which is currently the only source of income of inhabitants</p> <p>Contractors should manage to facilitate the water supply lines during construction.</p> <p>Emphasis to ensure EMP implementation during the entire life cycle of the proposed project, while ensuring that they comply with all relevant legislative requirements applicable on the proposed project.</p> <p>Technical and non-technical employment opportunities for the locals to be reserved.</p>	<p>Contractor will be responsible to comply the EMP implementation under the contract agreement.</p>
----	-----------	---------------------------	------------------	----	--	--



Plate 9.1: Public involvement Process

310. A second round of consultations was planned for January 2020. However, due to the current lock down situation due to the Pandemic (Covid-19), following the Governments directives and SOPs it is not possible to personally visit the stakeholders and conduct consultation meetings. Therefore, different stakeholders

have been contacted via letters to conduct consultations keeping social distancing through phone calls, conference calls, skype call utilizing the e-media. The response from these organizations is given in **Table 9.2**. A sample letter is attached as **Annex VII**.

311. List of departments / NGOs to which letters are dispatched and contacted for this purpose is provided below:

- District Office Environment, Rajanpur
- Forest Department, Sindh
- Forest, Wildlife & Fisheries Department, Punjab
- Agriculture Department, Punjab
- Social Welfare and Bait-ul-Maal, Punjab
- District Office, Social Welfare & Baitul Maal, Rajanpur
- AL-Noor Development Social Welfare Association-ANDSWA
- Idara-e-Taleem-o-Aagahi (ITA), Shikarpur Office
- SRSO Unit Office, Shikarpur
- Kainaat Development Association [KDA], Kandhkot
- Tameer Development Organization (TDO), Kandhkot, Sindh
- RDPI-Rural Development Policy Institute Rajanpur
- Sayya,Kotla Naseer, Rojhan
- Punjab Goods and Transport Association
- Karachi Goods Transport Association

Table 9.2: Departmental Consultation

Sr. No.	Department	Concerns/Observations	Response
1.	Environmental Protection Department Mr. Arif Hussain (Field Assistant) Contact No. 0333-6762527	<p>The official appreciated the efforts of IEE team for stakeholder consultations even in this COVID-19 pandemic scenario.</p> <p>He also praised the efforts of Govt. for dualization of the N-55 road section because road dualization will reduce the accident risks in the area.</p> <p>Road should be designed by considering flood discharge in the area so that road would not be damaged in flood seasons.</p> <p>Proper sprinkling should be done during construction phase of the project.</p> <p>He insisted the team to provide necessary data and information regarding the area and its surroundings.</p>	<p>All concerns and suggestions are noted and incorporated in report.</p>
2.	Irrigation Department Mr. Ghulam Akbar	<p>The official of Irrigation Department acknowledged the process of consultation with the respective stakeholders to incorporate their concerns and feedback in the report.</p>	<p>All concerns and suggestions are noted and</p>

Sr. No.	Department	Concerns/Observations	Response
	(Sub Engineer) Contact No. 0334-8180300	He was also of the view that irrigation structures need to be extended at canal crossings for dualization of the N-55 road section. Diversions should be established by considering flood flows in the area.	incorporated in report.
3.	Idara –e- Taleem O Aagahi Jalaldin Jamali (District Coordinator) Contact No. 03313474940	He also praised the efforts of Govt. for dualization of the N-55 road section and acknowledged that project is really needed in the area. Due to poor road condition and over speeding lot of accidents are observed in the area. Hence, animal crossings/cattle creep must be provided Plantation must be done on both sides of Road.	All concerns and suggestions are noted and incorporated in report.
4.	Kainat Development Association Ahmed Buksh Channa (CEO) Contact No. 0333734428 0722572186	He appreciated the project and stakeholder consultations and indicated that the project is really needed in the area. Numerous accidents are observed which not only results in loss of precious lives but also leave socio economic implications for the grievd members of family. Thus, the road needs to be dualized with proper crossings for both humans and animals The material used shall be of good quality as previous structures are easily damaged/not well maintained As a social activist he indicated that the project is a dire need and demand of people of Kashmore and Shikarpur. Moreover, it will help improve socioeconomic conditions of the area.	All concerns and suggestions are noted and incorporated in report.
5.	Karachi Goods Transport Association Ghulam Muhammad Afridi	He indicated that traffic issues are really serious in the area. In addition to road accidents, theft activities are also faced along the road.	All concerns and suggestions are noted

Sr. No.	Department	Concerns/Observations	Response
	General Secretary Contact No. 03003499322	Efforts shall be made to control theft activities	and incorporated in report.
6.	SAYYA Micro Finance Company Atiq Ur Rehman (Programme Manager) Contact No. 03326265980	Road side safety for the different hazards shall be considered. e.g: flash floods Green belts and plantation shall be considered on road sides	All concerns and suggestions are noted and incorporated in report.
7.	Sindh Forest and Wild Life Department (Divisional Forest officer) Contact No. 03332688310	If the proposed road passes through any reserved forest, It must be notified to the department for the purpose of transportation/road. If trees are damaged due to project. Compensatory plantation must be carried out.	The area does not pass from reserve forest area.
8.	Punjab Fisheries Department Muhammad Raza (AD) Contact No. 03336445202	He appreciated the project and affirmed that no major fisheries assets will be disturbed.	-
9.	Sindh Rural Support Organisation Dr. Shahid Ahmed Lakh (District Manager) Contact No. 03023129198	It is good project providing easy access to the public especially the commuters of 3 the districts. It will also reduce the travelling time. Kashmore bypass is the dire need of the area. Plantation shall be done on both sides of the road Overhead bridges shall be provided where road crosses the big cities.	All concerns and suggestions are noted and incorporated in report.
10.	Social Welfare and Bait ul Mal, Rajanpur Tehmina Dilshad	Plantation and green belts is very necessary	All concerns and suggestions

Sr. No.	Department	Concerns/Observations	Response
	(Deputy Director) Contact No. 03331615996	Crossings for hill torrents must be considered	are noted and incorporated in report.
11.	Tameer Development Organisation Nazir Ahmed Somroo 03003297884	Judicial compensation to the affected people shall be granted. The project will benefit the locals and uplift the socioeconomic status of the area.	All concerns and suggestions are noted and incorporated in report.
12.	Al Noor Development Social Welfare Asif Ali Somroo (President) Contact No. 03003106602	Several accidents are observed on the road; hence the project is need of the area. The project must be implemented as soon as possible	All concerns and suggestions are noted and incorporated in report.

Note: Response from some departments are not received yet. They will be included in the final IEE.

9.4 Information Disclosure

312. In line with ADB's Access to Information Policy (AIP) relevant information about social and environmental safeguard issues will be made available in a timely manner, in an accessible place, and in a form and language(s) understandable to affected people and to other stakeholders, including the general public, so they can provide meaningful inputs into project design and implementation.
313. Initial Environmental Examinations will be posted on ADB's website after approval and semiannual EMRs will be posted after approval every six (6) months. It will also be posted on NHAs website.
314. The IEE Report will be accessible to interested parties on request and the report will be available in the national library. In addition to it, brochures describing project information and its environmental impacts and mitigation measures in local language will be available at the project's site office and district administration offices where they are easily accessible to the local population.

9.5 Grievance Redress Mechanism (GRM)

315. The purpose of the GRM is to receive, review and resolve grievances from people and thereby resolve the community concerns raised during execution of project works. The GRM will remain intact throughout project implementation period to address the community concerns and issues arising during execution of project works.
316. The formal GRM proposed and provided for this project has a three-tiered structure including: first at local/village level set-up through community involvement; second at PIU level where a formal GRC is established and operational and third at NHA

(PMU/EALS) level. This will enable to resolve simpler and less complex grievances at local and project level by mobilizing local recourse and provide a higher-level review system to look into and address more difficult and complex issues that are not resolved at the PIU or local level. To ensure that all geographic reaches and relevant administrative units involved in the project are covered under the GRM, it will include (i) first level of GRM consisting of the Displaced Person Committees (DPCs) as a grievance redress focal points for each affected village; and (ii) a project based grievance redress committee (GRC) at PIU level and the iii) the PMU/ELAS level grievance redress focal points. The functions and responsibilities for each level of GRM are explained below.

9.5.1 First Level of GRM

317. The first level of grievance redress system includes the village level displaced person committee (DPC) selected and nominated by the displaced person from each affected village/settlement located along the project road alignment. The DPC will be presided by its president who will be selected by the committee members nominated by the displaced persons. These DPCs will be a formal node for coordination and communication with the project execution authorities and are required to act as local node for recording and redress of grievances as per their local customs and practices. The project LAR units and the technical staff will maintain a close liaison with the DPCs to guide and assist them in recording and resolution of grievances as per provision of this LARP/EMP. In this regards, the Environmental specialist/resettlement specialist and social mobilizers will closely coordinate and work together with the DPC members and the local community to ensure grievances are recorded, investigated and discussed during DPC's meetings and guide them to explore and recommend remedial measures at their level in accordance with provisions of the resettlement plan. They will also liaise with the counterpart engineering staff, and contractors to ensure implementation of the DPC's recommendations and/or raising the complaint to sub-project GRC for review and redress if the issues are not resolved at DPC level.

9.5.2 Second Level of GRM

318. If the grievance is not resolved at village DPC level, it shall be raised to formal grievance redress mechanism which is first level of GRM. A formal complaint will be tendered with the Project GRC by the aggrieved persons or through the social mobilizers. A complaint register will be maintained by the GRC through DD/AD (land management, implementation and social) to record the complaints received covering complaint receipt date, name and address of the complainant, gist of complaint, gist of field report, decision of GRC with its communication date to the DPs and decision implementation status or elevating the complaint to next level of GRM in case of disagreement by the aggrieved Persons.
319. Once the complaint is submitted with the Project GRC, it shall record it in complaint register and send acknowledgement to the affected person without delay; and initiate the process of investigation within 7 days through its technical and resettlement/environment field teams. After receipt of directions of GRC, the field teams including resettlement/environment specialist and Land Staff will coordinate with complainant and complete its investigation of facts in consultation with aggrieved person, DPC representatives and local community and submit its fact-finding report and recommendations to the GRC within 15 days from the receipt of complaint. Upon receipt of the fact finding report, the GRC will summon and hear the aggrieved person and decide the complaint in light of EMP and communicate its decision to the PMU and aggrieved persons within next 15 days. On an overall basis the GRC will decide the grievances within 30 days of receipt of complaint in GRC. If the final

decision made by GRC is not acceptable to the DPs they may advise GRC for elevation of their grievance to next higher level of GRM. However, the project based GRM will not bar aggrieved persons to avail remedies available under the court of law and they will be at liberty to approach the court of law as and when they wish to do so.

9.5.3 Third Level of GRM

320. In case the aggrieved person is unsatisfied with GRC decision, he himself or through GRC can elevate his complaint to third level of GRM i.e. at PMU/EALS in NHA HQ, within 7 days after GRC decision on complaint. Once the complaint is received at PMU/EALS along with GRC proceedings, it will be registered and the complainant will be informed accordingly. The GRC record and complainants' claim will be scrutinized and the complainant will be advised to produce any additional record in favour of his claim. After thorough review and scrutiny of the available record PMU/EALS can visit the field to meet the complainant, collect additional information and evidence if required. Once the investigations are completed the PMU/EALS shall get its recommendations approved by Member (aided projects) and forward them to the Project Director and the complainant accordingly within 30 days of receipt of the complaint. Moreover, the aggrieved person/party (s) is free to go to the Court of Law as and when desired.

9.5.4 Constitution and Function of the GRC

321. The project based GRC will be a public forum for raising concerns and invoking conflict resolution system available within the project for addressing LAR related and other social or environmental issues adequately. The GRCs will continue to function, for the benefit of the DPs/aggrieved persons, during and after implementation of LARP/EMP till completion of the project.
322. The GRC will be headed by the Project Director, including DD/AD (land) or AD (environment) as member and focal person for social and environmental grievances, the Land Acquisition Collector and resettlement /environment Specialist mobilized through supervisions consultants as members. Besides, the GRC may also include one representative from District Revenue Office and Village level Displaced Persons Committees (DPCs).
323. For redress of grievances, the GRC will meet at least once in a month. For the purpose of social safeguards, the GRC will review grievances involving all resettlement issues including, compensation, relocation, and other assistance. GRC will perform following functions:
- Record grievances; categorize and acknowledge the complainants about receipt of grievances; investigate the issue and summon aggrieved persons/parties to produce the evidence and explain their claims; and resolve the grievances within stipulated time frame preferably in 30 days;
 - Communicate its decisions and recommendations on all resolved disputes to Project executors and the aggrieved persons for implementation and follow the implementation progress;
 - Forward the un-resolved cases, at its own or as required by the unsatisfied aggrieved parties, to PMU (second level of GRM) within an appropriate time frame with reasons recorded and its recommendations for review and resolution at second level of GRM;
 - Develop an information dissemination system and acknowledge the aggrieved parties about the development regarding their grievance and decision of PIU and PMU level;

- Maintain a complaint register accessible to the all stakeholders with brief information about complaints and GRC decision with status report; and
- Maintain complete record of all complaints received by the GRC with actions taken.

324. The flow chart of the proposed redress mechanism is shown below in **Figure 9.2**.




Figure 9.2: Flow Chart of the Proposed Grievance Redress Mechanism

9.5.5 Type of Grievances to be expected

325. The following are some of the environmental issues could be subject for grievance from the affected people, concerned public and NGOs.

- Dust, noise and air pollution during construction activities

- Nuisance
- Intensive schedule of construction activities
- Inappropriate timing of construction vehicle flow
- Traffic Movement
- Water Pollution
- Waste disposal
- Disturbances to flora and fauna
- Health and safety
- Criminal activities
- Failure to comply with standards or legal obligations

SECTION 10 CONCLUSION

326. Conclusively, the proposed development will enhance the trade activities on regional basis and provide smooth and safe road corridor linking with the Central Asian States. This will involve some potential adverse environmental impacts of low to moderate level, which are mostly related to construction stages of the Project and are however manageable by properly implementing the EMP and meaning full and timely consultation with the community. No long-term and significant adverse environmental impacts are however envisaged for the operation stage of the Project.