

**INTEGRATED SAFEGUARDS DATA SHEET
APPRAISAL STAGE**

Date ISDS Prepared/Updated: 04/26/2016

I. BASIC INFORMATION

Report No.: AC7183

Country:	Sierra Leone	Project ID:	P153805			
Project Name:	Western Area Power Generation Project					
Task Team Leaders:	Carol Litwin / Katharine Baragona					
Estimated Appraisal Date:	May 23, 2016	Estimated Board Date:	June 28, 2016			
Managing Unit:	GEE07	Lending Instrument:	Partial Risk Guarantee			
Sector:	Energy					
Theme:	Infrastructure Services for Private Sector Development (100 %)					
Is this project processed under OP 8.50 (Emergency Recovery) or OP 8.00 (Rapid Response to Crises and Emergencies)			Yes [] No [X]			
Project Financing Data (in USD million)						
Total Project Cost :	US\$133.9 million	Total Bank Financing:	Up to US\$40 million equivalent IDA Guarantee)			
Total Cofinancing:		Financing Gap:				
Financing sources						
	Project Cost	US\$ Millions	%	Financing Plan	US\$ Millions	%
	EPC	68.5	51%	Equity	3.0	2%
	Contingencies	5.1	4%	Shareholder Loan	30.5	23%
	Development Costs	25.5	19%			
	Owner's Costs	4.6	3%	Debt (from IFIs)	100.4	75%
	O&M Mobilization	1.2	1%			
	Financing Costs	10.1	8%			
	Reserve Accounts	18.9	14%			
	Total	133.9	100%	Total	133.9	100%
Environmental Category:	B - Partial Assessment					
Is this a transferred project?	Yes []		No [X]			
Is this a repeater project?	Simple [X]		Repeater []			

A. Project Objectives

The Project Development Objective is to increase the power generated by independent power producers (IPPs) and mobilize private capital.

The direct beneficiaries of the Project are: (i) EDSA, who will on-sell electricity received under the Project and benefit from increased revenues through those sales; and (ii) the private sponsors and lenders, who will indirectly benefit from the combined WBG support for the Project.

The indirect beneficiaries of the Project are: (i) electricity consumers in the Freetown Capital Western Area, who will see improved reliability and increased availability of electricity services; and (ii) the GoSL, who will benefit from reduced imports of expensive diesel through the replacement of inefficient generation and self-generation by an efficient heavy fuel oil (HFO) thermal plant. The proposed operation will result in a net reduction of greenhouse gas emissions (GHG) by displacing less efficient fossil-fueled thermal capacity and other residential fuels such as kerosene.

The PDO indicators are:

- (a) Amount of electricity generated by the project (MWh/year);
- (b) Private sector capital mobilized (amount, US\$); and
- (c) Indirect project beneficiaries of which female (number/percentage)

B. Project Description

The Western Area Power Generation Project (the Project) is responding to an urgent need of generation capacity in Sierra Leone and is the most advanced power project currently under development in the country. The combined World Bank Group (WBG) instruments will leverage financing for the development of the proposed Project comprising a 57 MW thermal power plant, which will significantly reduce the supply-demand deficit in the Freetown Capital Western Area. Successful commissioning of the Project will improve the reliability and availability of electricity services in the Freetown Capital Western Area. The proposed IDA Guarantee will leverage US\$134 million in investments into the power sector in Sierra Leone, and serve as an important signal for investment opportunities at a time when the country is in a fragile recovery from Ebola Virus disease.

The Project comprises the development, financing, construction and operation by the Copperbelt Energy Corporation (CEC) Africa Sierra Leone Generation Limited (CECA SL) of a green-field thermal power plant running on Heavy Fuel Oil (HFO) on a build-own-operate-transfer (BOOT) basis. CECA SL is the Project Company established in Sierra Leone by private sponsors comprising CEC Africa Investments Ltd (50.1 percent equity) and Tempus Constant Qualitas Power Ltd (TCQ) (49.9 percent equity).

The Project Company is responsible for the implementation and operations of the Project under a 20-year Power Purchase Agreement (PPA). While the PPA provides provisions for the possibility of expanding the capacity of the Project up to 128 MW at a later stage, the proposed WBG support is limited to the initial phase of 57 MW.

The power plant will be located at the Kissy Industrial site to the east of Freetown and serve consumers in the Freetown Capital Western Area. The land at the Kissy Industrial site, which is

owned by the GoSL, is leased to the Project Company under a plant site lease agreement signed in March 2015 with a tenor of 26 years. The Project comprises:

- (a) The installation of six reciprocating Wärstilä engines (type Wärstilä W20V32) using HFO, each rated at 9.5 MW nominal output;
- (b) HFO storage tanks and water treatment facilities at the Kissy site;
- (c) A new 33 kV indoor substation at the Kissy site;
- (d) A 8 km reinforcement of the 33 kV transmission from Blackhall road to the Wellington substation to enhance evacuation capacity from the generation facility;
- (e) Installation of additional 33/11Kv transformers at the Blackhall road, Ropotee, and Wellington substations; and
- (f) Construction of an approximately 1.3 km fuel pipeline from a new jetty for the landing of the HFO to the Kissy site. The jetty is operated as a joint venture between GoSL and Addax.

Construction of the Project will be undertaken under a turn-key Engineering, Procurement, and Construction (EPC) contract and the commercial operation date is expected 18 months after the start of construction. Wärstilä, the main equipment supplier with a proven track-record, has been awarded the EPC contract and a 15-year operation and maintenance (O&M) contract for the Project (under negotiation).

Fuel costs are a pass-through under the PPA, and the GoSL has selected BB Energy as the fuel supplier. The Fuel Supply Agreement (FSA) will be entered into by the Project Company and BB Energy. The initial FSA term is expected to be seven years. Thereafter, the Project Company, with agreement from GoSL, can elect to extend the FSA or undertake a new tendering process. Fuel for the Project will be transported by a 1.3 km pipeline from the landing jetty to the project site, which will be constructed under the Project. The land lease and right-of-way agreements between the GoSL and the Project Company are being negotiated.

The GoSL has committed to implementing a number of measures to improve the performance of the power sector. The measures are designed to improve transparency and predictability of cash flows in the sector and to reduce subsidy requirements from the fiscal budget. Implementation of these measures will help EDSA, as the off-taker, meet the payment obligations under the PPA for the Project. The measures are outlined in the GoSL (draft) Policy Letter to IDA

The proposed Project will be supported by the WBG through an IDA Guarantee, IFC Investment Loan, and a MIGA Guarantee. It is proposed that IDA provide a payment guarantee of up to US\$40 million, to support certain payment security obligations of EDSA and the GoSL under the PPA. The proposed IDA Guarantee is designed to mitigate the low creditworthiness and lack of timely payment track-record risks of the newly established state-owned power off-taker, EDSA, as well as the risk of non-performance by GoSL of its joint and several contractual obligations, as the co-signer, under the PPA. IFC will extend up to US\$30 million A Loan, and also serves as the lead arranger to help mobilize up to US\$70 million of additional senior debt from other DFIs to the Project. MIGA would provide a guarantee of up to US\$60 million covering equity, the shareholder loan, and retained earnings against the risk of Transfer Restriction, Expropriation, War and Civil Disturbance, and Breach of Contract.

C. Project Location and Salient Physical Characteristics Relevant to the Analysis of Environmental and Social Risks and Impacts (if known):

The Project will be located nearly 4 km east from the center of Freetown, about 500 meters south of the sea, on existing industrial land with refinery tank farm. The Project site is in a brownfield industrial/commercial area within an urban location. Land for the project site is owned by the GoSL and is leased to the Project Company under the Plant Site Lease signed in March 2015, with a tenor of 26 years.

Despite the industrial and commercial land use zoning, a number of residential and educational receptors (formal and informal residential dwellings including two shanty areas, and a few schools, including an Islamic compound) are located in the Project's area of influence. The key environmental and social risks and impacts therefore include air quality, noise, occupational health and safety, traffic management, hazardous material and waste management, fuel transport, economic displacement of a small number of artisanal farmers, and community health and safety. The zone of impact is restricted to the Project site itself.

The Sierra Leone River Estuary Ramsar site is designated for its mangrove wetlands and bird interest. The site extends to include a large portion of the coast line east of the Kissy Industrial site, where the Project will be located, and the shorelines around Tagrin Bay and the Bunce River. Aberdeen Creek is located approximately 9 km west of the proposed site. The Western Area Peninsular National Park (WAPNP) is an area of equatorial rainforest located approximately 2 km south-west of the project site at its nearest point. The forest is degraded despite its status, with higher density forest at 6 km of the site. CECA SL has addressed the potential impacts on the Ramsar site by avoiding the need for abstraction and discharge of cooling water by use of air cooling and will address potential risks associated with accidental spillage of oil through robust spill prevention measures and liaison with the developers and operators of the Addax Petro jetty as part of the environmental, social, health and safety management policies and procedures for the project.

The key environmental and social (E&S) risks and impacts identified and assessed in the Environmental, Social and Health Impact Assessment (ESHIA) include potential impacts on (i) ambient air quality during construction and operations, (ii) noise generated by the power plant construction and operations, (iii) community health and safety associated with construction traffic and conditions of the access roads, (iv) economic displacement of a small number of artisanal farmers currently utilizing the site for subsistence farming, (v) soil and groundwater quality due to fuel spills or inadequate waste management, (vi) community water supply due to water abstraction for plant operations, and (vii) emergency conditions, particularly due to fire risk from fuel stored on site, pipeline ruptures and accidental spills. Due to the lack of urban planning, the company will engage with the relevant local authorities to identify and communicate risks associated with potential future informal settlements around the project. Risks and impacts identified and relevant mitigation and management measures are described in Environmental, Social and Health Impact Assessment (ESHIA).

D. Borrower's Institutional Capacity

The institutional capacity of CEC Africa SL with regard to Safety, Health and Environmental (SHE) aspects is not adequate at present, but will be strengthened before project implementation

starts. The mother company of CECA SL has considerable experience in SHE. The SHE aspects will be implemented by the EPC Contractor and the plant Operator.

The Project Company will prepare and implement a Health, Safety, Environment and Social Management System (HSES MS). The HSES MS will be designed based on international standards such as ISO 14001 Environmental Management System and OHSAS 18001 Occupational Health and Safety Management, and be compliant with the requirement of the financiers, including World Bank and IFC *Performance Standards*.

Project-specific detailed E&S management plans and programs will be developed in accordance with the World Bank, IFC and MIGA Performance Standards. The management plans will be incorporated into the HSES MS. The Project Company will require that the EPC and O&M contractor develops their own specific implementation plans demonstrating how they intend to comply with project requirements. All contractor plans will be reviewed and approved by the Project Company. The EPC and O&M contractor will be responsible to ensure that any sub-contractors will comply with the relevant health, safety, environment, and social (HSES) requirements, and its compliance will be monitored by the Project Company.

The Project Company will employ a full time HSES manager along with two assistants, and a social and community liaison officer. They will be responsible to develop and implement CECA SL's HSES Management System and other relevant programs and plans, and to review and supervise implementation of those of the EPC and O&M contractor, ensuring compliance with the requirements of host country laws and World Bank, IFC, and MIGA Performance Standards. The EPC and O&M contractor will have a Health, Safety and Environment (HSE) supervisor on the site. The social and community liaison officer will be responsible for managing potential social impacts, implementing the Stakeholder Engagement Plan and its project grievance mechanism as well as supervising and coordinating with the contractor in all related matters. .

The Project Company is responsible for that all staff comply with the environmental and social policies, procedures and mitigations, including requirements under the Performance Standards. The identification of training and awareness needs and implementation of the training plan will be the responsibility of HSES manager with inputs from the social / community liaison officer and relevant line managers. Similarly, the EPC contractor's HSE on-site supervisor will ensure proper training of contractor's and subcontractor's workers, under the supervision of the company's HSES manager.

E. Environmental and Social (including Safeguards)

The Project follows the World Bank Group Performance Standards and is rated a Category B project. Five of the eight Performance Standards (PS) are applicable to the Project: PS1 Assessment and Management of Environmental and Social Risks and Impacts; PS2 Labor and Working Conditions; PS3 Resource Efficiency and Pollution Prevention; PS4 Community Health, Safety and Security; and PS5 Land Acquisition and Involuntary Resettlement. Other PS are not applicable as the project site is in a brownfield industrial/commercial area within an urban location.

Mitigation measures have been prepared that address potential risks and impacts of the Project. The ESHIA and the Environmental Management Plan (ESMP) were disclosed in-country on

November 17, 2015 and on the Bank's InfoShop on January 29, 2016. The World Bank, IFC and the Sierra Leone Environment Protection Agency (SL-EPA) has agreed that the ESMP will be reviewed and updated with detailed mitigation developed as part of the detailed design phase, prior to commencement of construction. The ESHIA identifies and addresses the potential risks and impacts from the Project, including the power plant, the fuel pipeline, connection to the transmission line, and the access road, and outlines proposed mitigation measures. An Environmental and Social Impact Assessment (ESIA) for the petroleum jetty at the Kissy oil terminal was prepared by the project sponsor. Quantitative studies were carried out involving numerical modelling of emissions to atmosphere and noise during plant operations, and quantification of water consumption and discharges. An Environmental and Social Action Plan (ESAP) was agreed between CECA SL and the World Bank Group. Through its implementation, the project is expected to be designed and operated in accordance with Performance Standards objectives.

The public review and public hearing, in accordance with Sierra Leonean regulations, has taken place on November 26 and 27, 2015 with the involvement of the affected community at Kissy. The ESHIA was made available in relevant government offices and public places in the project region and non-technical summaries were distributed in the Project's area of influence.

The project site will not involve physical displacement as there are no inhabitants (legal residents or squatters), but will result in limited economic displacement and livelihood impacts on artisanal farmers. The zone of impact is restricted to the project site. Initially, 16 farmers were identified farming small areas within the project site during the two consultative meetings held in early February 2014 and early May 2014. A follow-up meeting was held with the artisanal farmers in September 2015, when updated data on the farmers (10 instead of 16 as initially identified) were collected and details of compensation were further discussed. The Project has prepared and disclosed an Abbreviated Resettlement Action Plan (ARAP) to manage the economic displacement of 10 artisanal farmers. The ARAP includes details on the farm plots referred as "heaps" and each ranging between 20 to 25 square meters in size. An initial estimated number of 32 heaps were identified within the project site and estimated compensation amounts were calculated based on the crops grown: potato leaf, cassava leaf, green, sour and krain-krain. The farmers are all women from around the area utilizing the heaps to supplement their subsistence and household income by selling the remainder crops at the nearby market. The ARAP will be finalized and implemented in consultation with the artisanal farmers prior to commencement of construction activities in accordance with PS5.

Extensive consultations with stakeholders were undertaken as part of project preparation. Consultations were undertaken during the ESHIA scoping phase (January 2014 to May 2014) and during the ESHIA assessment phase (February 2015 to March 2015) despite challenging conditions related to the EVD outbreak. A number of informal and formal meetings were also held with key stakeholders from January 2014 to May 2014: SL-EPA) including JICA, Sierra Leone Roads Authority (SLRA), Sierra Leone Non- Governmental Organizations (SLANGO), Conservation Society of Sierra Leone (CSSL), China Road Construction Corporation (CRCC), Ministry of Agriculture Forestry and Food Security (MAFFS), EDSA, and the local community members and residents around the project site as well as with the Islamic school and the Sir Winston Churchill School. A public community consultation workshop took place on May 15, 2014, indicating broad support for the project, but also showing local people's high expectations

for job opportunities, electricity supply and economic and community development. Ongoing consultation with the artisanal farmers at the project site was highlighted as being of particular importance.

A Project grievance mechanism will be established. As a result and as part of the agreed Environmental and Social Action Plan, the Project Company has committed to develop and implement a Stakeholder Engagement Plan (SEP) to continuously inform the public throughout the Project cycle. The Project Company will also ensure that a grievance mechanism is established under the EPC and O&M contractor.

F. Environmental and Social Safeguards Specialists on the Team:

Robert Robelus, Consultant - Environmental Specialist (GENDR)

Demba Balde, Snr. Social Development Specialist (GSU01)

II. PERFORMANCE STANDARDS THAT MIGHT APPLY

Performance Standards <i>(please explain why)</i>	Yes	No	TBD
PS 1: Assessment and Management of Environmental and Social Risks and Impacts	X		
<u>Environmental and Social Assessment and Management System.</u>			
<p>An ESHIA/ESMP was prepared and disclosed in-country on November 17, 2015, in the Bank's InfoShop on December 10, 2015, and with the IFC Environmental and Social Review Summary (ESRS) disclosed on December 18, 2015. The ESMP will be reviewed and updated with detailed mitigation developed as part of the detailed design phase, prior to commencement of construction.</p>			
<p>The ESHIA identifies and addresses the potential risks and impacts from the project, including the power plant, the fuel pipeline, the connection to the transmission line and the access road, and outlines proposed mitigation measures. An Environmental and Social Impact Assessment for the petroleum jetty was prepared by the project developer. Quantitative studies were carried out involving numerical modelling of emissions to atmosphere and noise during plant operations, and quantification of water consumption and discharges. The public review and public hearing, in accordance with Sierra Leonean regulations, took place on November 26-27, 2015 with the involvement of the affected community at Kissy. The ESHIA was made available in relevant government offices and public places in the project region and non-technical summaries will be distributed in the project's area of influence.</p>			
<p>The current framework ESMP will be the basis of developing detailed construction and operation phase management plans. The ESMP describes the structure and processes that will be applied to construction and operation activities to assess and monitor compliance and effectiveness of the mitigation measures. Its objectives are to:</p>			
<ul style="list-style-type: none"> (a) Describe the mitigation measures and actions identified by the ESHIA, requiring detailed design and implementation during construction and operation phases of the project; (b) Identify and describe monitoring requirements; (c) Identify roles and responsibilities of parties involved, including CECASL and the EPC and O&M contractor; and (d) Identify environmental and social reporting requirements, such as audits of performance. 			
<p><u>Emergency Preparedness and Response.</u> Storage, handling and use of HFO at the facility can present potential hazard in relation to accidental spills and fire. The EPC and O&M contractor will develop an emergency preparedness and response plan for the construction and operational phase respectively. The plan will describe the procedures to follow when handling an emergency situation such as fire, hazardous material, waste or fuel spills, injuries, natural disasters.</p>			
<p>The Fire Safety and Emergency Preparedness and Response plan will be developed in close coordination with the community facilities (including the schools) and will be communicated</p>			

to the affected community.

Monitoring and Review.

The ESHIA commitments include further survey work (supplemented by project consultations) to be conducted post-Ebola, including air quality, noise, groundwater and socio-economic aspects (with special focus on the nearby formal and informal shanty dwellings), as well as the development of a number of monitoring plans that will be needed for the project. Monitoring will be conducted to ensure compliance with regulatory requirements and the Performance Standards, as well as to evaluate the effectiveness of operational controls and other measures intended to mitigate potential impacts, as identified in the ESHIA. The monitoring plans will describe the indicators to be measured and the frequency, and will define roles and responsibilities for monitoring and reporting.

Indicators to be monitored during construction include: vehicle accidents, noise and dust generation, water quality, waste disposal, occupational health and safety (including near misses, accidents, lost time incident, root cause analysis), and job creation within local communities. During operations, monitoring will include: air emissions and ambient air quality, noise, occupational health and safety, effluent discharge, water and fuel consumption, fuel characteristics (including sulfur, ash and Conradson carbon residue content), greenhouse gas emissions, and job creation within the local communities.

CECA SL will perform a number of internal and external audits and inspections annually and will develop and implement an audit schedule. The contractor will be required to provide HSE performance reporting to the World Bank, IFC, and MIGA on a regular basis and include audits in their respective HSE Plans.

PS 2: Labor and Working Conditions	X		
---	----------	--	--

At the peak of construction, the Project is anticipated to employ up to 200 construction workers. During operations, the plant is expected to employ approximately 45 permanent employees. During construction which will last approximately 18 months, the company will maximize employment from the surrounding community. It is expected that Freetown is able to provide local labor for the project construction and therefore risks associated with a significant influx of workers are considered limited. A worker's accommodation camp is not anticipated to be required for the project, and, as needed, the EPC contractor will ensure that transportation to the site for workers is provided. However, if the EPC contractor elects to develop an accommodation camp, it will be designed and operated consistent with IFC/EBRD guidance note on Workers' Accommodation: Processes and Standards.

CECA SL will develop a Human Resources policy that describes its approach to managing its workforce consistent with national labor requirements including policies on equal opportunities, harassment, child labor, sexual abuse of minor girls (<18 years of age) freedom of association; and a simple and clear manual which outlines the employees' rights under national employment laws, any collective bargaining agreement as well as their rights with regards to working hours, wages, overtime compensation, benefits, company code of conduct and disciplinary action, grievance mechanism, and performance management ensuring compliance with this Performance Standard. The Project Company will monitor and audit as necessary labor and working conditions of its contractor, subcontractors and main

suppliers. Subcontractors will be required to provide a self-declaration on compliance with environmental and social safeguards and labor policies and undergo a full due diligence process including reviewing of documentation and site visits to the vendor's operations.

Occupational Health and Safety. Occupational health and safety of the employees and workers engaged by third party are addressed in CECA SL Project Health and Safety Plan. The selected EPC and O&M contractor has an established health and safety management system that is consistent with OHSAS 18001. Key performance indicators, including lagging (such as total recordable injury rate and loss time injuries frequency) and leading indicators, will be used to measure occupational health and safety performance. Project safety performance will be monitored and reported on a monthly basis.

An occupational health and safety manual will be provided to all personnel on site. The company will ensure that all contractor's and subcontractor's workers are adequately trained and will monitor their performance. Staff on the site (employees, contractors and subcontractors) will be required to wear relevant personal protective equipment which will be supplied by the company and the EPC and O&M contractor. First aid kits will be readily available at the site. A worker health monitoring program, including Ebola-related measures, will also be established to ensure proper management of occupational health and safety concerns and incidents.

A process hazard analysis (PHA) (e.g., hazard and operability study (HAZOP)) will be prepared to cover the full project infrastructure. The information generated from the PHA/HAZOP will be used to prepare the Fire Safety and Emergency Preparedness and Response Plans. Prior to start of operation, designated staff will be trained in first aid response, fire safety and spill response. The plant design will incorporate provisions for fire prevention, fire detection, and fire suppression (including water and foam and portable extinguishers, readily available). The design of the fire protection system will follow National Fire Protection Association (NFPA) 850 guidelines. The facility will have equipment installed including gas detectors, heat sensors and manual pull stations in the event of a fire and an audible alarm system. A fire water tank will be installed and a peak instantaneous flow rate of 55m³/hour will be required for fire water (beyond the existing capacity provided in the fire water tank).

PS 3: Resource Efficiency and Pollution Prevention	X		
---	----------	--	--

Resource Efficiency. The plant configuration will use six medium speed diesel generating sets, inside a closed HVAC controlled power house, closed loop fin-type radiator cooling system, and steam system operating on the recovery of the exhaust gas heat. The selected technology has been continuously improved and adapted to meet international emission standards, increased specific capacity and increased fuel efficiency.

Air Emissions. Ambient air quality measurements showed concentrations of NO₂, albeit measured over a relatively short timescale, within the annual mean WHO ambient air quality guideline (AAQG) of 40 µg/m³ and concentrations of SO₂ well within 24-hour average guideline of 20 µg/m³. Measurements of 24 hour mean PM₁₀ concentrations ranged from 112 to 448 µg/m³ during the dry season and from 48 to 120 µg/m³ during the wet season, compared with the 24 hour mean WHO ambient air quality interim target of 150 µg/m³ and

the guideline of 50 $\mu\text{g}/\text{m}^3$. Measurements of 24 hour mean PM_{2.5} concentrations ranged from 15 to 80 $\mu\text{g}/\text{m}^3$ in the dry season and from 7 to 25 $\mu\text{g}/\text{m}^3$ during the wet season, compared with the WHO ambient air quality interim target of 75 $\mu\text{g}/\text{m}^3$ and the guideline of 25 $\mu\text{g}/\text{m}^3$. The air shed at the Project site is therefore considered non-degraded for NO₂, SO₂ and PM_{2.5}, and potentially degraded for PM₁₀, due to the high values measured during the dry season.

Based on fuel specifications in the fuel supply agreement, the HFO will have an ash content of a maximum 0.15%, carbon residue of a maximum 20%, and a sulfur content of 2% or less, which is in compliance with WBG's guidelines for non-degraded airsheds for SO₂. Air emissions, as predicted by the EPC contractor and supplier of the engines, are expected not to exceed the applicable and relevant guideline levels set out in the WBG's EHS Guidelines for Thermal Power Plants, with the exception of particulates, which the contractor guarantees will not exceed 100 mg/Nm³ (above the guidelines of 50 mg/Nm³ and 30 mg/Nm³ for a facility located within a non-degraded airshed and within a degraded airshed, respectively). Because less stringent levels of PM emissions than those provided in these EHS Guidelines are conservatively predicted based on the worst fuel characteristics allowed by the fuel specifications, as part of the ESHIA, the company has provided a technical and financial justification and a site-specific quantitative assessment to demonstrate compliance with applicable ambient air quality standards and minimization of incremental impacts. The impact of the flue gas emissions on ambient air quality was assessed using the Atmospheric Dispersion Modelling System (ADMS) version 5 dispersion modelling software. Modeling assumed 6 x Wärtsilä 20v32 generating sets operating at 100% load for 7884 hours per year (i.e. 92.5% of the year), and emitting via a common stack grouping with stack height of 65 m. The assumption that the plant is operating at 100% load, 92.5% availability is conservative, as the average plant load is expected to be below 100%. A stack height assessment was undertaken to determine the appropriate stack height for the proposed power plant. Conservatively, the emissions from the engines were assumed to be constantly at the limits for liquid fueled reciprocating engines <300 MWth input.

The model showed no predicted exceedance of the relevant WHO AAQG for NO₂ and SO₂. The project contribution was predicted to be less than 25% of the AAQG values for annual mean NO₂, which is in line with the WBG EHS guidelines. There is also no predicted exceedance of the annual mean or 24-hour mean AAQG for PM_{2.5} and the project contributions for the respective averaging periods are relatively low, approximately to 2.8% to 4.7% of the annual mean and 24-hour mean AAQGs, respectively. While exceedances of both the annual mean and 24 hour mean AAQG values for PM₁₀ were predicted due to the high background concentrations measured (particularly the dry season measurements), the project maximum contributions in terms of PM₁₀ for the respective averaging periods is, however, low, approximately 1.4% to 2.4% of the AAQG values for the most conservative scenario of plant operating at 100% load with maximum PM emission levels. The maximum 24-hour mean levels and the annual maximum mean levels were predicted to be located approximately 0.9 km east of the site and east of Wellington Creek, a predominantly industrial/commercial area on the coast and, therefore, the predicted concentrations of the emitted substances will be lower within the nearby more densely populated residential areas. The assessment concluded that the maximum predicted annual mean increases for each pollutant are not significant, with regard to potential human health effects.

Regular monitoring of fuel quality will be implemented by the company. A Continuous Emissions Monitoring System (CEMS) will be installed to monitor the emissions of the relevant pollutants and associated emissions parameters, and provision will be made for manual sampling of pollutants, including sampling points with safe access. The company will develop and implement an ambient air quality monitoring program (ESAP actions #1 and #2) with monthly sampling to assess the air shed conditions and monitor concentrations of NO₂, SO₂ and particulates (PM₁₀ and PM_{2.5}) in the project's area of influence during construction and operations phase. Heavy metals and unburned hydrocarbons will also be periodically measured. The ambient air quality monitoring program will be undertaken for at least two full year of operations and will be subsequently calibrated based on the results of the monitoring, in consultation with WBG and EPA-SL. Should actual monitoring indicate that air emissions are above the predicted levels and a measurable impact on ambient air quality is associated with the plant's operations, CECASL will implement additional pollution control measures to further reduce stack emissions, including, as needed, necessary capital and/or operating improvements.

Noise and Vibrations. Two ambient noise surveys were conducted during the ESHIA study. While the project site and its surroundings are zoned by Freetown City Council as commercial/industrial land use, several buildings surrounding the project site have residential, community or educational usage. The average night-time noise levels measured around the site were below the WBG noise level guideline for industrial areas of 70 dBA, although the guideline was exceeded during the day. Measured levels were well above the WBG guidelines of 45 dBA (night time) and 55 dBA (daytime) for residential, institutional and educational uses, exceeding both the daytime and the night-time guidelines by between 14 – 19 dBA.

The construction phase will have temporary impact on ambient noise mainly due to use of heavy equipment at the site and construction traffic. Construction works are estimated to generate high noise levels in the range 83-87 dBA at a distance of 10 m. Noise will be mitigated by limiting construction activities to daytime according to a time schedule which will be presented to the affected community during public consultation and as part of the engagement activities with the residents and management of the schools prior to construction.

During operations, the main noise sources will be the diesel engines operating within an engine hall, the exhaust stack, the combustion air intake, the engine hall air supply, the four electrical transformers, and the cooling radiator array. Design noise attenuation measures include air intake and ventilation attenuators and exhaust silencers. In addition, enhanced mitigation measures have been considered in the design, including enhanced ultra-low noise radiator fans and increased size of the ventilation attenuators. The noise levels were predicted using a 3D noise model prepared in Cadna/A. WBG noise level guideline for industrial areas of 70 dBA is predicted to be complied with at the site boundary. Due to the presence of residential and educational receptors, the study carried out (i) a comparison of the modeled nighttime noise levels with the relevant 45 dBA criterion and (ii) an assessment of the criterion of maximum increase in background levels of 3 dBA, per WBG EHS Guidelines. While, due the high noise baseline levels measured, the noise levels were predicted to exceed

the nighttime 45 dBA criterion for considerable distances from the site boundary, the predicted change in noise level did not exceed 3 dB at any building in the project vicinity.

Although the modeled change in noise levels did not exceed 3 dB criterion, the ESHIA has committed to identify and implement additional enhanced noise reductions (layout optimization, ultra-low noise radiator fans, increased size of the ventilation splitter attenuators and noise barrier) to reduce night time noise levels to 55 dB LAeq at the nearest residential dwellings located in the proximity of the site, an approach considered prudent to ensure the plant operations do not worsen the current noise environment. As indicated in ESAP action #9, a Noise Management Plan will be developed including provisions identified during detailed design for noise reductions at source and specific engagement with the affected people, including nearest residential receptors and schools. An ambient noise monitoring program will be undertaken for at least two full years of operations and will be subsequently calibrated based on the results of the monitoring. Should actual monitoring indicate that noise impacts are above the predicted levels, CECASL will implement additional enhanced noise mitigation.

Vibrations are expected to be limited and mainly associated with the construction phase: a Construction Vibration Management Plan will be developed and implemented, including structure survey and vibration monitoring during construction, as per ESAP action #1.

Water Consumption and Liquid Effluents. During construction water will be supplied to the project by tankers. Potable water will be provided in bottles/drums and delivered to site via trucks. As the power plant is air cooled, limited water volumes will be required for radiator makeup water, wash down and sanitary/domestic use. During operations water will be supplied by groundwater abstraction boreholes, which will be drilled to supply water for the project. As indicated in ESAP action #10, the company will undertake a borehole survey to identify the location of any nearby water wells and will provide assurance that the boreholes drilled to provide water to the plant will not affect existing community water sources. If water purchased from Guma Valley Water Company is considered as a supplemental source, the company will carry out an assessment of water availability to other water users on the network to ensure continued water usage.

A water treatment system designed to treat brackish water, with low organic matter and suspended solids content, will provide treated water which will be stored in a 100m³ water tank. Two water tanks, each of 700m³ size capacity, will be installed on site for the fire response system.

All sanitary sewage will be sent to either an onsite septic tank for storage and disposal or to an onsite effluent treatment plant, depending on the final design. Industrial wastewater generated will be a limited quantity and treated in an oil/water separator. Potentially contaminated storm water drainage system will be directed to an oil/water separator for treatment. Oil from the oil/water separator(s) will be recycled or disposed of in the on-site incinerator. The containment basin for the transformers will be sized to contain both oil leakage and firefighting water in case of emergency. The design of the wastewater management network and units is not finalized yet, but, as indicated in the ESHIA, if treated wastewaters are discharged to a stream or a drain, they will meet the applicable and relevant

effluent guidelines of the WBG General EHS Guidelines (Table 1.3.1) and EHS Guideline for Thermal Power Plants (Table 5).

Waste and Hazardous Materials. Both CECASL's and the contractors' management plans will include waste management procedures. The company will ensure that the EPC and O&M contractor appropriately minimizes and controls release of hazardous materials (e.g. used oils, chemicals for water treatment, fuel, and wastewater treatment).

Waste generated during construction will include excavated soil, domestic waste, various packaging, containers, used oil, and batteries. The excavation will be limited given that the topography of the site is relatively flat.

During operations, the most significant solid wastes will be sludge from the HFO cleaning with fuel separators (centrifuges), lube oil cleaning, any fuel and lube oil drain and leakage at the plant, and the water/effluent treatment plant. Other sources of solid waste will include domestic and commercial waste (cardboard, paper, pallets, packaging material from spares, food wastes), and wastes produced during maintenance, such as sludge removed from oil separators, scrap metals; air filters, and paper and plastic packaging materials. Because there are not suitable hazardous waste disposal facilities in Sierra Leone, hazardous waste will be stored on-site and appropriate disposal determined as part of the Waste Management Plan. Hazardous waste will be managed in compliance with PS 3 requirements. If transboundary movement of hazardous materials and waste is needed, it will be consistent with national, regional and international law.

Although the design is not finalized yet, the company plans that the sludge waste is burned in a small on-site incinerator, which will be intermittently operated, will be used for the disposal of HFO sludge only and will not be used for incineration of any other materials. The quantity of the sludge to be incinerated will approximate 10 tonnes/month. The incinerator will have a combustion capacity below 3MWth. If confirmed to be the preferred option for HFO sludge disposal, the incinerator will be designed and operated to meet good industry international practice to prevent technical problems and environmental impacts. The final options for hours of operation and volume of sludge to be processed in the incinerator will be defined in the Waste Management Plan to be developed as part of the ESMP. Hours of operation will be restricted to ensure that the incinerator it is not considered a significant source of air quality emissions. Bottom ash and residuals should be managed based on their classification as hazardous or non-hazardous materials. The resulting ash will be analyzed and will be stored and disposed of per Waste Management Plan. If hazardous, the ash will be shipped overseas to appropriate facilities for disposal.

A number of measures will be integral to the design and operation of the proposed incinerator, including:

- The incinerator will be fully automated with flue gas O₂ and temperature in combustion chamber flue gas outlet, combustion temperature controller, negative pressure switch, flame safeguard control, and relevant alarms;
- The incinerator will be operated intermittently and will not exceed the operating limits defined in the Small Combustion Facilities Emissions Guidelines included in the WBG General EHS Guidelines (pg. 6).

As indicated in ESAP action #11, the company will provide IFC and the World Bank with

detailed information on the foreseen incineration technology, and with the Incinerator Operations Manual which will define the operations of the incinerator including total quantity to be incinerated and hours of operations.

The fuel storage tanks will be above ground with secondary containment. The anticipated total amount of fuel onsite at any given time is estimated 11,000 m³. The estimated fuel consumption is 261m³ of HFO per day.

Greenhouse Gases (GHG). The company estimates that the power plant will produce up to 464 GWh of electricity per year depending on the load factor, with carbon dioxide emissions up to 312,000 t CO₂ equivalent per year at CO₂ emission performance of 0.67 kg CO₂/kWh. As required for projects with GHG emissions greater than 25,000 tons CO₂ equivalent per year, the company will quantify GHG emissions annually in accordance with internationally recognized methodologies and good practice.

A “Climate Change Potential Review” was included in the ESHIA scoping report and concluded that there will be no significant climate change effects. The plant site is located >15 m above sea level and 500 m inland. Climate change effects for the project are therefore limited to lesser implications such as changes in rainfall frequency/intensity and minor temperature change implications for engine efficiency. The design included adaptation measures to address this risk, such as additional capacity for the drainage design in addition to appropriate engine selection.

PS 4: Community Health, Safety, and Security	X		
---	----------	--	--

Community Health and Safety. The site is about 0.9 km from the main road (Bai Bureh Road) through Parsonage and Factory roads, which are in poor conditions. In addition to the presence of two schools and the Islamic compound (whose entrance is directly on the access road), there are some shanty houses along access road and some artisanal farming areas, particularly within the storm drain overflows of Factory Road. The distance from the Queen Elizabeth II Quay, where the heavy plant equipment will be unloaded, to the site is 4.4 km.

Due to the conditions of the access roads and the shanty houses located in close proximity to the project entrance, community health and safety risks will be mitigated by the project during construction and operations. As indicated in ESAP action #12, CECASL will develop and implement a Traffic Management Plan to control traffic and ensure community safety.

The Traffic Management Plan will include measures related to safety of delivery of raw materials, road grading and maintenance, roadside incident management and spill response, defensive driving, and drugs and alcohol testing for truck drivers, and community awareness.

To minimize the fire risk to surrounding community posed by storage of large quantities of fuel on the plant site, CECASL will ensure that the design will include a detailed hazard analysis, focused on potential effects of fire on the residential and community receptors located in the vicinity of the project site, and the needed measures to mitigate the risk. The tank farm will be designed following NFPA 850 guidelines, including minimum physical separation of the tanks. Each tank will be banded to contain all the volume of fuel, a cooling

ring will be installed in all the tanks, a foam system will be installed inside each tank, and hydrants will be installed in the tank farm. CECASL and the EPC and O&M contractor will put in place an emergency preparedness and response system that will be tested for its integrity as described in PS1 above.

As indicated in the ESHIA report, CECASL is committed to ensure that the HFO pipeline route is all within secured areas of the NP facility and the refinery with the exception of the road crossing next to the site entrance, where the pipeline will be underground and duly protected.

A Worker Policy and Code of Behavior will be developed, including guidance for staff and construction workers, disciplinary actions for conduct violations and a grievance mechanism for community complaints. Compliant with national law and consistent with relevant international good practice recommendations, a worker health screening program, based on sound ethical and technical practice, will be developed and implemented during construction.

Security. Security arrangements to be performed during the construction and operational phases have not been established yet. CECASL will ensure that security personnel have undertaken necessary screening and training in accordance with good industry practices. As indicated in ESAP action #13, the company will prepare policy and procedures, including a Code of Behavior for security personnel, to ensure that security arrangements will follow the requirements of PS4 including provision of a grievance mechanism. The project will adhere to the Voluntary Principles on Security and Human Rights to ensure that adequate health and safety training of security personnel takes place. The company will ensure that EPC and O&M contractor implement appropriate incident response procedures in accordance with the recommendation relevant to Interactions Between Companies and Public Security included in the Voluntary Principles on Security and Human Rights.

PS 5: Land Acquisition and Involuntary Resettlement	X		
--	----------	--	--

The development of the project site will not involve physical displacement as there are no inhabitants (legal residents or squatters), but will result in limited economic displacement and livelihood impacts on artisanal farmers who do not own the land but are allowed to cultivate subsistence crops. The zone of impact is restricted to the project site itself. Initially, 16 farmers were identified farming small areas within the project site during the two consultative meetings held in early February 2014 and early May 2014. After the Ebola situation in the country, a follow-up meeting was also held with the artisanal farmers in September 2015, when updated data on the farmers were collected and details of compensation were further discussed. Although during the original project consultation with the farmers in February 2014 it was indicated that there were 16 farmers utilizing the site, only 10 farmers were identified as permanently farming within the site in September 2015. Based on the discussion with the farmers, it is understood that the other farmers used the plots occasionally and had since moved on. The project has prepared and disclosed an Abbreviated Resettlement Action Plan (ARAP) to manage the economic displacement of the 10 artisanal farmers. The ARAP includes details on the farm plots referred as “heaps” and each ranging between 20 to 25 square meters in size. An initial estimated number of 32 heaps were identified within the project site and estimated compensation amounts were calculated based on the crops grown: potato leaf, cassava leaf, green, sour and krain-krain. The farmers are all women from around the area utilizing the heaps to supplement their subsistence and

household income by selling the remainder crops at the nearby market. As indicated in the ESAP action #14, the ARAP will be finalized and implemented in consultation with the artisanal farmers once the Ebola situation is all clear, prior to project construction, in accordance with Bank’s social safeguards standards. The ARAP will be finalized based on further assessment on determining the adequate compensation measure and mechanism for the artisanal farmers as well as identifying the supporting livelihood restoration activities. Though the artisanal farmers do not own the heaps, the project is committed to identify areas that would allow them continuing their farming activities.




In addition, the project is currently assessing the potential impacts, especially during the construction phase, and relevant mitigation options for seven families located on the side of the project site’s front entrance. Despite being an industrial zone, the families have settled in the area for some time and reside in informal structures mainly composed of zinc roofs and wooden beams. The main impact involves traffic safety concerns, especially during the construction phase, with increasing traffic in and out of the project site. Analysis of mitigation options being assessed may identify, as preferred option, the physical relocation of these families, for which the project would be required to complement the ARAP and define specific measures to adequately manage the physical displacement of the families and restore their livelihoods in line with PS5 as per ESAP action #14.

PS 6: Biodiversity Conservation and Sustainable Management of Living Natural Resources		X	
The designated biodiversity areas are at least 2km away from the project site and are not predicted to be adversely affected.			
PS 7: Indigenous Peoples		X	
No groups that meet the definition in PS7 have been identified in the project area.			
PS 8: Cultural Heritage		X	
No cultural heritage issues have been identified. A “Chance Find Procedure” will be included in all contractor contracts.			
OP 7.50: Projects on International Waterways		X	
OP 7.50 is not applicable since the Project is not located near any International Waterways.			

III. SAFEGUARDS PREPARATION PLAN

The disclosure of the ESHIA and the Abbreviated Resettlement Action Plan (ARAP) in country was done on November 17, 2015, while the disclosure in the InfoShop took place on January 29, 2016.

IV. APPROVALS

<i>Signed and submitted by:</i>		
Task Team Leader:	Name: Carol Litwin 	Date May 23, 2016
<i>Approved by:</i>		
Regional Safeguards Coordinator:	Name: Hanneke Van Tilburg 	Date May 24, 2016
Comments:		
Acting Practice Manager:	Name: Sameer Shukla 	Date MAY 24, '16
Comments:		