Environmental Impact Assessment (Draft)

August 2014


BHU: Green Power Development Project II

(Part B: Transmission Component)

Prepared by Druk Green Power Corporation Limited and Tangsibji Hydro Energy Limited for the Asian Development Bank

The environmental impact assessment report is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature.





NIKACHHU HYDROPOWER PROJECT, BHUTAN (118 MW)

ENVIRONMENTAL IMPACT ASSESSMENT FOR 132 kV TRANSMISSION LINE FROM NIKACHHU POTHEAD YARD TO MANGDECHHU POTHEAD YARD- 2014

Prepared for:

Druk Green Power Corporation Limited and Tangsibji Hydro Energy Limited (THyE) Thori Lam, Thimphu Bhutan Prepared by:

Bhutan Consultants & Research (BHUCORE) Taba, Post Box: 955, Thimphu (revised by PWC Consultants)

Contents

E	xecuti	ve Sı	ummary	10
1	Intr	oduc	tion	24
	1.1	Bad	ckground	24
	1.2	Pur	pose of the report	24
	1.3	Ext	ent and scope of the study	24
	1.4	Stru	ucture of the Report	25
2	Pol	licy, L	_egal, and Administrative Framework	27
	2.1	Nat	ional Laws and Regulations	27
	2.2	App	olicable Guidelines and Standards	32
3	De	scrip	tion of the Project	36
	3.1	Intr	oduction	36
	3.2	Des	scription of the Transmission Line	38
	3.2	.1	Project Ancillaries	45
	3.2	.2	Land Required for the Project	;46
	3.2	.3	Construction Power Requirements	47
	3.2	.4	Water Supply Requirement	48
	3.2	.5	Requirements for Raw Materials/Construction Materials	49
	3.3	Cor	nstruction Activities and Schedule	50
	3.4	Wo	rk Implementation and Staffing Requirement	51
4	Ana	alysis	s of Alternatives	54
5	De	scrip	tion of the Environment	56
	5.1	Phy	sical Resources	56
	5.1	.1	Location	56
	5.1	.2	Topography, Geology and Soils	59
	5.1	.3	Climate	62
	5.1	.4	Air Quality	64
	5.1	.5	Noise	68
	5.1	.6	Surface Water	69
	5.1	.7	Ground Water	73
	5.2	Eco	ological Resources	74
	5.2	.1	Protected Areas	74

	5.2	2.2	Forest and Vegetation	75
	Ve	getat	ion Types in Bhutan	75
	5.2	2.3	Wildlife	85
	Gra	aph 5	5.5: Percentage of plots with wildlife signs in them	85
	5.2	2.4	Birds	87
	5.2	2.5	Amphibians and Reptiles	88
	5.3	Eco	onomic development	89
	5.3	3.1	Land Use, Industry and Agriculture	89
	5.3	3.2	Infrastructure	93
	5.3	3.3	Transportation	94
	5.3	3.4	Tourism Industry	94
	5.4	Soc	cial and Cultural Resources	95
	5.4	.1	Demography	95
	5.4	.2	Health and Education	96
	5.4	.3	History and Culture	97
6	An	ticipa	ted Project Impacts	99
	6.1	Intr	oduction	99
	6.2	Det	termining the degree of potential impacts	99
	6.3	Imp	pacts during Pre-Construction	101
	6.3	3.1	Economic Impacts	101
	6.3	3.2	Employment Opportunities	102
	6.3	3.3	Mobilization of Construction Equipment and Materials	103
	6.3	3.4	Environmental Impacts	106
	6.4	Imp	pacts during construction phase	107
	6.4	.1	Economic Impacts	108
	6.4	.2	Social Impacts	108
	6.4	.3	Environmental Impacts	109
	6.4	.3.5	Risk of slope instability	112
	6.4	.3.6	Impacts on community forest	112
	6.4	.3.7	Impact on surface waters	112
	6.4	.3.8	Impacts from improper storage of fuel	113
	6.4	.3.9	Impacts from improper closure of project work sites	113

	6.5 l	mpacts during Operation Phase	113
	6.5.1	Economic Impacts: Decrease in income opportunities	113
	6.5.2	Social Impacts	113
	6.5.3	Environmental Impacts	114
	6.5.4	Electrocution of raptors and other large birds	115
7	Envir	onmental Mitigation and Management Plan	116
	7.2	Employment opportunities	117
	7.3 their s	Management of impacts from mobilization of equipment, construction mate storage	
	7.4	Management of Social Impacts	118
	7.7	Air Quality Management	127
	7.8	Management of Noise generation	127
	7.9	Management of Aesthetics	128
	7.12	Biodiversity Conservation	132
	7.13	Muck Management	134
	7.14	Managing risk of slope instability and impact on surface waters	135
	7.15	Closure Plan	136
	7.16	Mitigating risk of electrocution and accidents during maintenance works	137
	7.17	Electromagnetic Field (EMF)	138
	7.18	Mitigating risk and hazard associated with TL	142
	7.19	Mitigating electrocution of raptors and other large birds	142
8	Envir	onmental Monitoring Program and Institutional Responsibilities	144
	8.1 T	he Environmental Monitoring Program	144
	8.2 l	nstitutional Responsibilities	164
9	Griev	ance Redress Mechanism	166
10	0 Inforn	nation Disclosure, Consultation, and Participation	166
1.	1 Refer	ences	172

LIST OF TABLES, MAPS, FIGURES, GRAPHS AND PHOTOS TABLES

Table 3.1:	Transmission line Route Details
Table 3.2:	Description of Project Components
Table 3.3:	Description of each Segment of the Transmission
Table 3.4:	Area requirement for Contractors facilities
Table 3.5:	Details of private land required
Table 3.6:	Land use along Project TL Right of Way
Table 3.7:	Daily water requirement for drinking and other purposes
Table 3.8:	Requirement of Construction Materials
Table 5.1:	International Commitments and dates of Ratification
Table 5.2:	Applicable time limits to obtain environmental clearance.
Table 5.3:	List of applicable acts and regulations for the Project.
Table 5.4:	Ambient air quality standards
Table 5.5:	Motor vehicle emission standards
Table 5.6:	Environmental standards for noise
Table 5.7:	Checklist of compliances required for the Project.
Table 6.1:	List of Blocks and Sub-Blocks in Trongsa district
Table 6.2:	Result of soil samples analysis of the study area (Source, MHEP, 2010)
Table 6.3:	Soil Type and Terrain along the TL
Table 6.4:	Location of Climatological stations closest to Trongsa
Table 6.5:	Permissible air quality standards
Table 6.6:	Air quality measured at various sites in the Project district
Table 6.7:	Suspended Particulate Matter in $\mu g/Nm3$ at various sites in the Project district
Table 6.8:	Oxides of Sulphur (SOx) in µg/Nm3at various sites in the Project district

Table 6.9: Oxides of Nitrogen (NOx) in µg/Nm3 at various sites in the Project district Table 6.10: Respirable particulate Matter in µg/Nm3 Table 6.11: Air Quality data collected by Nikachu Project Table 6.12: Ambient air quality for 24 hours Table 6.13: Work place emission for average 8 hours Table 6.14 Noise levels at various sites in Project site Table 6.15: Baseline noise levels (sampled July 2012) Table 6.16: River and stream crossing along the TL alignment Table 6.17: Water quality at the project site and downstream (sampled July 24-29, 2012). Table 6.18: Water quality at the project site and downstream (sampled December, 2012) Table 6.19: Proximity to access roads and other structures along TL Table 6.20: Types of wildlife signs found during biodiversity survey Status of Wildlife present in the project area Table 6.21: Table 6.22: Land use cover in Trongsa and the Country Table 6.23: Villages that are crossed along the TL alignment Table 6.24: Medical Facilities in Trongsa and the entire country Table 6.25: Types of schools in Trongsa and the entire country Table 7.1: Fields in which construction is not expected to have significant impacts Table 7.2: The detail of project land acquisition Table 7.3: Temporary land requirement Table 7.4: Staffing requirements of BPC Table 7.5: Cultural and heritage site details Table 7.6: Total Quantity of water required for domestic and construction purposes Table 7.7: Area of land use along transmission line ROW Table 8.1: List of households whose dry land will be acquired Table 8.2: Grievance Redressal Mechanism

Table 8.3:	Total quantity of water required for domestic and construction purpose
Table 8.4:	Streams near project area
Table 8.5:	Specific PPE requirement for each type of work
Table 8.6:	Maximum exposure periods specified by MoLHR
Table 8.7:	Summary of ICNIRP Exposure Guidelines
Table 8.8:	Over head electric conductor clearance
Table 8.9:	Minimum distance to be maintained from the TL
Table 8.10:	Line crossing at different voltage levels
Table 8.11:	Minimum clearance from live metal to earth metal
Table 9:1:	Environmental Impacts, Significance, Duration and their Mitigation
Table 9:2:	Environmental Monitoring Plan
Table 9:3:	Environmental Management Cost
Table 10:1:	Details of Public Consultation
FIGURES	
Figure 3.1:	TL alignment showing the location of the Towers
Figure 3.2:	Organogram of the Bhutan Power Corporation
Figure 3.3:	Organogram of the 'Development and Construction Department'
Figure 3.4:	Organogram of the Project Management Unit
Figure 4.1:	The two TL alternatives that were considered
GRAPHS	
Graph 6.1:	Changes in elevation along TL
Graph 6.2:	Monthly variation in temperature
Graph 6.3:	Monthly variation in Rainfall
Graph 6.4:	Land use along transmission line
Graph 6.5:	Parcentage of Plate with wildlife signs in them

Graph 6.6: Frequency of bird occurrence along transects

MAPS

Map 1: Map of Bhutan showing Location of the Trongsa district

Map 2: Map of Trongsa and its gewogs

Map 3: Map showing alignment of the Transmission line

Map 4: Map showing existing 33 kV system

Map 6.1: Seismic hazard risk for Bhutan.

Map 6.2: Map showing the Mangdechu River

Map 6.3: National parks and biological corridors in Bhutan (the project area is marked).

Map 6.4: TL alignmemt vis-à-vis Protected Area

Map 6.5: Land use in Project area

Map 6.6: Map showing the different Gewogs in Trongsa

PHOTOS

Photo 6.1: Villages located near the TL

Photo 6.2: Forest Cover along TL

Photo 6.3: Vegetation along TL

Photo 6.4: Photos along transmission line

Photo 6.5: The village and the Highway just below the TL

Photo 6.6 and 6.7: The vegetation and forest cover along the proposed alignment

Photo 9: Public consultation at Project site

ABBREVIATIONS

ADB Asian Development Bank

ADB-SPS ADB Safeguards Policy Statements (2009)

BAP Biodiversity Action Plan
BC Biological Corridor
BDL Below Detection Level
BHU Basic Health Unit

BHUCORE Bhutan Consultants & Research
BPC Bhutan Power Corporation

CA Competent Authority
CA Concession Agreement

CDM Clean Development Mechanism

CITIES Convention on International Trade in Endangered Species of Wild

Fauna and Flora

CNR College of Natural Resources

Db decibel

DGM Department of Geology and Mines
DGPCL Druk Green Power Corporation Limited

DHPP Dagachhu Hydropower Project

DLAAC Dzongkhag Land Acquisition and Allotment Committee

DoFPS Department of Forest and Parks Services

DoR Department of Roads

EA Environmental Assessment

EC Environmental Clearance

EFP Environmental Focal Person

EMP Environment Management Plan

ESIA Environmental and Social Impact Assessment

FNCA Forest and Nature Conservation Act
FNCR Forest and Nature Conservation Rule

GDP Gross Domestic Product

GLOF Glacial Lake Outburst Flooding

GNHC Gross National Happiness Commission

GRC Grievance Redressal Committee
GRFL Government Reserved Forest Land

HH Households

IEE Initial Environmental Examination

IPCC Inter-Governmental Panel on Climate Change

JE Junior Engineer

JSWNP Jigme Singye Wangchuck National Park

LPG Liquid Petroleum Gas LRO Land Record Officer M&E Monitoring & Evaluation

MHEP Mangdechhu Hydro-Electric Project
MoAF Ministry of Agriculture & Forest

MT Metric Tons MW Mega Watt

NBC National Biodiversity Centre

NEC National Environment Commission

NECS National Environment Commission Secretariat

NHPP Nikachhu Hydropower Project

NOC No Objection Certificate

NLCS National Land Commission Secretariat

OHS Occupational Health and Safety
O&M Operation and Maintenance

ORC Outreach Clinic PA Protected Area

PAVA Property Valuation & Assessment Agency

PFS Pre-Feasibility Study

PHCB Population and Housing Census of Bhutan

PM Particulate Matter PM Project Manager

PSMP Power System Master Plan
PWC PriceWaterhouseCoopers
RGoB Royal Government of Bhutan
RNR Renewable Natural Resources

RoW Right of Way

RP Resettlement Plan RS Resettlement Plan

SFD Social Forestry Division
SIA Social Impact Assessment
SPS Safeguard Policy Statement
STD Sexually Transmitted Disease

TA Technical Assistance

TCD Transmission and Construction Division

TGC Thimphu Gneissic Complex

TL Transmission Line
ToR Terms of Reference
TW Transmission Wing

UNCCD United Nations Convention to Combat Desertification

WCD Wildlife Conservation Division WHO World Health Organization

UWICE Ugen Wangchuck Institute for Conservation and Environment

Executive Summary

1.0 Background

Bhutan's technically feasible hydropower generation potential is estimated to be 23,760 MW. At present, only about 5% (or 1,488 MW) of this generation potential has been harnessed. Export of hydropower is the largest revenue source for the Royal Government of Bhutan (RRGoB) accounting for over 17.3% of its national revenues. A total of 10 projects (about 10,000 MW) have been selected jointly by RRGoB and the Government of India (GoI) for hydropower development by 2020. These 10 projects have different implementation modalities such as bilateral development by RRGoB and GoI, and by joint ventures between government corporations of the two countries. Hydropower development in Bhutan is considered to be a source of 'clean power' due to its minimal contribution to greenhouse gas (GHG) emissions compared to conventional energy sources.

Recognizing the need to develop the hydropower potential, the Asian Development Bank (ADB) provided in October 2011 a technical assistance to prepare the 118 MW Nikachhu Hydropower Project (NHPP). NHPP is a medium-sized run-of-river (ROR) hydropower type which will have lesser degree of environmental and social impacts compared to reservoir types. The power generated by NHPP will be evacuated by a 18.6 km 132 kV D/C transmission line running to Yurmo, where it will be integrated into the Pothead yard of MHEP. Farther power transmission to India shall be through the MHEP power transmission system. The associated transmission line has an estimated cost amount of Nu. 233.836 million.

NHPP will be located in Trongsa District and will draw water from the Nikachhu River and will discharge its tailrace water above the dam of the Mangdechhu Hydroelectricr Project (MHEP). The NHPP will be constructed over a 5-year period and expected to be operational by 2019. The power generated by NHPP will be evacuated through a 18.6 km 132 kV D/C transmission line running to Yurmo, where it will be integrated into the Pothead yard of MHEP. Farther power transmission to India shall be through the MHEP power transmission system.

Druk Green Power Corporation Limited (DGPCL), established in 2008 and mandated to accelerate hydropower development projects, will implement the NHPP. DGPCL currently operates five power plants with an installed capacity of 1,480 MW.

According to ADB's Safeguard Policy Statement 2009 (SPS 2009), NHPP is Category A on environment requiring the preparation of an Environmental Impact Assessment (EIA).² As specified by Bhutan National Environment Commission (NEC) regulations and the SPS 2009,

¹ Bhutan Power System Master Plan-April 2004

Asian Development Bank Safeguard Policy Statement (SPS 2009), http://www.adb.org/documents/safeguard-policy-statement (Accessed 25 July 2013)

an EIA was conducted for the hydropower project along with the preliminary assessment for the associated transmission line.

The EIA was prepared based on the Terms of Reference (ToR) approved by NEC as required by the Environmental Assessment Act 2000 and its Regulation 2002. The original EIA was prepared by Bhutan Consultants & Research (BHUCORE) in 2012. Based on additional field data and consultations undertaken in 2013, the updated EIA, Environmental Management Plan, and the Resettlement Plan were submitted by Pricewaterhouse Coopers (PWC India) Consultants to NEC in December 2013. The EIA was later revised in May 2014 to incorporate stakeholder presentations and comments from NEC. The EIA of the NHPP consists of two parts: Part 1 - 118 MW Nikachhu hydropower project and Part 2 - 18.6 km 132 kV D/C transmission line. This report covers Part 2.

2.0 Need for the project

This project forms a vital part of NHPP as it entails the construction of 18.6 km 132 kV D/C transmission line from Nikachhu Pot Head Yard - to Yurmoo under Trongsa Dzongkhag which will evacuate the power generated from NHPP. At Yurmo, it will be integrated into the Pothead yard of MHEP from where it will be evacuated to India through the MHEP transmission line system. The project is entirely for the purpose of power evacuation from NHPP and shall not entail construction of any access road or establishment of sub-stations.

3.0 Expected Impacts and Proposed Mitigation Measures

Protected area. The Environmental Assessment reveals that the Transmission line does not fall within any Protected Area, National Park, Wildlife Sanctuary, Strict Nature Reserve or Biological corridor. The line stretches from Nikachhu Pothead in Tangsibji gewog to the Mangdechu Pothead in Langthel gewog at a distance of 18.6 km.

Forest clearance. Along the transmission line (TL) route, a right-of-way (RoW) of 27 m needs to be cleared to prevent shorting and disturbance. The total amount of forest to be cleared is 100 acres or 0.5 km² (27 km x 15 km) within the project area. Field surveys of the TL confirms that 15 km of the line passes through broadleaf and mixed conifer forest while 3.6 km passes through scrub forest comprising of a few trees shrubs, degraded vegetation, community forest and private land. The biggest impact of any TL is usually the loss of forest cover (or vegetation) and the loss of habitat for wildlife. In the case of this TL however, the magnitude of this impact is lessened due to the following reasons:

- (i) The proposed 132 kV line is aligned almost parallel to the existing 66 kV line running from Trongsa to Yurmo and crosses the upcoming 400 kV D/C Mangdechu-Goling-Jigmeling transmission line as well. Thus, much of the alignment falls on an already semi-cleared forest land;
- (ii) The actual forest area requiring clearance is <0.03% of the total forest land in the Dzongkhag and largely insignificant considering the total forest cover in the district. Also, field investigations revealed that the selected route runs through forest which forms the

- buffer between the high forest on the hill tops and the villages and agricultural lands on the lower elevations. Due to its proximity to the villages, much of the forest is highly disturbed and it is not expected that it is the habitat of wildlife species;
- (iii) The forest area is already cleared so not much trees need to be felled along most of the alignment from TL27-TL50.

The main mitigation measure proposed to offset the reduction in forest cover is to undertake Compensatory Afforestation wherein twice the area of the forest (in this case 100 acres) should be replanted with local species of trees and shrubs.

Impacts on biodiversity. The removal of trees and other vegetation may have ecological impacts as it will destroy forest habitat and displace wildlife, birds, herpetofauna and insects. The forest being continuous especially above the highway provides good habitat for a variety of wildlife species but within the TL area, the most common wildlife species signs recorded were those of Wild Pigs, Barking deer and Sambar. These species are considered more as pests due to crop damage caused by these on neighboring agricultural fields. Other rarer species like Tigers, Leopards and Bears are expected in the denser, less disturbed forests on the higher slopes. Since the project does not lie within any protected area or biological corridor, it is not expected to hinder any migratory routes of such species, and the motility of most animals means that they are very likely to move away in response to the disturbance caused by the felling activity, thus avoiding accidental damage or death.

There is also a high diversity of birds in the project area. While there are Vulnerable species, the biggest constraint is the lack of information on the distribution, range and population of these bird species in Bhutan to adequately determine their population trends. Bird surveys revealed species such as Rufous-necked Hornbill (*Aceros nipalensis*), listed in the list of totally protected species in Schedule-I of the Forest and Nature Conservation Act, 1995 and categorized as *Vulnerable* (population trend decreasing) in IUCN. Other significant bird species include the Satyr Tragopan (*Tragopan satyra*) and the Yellow-rumped Honeyguide (*Indicator xanthonotus*) both listed as 'Near Threatened' (population trend decreasing) by the IUCN Red List (IUCN, 2014). The presence of many birds in these areas indicates that local disturbance is not significant. However, with increasing intrusion of workers, the risk of poaching is quite real, especially.

Mitigation measures proposed are aimed at:

- (i) Minimize forest clearance along the RoW by reducing the width of the RoW where conductors are strung from one slope to another across a valley, ensuring that clearance does not go beyond the approved width and only marked trees are felled;
- (ii) Leaving low trees, shrubs and ground vegetation to grow back to at least 2 meters height, which will provide cover for most wildlife that need to move through the right-ofway;
- (iii) Counter the loss of trees through habitat enhancement and planting suitable fruit trees at the edge of the RoW;

- (iv) Provide funds to the Department of Forest to conduct surveys in the forest areas to determine the distribution and population of rare and endangered bird species (to be prioritized by Forestry Office), and to conduct ecological studies to determine the precise habitat requirements, feeding, breeding and impacts on species distribution from habitat fragmentation;
- (v) All wildlife encounters must also be logged by the supervisor, wherever land clearing may result in encounters with wildlife and birds;
- (vi) Since this project forms a component of the NHPP rather than duplicating conservation efforts of the NHPP and MHEP, this project must tie up its conservation activities with the two projects and become part of their conservation programs which include; a) Establishing the Biodiversity Management Committee to prioritize conservation areas and programs; b) Rescue and Release Program c) Wildlife conservation program for capturing, treating/rehabilitating, and releasing wild animals found in pain or distress; d)Biodiversity Conservation and Management programs aimed at conserving and preserving natural ecosystems around the proposed project, and developing the information database on biodiversity at the project site.
- (vii)Measures to reduce poaching include a) awareness-raising of the existing laws, rules and penalties against poaching and prohibiting workers from indulging in such lawless activities; b) strengthen patrolling by forestry staff and involvement of locals in vigilance activities.

Land acquisition

There will be two kinds of land acquisition, permanent and temporary land requirement.

Permanent land requirement is only 0.6 acres, for the construction of 6 towers, which falls on privately owned dry land. In total this will affect 6 households that will lose 10 decimal of land each towards the footing of the transmission towers. All other towers will be located on Government Reserve Forest Land for which not land acquisition is required.

Temporary land requirement for Project work sites, worker campsites, storage of materials and machinery. These however are not expected to be much and impacts are transient in nature and land taken for these purposes will be handed over back to the Dzongkhag or Department of Forest on completion of the Construction work.

Mitigation. The direct impact of project land acquisition will be mitigated through Compensation which is guided by the "Land Compensation Rates (2009)" and the Land Act of Bhutan (2007). This will prevent any additional vulnerability for the affected households. If affected households are not satisfied with the proposed compensation, the grievance redress mechanism, based on the existing governance structure involving the Gewog Yargay Tshogchung and the Dzongkhag Yargay Tshogde can be activated.

To minimize the clearance of forest for temporary land use, Contractors must be encouraged to lease private land from land owners close to the project site. Where this is not possible,

especially for the worker camps in the forest, the Project, Forestry staff and Dzongkhag can collectively select areas that are already quite degraded and where not much forest clearance is required.

Once project construction phase is completed, contractor must follow Closure Plan before handing over the land back to the Dzongkhag.

Mobilization of vehicles, construction equipment and materials

The major materials to be mobilized are construction materials for tower excavation and footing and erection. Other materials are the insulators and conductors that are required for the evacuation of power. Since there are only 61 towers, the quantity of material required is low and all these can be easily dropped to the site by the Pre-construction phase.

The main impacts of mobilization of vehicles, construction equipment and materials is the risk of accidents, congestion on the Trongsa-Zhemgang highway, air pollution and potential "wear-and-tear" on the highway (damage) due to heavy truck traffic. Such impact shall not be significant due to the TL construction alone, since the number of vehicles required for the TL construction is significantly less.

The net impacts are deemed acceptable as these impacts will be temporary and can be mitigated through proper planning and sequencing of tasks to reduce these impacts.

Mitigation measures involve (i) (ii) use flag persons and signs to reduce congestion and warn travelers; (iii) encourage Contractors to plan and stage drop off of materials to avoid congestion; and to (iv) provision budget for making repairs to the National Highway and Access roads damaged by the project

Air Quality. With the current ongoing construction works of the Mangdechhu Hydropower Project, it is expected that air quality will be impacted due to cumulative impacts of additional machines and vehicles from the new Nikachhu project. The other sources of air contaminants will be from the additional worker camps where wood and kerosene may be the main fuel for cooking and heating, especially since these camps will be located away from access roads and LPG or electricity will not be readily available.

The net impact of the Project on Air Quality is small and transient, because air pollution will be generated at the sporadically spread worker camps and along the highway, and will be limited to the pre-construction and construction period.

A number of mitigation measures are recommended that include;

- (i) Ensuring that all vehicles and machinery meet Bhutanese regulations and standards for noise and vehicle emissions;
- (ii) Requiring trucks to be covered to avoid spillage; compacting;

- (iii) Providing the use of personal protective equipment including respiratory protection devices;
- (iv) Spraying water regularly on the access roads to reduce dust;
- (v) Prohibit burning waste vegetation;
- (vi) Establishing an ambient air monitoring program.

Noise, dust and access issues during vegetation clearing

Much of the noise generated will be during the felling of trees in the RoW and from the operation of construction equipment and movement of vehicles. Noise emanating from such activities may have some adverse impact on the ambient noise levels in the area. The clearance of forest for the RoW is expected to sometimes impede access for workers or wildlife. The impact from this however is small as it is localized and limited to the area along the RoW. For the most part, while these are unavoidable risks, they are not considered significant because the quantity of materials required are limited to basic tower structure materials like steel lattice, insulators, conductors and accessories.

Mitigation measures

- (i) Work times near villages must be limited to daylight hours (8am-6pm);
- (ii) Cordon off work sites and leave enough space for locals to move around these;
- (iii) All workers must also be required to wear PPE at appropriate times and locations;
- (iv) Contractors must not stock material also foot trails or access roads where access may be impeded.

Increase in demand for water resources

It is estimated that about 246 workers (14 management staff and 230 labourers) will be deployed at various locations along the Transmission line during the peak pre construction and construction period. Assuming usage of 50 litres of water per day for each worker (as communal kitchens and pit latrines are expected to be used), the total water requirement during peak construction period is 12,500 liters per day.

Water will also be required for sprinkling on roads to suppress dust and for foundation works at each tower location. The net impacts of the project activities on water resources small and transient, and drinking water can easily be sourced from streams crossing the TL.

Excavation of soil and impacts on surface water

With a total of 61 towers, the total amount of land required for tower footings is 12,810 m³ generating a total of 11,346 m³ of muck. The net impacts of the excavation and muck generation is small and transient, because not all tower sites are located on steep slopes or near streams, so excavation is not expected to cause large quantities of silt/soil to be washed into the river or streams during rain. Also, tower sites are dispersed and spaced at least 300m away from each other and will generate only 186 m³ of muck per site. Thus, there will be no large stockpiles of soil that could create a major point-source of silt pollution.

Mitigation measures

- (i) Locate all towers at a safe distance of 30m from water sources so that excavation work does not cause large quantities of soil to be washed into the streams;
- (ii) Stockpile all excavated muck at a safe distance from the foundation site, to minimize the risk of soil falling back into the pits, or blocking access to the pit;
- (iii) Dump and compact unused remaining muck nearby and revegetate through the Compensatory Afforestation Program;
- (iv) Contamination of water. Linkages between the project and groundwater are difficult to predict, but are expected to be minimal. The major source of contamination of water sources is from the workers camps since there will be no requirement for fuel storage and risks of fuel spills. Thus the impacts on aquatic habitats are minimal as most streams are fast flowing and any sediment or pollution will be quickly flushed out;
- (v) Any intrusion or contamination of sediments is avoided by locating towers 30-50m away from water sources so no impacts on aquatic habitats or fish are anticipated. Also all water required will be properly sourced through pipes and storage tanks. No washing of clothes, dishes or cars in the streams will be permitted, and pit latrines will be located far away from water sources.
- (vi) Water quality monitoring will be conducted at key streams along the alignment at least twice a year.

Risk of slope instability

The concern for slope stability only arises where excavation work is carried out at localized tower sites. Since the economic and technical consequences of slope instability are significant for the Project, this risk will be adequately addressed during the design and planning phase through detailed investigation of the geotechnical hazards and soil of each tower footing site to ensure that there are no risks associated with stability of tower foundations. The site reconnaissance survey report indicates that there are no geological disturbances on any segment of the TL alignment.

Mitigation Measures

Detailed investigation of the geotechnical hazards and soil of each tower footing site to ensure that there are no risks associated with stability of tower foundations. Tower footings will be located at stable locations.

Blasting. Blasting is not anticipated but may be required at Tower sites where foundations need to be dug in difficult geology. If this is so, the impacts of blasting will be localized at such sites, which are away from local communities. Disturbance from blasting will thus be localized and transient during pre-construction and construction. Construction activities such as excavation, concreting, tower erection, backfilling, use of pumps (for pumping excess water) and compressors, etc.; might result in noise levels in the surrounding area.

Social Impacts.

Impacts from influx of workers. Only about 246 workers, at the maximum, shall be deployed during the peak construction phase of the project when most of the works such as tower erection, foundation laying and sagging are carried out simultaneously. Since, for transportation of material no access road shall be constructed, all the equipments and materials shall be transported by manual head loading for which most of the laborers shall be required.

The main concerns with an influx of workers include:

- (i) Possible social instability;
- (ii) Increased pressure on housing, infrastructure, and services;
- (iii) Risk of communicable diseases spreading in the local community;
- (iv) Waste and sewage entering the local environment;
- (v) Health concerns in the camps (communicable diseases, poor air quality), and
- (vi) Safety issues at the work sites.

Mitigation measures against the risk of communicable diseases spreading in the local community include (i) Screening and regular unannounced checking of workers, and (ii) conducting sudden, unannounced checks on workers to look for diseases such as HIV, STDs, and hepatitis.

To reduce the pressure on housing, infrastructure, and services, the Contractor must provide proper sitting and design of the temporary worker camps that takes into account drinking water storage tanks; communal kitchens; pit latrines and soak-aways (as far away from watercourses as possible), proper site drainage; a solid waste storage area (for onward transfer to the local landfill). Other important requirement are LPG gas, kerosene, or fuel wood for cooking.

The Occupational Health and Safety program will aim to ensure that the workplace is safe and healthy. Other measures include addressing the hazards and risks at the workplace; nominating focal health personnel; outlining the procedures and responsibilities for preventing, eliminating and minimizing the effects of those hazards and risks; identifying the emergency plans for the workplace or workplaces; providing Personal Protective Equipment for workers and ensuring awareness on safety at the work place.

Workers must also be briefed on code of conduct and behavior towards the host community as well as penalties for illegal activities such as hunting.

When the project construction is completed, worker numbers will decrease significantly, just leaving permanent project staff, so all positive and negative impacts associated with an influx of workers will be transient. Campsites should also be cleared at the end of their occupation, all temporary structures demolished, pit latrines covered up, all materials removed and the area revegetated and allowed to grow back to its natural state.

Impacts on Cultural and Religious Sites

There are a few religious and cultural sites within the project area but it is expected that there will be no impact on Cultural and Religious sites because during design stage extra care was

taken to ensure that religious structures/ public property were avoided. No Transmission towers are located adjacent to such sites and the Transmission line will not in any way or manner hinder any religious or cultural practices.

Mitigation Measures include consulting all affected communities and custodians of monasteries, lhakhangs, and nunneries in advance to inform them of the purpose, nature, duration, extent and timing of all work in and around their village, and explain to them the purpose of the Project and its activities along with the work plan and schedule of activities.

All work must be planned to avoid sensitive times (such as key dates in the religious calendar, festivals etc).

Visual impacts

The main negative impact on visual aesthetics in the project area will occur during construction, as a result of clearing, site work, and heavy equipment and vehicles on the road. Specifically to this Transmission Line (TL), the visual impacts are not expected to be significant because the TL is aligned parallel along the already existing 66 kV line from Trongsa to Yurmo. Only TL 27 to TL 31 shall be visible from the national highway. While the forest itself could provide a good natural screen to hide the TL from the highway, this is difficult as the hilly terrain makes the TL line quite visible.

Mitigation measure

Developing a greenbelt along the highway will allow for enhancing forest habitat as well as providing a good natural screen while also achieving slope stability, reducing soil erosion and reducing air pollution. These areas will be demarcated and handed over to be replanted under the Compensatory forestry program.

Economic Impacts. The project is expected to have a positive impact as far as opportunities for income generation for project-displaced households is concerned because it is expected that the influx of workers for both the Hydropower Component and the TL component will substantially increase the demand for locally grown vegetables, crops and dairy products as well as provide employment opportunities within the project for implementation of various components such as construction work, forest clearance, slope stabilization, afforestation which require little or no education.

Potential economic impacts that are associated with the mobilization of construction equipment and vehicles include potential "wear-and-tear" on the highway (damage) due to heavy equipment and truck traffic for the main project compinent. This will result in increase in maintenance and repair costs both to the project as well as the Ministry of Works and Human Settlement.

Impacts during Operation Phase

Economic Impacts: Decrease in Income opportunities

The routine maintenance of the RoW will not have any negative economic impacts as it will not affect agricultural areas or farm roads used by locals for transporting produce. If a line failure requires the repositioning of Towers, it should not be necessary to purchase land for the new foundations, as the new foundations maybe dug close to the old ones, involving the same land owners so exchange of land can be possible and the previously used area can be returned.

At the local level though, once the major construction works are completed, and as contractors and migrant workers leave, there will be a huge decrease in demand for agricultural products such as vegetables, dairy products etc.

At the national level, the evacuation of power from the Mangdechhu will have significant positive economic impacts for the country in terms of increasing its income generation from the sale of power to India.

Mitigation measures include ensuring (i) prior briefing by Project on project duration and scheduling at the outset of the project, (ii) assisting farmers to increase productivity on newly compensated land; and (iii) revenue sharing arrangements

Reduced pressure for local resources.

With the removal of workers from site, no negative social impacts are anticipated. Instead, the local district authorities will benefit positively due to reduced pressure on health, water, resources such as LPG, kerosene, diesel and fuel wood, as well as reduced incidences of poaching, and anti-social activities.

Risk of electrocution and accidents during maintenance works.

The main hazard to people from the operation and maintenance of the completed TL system is the risk of electrocution. All workers are exposed during the performance of their duties such as repairing towers, transmission lines and its associated components. Locals can also be at risk especially as they are unaware of the risks and potential hazards which make them vulnerable to the danger of electrocution.

Mitigation measures include following the Operation and Maintenance procedures and Occupational Health and Safety Guidelines issued by BPC for the O& M of all Transmission lines in the country. This must also include securing the workplace, wherein all lines are shut down prior to maintenance work, use of PPE and procedures for emergencies and compensation procedures in case of accidents.

Electromagnetic Field (EMF)

The impacts of EMF are considered during the design stage and mitigation options for Transmission lines. This includes increasing the distance of local communities, populated areas, other occupied buildings and wildlife and vegetation from the EMF source.

There is no specific regulation on EMF for high voltage transmission line in Bhutan. According to Safety Code 2008 issued by Bhutan Electricity Authority, the clearance of 132 kV line should be 2.1 m horizontal and 5.5 m vertical distance from any buildings. Since the entire stretch of 132 kV transmission lines of NHPP will not traverse settlements, it does not violate any such safety requirements.

Mitigation measures include following the minimum distance requirements for a RoW; minimum clearance of 6.1 m from the ground vegetation or moving workers and wildlife; minimum distance has to be maintained for line crossings at different voltage levels (66 kV, 132 kV and 400 kV). Other options include phase cancellation, conductor separation, vertical double circuiting, selection of conductor and OPGW and spacing and clearance from live metal to earthed metal

Risk and hazard associated with TL

The transmission line runs parallel to the existing 66 kV line that has been in operation for over 7 years. Thus far, there has been no record of incidents related to landslides or earthquakes damaging the existing 66 kV line. The TL will be designed following the national and international (as applicable) standards required by incorporating a margin of safety to withstand natural disasters such as earthquake.

Mitigation measures include a) selection of stable tower foundation areas during design and survey stage; b) regularly cut overhanging trees that could fall on the Transmission line during during an earthquake or landslide; c) enforce appropriate building codes and infrastructure design; d) raise public awareness about disasters, their risks and ways to cope; e) develop emergency protocols; and, f) conduct regular check and maintenance.

Environmental impacts of RoW maintenance

Maintaining the RoW through regular clearing and repairing faults along the line will have no new major ecological impacts because there are no additional physical impacts. Maintenance work will be very small in scale and infrequent, and involves few changes to the existing situation.

Mitigation measures include (i) scheduling of work to avoid disturbing wildlife and birds during such maintenance works; (ii) public education on the risks of tampering with the towers and TL lines and (iii) provide prior notice to locals about Operation and Maintenance work being carried out in their areas, they may be more amenable to disturbance.

Electrocution of raptors and other large birds

While there has been no documented evidence in Bhutan that existing transmission lines have caused electrocution of large birds, this risk needs to be considered. The impact of electrocution of birds depends on the electro- technical design of the pylon and the natural features surround it.

Mitigation measures to minimize the risk of electrocution include (i) construction of cage box on conductors to prevent birds from sitting or making nest on the towers; (ii) Placing colorful/fluorescent tape on the towers to make them conspicuous; (iii) aligning the TL close to the 66 kv line which reduced the need for birds to duck two power lines at the same time; (iv) ensuring sufficient phase-to-phase and phase-to ground wire spacing; (v) using silhouettes of predators (falcon/hawk) as scaring devices for repelling bird; and (vi) working closely with the Department of Forest to collect information on any reports of bird collisions/accidents due to the TL.

4.0 Analysis of alternatives

The preliminary assessment of the project includes an analysis of various project alternatives, addressing the optimal match between required technical specifications and site conditions, especially geological stability, as well as addressing any concerns for environmental, social, and economic features in each location.

1st Option: The proposed 132 kV transmission line with 18.6 km and 19.2 km respectively is aligned mostly in the Government Reserved land/forest with only 6 towers within private land and community forest. The preferred route, 18.6 km was diverted via Raphey top crossing the existing 66 kV line at T7 and T8.

2nd Option: The second option after crossing 66 kV line at T7 and T8 runs parallel to 66 kV line and crossing upcoming 400 kV D/C Mangdechu-Goling-Jigmeling transmission line and finally enters the Mangdechu Pothead yard.

The "Do Nothing" Alternative

The "do nothing" alternative is not viable as it is absolutely necessary to have a transmission line to evacuate the power generated in NHPP. Without this associated transmission line, the NHPP is incomplete.

The first option was chosen due to the following reasons:

- (i) Environmental impacts of the length of the transmission line: 2nd option is 19.2 km which is 0.6 km longer than the 1st option entailing an additional 5 acres to be cleared for the RoW.
- (ii) Social impacts on private land: In the 2nd option, an additional 4 towers fall within a wetland at Yurmoo village whereas the 1st option will have 6 towers in dryland. Thus, the number of affected parties is much lower in the 1st option compared to the 2nd option.
- (iii) Technical reasons: The terrain along the route of the 1st option was found to be comparatively moderate than the 2nd option.

5.0 Conclusions

The environmental assessment of the TL indicates that there are no significant adverse economic, environmental, and socioeconomic impacts associated with the 18.6 km transmission line route due to the following reasons:

- (i) The TL alignment does not fall within any environmentally-sensitive, protected area, or biological corridor of the country.
- (ii) Although the length of the TL is 18.6 km, most part of the alignment falls within forest areas located close to the local community, is heavily disturbed, and is not relatively dense. Trees that have to be cut will be replaced in a larger re-vegetated area, and land that is required for the project will be compensated.
- (iii) One of the major criteria for selection of the TL alignment is to minimize, as far as possible, the need for forest clearance and the acquisition of private land. Almost 90% of the alignment runs parallel to the existing 66 kV line from Trongsa to Yurmo, where the forest is already cleared.
- (iv) Most of the construction work is small in scale (involving the excavation of small pits for the tower foundations and erection of towers and stringing of conductors) and will be conducted by small teams of workers without the use of heavy vehicles and machinery. Construction work is relatively straightforward and can be completed in a fairly short time (17 months).
- (v) Most of the impacts are temporary and occur only during the pre-construction and construction phase. These impacts are social and environmental impacts arising from construction works and operation of worker camps, impacts on health and safety, waste generation, increase in demand for resources (fuel, water, space) and services, impacts on air quality and noise from increase in traffic, and impacts on water quality from excavation works. These impacts will be temporary and will be over once the Construction period is complete.
- (vi) Only 6 households are affected due to the location of 6 towers requiring 10 decimal of dryland. No relocation is required and no other infrastructure will be affected.

The Bhutan Power Corporation has gained significant experience with similar projects in other parts of the country and is well equipped to cope with the risks that may arise during operation and maintenance works. The project will bring significant power service reliability to Bhutan and local and national economic benefits, as well as significant greenhouse gas emission reductions.

The overall conclusion of this process is that providing the mitigation, compensation and enhancement measures are implemented in full, there should be no significant negative environmental impacts as a result of location, design, construction or operation of the subproject. There should in fact be some small benefits from recommended mitigation and enhancement measures, and major positive economic impacts for the country once the scheme is in operation.

The total estimated environmental management cost of the Project is Nu. 143 million. An additional budget of Nu. 7. 8 million is earmarked for environmental mitigation and monitoring for the transmission line.

The EIA was prepared based on the ToR approved by the NEC and in accordance with SPS 2009. The environmental assessment was based on findings from field investigations and

ocular inspection, secondary data from sources such as feasibility studies and design of NHPP and MHEP, and from public consultations.

1 Introduction

1.1 Background

- 1. Bhutan's technically feasible hydropower generation potential is estimated to be 23,760 MW. At present, only about 5% (or 1,488 MW) of this generation potential has been harnessed. Export of hydropower is the largest revenue source for the Government of Bhutan (RGoB) accounting for over 45% of its national revenues. A total of 10 projects (about 10,000 MW) have been selected jointly by RGoB and the Government of India (GoI) for hydropower development by 2020. These 10 projects have different implementation modalities such as bilateral development by RGoB and GoI, and by joint ventures between government corporations of the two countries. Hydropower development in Bhutan is considered to be a source of 'clean power' due to its minimal contribution to greenhouse gas (GHG) emissions compared to conventional energy sources.
- 2. Recognizing the need to develop the hydropower potential, the Asian Development Bank (ADB) provided in October 2011 a technical assistance to prepare the 118 MW Nikachhu Hydropower Project (NHPP). NHPP is a medium-sized run-of-river (ROR) hydropower type which will have lesser degree of environmental and social impacts compared to reservoir types. The power generated by NHPP will be evacuated by a 18.6 km 132 kV D/C transmission line running to Yurmo, where it will be integrated into the pot head yard of MHEP. Farther power transmission to India shall be through the MHEP power transmission system. The associated transmission line, with an estimated amount of Nu. 233.836 million.
- 3. NHPP will be located in Trongsa District and will draw water from the Nikachhu River and will discharge its tailrace water above the dam of the Mangdechhu Hydropwer Project (MHEP). The NHPP will be constructed over a 5-year period and expected to be operational by 2019.
- 4. Druk Green Power Corporation Limited (DGPCL), established in 2008 and mandated to accelerate hydropower development projects, will implement the NHPP. DGPCL currently operates five power plants with an installed capacity of 1,480 MW.

1.2 Purpose of the report

5. The EIA has been prepared based on the Terms of Reference (ToR) endorsed by the National Environment Commission as required by the Environmental Assessment Act 2000 and in accordance with the Safeguard Policy Statement 2009 (SPS 2009) of ADB.

1.3 Extent and scope of the study

6. Bhutanese law and SPS 2009 require that the environmental impacts of development projects are identified and assessed as part of the planning and design process, and that action is taken to reduce the impacts to acceptable levels. This is done through the environmental

assessment process which has become an integral part of lending operations and project development and implementation worldwide.

- 7. This report discusses the existing environment within the project's area of influence, environmental impacts and mitigation measures relating to the location, design, construction and operation of all physical works that will be covered by the associated transmission line for NHPP.
- 8. As required by the Environmental Assessment Act 2000 and its Regulation 2002, a ToR providing the scope and framework for conducting the EIA of the 18.6 km 132 kV D/C transmission line (TL) for NHPP was submitted to the NEC and was subsequently approved. The TL will start from Nikachhu Pothead Yard to Mangdechhu Pothead Yard and is under Trongsa Dzongkhag.
- 9. Based on the approved ToR from the NEC, the EIA was prepared. The level of detail and analysis in the report reflects the potential environmental, economical and social impacts of the proposed project and recommends mitigation and management plans for the likely adverse environmental impacts. Along with the EIA, other documentation and clearances required that are under process include the following:
 - (i) Forest Clearance from the Department of Forest and National Park Services for vegetation clearing along the 27 m right-of-way (RoW);
 - (ii) A report on the public consultations held to discuss issues and concerns related to the NHPP including the TL;
 - (iii) Reports on separate consultations held with affected people along with their signatures of 'No Objection' for the TL; and,
 - (iv) Clearance from the Local District Authorities, Trongsa Dzongkhag for executing the project.

1.4 Structure of the Report

10. Following the SPS 2009, the Report is structured as follows:

Executive Summary

Chapter 1 *Introduction* provides the background on the project, environmental clearance applicant details, and the scope of work.

Chapter 2 *Policy, Legal, and Administrative Framework* presents a review of relevant national laws and policies, international environmental obligations, and ADB's environmental requirements.

Chapter 3 Description of the Project provides a brief description of the Project, the location, size and need, description of project components, implementation schedule and staffing requirements.

Chapter 4 *Analysis of Alternatives* presents the two alternatives considered during the feasibility study in order to arrive at the best option.

Chapter 5 Description of the Environment includes details on the baseline data for environmental conditions in the project area (current features and conditions, pre-project) including the methodology used to obtain the baseline data.

Chapter 6 *Anticipated Project Impacts* identifies the potential environmental, economic and social impacts from pre-construction, construction, and operation phase.

Chapter 7 Environmental Mitigation and Management Plan

Chapter 8 Environmental Monitoring Program and Institutional Responsibilities outlines the environmental monitoring program, institutional responsibilities including the cost of implementing the EMP

Chapter 9 Grievance Redress Mechanism describes the process of addressing complaints

Chapter 10 *Information Disclosure, Consultation, and Participation* discusses the issues raised during the consultations, proposed actions to address them, and the information needed to disclose to the public.

Chapter 11 References

Annexes

2 Policy, Legal, and Administrative Framework

2.1 National Laws and Regulations

- 11. Sustainable development is enshrined in the policy of RGoB through the *Middle Path* approach of its National Environment Strategy for Bhutan (1998) which aims to maintain a balance between environment and development. One of the key implementing mechanisms is the Environmental Assessment Act (2000) which establishes procedures for assessing the potential impacts of plans, policies, programs and projects. It also establishes that Environmental Clearance (EC) must be obtained from the National Environment Commission (NEC) or other Competent Authority for any project or activity that may have adverse environmental impacts.
- 12. A number of Acts and Regulations are pertinent for this Project. A brief summary of these is as follows:

1. Forest and Nature Conservation Act 1995

- 13. The Bhutan Forest Act 1969 was repealed in 1995, with the enactment of the Forest and Nature Conservation Act (FNCA) 1995, in keeping with evolving conservation needs and to allow for community stewardship of forests. The objective of the FNCA is to "provide for the protection and sustainable use of forests, wildlife and related natural resources of Bhutan for the benefit of present and future generations". The act covers forest management, prohibitions and concessions in government reserved forests, forestry leases, social and community forestry, transport and trade of forestry produce, protected areas, wildlife conservation, soil and water conservation, forest fire prevention, and enforcement and penalties.
- 14. Protected areas are regulated under this act in Bhutan. A protected area is an area that has been declared to be a national park, conservation area, wildlife sanctuary, wildlife reserve, nature reserve, strict nature reserve, reserve forest, or critical watershed. Other protected areas include areas for the preservation of natural beauty of national importance, protection of biological diversity, management of wildlife, conservation of soil and water and related purposes. A Protected Area includes various management zones classified as: core zone, buffer zone, administrative zone, seasonal grazing zone, enclave zone, and multiple use zones. Schedule I of the Act provides a list of wild animals and plant species that needs full protection in Bhutan.
- 15. Among others, the Forest and Nature Conservation Rules (FNCR) 2000, allows for: declaration of protected areas (PA), administration of PAs, and prohibitions in PAs; and for protection of wildlife and use of certain wild species.

2. The Forest and Nature Conservation Rules of Bhutan, 2006

- 16. This came into force with effect on September 1, 2006 and supersedes all relevant rules and regulations, notifications, circulars and instructions existing as of August 31, 2006. Chapter III describes regulations related to Government Reserved Forests. For any developmental activity in a Government Reserve Forest, the proponent is required to seek Forestry Clearance from the Respective Divisional Forest Office in the District (there are 12 Forest Divisions and 9 Protected Areas). The proposal after being reviewed in the field by the District Forest Officer (now known as Chief Forestry Officer) is forwarded to the Department of Forest and Park Services where the final Clearance is granted based on the field review.
- 17. Once clearance is granted and the Project is ready to commence, the trees to be cut are marked by the field staff. Marking or felling of trees within 100 feet of the bank or edge of any river, stream, and watercourse or water source; Marking or felling of trees within 600 feet uphill and 300 feet downhill of any motor road or Felling from any place where the slope is greater than 45° is restricted. By law, no trees may be felled it if has not been marked by a designated Forestry staff.

3. The Environment Assessment Act (2000)

18. This act requires the government to ensure that environmental concerns are considered when formulating, renewing, modifying and implementing any policy, plan or programme. Issuance of an environmental clearance is to be a prerequisite to the issuance of any development permit.

4. Regulation for the Environmental Clearance of Projects 2002

- 19. The EC procedure is described in the Regulation for the Environmental Clearance of Projects (2002), and specific guidance is given in a series of sectoral guidelines, prepared in 1999 and revised with ADB assistance in 2006. For any developmental activity, the proponent is required to submit an EC Application, containing information on the applicant, the project, funding agency, the affected environment, potential impacts, mitigation, monitoring and public consultation. The NEC considers the application and issues or denies EC, or decides that a full EIA is necessary.
- 20. For all transmission lines above 33 kV, NEC requires an EIA to be conducted irrespective of whether the projects falls in a protected area buffer zones or biological corridors. The proponent, the DGPCL in the case of this project submits a proposed Terms of Reference (ToR) to NEC, and then conducts the EIA study and prepares the report according to the approved ToR. NEC will then review the completed EIA report and decide whether Environmental Clearance is granted or denied based on an EIA presentation conducted by the proponent and the field visits conducted by the NEC review team. EC may include certain conditions with which the proponent must comply, which would include some or all of the mitigation proposed in the EIA or EC Application, plus other measures if necessary.
- 21. The NECS or CA may issue EC based on the following: (a) the effects of the project on the environment are foreseeable and acceptable; (b) the applicant is capable of carrying out the

terms of EC; (c) the project, alone or in connection with other programs/ activities, contributes to the sustainable development of the Kingdom and the conservation of its natural and cultural heritage;(d) adequate attention has been paid to the interests of the concerned people; and, (e) the project is consistent with the environmental commitments of the Kingdom.

- 22. As per Article 16 of the act, public consultation is mandatory. EC for a project shall be reviewed and may be revised and renewed at least every five years, unless a shorter period is stated. The NECS or CA may review and modify the terms whenever there are: (a) unacceptable risks to the environment resulting from the project which were not known at the time the clearance was issued; (b) availability of improved and cleaner technology; and, (c) a need to bring the project into compliance with changes to the laws of the country.
- 23. Non-compliance with environmental terms specified in the issuance of environmental clearance makes the offender liable to penalties that may include compensation for environmental damage, fines, sanctions, and suspension or revocation of environmental clearance in part or full. The applicable time limit that will be required to obtain environmental clearance is provided in **Table 2.1**.

Table 2.1: Applicable time limits to obtain environmental clearance

Works	Time limits
Response by National Environment Commission Secretariat on the receipt of application. This is simply an acknowledgement of the receipt of the application.	Within 15 days
Review by the Secretariat to assess the adequacy of the application as per government rules and guidelines.	30 – 90 days
Decision/Response on the environmental clearance, based on the findings of the Environmental Assessment report.	30 – 90 days
Public notification on decision by the Secretariat/Competent Authority.	Within 15 days
Appeal on decision by public.	Within 30 days
On approval of the clearance, a legal undertaking with the proponent of new projects to comply with the EA Act, 2000.	10 – 30 days
Maximum time required to get EC	270 days

5. The Biodiversity Act (2000)

24. Among the many objectives of this Act, the relevant ones are to ensure the conservation and sustainable use of the biological and genetic resources; to promote the equitable sharing of benefits derived from the use of genetic resources, to recognize and protect traditional knowledge, innovation and practices of local communities associated with biodiversity and to promote technology transfer and capacity building relevant to the conservation and sustainable use of biological diversity;

6. National Environment Protection Act 2007

25. The National Environment Protection Act (2007) outlines principles and a legal framework that have implications for forest governance and management. It requires that a person taking natural resources from the environment, or deriving economic benefits from it, should ensure sustainable use and management of the resources and ecosystems

7. Mines and Minerals Management Act, 1995

26. The relevance of this Act for a hydropower project is when the project requires quarries for sand or stone; this law is enforced to get the site clearance. However, since this TL project does not require any quarries, it is not necessary to seek clearance from the Department of Geology and Mines, the Competent Authority over all Mines and Minerals in the Country.

8. The Road Act, 2004

27. The Act establishes a framework to ensure balanced socio-economic development, promote social equity, and define and establish an efficient system of road networks. According to the Act, the construction of access roads for a hydropower project falls directly under the jurisdiction of Ministry of Economic Affairs, and termed as a power road. If there is a need to construct access roads that take off from the National Highway, a Clearance is required from the Ministry of Works and Human Settlement. In this project, there are no new access roads to be constructed so No clearance is required.

9. Bhutan Electricity Act, 2003

28. This act provides a framework for licensing and regulating the operations of power companies. Under this act, the Bhutan Electricity Authority has been established as an autonomous body and the custodian for enforcing this act. The Electricity Act provides power to acquire land and water for generation and supply of electricity.

10. Waste Prevention and Management Act 2009 and Waste Prevention and Management Rules, 2012

29. This Act clearly states that: all developmental activities that generate waste shall be planned and executed in harmony with the carrying capacity of the country's fragile ecological settings and geographical terrains, in line with the concept of 3 Rs (Reduce, Reuse and Recycle). Any person polluting the environment or causing ecological harm shall be responsible for the costs of avoidance, containment, abatement, medical compensation, mitigation, remediation and restoration. Implementing agencies shall ensure that the minimization, storage, treatment and disposal of hazardous waste are addressed in an environmentally sound manner.

11. The Local Government Act of Bhutan, 2009

- 30. This Act repeals the Local Government Act 2007; Thromde Act 2007; Dzongkhag Yargay Tshogdu Chathrim, 2002; Gewog Yargay Tshogchung Chathrim, 2002. According to this Act, local Governments shall comprise the following categories:
- 31. The Dzongkhag (District) Tshogdu shall be the highest decision making body in the Dzongkhag. It shall comprise the Gup and Mangmi as the two elected representatives from each Gewog, one elected representative to represent the Dzongkhag Thromde and one elected representative to represent the Yenla Throm.
- 32. The Gewog (block) Tshogde (Committee) shall be the highest decision making body in the Geog. It shall comprise the Gup, Mangmi and Tshogpas.
- 33. Under this Act, the Dzongkhag and Gewog Tsogde must ensure the provision of such social and economic services for the general wellbeing of the residents of the communities in a sustainable and equitable manner; Local Governments shall be supported by the Government to promote holistic and integrated area-based development planning.

12. Bhutan Sustainable Hydropower Development Policy 2008

- 34. The key objectives of the policy are to:
 - (i) Mobilize funds and attract investments for accelerated hydropower development.
 - (ii) Enhance the revenue contribution to the Royal Government.
 - (iii) Contribute to socio-economic development.
 - (iv) Ensure domestic electricity supply security and reliability.
 - (v) Ensure that the hydropower development is in accordance with the sustainable development policy of the Royal Government, keeping in view the fragile mountain ecosystem of the country.
 - (vi) Contribute towards development of clean energy to mitigate problems related to global warming and climate change.
- 35. Listed under the Institutional Arrangements of the Hydropower Sector in this policy document, DGPCL is responsible for managing all hydropower plants fully owned by the Royal Government. It will also develop projects on its own, through joint ventures on behalf of the Royal Government as may be directed. The policy document stipulates that projects funded through bilateral assistance shall continue to be managed and supervised by the MoEA through formation of project authorities. Such fully Government-owned generating plants shall be handed over to DGPCL when the Project Authority is dissolved.

13. The Water Act of Bhutan, 2011

36. This Act applies to all issues related to water resources with the objective to ensure water is protected, conserved and/or sustainably managed through Prioritization of water use, Protection of Water Catchments, Development of National Integrated Water Resources Management Plans for the conservation, development and management of water resources, river basins, ensuring Minimum Environmental Flow requirement of Rivers, Prohibition to

abstract or use water without Environmental Clearance (except for exemptions) and ensuring Prevention and Control of Water Pollution.

14. Rules and Regulations on Occupational Health and Safety 2006

37. The purpose of the OHS Rules and Regulations is to assure safe and healthful working conditions for workingmen and women, as well as other persons present at workplaces, and protect them from work-related risks to their health, safety, and well-being. The rules apply to all employers and workers (both Bhutanese and non-Bhutanese) of licensed manufacturing, mining and service enterprise, construction companies, bodies corporate incorporated under the Companies Act 2000 of the Kingdom of Bhutan, and any other agency employing large numbers of workers at the work site.

Table 2.2: List of applicable acts and regulations for the Project

No.	Acts/ Regulations	Pre- Construction phase	Construction Phase	Operation Phase
1	The National Environment Protection Act 2007	Y	Y	Υ
2	Forest and Nature Conservation Act 1995	Y	Y	Υ
3	Forest and Nature Conservation Rules 2006	Y	Y	Υ
4	Environmental Assessment Act 2000	Y	Y	Υ
5	Regulation for the Environmental Clearance of Projects 2002	Y	Y	Y
6	National Environment Protection Act 2007	Y	Y	Υ
7	Land Act (2007) Cash Crop Compensation Rates (1996) and PAVA Rates (2009).	Y	Y	N
8	Mines and Minerals Management Act, 1995	N	N	N
9	The Road Act, 2004	N	N	N
10	Bhutan Electricity Act, 2003	Y	Y	Υ
11	Waste Prevention and Management Act, 2009	Y	Y	Υ
12	Waste Prevention and Management Rules, 2012	Y	Y	Y
13	The Local Governance Act of Bhutan, 2009	Y	Y	Υ
14	Bhutan Sustainable Hydropower Development Policy 2008	Y	Y	Y
15	Biodiversity Act, 2003	Y	Y	Υ
16	The Water Act of Bhutan, 2011	Y	Y	Υ
17	Rules and Regulations on Occupational Health and Safety, 2006	Y	Y	Y

2.2 Applicable Guidelines and Standards

38. A number of guidelines and standards have been notified or issued by line ministries and departments in Bhutan in order to ensure compliance. The guidelines and standards relevant to the current project are noted below.

1. Environmental Discharge Standard 2010

39. National ambient air quality standards establish upper limits on the concentration of air pollutants in outdoor air, for the protection of human health, agriculture, natural vegetation and ecosystems, and the environment in general.

Table 2.3: Ambient air quality standards (maximum permissible limits in $\mu g/m^3$) NECS Bhutan (2010)

Parameter	Industrial Area	Mixed Area*	Sensitive Area**
Total Suspended Particulate Matter			
24 Hour Average	500	200	100
Yearly Average	360	140	70
Respirable Particulate Matter (PM 10)			
24 Hour Average	200	100	75
Yearly Average	(World Bank/WHO = 150)	60	50
	(World Bank/WHO = 70)		
Sulfur Dioxide			
24 Hour Average	120***	80	30
Yearly Average	80	60	15
Nitrogen Oxides			
24 Hour Average	120	80	30
Yearly Average	80	60	15
	(World Bank/WHO = 40)		
Carbon Monoxide			
8 Hour Average	5,000	2,000	1,000
1 hour Average	10,000	4,000	2,000

^{*} Mixed Area means an area where residential, commercial, or both activities take place.

Table 2.4: Motor vehicle emission standards

Fuel Type	Vehicle registered prior to Jan 1, 2005	Vehicle registered after Jan 1, 2005	Type Approval
Petrol (%CO)	4.5	4	
Diesel (%HSC)	75	70	Euro-II

^{*}Sensitive Area means an area where sensitive targets are in place, like hospitals, schools, sensitive ecosystems.

^{*}Exceeds (better than) WHO/World Bank guidelines.

Table 2.5: Environmental standards for noise

Land Use	Maximum Level				
Category	Day	Night			
Industrial Area	75 dB	65 dB			
Mixed Area	65 dB	55 dB			
Sensitive Area	55 dB	45 dB			

40. Noise standard as per land use Category 2. World Bank noise guidelines are 70 dB day and night for industrial areas, and the same as Bhutan guidelines for sensitive areas.

Table 2.5: Checklist of compliances required for the Project

No.	Agency/Concerned Person	Why/When	Sought?
1	Trongsa Dzongkhag	Administrative Approval from Dzongkhag	Yes
2	Department of Forest and Park Services	Should the project damage or acquire Tsamdo	Yes
3	Department of Culture	Should the project be located within 50 m of a cultural or religious site	Not required
4	Private Owners	Should the project need to acquire private property	Yes
5	Public Consultation	Project is impacting their gewog	Yes
6	Department of Health	Within 50 m of a hospital	Not required
7	Department of Education	Within 50m of a school	Not required
8	Department of Roads	Should the project require access from highways and feeder roads	Not required

2.3 International Agreements and Conventions

41. RGoB is well represented in the international and regional environmental arena as part of its commitment to environmental conservation and protection. The National Environment Commission Secretariat, as a key environmental policy making body/nodal agency of the country, participates in various international meetings relating to conventions and agreements that Bhutan has signed or ratified. Bhutan is party to Multilateral Environmental Agreements as given in Table 2.6.

Table 2.6: International Commitments and Dates of Ratification

No.	International Commitments	Instrument of Ratification
1	UN Framework Convention on Climate Change	1995
2	UN Convention on Biological Diversity	1995
	Convention on International Trade in Endangered Species of Wild Fauna and	2004
3	Flora (CITES)	
4	Kyoto Protocol to the United Nations Framework Convention on Climate	2005

No.	International Commitments	Instrument of Ratification
	Change	
5	Cartagena Protocol on Biosafety (the Convention on Biological Diversity)	
6	Basel Convention on the Control of Transboundary Movements of Hazardous Wastes and their Disposal Bhutan became a party in 2004.	2002
7	UNESCO World Heritage Convention	2001
8	International Plant Protection Convention (Adherence)	1994
9	The Final Act and the Law of Sea Convention	1982
	Statute of the Centre for Science and Technology of the Movement of Non-	
10	Aligned Countries and other Developing Countries	1985
11	Statutes of the International Centre for Genetic Engineering and Biotechnology	1985
12	Vienna Convention for the Protection of the Ozone Layer;	2004
13	United Nations Convention to Combat Desertification (UNCCD)	2004

2.4 Environmental Requirements of ADB

42. The SPS 2009 of ADB provides guidance on the environment category of projects based on the degree of anticipated environmental impacts. The initial process of categorization involves filling out a sectoral Rapid Environmental Assessment (REA) checklist. A project is classified as one of the four environmental categories (A, B, C, or FI) based on the most environmentally sensitive component. Categories are as follows:

Category A: Project that is likely to have significant adverse environmental impacts which are irreversible, diverse, or unprecedented. These impacts may affect an area larger than the sites or facilities subject to physical works. An environmental impact assessment (EIA), including an environmental management plan (EMP), is required.

Category B: Project with potential adverse environmental impacts that are less adverse than those of category A projects. These impacts are site-specific, few if any of them are irreversible, and in most cases mitigation measures can be designed more readily than for category A projects. An initial environmental examination (IEE), including an EMP, is required.

Category C: Project that is likely to have minimal or no adverse environmental impacts. An EIA or IEE is not required, although environmental implications need to be reviewed.

Category FI: Project is classified as category FI if it involves the investment of ADB funds to, or through, a financial intermediary.

43. The SPS 2009 also provides the content and format of environmental assessments (see Annex to Appendix 1, p. 41). Impacts and risks are required to be analysed according to the project's area of influence which encompasses the primary project site(s) and related facilities that the Borrower (including its contractors) develops or controls such as power transmission corridors, construction camps, etc., and associated facilities that are not funded as part of the project but whose viability and existence depend exclusively on the project and whose goods and services are essential for the successful operation of the project. An EIA is required for public disclosure to ADB website 120 days prior to its Board consideration of the project.

3 Description of the Project


3.1 Introduction

- 44. The 18.6 km 132 kV D/C transmission line will evacuate the power generated from the 118 MW run-of-river Nikachhu Hydropower Project (NHPP) located in Trongsa District, with a proposed installed capacity of 118 MW.³ This transmission line will start from Nikachhu Pothead yard and terminating at the Mangdechhu Pothead yard at Yurmo. Construction activities for NHPP is expected to begin by 2014.
- 45. The 132 kV transmission line is within Trongsa Dzongkhag and will traverse three gewogs: Tangsibji, Drakteng, and Langthel.
- 46. The construction of transmission line and power evacuation system for NHPP shall be awarded to Bhutan Power Corporation (BPC) on a deposit work basis. Tentatively, detailed survey and engineering and design of the transmission lines shall be implemented between 2015 and 2018, and shall be completed before the commissioning of NHPP.
- 47. **Map 1** presents the location of Trongsa District, **Map 2** shows Trongsa District and its gewogs while **Map 3** shows the alignment of the transmission line.

³ The 18.6 km 132 kV D/C transmission line is an essential component of the 118 MW Nikachhu Hydropower Project to evacuate power it generates into the national grid but will not be financed by ADB and thus, considered an associated facility according to ADB's Safeguard Policy Statement 2009 (SPS 2009). The SPS 2009 provides that, "Impacts and risks will be analyzed in the context of the project's area of influence. This area of influence encompasses...(ii) associated facilities that are not funded as part of the project (funding may be provided separately by the borrower/client or by third parties), and whose viability and existence depend exclusively on the project and whose goods or service are essential for successful operation of the project...(Appendix 1, para. 6, p.31)."

Map 2: Trongsa District and its Gewogs

Map 1: Location of Trongsa District



3.2 Description of the Transmission Line

48. The associated transmission line of NHPP consists of the following:

(i) Voltage level: 132 kV

(ii) Tapping point: Nikachhu Pot Head Yard

(iii) Termination point: Mangdechhu Pot Head Yard

(iv) Length of line: 18.6 km (Maximum)(v) Right of Way (RoW) width: 27 m

49. As shown in **Map 3**, the transmission line route stretches from Nikachhu Pot Head Yard - Mangdechhu River Crossing - parallel to Mangdechhu Dam Axis road - TL1 – Alternative - TL56, Taktse-Tashidenkha-Euse-Bubja-Kuengarabten-Samchholing-Lhakhang Jab-Raphey-Khompey-Yurmoo at Yurmo, it will be integrated into the Pothead yard of the Mangdechhu Hydropower Project (MHEP). **Table 3.1** presents the details of the transmission line route while **Table 3.2** provides the description of the components.

Table 3.1: Transmission Line Route Details

From	То	GIS Dist (Crow Fly)	Actual in km (approx.)	Place under Trongsa Dzongkhag
TL1	T6	2.07	2.48	Tashidingkha, Eusa
TL7	TL14	2.02	2.42	Tashidingkha, Eusa, Taktse
TL15	TL26	3.15	3.78	Taktse, Eusa, Bubja, Kuengarabten
				Kuengarabten, Samcholing, Lhakhang
TL27	TL42	5.32	6.38	Jab
TL43	TL50	1.7	1.57	Lhakhang Jab, Raphey Top
	TL56 at			
TL51	Yurmo	1.31	1.57	Raphey, Khompey and Yurmo
Total Distance (km)		15.57	18.68	

Table 3.2: Description of Project Components

Component	Function	Description
Towers comprising of	To support the	Total of 61 towers
body, cage, cross	conductors	Design (height of 41m, width of 8m)
arms and peak		Material- Stainless steel
		Purpose. To provide support to the overhead
		conductors
Insulators	To prevent unwanted	Pre-manufactured electrical component made of
6 string (each with 10-	flow of electric current	Porcelain
11 discs)	from conductor to the	For each tower 12 insulators (tension string) are
	earth	required
Conductors (Double	To evacuate electricity	Type used: Panther /EW; OPGW (Optical fiber

Component	Function	Description		
circuit)	from Yurmo to MHEP	composite overhead ground wire)		
18.6 km length	pothead			

Infrastructure requirement


50. The associated transmission line (TL) for NHPP will not require any access roads to be constructed because the take off point is right next to the Mangdechhu dam site, and then the transmission line mostly runs either below or above the National highway from Trongsa to Zhemgang. At regular intervals, the TL crosses other access roads such as the Mangdechhu dam axis road, access to dam colony, Taktse College, cremation ground, Samcholing MSS School, Kuengarabten Nunnery Centre and to the Mangdechhu Surge shaft area.


Construction of towers


51. The TL will require the erection of 61 towers, each of which will be spaced at a distance of 250-350 m (depending on the terrain and stability of the soil) along the 18.6 km stretch. **Figure 3.1** shows the location of the towers while **Table 3.3** presents the description of each segment of the TL..

Figure 3.1: TL alignment showing the location of the towers

Table 3.3: Description of each segment of the transmission line








3.8 Gewogs Drakteng

Section 4: Kuengrabten top (TL27) to Lhakhang Jap (TL42) TL 33 Lhakhang TL 34 TL\38 TL 39/A Tree Plantation Google earth Type of soil Hard and dry soil type, steep terrain at TL27 4.1 Old footpath, access road to Samchholing middle school and 4.2 Accessibility Kuengrabten Nunnery centre Small stream, and tree plantation, valley crossing at TL 28 & TL Details of 4.3 crossing 29. Places along the Kuengarabten, Shomchholing, Lhakhang Jap. TL 40 & TL 41 4.4 TL line falls under private land Cool broad leaved forest, oak species, mixed forest and barren 4.5 Vegetation land Geological 4.6 stability Stable with barren land and no geographical disturbance. 4.7 Land use Forest territory and TL40 & TL 41 public land

4.8 Gewogs Drakteng Section 5: Kompey (TL43) to Raphy (TL50) Tharpa L 45/A TL 46 TL 47 Google earth Type of soil 5.1 Hard and dry soil type, barren land with gentle slope Old footpath, approach road to surge shaft 5.2 Accessibility No major crossing, only small streams, TL 43 falls in the private Details of crossing land, 66 kV line crossing at T7 & T8. 5.3 Places along the 5.4 TL line Lhakhang Jap, Raphey top Warm tropical thin alpine forest, mixed thin bushes and barren 5.5 Vegetation Geological Stable with gentle slope, barren land and no geographical 5.6 stability disturbance



3.2.1 Project Ancillaries

52. The project will not require any access roads, sub-stations or construction of buildings, or other large infrastructure.

3.2.1.1 Project office site

53. It is expected that staff will be required only during the Project Pre-Construction and Construction Period. It is planned that the transmission line component of NHPP will be placed under the responsibility of the Superintendent Engineer and his staff who are currently overseeing the on-going 400 kV Mangdechhu Project Transmission Line Project. Therefore, there is no need for a separate project office.

3.2.1.2 Contractors facilities and worker camps

54. The private contractors will require space to build their temporary labour camps at various sites, stores/warehouse and parking yards for machines/equipment and material stock piling yards, etc. Local building shall be hired for site office and residence for regular technical employees, there is no need for its construction. Adequate space has been earmarked for the construction of facilities as given in Table 3.4.

Table 3.4: Area requirement for contractors' facilities

No.	Description	Area (in acres)	Remarks
1	Site Office	0.2	1 site
2	Labor Camps	0.8	5 sites
3	Godown/Store	1.8	1 common go-down and one store at each site
4	Material stocking yard/machine parking	0.8	
	Total area	3.6	

3.2.1.3 Muck disposal

55. An estimated amount of about 12,810 m³ shall be generated from excavation works of 61 towers along the 18.6 km stretch. Considering 50% reuse in backfilling the pits of 2mx2mx3m, the amount of balance muck will be about 11,346 m³. The muck generated will be mainly due to benching which requires clearing and excavation to about 2 m below the ground. At each tower only about 168 m³ of muck shall be generated. Considering the relatively small amount of excess material, the muck shall be disposed off at appropriate area near the towers which shall be used for levelling the burrow.

3.2.2 Land Required for the Project

- Along the TL, a right-of-way (RoW) of 27 m needs to be cleared to prevent shorting and disturbance. About 15 km of the line passes through broadleaf and mixed conifer forest while 3.6 km passes through scrub forest comprising of a few trees and mostly shrubs, degraded vegetation, community forest, and private land.
- 57. Of the 61 transmission towers to be constructed, 55 fall on government land and 6 towers fall on private land. 60 decimal of land will have to be acquired from 6 displaced households that will lose 10 decimal of land each towards the footprint of the 132 kV transmission towers. All the tower feet falls in dry land and no wetland shall be affected by the TL. **Table 3.5** gives the details of private land requirement while **Table 3.6** provides the land use along the ROW.

Table 3.5: Details of private land required in acre

No.	Name of owner	Village	Thra m No.	Land required	Land type	Drylan d	Wetland	Total Land	% of total land
1	Phurpamo	Yurmo	284	0.1	dryland	3.4	2.462	5.862	1.7
2	Lemo	Yurmo	274	0.1	dryland	3	0	3	3.33
3	Tshering Mo	Refe	361	0.1	dryland	2	1.642	3.641	2.75
4	Tshering Dema	Refe	52	0.1	dryland	3	3	6	1.67
5	Sangay Wangdi	Refe	357	0.1	dryland	3.65	1.95	5.6	1.78
6	Tashi Wangmo	Kinga Rabten	372	0.1	dryland	2.13	2	4.13	2.42


Table 3.6: Land use along transmission line right-of-way

Compone nt	Drylan d	Wetlan d	Orchar d	BL and Conif er	Conif er forest	Scrub forest	Communi ty forest	Expos ed/Roc ky area	Total	Acres
Transmissi on line	0	0	0	15	0	3.3	0.3	0	0	
Corridor required	0	0	0	0.027		0.027	0.027	0	0	
total area required	0	0	0	0.405		0.089 1	0.0081	0	0.5 km ²	123

3.2.3 Construction Power Requirements

58. There will be no requirement for electricity for the construction of this Project. However, light may be required for lighting of labour camps. About 5 kW of power has been estimated to be required for lighting and heating purposes.

- 59. The 132/33 kV, 2 x 15 MVA , Endocholing Sub-Station which is currently under construction will be the main source of supply for Trongsa Region. There is also existing 33/11 kV, 2x 2.5 MVA Sub-Station at Kewathang which at present supplies power to Bumthang and some parts of Trongsa region. The present power supply in Drakteng Gewog, Taktse Gewogs are met through the 33 kV Nubi Feeder.
- 60. As seen above, the power supply for the labour camps in all the project areas shall be drawn at the 33 kV system which is more than adequate to meet the power requirements. The capacity of the 33/0.415 kV Sub-Stations shall be developed through which electricity shall be drawn to the camps.
- 61. Low voltage Ariel Bundled Cables shall be used for distribution of electricity in the camps which shall not require clearing of vegetation in the ROW. Map 4 shows the existing 33 kV system within the project area.



Map 4: Existing 33 kV system in project area (indicated by blue colour)

3.2.4 Water Supply Requirement

- 62. With a total of 14 project staff and 230 Contractors' staff and workers, the daily water requirement is estimated at 12,500 liters per day.
- 63. For construction work, water shall be used only for concreting. The volume of concrete used shall be about 952.897 m³ which shall consume about 300 litres/day. However, concreting shall be done only for laying foundation for the tower and the duration shall be at the most 60 days. Table 3.7 gives the daily water requirements.

Table 3.7: Daily water requirements for drinking and other purposes

No.	Purpose	No of staff/workers	Water Requirement (liters per day)	Total water required (in liters per day)				
1	Project staff requirement	14	50	700				
2	Contractor facility and workers	230	50	11500				
3	Construction works		300	300				
	Total water required							

64. The major requirement of water is in the labour camps for domestic purposes. All the 230 labourers shall not be camped in the same area but shall set up camps in 5 groups along 61 tower locations. Each camp shall have about 50 labourers and the camp area shall be identified in proximity to streams.

3.2.5 Requirements for Raw Materials/Construction Materials

65. The construction of NHPP will require large quantities of materials. These materials include cement, coarse aggregates, sand, rough sawn timber, ballies and steel. The details are provided in Table 3.8.

Table 3.8: Requirement of Construction Materials

Purpose	Concrete Volume (m³)	Cement (m³)	Sand (m³)	Gravel/ Aggregate (m³)	Boulders (m³)	Ballies (m)	Rough sawn timber (m³)	TMT Bars (kg)
Soling for tower foundation					146.40			
Plane Cement Concrete for foundation	48.80	8.30	24.40	47.01				

Purpose	Concrete Volume (m³)	Cement (m³)	Sand (m³)	Gravel/ Aggregate (m³)	Boulders (m³)	Ballies (m)	Rough sawn timber (m³)	TMT Bars (kg)
Reinforced Cement Concrete for foundation and pillars	815.27	261.94	383.17	766.35				856.03
Shuttering works						1,586.75	19.42	
Plastering works	2.2	25.38	67.47					
Total	866.27	295.62	475.04	813.36	146.40	1586.75	19.42	856.03
Contingencies (10%)	86.627	29.562	47.504	81.336	14.64	158.675	1.942	85.603
Grand Total	952.897	325.182	522.544	894.696	161.04	1745.425	21.362	941.633

^{***} The quantity requirement has been worked based on LMC 2012

3.3 Construction Activities and Schedule

66. **Pre-construction Activities:** All administrative, financial and legal formalities for the execution of the project will be completed before the start-up of construction activities. Activities such as site preparation, setting up project offices, contractors' offices and worker camps will be completed prior to the beginning of the formal construction works.

Deputation of Project Staff

- 67. **Land Acquisition:** The permanent land acquisition process will be completed before construction work. There will be temporary use of some land for the work areas of the contractors, their camps, and other facilities. These will be identified by the Project Management, the Dzongkhag Authorities and allocated according to (i) proximity to the project site, (ii) minimal forest clearance required, and (iii) accessibility to the roads as well as drinking water and electricity.
- 68. **Tenders and Contracts:** The contracts for the various packages will be finalized during the pre-construction phase.
- 69. Establishment of contractors' camps, arrangement of electricity, drinking water, cooking gas and fuelwood will also be completed during this phase.
- 70. **Implementation of construction works**: The construction works will be carried out in the following sequence:
 - (i) Delineation of TL corridor. The selected route which has already been identified and approved will be finalized by the project staff in consultation with the affected landowners, the district authorities, local custodians of religious sites and Forestry staff. This includes resurveying the entire alignment and securing forestry marking on trees.

- (ii) Vegetation clearance along RoW, wherever required.
- (iii) Excavation of foundation areas, casting, and construction of foundation.
- (iv) Assembly and erection of towers.
- (v) Stringing of conductors.
- (vi) Rehabilitation of disturbed areas and protection of erosion/slope sensitive areas.
- (vii) Testing and commissioning.
- (viii) Operation and Maintenance works.

3.4 Work Implementation and Staffing Requirement

71. The project construction will be outsourced to the Transmission Construction Department of BPCL under the Transmission Wing (TW). This Department is responsible for the construction of all 66 kV and above transmission lines, substations and any associated infrastructures. It is mainly responsible for the award of work, monitoring of progress, supervision, and quality control during construction. The construction works are usually executed by engaging both local and international (mostly from India) contractors. The organogram of the BPCL and the Development, Construction Department and the Project Management Unit is depicted (see **Figure 3.2** and **Figure 3.3**).




Figure 3.2: Organogram of the Bhutan Power Corporation


Construction and Development Department Line & Sub-station up gradation Unit Construction Monitoring Unit 440kV 220kV Dagachhu 220kV Malbase-TCS-Central Mangdechu TP Punatsangchu TP TP Trongsa Samtse TP Division I Division II-Zhemgang Gelephu Nikachu TL \ Component

Figure 3.3: Organogram of the Development and Construction Department

72. **Construction Phase.** It is estimated that 14 staff will be hired/deputed during the preconstruction and construction stage excluding security. This does not include contractors and their regular staff plus migrant workers (see **Figure 3.4**).

Figure 3.4: Organogram of the Project Management Unit

Superintendent Engineer (Mangdechu)



OPERATION AND MAINTENANCE

73. After completion of the construction, the TL will be included under the Transmission Department (TD) of BPCL, that is responsible for the operation and maintenance (O&M) of high voltage (66 kV and above) transmission system in Bhutan. It is mandated to ensure reliable transmission network for transmitting electric power from hydropower plants to load centers within Bhutan for local consumption and export to India. This Department has 598 staff posted under three Regional Superintendent Engineers overseeing eight Divisions.

4 Analysis of Alternatives

- 74. The preliminary assessment of the project included an analysis of alternatives, addressing the optimal match between required technical specifications and site conditions, as well as addressing any concerns for environmental, social, and economic features in each location.
- 75. , A walk on survey of the 132 kV line was carried out from Nikachhu Pot Head yard to Mangdechhu Pot Head yard by BPCL technical staff, from 24th September to 14th October, 2013. Two options were considered and described briefly below:
- 76. There are two TL routes with 18.6 km and 19.2 km which are aligned mostly in the Government reserved land/forest with few numbers of towers falling under private land and community forest. **Figure 4.1** shows the two TL routes.
- 77. **1**st **Option**: The first and the preferred route with 18.6 km is diverted via Raphey top crossing the existing 66 kV line at Tower No.7 and T8.
- 78. **2nd Option**: The 19.2 km option is after crossing 66 kV line at T7 and T8 runs parallel to 66 kV line and crossing the newly constructed 400 kV D/C Mangdechu-Goling-Jigmeling transmission line then finally enters the Mangdechu Pothead yard.
- 79. The 1st option was chosen due to the following reasons:
 - (i) Environmental impacts of the length of the TL: The 2nd option is 19.2 km which is 0.6 km longer than the 1st option entailing an additional 5 acres to be cleared for the ROW.
 - (ii) Social Impacts on private land: In the 2nd option, an additional 4 towers fall in the wetlands at Yurmoo village compared to the 1st option where the 6 towers are within drylands resulting to lesser number of affected parties.
 - (iii) Technical reasons: The terrain along the 1st option was found to be comparatively moderate compared to the 2nd option.

The "Do Nothing" Alternative

80. The "do nothing" or "without the project" option is not viable as the associated transmission line is an essential component of power evacuation from NHPP to the national grid.



Figure 4.1: The two TL routes considered

Description of the Environment

5.1 Physical Resources

5.1.1 Location

- 81. The Nikachhu Hydropower Project is located in Trongsa Dzongkhag, which is located in Central Bhutan at latitude 27.5° North and longitude 90.5° East, with Bumthang Dzongkhag to the northeast, Wangdue Phodrang Dzongkhag to the west, and Sarpang and Zhemgang Dzongkhags to the south.
- 82. Trongsa District covers an area of about 1,807.29 sq. km. (km²) and is subdivided into five gewogs. The 18.6 km 132 kV D/C transmission line will cross through three of these five gewogs (Drakteng, Langthel, and Tangsibji). The dzongkhag is further divided in two Constituencies - Nubi-Tangsibji and Drakteng-Langthel for electoral purposes. The main administrative centre is Trongsa town, which is approximately 150 km east of the national capital, Thimphu (see Maps 1-3). Table 5.1 gives the list of blocks and sub-blocks at Trongsa District.

Table 5.1: List of Blocks and Sub-Blocks in Trongsa District

No.	Gewogs/Block	Chiwogs (basic electoral precinct/sub-block)
1	Drakten	Kuenga Rabten, Samlingkha Maed, Samlingkha Toed, Tagtse Tashidingkha, Uesar
2	Korphu	Korphoog Maed, Korphoog Toed, Nabi, Nyimzhong Maed, Myimzhong Toed
3	Langthel	Baling, Dangdoong, Jangbi, Langthil, Yuendroonchhoeling
4	Nubi	Bagochen Boolingpang Ueling, Bemji Chela, Bji Saengbi, Darbab Sinphoog, Gagar karzphong
5	Tangsibji	Chendebji, Kyela, Nyala Drangla, Tangsibji, Tshangkha

a. Drakten Gewog

Drakten Gewog is located about 25 km South-East of Trongsa Dzong. Although the 83. smallest of the 5 gewogs in Trongsa covering just 84 km², it is the most populous consisting of 37 villages with a total population of 2,697 people and 445 households. It has a population density of 31.9 persons per km². Forest cover is 67 percent of its total land area.⁴

Drakten gewog has 1 RNR Centre, 1 BHU, 3 Out Reach Clinics, 3 farmers cooperatives, 8 irrigation schemes, 1 Higher Secondary School, 1 Middle Secondary School, 3 Community

⁴ 11th Five year Plan Document

primary Schools, and 4 non-formal education centers. The gewog has 20 lhakangs (temples/monasteries).5

84. Paddy, maize, wheat, and vegetables are the major crops cultivated. Most households rear livestock which is an important source of income. Although all the 37 villages are electrified, not all the households are electrified. Out of 445 households, 420 households receive electricity while 25 households do not receive electricity. Photo 5.1 shows the villages near the proposed alignment that will traverse the Drakten gewog.



Photo 5.1: Villages located near the proposed alignment

b. Langthel gewog

Langthel gewog is located about 52 km South-East of Trongsa and covers an area of 508 km². The gewog has a population of 2,637 people living in 424 households spread across

 ⁵ 11th Five Year Plan Document
 ⁶ 11th Five Year Plan Document

20 villages. The population density is 5.2 persons per km². 78 percent of the gewog is under forest cover'.

- 86. Langthel gewog has 1 RNR centre, 2 BHUs, 6 outreach clinics, 23 irrigation schemes covering 91 kms, 1 Lower Secondary School, 4 Community primary Schools, and 15 Non-formal education centers. The gewog is home to 8 lhakangs (temples/monasteries)⁸.
- 87. Paddy, maize, mandarin, and vegetables are the major crops and fruits grown. Livestock rearing is a major source of income with most households owning and rearing livestock.
- 88. 17 of the 20 villages under the gewog are electrified and 387 of the 424 households are electrified.9

c. Tangsibji gewog


- 89. NHPP falls mostly in this gewog since all the project components and infrastructures (apart from the transmission line component) are located in this gewog.
- 90. Tangsibji gewog is located about an hour's drive away from Trongsa along the east-west highway that runs through the Gewog. The Gewog consists of seven villages, 270 households and a population of 1,848 persons according to the 11th Five Year Plan (FYP). The population density of Tangsibji gewog is 5.0 persons per km². It covers an area of 372 km² with Wangdue Phodrang Dzongkhag to the west, Langthel Gewog to the south and Drakteng Gewog to the east.
- 91. The gewog has 4 farm roads and 11 irrigation schemes that cover 40 kms. It also has 1 RNR centre, 3 farmer's cooperatives, 1 BHU, 6 outreach clinics, 1 Higher Secondary School, 5 Community Primary Schools, and 10 Non-formal education centers.
- 92. Paddy, wheat, chili, potato, and cabbage are the major crops grown. Livestock is owned and reared by most households accounting for a large portion of household incomes.
- 93. It is inhabited by people known as Mandeps who speak Mangdehka, a dialect spoken in Tangsibji gewog and a few villages under Drakten gewog such as Taktse, Yuesa and Tashidingkha.
- 94. There are two micro hydels in the Gewog at Chendebii and Tangsibii, respectively. The micro hydel at Tangsibji village was established in 1987 with a generating capacity of 0.03 MW benefiting 53 households. The micro hydel at Chendebji was established in 2005 with a generating capacity of 70 KW benefiting 31 households. All villages now have electricity supply. Besides the Trongsa Dzong, the most popular and sacred monument, Chendebji chorten is located within this Gewog. There are 14 lhakhangs (temples) in the gewog.

 ^{7 11&}lt;sup>th</sup> Five year Plan Document
 8 11th Five Year Plan Document

⁹ 11th Five Year Plan Document

5.1.2 Topography, Geology and Soils

95. The topography of the project area is rugged with deeply cut valleys with steep side slopes and narrow V-shaped valley floors, caused by swift-flowing rivers like the Mangdechhu, and the Nikachhu. The elevation of the Dzongkhag ranges from 1,200 m to 4,800 m above sea level (masl), but most settlements are situated closer to the valley floors and at mid-level altitudes of up to 3,000 m (Atlas of Bhutan, 1997). The project area is located in mid elevations from 1,140 m to 2,355 m (see **Graph 5.1**).



Graph 5.1: Changes in elevation along the TL

- 96. The intense tectonic activity that resulted from the collision of the Indian and Eurasian continental plates, the closure of the intervening Tethys Ocean, and the uplift of the Himalayas are responsible for the topography and geology of Bhutan. The project area falls in the zone of predominant north-south valleys and ranges, with smaller east-west river system cuts, where the bedrock comprises mostly gneiss, schist, quartzite, and limestone, with intrusions (Norbhu et al., 2003).
- 97. The recorded seismic activity in the project area dates back to June 12, 1897, when the epicenter of an earthquake was 80 km south of Bhutan (in Rangjoli, Assam, India). In Bhutan, the earthquake destroyed Punakha and Lingzhi Dzongs, and damaged Wangdi, Trongsa, Jakar and Utse of Tashicho Dzong. **Figure 5.1** shows the seismic hazard map of Bhutan prepared by the Indian Institute of Technology in Roorkee, India. The seismic hazard map shows that the Trongsa area lies in a low hazard zone (rated in a 4-point scale of low to very high).
- 98. The Nikachhu project area lies in a central crystalline belt surrounded by the lithology of the Thimphu Gneissic complex (TGC) and the meta-sediments of the Chekha Formation. The

riverbed geological investigation revealed that below 2 m under the riverbed, the granite bedrock was found to be highly stable.

99. The site of the Mangdechhu Hydropower Project encompasses a linear area between Trongsa and Yurmu village. The southerly flowing Mangdechhu River, in its upper reaches, flows almost along the contract plane between the rocks of the Sure Formation on its left flank and the rocks of the Chekha Formation on its right flank. After taking an easterly turn, the river cuts across the leuco-granite suite of rocks. Further, it continues through the rocks of Chekha Formation (MHEP, 2010)




Figure 5.1: Seismic hazard risk of Bhutan

100. In Bhutan, the soils produced by local base materials remain largely unmapped. In the valleys, surface layers consist mainly of alluvium brought in by the rivers, which deposit large quantities of sand and silt on the banks each year. The rivers and forested catchments produce soils that are high in organic material, and are mainly temperate stagnogleys and podzols (Norbhu *et al.*, 2003). Soils are generally sandy loam and clay loam, with good permeability and moderate moisture retention (DOFPS website). Forest soils are generally shallow. The topsoil in agricultural areas has a pH value between 5 and 6, with loamy clay making up 10-30% content, and silt comprising 20-50% (MPFD, 1991). The rugged terrain in the project area suggests that maintenance of vegetative cover and careful use of soils is necessary to check erosion and landslides.

101. Soil samples were collected from seven sites from the Mangdechu Hydropower Project. Soils in rural areas are largely uncontaminated from chemical fertilizers as farmers mostly use leaf litter and manure from farm animals for their fields. Soils in the project site are largely sandy clay with pH value between 5.4 and 6.2. **Table 5.2** gives the results of the analysis of the soil samples.

Table 5.2: Results of soil samples analysis of the study area

Davamatava	Soil Samples						
Parameters	S-1	S-2	S-3	S-4	S-5	S-6	S-7
рН	6.19	5.96	5.59	5.84	6.1	5.91	5.44
E.C m.mho/ cm	0.3	0.35	0.32	0.39	0.36	0.42	0.36
Organic carbon (%)	0.4	1.71	0.87	1.28	0.23	1.77	0.53
Organic matter (%)	0.695	2.954	0.821	2.733	0.391	2.972	0.732
Moisture content (%)	7.84	73	47	75	21.36	80	58
Total Kjeldahl N %	0.055	0.109	0.076	0.031	0.236	0.279	0.053
Potash as K ₂ O in ppm	72.38	69.72	71.3	64.48	92.12	90.23	70.74
Phosphorus as P ₂ O ₅ in ppm	14.56	14.31	17.28	13.06	25.03	25.41	15.46
Sulphur (as SO ₄ ² -) in ppm	22.58	29.47	31.22	34.56	32.82	33.65	31.32
Texture	Sandy clay						
Sand (%)	62	63	63	60	58	56	62
Silt (%)	2	3	2	4	6	7	3
Clay (%)	36	34	35	38	34	37	35

Source: MHEP, 2010

102. About 11,346 m³ of spoils shall be generated from the excavation works of the 61 towers along the 18.6 km stretch. The volume of excavated material will be at various locations along the TL route and is considered low with some to be reused as backfill for the foundation of tower footing to stabilize it. **Table 5.3** gives the soil type and terrain along the TL route.

Table 5.3: Soil Type and Terrain along the TL

Section of TL	Soil Type and Terrain				
Section 1: Port head Yard (TL1) to Dam colony opposite (T6).	Hard soil type, black alluvial/Soft & hard rock, gentle slope.				
Section 2: Tashidingka(TL7) to Taktse top(TL14)	Hard and dry soil type/soft rock, marshy area				
Section 3: Bubja top (TL15) to kuengarabten(TL26)	Hard and dry soil type with thin vegetation, steep terrain at TL 25 & TL26				
Section 4: Kuengrabten top (TL27) to Lhakhang Jap (TL42)	Hard and dry soil type, steep terrain at TL27				
Section 5: Kompey (TL43) to Raphy (TL50)	Hard and dry soil type, barren land with gentle slope				
Section 6: Raphey top (TL51) – Alternative-Yurmo (TL56)	Stable with barren land and no geographical disturbance.				

5.1.3 Climate

- 103. Most of the central portion of the country experiences a cool, temperate climate year-round. In the south, a hot, humid climate helps to maintain a fairly even temperature range between 15° C and 30° C year-round, although temperatures sometimes reach 40° C in the valleys during the summer.
- 104. Spring starts in early March and lasts until mid-April. Summer weather commences in mid-April with occasional showers and continues through the pre-monsoon rains till June. The monsoon lasts from June to September with heavy rains of the southwest. The monsoon brings heavy rains, high humidity, flash floods and landslides, and numerous misty, overcast days. Autumn, which starts from late September to late November, follows the rainy season. It is characterized by bright, sunny days and some early snowfalls at higher elevations. From late November until March, winter sets in and with frost throughout the country. Snowfall is common above elevations of 3,000 masl.

5.1.3.1 Temperature and Relative Humidity

105. The climate data exist for each day of each month over a period of 16 years. The location of various climatological stations closest to Trongsa is given in **Table 5.4** while **Graph 5.2** presents the monthly variations in temperature.

Table 5.4: Location of Climatological stations closest to Trongsa

Name of station	Latitude (N)	Longitude (E)	Altitude (m)
Bjizam	27 ⁰ 31' 11"	90 ⁰ 27' 23"	1840
Chendebji	27 ⁰ 30' 29"	90 ⁰ 16' 35"	2660
Kuengarabten	27 ⁰ 24' 23"	90° 31' 05"	1780
Nobding	270 32' 52"	900 09' 10"	2600
Trongsa	270 30' 07"	900 30' 18"	2120


106. During winter, temperatures can drop to below 1 degree in January, but ranges from 6.1°C to 11°C while the highest temperature during July to August goes up to 23.6°C (average ranges between 17-20°C).

25
20
15
10
jan feb mar apr may jun jul aug sep oct nov dec

Graph 5.2: Monthly variation in temperature

5.1.3.2 Rainfall

107. The rainy season commences from late May and continues until the end of September and is characterized by heavy rains, high humidity, misty overcast days, and the risk of flash floods and landslides. Autumn weather is characterized by bright sunny weather running to late November. Winter, from end-November to March, is characterized by lowest temperatures and generally dry weather. The maximum rainfall recorded in 2012 was 1,173 mm (NSB, 2013). **Graph 5.3** shows the monthly rainfall variations within the project area.



Graph 5.3: Monthly rainfall variations (mm)

5.1.4 Air Quality

108. Trongsa being a largely rural area with 87% forest cover, low population density and little traffic, has good air quality especially as there are no industrial activities in the project area. Generally, the air is clean and does not show any deviations from the standards set internationally or by the National Environment Commission for assessing the quality of air. The ongoing construction activities by the Mangdechhu Hydroelectric Project (MHEP) are the only source of dust and air emissions that are expected to be completed in the next three –four years.

109. Air quality measurements were taken during preliminary environmental assessment for the MHEP and NHPP. Ambient air quality standards of the government and the WHO/Woldbank are given in **Table 5.5** while **Table 5.6** presents the results of ambient air quality measurements within the project area.

Table 5.5: Ambient air quality standards

Standards	Particulate Matter (PM10)	SOx	NOx
Bhutan standards for sensitive areas	75 μg/m³	30 μg/m³	30 μg/m³
WHO/World Bank guidelines	150 μg/m ³	125 μg/m³ - 24 hour average	40 μg/m³ yearly average

Table 5.6: Results of ambient air quality measurements in the project area

No.	Location	Oxides of Nitrogen (NOx) in µg/Nm³	Respirable particulate matter in μg/Nm³ (size less than 10μ)	Information Source
1	Lorim	BDL	20.293 μg/m ³	NHPP
2	Trongsa View Hotel	BDL	24.607 μg/m ³	NHPP
3	BOC Petrol Pump	BDL	10	MHEP
4	Yankeel Resort, Trongsa	BDL	6	MHEP
5	Hospital, Trongsa	BDL	8	MHEP
6	High School, Trongsa	BDL	10	MHEP
7	NHPPC Office, Sherubling, Trongsa	BDL	8	MHEP
8	Hotel Chokhorling, Trongsa	BDL	7	MHEP
9	NHPPC Camp,Kuengarabten	BDL	8	MHEP
10	Community Centre, Kuengarabten	BDL	6	MHEP
11	Sonam Wangmo,Kuengarabten	BDL	8	MHEP
12	Near D.G. Set, Yurmong	11	10	MHEP
13	Near Powerhouse, Yurmong	BDL	8	MHEP
14	Rice Mill, Refee	BDL	9	MHEP

No.	Location	Oxides of Nitrogen (NOx) in µg/Nm ³	Respirable particulate matter in μg/Nm³ (size less than 10μ)	Information Source
15	Tendril General Cum Bar	BDL	8	MHEP
16	Dzong,Trongsa (Police duty House)	BDL	9	MHEP
17	Dzong,Trongsa(Car parking)	BDL	11	MHEP
18	Saw Mill,Bagoshin	BDL	10	MHEP
19	On Road side NH Bumthang(Near PWD Colony)	BDL	10	MHEP
20	In front of PWD Guest House	BDL	8	MHEP
21	Kuengarabten-I	BDL	10	MHEP
22	Kuengarabten-II	BDL	8	MHEP

BDL: below detection limit.

110. Sulphur oxides (SO_x) and nitrogen oxides (NO_x) were not detected while analyzing (reflecting the low population density, absence of heavy industry, and low traffic levels). These results were substantiated by the air sampling results from 19 sites out of the 20 sites at MHEP. Particulate matter (PM_{10}) in NHPP area was quite consistent at 20.3 - 24.6 $\mu g/m^3$, only about one-third of the standard for Bhutan. The only real sources of air contaminants are the small amount of traffic and a number of rural households where wood and kerosene are the main fuel for cooking and heating. The latter may result in localized increases in levels of smoke and soot (contributing to PM_{10}), and carbon dioxide, when fuel usage is highest (in the evening and during winter). **Table 5.7** gives the results of suspended particulate matter (SPM) measurements at various sites within the project area, **Table 5.8** shows the results of ambient SO_x . **Table 5.9** presents the ambient NO_x and **Table 5.10** provides the results of PM_{10} .

Table 5.7: Levels of Suspended Particulate Matter within project area (µg/Nm³)

No.	Location	Winter	Post monsoon	Summer	Monsoon	Total	Average
1	BOC Petrol Pump	38	42	41	31	152	38
2	Yankeel Resort, Trongsa	18	25	21	19	83	21
3	Hospital, Trongsa	22	28	24	17	91	23
4	High School, Trongsa	14	15	18	13	60	15
	NHPPC Office, Sherubling,						
5	Trongsa	22	19	25	14	80	20
6	Hotel Chokhorling, Trongsa	34	37	38	22	131	33
7	NHPPC Camp, Kuengarabten	22	22	26	19	89	22
	Community Centre,						
8	Kuengarabten	12	14	20	12	58	15
	Sonam						
9	Wangmo,Kuengarabten	23	21	27	16	87	22
10	Near D.G. Set, Yurmong	18	21	22	17	78	20
11	Near Powerhouse, Yurmong	19	20	26	15	80	20
12	Rice Mill, Refee	12	23	19	17	71	18
13	Tendril General Cum Bar	22	22	27	16	87	22

No.	Location	Winter	Post monsoon	Summer	Monsoon	Total	Average
	Dzong,Trongsa (Police duty						
14	House)	18	18	21	13	70	18
15	Dzong,Trongsa(Car parking)	18	20	21	20	79	20
16	Saw Mill,Bagoshin	21	19	23	19	82	21
	On Road side NH						
17	Bumthang(Near PWD Colony)	20	21	24	21	86	22
18	In front of PWD Guest House	17	17	22	11	67	17
19	Kuengarabten-I	18	18	21	12	69	17
20	Kuengarabten-II	17	18	21	13	69	17

Table 5.8: Results of SO_x measurements at various sites in the Project district (µg/Nm³)

No.	Location	Winter	Post monsoon	Summer	Monsoon
1	BOC Petrol Pump	7	BDL	6	BDL
2	Yankeel Resort, Trongsa	BDL	BDL	BDL	BDL
3	Hospital, Trongsa	BDL	BDL	BDL	BDL
4	High School, Trongsa	BDL	BDL	BDL	BDL
	NHPPC Office, Sherubling,				
5	Trongsa	6	BDL	6	BDL
6	Hotel Chokhorling, Trongsa	BDL	BDL	BDL	BDL
7	NHPPC Camp,Kuengarabten	BDL	BDL	BDL	BDL
8	Community Centre, Kuengarabten	BDL	BDL	BDL	BDL
9	Sonam Wangmo,Kuengarabten	BDL	BDL	BDL	BDL
10	Near D.G. Set, Yurmong	8	BDL	7	BDL
11	Near Powerhouse, Yurmong	BDL	BDL	BDL	BDL
12	Rice Mill, Refee	BDL	BDL	BDL	BDL
13	Tendril General Cum Bar	BDL	BDL	BDL	BDL
14	Dzong,Trongsa (Police duty House)	BDL	BDL	BDL	BDL
15	Dzong,Trongsa(Car parking)	BDL	BDL	BDL	BDL
16	Saw Mill,Bagoshin	BDL	BDL	BDL	BDL
	On Road side NH Bumthang				
17	(Near PWD Colony)	BDL	BDL	BDL	BDL
18	In front of PWD Guest House	BDL	BDL	BDL	BDL
19	Kuengarabten-I	BDL	BDL	BDL	BDL
20	Kuengarabten-II	BDL	BDL	BDL	BDL

Table 5.9: Results of NO_x measurements at various sites in the Project district ($\mu g/Nm^3$)

No.	Location	Winter	Post monsoon	Summer	Monsoon
1	BOC Petrol Pump	BDL	BDL	BDL	BDL
2	Yankeel Resort, Trongsa	BDL	BDL	BDL	BDL
3	Hospital, Trongsa	BDL	BDL	BDL	BDL
4	High School, Trongsa	BDL	BDL	BDL	BDL

No.	Location	Winter	Post monsoon	Summer	Monsoon
	NHPPC Office, Sherubling,				
5	Trongsa	BDL	BDL	BDL	BDL
6	Hotel Chokhorling, Trongsa	BDL	BDL	BDL	BDL
7	NHPPC Camp,Kuengarabten	BDL	BDL	BDL	BDL
8	Community Centre, Kuengarabten	BDL	BDL	BDL	BDL
9	Sonam Wangmo,Kuengarabten	BDL	BDL	BDL	BDL
10	Near D.G. Set, Yurmong	11	10	11	9
11	Near Powerhouse, Yurmong	BDL	BDL	BDL	BDL
12	Rice Mill, Refee	BDL	BDL	BDL	BDL
13	Tendril General Cum Bar	BDL	BDL	BDL	BDL
14	Dzong,Trongsa (Police duty House)	BDL	BDL	BDL	BDL
15	Dzong,Trongsa(Car parking)	BDL	BDL	BDL	BDL
16	Saw Mill,Bagoshin	BDL	BDL	BDL	BDL
17	On Road side NH Bumthang(Near PWD Colony)	BDL	BDL	BDL	BDL
18	In front of PWD Guest House	BDL	BDL	BDL	BDL
19	Kuengarabten-I	BDL	BDL	BDL	BDL

Table 5.10: Results of PM_{10} measurements at various sites in the Project district $(\mu g/Nm^3)$

No.	Location	Winter	Post monsoon	Summer	Monsoon		Average
1	BOC Petrol Pump	10	8	10	5	33	8
2	Yankeel Resort, Trongsa	6	5	9	3	23	6
3	Hospital, Trongsa	8	7	7	4	26	7
4	High School, Trongsa	10	9	11	4	34	9
	NHPPC Office, Sherubling,	_	_		_		_
5	Trongsa	8	7	9	5	29	7
6	Hotel Chokhorling, Trongsa	7	4	8	3	22	6
7	NHPPC Camp,Kuengarabten	8	6	8	4	26	7
0	Community Centre,		-	7	0	01	F
8	Kuengarabten	6	5	/	3	21	5
9	Sonam Wangmo,Kuengarabten	8	6	9	4	27	7
10	Near D.G. Set, Yurmong	10	11	10	6	37	9
11	Near Powerhouse, Yurmong	8	9	9	4	30	8
12	Rice Mill, Refee	9	7	10	4	30	8
13	Tendril General Cum Bar	8	5	7	3	23	6
	Dzong,Trongsa (Police duty						
14	House)	9	7	8	3	27	7
15	Dzong,Trongsa(Car parking)	11	10	10	5	36	9
16	Saw Mill,Bagoshin	10	8	11	6	35	9
	On Road side NH				_		
17	Bumthang(Near PWD Colony)	10	8	11	4	33	8
18	In front of PWD Guest House	8	7	8	4	27	7

No.	Location	Winter	Post monsoon	Summer	Monsoon		Average
19	Kuengarabten-I	10	9	9	5	33	8
20	Kuengarabten-II	8	7	9	3	27	7

111. Air quality data was collected by MHEP in June 2013 assisted by the National Environment Commission. Respirable Dust Sampler was used for PM_{10} sampling for 8 hrs and 24 hrs (see **Table 5.11**). Level of PM_{10} for 8-hour average was also measured at the workplace (see **Table 5.12**).

Table 5.11 Results of PM₁₀ measurements (24 hrs)

SI. No	Location	PM ₁₀ (μ/m ³)	National Standard (μ/m³)
1	Trongsa Town	30.28	100
2	Dangdung Colony	78.32	100

Table 5.12 Work Place Emission for average 8hrs

SI. No	Location	PM ₁₀ (μ/m ³)	National Standard (µ/m³)
1	Kuenga Rabten (Gup Office)	0.072	5
2	Khamey	0.083	5

5.1.5 Noise

- 112. The Project area is remotely located with sparse population, devoid of any industry and thickly buffered by vegetation. While the town lies along the Trongsa Gelephu highway, the frequency of long distance travelers and vehicles is quite low.
- 113. Ambient noise levels were measured by MHEP at 10 locations in different seasons (see **Table 5.13**) and two sites for NHPP (see **Table 5.14**).

Table 5.13: Noise levels at various sites in MHEP

SI. No.	Mangdechu Project	Noise level, dB				
31. 110.	sites	Monsoon	Post-monsoon	Winter		
1	Trongsa market (11 a.m.)	47	48	41		
2	Chunjupang Road side	41	38	37		
3	Mid-way to Dam site	33	33	31		
4	Dam site	48	47	43		
5	Bubja Road side	40	49	37		
6	Power House area	31	31	30		
7	Langthel	36	39	33		
8	Yurmu quarry site	34	35	34		
9	Kurjey quarry site	33	33	33		
	Kuengarabten Adit 4					
10	area	32	33	32		

Table 5.14: Noise levels at NHPP (July 2012)

SI.No.	Nikachhu project sites	Noise level, dB(A)		National Standards	
		Day	Night	Day	Night
1	Trongsa view hotel	48.11	42.84	55 dB(A)	45 dB(A)
2	Dam site at Lorim	40.7	35.49	55 db(A)	

114. The data indicate that noise levels are currently below the national standards for noise, day and night. With MHEP currently being implemented, noise is by generated from the operation of construction equipment, movement of vehicles, and blasting operations. However, many of the access roads have been completed and not much construction work remains as the construction phase is nearing completion.

5.1.6 Surface Water

- 115. There are four major rivers in Bhutan. Drangme Chhu is the largest river system which flows south-westerly from India's state of Arunachal Pradesh. It has three major tributaries: the Drangme Chhu, Mangdechhu, and Bumthang Chhu. These three tributaries form the Drangme Chhu River basin which spreads over most of eastern Bhutan and drains the Trongsa and Bumthang valleys. In the southern plains, where eight tributaries join it, the Drangme Chhu is called the Manas Chhu. The Puna Tsang Chhu rises in northwestern Bhutan as the Mo Chhu and Pho Chhu are both fed by the snow-covered Himalayas. These two rivers join to form the Puna Tsang Chhu in Punakha and flow southerly into West Bengal, India. The smallest river system, the Torsa Chhu or Amo Chhu, flows out of Tibet into the Chumbi Valley and swiftly through western Bhutan before broadening near Phuntsholing and then flowing into India.
- 116. The Mangdechu River flows through the heart of the dzongkhag dividing it into two. The Mangdechhu, rises in northern Bhutan near Kula Kangri Peak. At Trongsa Dzong, the bed of the river is about 1, 666 masl and its flow is very swift.
- 117. The Nikachhu River is a tributary of Mangdechhu River with the catchment north and south of the road running from Pele La to Tangsibji. The topography in the area is characterised by steep slopes, deep gorges with approximately one third of the catchment area lying above 4,000 m elevation. A number of smaller tributaries flow into the Nikachhu River.

118. The different sites of the project are located in an area of about 40 km in length between Trongsa to Langthel. **Table 5.15** shows the various streams where the transmission line has crossings.

Table 5.15: River and stream crossing along the TL alignment

Section of TL	River and stream crossing
Section 1: Port head Yard (TL1) to Dam colony	Mangdechu river
opposite (T6).	Mangacona nver
Section 2: Tashidingka(TL7) to Taktse	Dzongkhalumpa
top(TL14)	Dzongknaiumpa
Section 3: Bubja top (TL15) to	Yuesagangchhu
kuengarabten(TL26)	ruesagangennu
Section 4: Kuengrabten top (TL27) to Lhakhang	Bubja fall and Nikhachhu
Jap (TL42)	Bubja ian and Nikhachilu
Section 5: Kompey (TL43) to Raphy (TL50)	None
Section 6: Raphey top (TL51) – Alternative-	None
Yurmo (TL56)	INOTIC

119. Water samples for analysis were collected in 2012 from ten sites in and around Trongsa in Central Bhutan in relation to MHEP and four sites for NHPP (see **Table 5.16** and **Table 5.17**).

Table 5.16: Water quality at the project site and downstream (sampled July 24-29, 2012)

				Locations	
Parameter	Unit	Category	Upstream of Nikachhu Dam Site	Downstream of Nikachhu Dam Site	Downstream of Nikachhu and Mangdechhu Confluence
Turbidity	TU	Physical	17	18	22
рН		Physical	7.52	7.4	7.6
Temperature	centigrade	Physical	13.4	16.5	16.2
Conductivity	S/m	Physical	62.8	58.5	51.1
Dissolved Oxygen	mg/L	Physical	7.91	8.49	9.3
Coliform	cfu/ml	Microbiological	25	29	70
Chlorine	mg/L	Chemical	< 0.05	< 0.05	< 0.05
Arsenic 50 ml	Ppb	Chemical	0	0	0
Arsenic 9.6 ml	Ppb	Chemical	0	0	0


				Locations	
Parameter	Unit	Category	Upstream of Nikachhu Dam Site	Downstream of Nikachhu Dam Site	Downstream of Nikachhu and Mangdechhu Confluence
Iron	mg/L	Chemical	0.082	0.065	0.82
Ammonia	mg/L	Chemical	0.025	0.025	0.016
Total Hardness	mg/L	Chemical	80	81	86
Calcium	mg/L	Chemical	59	45	19
Magnesium	mg/L	Chemical	21	27	67

Table 5.17: Water quality at the project site and downstream (sampled December 2012)

	Sites					
Parameters	Near dam site	Downstrea m from Dam Site	Confluence with Mangdechhu	Downstrea m from Confluence	Downstream Mangdechhu	Downstream Mangdechhu
Conductivity (S/m)	82	82	117	90	105	110
TDS (ppm)	41	41	57	44	52	56
Water Temp. (°C)	7	7	9	9	10.5	12

- 120. In general, the analytical data for the Nikachhu reflect a very healthy river system, with no evidence of contamination from human sources. In addition, despite water sampling at the beginning of the monsoon, turbidity is actually very low, reflecting very little sediment mobilization (from erosion) in the upper watershed of the Nikachhu (which in turn reflects very high vegetative cover).
- 121. On the other hand, there is some evidence of higher levels of some water quality parameters in the Mangdechhu below the confluence. Given the much higher discharge of the Mangdechhu and the fact that it flows near Trongsa town, it is not surprising that there are higher levels of coliform. The surficial geology of the Mangdechhu Basin may also account for the higher levels of iron and magnesium, and lower levels of calcium. Like the Nikachhu, the Mangdechhu shows little evidence of contamination from human activity, and all parameters, such as turbidity, ammonia, and coliform are low by any standard. Water quality at Tsheringma Drupchhu (a small tributary of the Nikachhu, on the north side, about 2 km upstream of the confluence of the Nikachhu and Mangdechhu) is also very good, although coliform levels are similar to those in the Mangdechhu (possibly reflecting more human habitation and pastureland in this area, compared to further upstream on the Nikachhu).

- 122. The water quality analysis in December 2012 reflected lower water temperatures, but showed the trend of increasing water temperatures from the Nikachhu to the Mangdechhu (the latter at lower altitudes). As with the July 2012 data, the Mangdechhu showed higher levels of total dissolved solids and conductivity, compared to the Nikachhu.
- 123. The river Mangdechhu, a tributary of river Manas, rises from Northern Bhutan near Kula Kangri Peak. The river system exhibits a dendritic pattern with tree like branches of smaller rivers meeting to form a larger river. The entire project area is located in a highly mountainous and difficult terrain of Bhutan. In the upper course the river flows between high rocky Himalayan Mountains confining the channel in a narrow valley.
- 124. The profile of Mangdechhu from source to proposed dam site is relatively steep. The overall river length is 80 km. The average slope of the river is around 40 m/km. There are two glaciers on the northern most part of the catchments, with total area of 5,079 ha (see **Map 5.2**). In addition, there are around 108 glacier lakes/water bodies in the northern and middle portion of the river basin, having a combined area of 1,177.53 ha. All the lakes are situated above elevation 4,271 m and around 50% of the lakes are situated above 500 m altitude.
- 125. The river Mangdechhu in general flows in southerly direction; however, in the vicinity of project area it follows a meandering course. In the dam area, it flows in northeast to southwest direction and after making a big loop, it follows a northwest to southeast course near power house site. The entire terrain is dissected by many streams, which drain into river Mangdechhu. Prominent left bank tributaries of Mangdechhu are Tarkha and its tributaries Tergang and Kharma; Trespang chhu; Gormang chhu and Bungzam chhu; whereas right bank tributaries are Khangkham chhu, Branji; Chuu, Dangi bang chhu, Duigang chhu and Thampe Chhu. Some of these nallas follow a sub-parallel drainage pattern indicating structural control, however the second order and third order streams are more or less dendritic. Peak flows occur during the monsoon months of June to September and lean flows during December to March.



Map 5.2: Mangdechu River system

5.1.7 Ground Water

126. Little is known of Bhutan's groundwater reserves, although there are many springs in both low and high altitudes, some of which are used for irrigation and/or domestic purposes. There has been no significant study on the location, extent and potential yield of aquifers, or on


the quality of the water they contain. Arsenic levels are, however, known to be low, and water quality should be good, given the limited population, lack of polluting industries, and relatively low use of chemical fertilizers in agriculture in the project area. It is known that no local communities use wells for any water supply.

5.2 Ecological Resources

5.2.1 Protected Areas

127. Bhutan has the highest proportion of forest cover and protected areas compared to all other countries in Asia¹⁰. With a total land area of 38,394 km², protected areas cover 51.32% (19,676.57 km²). This comprises 16,396.43 km² in ten protected areas and 3,307.14 km² of Biological Corridors (Circular of NCD, Nov 30, 2009; NEC/Adm (02)/2009/1595). These are shown in the Map below.

Map 5.3: National parks and biological corridors in Bhutan (the project area is marked)



128. The protected areas in Bhutan are all joined by biological corridors, which are intended to maintain the biological connection between each area, and permit the unhindered migration of mammals and other organisms. As noted previously, these are all considered as protected areas by the Department of Forest and are given special protection under the Forest and Nature Conservation Act (1995), although with a lower status than the National Parks themselves.

_

¹⁰ MOA (2002): Biodiversity Action Plan for Bhutan. Ministry of Agriculture, RGOB.

129. To date around 5,603 species of vascular plants (includes 369 species of orchids and 46 species of rhododendrons), over 678 species of birds, and nearly 200 species of mammals have been recorded in Bhutan (NBC, 2009). This possibly represents a fraction of the species that are present, as Bhutan remains one of the least explored countries in the world. Only 23 species of herpetofauna have been inventoried so far (NBC, 2009). The rich biodiversity is due to the remote nature, geographical relief and climatic heterogeneity of the country, and its location between temperate Eurasia in the north and the tropical Indian subcontinent in the south. The National Parks are intended to protect the most important habitats for this terrestrial biodiversity. The Transmission line is not located in any protected area, Wildlife Sanctuary, Strict Nature Reserve or Biological Corridor (shown below).



Map 5.4: Map showing TL alignment vis-à-vis Protected Area


5.2.2 Forest and Vegetation

Vegetation Types in Bhutan

130. Forests are the most dominant land cover, making up 72.5 percent of the country's territory. Mixed conifers and broadleaf forests are the most dominant forest types and virtually all forests are natural with plantation forests accounting for a mere 0.2 percent of the country's

area. Forests are the most dominant land cover, making up 72.5 percent of the country's territory. Mixed conifers and broadleaf forests are the most dominant forest types (NBC, 2009).

- 131. So far, most of the classifications on forest is based on 12 vegetation types based on the observations in Grierson & Long (1983) who recorded the existence of vegetation types in Bhutan. Within Trongsa Dzongkhag, the majority of the project area falls in the Government Reserve Forest. Forest covers 87.6% of the total land area, a significant degree of coverage. Within the Dzongkhag, the overall distribution of forest types is as follows:
 - (i) Broadleaf forest (40.5%): these forests are mostly characterized by trees such as *Alnus nepalensis* (alder);
 - (ii) Mixed conifer (15.1%): prevalent between 2,000 m and 2,700 m, this forest type is dominated by spruce, hemlock and larch, or a mixture of these species;
 - (iii) Broad leaf and conifer (11.4%): these mixed forests are generally oak mixed with blue pine, or higher altitude broadleaf species mixed with spruce or hemlock, and generally occur between 2,400 m and 3,000 m;
 - (iv) Scrub forest (9.9%): this is generally forest that has been either de-forested, damaged by fire, or overgrazed, and is more dominated by scrub than trees;
 - (v) Fir forests (8.8%): this forest type occurs at very high altitudes, between 2,700 m and 3,800 m; hemlock and birch may also be present; towards the timber line, fir stands become stunted, and juniper and rhododendron scrubs become more prominent;
 - (vi) Chirpine (1.3%): a xerophytic forest type occurring in deep dry valleys under subtropical conditions, between 900 m and 1,800 m;
 - (vii)Blue pine (0.5%): most common in valleys between 1,800 m and 3,000 m; it is sometime found mixed with oak and rhododendron.
- 132. Within the project area, the forest type is mostly cool broadleaf forest (altitudes of 11400-2000m and Broadleaf and Conifer forest at higher altitudes (2000m-2400). Along the alignment for the Transmission line a total of 74 plots were randomly selected at intervals of approximately 250m each in December 2013. Survey plots comprised of 10x10m plots for Trees, 5x5m plots for Shrubs and 1x1m plots for ground vegetation. The survey area covered the entire length of the Transmission Line and also extended into the areas beyond (where observations were simply listed). 80% of the alignment fell under broadleaf forest and mixed coniferous forest, while 15% was in Scrub forest and the remaining 3% in agricultural land, community forest, or crossing footpaths or roads.




Graph 5.4: Land use along transmission line

- 133. Below is a brief description of how the vegetation changes as one proceeds along the transmission line alignment (From TL 1to TL 56). The typical structure of these forests includes the following layers: a top canopy comprising of tall mature trees; a shade-tolerant middle canopy comprising smaller mature trees; shrub layer, comprising mostly woody or herbaceous plants; followed by the ground cover.
- 134. Within the Warm broadleaf forest, the dominant trees are Oaks, especially *Quercus griffithii*, *Quercus Lamellosa* and *Quercus Lanata*. Other species include *Alnus nepalensis*, *Docynia indica, Juglans regia*, *Lyonia ovalifolia*, *Exbucklandia populnea*, *Daphne phyllum*, *Symplocus ramossima*, *Maesa chisea* and *Daphne bholua*. The middle shrub layer comprises mostly of younger tree species of Quercus, Rhododendrons, Symplocus and other species like *Ardisia macrocarpa*, *Berberis aristata*, *Brassaiopsis mitis*, *Dichroa fibrifuga*, *Toricella tiliifolia*, *Daphne bholua*, *Leucosceptrum*, *Viburnum cylindricum*, *Cinnamomum bejolghota*, *Samraria nepalensis* and *Arundinaria*. The ground species include mostly common species like *Artemisia vulgaris*, *Eupatorium adenophorum*, *Inula cappa*, *Rubus ellipticus* and *Urtica parviflora*. There are also climbers like *Hedera nepalensis*, *Agapetes serpens*, *Orchids*, *and ferns like Pteridium aquilinium*, *Diplazium esculentum*, *Drynaria* and *Pteris wallichiana*. Grass species include *Poa annua*, *Anthraxon*, *Borinda*, *Cynodon dactylon* and *Cyperus cyperoides*.
- 135. Moving further onwards towards TL14, the vegetation is not as dense as it passes close to the Mangdechu Dam colony area and the Taktse Community Forest. Here the oaks are not as dominant but other tree species such as Castanopsis hystrix, Daphnephyllum, Exbucklandia populnea, Symplocus ramossima, Symplocus glomerta, Lyonia ovalifolia, Maesa chisia, Rhododendron arboretum, Toricellia tiliifolia, Prunus cerasoides, Alnus nepalensis and Viburnum are found. The middle lower trees and shrubs comprise of Viburnum cylindricum, Eurya acuminata, Dichroa fibrifuga, Daphne bholua and Berberis aristata. The ground vegetation is dominated largely by Eupatorium adenophorum, Anaphalis triplinervis, Ancelia

aptera, Cirsium falconeri and ferns like Pteridium aquilinium, Diplazium esculentum, Pteris wallichiana and other species like Smilax, Solanum virginianum and Swertia chirata. Orchids like Cymbidium, Otochilus lanciliabius, Dendrobium candidium, and Coelogyne are also found.

136. Continuing onwards towards TL25, other trees species such as *Michelia doltsopa*, *Prunus cerasoides*, *Persea bootanica*, *Rhus wallichii*, and Oaks (*Quercus griffithii*, *Quercus glauca*, *Quercus semicarpifolia*, *Quercus lanata*) are observed again with *Sympolocus*, *Lyonia ovalifolia*, *Exbucklandia populnea*, *Maesa chisia* and Rhododendrons. The middles storey is almost the same as before but also including species like *Nellia rubiflora*, *Lindera pulcherra*, *Viburnum cylindricum*, *Edgeworthia gardneri*, *Ilex aquilinium*, and *Cotoneaster microphyllus*. Additional ground species observed include *Tupistra chinensis*, *Solanum khasianum*, *Smilax ovalifolia*, *Raphidophora*, *Hemiphragma heterophyllum*, *Inula cappa*, *Pilea umbrosa*, *Potentilla fruticosa*, *Lycopodium clavatum*, *Glienchenia gigantean*, *Vanda cristata* and *Oleandra pistillaris* and *Otochilus* species.





The density of trees is much lower moving towards TL42 as the forest is mostly scrub forest with fewer trees and scantier understory and barren land. Tree species are mostly Quercus lanata, Quercus semicarpifolia, Quercus griffithii, Alnus nepalensis, Rhus wallichii, Maesa chisia, Lyonia ovalifolia, Castanopsis hystrix, Docynia indica, Symplocus ramossima, Exbucklandia populnea, Rhododendron and Schima wallichii. The scanty shrub layer comprises mostly of Artemisia vulgaris, Eupatorium adenophorum, Rubus ellipticus, Berberis aristata, Maesa chisia, Leucoceptrum species, Zanthoxylum and Indigofera dosua. Even the ground

vegetation is scanty comprising mainly of *Pteridium aquilinium*, *Eupatorium adenophorum*, *Osbeckia stellata*, *small Rhododendrons*, *Anaphalis triplinervis*, *Artemisia vulgaris*, *Rubus ellipticus* and some grass species like *Poa annua* and *Arthraxon* species.



Photo 5:3: Photo showing vegetation cover along TL

- 137. From TL 40, the TL passes through private land, plantation forest and scrubland interspersed with forest land. The main trees species are *Castanopsis hystrix, Lyonia ovalifolia, Quercus lanata, Symplocus ramossima, Pinus roxburghii* and *Schima wallichii*. As the elevation drops and the climate is warmer, the vegetation becomes more sub-tropical, with species like *Duabanga grandiflora, Alnus nepalensis, Bischofia javanica, Rhus chinensis, Pinus roxburghii, Ficus roxburghii, Ficus semicordata*, and *Quercus lanata* in Langthel and Yurmo. Overall tree density is not very high along the TL, with a maximum of 14 trees per 100 m².
- 138. Shrubs include Berberis aristata, Ardisia macrocarpa, Edgeworthia gardneri, Dichroa fibrifuga, Viburnum erubescens, Mahonia nepalensis, Brassaiopsis mitis, Daphne bholua, Viburnum cylindricum, Maesa chisia, Eurya acuminatum, Rhododendron arboreum, Symplocos glomerata, Viburnum cylindricum, Ilex species, Cotoneaster microphylla, Elaeagnus parvifolia, Rubus ellipticus, Eupatorium adenophorum, Zanthoxylum species,. Vaccinium myrtillus, Rhododendron vaccinoides, Indigofera dosua, Aconogonum molle, Datura suaveolens, Adhatoda vasica and Arundinaria species
- 139. Herbs include Artemisia vulgaris, Artemisia indica, Leucas ciliata, Inula cappa, Leucosceptrum species, Eupatorium adenophorum, Urtica parviflora, Anaphalis triplinervis, Cirsium falconeri, Solanum virginianum, Smilax ovalifolia, Swertia chirata, Pilea umbrosa,

Ainsliaea aptera, Elatostema platyphyllum, Hedychium ellipticum, Elshotzia fruticosa, Osbeckia stellata, Oxalis corniculata, Pilea anisophylla, Colocasia esculenta and Pilea umbrosa.

- 140. Ground cover includes *Polygonum runcinatum*, *Hydrocotlye javanica*, *Fragaria nubicola*, *lycopodium clavatum* (moss), *Poa annua* (turf grass), *Hemiphragma heterophyllum* (creeping plant), *Potentilla fruticosa*, *Potentilla microphylla*, *Tupistra chinensis*, *Osbeckia stellata*, *selaginella sp* (spike moss),
- 141. Climbers include Raphidophora species, *Hedera nepalensis* and *Agapetes serpens*. Ferns include *Diplazium esculentum*, *Pteris wallichiana*, *Oleandra pistillaris*, *Glienchenia gigantean*, *Pteridium aquilinium* and *Drynaria propinqua*, *Adiantum caudatum*, Asplenium sp.
- 142. Orchids include *Calanthe* sp, *Eria coronaria*, *Phalaenopsis* sp. *Vanda cristata*, Cymbidium cyperifolium, *Gastrochilus* sp., and *Dendrobium candidum*, Coelogyne corymbosa and Bulbophyllum sp.
- 143. Mushrooms that can be found there include Amanita sp., *Lactarius piperatus*, *Laetiporus* sp., *Lycoperdon* sp., *Trichaptum abietinum*, *Boletus sp.*, *Laccaria sp.*, *Ramaria sp.*A list of all species recorded is provided in the Annex.

Human influence/disturbance of the forest

- 144. The main threat to forest cover and integrity is human activity. In each surveyed plot, the level of human influence in the area was recorded according to the following categories:
 - 0: None (no grazing, fire, logging);
 - 1: Low (undisturbed forest, but with a few signs of human presence);
 - 2: Medium (fairly undisturbed under-story vegetation, but with some signs of human presence);
 - 3: High (forest is grazed, trees cut and under-story vegetation disturbed); and,
 - 4: Very High (very disturbed and degraded habitat; highly disturbed under-story vegetation due to grazing, human activities, lopping of trees).
- 145. The most significant finding from the field assessment was that in all plots Disturbance was rated as 'High'. This reflects the high use of the site for grazing, cutting of trees, collection of firewood or leaves for fodder. This is examined further below. Basically, the TL extends from below and the moves above the National Highway from Trongsa to Zhemgang, and all along the Transmission line alignment, it criss crosses access roads to the Mangdechhu project Dam Axis site runs parallel to the 66KV and 400 KV lines or crosses some footpath.

Table 5.18: Proximity to access roads and other structures along TL

Tower location	Elevation	Accessibility/Adjacent structures along TL
----------------	-----------	--

Tower location	Elevation	Accessibility/Adjacent structures along TL
Pothead	2040	Mangdechhu dam site, take off point
OOP1	2067	below national Highway, near grazing land
TL6	2110	Mangdechhu dam axis Road, old footpath
TL7	2060	opposite mangdechu dam colony
TL8	2047	parallel to existing 66KV, T60, T61
TL9	2035	above Highway, Crossing 66KV
TL10	2054	Access road to Mangdechu Dam colony area
TL12	2126	Mangdechu Dam colony top and Taktse Road, old footpath
		Road to cremation ground, Approach road to Taktse College,
TL13	2247	old footpath
TL21	2104	Parallel to 66KV
TL24	2091	Above 66KV line
TL27-		Access road to Samcholing MSS school and Kuengarabten
TL42	2060	Nunnery Centre
TL40	2156	under Taktse community forest
TL43-		
TL50		Old footpath, Approach road to Mangdechu Surge shaft
TL52	1488	Parallel to 400KV/D/C line, private land
TL53	1426	Crossing 400KV D/C line
TL54	1296	Parallel to 400KV/D/C line, private land
TL55	1295	Parallel to 400 KV, D/C line
TL56	1238	Parallel to 400 KV, D/C line

146. The field assessment concluded that the project area does not contain any pristine forest as the entire area has been heavily grazed by the cattle, or used for collection of leaf litter, or revegetated recently as community forests.





147. The picture shows the alignment of the existing 66kV line. The proposed 132kV line is aligned parallel to this line just above it. The picture below shows the same 66kV line and the access road to the Mangdechhu colony below it.



Photo 5.5: The village and the Highway just below the TL




Photo 5.6 and 5.7: The vegetation and forest cover along the proposed alignment



5.2.3 Wildlife

- 148. A wide variety of fauna inhabits the forested areas in Trongsa due to its high forest cover and diversity in elevation and forest types.
- 149. During the Biodiversity survey, the study of faunal distribution and its occurrence was conducted by looking at specific plots of 10x10m, every 250m along a transect running parallel to the Transmission line. Within each plot, observations on Visual observation of wildlife signs (rooting, feeding, resting, fecal droppings, foot prints, or wildlife sounds were recorded. Also, during public consultation meetings, additional information on wildlife presence was also discussed.
- 150. From a total of 74 plots, wildlife signs were found in 23 plots. Species signs that were observed during mammal surveys include those of Sambar Deer (footprints), Barking Deer (sighted, as well as foot prints and dung), Wild Pigs (resting/wallowing place, footprints) and Assamese Macaque (sighted). All of these four species are considered as pest species and responsible for crop damage and endless sleep for farmers who spend hours protecting their crops from these species.



Graph 5.5: Percentage of plots with wildlife signs in them

Table 5.19: Types of wildlife signs found during biodiversity survey

Plot No.	Wildlife species	Sign type	No. of signs
1	Wild pig	resting pl.	1
2	Barking deer	dung	1 clump

Plot No.	Wildlife species	Sign type	No. of signs
7	Barking deer	dung	1 clump
7	Wild pig	rooting	1
8	Wild pig	rooting	1
9	Barking deer	footprint	3
12	Barking deer	dung	1
19	Barking deer	footprint	3
25	Wild pig	rooting	1
30	Wild pig	rooting	1
32	Jungle fowl	scratching	many
33	Sambar	footprint	4
34	Barking deer	spotted	1
37	Wild pig	resting place	1
38	Wild pig	rooting	1
39	Barking deer	footprint	1
44	Wild pig	Rooting	1
45	Wild pig	wallowing	1
46	Wild pig	rooting	1
49	Wild pig	wallowing	1
52	Wild pig	nesting	1
55	Wild pig	rooting	1
60	Wild pig	footprint	1
65	Wild pig	rooting	1
	TOTAL plots		23

- 151. Much of the lower slopes in the Project area comprises of Agricultural Land. In the warmer Broad-leaved Forest that occurs along the Trongsa Zhemgang Road there are signs of high anthropogenic disturbances including heavy grazing and lopping so signs of wildlife are much lower.
- 152. Based on the forest type and lower level of disturbance higher up on the slopes, the rarer and more elusive species like Leopards, Bears, Capped Langur, Goral, Gray Langur, Himalayan Black Bear, Indian Porcupine, Little Himalayan Rat, Jungle Cat, Leopard Cat and Otter are expected.

Table 5.20: Status of wildlife present in the project area

No.	Common Name	Scientific Name	Expected in project area	Status in Bhutan	IUCN status
1	Leopard	Panthera pardus	Yes	Sch-I	Near threatened
2	Clouded Leopard	Neofelis nebulosa	Yes	Sch-I	Least Concern
3	Leopard Cat	Prionailurus bengalensis	Yes	Sch-I	Least Concern
4	Asiatic Black Bear	Ursus thibetanus	Yes	Sch-I	Vulnerable
5	Wild pig	Sus scrofa	Yes		Least Concern
6	Wild dog	Cuon alpinus	Yes		Least Concern
7	Barking deer	Muntiacus muntjak	Yes		Least Concern
8	Sambar	Cervus unicolor	Yes		Least Concern
9	Indian crested porcupine	Hysterix indica	Yes		Least Concern
10	Grey langur	Semnopithecus entellus	Yes		Least Concern
12	Goral	Naemorhedus goral	Yes		Near threatened
13	Indian gray mongoose	Herpestes edwardsii	Yes		Least Concern
14	Bengal fox	Vulpes bengalensis	Yes		Least concern
15	Assamese macaque	Macaca assamensis	Yes		Near threatened
16	Capped Langur	Trachypithecus pileatus	Yes		Vulnerable
17	Himalayan Serow	Capricornis thar	Yes		Near threatened
18	Jungle cat	Felis chaus	Yes		Least concern
19	Yellow-throated Marten	Martes flavigula	Yes		Least concern
20	Gaur	Bos gaurus	Yes	Sch-I	Vulnerable
21	Little Himalayan Rat	Niviventer eha	Yes		Least concern

Schedule I* means that the species is included in the Schedule I of the Species and Nature Conservation Act of Bhutan.


153. Given the presence of the National Highway, the extent of degraded forests and the cleared RoW, and level of human disturbance, it is expected that this area is much less important to the rarer wildlife compared to the undisturbed great expanse of suitable habitat on the higher more remote altitudes away from the villages and the highway.

5.2.4 Birds

154. At total of 123 species of birds were recorded in and around the Project site. These are presented in the table. From these the Rufous-necked Hornbill (Aceros nipalensis) is listed as Vulnerable in IUCN and a totally protected species listed in Schedule-I of the Forest and Nature Conservation Act, 1995. The Satyr Tragopan and the Yellow-rumped Honeyguide are both listed as 'Near threatened' in the IUCN Red List. All of these three species were recorded once during the field survey, the Stayr Tragopan near the Taktse Community Forest area, and the

^{**} The project area is taken to mean within about 5 km of the specific project component footprints.

Yellow-rumped Honeyguide and the Rufous-necked Hornbill (2 Male and 1 Female) near the top of Kuengrabten.



Graph 5.6: Frequency of bird occurrence along transects

155. Many of the species that are found in the project site fall in the "Least Concern" category. These include Thrushes, Bulbuls, Laughing thrushes, Robins, Tree pies, Eagles, Mynas, Minlas, Fulvetta, Honeyguides, Leafbird, Magpie, Fantails, Warblers, Babblers, Pigeon, Wallcreeper, Prinia, Fork tail, Sparrow, Crows, Redstarts, Pheasants and many more. A full list of species is detailed in **Annexure 3**.

5.2.5 Amphibians and Reptiles

156. Till date no specific surveys have been specifically conducted on Amphibians and Reptiles in Trongsa dzongkhag. Thus, there is no baseline information on species that thrive there. During the field surveys, snakes such as Pit viper (*protobothrops*) and Green rat snake (*Ptyas nigromarginata*) were recorded from the Nikachhu project area. Amphibians are usually found in moist places and near water bodies. Flat tailed Gecko (*Hemidactylus platyurus*) and the common Garden lizard (*Calotes versicolor*) can also be found there. Lizards found in Mangdechu include Eastern green calotes (*Calotes jerdoni*), Draco (*Draco dussumieri*), Green Keelback (*Macropisthodon plumbicolor*), Banded Krait (*Bungarus fasciatus*), Python (*Python molurus*) and Common skink (*Mabuya carinata*). (MHEP, no date).

157. The tadpole could belong to an *Amolops* sp. since this group of frogs inhabits mountain rapids. Other species of frogs spotted in the Mangdechu area include East Asian Tree Frog (*Polypedates leucomystax*), Giant tree frog (*Rhacophorus maximus*), Himalayan torrent frog (*Amolops marmoratus*), Himalayan bull frog (*Pea leibigii*), Tree frog (*Polypedates spp.*) and Leaping frog (*Rama erythraea*) (MHEP, no date).

- 158. There is a good diversity of Macro invertebrates at the project site. These include Flies (Diptera), Beetles such as the Rhinoceros beetle, dung beetle, Ladybird, Stag beetle, (Coleoptera), Grasshoppers and Crickets (Orthopterans), Aphids (Hemiptera), Stoneflies (Plecoptera), Mayflies (Ephemeroptera), Caddis flies (Trichoptera), Dragonflies and damselfly (Megaloptera), Moths and Butterflies (Lepidoptera), Bees and Wasps and Ants (Hymenoptera), Spiders (Araneae), Leeches (Clitellata), Ticks (Acarina) and Worms (Oligochaeta).
- 159. 49 species of butterflies were reported from the Mangdechhu area. These are mainly from the families Papilionidae, Nymphalidae, Pieridae, Hesperidea and Lyeaenidae.

5.3 Economic development

5.3.1 Land Use, Industry and Agriculture

160. 87.6% of the Dzongkhag is covered by forest, leaving only 5.7% for agriculture, 3.6% Tsamdro (pasture), 0.1% settlements with the remaining 3% covered by rocky outcrops and water bodies. The dominant agricultural practice is Kamzhing or dry land cultivation followed by Chhuzhing or wetland cultivation. Tseri farming (slash and burn cultivation) is also practiced in some areas. The total land cultivated is 2,287.2 km² (NSB, 2011).

Table 5.21: Land use cover in Trongsa and the Country


Land use	% cover dzongkhag	% cover National level
Forest	87.16	4.14
Agriculture land	1.26	0.06
Meadows	2.87	0.14
Shrubs	6.21	0.29
Water bodies	0.16	0.01
Snow cover	1.78	0.08
Others	0.56	0.03
_	100	4.75

- 161. In terms of area, the most important crops grown are Paddy, Maize, Buckwheat, Wheat and Barley. Other crops grown to a lesser extent include Potatoes, Chilli, Radish and other green vegetable. The perennial crops consist mostly of Oranges, Guava, Banana and Cardamom (Atlas of Bhutan, 1997).
- 162. Livestock rearing also plays a very important role in supporting the rural livelihood. More than 90% of the households own livestock, which is an important source of cash income for farmers. Livestock also provide farmyard manure and draft power for farming.

163. The town contains six small industries of which two are agriculture based and four forestry based. There are 57 small licensed contractors but not all are operational. The town has ten hotels and eight restaurants, and couple of repair workshops but there is no heavy industry or major manufacturing industry.

Table 5.22: Villages that are crossed along the TL alignment

Section of TL	Villages along the TL
Section 1: Port head Yard (TL1) to Dam colony opposite (T6).	Tashidingka, Eusa
Section 2: Tashidingka(TL7) to Taktse top(TL14)	Tashidingka, Eusa, Taktse.
Section 3: Bubja top (TL15) to kuengarabten(TL26)	Taktse, Eusa,
Section 4: Kuengrabten top (TL27) to Lhakhang Jap (TL42)	Bubja, Changrey, Kuengarabten,Shomchholing,
Section 5: Kompey (TL43) to Raphy (TL50)	Khamey, Raphey top.
Section 6: Raphey top (TL51) – Alternative-Yurmo (TL56)	Raphey, Yurmoo area.



Map 5.5: Land use in Project area

- 164. Only 67% of Drakteng gewog falls under forest cover as it is one of the more populous areas (population density of 31.9 km²) but 78% of Langthel is under forest cover. The Trongsa Zhemgang highway runs through the Gewogs acting as a main artery for economic development.
- 165. Paddy, maize, wheat, and vegetables are the major crops cultivated in the two gewogs with Mandarin more commonly grown in Langthel. Most households rear livestock which is an important source of income. While households earn from farming, some members of the household are involved in business, work in the Civil Service or the Private Sector. The neighboring forests are used for collection of leaf litter and for grazing but households are not totally dependent on the forest for their livelihood. Thus the project is not expected to cause any impacts on livelihood benefits from the forest. In fact, it is more likely that locals will benefit in terms of employment with the Contractor, or with the Project for its Conservation Programs, through rental of rooms to Project staff or through the sale of agricultural and dairy products.

5.3.2 Infrastructure

- 166. Infrastructure is better developed in the towns because of the technical difficulties presented by the mountainous terrain, and the proportionally high cost of providing services to scattered communities. The government is however committed to providing for the needs of the rural population, and has made significant progress over the past few decades. For example around 97.2% of households have access to safe drinking water through pipes, via household systems in the towns and larger villages, and community standpipes in smaller villages.
- 167. Like most other Dzongkhags, there is no centralised sewerage system in Trongsa, but 92.6% of the households have self-built pit latrines in the villages, which are normally located in a brick or wooden enclosure away from the house.
- 168. The MHEP is currently under implementation with major infrastructure works such as tunnels and access roads being constructed. There are three micro-hydel stations at Kuengarabten, Sherubling and Tangsibji.
- 169. Only 23.6% of Households use electricity for cooking, while 21.8% use LPG, and 54.2% of the households utilise fuel-wood for both cooking. Less than 1 % uses kerosene. The drainage infrastructure in the towns consists mainly of open concrete drains alongside roads and shops. There is a waste disposal system implemented by the District authorities but no such system exists in rural areas where people generally burn their waste, or deposit it on open ground.
- 170. Every Gewog in the Dzongkhag has a BHU, RNR centers and a School each but the entire district has only one Post Office and one Bank. Almost every household has a mobile phone and 631 households have telephone connections in their house.

5.3.3 Transportation

- 171. The total road network in Bhutan amounts to 10,578 km. From this, 49.6% comprises of farm roads, many of which were recently constructed during the past decade. The Primary and Secondary National Highway covers 23% of this road network. The remaining 27.3% comprises of district roads, urban forests, forest roads and access roads.
- 172. The East-West lateral highway and the Trongsa-Gelephu highway passes through Trongsa connecting almost all the Gewogs in the Dzongkhags by motorable roads. The district has a total of 392km of road network. This includes 174.74km of national highway, 24km of district road, 178km of farm roads, and the remaining 14.8km comprises of power tiller tracks, access roads or urban roads. Still there are a number of settlements that are still remote due to lack of feeder roads.
- 173. Private minibuses provide a service between the main towns, and minibuses run by tour companies ferry tourists to the more popular trekking destinations. There are few vehicles in the villages where transportation is mainly by foot or on horseback.
- 174. Domestic air travel includes flights from Paro (the only Airport) to Bumthang and Yongphula. From the outside, Paro can be reached via international travel from Bangkok, Bangladesh, Calcutta, Delhi, Singapore and Nepal.

5.3.4 Tourism Industry

- 175. Before the 1970's only the royal family had the authority to issue invitations to Bhutan, so almost all foreign visitors were royal guests. The first time a large number of foreign visitors entered the kingdom was for the coronation of the fourth king in 1974, and this was followed soon after by the first paying tourists. Paro airport opened in 1983, and the newly formed national airline, Druk Air started operating flights to Kolkata. Tourism grew gradually, and in 1991 the industry was privatised, and numerous tourist agencies were established.
- 176. Visitor numbers have continued to rise, particularly over the past few years, despite the requirement for all tourists to pay a non-refundable daily tariff of US \$200 to the tour operator, for the cost of accommodation, food and internal travel.
- 177. There are a total number of 741 registered tour operators in the country but only 318 were operational in 2010. There are at least 8,818 people directly employed and 13,227 indirectly employed by the Tourism industry (Bhutan Tourism Monitor, 2011). The highest number of tourists visiting Bhutan was recorded in 2012, with visitor arrivals peaking at 105,407, representing a growth of 64.62% over the previous year. From the International segment, Japanese arrivals surpassed US arrivals for the first time by contributing 15.98% followed by USA with 13.67% of total international visitors. China remained the third biggest contributing 8.57% in 2012. There was also significant increase in visitors from other countries too.


- 178. Because of the difficulty of internal travel in Bhutan, requiring long journeys on winding roads between and over mountains, only relatively fewer tourists venture to the east of the country where there are few hotels or major attractions. Tourism has little impact in the villages because of the difficulty of reaching most locations, so most villages remain much as they have for the past few centuries.
- 179. Trongsa town being located right on the National highway has many visitors. In terms of visits to the districts, Trongsa ranked 6th in terms of visitors with 7,435 visitors in 2012, of which over 50% visited during the months of September-November, and 27% visited during March-May. About 7 % visited during the winter (December-February) and 6% during summer (June- August).

5.4 Social and Cultural Resources

5.4.1 Demography

- 180. The demographics of Bhutan show that it is a country with a low and relatively dispersed population, with the 2013 census¹¹ reporting a total of 733,004 people living at an average density of 16 persons/km². However, population density in districts like Trongsa is much lower, 8 persons/km². This is probably due to rural urban migration of the younger generation from the countryside into towns to seek better economic rewards. The population growth rate is 1.3% per year.
- 181. Trongsa is typical of most Dzongkhags, as it contains a small main town and large areas of countryside in which people live in small scattered communities. The total projected population for the Dzongkhag in 2009 was 14,712 with an annual growth rate of 1.4%, with almost equal number of males and females. The rural character is shown by the fact that there are 56 villages with a total of 2,739 households.
- 182. The population of Bhutan includes many ethnic groups such as the Sharchops from the east, Ngalongs from the west, Khengpas from the central region, nomads from the north and Lhotshampas from the south. These (and others) are all found in Trongsa dzongkhag, especially due to the large influx of non residents. Because of the mix of ethnicities a wide variety of dialects is spoken, of which Dzongkha, Khengkha, Mangdep, Sharchop and Nepali are the most common.

¹¹ Population and Housing Census of Bhutan 2005: National Statistics Bureau, RGOB, Thimphu.



Map 5.6: Map showing the different gewogs in Trongsa

Source: NSB_Population & Housing Census of Bhutan 2005

5.4.2 Health and Education

183. As in most other Dzongkhags, the main administrative centre is housed in the Dzong (originally a fort or monastery). Apart from a hospital and government offices, there are few other public facilities in the town, which is very small and contains shops and restaurants, hotels, and a small number of permanent houses. Expansion of the town has largely been constrained by the steep topography.

184. The only hospital is in Trongsa town, which has two doctors and has room for 20 beds. There are 6 Basic Health Units (BHUs- level II) in the gewogs, plus 21 Out-reach Clinics (ORCs) in some of the larger villages. There are also 2 Units that provide Indigenous treatment and services.

Table 5.23: Medical Facilities in Trongsa and the entire country

Medical facility	No. in Trongsa	Total in the country
Hospitals	1	32
BHUs	6	181
ORCs	21	518

185. There is only one Higher Secondary School, Two Middle Secondary Schools, Two Lower Secondary Schools, 4 Primary schools and fifteen Community schools totalling 24

schools in the district. At present 3,822 students were enrolled in these schools last year with a teacher student ratio of 1:16. There is a further forty six Non-formal education centres

Table 5.24: Types of schools in Trongsa and the entire country

Type of School	No. in Trongsa	Total in the country
Primary School	19	353
Lower Secondary School	2	93
Middle Secondary School	2	59
Higher Secondary School	1	48
	24	553

186. The entire country has 139 Agricultural Extension Centers (of which 5 are in Trongsa) and 4 Regional Research Centers. Within each District Agriculture Extension services are provided by the Agricultural sector.

5.4.3 History and Culture

- 187. Till early 17th century, Bhutan was the battleground of warring tribes that were later unified by Shabdrung Ngawang Namgyal, a Tibetan lama and military leader, who came to Bhutan in 1616. He established the dual system of government where the power was shared by an administrative leader and a spiritual leader together. Ugyen Wangchuck, the Penlop of Trongsa, was the first hereditary monarch of Bhutan. He came to power in 1907 and since then Bhutan has had five Monarchs. From a constitutional monarchy, the country transitioned to a democracy after its first elections in March 2008.
- 188. Bhutan places very high emphasis on its culture and believes that its future sovereignty as a nation state will continue to depend on its cultural identity (Planning Comission 1999). Bhutanese traditions include the rituals, customs, dress, code of etiquette, religious ceremonies, and customs, among others (Chophel, S, 2012) and its traditional values have always been largely shaped by Buddhist concepts. To preserve its unique age-old culture and traditions, the Institute for Culture was established as early as 1961. The country is dotted with numerous Buddhist religious and cultural sites some of them dating back to the 17th century. Each district has special religious celebrations called Tsechus where traditional mask dances are performed on auspicious days. These dances and festivals provide an important means to impart knowledge to the public.
- 189. Trongsa has the famous Dzong which was built in 1648. This was the seat of power over central and eastern Bhutan during the reign of both the first and second kings. All four kings were invested as Trongsa Penlop ("governor") prior to ascending the throne. It currently holds 28 religious altars in its premises.

- 190. Another famous structure is the Ta Dzong, a watchtower, built in 1652, which once guarded Trongsa Dzong from internal rebellion. It has four observation points resembling Tiger, Lion, Garuda, and Dragon. It is now a fascinating museum for visitors and locals.
- 191. The Threupang Palace is the birthplace of the Late King Jigme Dorji Wangchuck and he also spent most of his early childhood days here.
- 192. The Chendebji Chorten lies en route to Trongsa. It is patterned on Kathmandu's Swayambhunath Stupa, with eyes painted at the four cardinal points. It was built in the 18th century by Lama Zhida, to cover the remains of an evil spirit that was subdued at this spot.
- 193. Kuenga Rabten palace was constructed on 1929. It is located in Kuenga Rabten, Drakteng Gewog, Trongsa District, about 24 km south of the main town of Trongsa on the road going to Zhemgang and Gelephu, situated on a slope overlooking the main road. During the first half of the 20th century, the palace served as winter residence for the second King, Jigme Wangchuck and his senior Queen, Ashi Phuntsho Choden. At present, the palace is looked after by monks from the central monastic body in Trongsa. Around fifty monks are living at the palace, including two teachers.

6 Anticipated Project Impacts

6.1 Introduction

- 194. The environmental, social and economic impacts of the project were assessed: to help determine the acceptability of the project, and to ensure that any residual impacts are properly recognized and addressed by appropriate mitigation measures. The process involved looking at the environmental baseline features, uniqueness, potential vulnerabilities and the nature, location, and duration of construction activities, and project design features in effect throughout operation.
- 195. A process of examining all possible interactions between all project components, in all phases (pre-construction, construction, and operation) and the environmental and socio-economic features in and around the project (5km) was then used as a "filter", to sharpen the impact assessment and focus on the critical interactions, and to separate out the less important interactions. Less important interactions are usually the ones that self-correct over time, due to the short-term nature of some interactions and the resilience of certain features.

6.2 Determining the degree of potential impacts

- 196. The degree of impact of the proposed transmission line is determined by the following factors:
 - (i) The degree of disturbance that already exists in the project site;
 - (ii) The uniqueness of the resources or protected nature of the habitat/forest/landscape;
 - (iii) The threat of future disturbance or considering how this project will affect land use in the future:
 - (iv) Duration of the impact or activity. Long term impacts exist as long as the Transmission line is in place, while temporary impacts occur only during pre-construction and construction phases or at infrequent intervals during operation phase (in case of accidents or repair or RoW maintenance).
- 197. To be clear on the nature of the impacts, the following definitions of impacts that embody the concept of recovery from impact are used:
- 198. A *major impact* can be considered as follows: (for environmental resources) the project affects an entire population or species in sufficient magnitude to cause a decline in abundance and/or change in distribution beyond which natural recruitment (reproduction, immigration from unaffected areas) would not return that population or species, or any other populations or species dependent upon it, to its former level within several generations; or (for social values), the project affects a subsistence or commercial resource use, business activity, or social behavior to the degree that the well being of the user or local community is affected over the long term. These kinds of impacts are difficult to mitigate, except by changing location or significantly altering project design.

- 199. A moderate impact (less significant) can be considered as follows: (for environmental resources) the project affects a portion of a population or habitat and may bring about a change in abundance and/or distribution over one or more generations, but does not threaten the integrity of that population, or any population dependent upon it; or (for social values), a short-term effect upon the social and economic well being of resource users or local communities using the project area may also constitute a moderate impact, but from which recovery is expected within 3-6 months. These kinds of impacts can be mitigated or may be acceptable without mitigation, if recovery can be assured.
- 200. A *minor impact* can be considered as follows: (for environmental resources) the project affects a specific group of localized individuals (plants and animals) within a population or a habitat over a short time period (one generation or less), but does not ultimately affect other trophic levels or the population itself; or (for social values), activities of resource users or local communities in the project area are not affected measurably beyond a minor disturbance of resource use or local activities, from which recovery is relatively quick. Impacts of this nature are often amenable to mitigation, or require no mitigation at all.
- 201. Some aspects of the environment that are not expected to be significantly affected by the construction process have been screened out and will not be mentioned further in assessing the impacts of the construction process (see **Table 6.1**).

Table 6.1: Fields in which construction is not expected to have significant impacts

Field	Rationale
Climate	Short-term production of dust is the only effect on atmosphere
Geology and seismology	Excavation will not be large enough to affect these features
Industries	There are no major industries in any areas to be affected by the project
Tourism	Tourists mostly drive by the villages located as these are located on the highway
Population and communities	Construction will not affect population numbers, location or composition

202. Basically, a habitat or population that can recover fairly quickly from a project impact is not considered to be significantly impacted. Also, if the habitat or population affected is only a small percentage of the total population or habitat in the immediate area (perhaps 1-2%), and there is continuity of habitat in affected areas with adjacent habitat in unaffected areas (providing a refuge for affected species), then the impact can also be considered insignificant, as it would likely not be visible or measureable within the spatial and temporal variability of habitat quality and function, and it would not create a barrier (at this scale) to access to adjacent similar habitat, which can provide a buffer or compensating function. To help assess impact significance, for each project activity, all possible interactions with the environment are considered; this means direct and indirect impacts (the latter requiring other conditions to be in place for an impact to occur), and cumulative impacts (the results of project interactions being added to the possible environmental impacts of other projects and planned development in the area). With regard to socioeconomic parameters, if a project activity causes a negative impact

in one parameter that can be compensated by an overall positive development impact, then the impact can usually be considered to be acceptable.

- 203. All impacts are identified by phase and in three main categories;
 - (i) Economic impacts
 - (ii) Social impacts
 - (iii) Environmental Impacts
 - (iv)

6.3 Impacts during Pre-Construction

6.3.1 Economic Impacts

6.3.1.1 Impact from Temporary and Permanent Land Acquisition

- 204. There will be two kinds of land acquisition. Temporary land requirement will last at the most 18 months for the construction of labour camps, and for storage of construction materials and machinery. Permanent land acquisition is required for clearing the RoW for the TL.
- 205. Special care was taken when surveying the transmission line route to avoid settlements, private land, wetland, monuments, common property resources and public utilities. Of the 61 transmission towers to be constructed, 55 towers fall on government land and 6 towers fall on private land. 60 decimal of land will have to be acquired from 6 displaced households that will lose 10 decimal of land each towards the footprint of the 132 kV transmission towers. **Table 6.2** gives the details of land acquisition. Thus, the permanent land requirement is only 0.6 acres all of which falls in dryland (Kamzhing). **Table 6.3** gives the temporary land requirement.

Table 6.2: Details of project land acquisition

No.	Name of owner	Village	Thra m No.	Land require d	Land type	Drylan d	Wetland	Total Land	% of total land
1	Phurpamo	Yurmun g	284	0.1	dryland	3.4	2.462	5.862	1.7
		Yurmun							
2	Lemo	g	274	0.1	dryland	3	0	3	3.33
3	Tshering Mo	Refe	361	0.1	dryland	2	1.642	3.641	2.75
	Tshering								
4	Dema	Refe	52	0.1	dryland	3	3	6	1.67
	Sangay								
5	Wangdi	Refe	357	0.1	dryland	3.65	1.95	5.6	1.78
	Tashi	Kinga							
6	Wangmo	Rabten	372	0.1	dryland	2.13	2	4.13	2.42

206. The project does not displace any private fruit trees, standing crops, structures (homesteads/house or living quarters, other physical structure, commercial or industrial structure, business establishments, and rented or occupied commercial premises) religious.

community or cultural sites, or any common property resources. The only asset that is displaced by the project is land. Also, no indigenous people are displaced by the project.

- 207. As is indicated in **Table 6.2**, none of the households will lose more than 4% of their total land holding to the project so there will be no impact on incomes arising from land acquisition. The private land to be acquired is either barren or fallow land with no crops being grown on them so there will be no impacts on fruit trees or standing crops.
- 208. Given that the total amount of land required is minimal and that there are provisions in the Law for providing compensation, the impact of permanent project land acquisition are deemed to be acceptable. The direct impact of project land acquisition (temporary and permanent) requires compensation for loss of land (permanent) and loss of access to land. Compensation (as already worked out) will prevent any additional vulnerabilities for the affected households.

		Area,	
No.	Description	acres	Remarks
1	Storage Sites	1.8	
2	Workers camps	0.8	5 sites
3	Material stocking yard	0.8	
4	Site office	0.2	
	Total area required	3.6	

Table 6.3: Temporary land requirement

- 209. Temporary land is required from the Dzongkhag for setting up Contractor facility establishment, storage site and worker camps. This only amounts to 3.6 acres and will not be acquired but shall be taken on lease from the private land owners. It is expected that the Contractor Facility and storage sites will be selected at the last point along the Highway or access road (closest site to the TL alignment) to reduce transportation costs. The 230 workers during the peak construction shall be distributed in 5 gangs and their camps will be selected and scattered along the TL in the Government Reserved Forest.
- 210. Given the fact that both types of project land acquisition are less than 1% of the map area, and that temporary land acquisition will actually result in rehabilitated and re-vegetated, the net impacts of temporary and permanent project land acquisition are deemed to be acceptable.

6.3.2 Employment Opportunities

211. The positive impact of the project is that it will create opportunities for employment and supplier business, for the duration of the project construction through increase in demand for vegetables, milk products and meat. In addition, the project will be able to provide job

opportunities to the locality. The skilled labourers shall be hired from outside the locality or from India but the unskilled labour shall be given priority to the local people and the affected people, in particular. Job opportunities include clearing the RoW, transportation of materials, involvement in compensatory forestation programs and land management programs. The main requirement of local labourers shall be for headloading of materials.

6.3.3 Mobilization of Construction Equipment and Materials

- 212. Surveys in July 2012 indicated that in the Thimphu-Trashigang National Highway, the average number of vehicles passing is about 100 vehicles/day, which have already increased due to the construction of MHEP. For the construction of the TL, only few trucks shall be required to transport construction materials mainly the transmission tower parts. However, the trucks shall be hired as and when required only. For transportation at the site from the road points, headloading shall be done eliminating the need of any vehicle.
- 213. Thus, the impacts of mobilization of construction equipment are marginal since large numbers of heavy vehicles and machines shall not be deployed compared to MHEP.

6.3.3.1 Influx of Project Staff and Contract workers

214. It is estimated that 14 staff will be hired/deputed during the pre-construction and construction stage excluding security (see **Table 6.4**). This does not include Contractors and their regular staff plus migrant workers.

Table 6.4: Staffing requirements by BPC for the Project

No.	Description	No.
1	Project Manager	1
2	Assistant Engineer/Junior staff	3
3	Accountant/ Store In-charge/ Supervisor/ Foreman/Office Assistant/Driver (Type-II)	7
4	Temporary/casual staff	2
5	Environmental Monitoring Officer	1
	14	

215. The Project office will be headed by the Superintending Engineer (SE) or Senior Project Manager (SPM) who is currently responsible for the Mangdechu Transmission Component. He will be assisted by an Assistant Engineer, Environmental Officer and other Administrative and Support Staff (see **Figure 6.1**).

Superintendent
Engineer (Mangdechu)

Nikachu Transmission
line sub-project

Engineer
Environmental
Technician

Support staff
Driver

Figure 6.1: Organogram of the Project Management Unit

- 216. Since these staff are already currently at site working for the MHEP transmission line component, there will be no requirement for construction of project infrastructure, office or stores.
- 217. Contract workers under an individual contractor will come in two phases; during the preconstruction phase to undertake the land clearing and preparation (relatively small numbers) and during the peak construction phase, for all project components, when numbers may rise to about 230. For works which require skills such as foundation work, tower erection and stringing, skilled labourers shall be hired from outside the locality or even the foreign labourers. But for those works such as benching, headloading and clearing, local people shall be hired. This shall not only minimize the influx of foreign labourers but also provide job opportunities to the affected people.
- 218. With the likelihood to influx foreign workers, the main concerns include:
 - (i) Possible social instability (poor mingling of workers from outside the district, or from outside Bhutan, with local communities, although Bhutanese have increasing experience with worker influxes and seem to handle them with equanimity);
 - (ii) Increased pressure on housing, infrastructure, and services;
 - (iii) Risk of communicable diseases spreading in the local community;
 - (iv) Waste and sewage entering the local environment;
 - (v) Health concerns in the camps (communicable diseases, poor air quality), and
 - (vi) Safety issues at the work sites.
- 219. The contractor shall be mandated to brief the foreign labourer on the rules and regulations of the country including the code of conduct, forest and nature conservation requirement and even the regulation on occupational health safety and welfare and waste management. Most of the worker camps will be located along the RoW of the TL. There will be five campsites that will be spaced out depending on access and proximity to water sources,

approximately 3.5 km away from each other. The maximum number of workers at each campsite is not expected to exceed 50.

220. Since the number of workers immigrating shall be less, the impact on society will not be significant and with the camps located away from the community and the highway, the chances of workers mingling with the local people is minimum. While the economic impacts may be positive, temporary social impacts must be mitigated through proper planning to reduce the risk of possible social instability, risks of communicable diseases and health concerns.

6.3.3.2 Cultural and religious sites

221. While there are no cultural and religious sites along the RoW, there are a few religious and cultural sites within the Project area. For instance, towards the first quarter of the transmission line, there is a nunnery, the Karma Drupdey Palmo Chokyi Dinkhang below Tower TL28 (see **Photo 6.1**). Other religious sites are the cremation ground and the Lhakhang near TL 32. **Table 6.5** gives the details of the cultural and heritage sites.



Photo 6.1: The Karma Drupdey Palmo Chokyi Dinkhang Nunnery

Table 6.5: Cultural and heritage site details

SITE	Location	GPS (E)	GPS (N)	Site listed with Department of Culture
Cremation ground	TL13	27.44438	90.48647	No
Kuengrabten Nunnery centre	Tl28	27.38964	90.54028	Yes
Lhakhang Jap	TL32	27.41675	90.52747	No

- 222. During the design stage, extra care was taken to ensure that religious structures/public property was avoided. As can be seen from Photo 6.1, the TL towers are not located adjacent to the Nunnery and will not in any way or manner hinder any religious or cultural practices.
- 223. The net impacts of the Project on religious and cultural sites is small and transient because firstly, the District and local community place high emphasis on such sites and will not allow any infrastructure to obstruct them. Also, care has been taken during the survey to avoid any proximity to these sites. In addition, the EMP will include mitigation measures to minimize any unanticipated impacts on social and cultural resources and disturbance during festival or religious prayers during construction work.

6.3.4 Environmental Impacts

6.3.4.1 Impacts on air quality

- 224. With its high forest cover of 87%, low population density and little industry, the air quality of Trongsa is relatively good. Baseline data on PM_{10} in NHPP area was between 20.3 24.6 $\mu g/m^3$, only about one-third of the standard for Bhutan (75 $\mu g/m^3$); SO_x and NO_x levels were not detected while analyzing (reflecting the low population density, absence of heavy industry, and low traffic levels).
- 225. With the current ongoing construction works in MHEP, it is expected that air quality will be impacted due to cumulative impacts of additional machines and vehicles from NHPP. The only source for air pollution from the TL construction shall be the excavation which shall be carried out during benching and foundation work. However, with only about 9mx9m area to be excavated, the amount of dust generated will be minimal.

6.3.4.2 Increase in demand for water resources

226. It is estimated that about 230 workers will be deployed at various locations along the TL during the peak pre construction and construction period. According to the World Health Organization (WHO), 50 to 100 liters of water per person per day are needed to ensure that most basic needs are met and few health concerns arise. Assuming usage of 50 litres of water

per day for each worker (as communal kitchens and pit latrines are expected to be used), the total water requirement during peak construction period is 12,500 liters per day. **Table 6.6** presents the water requirements.

Table 6.6: Total quantity of water required for domestic and construction purposes

No.	Purpose	No of staff/workers	Water Requirement (liters per day)	Total water required (in liters per day)
1	Project staff requirement	14	50	700
2	Contractor facility and workers	230	50	11500
3	Construction works		300	300
	Total water required			12,500

- 227. While the water in the labour camps shall be required throughout the peak construction, for construction work water shall be used only for concreting. About 300 litres/day of water shall be used in concrete works. However, concreting shall be done only for laying foundation for the tower.
- 228. About 50 liters of water will be also required for sprinkling on to the area of excavation to suppress dust. However, this shall be required only during the excavation at tower foot. All water requirements will need to be met from nearby streams, which have been identified in the EMP.
- 229. The net impacts of the Project activities on water resources is small and transient because the only use of water for construction of the TL is to serve for domestic purposes and several stream runs through the project area from Tashidingkha to Yurmo. Water use has been calculated for the peak period and could be considerably lower than the estimated quantity depending on number of workers at each site.

6.3.4.3 Risk of poaching by workers

- 230. With increasing intrusion of workers in remote locations, the risk of poaching is quite real, especially since the project site is far from town (> 50 km), and meat is not readily available in the rural areas. Also, these areas are not frequented by Forestry Personnel so monitoring may not be quite as often.
- 231. The net impacts from poaching, although transient, can become significant if these risks associated with a worker influx are not addressed at the beginning of the Project with good planning and suitable awareness measures along with monitoring of project sites by Forestry Personnel.

6.4 Impacts during construction phase

6.4.1 Economic Impacts

- 232. The project will create opportunities for employment and supplier business, for the duration of the project construction. These will be through increase in income generating sources. The project will bring positive benefit if the Project and Contractors give first priority when employing the displaced persons in work such as forest clearance along the RoW, road repair and maintenance, water supply work, afforestation, planting of seeds, nursery work, fencing, construction of retaining walls etc. These do not require much expertise and can easily be taken up by locals.
- 233. Another source of income may be through increase in sales of fresh vegetables, dairy products and food to workers and travellers through roadside stalls or small outlets/shops near worker camps.

6.4.2 Social Impacts

6.4.2.1 Impacts from Influx of more workers

234. The social impacts described in the pre-construction phase will continue into the Construction Phase with more workers, increased number of work locations, more frequent transportation of construction materials as additional workers are brought in to complete the work, the risk of social conflicts, risks of spread of communicable diseases, health and safety risks, waste generation and sewage and increased pressure on resources, are all expected to increase.

6.4.2.2 Mobilization of more construction equipment and vehicles

- 235. No heavy vehicles shall be deployed regularly for the project construction. Transporation shall be done as and when required, because the quantity of materials required are limited to basic tower structure materials like steel lattice, insulators, conductors and accessories, the impact on the society is not forseen. Moreover, transportation of materials to work site shall be done through manual headloading, the impact become even lesser and benefits greater with employment opportunities.
- 236. Also, construction materials such as aggregates, cement and sand are only required for 61 tower foundations. The delivery of all materials can be completed by early part of the construction phase. Since no new road construction is required, there will be no disturbance to wildlife and the local communites residing along the National Highway and access roads for MHEP.

6.4.2.3 Potential damage to the highway due to heavy equipment and truck traffic

237. From an average of 100 vehicles a day on the Thimphu-Trashigang, the NHPP and the TL component is expected to add another 150 vehicles to the traffic load. This will increase traffic density from the current 8 vehicles per hour to about 20 vehicles/hour (at times), or one vehicle every 3 minutes, in the worst scenario. This may lead to some confusion about rights of way, and will certainly increase the risk of accidents and will delay the traffic flow, making local

journeys longer. The heavy equipment may also stress the load factor of the current highway (some equipment may be 16 tonnes). Currently, the existing highway between Trongsa towards Zhemgang is already damaged due to the heavy traffic from MHEP. There are sections of the highway where dust generation is a problem already.

238. The additional burden of vehicles is expected to excarbate the existing situation and further damage the highway. With no requirement for regular transportation, the extent of damage to highway solely due to the construction of the TL shall be marginal. However, the repair and maintenance of the Highway is under the scope of NHPP.

6.4.2.4 Noise, dust and access issues during vegetation clearing

239. Clearing of vegetation for the RoW is expected to generate noise, dust, and sometimes impeded access for workers or wildlife. The impact from this, however, is small as it is localized and limited to the area along the RoW. The impacts from vegetation clearing activities can also be reduced through mitigative measures.

6.4.2.5 Loss of visual aesthetics

240. Visual impacts are generally considered significant where they affect large numbers of people and tourists. The main negative impact on visual aesthetics in the project area will occur during construction, as a result of clearing, site work, and heavy equipment and vehicles on the road. Specifically to this TL, the visual impacts are not expected to be significant because the TL is aligned parallel along an already existing 66 kV transmission line from Trongsa to Yurmo. The forest itself provides a good natural screen to hide the TL from the highway.

6.4.2.6 Occupational health and safety

- 241. The main health and safety risks are associated with construction activities, and the risks are faced by workers. Clearance of the RoW is an activity in which there is a significant element of danger, particularly to workers, but also to inhabitants of villages. Workers also face other health risks and concerns in the camps (e.g., communicable diseases, poor air quality). The major issue shall be safety when working on foundation tower or felling of trees to clear the RoW both for workers as well as local community using the area and even during stringing. Working at height should have proper occupational and health safty (OHS) measures.
- 242. These impacts are not significant as long as they can be mitigated through proper OHS. If the Contractor is made to follow and OHS Plan, these impacts will be removed once the construction phase is completed.

6.4.3 Environmental Impacts

6.4.3.1 Loss of forest cover and habitat for wildlife

243. The biggest impact of the TL is the loss of forest cover and destruction of habitat for wildlife (see **Table 6.7**). For 132 kV transmission line only 6.1 m ground clearance is required from the lowest conductor. The shrubs over 3 m can be allowed to grow. With about 3.6 km shrub forest, the total amount of forest to be cleared is 100 acres or 0.4 km² (27x15 km) within

the project area. This amounts to 0.03% of the total forest land in the dzongkhag (total forest cover in Trongsa is 1,588 km².

Table 6.7: Area of land use along transmission line ROW

Facility	Wetland	Drylan d	Mixed Broadlea f forest	Conifero us forest	Scrublan d	Orchard s	Expos ed rock	Total
Transmissio n line length (km)		0	15 km	0	3.6	0	0	18.6 km
Actual corridor to be cleared			0.045 km ²		0.0972 km²			0.50 km ²

- 244. Despite the size of the forest area requiring clearance, the net impacts on forest cover is not considered significant for the following reasons:
 - (i) The proposed TL will be aligned parallel to the existing 66 kV transmission line from Trongsa to Yurmo so the actual area that will be cleared is less than 123 acres, especially where the TL runs through scrubforest and agricultural land.
 - (ii) Along this alignment, the RoW has already been cleared for the 66 kV line and forest cover along most of the alignment is sparse with low tree density and scanty shrub and scrub forest.
 - (iii) Where the TL spans gullies and valleys, it is not necessary to clear the 27 m RoW but rather clearing a smaller RoW of 4 m is practiced by BPC (to allow for operation and maintenance works).
 - (iv) The project site is not unique in terms of biodiversity or located in a protected area. The closest Park is the Jigme Singye Wangchuck National Park located over 50 km away.
- 245. As with other project areas where trees will be cut, the potential loss of bird and wildlife habitats can be countered by habitat enhancement in areas adjacent to the RoW, and replanting twice the size of the area cleared through Compensatory Afforestation where suitable local trees are planted in currently degraded areas.
- 246. The removal of trees and other vegetation along the RoW of the TL will also have ecological impacts as it will destroy forest habitat and displace species that are living in these areas. This could affect large and small mammals, birds, reptiles, amphibians, insects and other invertebrates. Some inhabitants will simply move away to other areas, but some could be damaged or killed during the clearing process. The biodiversity survey along the TL line indicates that a high level of disturbance already exists in the area, from grazing, lopping of trees, fodder leaf collection by local communities in the area.

- 247. At the same time, there is also a high diversity of birds in the area. Like many other hornbills (e.g., Rufous-necked) depend greatly on mature, large trees for feeding and nesting, as well as large expanses of forest. Little is known about the population trend of Yellow-rumped Honeyguide (*Indicator xanthonotus*), considered Near Threatened, but declines have been suspected to be occurring due to habitat loss, degradation and human exploitation of Giant Honey Bee (*Apis dorsata*) colonies with which it has very strong association. The Satyr Tragopan (*Tragopan satyra*) is considered the least threatened of all Tragopan species, but it is still classified as Near Threated because of hunting pressure over most of its range and habitat loss from logging (Birdlife International, 2014). Birds are good indicators of the health of forests.
- 248. While clearing of forest areas can have huge consequences on the species' abundance (wildlife, birds, insects) and these pressures may be further exacerbated by hunting/poaching by outsiders, the forest cover along the alignment is quite scanty and tree density is not very high (the highest tree density was 14 per 100m²). Thus, using this higher value of tree density, the total number of adult trees that will be felled along the 18.6km TL is 7,030 trees.
- 249. The net impacts of the Project on forest cover may be low but ecological impacts are more significant. Mitigation measures must compensate not only for loss of trees (and forest cover) but also include measures to collect more information and conduct research on the rarer and near threatened species so that specific conservation measures can be implemented.

6.4.3.2 Impacts on air quality

- 250. Normally with its high forest cover of 87%, low population density and little industry, the air quality of Trongsa is relatively good. Baseline data on Particulate matter (PM_{10}) in the Nikachhu project area was between 20.3 24.6 $\mu g/m^3$, only about one-third of the standard for Bhutan (75 $\mu g/m^3$) while SO_x and NO_x were not detected while analyzing (reflecting the low population density, absence of heavy industry, and low traffic levels).
- 251. One of the complaints of the households from the ongoing construction of MHEP was dust pollution. It is expected that air quality will be impacted due to cumulative impacts of additional machines and vehicles from NHPP. Other sources of air contaminants during construction of TL will be from the fugitive dust emission during benching of ground level at the tower foot.
- 252. The net impact of the Project on air quality is not significant and temporary, and will be limited to Construction Period.

6.4.3.3 Risk of poaching by workers

253. With increasing intrusion of workers in remote locations, the risk of poaching is quite real, especially since the project site is far from town (> 50 km), and meat is not readily available in the rural areas. Also, these areas are not frequented by Forestry Personnel so monitoring may not be quite as often. The risk of poaching by workers is high but temporary and preventable through appropriate mitigative measures.

6.4.3.4 Impacts from excavation works and muck disposal

- 254. About 12,810 m³ shall be generated from excavation works of 61 towers along the 18.6 km stretch. The volume of excavated material is at dispersed locations and is considered low. About 50% of the excavated material from the pits will be reused to fill the foundations of the tower footing to stabilize it. The concerns here include the slope stability and proper containment and stockpiling of excavated materials to prevent interference with drainage paths and to minimize the risk of sediment entry to local creeks and the river. The net impact of the excavation and muck generation is small and temporary due to the following:
 - (i) Not all tower sites are located on steep slopes or near streams, so excavation is not expected to cause large quantities of silt/soil to be washed into the river or streams during rain;
 - (ii) Tower sites are dispersed and spaced at least 300 m away from each other and will generate only 186 m³ of muck per site.
- 255. The excavation and muck generation is small, site specific and temporary in nature.

6.4.3.5 Risk of slope instability

- 256. The concern for slope stability only arises for excavation work carried out at localized tower sites. The design and planning of the TL requires detailed investigation of the geology (geotechnical hazards and soil of each tower footing site to ensure that there are no risks associated with stability of tower foundations.
- 257. The aim of the site reconnaissance survey was to identify potential site conditions at the support sites. The survey report indicates that there are no geological disturbances at all segments of the TL alignment. Marshy area has been noted at TL 9 for would require mitigation measures to ensure the stability of foundation.
- 258. The net impact from slope stability is small because this forms an important component of the design and planning process for each tower foundation site based on a good understanding of the known ground condition.

6.4.3.6 Impacts on community forest

259. Some parts of the TL route traverse Taktse and Samcholing Community Forest (CF), thus mitigation measures will be needed to ensure that no loss will be incurred to the community. To minimize impacts on community forestry, the project will consider the following: a) provide funds for compensatory plantation so that the locals can undertake this work themselves; and, b) provide incentives for improvement of the existing community and for forest management group. Incentives could include provision of equipment, water supply, fencing, nursery development or in-country tours to other community forests.

6.4.3.7 Impact on surface waters

- 260. The impact on surface water is directly linked to slope instability and therefore impacts on surface water will also be negligible if towers are located at a safe distance of at least 30 m away from surface water sources. Other impacts on surface water will arise from improper waste disposal and sewerage from the workers camps, improper sourcing of water, washing dishes and clothes or bathing along streams.
- 261. Like the risk of slope stability, the net impact on water quality will be small provided mitigation measures restricts the distance of towers and workers camps away from the rivers and streams, and prohibit and enforce measures to minimize pollution of surface water.

6.4.3.8 Impacts from improper storage of fuel

262. Since the material requirements for this project need to be supplied prior to construction period (to allow tower foundation, erection and stringing works to commence), there is no need for large quantities of fuel as material drop off is limited to this period alone. Thus, there are no risks of improper storage of fuel and spillage resulting in contamination of groundwater and surface water. Vehicles can get the required fuel from the local depot at Trongsa and no fuel is required for the construction work itself.

6.4.3.9 Impacts from improper closure of project work sites

263. To ensure that project components will not pose future threat to human health or to the environment, Contractor(s) will be required to ensure proper closure of pre-construction and construction project activities such as worker camps and storage sites along the TL.

6.5 Impacts during Operation Phase

6.5.1 Economic Impacts: Decrease in income opportunities

- 264. The routine maintenance of the RoW will not have economic impacts as it will not affect agricultural areas or farm roads used by locals for transporting produce. If a line failure requires the repositioning of towers, it should not be necessary to purchase land for the new foundations, as the new foundations maybe dug close to the old ones, involving the same land owners so exchange of land can be possible and the previously used area can be returned. At the local level though, once the major construction works are completed, and as Contractors and migrant workers leave, there will be a huge decrease in demand for agricultural products such as vegetables, dairy products etc.
- 265. At the national level, the evacuation of power from NHPP will have significant positive economic impacts in terms of increasing its income generation from the sale of power to India.

6.5.2 Social Impacts

6.5.2.1 Reduced pressure for local resources

266. During the operation phase, no negative social impacts are anticipated. Instead, the local district authorities will benefit positively due to reduced pressure on health, water,

resources such as LPG, kerosene, diesel and fuelwood, as well as reduced incidences of poaching, and anti-social activities.

6.5.2.2 Risk of electrocution and accidents during maintenance works

- 267. As the proposed transmission line carrying 132 kV runs over an area where people bring their cattles for grazing, the project has to pay special attention to the safety of people during maintenance works. Those working under the power lines are directly or indirectly exposed to potential safety risks.
- 268. During maintenance works, people should take precautionary measures to protect themselves keeping the maximum distance over 15-17 feet between themselves/objects in their hands or physical contact and the power line.
- 269. The main hazard to people from the operation and maintenance of the completed TL system is the risk of electrocution. Electrical injuries consist of four main types: electrocution (fatal), electric shock, burns, and falls caused as a result of contact with electrical energy. All workers are exposed during the performance of their duties such as repairing towers, transmission lines and its associated components. Locals can also be at risk especially as they are unaware of the risks and potential hazards which make them vulnerable to the danger of electrocution. Impacts during the operation and maintenance phase will be reduced through the implementation of BPCL's Operation and Maintenance Procedures wherein all Lines are shut down prior to conducting maintenance work. This risk is further reduced by adherence to the Occupational Health and Safety Guidelines issued by BPC for the O& M of all transmission lines in the country.

6.5.2.3 Electromagnetic Field (EMF)

270. There has been much research on the health and environmental impacts of EMF since the 1970s, but most research and laboratory studies have failed to show strong associations between exposure to EMF and health effects. A number of scientific panels convened by national and international health agencies and the U.S. Congress reviewed the research and concluded that there was insufficient evidence to prove the same. However, they also concluded that there is insufficient evidence to prove that EMF exposure is safe (Minnesota State Interagency Working group, 2002).

6.5.2.4 Risk and hazards associated with TL

271. The transmission line runs parallel to the existing 66 kV line that has been in operation for over 7 years. Till date there have been no recorded incidents of any landslides or earthquakes damaging the existing 66 kV line. The impacts from disaster and hazards to the transmission line cannot be predicted, thus, all the associated structures will be designed and constructed to withstand the impacts of catastrophes.

6.5.3 Environmental Impacts

272. Operations and maintenance of the RoW will not incur major ecological impacts as there will no new towers to be erected. Maintenance works will be very small in scale and infrequent, and involves few changes to the existing situation. The practice of allowing some re-growth of vegetation along the RoW will also have ecological benefits as it will allow plants and animals to re-colonise. Because the forest canopy is now open in these areas the species will be different from those that were originally present, which may be seen as a further gain as this will increase the diversity of habitats.

6.5.4 Electrocution of raptors and other large birds

273. The risk of electrocution of large birds by transmission line is real as they provide a structure for birds from which they can hunt and roost. This is more so in places where there are few natural perches for the birds to use. Electrocution occurs when a bird comes in contact with two wires or when it perches on a conductive pylon and comes into simultaneous contact with a wire. Collisions may also occur if the transmission lines are difficult to see. While there has been no documented evidence in Bhutan that existing transmission lines have caused electrocution of large birds, this risk needs to be considered. The impact of electrocution of birds depends on the electrotechnical design of a pylon and the natural features surrounding it. The net impact of electrocution of large birds is not considered significant because (a) there has been no documented evidence of large bird kills from the existing 66 kv TL line in the same project area; (b) the existing design incorporates construction of cage boxes for conductors to prevent birds from sitting or making nests; and (c) other mitigative measures are proposed to lessen any unforeseen or impacts

7 Environmental Mitigation and Management Plan

274. This chapter discusses the mitigation and management plan for the impacts associated with the transmission line and the required management plans. Specific details associated with each proposed mitigation measure, including the institutional and financial requirements to ensure proper implementation, accountability and monitoring is also detailed out. The identification of impacts covers both the immediate project area as well as adjoining areas within 5 km in the immediate vicinity of the Project.

7.1 Management plan for loss of private land and livelihood

- 275. Since all designated forest is owned by the state there is no need to purchase land for the TL where it runs through the forest. The project will not affect any infrastructure or private homes but 6 towers will have to be built on private land. The displaced households that will lose 10 decimal of land each to accommodate 1 transmission tower are from Drakten gewog (4 households) and Langthel gewog (2 households). Thus, the total project land requirement is only 0.6 acres all of which falls in Dryland (Kamzhing) (see **Table 6.2**).
- 276. Land compensation is guided by the "Land Compensation Rates (2009)" and the Land Act of Bhutan (2007). The compensation rates also apply for compensating structures and fruit trees. There are three classes of land under the rural category, based on distance from the municipal boundary. As the Project falls within Class C of rural land, the compensation rate per decimal (= 40.47 m²) is Nu 2,262.54, which means one acre will cost Nu 226,254. Chapter 7 of the Land Act 2007, specifically pertains to land that will be acquired by the Government for wider public interest. It states:
 - (i) acquisition shall entail fair compensation;
 - (ii) The compensation can be in cash or land or a combination of both (the land owner shall have the discretion to opt for one or the other);
 - (iii) All the compensation process should be completed before the actual start of the project on the ground;
 - (iv) If land is provided as compensation, the certificate for new land shall be made available so that the affected people do not encounter any problems in the future. The project shall ensure that no tower construction will take place until the compensation process is completed and the affected are fully compensated.
- 277. If affected households are not satisfied with the proposed compensation, thier grievances shall be redressed through so called the "Grievance Redressal Mechanism" to the Grievance Redressal Committee constituted under Tangsibji Hydro Energy (THyE) for NHPP.
- 278. Due to the type of land being acquired as well as the extent of land acquisition, no significant impacts on the income of the displaced households is anticipated as a result of the acquisition. There may be minor impacts on incomes arising from land acquisition because the

6 households losing land to the transmission line towers will face some restrictions on their land use owing to the transmission tower footing on their land and the overhead transmission line that will pass through their land. Due to this they will not be able to make optimal use of their land. To compensate them for the restriction of land use, an entitlement of 20 percent of the total cost of the impacted land will be paid (at PAVA's rates) as compensation for causing restricted land use. The total compensation to be paid under this entitlement amounts to Nu. 27,150.48. The 6 displaced households will receive Nu. 4,525.08 each as an additional 20 percent of the cost of their displaced land. These 6 households will lose 10 decimals of land each to the 6 transmission line towers footing.

- 279. Land that shall be used temporarily for storage of materials, construction of labour camps only totals 3.6 acres. These, the labour camp particularly, shall be located on GRF land at five different places. The stores shall be located near the highway. Private land shall be taken up for storage of materials on lease depending on the interest of the people.
- 280. In the case of temporary land leased for the project (18 months at most), the project requires that on completion of all construction work, all temporary land utilized will be rehabilitated, re-vegetated and in turn become possibly more useful land for local communities.
 - Revenue sharing arrangements wherein a) 12 15 percent of royalty revenue generated from the export of power from NHPP will be used to provide free electricity (of 100 units per month) to rural households by the RGoB; b) the RGoB will provide free electricity of 10,000 kWh per annum for every acre of land (or prorated thereof) acquired for the project from the Royalty Energy after the project comes into commercial operation till the end of the initial Concession Agreement (CA). The land owner may either avail free electricity or cash in lieu thereof at the export rates from the project. This benefit will continue beyond the concession period.

7.2 Employment opportunities

- 281. The project will be able to provide job opportunities to the local people. Since, the construction of TL shall not construct access roads, transportation of construction materials from the nearest road point shall be done through manual headloading. This shall require several workers and the preference shall be given to those affected by the project. Further, the affected people shall also be provided employment in construction work depending on their skills and qualification. Job opportunities include working for Contractors, for clearing the RoW, transportation of materials, involvement in compensatory forestation programs and land management work initiated by the project.
- 282. The project will also bring in new opportunities to sell locally grown vegetables, milk products and meat. Renting of living quarters and office space to project contractors and their employees, leasing of vehicles and equipment to the project contractors, or leasing of private land to project contractors are some other ways for locals to earn increased incomes.

7.3 Management of impacts from mobilization of equipment, construction materials and their storage

283. Construction materials include aggregate, sand, cement and steel lattice structures for tower. These materials requirement are not huge for only 61 towers. Therefore, the materials shall be transported through trucks hired as and when required. No heavy vehicles or machines shall be deployed regularly for the construction of the TL. These materials shall be stored near the nearest road point and shall be headloaded at the actual site during the construction, at least 15 days ahead of the activity. The material shifting will be in accordance to the progress of the activity to avoid congetion of space at the site. Since, there is no requirement of huge number of vehicles and machines, the impact on the existing highways is not significant. Moreover, repair and maintenance of the National-Highway shall be undertaken as a part of overall Nikachhu Hydropower Project.

7.4 Management of Social Impacts

284. The project may cause a conglomeration of internal and external labour in the project sites. Workers may come from either the same locality or from other areas. There would be workercamps established. The impacts from these would increase opportunities for employment for the local people which is a positive move but on the negative side the accumulation of waste both liquid and solid, intrusion to the village life etc. should be managed. Waste disposal should be properly organized so that there would not be any littering and pollution of nearby water bodies. All the construction sites, stores of materials, temporary and permanent building, utensils used for cooking etc. should be carefully maintained. All the disposals should be properly supervised.

7.5 Management of workers/worker camps

285. The impacts due to influx of workers will begin from the pre-construction phase and will continue at an expanded scale in the construction phase. This means more workers at each work location, and more frequent movement of construction materials and equipment. Proper planning and experience in the pre-construction phase will set the stage for effective planning and mitigation measures in the construction phase. The main concerns with an influx of workers include:

- (i) Risk of communicable diseases spreading in the local community;
- (ii) Waste and sewage entering the local environment;
- (iii) Safety issues at the work sites.
- (iv) Possible social instability:
- (v) Health concerns in the camps (communicable diseases, poor air quality).

a) Risk of communicable diseases spreading in the local community

- 286. To avoid or at least to minimize the spread of communicable diseases to the local community, the following management measures shall be taken up:
 - (i) Screening and regular unannounced checking of workers. As per the procedure for hiring foreign workers, all contractors and labour agencies are required to make all prospective workers undergo medical tests to screen for diseases and sicknesses, prior to selection and employment of any foreign worker. The contractor is also responsible for ensuring that no foreign worker who has a criminal record is employed at the project site. It will be ensured that all workers undergo medical tests to screen diseases at source and at sites in consultation with the Trongsa hospital Dzongkhag Health Officer.
 - (ii) Checking of workers. In addition to this, the Project Management will also undertake sudden, unannounced checks on workers to look for diseases such as HIV, STDs, and hepatitis. This is being suggested because surprise checks in projects like Mangdechhu have resulted in workers being detected as positive for HIV and STD. If such cases are detected, the contractor will be required to immediately release the worker from the site (as this indicates that proper screening was not conducted).

b) Increased pressure on housing, infrastructure, and services

1. Ensure Minimal Land clearing and Removal of Vegetation for housing

287. The project will ensure that wherever possible no land conversion will be required for additional housing. This can be done through worker camp selection in already degraded/semi cleared forests in discussion with the Dzongkhag authorities.

2. Housing and sanitation for workers

- 288. The main mitigation approach is proper siting and design of the temporary worker camps, and to get these built quickly (accommodating at least 50 workers at a site). The relative isolation of the worker camps (quite far away from local communities) will help to minimize an overloading of worker-local community interactions, which should help reduce social and cultural conflicts, as well as the risk of spread of communicable diseases.
- 289. Prior to beginning the construction works, the general layout of the labour camps at each construction site should be designed to plan for location of important structures like:
 - (i) drinking water storage tanks or taps
 - (ii) communal kitchens
 - (iii) Pit latrines and soak-aways (as far away from watercourses as possible),
 - (iv) proper site drainage
 - (v) a solid waste storage area (for onward transfer to the local landfill).
- 290. The use of communal kitchen and communal toilets will help to reduce both the demand for fuel, water and minimize pollution and allow centralized waste and wastewater management.

3. Provision of Drinking water

- 291. It is estimated that about 230 workers will be deployed at various locations along the Transmission line during the peak pre construction and construction period. According to the World Health Organization (WHO), 50 to 100 liters of water per person per day are needed to ensure that most basic needs are met and few health concerns arise. Assuming usage of 50 litres of water per day for each worker (as communal kitchens and pit latrines are expected to be used), the total water requirement during peak construction period is 12,500 liters per day (see **Table 6.6**).
- 292. While the water in the labour camps shall be required throughout the peak construction, for construction work water shall be used only for concreting. About 300 litres/day of water shall be used in concrete works. However, concreting shall be done only for laying foundation for the tower.
- 293. About 50 liters of water will also be required for sprinking on to the area of excavation to suppress dust However; this shall be required only during the excavation at tower foot. All water requirements will need to be met from nearby streams, which have been identified in the EMP.

Mitigation Measure

294. Drinking water will be sourced and provided for each worker camp as shown in **Table 7.1**.

Table 7.1: Streams near the Project site and their availability

No.	Stream	Min. Discharge (cumec)	Min. Discharge (litre/sec)	Min. Discharge (litre/day)	Requirement	Percentage to be drawn
1	Dzongkha Lumpa	1	1,000	86,400,000	3,000	0.003%
2	Sesaychen Chu Stream between Dzongkhag Lumpa and DOR camp at Trasidingkha- Sesechen stream	0.011	11	950,400	2,300	0.242%
3	Yusagang Chu	1	1,000	86,400,000	2,300	0.003%
4	Nikhachu Stream	0.025	25	2,160,000	2,300	0.106%
5	Migthichu Stream	3	3,000	259,200,000	2,300	0.001%

295. The amount of water available in the project area is sufficient to meet the requirement of the project. Although, it is been estimated as above, the actual quantity of use shall be even lesser due to use of communal kitchen and pit latrines. All labour camps shall be located near the streams and water extracted through PVC water pipes. The labourers shall be distributed

into 5 gangs at different locations of towers and shall be provided each with a camp, a communal kitchen and two pit latrines.

Method of Water Extraction

296. The water shall be extracted through Gravity-Fed System. The system works on gravity which allows the water stored in the tank to move down by its own weight inside the pipes and run out from the taps. The water from the nearest stream shall be tapped into the Header Tank/the collection which shall then be passed into a Rapid sand filter and then into storage tank. The main distribution pipe shall be connected to the storage tank through which water shall be distributed into the secondary distribution pipes into labour camps, kitchen and common tap.

4. Waste and sewage entering the local environment

- 297. The source of the waste will be from the temporary colonies of labour, and construction sites. Waste includes PET bottles, papers, plastics, glass, organics, metal, batteries etc. Improper segregation and dumping of waste will result in negatively impacting the visual aesthetics, pollute nearby streams as well as invite vectors to transmit diseases.
- 298. As per the Waste Prevention and Management Act 2009, all implementing agencies must ensure that the reduction, reuse, recycling and disposal of non-hazardous waste are addressed in an environmentally sound manner.
- 299. The project will implement the following waste management:
 - (i) **Waste Reduction** through promoting the use of electricity instead of firewood wherever possible.
 - (ii) **Waste Reuse** by promoting the reuse of large plastic containers, jars and bags wherever possible in worker campsites.
 - (iii) **Waste Recycling** especially organic waste which can be recycled to make compost at a suitable location. Otherwise the organic waste cans also be given to the nearest household to be fed to cattle and pigs.
 - (iv) Waste segregation for recycling Each site (including offices, colonies and worker camps) will be provided with 2 separate bins for degradable and non-biodegradable waste. Only Waste that cannot be reused or recycled will be disposed. This residual solid waste will have to go to a designated landfill site, away from settlements and water sources. The current landfill for Trongsa area is filling up and plans for creating a new landfill in either Langthel or Drakten is underway by the Dzongkhag. A waste collection protocol will be established for each site so that waste does not pile up and cause problems to the environment or workers. The waste from the labour camps and construction sites shall be brought to the nearest road side from where it shall be collected by the Compactor truck of MHEP which collect wastes from the entire gewog. Since, the labour camps shall be located away from the highway; the waste generation shall be less mainly the packaged foods and PET bottles. The solid waste shall be gererated only from the covers of basic grocery items and kitchen waste.

- (a) Site drainage and sewage. At each campsite, the pit latrines and sewage shall be located at least 30 m from watercourses. The sewage treatment on-site, and proper management of worker camps should minimize the risk of contamination of surface.. Washing of clothes and dishes directly in streams shall be prohibited to prevent pollution in case there are downstream users. At each worker camp two pit latrines shall be provided as required by the Regulation on Occupational Health Safety and Welfare prescribed by Ministry of Labour and Human Settlement.
- (b) Awareness. The biggest cause of improper waste management is due to lack of awareness on waste and waste management. The Project will conduct awareness meetings and campaigns through posters or talks to make workers aware of the 4R's: Reduce, Reuse and Recycle and Responsibility.
- (c) **Site inspections**. Monitoring of waste management at all sites will include visual inspections of the camps and work sites. This will be conducted by the Environmental officers of BPCL.

(v) Safety issues at the work sites

- 300. Occupational Health and Safety covers all personnel working under the project and will be in line with the General Rules and Regulations on Occupational Health and Safety (OHS) in Construction, Manufacturing and Mining and Service Industries, 2006 (RGOB). Chapter IX of the Labor and Employment Act of Bhutan (2007) clarifies details on the Occupational Health and Safety of workers, which are mandatory in the Construction Industry.
- 301. The Occupational Health and Safety program will aim to ensure that the workplace is safe and healthy by: addressing the hazards and risks at the workplace; outlining the procedures and responsibilities for preventing, eliminating and minimizing the effects of those hazards and risks; identifying the emergency management plans for the workplace or workplaces; and, specifying how consultation, training and information are to be provided to employees at various workplaces.

a) Nomination of a Health and Safety Focal Person

302. Within each site the Contractor must nominate a Health and Safety Focal Person who will Function as the focal person/representative for all health and safety matters at the workplace, be responsible for maintaining records of all accidents and all health and safety issues at each site, the number of accidents and its cause, actions taken and remedial measures undertaken in case of safety issues. He will be the link between the contractor and all workers and submit grievances of the workers to the contractor and instructions/directives on proper health care and safety from the contractors back to the workers. He will also ensure that

all workers are adequately informed on the requirement to use Personal Protective Equipment and its correct use.

b) Minimizing hazards and risks at the workplace.

303. To ensure safety at all work sites, the following will be carried out:

- (i) Installation of signboards and symbols in risky and hazardous areas, to inform workers to be careful:
- (ii) Ensuring that materials are all stacked, racked, blocked, interlocked, or otherwise secured to prevent sliding, falling, or collapse;
- (iii) Removing all scrap and waste material from the immediate work area as the work progresses. All excavated earth must be stockpiled at least 2 feet from the pit to avoid material such as loose rocks from falling back into the excavated area and injuring those working inside excavated sites;
- (iv) Where scaffolds are required, ensuring that each scaffold or its components shall be capable of supporting its own weight and at least 4 times the maximum intended load applied or transmitted to it. The platform/scaffold plank shall be at least 15 inches (46cm) wide and 1.5 inches thick. The rope should be capable of supporting at least 6 times the maximum intended load applied or transmitted to that rope. Pole scaffolds over 60 feet (5.6m) in height shall be designed by a registered professional engineer and shall be constructed and loaded in accordance with that design;
- (v) Use only trained staff to construct, install and repair all electrical equipment to prevent risks of electrical shocks and electrocution:
- (vi) Install fire extinguishers and/or other fire-fighting equipment at every work site to prepare for any accidental fire hazards.

c) Provision of Personal Protective Equipment

304. Risks to the health and safety of workers can be prevented by provision of Personal Protective Equipment (PPEs) to all workers (see **Table 7.2**). Personal protective equipment like safety gloves, helmet, mufflers etc. will be provided during the construction period and during the maintenance work. This will be included in the construction cost for each Contractor. Depending on the nature of work and the risks involved, contractors must provide without any cost to the workers, the following protective equipment:

- (i) Helmet shall be provided to all workers, or visitors visiting the site, for protection of the head against impact or penetration of falling or flying objects.
- (ii) Safety belt shall be provided to workers working at heights (more than 20 ft) such as stringing and conductor installation;

- (iii) Safety boots shall be provided to all workers for protection of feet from impact or penetration of falling objects on feet;
- (iv) Ear protecting devices shall be provided to all workers and will be used during the occurrence of extensive noise.
- (v) Eye and face protection equipment shall be provided to all welders to protect against sparks;
- (vi) Respiratory protection devices shall be provided to all workers during occurrence of fumes, dusts, or toxic gas/vapor;
- (vii)Safety nets shall be provided when workplaces are more than 25 feet (7.5 m) above the ground or other surfaces where the use of ladders, scaffolds, catch platforms, temporary floors or safety belts is impractical;
- (viii) First aid facilities will be made available with the labor gangs and doctors called in from nearby towns when necessary.
- (ix) The safety and emergency procedures manual will be kept. Necessary training regarding the safety aspects of the personnel working at the project site will be provided.

Table 7.2: Specific PPE requirements for each type of work

Type of Work	PPE		
Elevated work	Safety helmet, safety belt (height greater than 20 ft), footwear for elevated work.		
Handling work safety	Helmet, leather safety shoes, work gloves.		
Welding and cutting work	Eye protectors, shield and helmet, protective gloves.		
Grinding work	Dust respirator, earplugs, eye protectors.		
Work involving handling of chemical substances	Dust respirator, gas mask, chemical-proof gloves. Chemical-proof clothing, air-lined mask, eye protectors.		
Wood working	Hard hat, eye protectors, hearing protection, safety footwear, leather gloves and dust respirator.		
Blasting	Hard hat, eye and hearing protection.		
Concrete and masonry work	Hard hat, eye protectors, hearing protection, safety footwear, leather gloves and dust respirator.		
Excavation, heavy equipment, motor graders, and bulldozer operation			
Quarries	Hard hat, eye protectors, hearing protection, safety footwear, leather gloves and dust respirator.		

d) Record maintenance and remedial action

305. The Project Management will maintain a record of all accidents and injuries that occur at the work site. This work will be delegated by the contractor to the site supervisor and regularly reviewed every quarter by project management. Reports prepared by the contractor shall include information on the place, date and time of the incident, name of persons involved, cause of incident, witnesses present and their statements. Based on such reports, the management can jointly identify any unsafe conditions, acts or procedures and recommend for the contractor to undertake certain mitigative actions to change any unsafe or harmful conditions.

e) Compensation for Injuries and Death

306. Any casualty or injury resulting from occupational activities should be compensated as per the Labor and Employment Act of Bhutan (2007). Where compensation is sought by the injured party, proper procedures for documentation of the case will be followed, including a detailed report on the accident, written reports from witnesses, report of the examining doctor and his/her recommendation for treatment. Each individual contractor will be responsible for ensuring compensation for the respective workers.

(vi) Possible social instability

- 307. Another concern with an influx of workers includes possible social instability (poor mingling of workers from outside the district, or from outside Bhutan, with local communities, although Bhutanese have increasing experience with worker influxes and seem to handle them with equanimity). There is also the risk of spreading communicable diseases to host communities.
- 308. Although the number of foreign workers for the TL shall not be huge, the following management measures shall be taken up to eliminate or at least to minimize the impacts of worker influx to social instability:

a) Awareness of the Code of Conduct for workers

- 309. The Project management will undertake awareness programs through posters, talks, and meetings with the contractors to clarify the rights and responsibilities of the workers regarding interactions with local people (including communicable disease risks, such as HIV/AIDS), work site health and safety, and to make workers aware of procedures to be followed in case of emergencies such as informing the focal health person who in turn will arrange the necessary emergency transportation or treatment.
- 310. The Contractor will be required to instruct the site supervisor on the code of conduct and ethics for foreign workers. As per the Regulations on working conditions of the Department of Labour, 2012, all foreign workers are required to respect the values, traditions, culture and law of the country and respect all regulations and rules. No worker will be allowed to enter areas restricted for foreigners without specific permits.

7. Management of health concerns in the camps

- 311. All workers living in temporary camps will also face health concerns in the camps such as risk of communicable diseases and poor air quality. The provision of communal kitchens will ensure that workers do not have to be exposed to emissions from individual kitchen. To address health concerns of workers, the Contractor must institutionalize procedures to deal with emergencies such as sudden illness or accidents.
- 312. First aid kits must be made available at all times throughout the entire construction period. This is very important, because all work sites are quite far from the nearest Basic Health Unit. In addition to the first aid kits, the following measures should be in place:
 - (i) Provisions of a vehicle on standby from the Project Office/Contractor, or provisions to hire vehicles during emergencies to take the severely injured/sick workers to the nearest BHU or Trongsa Hospital for immediate medical attention;
 - (ii) Communication arrangements, such a provision of radios or mobile communication for all work sites, for efficient handling of emergencies, will be made;
 - (iii) The designated focal health persons' contact number will be posted at the work site for speedy delivery of emergency services. The focal person should know what medical facilities area available at the Trongsa Hospital and the BHU.

7.6 Management of impacts on cultural and religious sites

- 313. It is expected that there will be no impact on Cultural and Religious sites because during design stage extra care was taken to ensure that religious structures/ public property were avoided. However for extra precaution, efforts should still be made to reduce the level of disruption where possible. To achieve this, the BPC shall:
- Determine the location of all sites that are of local social or cultural importance (temples, shrines, meeting places, etc) and ensure that no towers are located in the vicinity, and no conductors are strung overhead. This has been done during the survey stage;
- ii) Consult all affected communities in advance to inform them of the purpose, nature, duration, extent and timing of all work in and around their village, and explain to them the purpose of the Project and its activities along with the workplan and schedule of activities;
- iii) Consult the custodians of all social and cultural facilities (monasteries, nunneries) on the proposed alignment and plan the work to avoid sensitive times (such as key dates in the religious calendar, festivals etc);
- iv) No towers shall be located near the cultural heritage sites and no transmission line shall be stringed above the structures.

7.7 Air Quality Management

- 314. The following measures shall be taken up to mitigate the impacts on air quality during construction phase:
 - (i) The fugitive dust generation at each excavation sites shall be suppressed by sprinkling water periodically.
 - (ii) Those trucks carrying construction materials shall be covered while transporting. This shall help prevent the dust particles being blown away by the wind;
 - (iii) Risks to the health and safety of workers can be prevented by provision of PPEs to all workers;
 - (iv) Leave a covering of grass and/or other naturally occurring low-growing vegetation where possible along the RoW to reduce dust;
 - (v) Avoid burning waste vegetation and instead leave this material *in situ* after cutting, to rot down gradually, and discourage re-growth whilst it is decomposing;
 - (vi) An Ambient Air Monitoring Program to monitor Air quality and noise levels will be implemented as part of the overall EMP by the BPC. The purpose of the monitoring program will be to observe air pollution levels and detect sources of air pollution so that remedial measures can be undertaken. The data collected will be compiled every month and, accordingly, if the air quality and noise levels exceed acceptable standards, this could potentially have health impacts, and require remedial planning and management.
 - Parameters that will be measured include: total suspended particulate matter, PM₁₀, SO_x, NO_x, CO, and noise levels.

7.8 Management of Noise generation

- 315. To minimize disturbance to the community and the potential increase in ambient noise levels, the Contractor shall be mandated to meet the noise level standard prescribed by National Environment Commission. The impact of noise level on the community shall not be adverse in the case of Transmission Line construction as the project site is located way away from the villages and settlements. Moreover, the forest belt itself shall serve as a buffer and attenuate the noise level.
- 316. The only towers located near the Highway are the TL 28 to TL 31. However, at these locations with the vegetation being shrubs, ROW clearing shall not be required and thereby the noise generation is not envisaged.
- 317. The workers shall be mandated to wear PPE including ear muff during work at site to prevent occupational diseases. Further, the standard noise exposure limt, prescribed by Ministry of Labour and Human Resource (MoLHR), shall be strictly adhered to. The standard permissible limit, with PPE, is given in **Table 7.3**.

Table 7.3: Maximum exposure periods specified by MoLHR

Hour/Day	Sound Level (dB)
8	90
6	92
4	95
3	100
2	102
1.5	105
1	110
0.5	115
0.25	120
No exposure permitted at or above this level	>140

7.9 Management of Aesthetics

- 318. Visual impacts are generally considered significant where they affect large numbers of people and tourists. The main negative impact on visual aesthetics in the project area will occur during construction, as a result of clearing and site preparation works. This will stop when the project construction is completed. The visual impacts here will not be significant because the TL will be aligned parallel to the already existing 66 kV TL. Also, at some locations, the forest itself will provide a good natural screen to hide the TL from the highway.
- 319. During construction, dumping of excavated material down the hill may impact the asthetics of the area. Therefore, management of muck shall be carried out appropriately as explained under Muck Panagement Plan..

7.10 Occupational Health and Safety

320. The Occupational Health and Safety program will aim to ensure that the workplace is safe and healthy by: addressing the hazards and risks at the workplace; outlining the procedures and responsibilities for preventing, eliminating and minimizing the effects of those hazards and risks; identifying the emergency management plans for the workplace or workplaces; and, specifying how consultation, training and information are to be provided to employees at various workplaces. The mitigation measures detailed earlier will be followed to minimize hazards and risks at the workplace and ensure the health and safety of workers. The contractor shall be manadated to abide by the Occupational Health and Safety Rules, Regulation on Occupational Health Safety and Welfare, 2012 and Occupational Health and Safety for Construction Industry, prescribed by Ministry of Labour and Human Resource. This requirement shall be incorporated in the Tender Document inorder to assure safe working environment.

321. The contractor shall:

(i) Ensure health and safety of all employees and any person at the workplace;

- (ii) Improve working conditionthat are hazardous to health and safety;
- (iii) Provide and maintain PPE in good condition and ensure they are used by the employees;
- (iv) Provide to the employee the information, instruction and supervision.
- 322. The First Aid Box shall be available at each work place under the charge of one trained First Aider. As per the regulation on Occupational Health Saftey and Welfare, 2012, there shall be one First Aider for every 50 employees.

7.11 Forest Conservation

323. Inorder the minimize the adverse impacts of clearing the forest cover, Contractors shall be made aware of the exact delineation of the RoW and only those trees marked per directives/delineation of Forestry staff within the RoW shall be cleared. Moreover, the actual ground clearance required for 132kV TL is 6.1 m from the lowest conductor. Therefore, all those trees which do not exceed the clearance shall be left undisturbed.

Compensatory Afforestation

- 324. The loss of trees will be addressed according to the current guidelines in Bhutan, with compensatory planting of trees in an area that is twice the size of the area cleared, allowing for up to 40% damage or mortality. Therefore, the total area that must be afforested is approximately 200 acres, although the actual deforestation may be far lesser.
- 325. To undertake Compensatory Afforestation the project shall develop a mutually agreeable proposal or a Memorandum of Understanding (MoU) between the DoFPS and the BPC, covering project activities for financing and execution. The Territorial Divisions, Dzongkhag Forestry Sector and the BPC shall be responsible for planning and implementation of afforestation activities, based on the MOU. The Social Forestry and Extension Division will be the focal agency for all the technical matters, including need-based monitoring and evaluation from the headquarters and reporting of these to the BPC.
- 326. The project will focus on deforested areas in and around the project site, but it will not be restricted to project areas if enough sites are not available; it will extend to other degraded areas, landslide prone areas, or areas where the muck excavated is disposed and terraced (especially in remote areas where it is not economically feasible to transport muck away from the tower foundation sites).
- 327. Within the Warm broadleaf forest, the dominant trees are Oaks, especially *Quercus griffithii*, *Quercus Lamellosa* and *Quercus Lanata*. Other species include *Alnus nepalensis*, *Docynia indica*, *Juglans regia*, *Lyonia ovalifolia*, *Exbucklandia populnea*, *Daphne phyllum*, *Symplocus ramossima*, *Maesa chisea* and *Daphne bholua*. The middle shrub layer comprises mostly of younger tree species of Quercus, Rhododendrons, Symplocus and other species like

Ardisia macrocarpa, Berberis aristata, Brassaiopsis mitis, Dichroa fibrifuga, Toricella tiliifolia, Dapne bholua, Leucosceptrum, Viburnum cylindricum, Cinnamomum bejolghota, Samraria nepalensis and Arundinaria. The ground species include mostly common species like Artemesia vulgaris, Eupatorium adenophorum, Inula cappa, Rubus ellipticus and Urtica parviflora. There are also climbers like Hedera nepalensis, Agapetes serpens, Orchids, and ferns like Pteridium aqulinium, Diplazium esculentum, Drynaria and Pteris wallichiana. Grass species include Poa annua, Anthraxon, Borinda, Cynodon dactylon and Cyperus cyperoides.

- 328. Moving further onwards towards TL14, the vegetation is not as dense at it passes close to the Mangdechu Dam colony area and the Taktse CommunityForest. Here the oaks are not as dominant but other tree species such as Castanopsis hystrix, Daphnephyllum, Ex-buklandia populnea, Symplocus ramosissima, Symplocus glomerta, Lyonia ovalifolia, Maesa chisia, Rhododendron arboretum, Toricellia tiliifolia, Prunus cerasoides, Alnus nepalensis and Viburnum are found. The middle lower trees and shrubs comprise of Viburnum cylindricum, Eurya acuminata, Dichroa fibrifuga, Daphne bholua and Berberis aristata. The ground vegetation is dominated largely by Eupatorium adenophorum, Anaphalis triplinervis, Ancelia aptera, Cirsium falconeri and ferns like Pteridium aquilinium, Diplazium esculentum, Pteris walliciana and other species like Smilax, Solanum virginianum and Swertia chirata. Orchids like Cymbidium, Otochilus lanciliabius, Dendrobium candidium, and Coelogyne are also found.
- 329. Continuing onwards towards TL25, other trees species such as *Michelia doltsopa*, *Prunus cerasoides*, *Persea bootanica*, *Rhus wallichii*, and Oaks (*Quercus griffithii*, *Quercus glauca*, *Quercus semicarpifolia*, *Quercus lanata*) are observed again with *Sympolocus*, *Lyonia ovalifolia*, *Exbucklandia populnea*, *Maesa chisia* and Rhododendrons. The middles storey is almost the same as before but also including species like *Nellia rubiflora*, *Lindera pulcherra*, *Viburnum cylindricum*, *Edgeworthia gardneri*, *Ilex aquilinium*, and *Cotoneaster microphyllus*. Additional ground species observed include *Tupistra chinensis*, *Solanum khasianum*, *Smilax ovalifolia*, *Raphidophora*, *Hemiphragma heterophyllum*, *Inula cappa*, *Pilea umbrosa*, *Potentilla fruticosa*, *Lycopodium clavatum*, *Glienchenia gigantean*, *Vanda cristata* and *Oleandra pistillaris* and *Otochilus* species.
- 330. Moving towards TL42 as the forest is mostly scrub forest with fewer trees and scantier understory and barren land. Tree species are mostly *Quercus lanata*, *Quercus semicarpifolia*, *Quercus griffithii*, *Alnus nepalensis*, *Rhus wallichii*, *Maesa chisia*, *Lyonia ovalifolia*, *Castanopsis hystrix*, *Docynia indica*, *Symplocus ramosissima*, *Exbucklandia populnea*, *Rhododendron* and *Schima wallichii*. The scanty shrub layer comprises mostly of *Artemesia vulgaris*, *Eupatori adenophorum*, *Rubus ellipticus*, *Berberis aristata*, *Maesa chisia*, *Leucoceptrum species*, *Zanthoxylum* and *Indigofera dosua*. Even the ground vegetation is scanty comprising mainly of *Pteridium aquilinium*, *Eupatorium adenophorum*, *Osbeckia stellate*, *small Rhododendrons*, *Anaphalis triplinervis*, *Artemesia vulgaris*, *Rubus ellipticus* and some grass species like *Poa annua* and *Arthraxon* species.
- 331. From TL40, the TL the main trees species are Castanopsis hystrix, Lyonia ovalifolia, Quercus lanata, Symplocus ramosissima, Pinus roxburghii and Schima wallichii, Duabanga

grandiflora, Alnus nepalensis, Bischofia javanica, Rhus chinensis, Pinus roxburghii, Ficus roxburghii, Ficus semicordata, and Quercus lanata in Langthel and Yurmo

- 332. Shrubs include Berberis aristata, Ardisia macrocarpa, Edgeworthia gardneri, Dichroa fibrifuga, Viburnum erubescens, Mahonia nepalensis, Brassaiopsis mitis, Daphne bholua, Viburnum cylindricum, Maesa chisia, Eurya acuminatum, Rhododendron arboreum, Symplocos glomerata, Viburnum cylindricum, Ilex species, Cotoneaster microphylla, Elaeagnus parvifolia, Rubus ellipticus, Eupatorium adenophorum, Zanthoxylum species,. Vaccinium myrtillus, Rhododendron vaccinoides, Indigofera dosua, Aconogonum molle, Datura suaveolens, Adhatoda vasica and Arundinaria species
- 333. From the above listed species, selection of species for plantation shall be decided by the Social Forestry Division and Local Forestry Office based on the climatic and edaphic conditions of the selected site, ensuring composition of different species (trees and shrub) for successful growth.

Methodology for plantation

- 334. The compensatory afforestation shall be carried out as an integrated afforestation program which would include soil conservation, fencing, protection, awareness, monitoring and evaluation along with maintenance for at least five years period. A properly planted tree or shrub is more tolerant to adverse condition and requires much less management than the one planted incorrectly. Successful tree growth involves proper planning, proper site preparation, selection of plant species, plantation methodology and plantation maintenance.
- 335. The best time for plantation would be early spring or autumn during which weather conditions are cool and allow plants to establish roots in the new location.
- 336. During the monsoon, the sapling shall be exposed to stress from hot weather and extreme rain soon after their plantation when the saplings are in their juvenile stage and during winter extreme cold will stress the seedling. Hand planting shall be adopted for planting saplings. Holes will be dug large enough (not to shallow and not to deep) with the shovel or hoes, for accommodation of root system, will be backfilled by the soil and compost, if required, and watered.
- 337. The saplings shall be planted as soon as possible after receiving from nursery to avoid reduced survival rate. Should the plantation be done later, the stocks shall be stored in cool, dark places to minimize loss of root moisture.
- 338. Organic mulching shall be done which helps not only to control weed but also helps retain moisture around the plant and provide nutrient as they decay. However, care shall be taken that the mulches are few centimeters away from the tree trunk to avoid trunk rotting.
- 339. The saplings shall be fenced using protective tree guard such as 'Performed Weld Mesh Tree Guards' or block plantation with iron barbed wire or others whichever is found suitable to prevent biotic interference.

Nursery Development

340. The need for nursery development is not envisaged since Zhemgang Forest Division under the Department of Forest and Park Services had established a nursery at Tingtibi to cater seedlings to Chamkharchhu HEP, Mangdechhu HEP and NHPP. Seedlings shall be bought from the Nursery directly and plantations done in consultation with Department of Forest and Park Services.

7.12 Biodiversity Conservation

- It is expected that no significant irreversible change in local biodiversity will occur as a result of the project. No specific unique wildlife habitats will be affected by the project, as the TL will not create any large barriers to wildlife and bird movements. While the transmission line alignment does not pass through any significant wildlife habitat (much of it is barren or common broadleaf forest) and is not expected to cause any net loss of species. Any disruption of wildlife behaviour will be temporary (just during pre-construction and construction), and animals (including birds) will be able to move around or over construction sites. Still there is always the risk that avifauna vulnerable or endangered species may be affected due to reduction in habitat size, disturbance in their daily movements, and will be at risk from poaching (construction workers).
- The vertical distance between two conductors shall be about 4 m and horizontally it is about 10 m. Further, as the tallest tree underneath the line shall be not more than 4 m, it is very unlikely that the birds or even monkeys could be electrocuted by contacting these lines. As well, the distance to the nearest tree is 13.5 m from the centre on either side, this does not allow animals to jump to the line from nearby trees.
- However, the following measures aim to minimize project impacts on rare, endangered or threatened species (if any) and for overall habitat management:
 - a. Ensure Minimal Land clearing and Removal of Vegetation by working closely with the Department of Forest to ensure that that there is no rampant clearing or felling of forest in and around work sites. Also, only those trees identified and marked by the Department of Forest will be felled and removed from the site;
 - b. Provide funds to the Department of Forest to conduct repeated surveys in the forest areas to determine the distribution and population of Rarer and endangered Bird Species (to be prioritized by Forestry Office), and to conduct ecological studies to determine the precise habitat requirements, feeding, breeding and impacts on species distribution from habitat fragmentation;
 - c. Seek the assistance of the Zhemgang Forestry Division, Dzongkhag Forestry Officer and other technical institutes like College of Natural Resources or Ugyen Wangchuck Institute for Conservation and Environment (UWICE); National Biodiversity Centre, to conduct Biodiversity surveys in and around the project site and create permanent

Monitoring Plots to look at the trend in Fauna and Avifauna and the change in use of habitat;

- d. As much as possible, large trees on the edge of the right-of-way should not be disturbed or damaged, as these are favoured habitat of the rufous-necked hornbill (which is protected). As with other project areas where trees will be cut, the potential loss of bird and wildlife habitats can be countered by planting suitable trees at other locations which are currently degraded (habitat enhancement in those areas). For example, for rufous-necked hornbills, which are largely frugivorous (feeding mainly on berries, drupes of Lauraceae, Meliaceae, Myristicaceae, Annonaceae and Moraceae figs), this would involve replanting of fig species and well as species like Ficus roxburghii, Ficus hookeri, and Ficus altissima, to compensate for the loss of felled species;
- e. Allow the vegetation along the alignment to grow back to at least 2 meters height, which will provide cover for most wildlife that need to move through the right-of-way;
- f. Collaborate with Nikachu and Mangdechu Wildlife and biodiversity Conservation Programs

344 The TL is an essential component of NHPP but only the hydropower plant will be financed by ADB. Nonetheless, the conservation activities of NHPP and MHEP will become part of the TL.

- Join as a member of the Biodiversity Management Committee recommended in the Nikachu Project EMP;
- Collaborate in the Rescue and Release Program. Rescue and conserve any botanical species deemed worth conserving and cultivating for scientific and educational purposes in Collaboration with MHEP or NHPP (as per their EMP);
- Collaborate in the Wildlife Conservation program for capturing, treating/rehabilitating, and releasing wild animals found in pain or distress, particularly as a result of human interference and project activities, has been proposed under the Nikachu project to be initiated with the DoFPS. The primary goal will be to treat and rehabilitate the wildlife and release them back to the habitat from which they were collected (or safe adjacent areas). Wherever land clearing may result in encounters with wildlife and birds; all wildlife encounters must also be logged;
- Collaborate on the Biodiversity Conservation and Management Plan for the Nikachhu project that is aimed at conserving and preserving natural ecosystems around the

proposed project, and developing the information database on biodiversity at the project site.

Anti-Poaching Measures

The biggest risk with intrusion of workers into new rural forested areas is the risk of poaching. Therefore efforts must be made to prevent this from the beginning of the project.

1. Awareness Raising

Awareness-raising will be an important means to mitigate this risk. The Contractor and his workers must be informed on the Forest and Nature Conservation Act, Rules and Regulations and copies of these must be made available to them. Workers must be made aware of the fines and penalties for poaching, as well as the risk of job loss, if caught in these illegal activities.

2. Strengthen Patrolling

347 To minimize the risks of poaching, awareness programs will be combined with an increase in patrolling by local forestry staff. To support enhanced patrolling, the project discuss possibilities for strengthening patrolling or monitoring of illegal activities in the project sites with local forestry staff. The use of 'risups' or village forest guards to alert forestry officials of any illegal activities in the worker camps or at project sites can also be used.

7.13 Muck Management

- 341. The impacts of excavation work and muck disposal are limited to Tower foundation sites. Since some of these sites are too far from the nearest access road, and all tower locations are dispersed at least 300m from each site, it is not economically feasible to select one muck disposal site. Also, it is impractical without access roads since the cost of transporting soil from excavated site would be too high.
- Maximum of the muck shall be generated during benching which involves clearing and excavation of average 2 m below ground for foundation work. Small part of the muck shall be generated from pit excavation for construction of tower foot foundation. The total area of each tower foot shall be 81 m² and excavating 2 m below ground would generate about 162 m³ of muck at each tower foot during benching. Additionally, one pit each for four tower legs shall be excavated. Each pit shall be 4 m² and an average 3 m depth shall be excavated from which an average 12 m³ of muck shall be generated totaling to 48m³ from the four pits. Therefore, taking a total excavated material as 210 m³ from each tower foot, the total muck generated from 61 towers shall be 12,810 m³ over 18.6 km stretch.
- 350 To reduce the quantity of muck generated, about 50% muck from each pit shall be reused in backfilling the pits. Therefore, 24 m³ at each tower base shall be reused and for 61 towers, the total muck reusable is 1,464 m³ leaving a balance of 11,346 m³.

- 351 Since 24 m³ of muck shall be reused at each tower foot, only 186 m³ shall require disposal. Given that the amount of muck generated shall be extremely low, the muck shall be disposed of near the tower foot, leveled and vegetated.
- 352 Disposal planning and management is very important, to mitigate the possible environmental impacts of improper disposal resulting in increased sedimentation of streams and damaging the visual aesthetics of the area.

Mitigation measure

- (i) Locate all towers at a safe distance from water sources so that excavation work does not cause large quanities of soil to be washed into the streams;
- (ii) Stockpile all excavated muck at a safe distance from the foundation site, to minimize the risk of soil falling back into the pits, or blocking access to the pit;
- (iii) Unused muck remaining after backfilling of tower foundation sites must be dumped at a selected location nearby, preferable a degraded area. To minimize the creation of dust, dumping will be avoided during the high speed winds, so that suspended particulate matter (SPM) levels are not excessive. It is expected that the amount of soil to be disposed will not be large enough to require construction of retaining walls, and compaction of muck in contours (following the local topography) can be done with small equipments;
- (iv) To stabilize the muck and restore the disposal sites, local fast growing plant species are recommended but final species depends on terrain, soil, and drainage conditions of the sites. This must be done in consultation with forestry staff as this dumped area can be included under the Compensatory Afforestation Program

7.14 Managing risk of slope instability and impact on surface waters

- 353 If excavation along tower footings is on steep slopes, there are chances of slope stability and landslides. There could also be impacts on aquatic ecology and fisheries if large quantities of silt are washed into the stream during rain.
- 354 All the angle tower locations (at turning points of the line route) are already decided while exact positions of suspension towers will be decided in a later stage after completion of the ground profile survey along the line route.
- 355 As a preconstruction measure, no tower will be sited close to reservations of public streams, rivers or any other water bodies. It will avoid disruption of existing drainage paths and reduce possibility of meeting surface runoff with water body which will eventually increase turbidity levels.

- 342. As line traverse in hilly terrain, excavation for tower footings will expose soil in slopes and aggravate soil erosion in rainy season. Once the soil is excavated for tower foundations, the earth should be backfilled or removed from the site. The loose soil should be protected with mulch or covered with water-proof materials such as tarpaulins.
- 343. Considering the relatively small amount of excess soil a proper place/s for dumping excess soil would be located nearby the work site and levelled properly.
- 344. Care shall be taken not to obstruct any natural process such as surface water runoff and stream water flow, during construction works. No tower shall be located near the streams and atleast 30m buffer shall be maintained from any water body. Earth retaining structures will be built with necessary drainage facilities around the towers located in sloping areas or any locations disturbed by the project implementation. Once the towers are constructed, the loose soil shall be covered with vegetation as much as possible to avoid soil erosion and sedimentation. Also to protect the tower footing, revetment walls shall be constructed at locations wherever necessary depending on the site conditions.

Mitigation measures

- (i) All towers must be located at least 30 m from the nearest water source to avoid polluting the waters and reduce the flow of sediments;
- (ii) Tower footings will be located at stable locations, and site preparation will ensure that sediments are not mobilized. Once the tower footing foundations are poured, sediments will be placed back against the footing, and the site re-vegetated (low elevation species), to reduce the erosion risk;
- (iii) Tree cutting must be undertaken, as much as possible, in the dry season and before the monsoon, when tree cutting work could create additional damage and muddy run-off in the forest;
- (iv) Within the RoW, allow ground vegetation, shrubs and naturally occurring low-growing vegetation to regenerate to reduce visual impacts as well as reduce erosion, dust and sediment mobilization;
- (v) Water quality monitoring will be conducted at key streams along the alignment at least twice a year. These samples will be compared to the baseline data. Parameters that will be measure include: ambient temperature (°C), pH, conductivity (μmhos/ cm), total suspended solids (mg/l), total phosphorus (mg/l), dissolved oxygen (mg/l), biological oxygen demand (mg/l), chemical oxygen demand (mg/l), total sulphate (mg/l), fecal coliform count (MPN Index)

7.15 Closure Plan

345. To ensure that project components not pose a future threat to human health or to the environment and to allow the natural environment to recover and flourish again, all elements of closure for each of the pre-construction and construction project activities have already been identified. The closure details are summarized below, and can serve as a checklist for completion of all pre-construction and construction activities.

Temporary land use for storage of materials and machines

346. Areas that have been used and rehabilitated through the Compensatory afforestation program will be identified and transferred back to the District with proper handing taking signed by both the Project and the District Authorities.

Labour Camps

- (i) All buildings and service infrastructure will be de-constructed and recycled, or disposed as solid waste:
- (ii) All equipment, debris, residual waste, etc. will be cleared from the site and disposed according to the project solid waste management plan;
- (iii) Septic tanks will be cleaned, filled and covered;
- (iv) The remaining area, once cleared as described above, will be graded and prepared for re-vegetation (a target for compensatory afforestation);
- (v) All camp sites will then be inspected, documented, and photographed as evidence of full camp closure;
- (vi) Sites will be handed back to the Department of Forest or District whichever has the ownership

Tower foundation sites

347. Any material left after excavation and erection of the towers will be removed and low-growing vegetation will be allowed to flourish for slope stabilization.

7.16 Mitigating risk of electrocution and accidents during maintenance works

348. The main hazard to people from the operation and maintenance of the completed TL system is the risk of electrocution. This is a danger to the BPCL staff when repairing towers, transmission line and its associated components.

Mitigation Measures

349. It is recommended that the Operational Health and Safety measures outlined in the Construction Phase are followed. This covers the following:

- (i) Securing the workplace;
- (ii) Use of PPE:
- (iii) Procedures to follow for emergencies and Compensation procedures in case of accidents
- 350. BPCL has its own set of OHS safeguards and compensation procedures, which are being followed to ensure safety of workers in all other sites, and will apply to the TL as well.

7.17 Electromagnetic Field (EMF)

- 351. When people are passing directly below a high voltage power line, they can be exposed to an electric field between 2 to 5 kV/m and to magnetic fields of less than 40 μ T. The strength of the electric and magnetic field diminishes rapidly with distance to the line.
- 352. In homes not located near power lines this background field may be up to about $0.2~\mu T$. Directly beneath power lines the fields are much stronger. Magnetic flux densities at ground level can range up to several μT . Electric field levels underneath power lines can be as high as 10 kV/m. However, the fields (both electric and magnetic) drop off with distance from the lines. At 50 m to 100 m distance the fields are normally at levels that are found in areas away from high voltage power lines. In addition, house walls substantially reduce the electric field levels from those found at similar locations outside the house.
- 353. Countries set their own national standards for exposure to electromagnetic fields. However, the majority of these national standards draw on the guidelines set by the International Commission on Non-Ionizing Radiation Protection (ICNIRP). This non-governmental organization, formally recognized by WHO, evaluates scientific results from all over the world. Based on an in-depth review of the literature, ICNIRP produces guidelines recommending limits on exposure. These guidelines are reviewed periodically and updated if necessary.
- 354. Electromagnetic field levels vary with frequency in a complex way. Listing every value in every standard and at every frequency would be difficult to understand. **Table 7.4** gives the summary of the exposure guidelines for the three areas that have become the focus of public concern: electricity in the home, mobile phone base stations and microwave ovens. These guidelines were last updated in April 1998.

Table 7.4: Summary of the ICNIRP exposure guidelines

	•	e Power uency		phone station ency	Microwave oven frequency
Frequency	50 Hz	50 Hz	900 MHz	1.8 GHz	2.45 GHz
	Electric		Power	Power	
	field	Magnetic	density	density	
	(V/m)	field (µT)	(W/m^2)	(W/m^2)	Power density (W/m²)

	•	Europe Power frequency		phone station lency	Microwave oven frequency
Public exposure					
limits	5 000	100	4.5	9	10

• EMF Regulations in Bhutan

355. There is no specific regulation on EMF for high voltage transmission line in Bhutan. According to Safety Code, 2008 issued by Bhutan Electricity Authority, the clearance of 132 kV line should be 2.1 m horizontal and 5.5 m vertical distance from any buildings (see **Table 7.5**). Since the entire stretch of 132 kV transmission lines of NHPP passes far away from the settlements, it does not violate any such safety requirements.

Table 7.5: Overhead Electric Conductor Clearance

Particulars	220 kV	132 kV	66 kV	33 kV	11 kV	LV
Ground clearance				1	7.1	
Across street	7.0 m	6.1 m	6.1 m	6.1 m	6.1 m	5.5 m
Along street	7.0 m	6.1 m	6.1 m	5.8 m	5.8 m	5.5 m
Elsewhere	7.0 m	6.1 m	5.5 m	5.8 m	5.8 m	4.6 m*
Separation between phases		17				
Horizontal	8.4 m	6.8 m	3.5 m	1.5 m	0.7 m	#
Vertical	4.9 m	3.9 m	2.0 m	1.5 m	0.6 m	#
Clearance from buildings					1	
Horizontal	3.7 m	2.8 m	2.1 m	1.8 m	1.2 m	#
Vertical	5.5 m	4.6 m	4.0 m	3.7 m	2.5 m	#

^{*}Safety Code, 2008- Bhutan Electricity Authority

356. No effect on environment and human is envisaged due to EMF from 132 kV line of NHPP. The line is routed far away from the settlement and the RoW of 27 m shall be adopted for the line as per the National and International Standard.

Mitigation measures

357. **Distance from TL**. The strength of magnetic fields varies depending on a) magnitude of the current and b) proximity to an EMF source. The impacts of EMF are considered during the design stage and mitigation options for Transmission lines include increasing the distance of local communities, populated areas, other occupied buildings and wildlife and vegetation from the EMF source. Much of the transmission lines guidelines are derived from the Indian Standard IS 5613 (BPC, 2014). **Table 7.6** and **Table 7.7** indicate the minimum distances that are

incorporated in the design of the TL. This takes into account distance from the ground, vertical and horizontal distances from buildings and crossing with telecommunication lines.

358. The minimum distance requirements ensure that no households are within the minimum distance of 27 m (13.5m on each side) and at a minimum clearance of 6.1m from the ground vegetation of moving workers and wildlife.

Table 7.6: Minimum distance to be maintained from the TL

Particulars	Minimum Clearance (m)
Minimum RoW to be maintained	27
Clearance to ground	6.1
Clearance to Buildings	
a)Vertical: From highest object	4.58
b)Horizontal: from nearest point	2.75
Crossing with Telecommunication lines	2.75

359. A minimum distance has to be maintained for line crossing at different voltage levels. Since the RoW for 66 kV lines is 16 m and RoW for 132kV lines is 27 m, a minimum distance of 20 m (8m+12.5m) is required to between the 66 kV line and the 132 kV line.

Table 7.7: Line crossing at different voltage levels

Particulars	Minimum Clearance (m)
Up to 66KV	3.05
132KV	3.05
220KV	4.58
400KV	5.49

- 360. **Phase cancellation**. Another option to significantly reduce EMF from transmission lines is Phase Cancellation. This can be accomplished by bringing the conductors close together, vertical double circuiting, or placing independent wire conductors between the TL and an area of exposure. Phase Cancellation is most effective when the three phases have the same current flow.
- 361. **Conductor separation**. A commonly used method to reduce EMF is to decrease the distance between the conductors. This reduces the magnetic fields created by each of the three conductors because the fields are out of phase with each other and thus cancel each other. Bringing the conductors closer together requires the supporting structures to be closer together to prevent arcing and shorting out between conductors. This adds additional construction and material cost to the line.
- 362. **Vertical Double-circuiting**. Vertical double circuiting includes attaching a set of three conductors, one above the other to each side of the transmission tower. Electromagnetic fields can be reduced by 50% by reversing the phase order of the other circuit. Partial cancellation of both magnetic and electric fields can be achieved. The effectiveness of the arrangement is dependent on the current flowing through each circuit.

Conductor and OPGW spacing and clearance

- 363. For all towers, the clearance from conductors, jumper loops and all live metal to the tower steel work shall not be less than those specified in table below 'Minimum clearance from live metal to earthed metal', under still air conditions and at assumed maximum swing of jumpers. Where uplift occurs at tension tower positions the minimum clearance between any arcing horn and the jumper loop of the phase immediately above it shall not be less than the minimum still air clearance from live to earth metal stated below. The length of angle tower cross arms shall provide for the distances between conductors of the two sides at straight line structures to be maintained in a plane normal to the conductors (see **Table 7.8**).
- 364. **Selection of conductors and OPGW**. Conductors and OPGW tensions shall be so selected that the sag of the OPGW at mid-span of basic span at everyday tension provides a minimum clearance to the top conductors. The sag of the OPGW shall not be more than 90% of the sag of the line conductor at mid span under all conditions.

Table 7.8: Minimum clearance from live metal to earthed metal

Particulars	Minimum Clearance (mm)
For Single Suspension String:	
Still air-no swing	1530
For 15 degree swing	1530
For 30 degree swing	1370
For 45 degree swing	1220
For Double Suspension String	1530
For Tension String (Single/Double)	1530
Still air-no swing	1530
For 10 degree swing	1530
For 20 degree swing	1070
Minimum Creepage Distance	25 mm/kV

7.18 Mitigating risk and hazard associated with TL

365. The transmission line runs parallel to the existing 66 kV line that has been in operation for over 7 years. Till date there have been no recorded incidents of any landslides or earthquakes damaging the existing 66 kV line. Thus it is not expected that the TL will be impacted easily by any earthquake.

Mitigation measures

- (i) During the design and Survey stage, selection of tower foundation areas are based on the soil conditions, topography and geological features along each of the sections of the transmission corridor and areas of potential slope instability, potential seismic risk, debris flows, and rock fall hazards are avoided at this stage to prevent mishaps in Operation and Maintenance;
- (ii) On the upper slopes of the TL, it may be necessary to cut down trees that may fall outside the range of required corridor. In such area(s), all trees/obstacles that may hit the conductor and or the transmission tower shall be felled. This will mitigate any risks of Trees or their branches from upper slopes falling on the TL during an earthquake or landslide;
- (iii) BPC must enforce appropriate building codes and infrastructure design to increase the ability of physical structure to withstand the impact of catastrophes;
- (iv) Raise public awareness of about disasters, their risks and ways to cope with them;
- (v) Developing emergency protocols to be followed during emergencies cause by disasters/catastrophes;
- (vi) Conduct regular check and maintenance. BPC conducts regular Operation and Maintenance of all TL lines to check on the conditions of all Tower locations and along the TL to ensure that towers are in good condition and wherever needed, retaining structures are constructed to stabilize these. Routine checks must also include removing overhanging trees and branches from upper slope likely to fall on the Conductors, and remove these to prevent damaging the power line.

7.19 Mitigating electrocution of raptors and other large birds

366. The risk of Electrocution of raptors or other large birds is more pronounced in areas where the vegetation is low and the terrain is flat, as Power Poles provide structures from which to hunt and roost, especially where few other perches exist (Manville, 2005). The advantage of

the project site is that there are ample trees beyond the RoW to provide for roosting and nesting. Still mitigation measures to minimize the risk of electrocution include:

- (i) Construction of cage box on conductors to prevent birds from sitting or making nest on the towers;
- (ii) Placing colorful/fluorescent tape on the towers to make them conspicuous enough to enable birds to see them and avoid these while flying overhead or using marking devices of various shapes that can be attached to phase conductors;
- (iii) Aligning the TL close to the 66 kv line reduces the need for birds to duck two power lines at the same time;
- (iv) Sufficient phase-to-phase and phase-to ground wire spacing is critical for large winged birds. Jumper wires on all electrical equipment should be insulated including at tap and dead-end locations;
- (v) Silhouette/Predator scaring method. Use of silhouettes of predators (falcon/hawk) as scaring devices for repelling birds has been used in Netherlands, and proved to result in significant decrease in collision frequency;
- (vi) Work closely with the Department of Forest to collect information on any reports of bird collisions/accidents due to the TL, to assess sensitive areas so that specific mitigation measures for high risk areas can be undertaken. Also, the project can fund studies to be conducted on distribution of birds and density, seasonal patterns and migration corridors will help better design future mitigation measures.

8 Environmental Monitoring Program and Institutional Responsibilities

8.1 The Environmental Monitoring Program

- 367. The main objectives of environmental monitoring program are:
 - (i) To assess the changes in environmental conditions,
 - (ii) To monitor the effective implementation of mitigation measures,
 - (iii) To warn about significant deteriorations in environmental quality so that further prevention action can be undertaken.
- 368. The DGPCL and BPCL Environmental Units will be responsible for ensuring the implementation of the environmental management plan (EMP). **Table 8.1** shows the proposed EMP which specifies the various monitoring activities to be conducted during all phases. Some of the measures have been consolidated to avoid repetition, and there has been some reordering to present together those measures that relate to the same activity or site. The EMP describes:
 - (i) Impact
 - (ii) Mitigation measures,
 - (iii) Responsibility for mitigation
 - (iv) Location,
 - (v) Monitoring method,
 - (vi) Frequency of monitoring and
 - (vii) Responsibility for monitoring
- 369. **Table 8.2** presents the environmental monitoring plan while **Table 8.3** shows the environmental costs.

Table 8.1: Environmental impacts, significance, duration and their mitigation

(sign= significance; S: Significant Impact, M: Medium impact; NS: Impact Not significant

(Dur= Duration; P: Permanent; T: Temporary)

	Activity Potential Negative Impacts			Dur	Mitigation Activities and Method	Responsibility
PR	ECONSTRUCTION PHAS	SE .				
EC	ONOMIC IMPACTS					
	A social time of a six sta	0.6 acres of dryland required permanently for tower footings from 6 Households	М	Р	Selection of chosen TL alignment to avoid wetland; Compensation as per Land Act 2006; Complete transfer of land ownership process Project Construction Phase; Follow Grievance Redress Mechanism.	BPC and Dzongkhag, NLC
1	Acquisition of private land	7.5 acres of land required temporarily for construction of contractors site office, storage site an worker camps	М	Т	Encourage Contractors to lease private land instead of using government land; If government land is to be leased, select land from cleared areas; Follow Closure Plan to revegetate land prior to handing it back to the Dzongkhag;	BPC and Contractor
PR	ECONSTRUCTION PHAS	SE and CONSTRUCTION PHASE				
EC	ONOMIC IMPACTS					
2	Recruitment of local workers by Contractors	Positive increase in income and livelihood source	S	Т	Project must employ as many locals as possible	BPC

	Activity	Potential Negative Impacts	Sign	Dur	Mitigation Activities and Method	Responsibility	
SO	CIAL IMPACTS			•			
		Risk of Communicable Diseases	М	Т	Contractors should be encourage to recruit locals; Initial screening of workers for HIV/STD; Provide camp clinics and regular screening for infection	Contractor	
		increased pressure on housing, infrastructure, services	S	Т	Provision of adequate housing Provision of communal kitchen and sewerage facilities	Contractor	
		increased pressure for water and fuelwood and LPG			Provision of drinking water, Request of quota for LPG, Fuel	Contractor, BPC	
3	Influx of construction workers	Health and safety issues Workers at risk from accidents on site			Nomination of a Health and Safety Focal Person Follow Occupational Health and Safety Plan and BPC prescribed work safety measures; Provide PPE to all workers; Workers must be informed of risks at workplace Minimize hazards at the workplace Use signage and barricades at risky sites Ensure proper transportation, storage of hazardous materials Provision of vehicles on standby, communication and emergency procedures Maintain record of accidents Provide compensation for injuries and accidents	Contractor, BPC	
		Possible social instability	М	Т	Locate Worker camps away from villages Workers briefed on required behaviour towards host community and Codes of Conduct to be followed; Penalty for irresponsible behaviour may result in unemployment	BPC, Contractor	
	Mobilization of Construction Equipment and Materials	Congestion and risk of accidents due to increase in vehicles and machines, and traffic	М	Т	Stage delivery of required materials and equipment Store all construction equipment and materials at "off road" sites Post signs along the National Highway and use flag persons Move heavy machines only early mornings and late evenings	Contractor	
4		Workers exposed to air and noise pollution	М	Т	Provide PPE for workers	BPC, Contractor	
5	Impact on Cultural and Religious sites	Encroachment or disturbance to nearby religious and cultural sites	S	Т	Locate no towers are located in the vicinity Consult all affected communities Consult the custodians of all social and cultural	BPC,Contractor	

Activity	Potential Negative Impacts	Sign	Dur	Mitigation Activities and Method	Responsibility
				facilities	

	Activity	Potential Negative Impacts	Sign	Dur	Mitigation Activities and Method	Responsibility
6	Construction of TL	Reduction in visual aesthetics	NS	Р	Green belt plantation	BPC, DoFPS, Local Forestry staff
	Forest clearance activities	Work may create noise, dust & impede access	М	Т	Work only during day time, Retain ground vegetation in RoW to reduce dust	Contractor
7	activities	Loss of visual aesthetics	NS	Т	Green belt development	BPC, DoFPS, Local Forestry staff
EN\	/IRONMENTAL IMPACTS	3				
8	workers Impact on forest if land is		M	Т	Locate worker camps in degraded sites where no clearing will be required	Contractor, BPC
		Increase in demand for firewood			Liaise with the Deptt. of Forest to utilize felled unusable trees as fuelwood	Contractor, BPC
		Emissions from stoves in worker camps	М	Т	Provide electricity for cooking if possible; Use centralized kitchen to reduce use of fuelwood Air quality monitoring	BPC, Contractor
		Water Pollution and waste generation from construction camps	М	Т	Follow Solid waste management system Provide sanitation facilities and sewerage collection and disposal	Contractor
		Increase in demand for Water	М	Т	Water sourcing and provision for all worker camps	Contractor
	Increase in risk of poaching by workers		М	Т	Prohibit workers from hunting, fishing and enforce strictly; Brief workers on Forest and Nature Conservation Rules and penalties through awareness meetings/programs	Contractor, BPC
9	Mobilization of Construction	Air emissions and increased air pollution	М	Т	Permit only those vehicles passing emission control tests by RSTA	BPC, Contractor
	Equipment and Materials	Noise pollution from increase in traffic	М	Т	Use of mufflers and emission control	BPC, Contractor
		Risk of landslides and erosion	М	Т	Construct retaining walls and implement land	BPC, DoFPS,

Activity	Potential Negative Impacts		Dur	Mitigation Activities and Method	Responsibility
				management plan	Local Forestry staff
	Potential disturbance to wildlife	М	Т	Use noisy equipment only during daytime	Contractor

	Activity	Potential Negative Impacts	Sign	Dur	Mitigation Activities and Method	Responsibility
		Reduction of forest cover by 100 acres	М	Р	Implement Compensatory Afforestation plan, revegetate twice area deforested; Reduce RoW on valleys where it doesn't cause shorting risk Collaborate with MHEP and Nikachu on land management	BPC, DoFPS, Local Forestry staff
	Forest clearance for Row	Impacts on wildlife and bird habitat and distribution	М	Р	Avoid felling of trees beyond RoW; Fell only trees marked by Forestry Field staff; Dispose of cut trees as required/instructed by Forestry Officials Provide funds to DoFPS to conduct research and surveys Collaborate with Nikachu project for a) Biodiversity Conservation; b) Rescue of endangered flora and fauna c) Human wildlife conflict; d) land management Collaborate with DoFPS on a) strengthening research on wildlife/bird species distribution, habitat use; b) strengthen antipoaching and patrolling; c)ensure minimal clearing and disturbance of forest; d) revegetation of cleared areas on project completion	BPC, DoFPS, Local Forestry staff
		Impacts on air quality Dust may blow from areas cleared of vegetation in RoW	М	Т	Retain short trees, shrubs and ground vegetation in RoW Allow cut materials to rot down in situ and do not burn Air quality monitoring	BPC, DoFPS, Local Forestry staff
10		Workers could damage species & habitats outside RoW	М	Т	Mark the boundaries of the RoW with tape and prohibit trespass outside Collaborate with Nikachu Hydropower project on all Biodiversity Conservation and Wildlife Management Plans	BPC, DoFPS, Local Forestry staff
11	Tower foundation	increase in demand for water	М	T	Source water from nearby streams/rivers for	

	construction	for construction and curing works			construction activities	
	Muck generation from excavation works		М	Т	Muck disposal and revegetation at all tower sites; Construct retaining walls and bio-engineering if required	BPC, DoFPS, Local Forestry staff
		Risk of erosion and sedimentation of nearby streams	М	Т	Keep all machines, fuel storage 30m from streams Water quality monitoring	Contractor
		Risk of slope instability	S	Р	All towers must be located at least 30m from the nearest water source Tower footings will be located at stable locations, Site preparation must ensure that sediments are not mobilized. Implement tree cutting during dry season or before monsoon Allow ground vegetation shrubs to grow	BPC and Contractor
12	Stringing of Transmission lines	Possible obstruction and disturbance to wildlife from materials stored along the Length of TL	М	Т	Remove all stored materials as soon as work is completed; Inform locals in advance of work schedule	Contractor
13	Construction of TL	EMF impacts			Phase cancellation Conductor separation Vertical Double-circuiting Conductor and OPGW spacing and Clearance Selection of conductors and OPGW. Maintain minimum distances and clearances as per standard norms	
14	Post Construction	Improper closure of project site sites	М	Р	Follow closure plan for all worker camps, Contractor and storage sites, muck sites	Contractor, BPC

			Sig	Du			
	Activity	Potential Negative Impacts	n	r	Mitigation Activities and Method	Responsibility	
	ERATION PHASE						
EC	ONOMIC IMPACTS			1	T		
15	Removal of workers from site	Reduction in income from sale outlets	S	Р	Local must be brief on project period and schedule	BPC	
	Reduction in employmen opportunities		S	Р	Make locals aware from outset about temporary nature of employment	BPC	
SO	CIAL IMPACTS						
16	Removal of workers from site	No anticipated impacts		Т			
17	Regular clearing of RoW	Risk of electrocution of Maintenance workers	М	Т	Provide PPE to workers Follow OHS and emergency procedures in case of emergencies	BPC, Contractor	
18	Operation and Maintenance of TL	Risk of electrocution of Maintenance workers and locals	М	Т	Follow OHS and emergency procedures in case of emergencies Secure the workplace and shut down Power Use of PPE Inform locals in advance of maintenance work being carried out Educate Public and locals on risks of TL	BPC	
EN	VIRONMENTAL IMPACT	rs					
29	Regular clearing of RoW for maintenance	Permanent openings within Forest		Р	Compensatory Afforestation	BPC, DoFPS, Local Forestry staff	
	now for maintenance	Visual impacts		Р	green belt plantation	BPC, DoFPS, Local Forestry staff	
20	Incomplete removal of project materials	Risk of soil, water, waste impacts from residuals left after project completion	М	Р	Clean up of all worksites/work camps after project completion; Revegetation of all sites and hand over to Dzongkhag	BPC, Contractor	
21	Electrocution of birds	Birds accidently hitting the TL leading to injuries and death			Construction of cage box on conductors Placing colourful/fluorescent tape on the Towers Aligning the TL close to the 66kv line Sufficient phase-to-phase and phase-to ground wire spacing	BPC, Contractor	

		Silhouette/Predator scaring method.	
		Collect information on bird collisions/accidents	

	Activity	Potential Negative Impacts	Sign	Dur	Mitigation Activities and Method	Responsibility
22	Disasters	Risks and hazards from catastrophes			selection of tower foundation areas based on detailed geological studies cut trees that may fall on TL from upper slopes enforce appropriate building codes and infrastructure design public awareness of about disasters, developing emergency conduct regular check and maintenance	BPC

Table 8.2: Environmental Monitoring Plan

Impact	Mitigation Measure	Responsibility	Location	Monitoring	Monitoring Frequency	Monitoring Responsibility
	ECONOMIC					
Land compensation	Compensation as per Land Act 2006	BPC	Villages	Compensation report	as needed	BPC
Local employment	Project must employ as many locals as possible	BPC	Villages	Contractors meeting, Public consultation	every 6 months	BPC
	Local must be aware of project period	BPC	Villages	Public consultation, Surveys	Start of Project	BPC
	Make locals aware from outset about temporary nature of employment	BPC	Villages	Public consultation, Surveys	Start of Project	BPC
SOCIAL IMPAC		51 0	T Timages	Carvoyo	Clart of Froject	1 51 0
Employment	Project must employ as many locals as possible	BPC	Villages	Contractors meeting, Public consultation	every quarter	BPC
Worker camps	locate Worker camps away from villages	BPC, Contractor	Villages	Field observations	every quarter	BPC
Housing and sanitation	Provision of adequate housing and sanitation facilities	Contractor	Worker camps	Field observations	every quarter	BPC
Drinking water	Water sourcing and provision for	Contractor	Worker	Field	every quarter	BPC

Impact	Mitigation Measure	Responsibility	Location	Monitoring	Monitoring Frequency	Monitoring Responsibility
	all worker camps		camps	observations		
	Provide electricity for cooking if				every quarter	
Pressure on	possible; Use centralized kitchen		Worker	Field		
resources	to reduce use of fuel wood	BPC, Contractor	camps	observations		BPC
Waste	Follow Solid waste management		Worker	Field	every quarter	
generation	system	Contractor	camps	observations		BPC
	Provide sanitation facilities and		Worker	Field	every quarter	
Sewerage	sewerage collection and disposal	Contractor	camps	observations		BPC
	Only locate worker camps in		Worker	Field	every quarter	
Social conflict	already cleared, disturbed areas	BPC, Contractor	camps	observations		BPC
	Prohibit workers from hunting,		Worker	Observations,	every quarter	
Poaching	fishing and enforce strictly	Contractor	camps	reports		BPC
	Brief workers on Forest and				every quarter	
	Nature Conservation Rules and		Worker	Observations,		
	penalties	Contractor	camps	reports		BPC
Worker health	Initial screening of workers for		Worker	Observations,	every quarter	
risks	HIV/STD	Contractor	camps	reports		BPC
	Provide camp clinics and regular		Worker	Observations,	every quarter	
	screening for infection	Contractor	camps	reports		BPC
	Provide PPE (masks, gloves,			Observations,	every quarter	
Worker safety	boots) for workers	BPC, Contractor	Work site	reports		BPC
-	Workers must be informed of			Observations,	every quarter	
	risks at workplace	Contractor	Work site	reports		BPC
	Use signage and barricades at			Observations,		
	risky sites	Contractor	Work site	reports	every quarter	BPC
	Ensure proper storage,			Observations,		
	transportation of materials	Contractor	Work site	reports	every quarter	BPC
	Encourage project workers and			•		
	Contractors to minimize travel					
	and drop off for all construction			Observations,		
	materials	BPC, Contractor	Highway	reports	every quarter	BPC
				Public		
				consultation,	during	
Impact on	No Towers will be located nearby			Field	construction of	
Religious sites	Such sites	BPC, Contractor	Villages	observation	towers	BPC
-	Discuss with custodians/In-	BPC, Contractor	Villages	Public	during	BPC

Impact	Mitigation Measure	Responsibility	Location	Monitoring	Monitoring Frequency	Monitoring Responsibility
	charge of Nunnery to inform			consultation,	construction of	
	about project activities			Field	towers	
				observation		
ENVIRONMENT	AL IMPACT MITIGATION					
			designated	Field		
Air pollution	Air and noise monitoring stations	BPC	sites	Observation	every quarter	BPC
	Sprinkle water during excavation		Each tower	Field		
	at tower footings	Contractor	foot	Observation	daily	BPC
Water sourcing	Source water from nearby					
and impacts on	streams/rivers for construction			Field		
streams	activities		Work sites	Observation	every quarter	BPC
	Keep all machines and fuel			Field		
	stored 30m from streams	Contractor	Work sites	Observation	every quarter	BPC
			Tower			
	Muck disposal and revegetation	BPC, DoFPS, Local	foundation	Field		
	plan	Forestry staff	site	Observation	every quarter	BPC
			Tower			
	Parala and the design of the second	DDO DEDO LESSE	foundation	Et al.d		
	implement land management	BPC, DoFPS, Local	landslide	Field		DDO
lasarat an	strategy	Forestry staff	areas	Observation	every quarter	BPC
Impact on	O	BPC, DoFPS, Local	Entire	Field		DDO
Forest cover	Compensatory Afforestation	Forestry staff	project area	Observation	every quarter	BPC
Disturbance to wildlife and	Biodiversity Conservation and	DDC DoEDC Local	Entire	Field		
wildlife and Biodiversity	Wildlife Management Plan	BPC, DoFPS, Local Forestry staff		Observation	overy quester	BPC
biodiversity	Reduce RoW on valleys where	Forestry Stair	project area	Observation	every quarter	DPC
	this does not increase shorting	BPC, DoFPS, Local		Field		
	risk	Forestry staff	RoW	Observation	every quarter	BPC
	Retain short trees, shrubs and	BPC, DoFPS, Local	TIOVV	Field	every quarter	ыс
	ground vegetation in RoW	Forestry staff	RoW	Observation	every quarter	BPC
	Allow cut materials to rot down in	BPC, DoFPS, Local	11000	Field	GVCI y quarter	5.0
	situ and do not burn	Forestry staff	RoW	Observation	every quarter	BPC
	Avoid felling of trees beyond	BPC, DoFPS, Local		Field	J. J. Guarton	
	RoW	Forestry staff	RoW	Observation	every quarter	BPC
	Fell only trees marked by	BPC, DoFPS, Local	3	Field		-
	Forestry Field staff	Forestry staff	RoW	Observation	every quarter	BPC

Impact	Mitigation Measure	Responsibility	Location	Monitoring	Monitoring Frequency	Monitoring Responsibility
	Dispose of cut trees as					
	required/instructed by Forestry	BPC, DoFPS, Local		Field		
	Officials	Forestry staff	RoW	Observation	every quarter	BPC
	Mark the boundaries of the RoW					
	with tape and prohibit trespass	BPC, DoFPS, Local		Field		
	outside	Forestry staff	RoW	Observation	every quarter	BPC
	Work only during day time,			Field		
	Retain ground vegetation in RoW	Contractor	RoW	Observation	every quarter	BPC
Visual		BPC, DoFPS, Local	Along	Field		
aesthetics	Green belt plantation	Forestry staff	highway	Observation	every quarter	BPC
Project						
Completion and	Remove all stored materials as		All work	Field	on completion	
Closure	soon as work is completed	Contractor	sites	Observation	of work	BPC
	Clean up of all worksites/work		All work	Field	on completion	
	camps after project completion	BPC, Contractor	sites	Observation	of work	BPC
	Revegetation of all sites and		All work	Field	on completion	
	hand over to Dzongkhag	BPC, Contractor	sites	Observation	of work	BPC
	-Phase cancellation					
	-Conductor separation					
	-Vertical Double-circuiting					
	-Conductor and OPGW spacing					
	and -Clearance					
	-Selection of conductors and					
	OPGW.					
	-Maintain minimum distances					
	and clearances as per standard			Field	During	
EMF mitigation	norms	BPC	All towers	observation	construction	BPC
			Tower	Field	Pre-	
Disasters	selection of tower sites	BPC	foundation	observation	construction	BPC
				Field	Pre-	
	cut overhanging trees	BPC	RoW	observation	construction	BPC
	enforce appropriate building			Field		
	codes	BPC	Tower sites	observation	Construction	BPC
			Local	No. of		
	public awareness	BPC	community	meetings	Construction	BPC
	regular check and maintenance	BPC	Entire site	Field report	Operation	BPC

Impact	Mitigation Measure	Responsibility	Location	Monitoring	Monitoring Frequency	Monitoring Responsibility
	Follow OHS and emergency					
Operation &	procedures in case of			Observations,		
Maintenance	emergencies	BPC	Work site	reports	every quarter	BPC

Mitigation Activities and Method	Indicators	Monitoring	Monitoring Frequency	Monitoring Responsibility
ECONOMIC and SOCIAL MEASURES				
Selection of chosen TL alignment to avoid wetland;				
Compensation as per Land Act 2006;				BPC and Dzongkhag,
Complete transfer of land ownership process				NLC
Project Construction Phase;				1420
Follow Grievance Redress Mechanism.				
Encourage Contractors to lease private land				
instead of using government land;				
If government land is to be leased, select land from				BPC and Contractor
cleared areas;				Di G and Contractor
Follow Closure Plan to revegetate land prior to				
handing it back to the Dzongkhag;				
Identify and upgrade parts of the National Highway;				
Provision budget for making repairs to the National				DGPCL/BPC/MOWHS
Highway; Plan and sequence delivery of materials				2 31 32/21 3/11/31113
to reduce traffic				
Project must employ as many locals as possible				BPC
Contractors should be encourage to recruit locals;				
Initial screening of workers for HIV/STD;				Contractor
Provide camp clinics and regular screening for				Contractor
infection				
Provision of adequate housing				
Provision of communal kitchen and sewerage				Contractor
facilities				

Mitigation Activities and Method	Indicators	Monitoring	Monitoring Frequency	Monitoring Responsibility
Provision of drinking water,				Contractor, BPC
Request of quota for LPG, Fuel				Contractor, Br C
Nomination of a Health and Safety Focal Person				
Follow Occupational Health and Safety Plan and				
BPC prescribed work safety measures;				
Provide PPE to all workers;				
Workers must be informed of risks at workplace				
Minimize hazards at the workplace				
Use signage and barricades at risky sites				Contractor, BPC
Ensure proper transportation, storage of hazardous materials				
Provision of vehicles on standby, communication				
and emergency procedures				
Maintain record of accidents				
Provide compensation for injuries and accidents				
Locate Worker camps away from villages				
Workers briefed on required behaviour towards				
host community and Codes of Conduct to be				BPC, Contractor
followed;				Di O, Contractor
Penalty for irresponsible behaviour may result in				
unemployment				
Stage delivery of required materials and equipment				
Store all construction equipment and materials at				
"off road" sites				
Post signs along the National Highway and use flag				Contractor
persons				
Move heavy machines only early mornings and late				
evenings				
Provide PPE for workers				BPC, Contractor
Locate no towers are located in the vicinity				BPC,Contractor
Consult all affected communities				שר ט,טטוווומטוטו

Mitigation Activities and Method	Indicators	Monitoring	Monitoring Frequency	Monitoring Responsibility
Consult the custodians of all social and cultural facilities				
Green belt plantation				BPC, DoFPS, Local Forestry staff
Work only during day time, Retain ground vegetation in RoW to reduce dust				Contractor
Green belt development				BPC, DoFPS, Local Forestry staff
Locate worker camps in degraded sites where no clearing will be required				Contractor, BPC
Liaise with the Deptt. of Forest to utilize felled unusable trees as fuelwood				Contractor, BPC
Provide electricity for cooking if possible; Use centralized kitchen to reduce use of fuelwood Air quality monitoring				BPC, Contractor
Follow Solid waste management system Provide sanitation facilities and sewerage collection and disposal				Contractor
Water sourcing and provision for all worker camps				Contractor
Prohibit workers from hunting, fishing and enforce strictly; Brief workers on Forest and Nature Conservation Rules and penalties through awareness meetings/programs				Contractor, BPC
Permit only those vehicles passing emission control tests by RSTA				BPC, Contractor
Use of mufflers and emission control				BPC, Contractor
Construct retaining walls and implement land management plan				BPC, DoFPS, Local Forestry staff
Use noisy equipment only during daytime				Contractor
Implement Compensatory Afforestation plan,				BPC, DoFPS, Local

Mitigation Activities and Method	Indicators	Monitoring	Monitoring Frequency	Monitoring Responsibility
revegetate twice area deforested;				Forestry staff
Reduce RoW on valleys where it doesn't cause				
shorting risk				
Avoid felling of trees beyond RoW;				
Fell only trees marked by Forestry Field staff;				BPC, DoFPS, Local
Dispose of cut trees as required/instructed by				Forestry staff
Forestry Officials				
Retain short trees, shrubs and ground vegetation in				
RoW				BPC, DoFPS, Local
Allow cut materials to rot down in situ and do not				Forestry staff
burn				Forestry stan
Air quality monitoring				
Mark the boundaries of the RoW with tape and				
prohibit trespass outside				BPC, DoFPS, Local
Collaborate with Nikachu Hydropower project on all				Forestry staff
Biodiversity Conservation and Wildlife Management				Forestry stan
Plans				
Source water from nearby streams/rivers for				
construction activities				
Muck disposal and revegetation at all tower sites;				BPC, DoFPS, Local
Construct retaining walls and bio-engineering if				Forestry staff
required				Forestry stan
Keep all machines, fuel storage 30m from streams				Contractor
Water quality monitoring				Contractor
All towers must be located at least 30m from the				
nearest water source				
Tower footings will be located at stable locations,				
Site preparation must ensure that sediments are				BPC and Contractor
not mobilized.				Di O and Contractor
Implement tree cutting during dry season or before				
monsoon				
Allow ground vegetation shrubs to grow				

Mitigation Activities and Method	Indicators	Monitoring	Monitoring Frequency	Monitoring Responsibility
Remove all stored materials as soon as work is				
completed;				Contractor
Inform locals in advance of work schedule				
Phase cancellation				
Conductor separation				
Vertical Double-circuiting				
Conductor and OPGW spacing and Clearance				
Selection of conductors and OPGW.				
Maintain minimum distances and clearances as per				
standard norms				
Follow closure plan for all worker camps,				Contractor, BPC
Contractor and storage sites, muck sites				Contractor, Dr C
Local must be brief on project period and schedule				BPC
Make locals aware from outset about temporary				BPC
nature of employment				ВРС
Provide PPE to workers				
Follow OHS and emergency procedures in case of				DDO Occionato
emergencies				BPC, Contractor
Follow OHS and emergency procedures in case of				
emergencies				
Secure the workplace and shut down Power				
Use of PPE				BPC
Inform locals in advance of maintenance work				
being carried out				
Educate Public and locals on risks of TL				
Compensatory Afforestation				BPC, DoFPS, Local
Compensatory Andrestation				Forestry staff
green belt plantation				BPC, DoFPS, Local
green beit piantation				Forestry staff
Clean up of all worksites/work camps after project				BPC, Contractor

Mitigation Activities and Method	Indicators	Monitoring	Monitoring Frequency	Monitoring Responsibility
completion;				
Revegetation of all sites and hand over to				
Dzongkhag				
Construction of cage box on conductors				
Placing colourful/fluorescent tape on the Towers				
Aligning the TL close to the 66kv line				
Sufficient phase-to-phase and phase-to ground wire				BPC, Contractor
spacing				
Silhouette/Predator scaring method.				
Collect information on bird collisions/accidents				
selection of tower foundation areas based on				
detailed geological studies				
cut trees that may fall on TL from upper slopes				
enforce appropriate building codes and				BPC
infrastructure design				DFU
public awareness of about disasters,				
developing emergency				
conduct regular check and maintenance				

Table 8.3: Environmental Costs

SI. No	Category	Unit	Quantity	Cost (in Nu.)
1	Waste Management (Dust bins)	no	10	73,000
2	Biodiversity Conservation	lumpsum		500,000
3	Compensatory Afforestation	Acres	200	7,284,600
		•	TOTAL	7,857,600.00

8.2 Institutional Responsibilities

- 370. The implementation of the TL will be managed within the institutional framework that already exists in BPC. Main agencies and their roles will be as follows:
 - (i) DGPCL is the Executing Agency (EA) responsible for management, coordination and execution of all activities funded under the loan.
 - (ii) BPC is the Implementing Agency (IA), responsible for the successful construction and subsequent operation of this subproject. Implementation will be managed centrally by the Transmission Department, located in the BPC head office in Thimphu, who will appoint a Project Manager and other senior and junior staff from the existing personnel who will be responsible for local implementation of the project
 - (iii) The DGPCL, BPC, NHPP, DOFPS and District Land Officers and the Gup will be responsible for executing all Land Compensation Measures, transfer of Thram (land title) as well as assisting farmers in developing the newly exchanged land into agriculturally productive parcels of land. All grievances will also be dealt by these offices.
 - (iv) DGPCL, BPC and selected contractors will be responsible for the following:
 - Proper siting of all project offices, labor camps,
 - Provision of water, fuel wood, gas, electricity for all temporary offices and worker camps
 - Sewerage and sanitation of all sites
 - Waste management
 - Staging and movement of machines and vehicles and construction materials to project sites
 - Development of muck disposal sites,
 - Fuel storage
 - Operational Health and Safety of all workers
 - Closure of all work sites, staff quarters, temporary storage sites
 - (v) Contractors will be held responsible by the BPC for the following;
 - Screening of all workers prior to being employed
 - Provision of PPE for workers and availability of first aid, emergency health care
 - Prohibiting workers from a) social instability and mingling with locals, poaching and fishing restrictions, health risks and safety issues
 - (vi) The DGPCL, BPC will ensure that this project will work closely with the Nikachu Project, MHEP project, SFD, DOFPS, UWICE, NBC, Zhemgang Forestry Division, CNR, JSWNP and dzongkhag Forest officer to develop and collaborate on the following;
 - Compensatory Afforestation
 - Development of a greenbelt
 - Wildlife and Biodiversity Conservation Plan

- Development of nurseries for tree plantation
- Rescue, treat and release of Wildlife species
- Rescue and conserve endangered or rare flora
- Land management especially along steep slopes and landslide prone areas
- Permission for clearing the forest along the RoW, tree marking and removal.
- Permission to use felled trees as fuel wood for worker camps
- Surveys and study on distribution and habitat use by birds

9 Grievance Redress Mechanism

371. The grievance redress mechanism at NHPP will follow the process described in Table 9.1 in case locally displaced persons are not satisfied with the compensation process.

Table 9.1: Grievance Redress Mechanism

Grievance redress procedure

Step 1: The aggrieved DP submits his/her grievance in writing to the Grievance Redress Committee comprising of the members of the Dzongkhag Land Acquisition Committee, the Gup of the respective gewog, and the Project Manager of NHPPP

GRC deals with grievance **within 15 days** of receipt of complaint from AP. If unresolved;

Step 2: The aggrieved DP is not satisfied with the decision rendered by the GRC or,if he/she does not receive a response within 15 days; he/she can approach the senior management of DGPCL, and can ultimately appeal to His Majesty the King through the existing local governments such as the Geog Tshogde and the Dzongkhag Administration.

10 Information Disclosure, Consultation, and Participation

372. Consultation and information disclosure are important components of NHPP including the associated transmission line to evacuate power to the national grid. **Table 10.1** gives the details of public consultation conducted for NHPP.

A. Project stakeholders

- 373. Most of the main stakeholders have already been identified and consulted during preparation of the EIA, and any others that are identified during project implementation will be brought into the process in the future. Primary stakeholders are:
 - Households that are directly affected by this subproject
 - Local communities and users of cultural and religious facilities along the alignment

B. Secondary stakeholders

- Trongsa Dzongkhag as the Dzongkhag authority
- DGPCL as the Executing Agency;
- BPC as the Implementing Agency;
- DoF as the custodian of the all forested areas through which TL must pass;

- NEC as the agency granting Environmental Clearance;
- Other government agencies whose remit includes areas or issues affected by the project;
- The ADB.

374. Public consultation is mandatory as per Article 16 of the EA Act 2000, and Section 31 of the Regulation for the Environmental Clearance of Projects 2002. As required by the ADB, The census of DPs and socioeconomic survey was carried out during the month of July 2012, and a re-survey was conducted in April 2014 to include the changes in the people displaced. The NHPP has been extensively discussed and along with the associated transmission line.

Table 10.1: Details of Public Consultation

No.	Date	Objective
1	25 July, 2013	To discuss the Nikachu project with the local community
2	18 September, 2013	To present and discuss the draft ESIA for Nikachhu Hydropower (included the TL component as well)
3	30 October, 2013	To present and discuss the ESIA especially the EMP
4	9 December, 2013	To discuss the ESIA to the Dzongkhag and community leaders (Minutes of meeting in Dzongkha)
5	27 December 2013	To present and discuss EIA with NEC and other stakeholders
6	27 January, 2014	To discuss the project with Local community and seek consensus (Minutes of the Meeting are in Dzongkha)
7	7 April, 2014	Meeting in Tshangkha with Representatives of the Displaced Households
8	9 April, 2014	Meeting in Drakten with Representatives of the Displaced Households

Summary of public consultations and key issues

- 375. The first meeting on the 25 July, 2013 was aimed at presenting the proposed project and seeking local people's views about the project. Participants were given an orientation of the project activities, location of project infrastructure facilities such as dam construction, ancillary facilities, access roads, adits, power house, muck disposal sites, staff colonies, potential quarries, and temporary camps using maps on the walls. The idea was to give local people an idea of the project footprint. The number of affected persons and type of land impacted that had been identified was presented and discussed and questions and clarifications were encouraged. Discussions were also held on existing problems in the villages.
- 376. **Key Issues**: Most people were concerned about minimizing the impact on their land as well as the environment in general and much of the discussion revolved around land being affected and compensation Participants felt that the meeting was very timely and proper land requirement by the project should be conducted and compensation issues should be sorted out well in advance of project implementation and infrastructure development. Employment for locals, opportunities for businesses, up gradation of the local school and learning from other existing projects like Punatsangchu and Mangdechu were emphasized.

- 377. The second meeting held on the 18th of September, 2013 was organized by the DGPCL and BHUCORE (local consultant) to present the ESIA to all stakeholders at Hotel Migmar. Feedback was sought from all stakeholders to improve the ESIA.
- 378. **Key Issues:** There were a number of recommendations from various stakeholders such as incorporation of studies already done by Park, taking care to ensure measures are in place for endangered species, local employment, acceptance of project by local communities, revisiting some of the figures in the report, allocation of funds to avoid duplication with other government projects, study on aquatic ecology and environmental flow, diversification of plantations during afforestation, allocation of more budget for afforestation, waste management and impacts by construction workers.

Action: All the issues raised have been incorporated into the revised ESIA.

- 379. The third and fourth meetings involved two public consultations organized on the 30th of October, in Tshangkha and Tangsibji Villages. A total of 90 participants attended the consultation. The Gewog Administrative Officer introduced the local consultant and explained the objectives of the meeting. He briefly explained how the Royal Government and DGPCL were seeking funds to implement the Nikachu Hydropower project with funding from ADB and the various studies being conducted. The Project Manager explained the various components of the project and the local consultant presented the EMP from the draft ESIA. A summarized EMP translated in the local language, Dzongkhag was handed over to the Gewog Administrative officer to keep in the Gups office for all to see and distributed to interested participants.
- 380. **Key Issues**: Discussions were held on location of project components such as access roads, tunnels, infrastructure and the impacts on locals. The project manager explained how the location of infrastructure was conducted to minimize the number of affected households. With respect to environmental impacts of the project, participants were of the view that since they did not know much about this the NEC and Department of Forest were the best agencies to take care of these issues. People were already preparing for the project in terms of building houses to rent to staff and planting crops and selling products. A discussion on the public consensus and what it meant versus no objection from affected persons followed by participants signing the consensus form.
- 381. **Action**: EMP has been revised to incorporate comments by the villagers on minimizing environmental impacts such as blasting, revision of the road alignment by project management and employment of locals.
- 382. A fifth meeting was organized on 9th December, 2013 by the DGPCL and Dzongkhag together. The objective was to get all the District officers as well as gewog staff and representatives on the same page with respect to the ESIA. The Director of DGPCL detailed all the project components and activities to the participants and the Environmental Officer presented the ESIA and EMP. Feedback was sought from participants on this. The minutes of

the meeting were prepared in Dzongkhag as it was being circulated to District officials and local representatives.

- 383. **Key Issues**: There were no serious issues as most stakeholders were already aware of the project. There was a query on the amount of budget allocated for EMP and it was explained that EMP budget was being increased. There were some discussions on the need for afforestation and monitoring of degraded areas, social compensation rates and appropriate timing of the compensation program before the project activities are implemented, generation of local employment and businesses for affected people, as well as provision of free electricity for affected persons, Other discussions revolved around inclusion of more budget and activities for conservation activities and a need to learn from the existing Mangdechu Project. The Dzongkhag officials said that the land assessment and finalization of Thrams were underway and almost completed so the exact size of land affected and affected households could be determined.
- 384. Action: These have all been incorporated in the revised ESIA and EMP
- 385. The ESIA was presented to national level stakeholders on 27 December 2013 at the NEC hall in Thimphu. NEC had invited all stakeholders from various government agencies to attend the presentation on the EIA and EMP. Discussions were held on the same and NEC informed the house that the Minutes of the Meeting would be circulated to all stakeholders and sent back to DGPCL. Also a field visit to the project site would be conducted following which more comments on the EIA would be further incorporated. The field trip wasfrom March 10-14, 2014. After resubmission of the final EIA and EMP, NEC will either request for more changes/information or grant clearance to the project.
- 386. **Key Issues**: The general opinion was that the ESIA was good and incorporated quite a bit of primary data. Data for four seasons is actually required and DGPCL said that they would collect this as the project progressed. A number of recommendations to improve the EMP were suggested.
- 387. Action: Data deficiencies were addressed and EMP revised according to comments
- 388. During the 7th Meeting, the DGPCL made a detailed presentation on Nikachhu Hydropower Project's (NHPPP) various components and infrastructure to be constructed, its environmental and social impacts, benefits of the project, mitigation measures to address adverse impacts, entitlements, compensation, and community development programs. The minutes of this meeting is in the Annex in Dzongkha.
- 389. Two more meetings (8 and 9th) were held at Tshangkha and Drakteng in April, 2014. Meetings were organized with representatives of the displaced families. In the meetings issues related to project components, land acquisition, land replacement, adequate and fair compensation, assistance to the gewog, wildlife damage to crops, and opportunities for displaced people were discussed. Details of the meetings can be referred to in the minutes of the consultations contained in appendixes.

- 390. Apart from the meetings, the local social consultant also contacted the gewog Tshogde (administration) at their office in Trashiling, Drakten and Langthel. Focus groups were carried out with them to discuss development potential of the gewog, solicit their views on the project, anticipate positive and negative impacts of the project, land acquisition and replacement, entitlement packages, compensation rates, and their participation in the project. The study team also met village representatives in five locations namely Sherpuchen, Tangsibji and Tshangkha, Drakten, and Langthel. Issues discussed were similar to those discussed with the gewog administration. It is vital to ensure prior information dissemination and transparency in all resettlement related activities of the project including land acquisition, land replacement, project impacts,
- 391. In conclusion, the people in the project area are aware of the potential project impacts and benefits, particularly related to land acquisition, compensation and resettlement
- 392. Based on the study a Resettlement Plan was prepared by assimilating information from a census of affected households, verification of affected land, focus group discussions with local administration, key informant interviews with village leaders and consultations carried out with affected persons, local communities and local government officials.
- 393. In the meetings issues related to project components, land acquisition, land replacement, adequate and fair compensation, assistance to the gewog, wildlife damage to crops, and opportunities for displaced people were discussed. Details of the meetings can be referred to in the minutes of the consultations contained in appendixes following this RP.
- 394. The gewog Tshogde (administration) was also consulted at their office in Trashiling, Drakten and Langthel. Focus groups were carried out with them to discuss development potential of the gewog, solicit their views on the project, anticipated positive and negative impacts of the project, land acquisition and replacement, entitlement packages, compensation rates, and their participation in the project. The study team also met Village representatives in five locations namely Sherpuchen, Tangsibji and Tshangkha, Drakten, and Langthel. Issues discussed were similar to those discussed with the gewog administration. It is vital to ensure prior information dissemination and transparency in all resettlement related activities of the project including land acquisition, land replacement, project impacts,
- 395. The people in the project area are aware, and generally supportive, of the project. DGPCL officials and the Social Safeguard Development consultant have conducted a series of meetings and consultations (seven consultations in total) with DPs and Dzongkhag Administration officials. Local residents and DPs are fully aware of the potential project impacts and benefits, particularly related to land acquisition, compensation and resettlement
- 396. The draft RP will be disclosed to the DPs, public, and stakeholders at the end of May 2014 for review and comments on the various mechanism and entitlements suggested for the implementation of the RP. The intention of this procedure is to receive comments from the project displaced families in particular so that appropriate suggestions can be incorporated in

the RP and also at later stages of implementation. Relevant components of the draft RP will be translated into Dzongkhag in a booklet form and will be distributed to all DPs, the Dzongkhag officials, and Gups one week prior to the RP disclosure consultation so that DPs and stakeholders have sufficient time to review the RP and discuss it among themselves before the actual disclosure consultation is held. Copies of the Dzongkha booklet will be placed at the Dzongkhag office, gewog offices, and office of the NHP. It will also be uploaded in the website of DGPCL.

11 References

Manville, A.M (2005). Bird strikes and Electrocutions at Power Lines, Communication Towers and Wind Turbines. State of the Art and state of the Science- Next steps towards mitigation. USDA Forest Service Gen.Tech.Rep. PSW-GTR-191.2005, pp1051-1064

ADB. 2009. Safeguard Policy Statement. Manila, Philippines.

Bhutan Consultants and Research. 2011. Nikachhu Hydropower Project (210 MW) at Trongsa, Bhutan. Environmental Assessment Report. Druk Green Power Corporation Ltd.. Thimphu, Bhutan.

Bhutan Tourism Monitor. 2011. Annual Report. Produced by the Tourism Council of Bhutan, Kingdom of Bhutan.

Birdlife International 2014. Yellow-rumped Honeyguide *Indicator xanthonotus* Retrieved from http://www.birdlife.org/datazone/speciesfactsheet.php?id=531 on 8th June, 2014

Chophel, S. 2012. Culture, Public Policy, and Happiness. Journal of Bhutan Studies: 83-99.

MHEP, 2010. Environmental Impact Assessment for Mangdechu Hydroelectric Project, DGPC

DGPC. 2010. Corporate Strategic Plan – Druk Green Power Corporation Limited. Thimphu, Bhutan.

DGPC.2013. Environmental and Social Impact Assessment Report for Nikachu Hydroelectric Project. Druk Green Power Corporation

FAO. 1999. Forestry Resources of Bhutan. Country Report. Forest Resources Assessment Programme Working Paper 14, Rome.

Grierson, A.J.C. and D.G. Long. 1983. Flora of Bhutan, Volume I, Part I. Royal Botanic Garden, Edinburgh.

Grierson, A.J.C. and D.G. Long. 1987. Flora of Bhutan, Volume I, Part III. Royal Botanic Garden, Edinburgh.

Grierson, A.J.C. and D.G. Long. 1983. Flora of Bhutan, Volume I, Part II. Royal Botanic Garden, Edinburgh.

Grierson, A.J.C. and D.G. Long.1991. Flora of Bhutan, Volume 2, Part I. Royal Botanic Garden, Edinburgh.

Ministry of Agriculture and Forest (MoAF). 2006. Rules on Biological Corridors, Bhutan.

Ministry of Finance. 2009. Compensation Rates for Land and Structures, Bhutan.

Minnesota State Interagency working group on EMF issues, 2002. A white paper on Electric and Magnetic Fields (EMF) policy and mitigation options. Retrieved from www.capx2020.com

Ministry of Works and Human Settlement. 2011. Existing Road Network **Information** http://www.mowhs.gov.bt/wp-content/uploads/2010/11/road-Network-information.pdf (retrieved on 30th August, 2013).

MoAF. 1995. Forest and Nature Conservation Act of Bhutan.

MoAF. 2002. Biodiversity Action Plan for Bhutan.

MoAF. 2003. Biodiversity Act of Bhutan.

MoAF. 2006. Forests and Nature Conservation Rules of Bhutan.

National Biodiversity Centre, 2009. Biodiversity Action Plan 2009, Ministry of Agriculture Royal Government of Bhutan

NEC. 2000. Environmental Assessment Act, Bhutan.

NEC. 2004. Application for environmental clearance guideline for hydropower, Bhutan.

NEC. 2009. Waste Prevention and Management Act, Bhutan.

NEC. 2012. The Waste Prevention and Management Regulation, Bhutan.

NEC. August 2004. Application for environment clearance guideline for mines, Bhutan.

NEC. August 2004. Application for environment clearance guideline for transmission and distribution line, Bhutan.

NEC. August 2004. Application for environment clearance guideline for roads and highways, Bhutan.

NEC. August 2004. Environmental Discharge Standards, Bhutan.

NEC. February 2001. Regulation for the Environmental Clearance of Projects, Bhutan.

Norbu, C., I. Baillie, T. Dorji, H.B. Tamang, K. Tshering, and A. Hutcheon. 2003. A provisional physiographic zonation of Bhutan. Journal of Bhutan Studies. 54. NSB. 2010. Annual Dzongkhag Statistics 2010. National Statistics Bureau, Royal Government of Bhutan

NSB. 2013. Population & Housing Census of Bhutan 2013. National Statistical Bureau, Royal Government of Bhutan

GNH (2009). 10th Plan Mid-term review Report (2008-2013). Retrieved from http://www.gnhc.gov.bt/wp-content/uploads/2011/10thplanmidterm/trongsa/Dzongkhag.pdf

Annex 1: Approved TOR	for 132 kV	Transmission	Line



मुण र्पेन्श अघत तर्कि ग्वाब्य भून्य सुन्य स्वर्ण मुन्य किया प्राथ्य स्वर्ण स्व

Royal Government of Bhutan



May 27, 2014

NECS/ESD/DGPC/ToR/2014/57/0

To,

The Director
Druk Green Power Corporation Limited
Thimphu

Subject: Terms of Reference (ToR) for carrying out EIA study for transmission line

Sir,

This has reference to the letter No. DGPC/PD/P&DD/20(f) 2014/484 dated May 27, 2014 regarding the terms of reference (TOR) for carrying out Environmental Impact Assessment (EIA) studies for the proposed 132KV transmission line from Nikachhu Pot Head Yard to Mangdechhu Pot Head Yard under Trongsa Dzongkhag.

In this regard, the National Environment Commission Secretariat (NECS) is pleased to endorse the TOR as attached herewith. Please ensure that the EIA study is conducted as per the approved TOR and the EIA report is submitted accordingly to NECS.

Further, please note that the submission of EIA report doesn't guarantee the issuance of environmental clearance.

If you have any queries, please contact the Environment Services Division of NECS @ 02323384 during office hours.

Thanking you,

Yours sincerely,

Chief Environment Officer
Environment Services Division

Copy to:

1. Guard File (Terms of Reference), ESD for record.

Fax: (975-2) 323385

www.nec.gov.bt

TERMS OF REFERENCE (TOR) FOR

CONDUCTING ENVIRONMENTAL IMPACT ASSESSMENT (EIA) FOR THE CONSTRUCTION OF 132KV TRANSMISSION LINE FROM NIKACHHU POT HEAD YARD TO MANGDECHHU POT HEAD YARD

These terms of reference (ToR) provides a framework for conducting environmental impact assessment for the construction of 132KV transmission line from Nikachhu Pot Head Yard to Mangdechhu Pot Head Yard under Trongsa Dzongkhag in line with the environmental assessment procedure under the Environmental Assessment Act 2000 and its Regulation 2002. The level of detail and analysis in the report should reflect the potential environmental, economical and social impacts of the proposed project and recommend mitigation and management plan for the likely adverse environmental impacts. The ToR provides the scope of studies for the environmental impact assessment (EIA). The report prepared as per this ToR should be submitted to the National Environment Commission Secretariat along with other perquisite clearances and approvals from relevant stakeholder agencies for granting environmental clearance for the proposed project.

- 1. Title page: the title page should contain the following:
 - a) The name and location of the project.
 - b) Name and Address of the proponent.
 - c) Name, qualification and address of the EIA consulting firm;
- **2. Table of Contents:** The title and page number of all sections, maps, plans, tables, figures, and appendices of the environmental assessment reports;
- 3. Executive Summary: A brief description of the proposed project in clear and non-technical language including:
- Summary of key findings and recommendations of the assessment, including the main environmental and social issues, economic benefits, significant environmental challenges and impacts covering cumulative impacts and proposed mitigation measures.
- The objective and need for the project, alternative alignment studies and justification for chosen alignment considering technical, environmental and social concerns.
- Make use of the base maps, tables and figures wherever possible to make the report clear and understandable to the reader/reviewer. Highlight the technical and procedural aspects that need to be addressed so that they do not hamper the work progress during implementation, and the recommended strategies to circumvent such risks.
- Project financial statement and the project activity schedule.
- A declaration stating that the information disclosed in the EIA report is correct.



4. Essential maps for EIA of transmission line projects:

- A map with appropriate scale showing the proposed transmission line along with alternative alignments, the location of towers, sub-stations, project access (road/rope ways), water supply, muck disposal site, site offices, labour camps and other existing infrastructure along the length of new route/ alignment. This should also be plotted in the Google Earth and soft copy needs to be submitted to NECS.
- A map specifying the existing land use patterns of the proposed transmission line RoW.
- A map specifying the forest cover along the right of way (RoW) of the transmission line, showing, if applicable, zonation of biological corridors, national parks, and sanctuaries and occurrence of any endangered/threatened flora and fauna species and/or plants and animals of economic/ecological, importance.
- A contour map (with appropriate scale) of the proposed transmission line RoW.
- Topography Plot the transmission line layout on an appropriate scale; topographical map with a map scale and geographical North. Geology, seismicity and stability characteristics at all project facility locations and in the area of influence should also be incorporated.

Note: Depending on the type, size and location sensitivity, NEC/Competent Authorities can decide the study area and recommend appropriate scale for Environmental Assessment.

5. Policy and Legal Frameworks

Provide descriptions on the review of existing legislations and policies governing the implementation of the proposed activity and environmental assessment requirements.

6. Project Description

- Information about the project proponent and his/her experience in transmission sector with following details (a) Name of the project (b) Name of the applicant (c) Present mailing address including telephone number, fax, and email (if any) (d) Name of the environmental focal person (e) Telephone number of environmental focal person.
- Name of organization/consultant preparing the EIA report, qualifications and experience of experts involved in report preparation.
- Type and nature of the project:
 - a) Source(s) and destination(s) of power.
 - b) Capacity, Voltage level.
 - c) Number of substation and capacity.
 - d) Project duration.
 - e) Total environmental management cost.



• Describe the route details of proposed alignment including administrative location as mentioned in *Table 1: Transmission line route details*.

Table 1. Transmission line route details

Dzongkhag	Geog	Village	Distance (Km)		
tal Distance (Km)					

- Design and Engineering features, such as:
 - a) Voltage level.....KV.
 - b) Tapping Point.....
 - c) Termination Point.....
 - d) Length of line.....km.
 - e) Right of Way (RoW) width.....m.
 - f) Conductors: Number of lines and circuits, composition and diameter, minimum height over ground level for overhead lines, depth and trench and fill specifications for underground lines.
 - g) Number, type and composition of towers (number of towers on private land), manholes (if any).
 - h) Number and designs of substations to be constructed or modified or operated in conjunction with the transmission lines.
 - i) Points of interconnection with the existing grid.
 - j) Load Flow Analysis.
- Design drawings for towers, manholes, trenches, substation and other facilities.
- Access roads for transmission lines, sub-stations and other facilities:
 - a) Means of access for each stretch of the route.
 - b) Detailed information on any roads to be constructed. If roads are being constructed mention whether they are 'Temporary' or 'Permanent.' Description on the consideration of alternative means of transportation such as 'cableway' were considered or not. (Note: All information required for applications for environmental clearances for the construction of road/cableways should be included).

• Construction phase:

(a) Identify and provide schedule for each phase of construction and operation for all project and ancillary facilities including the environmental issues associated with each ancillary activity, wherever possible:

i. Mobilization of work including resources and labours.

ii. Road construction and improvements.

Page 3 of 13

- iii. Land clearing.
- iv. Blasting, if required.
- v. Borrow and spoil disposal.
- vi. Excavation and sub-grade preparation.
- vii. Foundation preparation.
- viii. Concrete work.
 - ix. Stockyard for construction materials.
 - x. Construction and installation of each project facility.
 - xi. Stabilization of disturbed areas.

(b) Construction camps (if applicable):

- i. Location of the camp. Land acquisition and compensation and study on the existing environment.
- ii. Water supply and distribution.
- iii. Waste generation, handling and disposal.
- iv. Fuel supply.
- (c) Handling and disposal of mucks: Provide the total quantity of excavated material likely to be generated during construction period (in m³), along with a management and disposal plan including identification of dump sites, dumping methods and restoration/reclamation plan.

Requirement of Resources

- Land: Provide details of the land requirements for different project activities such as transmission line RoW, substations, roads, labour camps, stock yards and offices.
- Raw materials: A complete list of the raw material requirements for the construction and erection of transmission line with quantities, sources, an inventory of chemical, toxic or hazardous substances and storage means etc., in case of sub-stations.
- Details of workforce to be employed –skilled, semi-skilled and unskilled labour both during construction and operational phases of the project with specific attention to employment opportunities for local population with assessment of skills available and training needs to make them employable for such project.
- Equipment: equipment and machineries required for the proposed project along with type and quantity of fuels required for their operations.
- The project should also explore the availability of environment friendly technologies for the type of project proposed and the feasibility of adopting such technologies in the Country.

7. Description of Existing Environment of the Project Area (Baseline Data)

A. Land Environment

- Provide details of topography, geology, stability and type of soil in the project area;
- Provide information on the existence of any transmission lines (of different voltage levels) in the proposed area and the status of their environmental impacts such as visual aesthetics due to such infrastructures;

Page 4 of 13

- Describe land use types of all lands required by the project such as transmission line alignment, substations, labour camps, stock yards, offices, etc.
- Discuss the characteristics of topsoil, its thickness and estimate the total quantity of topsoil to be generated during clearance of land along the RoW, construction of the transmission towers, sub-stations, access roads, labour camps, site offices, etc.

B. Air Environment

- Provide data on ambient air quality including parameters such as PM₁₀, gaseous pollutants, and information on existing meteorological conditions such as temperature, humidity, rainfall and wind speed and direction, wherever applicable.
- Describe the sources of the emissions.

C. Water Environment

Provide:

- Data on surface and sub-surface water characteristics including inventory of rivers, streams, springs, water crossings falling along the RoW of the transmission line.
- Information on the existence of any water sources along the line route should be spelled out in report
- Detailed information on existing natural drainage/run-off patterns along the length of the proposed alignment.
- If any changes are likely in the drainage pattern due to the proposed activity, provide details of such changes including the identification of areas vulnerable to erosion and landslide.

D. Biodiversity

- Obtain a list on the type of vegetation and wildlife including birds along the RoW of transmission line and approach roads/cableways and proposed substation location from the nearest forest office;
- Collect primary data through biodiversity survey on the occurrence of forest type and wildlife including avi-fauna in the project area and document the findings.
- Conduct public interviews to collect information on biodiversity.
- Compare the findings of the survey and interview with the list provided by forest office.
- Existence of any restricted areas from a biodiversity perspective, if applicable.
- Give details on the type of forest being diverted for non-forest use and status of forest cover in the length of new alignment proposed.
- Inventorise species of trees and plants along the RoW and 200 metres on both sides of the RoW of the alternative as well as the final proposed alignment of the transmission route in every 10KM stretch, access road/cableways and other project infrastructures locations which will be permanently affected.
- Provide information on the existence of any unique, endemic, threatened or declining species, or species of high economic and cultural value to society or ecosystem in providing important services.
- Obtain authentication and verification of the wildlife corridor by the competent authority.
- Provide information on the existence of any community forests and their significance;

Page 5 of 13

- Provide information on the existence of biological corridors, national parks, sanctuaries and their significance in terms of occurrence of any endangered/threatened flora and fauna species and their habitats. In case of biological corridors, state the type/species of fauna which uses it.
- In case of transmission passing through Protected Areas, provide the following.

Table 4. Protected area details for transmission line

Name of protected area	Length of	ftransmissi	on line in	different zones	within the protecte	ed area (km)	Total (km)	Length
	Enclave zone	Buffer zone	Core	Seasonal grazing zone	Administrative zone	Multiple use zone		

If Sub-stations fall fall in the Protected Area, provide the following information.

Table 5. Protected area details for sub-stations

Name of protected area	Area occu (km)	pied by Sul	o-stations	in different	zones within the p	rotected area	Total (km)	Length
	Enclave zone	Buffer zone	Core zone	Seasonal grazing zone	Administrative zone	Multiple use zone		

- Provide the zonation map of the protected areas through which the transmission line passes.
- E. Socio-economic and Cultural Aspect
- Cultural and heritage sites Existence of any significant cultural, historical, archaeological or environmentally sensitive sites along and 10KM on both sides of the RoW of the transmission line, access road/cableways alignment and other project infrastructures. List these sites as per *Table 6 below*.

Table 6. Cultural and heritage site details

Name of cultural heritage	Location Easting	Coordinates Northing	Describe the significance of site. Is the site listed with Department of Culture



- Describe with the help of maps the number of villages likely to be affected by the proposed project. Provide details of the land use type likely to be affected in the villages.
- Study the socio-economic and livelihood benefits obtained by local communities from the forests likely to be affected by the transmission project and its ancillary facilities.
- 8. Public Consultation: Public consultation is mandatory as per Article 16 of the EA Act 2000, and Section 31 of the Regulation for the Environmental Clearance of Projects 2002.

The proponent must explain the expected impacts of the proposed project to the public and surrounding environment indicating where they will occur, level and extent of impacts and how they will be mitigated. Concerned public should be made aware of both positive and adverse impacts likely from the proposed project, listen to the concerns raised, provide clarifications and maintain record as follows:

- Description of issues raised and resolved during the consultation. List out pending issues and the proponent's views on the pending issues.
- Provide evidences of public meetings and participations duly approved by the Local Government and Dzongkhag;

9. Assessment of Potential Environmental Impacts

This section should provide the prediction, assessment and description of environmental impacts likely to be caused by the proposed project.

A. Land Environment


Provide the assessment of the following:

- Impact due to land acquisition for the proposed project and corresponding land use changes the project would cause.
- Provide detailed assessment of the area of land required for the transmission line RoW. In areas of steep topography not all the forest within the RoW needs to be cleared. For a particular transmission line project, the total area of forest to be cleared should be calculated based on the length of transmission line and RoW for corresponding voltage level. However, the areas which are not required to be cleared should be estimated depending on the topography, type of land, and ground clearance requirement and should be subtracted from the total area to obtain the actual forest area to be cleared.

Refer Table 2: Areas of landuse along transmission line RoW.

Table 2. Areas of land use along transmission line RoW

THOIC MITTE	CHS OF INTE	d disc along	5 transn	TIOSIOH III	HC IZO VV				
Facility	Chushing (km ²)	Kamshing (km ²)	Tseri (km²)	Tsamdo (km²)	Sokshing (km ²)	Broadleaf (km²)	Conifer forest (km ²)	Scrub land (km²)	Total (km²)
Transmission line RoW									
Actual Corridor clearing required									



• Substations – Detailed information on the land use required for the substation and type of vegetation existing in the proposed area should be provided as per *Table 3*.

Table 3. Areas of land use required for sub stations (m²)

				I Sul Sta	tions (III				
Facility	Chushing (km²)	Kamshing (km²)	Tseri (km²	Tsamdo (km²)	Sokshing (km²)	Broadleaf (km²)	Conifer forest (km ²)	Scrub land (km ²)	Total (km²)
Substation 1								(*****)	
Substation 1									
			Total are	a requiring	clearance (r	n ²)			

Note: Scrubland also includes disturbed areas of Broad Leaf and Coniferous forest that have been logged and are now regenerating

- Impact to the surrounding environment due waste generation from labour camps and site offices.
- Impacts due to earth excavations. Provide the quantity of mucks likely to be generated surplus mucks likely to be generated from the proposed project.
- Impacts from extraction and production of construction materials such as aggregates, if applicable;
- Impact of project on the hilly terrain due to slope destabilization caused by site preparation, civil works, construction of access roads and other activities, if applicable such as landslides, soil erosions and sedimentations due to surface run-offs;
- Aesthetics Mention whether the location of transmission line will significantly impair visual aesthetics. Explain in detail.
- Details of the quantity and characteristic of solid/hazardous wastes likely to be generated including from utilities, if applicable.
- Complete information on the use of hazardous materials such as insulating oils/gases (e.g. Polychlorinated Biphenyls [PCB] and Sulphur Hexafluoride [SF₆]) used in transformers used during the construction and vegetation maintenance of RoW should be enumerated in the EIA, if any.

B. Air Environment

- Details about the potential sources of fugitive emissions and list of activities that may generate fugitive dust.
- Impact of fugitive emissions on ambient air quality and on workers during the construction phase of project.
- Details about the potential sources of noise generating equipments and activities that may cause noise pollution. Level of noise likely to be generated from such sources.

C. Water Environment

- List of potential project activities which can cause contamination of water resources.
- Impacts of the project on local hydrology along the length of the new alignment including impact on surface and groundwater resources.
- Impact of project and its auxiliary activities on land and water contamination.
- Impacts on water bodies due to discharge of effluents from labour camps, colonies and offices.

Page 8 of 13

D. Biodiversity

Describe and provide assessment of:

- Impact of transmission line project on biodiversity.
- Likely illegal hunting and poaching.
- Impact on wildlife habitats.
- Loss of species; Address the concern of possible extinction of such species.

E. Socio-economic and Cultural Aspect

Provide assessment of:

- Socio-economic impact of the project.
- Scope of land acquisition and its impact on the social environment.
- Employment opportunities for Bhutanese.
- If land acquisition is involved, the report should give the extent of land to be acquired for the project along with name of affected people village wise with followings information:
 - (a) Village-wise list of the affected persons or family-wise along the RoW.
 - (b) The extent and nature of land and immovable property to be acquired from affected persons; including list of public utilities and government buildings which are affected or likely to be affected, details of public and community properties, assets and infrastructure, likely to be affected. For providing information refer Table 2.8: Losses of houses and other infrastructures.
 - (c) A list of agricultural labourers in such area and the names of such persons whose livelihood depends on agricultural activities; if applicable.
 - (d) A list of persons likely to lose their employment or livelihood or likely to be alienated wholly or substantially from their main sources of trade, business, occupation due to acquisition, if applicable.
 - (e) Non-agricultural labourers, including artisans in such area, if applicable.
 - (f) Land ownership of the acquired land; provide information as described in Table 7.

Table 7. Land ownership and affected household details (m² or acres or decimal)

Where HH= Households, O=Owner, Total Affected Area=TAA

Facility	Chu-shing		Kam-		Tseri		Tsamd		Sok-		Forest	Scrub	Wetlan	Total
			shing				0		shi	ng		land	d	
	Ownership	Total	0	T	0	T	0	T	0	T	TAA	TAA	TAA	TAA
	(O) /	Area	/	Α	/	Α	/	Α	/	Α				
	Households	Affected	Н	Α	Н	Α	Н	Α	Н	Α				
	(HH)	(TAA)	Н		Н		Н		Н					
Sub-Station 1														
Sub-Station 2													,	
Transmission Line														
Total affected households (no.)														



Table 8. Losses of houses and other infrastructure

Facility	Houses (no.)	Other infrastructure, describe
Sub-station 1		
Sub-station 2		
Sub-station 3		
Transmission Line		
Total (no)		

Note: Other infrastructure losses could include shops, hotels, offices, health posts, schools, etc.

- Provide assessment of displacement of communities/people, if required.
- Describe the possibility of human-wildlife conflict due to the proposed project.
- Provide assessments of risk and hazard associated with transmission line, substation and other allied activities both during construction and operation.
 - (a) Electromagnetic Field (EMF): If EMF levels are confirmed or expected to be above the recommended exposure limits then:
 - Evaluate potential exposure on workers, people living in existing residences, schools, other occupied buildings, and populated areas along the transmission corridor.
 - Evaluate effects of EMF on wildlife and vegetation (if applicable).
 - (b) Landslides, earthquakes and snow avalanches Based on the soil conditions, topography and geological features along each of the sections of the transmission corridor, evaluate areas of potential slope instability, potential seismic risk, debris flows, and rock fall hazards.
 - (c) Substation failure: Identify potential effects due to accidents and malfunctions associated with mechanical failures of project-related substation and capacitor station equipment.
 - (d) Occupational health and safety: Assess the potential occupational health and safety issues that may arise out of:
 - Live power lines (Electrical hazards)
 - Electric and magnetic fields
 - Working at height
 - Fire/explosions from transformers
 - Exposure to chemicals

10. Assessment of Alternatives

A description and analysis of alternatives to the project and its alignment including:

- a) all feasible alternatives for both the project and its alignments;
- b) the alternative of not undertaking the project (i.e., the no-build alternative) for the purpose of establishing a future baseline in relation to which the project

Page 10 of 13

and its alternatives can be described and analyzed and its potential environmental impacts and mitigation measures can be assessed;

- c) an analysis of the feasible alternatives for both project and alignments in light of the objectives of the proponent;
- d) an analysis of the principal differences among the feasible alternatives under consideration, particularly regarding potential environmental impacts;
- e) a brief discussion of any alternatives no longer under consideration including the reasons for no longer considering these alternatives;

11. Mitigation and Environment Management Plan (EMP)

The EMP should discuss the mitigation measures to be taken against every impact on Land, Air, Water, Biodiversity, and Socio-economic and cultural aspects and the timeline for completion, the responsible agencies for implementation, and the budget for the EMP, post-monitoring provisions and reporting to the concerned regulatory authority. EMP should include:

- Resettlement and Rehabilitation plan (R&R) if displacement is involved. The plan should include details of the compensation provided/to be provided, including land-for-land compensation, employment or money; provisions at the resettlement colony (such as basic amenities including housing, educational facilities, infrastructure and alternate livelihood potential); a clear timeline for implementation, responsibility, budgets, grievance mechanism, etc.
- Detailed management plan to reduce landslides and ensure slope stabilization during transmission line construction, wherever applicable.
- Options for alternative or any substitute to avoid or minimize land acquisition with appropriate justification.
- Detail waste management plan; waste generated from the worksite, site offices, labour camps and stockyard if any must be managed and must prevent open dumping in the surrounding environment.
- Public safety strategy and plan; risk of circuit failure and electric shock must be addressed in the EIA report. Proper awareness program and plan must be adopted for general public awareness;
- Mitigation measures for control of erosion and run-off from the area where construction is to take place, especially if there is a river or agricultural land adjoining the project site.
- If the transmission line project passes through sensitive areas, Biodiversity Action Plan must be prepared. Detailed mitigation and management measures must be planed for protecting endangered species.
- Mitigation measures for noise abatement and control, wherever applicable.
- Management plan for topsoil utilization and conservation.
 - Management plan to reduce fugitive emissions during land-clearing, civil works, handling/transporting of construction material, construction of access roads, quarry operations, etc., *if applicable*.



Page 11 of 13

- Mitigation plan to reduce, avoid or minimize spills and leaks from transformers, sub stations etc.
- Restoration and reclamation plan for all debris/spoil/ muck disposal sites and other project affected areas.
- Management plan to minimize or avoid electrocution of raptors and other large birds.
- Mitigation plan to minimize or avoid EMF exposure, if applicable.
- Mitigation measures against extreme weather events and natural catastrophes such as landslides, earthquakes and avalanches.
- Afforestation and reforestation plan.
- Mitigation plan to minimize or avoid hazardous materials spills and leakages.
- A management plan for occupational health and safety of the workers and local community in the proposed transmission line RoW.
- A detailed mitigation plan and EMP for improving and enhancing socio-economic condition.
- **Decommissioning Plan:** Provide detailed plan to be implemented during decommissioning of the project.
- Rescue plan for flora and fauna species and habitats.
- Measures to manage and combat Human-wildlife conflict, if caused by the proposed project.
- Slope stabilization plan.

12. Environment Monitoring Plan

Provide a comprehensive and detailed plan covering the environmental and social parameters/variables to be monitored. Clearly state the agencies responsible for the monitoring plan during construction and operation.

13. Environmental Budget Outlay

Provide the activity breakdown and budget for the implementation of EMP and environmental monitoring both during construction and operation.

14. Response to Comments: A response to each comment received on environmental report unless the NEC Secretariat or Competent Authority, has indicated otherwise, the environment assessment report shall contain a copy of each comment either in this section or in a separate appendix, provided that this section clearly explains the location of each comment and the response to each comment.

15. Annexures:

Provide the following annexures.

- A presentation of detailed technical data to the extent necessary to keep the main text of the environmental assessment report clear and readable. The main text of the environmental impact assessment shall refer to and summarize any information contained in any annexure.
- A copy of the terms of reference duly approved by NEC Secretariat.
- Curriculum Vitae of the EIA Team members.



- List of all regulatory approvals, clearances and No Objection Certificates (NOC) required for the project and their status.
- All stakeholder clearances and approvals.
- Copy of Minutes of all consultation meetings.
- Copy of Minutes of the EIA presentation (for final EIA reports).

NOTE:

- The Proponent should maintain consistency and accuracy in the report and no subjective statements shall be accepted.
- The Proponent shall be responsible for undertaking any other related study desired by the NEC during the process of environmental clearance.
- Consistency and accuracy of information should be ensured in the report and no subjective statements shall be accepted.
- The EIA report shall include all other necessary documents such as clearance from respective Dzongkhag Administration, Department of Forest, evidence of public consultation, etc.
- A soft copy of the report including all the annexes, maps including Google Earth images/maps, GIS data, etc. needs to be submitted along with the hard copy of the report.



Annex 2: PUBLIC CONSULTATION

1. Summary of Minutes of the Public consultation for Nikachu Hydropower Project

Date: 30th October, 2013

Venue: Tsangkha and Tangsibji villages, Trongsa

Participants: Representatives of households from Tsangkha and Tangsibji villages

Two public consultations were organized on the 30th of October, in Tsangkha and Tangsibji Villages. A total of 90 participants attended the consultation. The meeting began with the Geog Administrative Officer introducing the Local Consultant and explaining the objectives of the meeting. He gave a brief background about how the Royal Government and DGPC was seeking funds to implement the Nikachu Hydropower project in Trongsa dzongkhag and that currently feasibility studies and environmental and social impact assessments were being carried out.

The Project Manager explained the various components of the project, such the location of the dam at Lorim, the Head Race Tunnel passing over the national highway to the power house from where the power from Nikachu will be evacuated to Mangdechhu station at Yurmo in Langthel Geog. He also explained how the access roads, power house, colonies and muck disposal sites will be constructed.

The local consultant explained the process of how the environmental and social assessments are being carried out as well as the need for forestry clearance, public awareness and consensus and the process of seeking environmental clearance from the National Environment Commission, after which the EIA reports and Resettlement plans will be submitted to ADB for approval. The Consultant also explained both social and environmental impacts that were identified during the EIA study along with the mitigation measures as in the EMP

A summarized version of the Environmental Management Plan translated in the local language, Dzongkhag would be handed over to the Gewog Administrative officer to keep in the Gups office for all to see and also distributed to interested participants.

The detailed component maps were also shown to the participants so that they could better understand the exact location of various project components. The Project Manager and consultant then sought the views of the participants who were encouraged to clarify any doubts or issues that they may have regarding the project.

Perception of the Project. The participants said that they understood that the project was going to be implemented in their geog but were not sure of the exact locations as they did not see many surveyors in their villages. It was clarified that much of the infrastructure work to be implemented falls within government owned land and so there was no need for surveyors in private land.

Aum Daw Zam from Tangsibji said that she thought that the project was going to be in her village but lately had heard that the project had moved. The project manager clarified that since the first preliminary surveys where it was verified that locating the powerhouse and access roads in Tangsibji would impact a large number of private land holders, the project had moved the tunnel above the highway and the Powerhouse towards the Mangdechu site. Aum Daw Zam and others agreed that this was a very good move since a lot of private land would have been affected otherwise.

The project Manager explained too how the feasibility study also identified an access road from Tseringma drupchu towards Tangsibji to a muck disposal site, but that would probably be abandoned and instead the existing farm road to the village would be widened, improved upon and used to access the muck disposal site. In this way, a smaller area will be disturbed and only one household would be affected.

Impacts.

Aum Seday from Tshangkha said that since there already seems to be so much awareness of Hydropower Projects such as PunaTsangchu, she expects that the new Project will take the problems encountered in these current projects to ensure less impacts in this new project.

Aum Dema from Tsangkha wondered whether the tunnel being underground would still affect their village. The Project Manager clarified that the tunnel would be underground and located above highway under much of government land. It would also be located very deep below and stabilized with concrete, rock bolt and metal to ensure the tunnel does not collapse, and so no impacts on the surface are expected.

There was much discussion between the Project Manager and Participants on the exact location of the infrastructure as many participants were curious as to whether their land would be affected. The Project Manager clarified that previously many households would have been affected but after the feasibility studies and reselection of sites, only 12 HH would be affected.

Aum Ugen wanted to know whether it was possible for households to lease the land to the project rather than sell it. On this the Consultant clarified that this being a long term project, it would be easier to sell the land or seek land compensation because in the future if the household decides to divide the property or sell it this would create problems for the project and the households. The Project Manager said that if people wanted to lease their land, this would probably be good for private contractors as they would require land for their labor camps and to stock materials and machines.

With respect to environmental impacts, the participants said that they did not know much about this and since there are already government agencies like the NEC and Department of Forest, this would be taken care of by them and the Project together.

Positive impacts. Aum Seday said that already in the village, people are starting to prepare for the project. Some households have started focusing on crops while some are even planning to build houses for rent to the project staff. Already the prices of cheese and vegetables had increased due to the Mangdechu Project and travelers.

Public Consensus. The Consultant explained that the Project was seeking consensus from the public for the project. Aum Ugen Tshomo was concerned that if she signed the public consensus to allow the project to go ahead but later encountered problems with the project then she would have no say in the matter. It was clarified that the public consensus was a general statement from the public and not approval by a single individual to use their property. Where individual property was affected, the project would follow the norms of the Land Act, and at the bidding of the Land Committee that would be formed at the Dzongkhag. Through this committee a separate agreement to be signed with each affected household and either cash or land compensation provided as per existing regulations.

The participants said that they would like to request that in the future, if there are any unforeseen damage to private property, the project should take care of all issues. The Administrative Officer and Consultant thanked all the participants for taking the time to attend the meeting and the Project Manager said that if any issues did arise the Project would definitely look into it.

The meeting concluded with the participants signing the Public consensus form.

Photos of public consultation in July 2013





Public consultative Meetings held in October, 2013. Tshangkha village





Public consultation Meeting held in October, 2013 Tangsibji village





2. Minutes of Detailed Project Report (DPR) Presentation for 118MW Nikachhu Hydropower Project (NHPP) to National Environment Commission (NEC) and other stakeholders.

Venue: Conference Room, National Environment Commission, Thimphu

Date: December 27, 2013

Participating Agencies:

- 1. National Environment Commission Secretariat;
- 2. Druk Green Power Corporation Ltd;
- 3. PwC Consultants:
- 4. Department of Road, MoWHS;
- 5. Bhutan Tourism Council;
- 6. National Biodiversity Center, MoAF;
- 7. Jigme Singye Wangchuck National Park, DoFPS, MoAF;
- 8. Department of Forest and Park Services, MoAF;
- 9. National Land Commission;
- 10. Gross National Happiness Commission;
- 11. Bhutan Electricity Authority;
- 12. Department of Culture, MoHCA;
- 13. Department of Geology and Mines, MoEA;
- 14. Mangdechhu Hydroelectric Project Authority;
- 15. Department of Hydropower and Power System, MoEA;
- 16. Bhutan Power Corporation;

The list of participants is enclosed as **Annexure I**.

Director (Projects), Druk Green welcomed all the participants to the DPR presentation and conveyed Dasho MD's apology for not being able to attend the presentation as he has become even busier due to his appointment as the Chairman of the 2nd Pay Commission. Director (Projects) made presentation on the existing hydropower plants, projects under investigations and revenue contributions from DGPC. Other works being undertaken by Druk Green, such as subsidiary companies like Bhutan Hydropower Service Limited (BHSL) and Dagachhu Hydro Power Corporation, other projects like Tsibjalumchhu Diversion Scheme (TDS) which will add annually 93 GWh of energy production from the Tala Hydropower Plant; starting of a hydropower construction company; establishment of Research and Development Center by amalgamation of the existing Centers of Excellences, obtaining of a Consultancy License to market the expertise of Druk Green were presented. He also informed that Druk Green is fully able to manage operation and maintenance of hydropower plants with Bhutanese and that substantial competency have now been developed to investigate, design and construct hydropower projects. He remarked that all Bhutanese must take justifiable pride in the Bhutanese capacity of management of hydropower assets from water to wire and thanked all agencies for their continued support and cooperation in the success of this important sector.

Following the welcome address, Mr. Tenzin Khorlo, Chief Environment Officer (Environment Service Division), NEC as the Chairman of the meeting gave the opening remarks. He thanked Director (Projects) for his presentation on the status and progress of hydropower sector in the Kingdom. He then briefed on the standard procedure of carrying out an Environment Impact Assessment (EIA), mentioning the need for carrying out EIA or Initial Environment Examination (IEE) based on the type of project and its magnitude of impact. He also mentioned that for projects requiring EIA, a Terms of Reference (ToR) needs to be prepared by the project developer and endorsed by NEC. The EIA to-be-prepared should be in line with the approved ToR.

Mr. Karma Tshering, Project Manager, Nikachhu Hydropower Project (NHPP) made detailed presentation on the technical aspects of the project. A copy of the salient features of the project and Executive Summary of the DPR were distributed to all the participants. The following were highlighted:

- Project background;
- Project layout and project salient features;
- Hydrology and power potential studies;
- Civil structures:
- Electro-mechanical equipment;
- Transmission line & construction power;
- Infrastructures & construction facilities;
- Construction schedule;
- Cost estimates;
- Financial analysis;
- Ownership structure and financing structure.

The presentation also highlighted on the financing and ownership structure of the project. The project shall be developed on 70:30 loan equity ratios. It was informed that ADB has already committed USD 120 million for the project: USD 80 million as loan to the project, and USD 40 million as grant/loan to provide the equity of Druk Green. Out of the 30% equity, 51% of the share shall be owned by Druk Green, 23-25% issued as Initial Public Offering to the public of Bhutan as equity shares, and 26% to a strategic partner.

On this, the following comments and discussions were made:

 Mr. Tenzin Khorlo, Chief (ESD) enquired on the process of floating shares and suggested if the preference could be given to the Project Affected People and those in the project area.

In response, Director (Projects) clarified that the allocation of shares has not yet been decided and this aspect could be examined before the issuance of IPO.

 Mr. Tashi Penjor, Dy. Chief Environment Officer, NEC also inquired on the need for strategic partner if Bhutanese could also subscribe to the 26% share which is proposed to be allocated to a strategic partner.

Director (Projects) clarified that seeking a strategic partner is for strategic reasons such as being able to bring in new technology or processes, ability to raise capital, influence in the targeted market for sale of electricity, etc.

 Mr. Ugyen Wangda, HoD, GSB, DGM raised concern on the impact of blasting as was in the case of Trongsa Dzong due to MHEP.

On this, Director (Projects) cited the example of the Tsibjalumchhu Diversion Scheme (TDS) in which a construction adit tunnel has been blasted right from the top of Tala Dam without having any impact on the THP Dam. He informed that there are controlled blasting techniques to limit impact on even attached structures and the Druk Green has the experience not to have any damage on Trongsa Dzong or other structures near the project components.

Mr. Pema Dorji (Environment Officer), Druk Green presented the Environmental and Social Impact Assessment (ESIA) of NHPP as contained in the DPR. He informed that ESIA was prepared in line with the ToR approved by NEC vide letter NEC/ESD/DGPC/1837/2012/3480 dated 26th March, 2012.

The following points were discussed during the presentation:

- Mr. Tenzin Khorlo, CEO, NEC reminded that while opting for alternatives, besides technical aspects, it is also important to take into account environment and social aspects. Mr. Ugyen Wangda, DGM also supplemented on the importance of geological stability, citing the example of Punatsangchhu-I HEP which has encountered geological problems at its Dam site. Director (Projects) informed that NHPP was initially planned as standalone 210 MW project with its Power House originally located at the confluence of Mangdechhu and Nikachhu, under Tangsibji village. However, due to poorer geology, greater environmental and social impacts, less electricity production despite higher capacity, the present scheme, with the tail water being discharged into the Mangdechhu reservoir to provide additional energy generation, was selected as the best alternative. Even for the present scheme, he informed that two sites for Power House and three sites for Dam were examined.
- Mr. Tenzin Khorlo, NEC stated that baseline data should be ideally for four seasons.
 However, he said that at least two seasons baseline data must be provided. Druk Green agreed to provide baseline data for at least two seasons.

Mr. Letro, Forest Officer from JSWNP, informed that JSWNP area has actually 37 species of mammal species as per updated data instead of 22 as presented, and also that buffer zone is to be considered as 1.5 to 2 km outside the park boundary.

Mr. Tenzin Khorlo, NEC supplemented that the raw data should be, as far as possible, be obtained from primary source.

Mr. Tashi Penjor, Dy. CEO also enquired whether surveys were carried out in the submergence area since NHPP shall submerge 6 acres of park, to which Ms. Deki Yonten, Local PwC Consultant recruited by ADB, clarified that surveys, as per standard practice, were done all over the project area and that the submergence area was also covered.

 Mr. Pema Dorji also informed that the Adit-2 of the project falls in one of the Biological Corridors connecting JSWNP and Wangchuk Centennial Park (WCP). Several flora and fauna species are present in the project area and none of which are endangered in the IUCN list.

To this the CEO, NEC suggested that reference be made to the Schedule-I of Forest and Natural Conservation Act of Bhutan.

• With regard to E-flow, Mr. Tenzin Khorlo, NEC informed that a study on environmental flow for all hydropower projects was carried out with Nu. 2 million contributed by Druk Green, which recommended 60% of the minimum flow as E-flow. However, he mentioned that the figure shall be site specific and studies shall be continued to decide on a specific figures. He expects to establish the figure of environmental flow within a year or two and the project developer should keep some provision to incorporate the changes, if required.

Director (Projects), DGPC informed that even with 10% of the minimum flow proposed as E-flow for Nikachhu Project, the tariff for electricity required from this project is quite high. He said that a sensitivity analysis would need to be conducted to examine if higher E-flows made the project financially un-viable.

Ms. Tashi Pem, DHPS recommended that the Department of Hydropower & power Systems which is the nodal RGOB agency for development of hydropower also be consulted/involved in the determination of E-flow for different projects. Mr. Tenzin Khorlo agreed to this.

 Mr. Ugyen Wangda, DGM raised concerns on impacts of reservoirs like RIM instability and reservoir-induced seismicity. He cited the example of Kurichhu Hydropower Plant (KHP) which has its reservoir RIM undergoing erosion. Therefore, studies could be carried out on reservoir stability and reservoir induced seismicity for Nikachhu. Director (Projects) informed that reservoir RIM instability study is part of the DPR studies and that in view of the small submergence and geology of the area, reservoir rim instability is not a problem with this project. As for the reservoir-induced seismic activity, he informed that this problem is anticipated only from reservoirs with huge volume of water storage. However, based on the recommendations of the participants, he agreed that Druk Green could examine this later.

Mr. Tashi Penjor, Dy. CEO, also cited example of Amochhu HEP having reservoir rim treatment plan. To this, Ms. Pratigya Pradhan, Head, P&DD, Druk Green clarified that the right bank has good rock and for the left bank, reservoir stability plan has been included in the DPR.

 Mr. Tenzin Khorlo, NEC pointed out that an EMP should have technical details including controlled blasting and listing vulnerable animals. He also mentioned to put the monitoring details including schedule of monitoring and institutions responsible for it. Besides the environmental parameters, he recommended to monitor blasting to eliminate adverse impact on Trongsa Dzong.

Director (Projects) informed that Druk Green has a team of experts (Center of Excellence for Vibration and Thermographic Analysis) who have the experience and knowledge to monitor vibrations from blastings. For monitoring, he also submitted that Druk Green has gained valuable experience from Dagachhu Project. He, therefore, assured that required monitoring shall be put in place.

 Mr. Tashi Penjor, NEC also enquired whether the quarry will be outsourced or operated by project developer. He recommended if this be outsourced to the Bhutanese contractors, since it is one of the activities whereby local contractors can be involved.

Director (Projects) clarified that it has been proposed to have the quarry operated by the main civil contractor but the proposal shall be examined.

 Mr. Tashi Penjor also enquired whether the impact on downstream users due to river diversion has been studied.

Mr. Pema Dorji, EO, Druk Green informed that no direct downstream users are present, and moreover ,11 perennial streams downstream of the Dam provide a minimum combined flow of 0.72 cumecs.

 Since 31.01 acres of private land shall be acquired affecting 12 households, Mr. Shankar Sharma from National Land Commission mentioned that the new land *Tharms* have been issued and therefore, project should use these to identify and quantify land requirements. He also suggested compensating all the Project Affected People at one go to eliminate compensation issues later since PAVA Rates are revised once every three years. Director (Projects) informed that total EMP cost of Nu. 55 million shall be revised, if required, after comments from stakeholders during the DPR Presentation to Trongsa Dzongkhag on December 12, 2013. Latest PAVA Rates shall be considered while making the revision.

- Ms. Tashi Pem, DHPS, enquired whether the cost for land development has been taken
 into account while working out compensation amounts. Mr. Kuenzang Yonten, Local
 PwC Consultant of ADB, clarified that the land development cost has been covered.
- Mr. Choki Gyeltshen, NBC inquired on how the sampling for epiphytes on trees like orchids and fungal species were carried out.

Ms. Deki Yonten, Local Consultant responded that no specific survey methodology has been adopted for epiphyte. The number of only those epiphyte found on the trees falling in the plot were counted.

In response, Mr. Tenzin Khorlo, NEC said whether the Biodiversity Impact Assessment was necessary or not in the first place. Since the project area is near JSWNP, information could be collected from the park office.

Mr. Tashi Penjor, NEC suggested if the methodology for biodiversity inventory could be done in collaboration with DoFPS or with the method approved by the Department for future projects.

 Mr. Shankar Sharma, NLC suggested that the muck dump sites after reclamation could be given to the people as compensation. He also mentioned if the project could look into health issues due to workers influx, job opportunities to Bhutanese, possibility of taking local infrastructures like housing and aligning project roads with existing farm roads.

Director (Projects) responded that the muck dump site can be given back to interested/relevant people according to laws since the muck dump sites shall be acquired only temporarily during the construction period. Regarding the health facilities, it was informed that the major EPC contractor shall be required to to have their own basic health facilities for their workers as at Dagachhu HPP.

On the job opportunities, he said one job per family can be given, during the construction period, to those affected adversely as per Sustainable Hydropower Development Policy 2008, depending on their skills. The project can rent local houses, if suitable. As for the alignment of projects road with existing roads, it was informed that the possibilities have been taken advantage of by aligning the road to Adit III with existing Tansgibji farm road to the extent possible, road to Adit V with the existing quarry road and road to muck disposal site at Tsangkha with existing Power Tiller Track.

- Mr. Leki Dorji, DoR, raised concern on whether separate budget has been allocated for maintenance of existing highways.
 - Ms. Pratigya Pradhan, Druk Green clarified that no budget has been allocated for existing road maintenance except for the maintenance of project internal roads.
 - Mr. Tenzin Khorlo, NEC added that maintenance of highway can be carried out once the project construction gets completed, however, proper traffic management must be done during construction phase to minimize impact on road condition.
- Ms. Tashi Pem, DHPS enquired whether the free 10,000 unit of electricity per acre of land acquired for the project annually to affected households have been considered to which Director (Projects) clarified that this has been taken into consideration as per the Sustainable Hydropower Development Policy, 2008.
- Mr. Choening Dorji, DoC, commented if the report could cover impact on cultural sites
 and if extensive studies can be done in the field. Director (Projects) assured that the
 impact of project on cultural sites has been covered in the project and that the
 Department of Culture has already provided NOC for the project.
 - Mr. Tenzin Khorlo also supplemented that this is one of the issues NEC should look into to include in future EIAs.
- Mr. Gorab Dorji, BPC enquired whether the Environment Impact Assessment (EIA) for transmission line for power evacuation has been carried out to which Mr. Pema Dorji, Druk Green responded that a walk-on route survey was done by BPC and detailed EIA Report is under preparation.
 - Mr. Tenzin Khorlo, NEC also added that EIA for transmission line is a huge exercise, but at least mention about the preliminary details need to be given in the report to inform the stakeholders.
- Mr. Letro, JSWNP also requested if the project developer could get the revised biodiversity data from the park office and also to look into secondary information on presence of Red Panda, one of the endangered species, at the dam site.
 - Ms. Deki Younten, PwC Local Consultant assured to work with DoFPS for secondary information.
- Ms. Namgay Bidha, DoFPS, commented that instead of capturing the wild animals, they
 may be allowed to pass since capturing may result to death of animal due to stress. She
 also enquired on the presence of muck disposal site in biological corridor, and if

downstream users like animals, has been considered. On the 2:1 compensatory afforestation monitoring, she cautioned about the survival of plantation.

Director (Projects) clarified that the muck disposals of ADIT-2 falls in the Biological Corridor for which clearance have been applied to Territorial Division and that required management shall be ensured. He also assured that plantation for compensatory afforestation shall be done in consultation with DoFPS. Mr. Tenzin Khorlo, NEC, also added that for the movement of animals downstream it is mandatory for all structures, except for dam, to keep a buffer of the required 100 feet from the water body.

• Mr. Tshering Dorji, NEC, commended on incredible primary baseline data that has been provided. He, however, said that data is confined to project area and data within the periphery of 5 km may be provided. He said that technical details of landfill, bioengineering and compensatory afforestation needed to be provided. Further, he added, if species rescue plan, like MHEP, can be incorporated such as use of eco-duct, eco-structure and habitat enrichment activities where applicable.

Ms. Deki Yonten, clarified that the Risk Assessment and Environment Valuation which was in the previous ESIA report has been dropped while updating since the information was found inadequate and weak: this would be updated and provided upon getting comments from NEC.

 Mr. Tshering Dhendup, NEC enquired on the decommissioning aspects of roads to ADITs, labor camps, recreational plans, and on the version of SPSS used for Social Data Analysis.

Director (Projects) informed that no specific decommissioning of access roads required for construction has been considered. Mr. Tenzin Khorlo also mentioned that the decommissioning plan is one important part of EMP which needs to be included.

The program concluded with the vote of thanks by Director (Projects). He said that Nikachhu Project is the first project that Druk Green is implementing from the basic investigation and ongoing consultations with stakeholders as with the present one has provided a lot of valuable education and feedback to Druk Green so that it can manage such future projects much better. He thanked all the stakeholders for continuing to support Druk Green in its continuing quest for sustainable development of hydropower for the common welfare of all Bhutanese. He also assured that all issues raised shall be appropriately managed by Druk Green.

The meeting ended with a vote of thanks to the Chair.



Director Projects, DGPC presenting the Project at the NEC EIA presentation and participants

3. Minutes of the Consultations with representatives of the Displaced Households

118MW Nikachhu Hydropower Project (NHPP)

Venue: Tangsibji Gewog Office, Trashiling, Trongsa

Date: April 7, 2014

Time: 9:30 a.m.

Mr. Kunzang Yonten, Consultant, welcomed all the participants to the consultative meeting. After the welcome address he took the attendance of the participants to ensure that every displaced household was represented at the meeting. Each representative of the displaced households was asked to introduce him/herself.

The consultant asked the participants how many of them had participated in the community consultations that was organized and conducted by DGPCL on 27.01.2014 at Tsangkha Lower Secondary School's auditorium in Trongsa. All the participants said that they had attended the consultation.

The consultant told the participants that since all of them had attended the consultation in January, 2014, where DGPCL made a detailed presentation on Nikachhu Hydropower Project's (NHPP) various components and infrastructure to be constructed, its environmental and social impacts, benefits of the project, mitigation measures to address adverse impacts, entitlements, compensation, and community development programs, in the interest of time there was no need to go through it all over again. He asked the participants if they their memories needed refreshing to which the participants said that they remembered the presentation and that there was no need to go over it again.

Detailed measurement Survey of private land to be acquired by the project

The consultant informed the participants that the detailed measurement survey (DMS) of all land (including private land) to be acquired by the project had been completed four days ago. The participants said that they had been aware of the DMS and that many of them had participated in the DMS. However, some participants requested the consultant to share the private displaced land details with them so that they could compare it with the information they had received. The consultant then read out each displaced land owners name along with the amount of land the owner would lose to the project. He informed the participants that this was the final list of displaced land owners and that the amount of private land to be acquired by the project has been finalized.

Ms. Kuenzang Wangmo, a displaced person, inquired what would happen if during construction of the access roads some additional private land (more than what has been measured during the DMS) is affected. She said that she was concerned because a steep bend along one of the access roads bordered her land and that during construction there was the danger of a portion of the steep bend collapsing on her land. To this the consultant said that the contractors will be asked to take extreme care to ensure that no private property/land is damaged during

construction. Where damages do occur, the contractor will be required to pay compensation immediately to displaced families, groups, communities or government agencies. Damaged property will be restored immediately to its former condition.

The consultant added that the DMS provided information on the lands to be acquired by the project but it did not mean that during the later stages of the project if some additional private land is required it can be acquired without paying any compensation. He said that, if, by chance extra private land is required, the land owner will be informed in advance and the same entitlements, benefits, and compensation will be made to the land owner, as is being done just now. The participants agreed that if land acquisition is done properly, as is being done just now, then they do not see any problem. The consultant assured them that the same procedure will be followed if additional land is required by the project at a later date.

Ms.Phub Zangmo, a displaced person, said that although she had attended 2 consultations on the project earlier she would like to confirm from the consultant on their entitlements, benefits, and compensation for their land lost once again.

The consultant answered by stating the entitlements, benefits and compensation as follows:

- 1. The land acquired by the project will be replaced and the title deed for the replacement land would be provided to the displaced households before any project work on the acquired land can commence. The consultant reminded the participants that the government had permitted the displaced persons to identify replacement land of their choice (as long as the replacement land is of the same size and land type as was acquired) from vacant government land around the project area. The consultant urged the displaced people to select and identify their replacement land at the earliest and inform their Gup and the Land Records Officer so that delays can be avoided in them receiving their replacement land title deeds.
- 2. Most probably, the replacement land will not be developed land ready for cultivation. So the project will pay land development costs for converting the replacement land into cultivable form. To meet this expenditure the displaced persons will be paid Nu. 75, 000 for every acre (or prorated thereof) of dry land they lose to the project. In the case of wet land the entitlement for land development cost will be Nu. 100,000 per acre (or prorated thereof).
- 3. The displaced households losing land to the project will be provided free electricity of 10,000 kWh per annum for every acre of land (or prorated thereof) acquired for the project. The displaced household may either avail free electricity or cash in lieu thereof at export rates from the project. This entitlement will continue beyond the concession period.

4. One member from each displaced family will be provided employment by the project during the construction period of the project. The employment offered will depend on the qualification and skills level of the member.

Apart from these household-level entitlements and compensations, the consultant said that the community would receive benefits from the Community Development Program for the affected community. Activities and programs that will be proposed are:

- 1. a waste disposal site for the communities of Tsangkha, Trashiling, and Tangsibji villages.
- 2. a garbage compacter truck to pick up the garbage and waste from the three villages and dump them at the waste disposal site.
- 3. an Agriculture & Dairy Product Sales outlet with refrigerators and freezers for the displaced community where they can display and sell their farming produce along with the woven products of the women in the communities.
- 4. skills training development programs will be conducted for the DPs and local community members under the project.

The consultant asked the participants from Tangsibji if the power supply from the micro hydel was reliable. Ms. Kuenzang responded that the power received is normally stable but when the villagers use all their electrical appliances the power shuts down. She said that her village was eagerly waiting for reliable electricity when villagers can use their electrical appliances without having to worry about power outages, which often left meals half-cooked in the rice and curry cookers.

Two of the displaced persons, Ms. Ugyen Tshomo and Ms. Tshewang Lham voiced their preference for cash compensation over replacement land for the land they will lose to the project while all the other displaced persons voiced their preference for land replacement.

The two ladies that preferred cash compensation requested that the cash compensation be paid at 2014 rates and not the existing PAVA's 2009 compensation rates. To this the consultant affirmed that the cash compensation will be paid at 2014 rates and that he was waiting for PAVA to revise the compensation rates. He informed the meeting that he had discussions with PAVA and that PAVA would be releasing the revised compensation rates at the end of April 2014. He assured the participants that cash compensation would be paid at 2014 PAVA rates.

Ms. Ugyen Zangmo inquired if the replacement land would be close to their land acquired by the project. The consultant responded by saying that it was up to the displaced persons to look for their own replacement land as the Dzongkhag and the Project had given them the choice of selecting their own replacement land from among the vacant land belonging to the government. Ms. Rinzin Wangmo, although she is not a displaced person, she attended the consultation because her land lies adjacent to one of the access roads. She was concerned that the access road may affect her land holding. The consultant responded to her by saying that only the lands

confirmed during the DMS will be acquired and utilized by the project. The project would ensure that, apart from the land already surveyed, additional land is not impacted whatsoever. Therefore, Ms. Rinzin Wangmo should not worry about her land holding being impacted by the access roads. The consultant added that, the project would guarantee that if any damage was caused to her land during construction she would be compensated in full by the project contractor responsible.

The consultant asked the participants if they had any other doubts, queries, or clarifications they wished to seek. The participants said that they did not have any further doubts or queries.

Mr. Sithar Wangchuck, who was the Acting Gup in the absence of the Gup, delivered the vote of thanks. He thanked the consultant for taking time to come and consult with the displaced persons. He said that on behalf of the community he would like to thank DGPCL and ADB for taking up the NHPP in their gewog of Tangsibji. He said that the gewog in particular and the country in general would benefit tremendously from the project. He said that the people were aware of the impacts and benefits of the project and that the people were happy to participate and contribute in this nation-building initiative. He also said that the displaced persons were now fully aware of their entitlements, benefits, and compensation packages and thanked DGPCL and ADB for their generosity and assistance in helping uplift their community and gewog.

The consultant then paid the displaced persons Nu. 200.00 each for taking the day off to travel and participate in the consultations.

The consultation concluded at 1:30 p.m.



Figure 1 Consultations with displaced households in Tangsibji Gewog Office, Trashiling, Trongsa



Figure 2 Consultations with displaced households in Tangsibji gewog Office, Trashiling, Trongsa



Figure 3 Consultations with displaced households in Tangsibji Gewog Office in Trashiling, Trongsa

LIST OF PARTICIPANTS

- 1. Mr. Sithar Wangchuk, Acting Gup, Tangsibji Gewog, Trongsa
- 2. Mrs. Ugyen Zangmo, displaced person
- 3. Mr. Dorji, displaced person
- 4. Sonam Wangchen, displaced person
- 5. Mrs. Dorji Zangmo, displaced person
- 6. Mrs. Phub Zangmo, displaced person
- 7. Mrs. Ugyen Tshomo, displaced person
- 8. Mrs. Sonam Pelmo, displaced person
- 9. Mrs. Tshering Lhamo, displaced person

- 10. Mrs. Dorji Dema, displaced person
- 11. Mr. Tsang Tsang Dorji displaced person
- 12. Mrs. Kunzang Wangmo displaced person
- 13. Mr. Sithar, representative of Namgay Chholing Community Primary School
- 14. Mr. Kunzang Yonten, consultant

4. Minutes of the Consultations with Representatives of the Displaced Households

Transmission Line Component of the 118MW Nikachhu Hydropower Project (NHPP)

Venue: Drakten Gewog Office, Trongsa

Date: April 9, 2014

Time: 10:00 a.m.

The list of participants is attached to these minutes

The consultant, Mr. Kunzang Yonten, welcomed the participants to the consultation. He informed the participants that although the main Nikachhu Hydropower Project (NHPP) components would be located about 45 kms away in Tangsibji gewog, the transmission line component of the Nikachhu Hydropower Project would extend from Tangsibji gewog through Drakten gewog and on to Langthel gewog where the Mangdechhu Hydropower Project's (MHPP) port head yard is located. He explained to the participants that the power from NHPP will have to be evacuated from NHPP's port head yard to Mangdechhu Hydropower Project's port head yard from where it would join MHPP's transmission line for the power to be evacuated and exported to India.

He informed the participants that Bhutan Power Corporation (BPC) had conducted the survey of the transmission line route and had identified the location of the 61 transmission line towers in December 2013. He explained that the length of NHPP's transmission line would be 18.6 kms long and would require 61 transmission towers to support the transmission lines. He said that every effort was made by the BPC survey team to avoid impacting private land and hence because of the efforts, out of the 61 transmission towers, only 6 transmission towers will fall on private land while 55 transmission towers will fall on government land. He added that even with the best efforts it was almost impossible to avoid every private land along the transmission line route.

The consultant explained that each transmission line tower would require a footprint of 10 decimals of land (1 acre = 100 decimals) and so 10 decimals of land will have to be acquired by the project from 6 different private land owners. In total the project would need to acquire 60 decimals (0.6 acre) of land from the 6 private land owners in total.

He then explained to the participants about the NHPP. The cost of the project, Its funding mechanism, the amount of power it would generate, the amount of revenue it would bring, benefits, its impacts, mitigation measures to address any negative impacts of the project, and the changes it would bring.

Ms. Tshering Dema, a displaced person, asked the consultant to explain what the compensation and benefits were for the people who lose land to the project. The consultant answered by stating the entitlements, benefits and compensation as follows:

- 1. The land acquired by the project will be replaced and the title deed for the replacement land would be provided to the displaced households before any project work on the acquired land can commence. The consultant reminded the participants that the government had permitted the displaced persons to identify replacement land of their choice (as long as the replacement land is of the same size and land type as was acquired) from vacant government land around the project area. The consultant urged the displaced people to select and identify their replacement land at the earliest and inform their Gup and the Land Records Officer so that delays can be avoided in them receiving their replacement land title deeds.
- 2. Most probably, the replacement land will not be developed land ready for cultivation. So the project will pay land development costs for converting the replacement land into cultivable form. To meet this expenditure the displaced persons will be paid Nu. 75, 000 for every acre (or prorated thereof) of dry land they lose to the project. In the case of wet land the entitlement for land development cost will be Nu. 100,000 per acre (or prorated thereof).
- 3. The displaced households losing land to the project will be provided free electricity of 10,000 kWh per annum for every acre of land (or prorated thereof) acquired for the project. The displaced household may either avail free electricity or cash in lieu thereof at export rates from the project. This entitlement will continue beyond the concession period.
- 4. One member from each displaced family will be provided employment by the project during the construction period of the project. The employment offered will depend on the qualification and skills level of the member.

Ms. Phurpamo, a displaced person, stated that she had also lost land to MHPP and that she had a bad experience with them. She said that initially, the MHPP had acquired 10 decimal of her land for which she was compensated but during the construction phase the project took 6 decimals of additional land from her (totaling to 16 decimals of land) and that it took over a year for her to receive that compensation. She said that she hoped the same would not occur under the NHPP. The consultant responded by saying that there was a big difference between MHPP and NHPP. He informed the participants that the MHPP was financed by the Government of India (GOI) while bulk of NHPP would be financed by ADB. He explained that since NHPP would be financed, in large part, by the ADB, the NHPP would be following ADB guidelines. He explained that ADB safeguard policies were very stringent with their fundamental objectives for involuntary resettlement being; to avoid involuntary resettlement wherever possible; to minimize involuntary resettlement by exploring project and design alternatives; to enhance, or at least restore, the livelihoods of all displaced persons in real terms relative to pre-project levels; and to improve the standards of living of the displaced poor and other vulnerable groups.

He added that if ADB requirements and guidelines were not followed the financing of the project by ADB might not materialize, therefore, NHPP follow ADB's guidelines without compromising national laws and regulations. Ms. Yeshey Choden, a nun, who is a displaced person, requested that the transmission tower to be located in her land be relocated elsewhere. The consultant responded saying that BPC had already completed their transmission line survey route and finalized the location of the transmission line towers and that any change at this point of time would necessitate other changes which might not be viable or feasible. He explained that the transmission line route was planned in such a way that the least amount of private land would need to be acquired. If Ms. Yeshey Choden's land was to be relieved of the planned transmission tower, it would have to be relocated in someone else's private land after re-aligning the transmission line which would neither be fair for the other land owner nor would it be ideal for the route alignment. Moreover, the next land owner might ask for the transmission tower to be relocated elsewhere again. Therefore, it would not be possible to relocate the transmission tower that falls on Ms. Yeshey Choden's land to another location, the consultant said.

The consultant reminded the participants that he was here in the capacity of a social safeguard consultant for the project to carryout consultations with the displaced people and that he had no authority whatsoever to make any decisions on the technical aspects of the project such as location of transmission towers or any other project infrastructure. He explained that his primary responsibility, apart from ensuring that the displaced persons are not worse off after the project than they were before it, was to assess the social impacts of the project and recommend mitigation measures to address the negative social impacts of the project.

Mr. Rinzin, the brother of a displaced person who was representing his sister, said that he knows about government policies since he was the ex-Gup of Drakten gewog. He asked why the displaced persons were not invited to participate in BPC's transmission line route survey. He opined that during such surveys BPC should invite displaced persons so that the displaced persons can participate during the identification of the location of the transmission line towers stage itself which is more like the actual decision-making stage for the location of project infrastructure. He added that if the displaced persons were involved right from the route survey stage the project would face less resistance and more support from displaced persons since the displaced persons would clearly understand why the transmission tower was being located in their private land. He also said that if the consultant could not take any technical decisions the project/DGPCL should, along with the consultant, send a suitable representative from their office who is authorized to make necessary decisions in the field during such important consultations with displaced people.

The consultant answered by saying that before BPC initiates such transmission line surveys it is not aware of who will be impacted by the results of the survey. Therefore, it would not be possible for BPC to invite displaced persons to participate in the transmission line surveys for the simple reason that prior to the survey BPC will not know who will be impacted or whose private land will need to be acquired. It is the survey results that determine the displaced persons and not vice-versa. However, the consultant conceded that BPC should have carried out a consultative meeting with the private owners of the impacted land immediately after the survey results had identified the location of the towers and the private land to be acquired for

the construction of the towers. He assured the participants that he would recommend to BPC to consult with the private land owners immediately after they complete their transmission line route surveys in future. This, he agreed, would definitely assist the project to get the local communities and displaced persons on the projects side since they would feel that they were involved in some aspects of the project's decision-making process.

Ms. Karma Lhatsho, asked what would happen if due to a landslide the erected tower falls on private land and damages some of it or if it affected some structures. To this the consultant responded by saying that any damage caused in the event of a transmission tower toppling or falling due to a landslide will be compensated for by BPC since the towers will be the property of BPC.

Mr. Rinzin said that after the consultant had explained to the participants the need for the project; the impacts and benefits of the project, mitigation measures to address any adverse impacts caused due to the project, entitlements, benefits and compensations the project would provide to the displaced persons, and above all the consultant's assurance that the NHPP being an ADB-financed project all entitlements, benefits and compensations would be paid prior to the commencement of any project construction works, the displaced persons now understood most aspects of the project particularly on land acquisition and compensation issues that concerned them the most. He added that the displaced persons were happy to receive such reassurances.

The consultant asked the participants if they had any further queries or clarifications they wanted. The displaced persons said that they did not have any other queries.

Mr. Rinzin, delivered the vote of thanks on behalf of the participants since the Gup, Tshogpa, and Gewog Administration Officer were not present during the consultative meeting since they had to attend a meeting in Trongsa Dzong. Mr. Rinzin thanked the consultant for taking the time to come to their gewog to consult with the displaced persons and for being patient and for clarifying all doubts and queries the participants had, and for even answering some irrelevant and stupid questions put up by ignorant villagers. He said that all the participants now understood the importance of the project; the projects objectives and policies when it comes to involuntary resettlement; its impacts and mitigation measures, and; entitlements, benefits and compensation packages. He said that the participants were happy to be involved in the project and did not mind surrendering their private land for the project provided replacement land was delivered before any project work commences on their private land, and that the participants were happy with the compensation packages that will be provided by the project. He opined that the entire Dzongkhag would be better off after the project than it was before. He also thanked DGPCL and ADB for taking up this important national project and locating it in Trongsa dzongkhag.

The consultant then paid the displaced persons Nu. 200.00 each for taking the day off to travel and participate in the consultations. He also paid Traveling Allowance and Per Diem to displaced persons who would lose some land to the transmission line who had come from other dzongkhags to attend the consultation.

The consultation concluded at 1:00 p.m.



Figure 4 Consultations with displaced persons in Drakten Gewog Office, Trongsa. (Transmission line component)



Figure 5 Consultations with displaced persons in Drakten Gewog Office, Trongsa. (Transmission line component)

LIST OF PARTICIPANTS

- 1. Ms. Yeshi Choden, displaced person
- 2. Ms. Phurpamo, displaced person
- 3. Ms. Tshering Dema, displaced person
- 4. Mr. Rinzin, brother and representative of Mrs. Tashi Wangmo, displaced person
- 5. Mrs. Karma Lhatsho, sister and representative of Mr. Sangay Wangdi, displaced person
- 6. Ms. Lemo, displaced person
- 7. Ms. Wangmo, Gewog Officer

5. Minutes Of the Meeting Held on 27th January, 2014, Trongsa Dzongkhag

Q & A session minutes for Technical and ESIA presentation of 118 MW Nikachu Hydroelectric Project Venue: Raven Hotel Date: December 12, 2013

SI. No	Agenda/Issue	Discussion	Recommendation/Resolution	Action to be followed
1	Land compensation	Need for initial assessment & study on private land	Initial assessment & study to be carried out before the onset of project works to compensate accordingly at later stage	Focal person from Nikachu project & Dzongkhag Land Lease committee
2	Location for Batching plant and stone quarry	Need for initial assessment and study to be carried out	Initial assessment & study to be carried out for appropriate location. The batching plant to be same as mentioned in DPR and not based on contingency.	Focal person from Nikachu & Dzongkhag Environment committee
3	Transmission Line	Need for study	Study & assess the transmission line corridor and incorporate in the project report	Nikachu Project
4	Eco-tourism	The need to explore & fund tourism site especially bird watching along project area	Eco-tourism to be explored and incorporated into project plan	Nikachu Project
5	Muck disposal, waste management & water	The need to identify and plan muck disposal site before the onset of project works The need to plan waste & sewerage before the onset of project works for people living in camps The need to check and treat water before consumption	To refer Water & Waste management Act To get necessary clearance for all environment and culture related works before the onset of project works To conduct open space planning to find adequate space to muck disposal, recreational site filling etc.	Nikachu Project & Dzongkhag Environment Officer

Participants at the Meeting

Government Representatives

- 1. Dasho Dzongda Director, Projects Department, DGPC Gup
- 2. Dasho Dzongrab Chief Designer (electrical division) Mangmi
- 3. Dzongkhag Principal Officer Survey Engineer 5 Tshogpas
- 4. Dzongkhag RNR Sector Heads Environment Officer Representative of DT Chairperson
- 5. Dzongkhag Health Officer Administrative Officers
- 6. Dzongkhag Planning Officer ADB Consultant
- 7. Dzongkhag Environment Officer
- 8. Dzongkhag Accounts Officer
- 9. Dzongkhag Land Record Officer
- 10. Park Manager, JSWNP, Tshangkha
- 11. Territorial Ranger, Trongsa
- 12. Territorial Ranger, Chendebji

Representatives from the District

- 1. Gup (Head of Gewog Administration)
- 2. Mangmi (
- 3. Tsogpas(Village Head)

Representatives from the DGPC

- 4. Director, Projects Department, DGPC Gup
- 5. Chief Designer (electrical division)
- 6. Survey Engineer
- 7. Environment Officer
- 8. Administrative Office

Representatives from the District

- 9. PWC local Consultant- Social
- 10. PWC local Consultant- Environment

Annex 3: Results of Biodiversity Survey Table 1. List of Plant species recorded from Project site

No.	Scientific Name	Family	Habit
1	Aconogonon molle	Polygonaceae	Shrub
2	Adhatoda vasica	Acanthaceae	Shrub
3	Agapetes serpens	Ericaceae	Semi-climbing shrub
4	Ainsliaea aptera	Compositae	Herb
5	Alnus nepalensis	Betulaceae	Tree
6	Anaphalis busua	Compositae	Herb
7	Anaphalis triplinervis	Compositae	Herb
8	Ardisia macrocarpa	Myrisinaceae	Shrub
9	Artemesia vulgaris	Asteraceae	herb
10	Artemisia indica	Asteraceae	Herb
11	Arundinaria sp.	Poaceae	Cane
12	Asplenium sp.	Aspleniaceae	fern
13	Berberis aristata	Berberidaceae	Shrub
14	Berberis praecipua	Berberidaceae	Shrub
15	Bischofia javanica	Bischofiaceae	Tree
16	Brassaiopsis mitis	Araliaceae	Shrub
17	Bulbophyllum affine	Orchidaceae	Orchid
18	Calanthe sp.	Orchidaceae	Orchid
19	Castanopsis hystrix	Fagaceae	Tree
20	Cautleya gracilis	Zingiberaceae	Herb
21	Cinnamomumm bejolghota	Lauraceae	Tree
22	Cirsium falconeri	Asteraceae	Herb
23	Cirsium verutum	Asteraceae	Herb
24	Coelogyene corymbosa	Orchidaceae	Orchid
25	Cotoneaster microphyllus	Rosaceae	Shrub
26	Cymbidium cyperifolium	Orchidaceae	Orchid
27	Cyperus Cyperoides	Cyperaceae	Grass
28	Daphne bholua	Thymelaeaceae	Shrub
29	Daphniphylluim calycinum	Daphniphyllaceae	Shrub
30	Daphniphyllum sp.	Daphniphyllaceae	Tree
31	Datura suaveolens	Solanaceae	Shrub
32	Dendrobium candidum	Orchidaceae	Orchid
33	Dichroa febrifuga	Hydrangeacea	shrub
34	Diplazium esculentum	Athyriacea	fern
35	Docynia indica	Rosaceae	Tree
36	Duabanga grandiflora	Sonneratiaceae	Tree

No.	Scientific Name	Family	Habit
37	Edgeworthia gardneri	Thymelaeaceae	Shrub
38	Eleagnus parvifolia	Elaeagnaceae	Shrub
39	Eria coronaria	Orchidaceae	Orchid
40	Erythrina arborescens	Leguminaceae	Tree
41	Eupatorium adenophorum	Asteraceae	Herb
42	Eupatorium odoratum	Asteraceae	Shrub
43	Eurya acuminata	Theaceae	T/S
44	Eurya acuminata	Theaceae	Shrub
45	Exbucklandia populnea	Hamamelidaceae	Tree
46	Ficus roxburghii	Moraceae	Tree
47	Ficus semicordata	Moraceae	Tree
48	Fragaria nubicola	Rosaceae	Herb
49	Gastrochilus	Orchidaceae	Orchid
50	Gleichenia gigantea	Glienchianaceae	Fern
51	Hedera nepalensis	Araliaceae	Climber
52	Hemiphragma heterophyllum	Scrophulariaceae	creeping plant
53	Hydrocotlye javanica	Apiaceae	Herb
54	llex aquifolium	Aquifoliaceae	Shrub
55	Indigofera dosua	Leguminosaceae	Shrub
56	Inula cappa	Asteraceae	Herb
57	Juglans regia	Juglandaceae	Tree
58	Leucas ciliata	Lamiaceae	Herb
59	Lindera pulcherrima	Lauraceae	Tree/Shrub
60	Lindera pulcherrima	Lauraceae	Tree/Shrub
61	Lycopodium clavatum	Lycopodiaceae	club Moss
62	Lycopodium clavatum	Lycopodiaceae	Moss
63	Lyonia ovalifolia	Ericaceae	Tree
64	Measa chisia	Myrinsinaceae	Shrub
65	Michelia doltsopa	Magnoliaceae	Tree
66	Mikania micrantha	Asteraceae	vine
67	Neillia rubiflora	Rosaceae	Shrub
68	Oleandra pistillaris	Oleandraceae	Fern
69	Ophiopogon wallichianus	Convallariaceae	herb
70	Osbeckia stellata	Melastomataceae	Herb
71	Persea bootanica	Lauraceae	Tree
72	Persea clarkeana	Lauraceae	Tree
73	Phalaenopsis sp.	Orchidaceae	Orchid
74	Pilea umbrosa	Urticaceae	Herb
75	Pinus roxburghii	Pinaceae	Tree
76	Poa annua	Poaceae	grass

No.	Scientific Name	Family	Habit
77	Polygonum runcinatum	Polygonaceae	Herb
78	Potentilla indica	Rosaceae	weedy plant
79	Potentilla microphylla	Rosaceae	Herb
80	Prunus cerasoides	Rosaceae	Tree
81	Pteridium aquilinum	Dennstaedtiaceae	Fern
82	Pteris wallichiana	Pteridaceae	Fern
83	Quercus glauca	Fagaceae	Tree
84	Quercus griffithii	Fagaceae	Tree
85	Quercus lamellosa	Fagaceae	Tree
86	Quercus lanata	Fagaceae	Tree
87	Quercus semicarpifolia	Fagaceae	Tree
88	Rhododendron arboreum	Ericaceae	tree
89	Rhus chinensis	Anacardiaceae	Tree
90	Rhus wallichii	Anacardiaceae	Tree
91	Rubus ellipticus	Rosaceae	Shrub
92	Sauraria nepalensis	Saurariceae	Tree
93	Schima wallichii	Theaceae	Tree
94	Selginella	Selaginellaceae	Spikemoss
95	Senecio scandens	Asteraceae	Climber
96	Smilax myrtilus	Smilacaceae	Climber
97	Solanum khasianum	Solanaceae	Herb
98	Sorbus microphylla	Rosaceae	Shrub
99	Swertia chirata	Gentianaceae	Herb
100	Symplocos glomerata	Symplocaceae	Tree/Shrub
101	Symplocos paniculata	Symplocaceae	Shrub
102	Symplocos ramosissima	Symplocaceae	tree/shrub
103	Toricellia tiliifolia	Torricelliaceae	Tree
104	Tupistra sp.	Convallariaceae	Herb
105	Urtica dioica	Urticaceae	Herb
106	Urtica parviflora	Urticaceae	Heb
107	Vaccinium myrtillus	Ericaceae	Shrub
108	Vanda cristata	Orchidaceae	Orchid
109	Viburnum cylindricum	Axodaceae	Shrub
110	Viburnum erubescens	Axodaceae	Shrub
111	Yushinia microphylla	Poaceae	Bamboo
112	Zanthoxylum armatum	Rubiaceae	Tree
113	Zanthoxylum oxyphyllum	Rutaceae	Shrub

Table 2 Wildlife signs recorded in plots

Plot No.	Wildlife species	Sign type	No. of signs
1	Wild pig	resting pl.	1
2	Barking deer	dung	1 clump
7	Barking deer	dung	1 clump
7	Wild pig	rooting	1
8	Wild pig	rooting	1
9	Barking deer	footprint	3
12	Barking deer	dung	1
19	Barking deer	footprint	3
25	Wild pig	rooting	1
30	Wild pig	rooting	1
32	Jungle fowl	scratching	many
33	Sambar	footprint	4
34	Barking deer	spotted	1
37	Wild pig	resting place	1
38	Wild pig	rooting	1
39	Barking deer	footprint	1
44	Wild pig	Rooting	1
45	Wild pig	wallowing	1
46	Wild pig	rooting	1
49	Wild pig	wallowing	1
52	Wild pig	nesting	1
55	Wild pig	rooting	1
60	Wild pig	footprint	1
65	Wild pig	rooting	1
	TOTAL plots		23

TABLE 3: List of Birds recorded during Biodiversity Survey

S/N o	Common Name	Scientific Name	Status in Bhutan	IUCN status
1	Aberrant Bush Warbler	Cettia flavolivacea		LC
2	Ashy Wood Pigeon	Columba pulchricollis		LC
3	Ashy-throated Warbler	Phylloscopus maculipennis		LC
4	Asian Brown Flycatcher	Muscicapa dauurica		LC
5	Barred Cuckoo-dove	Macropygia unchall		LC
6	Black Bulbul	Hypsipetes leucocephalus		LC
7	Black Redstart	Phoenicurus ochruros		LC
8	Black-faced Laughingthrush	Garrulax affinis		LC
9	Black-tailed Crake	Amaurorius bicolor		LC
10	Black-throated Tit	Aegithalos concinnus		LC
11	Blue Whistling Thrush	Myophonus caeruleus		LC
12	Blue-fronted Redstart	Phoenicurus frontalis		LC
13	Blue-throated Barbet	Magalaima asiatica		LC
14	Blyth's Leaf Warbler	Phylloscopus reguloides		LC
15	Brownish-flanked Bush Warbler	Cettia fortipes		LC
16	Chestnut-bellied Rock-thrush	Monticola rufiventris		LC
17	Chestnut-crowned laughingthrush	Garrulax erythrocephalus		LC
18	Chestnut-crowned Warbler	Seicercus castaniceps		LC
19	Chestnut-tailed Minla	Minla strigula		LC
20	Chestnut-tailed Starling	Strunus malabaricus		LC
21	Collared Owlet	Glaucidium brodiei		LC
22	Oriental Scops Owlet	Otus sunia		LC
23	Common Buzzard	Buteo buteo		LC
24	Common Hoopoe	Upupa epops		LC
25	Common Kestrel	Falco tinnunculus		LC
26	Common Myna	Acridotheres tristis		LC
27	Common Quail	Conturnix conturnix		LC
28	Common Tailorbird	Orthotomus sutorius		LC
29	Coral-billed Scimitar-babbler	Pomatorhinus ferruginosus		LC
30	Himalayan cutia	Cutia nipalensis		LC
31	Darjeeling Woodpecker	Dendrocopos darjellensis		LC
32	Dark-throated Thrush	Turdus ruficollis		LC
33	Eurasian Jay	Garrulus glandarius		LC
34	Eurasian Tree Sparrow	Passer montanus		LC
35	Eurasian Treecreeper	Certhia familiaris		LC

S/N o	Common Name	Scientific Name	Status in Bhutan	IUCN status
36	Eurasian Woodcock	Scolopax rusticola		LC
37	Golden-throated Barbet	Magalaima franklinii		LC
38	Great Barbet	Magalaima virens		LC
	Greater Necklaced			
39	Laughingthrush	Garrulax pectoralis		LC
40	Green-backed Tit	Parus monticolus		LC
41	Green-tailed Sunbird	Aethopyga nipalensis		LC
42	Grey Bushchat	Saxicola ferreus		LC
43	Grey Treepie	Dendrocitta formosae		LC
44	Grey Wagtail	Motacilla cinerea		LC
45	Grey-backed Shrike	Lanius tephronotus		LC
46	Grey-headed Canary Flycatcher	Culicicapa ceylonensis		LC
47	Grey-hooded Warbler	Phylloscopus xanthoschisto	os	LC
48	Grey-winged Blackbird	Turdus boulboul		LC
49	Hill Partridge	Arborophila torqueola		LC
50	Hill Prinia	Prinia atrogularis		LC
51	Hoary-throated Barwing	Actinodura nipalensis		LC
52	Hodgson's Redstart	Phoenicurus hodgsoni		LC
53	Kalij Pheasant	Lophura luecomelanos		LC
54	Large Niltava	Niltava grandis		LC
55	Large-billed Crow	Corvus macrorhynchos		LC
56	Lemon-rumped Warbler	Phylloscopus proregulus		LC
57	Lesser necklaced Laughingthrush	Garrulax monileger		LC
58	Little Bunting	Emberiza pusilla		LC
59	Little Forktail	Enicurus scouleri		LC
60	Little-pied Flycatcher	Ficedula westermanni		LC
61	Long-tailed Minivet	Pericrocotus ethologus		LC
62	Long-tailed Shrike	Lanius schach		LC
63	Long-tailed Thrush	Zoothera dixoni		LC
64	Maroon-backed Accentor	Prunella immaculata		LC
65	Mountain Bulbul	Hypsipetes mcclellandii		LC
66	Mountain Hawk-eagle	Nisaetus nipalensis		LC
67	Olive-backed Pipit	Anthus hodgsoni		LC
68	Orange-flanked Bush Robin	Tarsiger cyanurus		LC
69	Oriental Magpie-robin	Copsychus saularis		LC
70	Oriental Turtle Dove	Streptopelia orientalis		LC
71	Plain-backed Thrush	Zoothera mollissima		LC
72	Plumbeous Water Redstart	Rhyacornis fuliginosa		LC

S/N o	Common Name	Scientific Name	Status in Bhutan	IUCN status
73	Pygmy Wren Babbler	Pnoepyga pusilla		LC
74	Red-billed Chough	Pyrrhocorax pyrrhocorax		LC
75	Red-headed Bullfinch	Pyrrhula erythrocephala		LC
76	Red-vented Bulbul	Pycnonotus cafer		LC
77	Rock Pigeon	Columbia livia		LC
78	Rufous-bellied Niltava	Niltava sundara		LC
79	Rufous-breasted Accentor	Prunella strophiata		LC
80	Rufous-capped Babbler	Stachyris ruficeps		LC
81	Rufous-gorgeted Flycatcher	Ficedula strophiata		LC
82	Rufous-necked Hornbill	Aceros nipalensis	Sch-I	V
83	Rufous sibia	Heterophasia capistrata		LC
84	Rufous-vented Yuhina	Yuhina occipitalis		LC
85	Rufous-winged Fulvetta	Alcippe castaneceps		LC
86	Russet Sparrow	Passer rutilans		LC
		Pomatorhinus		
87	Rusty-cheeked Scimitar -babbler	erythrogenys		LC
88	Rusty-flanked Treecreeper	Certhia nipalensis		LC
89	Satyr Tragopan	Tragopan satyra		near Threatened
90	Scaly Thrush	Zoothera dauma		LC
91	Scaly-breasted Munia	Lonchura punctulata		LC
92	Scarlet Minivet	Pericrocotus flammeus		LC
93	Slaty-backed Forktail	Enicurus schistaceus		LC
94	Slender-billed Scimitar Babbler	Xiphirhynchus superciliaris		LC
95	Small Niltava	Nitava macgrigoriae		LC
96	Solitary Snipe	Gallinago solitaria		Lc
97	Speckled Wood Pigeon	Columba hodgsonii		Lc
98	Spotted Forktail	Enicurus maculatus		LC
99	Streak-breasted Scimitar Babbler	Pomatorhinus ruficollis		LC
100	Striated Bulbul	Pycnonotus striatus		LC
101	Striated Laughingthrush	Garrulax striatus		LC
102	Striated Prinia	Prinia crinigera		LC
103	Stripe-throated Yuhina	Yuhina gularis		LC
104	Ultramarine Flycatcher	Ficedula superciliaris		LC
105	Verdicter Flycatcher	Eumyias thalassinus		LC
106	Wallcreeper	Tichodroma muraria		LC
107	Wedge-tailed Green Pigeon	Treron sphenurus		LC
108	Whiskered Yuhina	Yuhina flavicollis		LC
109	Whistler's Warbler	Scicercus whistleri		LC

S/N o	Common Name	Scientific Name	Status in Bhutan	IUCN status
110	White Wagtail	Motacilla alba		LC
111	White-browed Bush Robin	Tarsiger indicus		LC
112	white-browed fulvetta	Alcippe vinipectus		LC
113	White-capped Water Redstart	Chaimarrornis leucocephali	IS	LC
114	White-collared Blackbird	Turdus albocinctus		LC
115	White-throated Fantail	Rhipidura albicollis		LC
116	White-throated Laughingthrush	Garrulax albogularis		LC
117	Yellow-bellied Fantail	Rhipidura hypoxantha		LC
118	Yellow-billed Blue Magpie	Urocissa flavirostris		LC
119	Yellow-rumped Honeyguide	Indicator xanthonotus		near threatened
120	Orange bellied leafbird	Chloropsis hardwickii		LC
121	Nepal Fulvetta	Alcippee nipalensis		LC
122	Orange bellied leafbird	Chloropsis hardwickii		LC
124	Nepal Fulvetta	Alcippee nipalensis		LC

Pictures of the Project site

Photo 1: Section and Interval Poles



Photo 3: Point 15



Photo 5: Point 41



Photo 7: Taktse College

Photo 2: RoW cleared through forest



Photo 4: Point 18



Photo 6: Point 4



Photo 8: Vegetation along RoW





Photo 9: View of National highway and MHEP Camp Photo 10: Community Forest Signboard



Photo 11: Scrub forest along RoW



Photo 12: Scrub forest along RoW



Photo 13: A local farmers house nearby



Photo 15: Forest type





Photo 17: Forest along RoW

Photo 14: local agricultural field nearby



Photo 16: Scrub Forest



Photo 18: View of Mangdechu River