June 2017

IND: Green Energy Corridor and Grid Strengthening Project

(320 kV VSC-HVDC power transmission lines between Pugalur, Tamil Nadu and North Trichur, Kerala)

Annexures 1–5

Prepared by Power Grid Corporation of India Limited for the Asian Development Bank.

This initial environmental examination is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature. Your attention is directed to the "terms of use" section on ADB's website.

In preparing any country program or strategy, financing any project, or by making any designation of or reference to a particular territory or geographic area in this document, the Asian Development Bank does not intend to make any judgments as to the legal or other status of any territory or area.

# ANNEXURE – 1

GUIDELINES ISSUED BY GOVT OF INDIA REGARDING ROW COMPENSATION

## No.3/7/2015-Trans Government of India Ministry of Power Shram Shakti Bhawan Rafi Marg, New Delhi – 110001

## Dated, 15<sup>th</sup> October, 2015

To

- 1. Chief Secretaries/Administrators of all the States/UTs (As per list attached)
- 2. Chairperson, CEA, New Delhi with the request to disseminate the above guidelines to all the stakeholders.
- 3. CMD, PGCIL, Gurgaon.
- 4. CEO, POSOCO, New Delhi.
- 5. Secretary, CERC, New Delhi.
- 6. CMD of State Power Utilities/SEBs

Subject: Guidelines for payment of compensation towards damages in regard to Right of Way for transmission lines.

During the Power Ministers Conference held on April 9-10, 2015 at Guwahati with States/UTs, it has, *inter alia*, been decided to constitute a Committee under the chairmanship of Special Secretary, Ministry of Power to analyse the issues related to Right of Way for laying of transmission lines in the country and to suggest a uniform methodology for payment of compensation on this count. Subsequently, this Ministry had constituted a Committee with representatives from various State Governments and others. The Committee held several meetings to obtain the views of State Governments on the issue and submitted its Report along with the recommendations (copy of the Report is at **Annex-1**).

2. The Recommendations made by the Committee are hereby formulated in the form of following guidelines for determining the compensation towards "damages" as stipulated in section 67 and 68 of the Electricity Act, 2003 read with Section 10 and 16 of Indian Telegraph Act, 1885 which will be in addition to the compensation towards normal crop and tree damages. This amount will be payable only for transmission lines supported by a tower base of 66 KV and above, and not for sub-transmission and distribution lines below 66 KV:-

 Compensation @ 85% of land value as determined by District Magistrate or any other authority based on Circle rate/ Guideline value/ Stamp Act rates for tower base area (between four legs) impacted severely due to installation of tower/pylon structure;

-1-

- (ii) Compensation towards diminution of land value in the width of Right of Way (RoW) Corridor due to laying of transmission line and imposing certain restriction would be decided by the States as per categorization/type of land in different places of States, subject to a maximum of 15% of land value as determined based on Circle rate/ Guideline value/ Stamp Act rates;
- (iii) In areas where land owner/owners have been offered/ accepted alternate mode of compensation by concerned corporation/ Municipality under Transfer Development Rights (TDR) policy of State, the licensee /Utility shall deposit compensation amount as per (i) & (ii) above with the concerned Corporation/ Municipality/ Local Body or the State Government.
- (iv) For this purpose, the width of RoW corridor shall not be more than that prescribed in the table at Annex-2and shall not be less than the width directly below the conductors.

3. Necessary action may kindly be taken accordingly. These guidelines may not only facilitate an early resolution of RoW issues and also facilitate completion of the vital transmission lines through active support of State/ UT administration.

4. All the States/UTs etc. are requested to take suitable decision regarding adoption of the guidelinesconsidering that acquisition of land is a State subject.

Yours faithfully,

ydis

(Jyoti Arora) Joint Secretary (Trans.) Tele: 011-2371 0389

Copy, along with enclosure, forwarded to the following:

- 1. Secretaries of Government of India (Infrastructure Ministries/Deptt including MoEF As per attached list)
- Prime Minister's Office (Kind Attn: Shri Nripendra Mishra, Principal Secretary to PM).
- Technical Director, NIC, Ministry of Power with the request to host on the website of Ministry of Power.

-2-

Copy to PS to Hon'ble MoSP (IC) / Secretary (Power) / AS (BNS) / AS (BPP) / All Joint Secretaries/EA/ All Directors/DSs, Ministry of Power.

# Report of the Committee for payment of compensation in regard to Right of Way (RoW) for transmission lines

## 1.0 Background:

٤

1.1 The Transmission Projects in the country are implemented by the licensee in accordance with the provisions of the Electricity Act, 2003. The compensation towards "damages" during implementation of such projects is governed by Section 67 & 68 of the Electricity Act read with Section 10 & 16 of the Indian Telegraph Act, 1885. The present stipulations provide for compensation towards all damages without acquisition of land which are assessed/ reviewed by the Revenue Authorities. However, there is no clear definition of the term "damages", nor are there any guidelines in this regard.

1.2 For laying electricity transmission lines, licensee erects towers at intervals of about 400 m. and conductors are strung on these towers maintaining a safe height depending on the voltage and other geographical parameters. Thus, typical transmission lines have following two kinds of impact:

- Tower base area which is more or less completely lost or loses its productivity due to severe restriction an access;
- (ii) Corridor of land underneath strung conductor between two towers may be adversely affected by imposition of restriction on its usage.

1.3 The maximum width of RoW corridor is calculated on the basis of tower design, span, and wind speed, maximum sag of conductor and its swing plus other requirement of electric safety. The requirement of ROW for different voltage types under standard conditions is as follows:

| Transmission Voltage                     | Width of Right of Way (in<br>Meters) |  |
|--|--------------------------------------|--|
| 66 kV                                    | 18                                   |  |
| 110 kV                                   | 22                                   |  |
| 132 kV                                   | 27                                   |  |
| 220 kV                                   | 35                                   |  |
| 400 kV S/C                               | 46                                   |  |
| 400 kV D/C                               | 46                                   |  |
| +/-500 kV HVDC                           | 52                                   |  |
| 765 kV S/C<br>(with delta configuration) | 64                                   |  |
| 765 kV D/C                               | 67                                   |  |
| +/-800 kV HVDC                           | 69                                   |  |
| 1200 kV                                  | 89                                   |  |

## ROW width for different voltage line\*

\* Width of Right of Way is as per the MoEF guidelines dated 5.5.2014 (Annex-A).

-3-

1.4 The Telegraph Act provides for compensation towards damages (without acquisition) while placing the tower and stringing the conductor. The local authorities/ District Magistrates have been provided Power under Section 16 (1) of the Telegraphic Act for adjudication and fixing the compensation. The provisions of the Electricity Act and Telegraph Act in respect of compensation are as follows:

#### A. The Electricity Act, 2003, Part-VIII, Section 67 & 68

#### Section 67 (3 & 4):

- "(3) A licensee shall, in exercise of any of the powers conferred by or under this section and the rules made thereunder, cause as little damage, detriment and inconvenience as may be, **and shall make full compensation for any damage, detriment or inconvenience** caused by him or by any one employed by him.
  - (4) Where any difference or dispute [including amount of compensation under sub-section (3)] arises under this section, the matter shall be determined by the Appropriate Commission.

### Section 68 (5 & 6):

- (5) Where any tree standing or lying near an overhead line or where any structure or other object which has been placed or has fallen near an overhead line subsequent to the placing of such line, interrupts or interferes with, or is likely to interrupt or interfere with, the conveyance or transmission of electricity or to interrupt or interfere with, the conveyance or transmission of electricity or the accessibility of any works. an Executive Magistrate or authority specified by the Appropriate Government may, on the application of the licensee, cause the tree, structure or object to be removed or otherwise dealt with as he or it thinks fit.
- (6) When disposing of an application under sub-section (5), an Executive Magistrate or authority specified under that sub-section shall, in the case of any tree in existence before the placing of the overhead line, award to the person interested in the tree such compensation as he thinks reasonable, and such person may recover the same from the licensee.

Explanation. - For purposes of this section, the expression tree shall be deemed to include any shrub, hedge, jungle growth or other plant."

### B. The Indian Telegraph Act, 1885, Part-III, Section 10 ("C"):

- "Section 10 The telegraph authority may, from time to time, place and maintain a telegraph line under, over, along, or across, and posts in or upon any immovable property, Provided that –
- a) the telegraph authority shall not exercise the powers conferred by this section except for the purposes of a telegraph established or maintained by the [Central Government], or to be so established or maintained;
- b) the [Central Government] shall not acquire any right other than that of user only in the property under, over, along, across in or upon which the telegraph authority places any telegraph line or post; and
- except as hereinafter provided, the telegraph authority shall not exercise those powers in respect of any property vested in or under the control or management of any local authority, without the permission of that authority; and
- d) in the exercise of the powers conferred by this section, the telegraph authority shall do as little damage as possible, and, when it has exercised those powers in respect of any property other than that referred to in clause (c), shall pay full compensation to all persons interested for any damage sustained by them by reason of the exercise of those powers."

1.5 As the "damages" have not been defined in the said Acts, licensees, in past, used to pay compensation for the damages caused to crops/ trees and structures. However, the land owners/farmers are now demanding the cost of land for tower base as well as cost diminution of land value in the corridor area due to laying of transmission

line on their land. The present provisions of the Act/ Rules do not provide for any set procedure for calculation of such compensation. In the absence of clarity and notified procedures, the provisions of existing Acts are being differently interpreted by concerned DC/ Revenue Authorities that are also at variance with each other even among neighboring districts which is resulting in the resistance by the farmers causing unwarranted delay in the project implementation. Presently many lines in the States of Maharashtra, Western U.P., Karnataka, Kerala, Andhra, Jharkhand etc. are held up due to resistance by land owners demanding enhanced compensation.

### 2.0 Constitution of the Committee:

2.1 The matter was deliberated during the Power Ministers' Conference on 9-10 April 2015 at Guwahati and a Committee under the chairmanship of Special Secretary, Ministry of Power was constituted vide order No. 3/7/2015-Trans dated 15<sup>th</sup> April 2015 to analyse the issues relating to Right of Way for laying transmission lines in the country and to suggest a uniform methodology for payment of compensation on this account. The composition of the Committee is given below:

- i. Shri R. N. Choubey, Special Secretary, Ministry of Power Chairman
- ii. Chairperson, Central Electricity Authority
- iii. Principal Secretary/Secretary (Energy), Madhya Pradesh
- iv. Principal Secretary/Secretary (Energy), U.P.
- v. Principal Secretary/Secretary (Energy), Maharashtra,
- vi. Principal Secretary/Secretary (Energy), Karnataka,
- vii. Principal Secretary/Secretary (Energy), Kerala,
- viii. Jt. Secretary (Trans.), Ministry of Power
- ix. CMD/Dir(Projects), POWERGRID
- x. Shri K. K. Arya, CE (SP&PA), CEA Convener & Member Secretary.

The notification of the Committee is at Annex-I.

## 3. Proceedings of the Committee:

3.1 The first meeting of the Committee was held on 20.04.2015. During the meeting Powergrid and States mentioned that the difficulties were being faced in construction of transmission lines in more or less all the states due to severe resistance being posed by the land owners/ farmers with the demand of higher compensation including demand for compensation for the diminution value of the land below towers and under

- 4 -

the line corridor. Powergrid also informed about the opinion of Attorney General of India taken by them, which states that the land underneath the legs of the tower is permanently lost by the owner and that the land under the corridor can be conveniently used but with certain restrictions and compensation for such diminution in land value for the line corridor is also payable to land owners. All the states were also of the view that compensation against the land diminution should be paid to the land owners. Most of the participants suggested that a uniform policy should be in place at the central level in terms of fixed percentages of market value of the land under transmission towers and under corridor, however, some of the states were of the view that this should be left to the concerned state to formulate the policy. 4

3.2 During the meeting, two views were emerged as under;

- (i) 100 % compensation for land should be paid for tower footing and 10% for corridor under the line.
- (ii) Policy should not be changed as state authorities are solving the compensation issues and it will also affect the financial viability of transmission projects.

The minutes of the meeting are at Annex-II.

3.3 The second meeting was held on 30.04.2015. Director (Projects), POWERGRID presented a detailed presentation including Legal & Regulatory framework about the compensation, policies of various States as well as the brief on the order of various Courts on compensation issues and various other order of different DM/DC regarding compensation and interpretation of present provisions. Copy of the presentation is at **Annex-III**. The summary of AG's opinion on legal position and coverage/inclusions of various aspects while deciding compensation including land value diminution was also informed by POWERGRID.

3.4 POWERGRID proposal regarding full compensation for tower base and at least 10% for RoW Corridor was also discussed in detail. The private entities M/s. Sterlite and Essel Infra also emphasized that there should be a standard norms for calculating compensation for transmission line and it should also be revised, reviewed periodically for its regular updation keeping in mind the market rate. M/s Sterlite also suggested that instead of land cost, corridor compensation per km may be fixed based on voltage of line. Chairperson, CEA informed that possibility of reduction in RoW width is minimal as it has already been fixed based on the required Electricity Safety norms.

3.5 The Committee opined that payment of full value of land cost, tower base seems justified due to severe restriction put in by placing of tower which heavily impact the productivity/use of land area falling below tower base. Principal Secretary (Power), U.P however expressed his reservation on 100% cost without acquisition may be a difficult proposition due to ongoing complication regarding compensation under new Land Acquisition Act. Principal Secretary (Power), U.P and Principal Secretary (Power), M.P expressed their apprehension about the proposal of RoW Corridor payment as in their view such payment may also hamper the implementation of distribution lines and may also put additional financial burden on distribution company. Moreover, they were also of the opinion that we may not be able to resolve compensation issue by paying 10% as in all probabilities the farmers/land owners will demand more as has already been stipulated in the different State policies and DCs orders.

3.6 Due to sensitivity of the proposal and its implementation by the different State Governments, it was decided that this issue may also be discussed during the forthcoming Power Secretaries meetings for wider consultation and acceptance. Minutes of the meeting are at **Annex-IV**.

3.7 The Committee further consulted many States to obtain their views on the issue during the Review, Planning and Monitoring (RPM) meeting held on 11.5.2015 at Delhi, which was attended by Principle Secretaries/ Secretaries (Energy) of various States. The issues related to compensation and deliberations held during last 2 meetings were informed to the participants and they were asked to give their opinion on whether Committee should recommend a minimum uniform standard compensation norm for transmission line RoW for whole country or not. The different States present in the meeting suggested following:

i. West Bengal: The state was not very keen on providing compensation for ROW corridor however they suggested for tower base 50 % of the land cost due to restriction and 20 % for corridor. However it should be left to state for final decision.

- ii. Jammu & Kashmir: It informed that because of the special provision in the state they were already acquiring tower base land by paying full compensation as per the land acquisition norm and accordingly state be granted power on such issue.
- iii. Madhya Pradesh: It also suggested that such decision be left to state government to decide.
- iv. Uttar Pradesh: The state was ready to pay the compensation as decided by the district authority and hence suggested there should be a mechanism so that such compensation be pass through as project cost.
- v. Kerala: Kerala was in favour of uniform compensation norms. It also suggested that beyond such uniform rate, it should be left to state who would also bear the cost if additional compensation is paid.
- vi. **Bihar:** The State was also in favor of compensation for tower base and corridor. However, it suggested that decision on deciding percentage be left on state for finalization.
- vii. **Karnataka:** It was also in favor of such compensation, however it also suggested that the finalization of percentage cost may be left at the discretion of the state.
- viii. Andhra Pradesh: The State was of the view that compensation for 100 % land value for tower base be paid to the landowner but no compensation for corridor should be given. It also suggested that such compensation should not be made applicable to line below 33 KV.
- ix. Jharkhand: The State was also in favor of uniform standard rate at generic level but suggested that state must be authorized for finalizing the quantum of such compensation.
- x. Odisha: The State was also in favor of uniform standard rate. However, it suggested that district authority must be authorized for finalizing such compensation.
- xi. Uttarakhand: It also wanted a uniform rate for such compensation considering revenue rate as basis and suggested 80% land value for tower base but no compensation for corridor as agricultural practices take place without any hindrance. However, they suggested that 5% cost of land for corridor for lines below 33 KV be included as these lines put severe restriction on agricultural practices.
- xii. **Meghalaya:** it suggested that they will come back after consulting other stakeholders and senior officials.
- xiii. **Gujarat:** it favors that certain minimum standard should be defined and state be given power to decide its detailing and these should not be any compensation for corridor. Such compensation should not be applicable for distribution line.

-7-

- xiv. **Punjab:** The State was in agreement for compensation towards tower base and line corridor and wanted that certain standard uniform norms be made for such compensation.
- xv. Nagaland: It informed that they will come back later on after consulting all concerned.
- xvi. **Maharashtra:** It also favors that it should be left to the discretion of the state and such compensation be made part of project cost.
- xvii. **Telangana:** It stated that they are in favor of 85% land value for tower base but no compensation for corridor.

3.8 The views of various states have been classified in four categories and are indicated below:

| Category   | Name of States  |  |  |
|--|---|--|--|
| Category-I: States agreeing for<br>payment of compensation for tower<br>base and part compensation for<br>RoW corridor | Odisha <b>(#)</b> , Maharashtra <b>(#)</b> , Uttarakhand,<br>Punjab<br>West Bengal, Bihar, Karnataka, Kerala,<br>Jharkhand, |  |  |
| Category-II: States agreeing for<br>payment of compensation for tower<br>base and no compensation for RoW<br>corridor  | Telangana, Andhra Pradesh   |  |  |
| Category-III: States suggesting that decision should be left with State Govt to decide                                 | Madhya Pradesh, Gujarat, Uttar<br>Pradesh.  |  |  |
| Category-IV: States to inform later  | Meghalaya, Nagaland   |  |  |

(#) States agreed in-principle but want final decision to be left on them.

3.9 The third meeting of the Committee was held on 1<sup>st</sup> June 2015 and the issue & opinions of various states were deliberated in detail. Based on detailed deliberations, AG's Opinion and views of the states on the issue of RoW compensation and its modalities the committee finalized its recommendations.

## 4.0 Recommendations:

The GoI may issue following guidelines for determining the compensation payable towards "damages" as stipulated in Indian Telegraph Act which will be in addition to the compensation towards normal crop and tree damages. This amount will be payable only

- 8-

for transmission Lines of 66 kV and above, and not for sub-transmission and distribution lines below 66 kV:

- i. Compensation @ 85% of land value as determined by District Magistrate or any other authority based on Circle rate/ Guideline value/ Stamp Act rates for tower base area (between four legs) impacted severely due to installation of tower/pylon structure;
- ii. Compensation towards diminution of land value in the width of RoW Corridor due to laying of transmission line and imposing certain restriction would be decided by the States as per categorization/type of land in different places of States, subject to a maximum of 15% of land value as determined based on Circle rate/ Guideline value/ Stamp Act rates;
- iii. In areas where land owner/owners have been offered/accepted alternate mode of compensation by concerned corporation/ Municipality under Transfer Development Rights (TDR) policy of State, the licensee /Utility shall deposit compensation amount as per (i) & (ii) above with the concerned Corporation/ Municipality/ Local Body or the State Government.
- iv. For this purpose, the width of RoW corridor shall not be more than that prescribed in para 1.3 above, and shall not be less than the width directly below the conductors.

**IN WITNESS WHEREOF**, the undersigned being duly authorized thereto have signed this Report of the Committee for payment of compensation in regard to Right of Way (RoW) for transmission lines.

melly

(R.N.Choubey) Chairman of the Committee Former Special Secretary, Ministry of Power.

(I.C Keshari)

Member of the Committee Principal Secretary (Energy) Government of Madya Pradesh

(P Ravi Kumar) Member of the Committee Secretary (Energy) Government of Karnataka.

(Jyoti Arora) Member of the Committee Joint Secretary (Trans.) Ministry of Power.

(Sanjay Agarwal) mber of the Committe

Member of the Committee Principal Secretary (Energy) Government of Uttar Pradesh.

asuby

(Shivasankar) Member of the Committee Secretary (Power) Government of Kerala.

Maynin Smil'

(Major Singh) Member of the Committee Chairperson, Central Electricity Authority.

Almelle

(Mukesh Khullar) Member of the Committee Principal Secretary (Energy) Government of Maharashtra.

(1.8. Jha)

Member of the Committee Director (Projects) Power Grid Corporatio of India Limited.

### F. No. 7-25/ 2012-FC Government of India Ministry of Environment and Forests (FC Division)

Paryavaran Bhawan, CGO Complex, Lodhi Road, New Delhi - 110 510 Dated: 5<sup>th</sup> May, 2014

То

## The Principal Secretary (Forests), All State / Union Territory Governments

Sub: Guidelines for diversion of forest land for non-forest purposes under the Forest (Conservation) Act, 1980- Guidelines for laying transmission lines through forest areas - *reg*.

Sir,

I am directed to say that the Hon'ble National Green Tribunal in their Order dated 7<sup>th</sup> March 2012 in the Appeal No. 10 of 2012 in the matter of Janajagarithi Samiti (Regd.) versus Union of India and Others directed this Ministry to take steps and notify the detailed fresh guidelines for laying transmission lines through forest area, incorporating necessary changes to mitigate the difficulties which arise during granting forest clearance.

Accordingly, this Ministry in consultation with the Central Electricity Authority formulated revised guidelines for laying transmission lines through forest areas. A copy of the same is enclosed.

Yours faithfully,

Encl.: As above.

057057224 (H.C. Chaudhary)

Assistant Inspector General of Forests

Copy along with a copy of the said guidelines to:-

- 1. Prime Minister's Office (Kind attn.: Shri Santosh D. Vaidya, Director).
- 2. Secretary, Ministry of Power, Government of India, Shram Shakti Bhawan, New Delhi.
- 3. Principal Chief Conservator of Forests, all State/UT Governments.
- Nodal Officer, the Forest (Conservation) Act, 1980, all State/UT Governments.
- All Regional Offices, Ministry of Environment & Forests (MoEF), Government of India (GoI).
- 6. Joint Secretary in-charge, Impact Assessment Division, MoEF, GoI
- All Assistant Inspector General of Forests/ Director in the Forest Conservation Division, MoEF, GoI.

## 8. / Director R.O. (HQ), MoEF, GoI.

9: Sr. Director (Technical), National Informatics Centre (NIC), MoEF with a request to place a copy of the letter on website of this Ministry.

10. Sr. PPS to the Secretary, Environment and Forests.

11. Sr. PPS to the Director General of Forests & Special Secretary, MoEF.

12. Sr. PPS to the Addl. Director General of Forests (Forest Conservation), MoEF.

13. PS to the Inspector General of Forests (Forest Conservation), MoEF.

14. Guard File.

onorwing (H.C. Chaudhary) Assistant Inspector General of Forests

2

# GUIDELINES FOR LAYING TRANSMISSION LINES THROUGH FOREST AREAS

- Where routing of transmission lines through the forest areas cannot be avoided, these should be aligned in such a way that it involves the least amount of tree cutting
- As far as possible, the route alignment through forest areas should not have any line deviation.
- 3. (i) The width of right of way for the transmission lines on forest land shall be as follows:

| Transmission Voltage                  | Width of Right of Way<br>(Meter) |  |
|---------------------------------------|----------------------------------|--|
| 11kV                                  | 7                                |  |
| 33 kV                                 | 15                               |  |
| 66 kV                                 | 18                               |  |
| 110 kV                                | 22                               |  |
| 132 kV                                | 27                               |  |
| 220 kV                                | 35                               |  |
| 400 kV S/C                            | 46                               |  |
| 400 kV D/C                            | 46                               |  |
| +/- 500 kV HVDC                       | . 52                             |  |
| 765 kV S/C (with delta configuration) | 64                               |  |
| 765 kV D/C                            | 67                               |  |
| +/- 800 kV HVDC                       | . 69                             |  |
| 1200 kV                               | 89                               |  |

- In forest areas, only vertical delta configuration of 400 kV S/C and delta configuration of 765 kV S/C shall be permitted.
- 4. (i) Below each conductor or conductor bundle, following width clearance would be permitted for stringing purpose:

| Transmission line with<br>conductor bundle | Width clearance below<br>each conductor or<br>conductor bundle<br>(meter) |  |
|--|---|--|
| Upto 400kV twin bundle                     | 3   |  |

or anona-

9-C

.....

| 400 kV triple bundle                                | 5  |
|---|----|
| 400 kV /+/- 500 kV HVDC<br>/765 kV Quadruple bundle | 7  |
| +/- 800 kV HVDC / 765 kV<br>hexagonal bundle        | 10 |

(ii)

The trees on such strips would have to be felled but after stringing work is completed, natural regeneration will be allowed to come up. Felling/ pollarding/ pruning of trees will be done with the permission of the local forest officer wherever necessary to maintain the electrical clearance. One outer strip shall be left clear to permit maintenance of the transmission line.

2

- (iii) During construction of transmission line, pollarding/ pruning of trees located outside the above width of the strips, whose branches/ parts infringe with conductor stringing, shall be permitted to the extent necessary, as may be decided by local forest officer.
- (iv) Pruning of trees for taking construction/stringing equipments through existing approach/access routes in forest areas shall also be permitted to the extent necessary, as may be decided by local forest officer. Construction of new approach/access route will however, require prior approval under the Act.

| (v) | In the remaining width of right of way trees will be felled or lopped to the exten | t |
|-----|--|---|
| × / | required, for preventing electrical hazards by maintaining the following:          |   |

| Transmission<br>Voltage | Minimum clearance between<br>conductor and trees (Meters) |  |
|-------------------------|---|--|
| 11 kV                   | 2.6   |  |
| 33 kV                   | 2.8   |  |
| 66 kV <sup>.</sup>      | 3.4   |  |
| 110 kV                  | 3.7   |  |
| 132 kV                  | 4.0   |  |
| 220 kV                  | 4.6   |  |
| 400 kV                  | 5.5   |  |
| +/- 500 kV HVDC         | 7.4   |  |
| 765 kV                  | 9.0   |  |
| +/- 800 kV HVDC         | 10.6  |  |
| 1200 kV                 | . 13.0  |  |

(vi)

The maximum sag and swing of the conductors are to be kept in view while

710500000

# 9-D

working out the minimum clearance mentioned as above.

- (vii) To avoid any hazard, felling/cutting/pruning of those trees which because of their height /location may fall on conductors shall also be permitted, as may be decided by local forest office.
- (viii) In the case of transmission lines to be constructed in hilly areas, where adequate clearance is already available, trees will not be cut except those minimum required to be cut for stringing of conductors.
- (ix) In case of transmission lines passing through National Parks, Wildlife Sanctuaries and Wildlife Corridors, insulated conductors shall only be used to prevent electrocution of animals.
- 5. Where the forest growth consists of coconut groves or similar tall trees, widths of right of way greater than those indicated at Sl. No.3 may be permitted in consultation with CEA.

\*\*\*\*\*

רומונטונט אר

3

.

Annex-I

### No.3/7/2015-Trans Government of India Ministry of Power Shram Shakti Bhawan, Rafi Marg. New Delhi-110001

Dated, 15th April, 2015

To.

As per distribution list.

Sir.

Subject - Constitution of the Committee for finalization of compensation in regard to Right of Way for transmission lines.

I am directed to inform that during the Power Ministers' Conference held on 9th and 10th April, 2015 at Guwahati with States/UTs. it has inter alia been decided to constitute a Committee under the chairmanship of Shri R.N.Choubey, Special Secretary, Ministry of Power to analyse the issues relating to Right of Way for laying of transmission lines in the country and to suggest a uniform methodology for payment of compensation on this account.

2 Accordingly, a Committee is hereby constituted with the following composition:-

- 1. Shri R.N. Choubey, Special Secretary, Ministry of Power Chairman
- 2. Chairperson, Central Electricity Authority.
- 3. Principal Secretary/ Secretary (Energy), Madhya Pradesh.
- 4. Secretary/ Principal Secretary (Energy), U.P.
- 5. Secretary/Principal Secretary (Energy), Maharashtra
- 6. Secretary/Principal Secretary (Energy), Karnataka
- 7. Secretary/Principal Secretary (Energy), Kerala
- 8. Joint Secretary (Trans), Ministry of Power
- 9. CMD/Director (Projects), PGCIL.
- 10. Shri K.K.Arya, Chief Engineer (SP&PA), CEA Convener & Member Secretary

3. Representative from EPTA (Electric Power Transmission Association) may also be called as a special invitee as and when required.

The Committee shall meet once in a week and submit the report within a month. The first 4. meeting of the Committee shall be held at 3.00 pm on 20.4.2015. You are, therefore, requested to attend the meeting in NPMC Room 2nd Floor, Shram Shakti Bhavan, New Delhi.

> Jydi fin (Jyoti Arora) Joint Secretary (Trans) Tele: 011-2371 0389

To

- Chairperson, Central Electricity Authority, New Delhi
  Principal Secretary/ Secretary (Energy), Madhya Pradesh.
- 3. Principal Secretary/ Secretary (Energy), U.P.
- 4. Principal Secretary/ Secretary (Energy), Maharashtra
- 5. Principal Secretary/ Secretary (Energy). Karnataka
- 6. Principal Secretary/ Secretary (Energy). Kerala
- 7. CMD/Director (Projects), PGCIL.
- 8. Shri K.K.Arya, Chief Engineer, Chief Engineer (SP&PA), CEA. New Delhi.

Copy to Sr PPS to SS (RNC)/ JS(Trans) / Director (Trans)/ US (Trans).

-10 -

# ANNEXURE – 2

# TREE / CROP COMPENSATION PROCEDURE

# TREE AND CROP COMPENSATION PROCEDURES

In exercise of the powers vested with Power Grid Corporation of India Limited (POWERGRID) under Indian telegraph Act'1885, part 3, section 10 to 19 conferred under section 164 of the Electricity Act 2003 through Gazette by India, extra ordinary dated 24<sup>th</sup> Dec. 2003, has the authority to place and maintain transmission lines under over along or across and posts in or upon, any immoveable property. As per the provisions of Indian Telegraph Act1885 Part III Section 10 (b) which prohibits acquisition of any rights other than that of use only, land for tower and right of way is not acquired and agricultural activities are allowed to continue. However, as per clause 10 (d) of same act stipulates that the user agency shall pay full compensation to all interested for any damages sustained during the execution of said work. Accordingly, POWERGRID pays compensation to land owners towards damages if any to trees or crop during implementation of transmission project as well as during Operation and maintenance phase. The procedure followed for such compensation is as follows:

POWERGRID follows the principle of avoidance, minimization and mitigation in the construction of line in agricultural field having crop due to inherent flexibility in phasing the construction activity and tries to defer construction in cropped area to facilitate crop harvesting. However, if it is unavoidable and is likely to affect project schedule, compensation is given at market rate for standing crops. All efforts are also taken to minimize the crop damage to the extent possible in such cases. As regards trees coming in the Right of Way (RoW) following procedure is adopted for enumeration:

- All the trees which are coming within the clearance belt of ROW on either side of the center line are identified and marked/numbered from one AP to the other and documented.
- ii) Type, Girth (Measured 1 m. above ground level), approximate height o the tree is also noted for each tree
- iii) Trees belonging o Govt., Forest, Highways and other local bodies may be separately noted down or timely follow up with the concerned authorities for inspection and removal.
- iv) Cashew, Guava, Lemon and other hybrid trees which are not of tall growing nature are not marked for cutting since these trees can be crossed using standard tower extensions if required.

A notice under Indian Telegraph Act is served to the land owners informing that the proposed transmission line is being routed through the property of the individual concerned. The notice shall contain the particulars of the land, ownership details and the details of the trees/crops inevitability likely to be damaged during the course of the construction of the proposed transmission line and acknowledgement received from land owner. A copy of said notice is further issued to the Revenue Officer, who has been authorized by the State Govt. for the purpose of assessment/valuation and disbursement of compensation to the affected parties.

The revenue officer shall further issue a notice of intimation to the concerned land owner and inspect the site to verify the documents related to the proof of ownership and a detailed Mahazar is prepared for the identified trees and crops inevitability damaged during the course of the construction. For assessing the true value of timber yielding trees help of forest officials is taken and for fruit bearing trees help of Horticulture department is taken.

The Mahazar shall contain the land owner details type of tree/crop, its present age, variety, yielding pattern etc. and the same is prepared at site in the presence of the land owner. These Mahazars are further compiled and a random verification is conducted by the concerned District Collector OR his authorized representative in order to ascertain the assessment carried out by the revenue office is genuine and correct. After this process the District collector issues a tree cutting permit to Power Grid Corporation to enable removal / damage to the standing tree/crop identified in the line corridor.

Once the tree/crop is removed / damaged, POWERGRID shall issue a tree cutting/crop damaged notice to the land owner with a copy to the Revenue Officer to process the compensation payment. Based on the above the compensation payment is generated by means of a computerized programme developed by the National Informatics Center exclusively for this purpose. The detailed Valuation statement thus generated using this programme is verified at various levels and approval of payment of compensation is accorded by the concerned District Collectors.

On approval of compensation, the revenue officer shall further intimate the amount payable to the different land owners and POWERGRID arranges the payment by way of

Demand Draft to the affected parties. The payment is further disbursed at the local village office after due verification of the documents in presence of other witnesses.

# Procedure exclusively followed in Kerala State:

Due to typical demography of Kerala state and presence of several orchards of Coconut and Rubber, State government in consultation with Kerala State Electricity Board (KSEB) have devised a formula for arriving the compensation which is as follows:

# Compensation = yield X constant factor X average market value X future age.

The constant factor is to arrive the net return component for the particular variety of tree in line with the annuity ratio slab prescribed for the balance life of the tree. A sample calculation sheet using the said formula to arrive at compensation towards trees / crop is enclosed for ready reference.

Another measure adopted in Kerala to expedite assessment and disbursement by POWERGRID is to appoint an Special Revenue Officer and associated staff on deputation from State Government exclusively for the project under execution. This has helped in timely assessment and distribution of compensation amount to affected farmer. Moreover, it has further contributed in simplifying the process as affected farmer need not to visit revenue official again and again and his case is processed at site quickly.

## **TREE / CROP COMPENSATION PROCESS**





# SAFETY PLAN

# SAFETY PLAN

# 13. FORM OF SAFETY PLAN TO BE SUBMITTED BY THE CONTRACTOR WITHIN SIXTY DAYS OF AWARD OF CONTRACT

## [TO BE EXECUTED ON A NON JUDICIAL STAMP PAPER WORTH RS. TWENTY ONLY]

## SAFETY PLAN

NOW THEREFORE, the Contractor undertakes to execute the Contract as per the safety plan as follows:

- 1. THAT the Contractor shall execute the works as per provisions of Bidding Documents including those in regard to Safety Precautions / provisions as per statutory requirements.
- 2. THAT the Contractor shall execute the works in a well planned manner from the commencement of Contract as per agreed mile stones of work completion schedule so that planning and execution of construction works goes smoothly and consistently through out the contract duration without handling pressure in last quarter of the financial year/last months of the Contract and the shall be finalized in association with EMPLOYER Engineer In-charge/Project Manager from time to time as required.
- 3. THAT the Contractor has prepared the safe work procedure for each activity i.e. foundation works including civil works, erection, stringing (as applicable), testing & commissioning, disposal of materials at site / store etc. to be executed at site, which is enclosed at Annexure 1A (SP) for acceptance and approval of Engineer In-charge/Project Manager. The Contractor shall ensure that on approval of the same from Engineer In-charge/Project Manager , the approved copies will be circulated to Employer's personnel at site [Supervisor(s)/Executive(s)] and Contractor's personnel at site [Gang leader, supervisor(s) etc.] in their local language / language understood by gang.

THAT the Contractor has prepared minimum manpower deployment plan, activity wise as stated above, which is enclosed at **Annexure – 1B (SP)** for approval of Engineer In-charge/Project Manager.

- 4. THAT the Contractor shall ensure while executing works that they will deploy minimum 25% of their own experienced work force who are on the permanent roll of the company and balance 75% can be a suitable mixed with the hired gangs / local workers / casual workers if required. The above balance 75% work force should be provided with at least 10 days training by the construction agencies at sites and shall be issued with a certificate. No worker shall be engaged without a valid certificate. Hired gang workers shall also follow safe working procedures and safety norms as is being followed by company's workmen. It should also be ensured by the contractor that certified fitters who are climbing towers / doing stringing operations can be easily identifiable with a system like issue of Badge / Identification cards (ID cards) etc. Colour identification batches should be worn by the workers. Contractor has to ensure that inexperience workers / unskilled workers should not be deployed for skilled job.
- 5. THAT the Contractor's Gang leader / Supervisor / Senior most member available at every construction site shall brief to each worker daily before start of work about safety requirement and warn about imminent dangers and precautions to be taken against the imminent dangers (Daily Safety Drill). This is to be ensured without fail by Contractor and maintain record of each gang about daily safety instructions issued to workers and put up to EMPLOYER site In-charge for his review and record.
- 6. THAT the Contractor shall ensure that working Gangs at site should not be left at the discretion of their Gang Leaders who are generally hired and having little knowledge about safety. Gang leader should be experienced and well versed with the safe working procedures applicable for transmission line/ Sub Station works. In case gang is having Gang leader not on permanent roll of the company then additional Supervisor from company's own roll having thorough knowledge about the works would be deployed so as to percolate safety instructions up to the grass root level in healthy spirits. Contractor has to ensure close supervision while executing critical locations of transmission lines / sub stations and ensures that all safety instructions are in place and are being followed.
- 7. THAT the Contractor shall maintain in healthy and working condition all kind of Equipments / Machineries / Lifting tools / Lifting tackles / Lifting gears / All kind of Ropes including wire ropes / Polypropylene ropes etc. used for Lifting purpose during execution of the project and get them periodically examined and load tested for safe working load in accordance with relevant provisions and requirement of Building & other construction workers Regulation of Employment and Conditions of Services Act and Central Rule 1998, Factories Act 1948, Indian Electricity Act 2003 before start of the project. A register of such examinations and tests shall be properly maintained by the contractor and will be promptly produced as and when desired by the Engineer In-charge/Project Manager or by the person authorised by him. The Contractor has to ensure to give special attention on the formation / condition of eye splices of wire rope slings as per requirement of IS 2762 Specification for wire rope slings and sling legs.

THAT the Contractor has prepared a list of all Lifting machines, lifting Tools / Lifting Tackles / Lifting Gears etc. / All types of ropes and Slings which are subject to safe working load is enclosed at **Annexure – 2 (SP)** for review and approval of Engineer Incharge/Project Manager.

8. THAT the Contractor has to procure sufficient quantity of Personal Protective Equipment (PPE)conforming to Indian / International standards and provide these equipment to every workman at site as per need and to the satisfaction of Engineer-in-charge/Project Manager of EMPLOYER. The Contractor's Site Supervisor/ Project Manager has to ensure that all workmen must use Personal Protective Equipment at site. The Contractor shall also ensure that Industrial Safety helmets are being used by all workmen at site irrespective of their working (at height or on ground). The Contractor shall further ensure use of safety shoes by all ground level workers and canvas shoes for all workers working at height, Rubber Gum Boots for workers working in rainy season and concreting job, Use of Twin Lanyard Full body Safety Harness with attachment of light weight such as aluminium alloy etc. and having features of automatic locking arrangement of snap hook, by all workers working at height for more than three meters and also for horizontal movement on tower shall be ensured by contractor. The Contractor shall not use ordinary half body safety harness at site. The Contractor has to ensure use of Retractable type fall arrestors by workers for ascending / descending on suspension insulator string and other similar works etc., Use of Mobile fall arrestor for ascending / descending from tower by all workers. The contractor has to provide cotton / leather hand gloves as per requirement, Electrical Resistance Hand gloves for operating electrical installations / switches, Face shield for protecting eyes while doing welding works and Dust masks to workers as per requirement. The Contractor will have to take action against the workers not using Personal Protective Equipment at site and those workers shall be asked to rest for that day and also their Salary be deducted for that day. EMPLOYER may issue warning letter to Project Manager of contractor in violation of above norms.

THAT the Contractor shall prepare a detailed list of PPEs, activity wise, to commensurate with manpower deployed, which is enclosed at **Annexure – 3 (SP)** for review and approval of Engineer In-charge/Project Manager. It shall also be ensured that the sample of these equipment shall be got approved from EMPLOYER supervisory staff before being distributed to workers. The contractor shall submit relevant test certificates as per IS / International Standard as applicable to PPEs used during execution of work. All the PPE's to be distributed to the workers shall be checked by EMPLOYER supervisory staff before its usage.

The Contractor also agrees for addition / modification to the list of PPE, if any, as advised by Engineer In-Charge/Project Manager.

 THAT the Contractor shall procure, if required sufficient quantity of Earthing Equipment / Earthing Devices complying with requirements of relevant IEC standards (Generally IECs standards for Earthing Equipments / Earthing Devices are – 855, 1230, 1235 etc.) and to the satisfaction of Engineer In-Charge/ Project Manager and contractor to ensures to maintained them in healthy condition.

THAT the Contractor has prepared / worked out minimum number of healthy Earthing Equipments with Earthing lead confirming to relevant IS / European standards per gang wise during stringing activity/as per requirement, which is enclosed herewith at **Annexure** – **4 (SP)** for review and acceptance of Engineer In-Charge/ Project Manager prior to execution of work.

- 10. THAT the Contractor shall provide communication facilities i.e. Walky Talkie / Mobile Phone, Display of Flags / whistles for easy communication among workers during Tower erection / stringing activity, as per requirement.
- 11. THAT the Contractor undertakes to deploy qualified safety personnel responsible for safety as per requirements of Employer/Statutory Authorities.

THAT the Contractor employing more than 250 workmen whether temporary, casual, probationer, regular or permanent or on contract, shall employ at least one full time officer exclusively as qualified safety officer having diploma in safety to supervise safety aspects of the equipment and workmen who will coordinate with Engineer In-charge /Project Manager/Safety Coordinator of the Employer. In case of work being carried out through sub contractors the sub – contractor's workmen / employees will also be considered as the contractor's employees / workmen for the above purpose. If the number of workers are less than 250 then one qualified safety officer is to be deployed for each contract. He will report directly to his head of organization and not the Project Manager of contractor He shall also not be assigned any other work except assigning the work of safety. The curriculum vitae of such person shall be got cleared from EMPLOYER Project Manager / Construction staff.

The name and address of such safety officers of contractor will be promptly informed in writing to Engineer In-charge with a copy to safety officer - In-charge before start of work or immediately after any change of the incumbent is made during the currency of the contract. The list is enclosed at **Annexure – 5A (SP)**.

THAT the Contractor has also prepared a list including details of Explosive Operator (if required), Safety officer / Safety supervisor / nominated person for safety for each erection / stringing gang, list of personnel trained in First Aid Techniques as well as copy of organisation structure of the Contractor in regard to safety. The list is enclosed at **Annexure – 5B (SP)**.

- 12. The Project Manager shall have the right at his sole discretion to stop the work, if in his opinion the work is being carried out in such a way that it may cause accidents and endanger the safety of the persons and/or property, and/or equipment. In such cases, the Contractor shall be informed in writing about the nature of hazards and possible injury/accident and he shall comply to remove shortcomings promptly. The Contractor after stopping the specific work can, if felt necessary, appeal against the order of stoppage of work to the Project Manager within 3 days of such stoppage of work and decision of the Project Manager in this respect shall be conclusive and binding on the Contractor.
- 13. THAT, if, any Employer's Engineer/ supervisor at site observes that the Contractor is failing to provide safe working environment at site as per agreed Safety Plan / EMPLOYER Safety Rule/ Safety Instructions / Statutory safety requirement and creates hazardous conditions at site and there is possibility of an accident to workmen or workmen of the other contractor or public or the work is being carried out in an un safe manner or he continues to work even after being instructed to stop the work by Engineer / Supervisor at site / RHQ / Corp. Centre, the Contractor shall be bound to pay a penalty of Rs. 10,000/ per incident per day till the instructions are complied and as certified by Engineer / Supervisor of Employer at site. The work will remain suspended and no activity will take place without compliance and obtaining clearance / certification of the Site Engineer / Supervisor of the Employer to start the work.

THAT, if the investigation committee of Employer observes any accident or the Engineer 14. In-charge/Project Manager of the Employer based on the report of the Engineer/Supervisor of the Employer at site observes any failure on the Contractor's part to comply with safety requirement / safety rules/ safety standards/ safety instruction as prescribed by the Employer or as prescribed under the applicable law for the safety of the equipment, plant and personnel and the Contractor does not take adequate steps to prevent hazardous conditions which may cause injury to its own Contractor's employees or employee of any other Contractors or Employer or any other person at site or adjacent thereto, or public involvement because of the Contractor's negligence of safety norms, the Contractor shall be liable to pay a compensation of Rs. 10,00,000/- (Rupees Ten Lakh only) per person affected causing death and Rs. 1,00,000/- (Rupees One Lakh only) per person for serious injuries / 25% or more permanent disability to the Employer for further disbursement to the deceased family/ Injured persons. The permanent disability has the same meaning as indicated in Workmen's Compensation Act 1923. The above stipulations is in addition to all other compensation payable to sufferer as per workmen compensation Act / Rules

THAT as per the Employer's instructions, the Contractor agrees that this amount shall be deducted from their running bill(s) immediately after the accident, That the Contractor understands that this amount shall be over and above the compensation amount liable to be paid as per the Workmen's Compensation Act /other statutory requirement/ provisions of the Bidding Documents.

- 15. THAT the Contractor shall submit Near-Miss-Accident report along with action plan for avoidance such incidence /accidents to Engineer – In-charge/ Project Manager. Contractor shall also submit Monthly Safety Activities report to Engineer – In-charge/ Project Manager and copy of the Monthly Safety Activities report also to be sent to Safety In-charge at RHQ of the Employer for his review record and instructions.
- THAT the Contractor is submitting a copy of Safety Policy/ Safety Documents of its Company which is enclosed at **Annexure – 6 (SP)** and ensure that the safety Policy and safety documents are implemented in healthy spirit.
- 17. THAT the Contractor shall make available of First Aid Box [Contents of which shall be as per Building & other construction workers (Regulation of Employment and Conditions of Services Act and Central Rule 1998 / EMPLOYER Guidelines)] to the satisfaction of Engineer In-Charge/ Project Manager with each gang at site and not at camp and ensures that trained persons in First Aid Techniques with each gang before execution of work.
- 18. THAT the Contractor shall submit an 'Emergency Preparedness Plan' for different incidences i.e. Fall from height, Electrocution, Sun Stroke, Collapse of pit, Collapse of Tower, Snake bite, Fire in camp / Store, Flood, Storm, Earthquake, Militancy etc. while carrying out different activities under execution i.e. foundation works including civil works, erection, stringing (as applicable), testing & commissioning, disposal of materials at site / store etc. which is enclosed at Annexure 7 (SP) for approval of the Engineer In-Charge/ Project Manager before start of work.
- 19. THAT the Contractor shall organise Safety Training Programs on Safety, Health and Environment and for safe execution of different activities of works i.e. foundation works including civil works, erection, stringing (as applicable), testing & commissioning, disposal

of materials at site / store etc. for their own employees including sub contractor workers on regular basis.

The Contractor, therefore, submits copy of the module of training program, enclosed at **Annexure – 9 (SP)**, to Engineer In-charge/Project Manager for its acceptance and approval and records maintained.

- THAT the Contractor shall conduct safety audit, as per Safety Audit Check Lists enclosed 20. at Annexure - 8 (SP), by his Safety Officer(s) every month during construction of Transmission Lines / Sub Stations / any other work and copy of the safety audit report will be forwarded to the Employer's Engineer In-charge / Site In-charge/Project Manager for his comments and feedback. During safety audit, healthiness of all Personal Protective Equipments (PPEs) shall be checked individually by safety officer of contractor and issue a certificate of its healthiness or rejection of faulty PPEs and contractor has to ensure that all faulty PPEs and all faulty lifting tools and tackles should be destroyed in the presence of EMPLOYER construction staff. Contractor has to ensure that each gang be safety audited at least once in two months. During safety audit by the contractor, Safety officer's feedback from EMPLOYER concerned shall be taken and recorded. The Employer's site officials shall also conduct safety audit at their own from time to time when construction activities are under progress. Apart from above, the Employer may also conduct surveillance safety audits. The Employer may take action against the person / persons as deemed fit under various statutory acts/provisions under the Contract for any violation of safety norms / safety standards.
- 21. THAT the Contractor shall develop and display Safety Posters of construction activity at site and also at camp where workers are generally residing.
- 22. THAT the Contractor shall ensure to provide potable and safe drinking water for workers at site / at camp.
- 23. THAT the Contractor shall do health check up of all workers from competent agencies and reports will be submitted to Engineer In-Charge within fifteen (15) days of health check up of workers as per statutory requirement.
- THAT the Contractor shall submit information along with documentary evidences in regard to compliance to various statutory requirements as applicable which are enclosed at Annexure – 10A (SP).

The Contractor shall also submit details of Insurance Policies taken by the Contractor for insurance coverage against accident for all employees are enclosed at **Annexure – 10B (SP)**.

25. THAT a check-list in respect of aforesaid enclosures along with the Contractor's remarks, wherever required, is attached as **Annexure – Check List** herewith.

THE CONTRACTOR shall incorporate modifications/changes in this 'Safety Plan' necessitated on the basis of review/comments of the Engineer In-Charge/Project Manager within fourteen (14) days of receipt of review/comments and on final approval of the Engineer In-Charge/Project Manager of this 'Safety Plan', the Contractor shall execute the works under the Contract as per approved 'Safety Plan'. Further, the Contractor has also noted that the first progressive payment towards Services Contract shall be made on submission of 'Safety Plan' along with all requisite documents and approval of the same by the Engineer In-Charge/Project Manager.

IN WITNESS WHEREOF, the Contractor has hereunto set its hand through its authorised representative under the common seal of the Company, the day, month and year first above mentioned.

For and on behalf of

9-155

M/s.....

| WI | TNESS     |                           |
|----|-----------|---------------------------|
| 1. | Signature | Signature                 |
|    | Name      | Name                      |
| 2. | Signature | Authorised representative |
|    | Name      | (Common Seal)             |
|    | Address   | (In case of Company)      |

## Note:

All the annexure referred to in this "Safety Plan" are required to be enclosed by the contractor as per the attached "Check List "

- 1. Safety Plan is to be executed by the authorised person and (i) in case of contracting Company under common seal of the Company or (ii) having the power of attorney issued under common seal of the company with authority to execute such contract documents etc., (iii) In case of (ii), the original Power of Attorney if it is specifically for this Contract or a Photostat copy of the Power of Attorney if it is General Power of Attorney and such documents should be attached to this Safety Plan.
- 2. For all safety monitoring/ documentation, Engineer In-charge / Regional In-charge of safety at RHQ will be the nodal Officers for communication.

# CHECK LIST FOR SEFETY PLAN

| S. N. | Details of Enclosure  | Status        | Remarks |
|-------|---|---------------|---------|
|       |   | of Submission |         |
|       |   | documents     |         |
| 1.    | Annexure – 1A (SP)  |               |         |
|       | Safe work procedure for each activity i.e.  | Yes/No        |         |
|       | foundation works including civil works, erection,   |               |         |
|       | stringing (as applicable), testing & commissioning,   |               |         |
|       | disposal of materials at site / store etc. to be executed at site                             |               |         |
| 2.    | Annexure – 1B (SP)  |               |         |
|       | •• • • • • • • •  | Yes/No        |         |
|       | Manpower deployment plan, activity wise foundation works including civil works erection       |               |         |
|       | stringing (as applicable), testing & commissioning,   |               |         |
| _     | disposal of materials at site / store etc.  |               |         |
| 3.    | Annexure – 2 (SP)   | Yes/No        |         |
|       | List of Lifting Machines i.e. Crane, Hoist, Triffor,  |               |         |
|       | Chain Pulley Blocks etc. and Lifting Tools and  |               |         |
|       | clamps, wire rope slings etc. and all types of  |               |         |
|       | ropes i.e. Wire ropes, Poly propylene Rope etc.   |               |         |
|       | used for lifting purposes along with test certificates  |               |         |
| 4.    | Annexure – 3 (SP)   |               |         |
|       | List of Dersonal Protostice Equipment (DDE)   | Yes/No        |         |
|       | activity wise including the following along with test   |               |         |
|       | certificate of each as applicable:  |               |         |
|       | 1 Industrial Safety Helmet to all workmen at  |               |         |
|       | site. (EN 397 / IS 2925) with chin strap and  |               |         |
|       | back stay arrangement.  |               |         |
|       | 2. Safety shoes without steel toe to all ground<br>level workers and canvas shoes for workers |               |         |
|       | working on tower.   |               |         |
|       | 3 Rubber Gum Boot to workers working in   |               |         |
|       | rainy season / concreting job.  |               |         |
|       | 4. Twin lanyard Full Body Safety harness with   |               |         |
|       | for all workers working at height for more  |               |         |
|       | than three meters. Safety Harness should be   |               |         |
|       | with attachments of light weight such as of   |               |         |
|       | automatic locking arrangement of snap hook  |               |         |

| S. N. | Details of Enclosure                                   | Status          | Remarks |
|-------|--|-----------------|---------|
| ••••• |  | of Submission   |         |
|       |  | of information/ |         |
|       |  | documents       |         |
|       | and comply with EN 361 / IS 3521 standards.            |                 |         |
|       | 5. Mobile fall arrestors for safety of workers         |                 |         |
|       | during their ascending / descending from               |                 |         |
|       | tower / on tower. EN 353 -2 (Guided type fall          |                 |         |
|       | arresters on a flexible anchorage line.)               |                 |         |
|       | 6. Retractable type fall arrestor (EN360: 2002)        |                 |         |
|       | for ascending / descending on suspension               |                 |         |
|       | insulator string etc.                                  |                 |         |
|       | 7. Providing of good quality cotton hand gloves        |                 |         |
|       | / leather hand gloves for workers engaged in           |                 |         |
|       | handling of tower parts or as per requirement          |                 |         |
|       | at site.   |                 |         |
|       | 8. Electrical Resistance hand gloves to workers        |                 |         |
|       | for handling electrical equipment / Electrical         |                 |         |
|       | connections. IS: 4770                                  |                 |         |
|       | 9. Dust masks to workers handling cement as            |                 |         |
|       | per requirement.                                       |                 |         |
|       | 10. Face shield for welder and Grinders. IS            |                 |         |
|       | : 1179 / IS : 2553                                     |                 |         |
|       | 11. Other PPEs, if any, as per requirement etc.        |                 |         |
| 5.    | Annexure – 4 (SP)                                      |                 |         |
|       |  | Yes/No          |         |
|       | List of Earthing Equipment / Earthing devices with     |                 |         |
|       | Earthing lead conforming to IECs for earthing          |                 |         |
|       | equipments are – (855, 1230, 1235 etc.) gang           |                 |         |
| 6     | Approxime 54 (SD)                                      |                 |         |
| 0.    | Annexure – 5A (5P)                                     | Voo/No          |         |
|       | List of Qualified Safety Officer(s) along with their   | res/inu         |         |
|       | contact details  |                 |         |
| 7     | Anneyure – 5B (SP)                                     |                 |         |
| 1.    |  | Yes/No          |         |
|       | Details of Explosive Operator (if required) Safety     | 100/110         |         |
|       | officer / Safety supervisor for every erection /       |                 |         |
|       | stinging gang, any other person nominated for          |                 |         |
|       | safety, list of personnel trained in First Aid as well |                 |         |
|       | as brief information about safety set up by the        |                 |         |
|       | Contractor alongwith copy of organisation of the       |                 |         |
|       | Contractor in regard to safety                         |                 |         |
| 8.    | Annexure – 6 (SP)                                      |                 |         |
|       |  | Yes/No          |         |
|       | Copy of Safety Policy/ Safety Document of the          |                 |         |
|       | Contractor's company                                   |                 |         |
| 9.    | Annexure – 7 (SP)                                      |                 |         |
|       |  | Yes/No          |         |
|       | 'Emergency Preparedness Plan' for different            |                 |         |
|       | incidences i.e. Fall from height, Electrocution, Sun   |                 |         |

| S. N. | Details of Enclosure                                    | Status          | Remarks |
|-------|---|-----------------|---------|
|       |   | of Submission   |         |
|       |   | of information/ |         |
|       | Strake Collapse of nit Collapse of Tower Snake          | documents       |         |
|       | bite Fire in camp / Store Flood Storm                   |                 |         |
|       | Earthquake, Militancy etc. while carrying out           |                 |         |
|       | different activities under execution i.e. foundation    |                 |         |
|       | works including civil works, erection, stringing (as    |                 |         |
|       | applicable), testing & commissioning, disposal of       |                 |         |
| 10    | Materials at site / store etc.                          | Voo/No          |         |
| 10.   | Annexure – o (SP)                                       | t es/ino        |         |
|       | Safety Audit Check Lists ( Formats to be                |                 |         |
|       | enclosed)   |                 |         |
| 11.   | Annexure – 9 (SP)                                       | Yes/No          |         |
|       |   |                 |         |
|       | Copy of the module of Safety Training Programs          |                 |         |
|       | on Safety, Health and Environment, safe                 |                 |         |
|       | Contractor's own employees on regular basis and         |                 |         |
|       | sub contractor employees.                               |                 |         |
| 12.   | Annexure – 10A (SP)                                     |                 |         |
|       |   |                 |         |
|       | Information along with documentary evidences in         |                 |         |
|       | statutory requirements including the following:         |                 |         |
| (i)   | Electricity Act 2003                                    | Yes/No          |         |
| (.)   |   |                 |         |
|       | [Name of Documentary evidence in support of             |                 |         |
|       | compliance]   |                 |         |
| (11)  | Factories Act 1948                                      | Yes/No          |         |
|       | Name of Documentary evidence in support of              |                 |         |
|       | compliance]   |                 |         |
| (iii) | Building & other construction workers (Regulation       | Yes/No          |         |
|       | of Employment and Conditions of Services Act            |                 |         |
|       | and Central Act 1996) and Welfare Cess Act 1996         |                 |         |
|       | with Rules.   |                 |         |
|       | Name of Documentary evidence in support of              |                 |         |
|       | compliance]   |                 |         |
| (iv)  | Workmen Compensation Act 1923 and Rules.                | Yes/No          |         |
|       |   |                 |         |
|       |   |                 |         |
|       | [Name of Documentary evidence in support of compliance] |                 |         |
| (y)   | Public Insurance Liabilities Act 1991 and Rules         | Yes/No          |         |
|       |   | 100/110         |         |
|       | [Name of Documentary evidence in support of             |                 |         |
|       | compliance]   |                 |         |

| S. N.  | Details of Enclosure                                    | Status<br>of Submission | Remarks |
|--------|---|-------------------------|---------|
|        |   | of information/         |         |
|        |   | documents               |         |
| (vi)   | Indian Explosive Act 1948 and Rules.                    | Yes/No                  |         |
|        |   |                         |         |
|        | [Name of Documentary evidence in support of             |                         |         |
| (yii)  | compliance]   | Voc/No                  |         |
| (1)    | indian reli oledini Act 1934 and Itales.                | 165/110                 |         |
|        |   |                         |         |
|        | [Name of Documentary evidence in support of compliance] |                         |         |
| (viii) | License under the contract Labour (Regulation &         | Yes/No                  |         |
|        | Abolition) Act 1970 and Rules.                          |                         |         |
|        |   |                         |         |
|        | [Name of Documentary evidence in support of             |                         |         |
| (ix)   | compliance  | Yes/No                  |         |
|        | any, from time to time.                                 | 100/110                 |         |
|        | Mama of Desumentary syldenes in support of              |                         |         |
|        | [Name of Documentary evidence in support of compliance] |                         |         |
| (x)    | The Environment (Protection) Act 1986 and               | Yes/No                  |         |
|        | Rules.  |                         |         |
|        | [Name of Documentary evidence in support of             |                         |         |
| ()()   | compliance]   | Vac/Na                  |         |
| (XI)   | Child Labour (Prohibition & Regulation) Act 1986.       | Yes/NO                  |         |
|        | [Name of Documentary evidence in support of             |                         |         |
| (vii)  | compliance]   | Ves/No                  |         |
| (,,,,) |   | 163/110                 |         |
|        | [Name of Documentary evidence in support of             |                         |         |
| (xiii) | Indian standards for construction of Low/ Medium/       | Yes/No                  |         |
| ()     | High/ Extra High Voltage Transmission Line              |                         |         |
|        | Name of Documentary evidence in support of              |                         |         |
|        | compliance]   |                         |         |
| (iv)   | Any other statutory requirement(s)                      | Yes/No                  |         |
|        | [piease specity]  |                         |         |
|        | [Name of Documentary evidence in support of             |                         |         |
| 12     | compliance]   |                         |         |
| 13.    | Annexure = 100 (3P)                                     |                         |         |
|        | Details of Insurance Policies alongwith                 |                         |         |
| S. N. | Details of Enclosure  | Status<br>of Submission<br>of information/<br>documents | Remarks |
|-------|---|---|---------|
|       | documentary evidences taken by the Contractor<br>for the insurance coverage against accident for all<br>employees as below: |   |         |
| (i)   | Under Workmen Compensation Act 1923 and Rules.  | Yes/No  |         |
|       | [Name of Documentary evidence in support of insurance taken]  |   |         |
| (ii)  | Public Insurance Liabilities Act 1991   | Yes/No  |         |
|       | [Name of Documentary evidence in support of insurance taken]  |   |         |
| (iii) | Any Other Insurance Policies  | Yes/No  |         |
|       | [Name of Documentary evidence in support of insurance taken]  |   |         |

**EMPLOYER** 

# **ANNEXURE – 4**

HEALTH, SAFETY & ENVIRONMENT CONDITIONS IN CONTRACT DOCUMENT not exceeding 2% of the cost of construction as may be modified by the Government. The Employer of the establishment is required to provide safety measures at the Building or construction work and other welfare measures, such as Centeens, First-Ald facilities, Ambulance, Housing accommodations for workers near the work place etc. The Employer to whom the Act applies has to obtain a registration certificate from the Registering Officer appointed by the government.

p) Factories Act 1948: The Act lays down the procedure for approval at plans before setting up a factory, health and safety provisions, welfare provisions, working hours, annual earned leave and rendering information regarding accidents or dangerous occurrences to designated authorities. It is applicable to premises employing 10 persons or more with aid of power or 20 or more persons without the aid of power engaged in manufacturing process.

## GC 22.4.1 Addition of New Clause GC 22.4.1

### **Protection of Environment**

The Contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nulsance to persons or to property of the public or others resulting from pollution, noise or other causes arising as consequence of his methods of operation.

During continuance of the Contract, the Contractor and his Subcontractors shall abide at all times by all existing enactments on environmental protection and rules made thereunder, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

Sallent features of some of the major laws that are applicable are given below:

The Water (Prevention and Control of Pollution) Act. 1974, This provides for the prevention and control of water pollution and the maintaining and restoring of wholesomeness of water. 'Pollution' means such contamination of water or such alteration of the physical, chemical or biological properties of water or such discharge of any sewage or trade effluent or of any other liquid, gaseous or solid substance into water (whether directly or indirectly) as may, or is likely to, create a nuisance or render such water harmful or injurious to public health or safety, or to domestic, commercial, industrial, agricultural or other legitimate uses, or to the life and health of animals or plants or of aquatic organisms.

8-16

The Air (Prevention and Control of Pollution) Act, 1981, This provides for prevention, control and abatement of air pollution. 'Air Pollution' means the presence in the atmosphere of any 'air pollutant', which means any solid. Ilquid or gaseous substance (including noise) present in the atmosphere in such concentration as may be or tend to be injurious to human beings or other living creatures or plants or property or environment.

The Environment (Protection) Act, 1986, This provides for the protection and improvement of environment and for matters connected therewith, and the prevention of hazards to human beings, other living creatures, plants and property. 'Environment' includes water, air and land and the inter-relationship which exists among and between water, air and land, and human beings, other living creatures, plants, micro-organism and property.

The Public Liability Insurance Act, 1991, This provides for public liability insurance for the purpose of providing immediate relief to the persons affected by accident occurring while handling hazardous substances and for matters connected herewith or incidental thereto. Hazardous substance means any substance or preparation which is defined as hazardous substance under Environment (Protection) Act; 1986, and exceeding such quantity as may be specified by notification by the Central Government.

Addition of New Sub Clause 22.4.2

#### GC 22.4.2

7

~ 7

ø

2

7

٦

2

2

Ç

¥

~

-. 9'

(i) The Contractor shall (a) establish an operational system of managing environmental impacts, (b) carry out all the monitoring and mitigation measures set forth in the environment management plan attached to the Particular Conditions as Appendix-I, and (c) allocate the budget required to ensure that such measures are carried out. The Contractor shall submit to the Employer (quarterly) semi-annual) reports on the carrying out of such measures.

(ii) The Contractor shall adequately record the conditions of reads, agricultural land and other infrastructure prior to transport of material and construction commencement, and shall fully reinstate pathways, other local infrastructure and agricultural land to atleast their pre-project condition upon construction completion.

(iii) The Contractor shall undertake detailed survey of the affected persons during transmission line alignment finalization under the Project, where applicable, and

(iv) The Contractor shall conduct health and safety programme for workers employed under the Contract and shall include information on the risk of sexually transmitted diseases, including HIV/AIDS in such programs.

#### GC 22.4.3 Addition of New Sub Clause 22.4.3 including its Sub-Clauses

#### Safety Precautions

GCC 22.4.3.1 The Contractor shall observe all applicable regulations regarding safety on the Site.

Unless otherwise agreed, the Contractor shall, from the commencement of work on Site until taking over, provide:

- a) fencing, lighting, guarding and watching of the Works wherever required, and
- b) temporary roadways, footways, guards and fences which may be necessary for the accommodation and protection of Employer / his representatives and occupiers of adjacent property, the public and others.
- GCC 22.4.3.2 The Contractor shall ensure proper safety of all the workmen, materials, plant and equipment belonging to him or to POWERGRID or to others, working at the Site. The Contractor shall also be responsible for provision of all safety notices and safety equipment required both by the relevant legislations and the Engineer, as he may deem necessary.
- GCC 22.4.3.3 The Contractor will notify well in advance to the Engineer of his intention to bring to the Site any container filled with liquid or gaseous fuel or explosive or petroleum substance or such chemicals which may involve hazards. The Engineer shall have the right to prescribe the conditions. under which such container is to be stored, handled and used during the performance of the works and the Contractor shall strictly adhere to and comply with such instructions. The Engineer shall have the right at his sole discretion to inspect any such container or such construction plant/equipment for which material in the container is required to be used and if in his opinion, its use is not safe, he may forbid its use. No claim due to such prohibition shall be entertained by the Owner and the Owner shall not entertain any claim of the Contractor

and the second second

and the second sec

#### Section VIII. Particular Conditions

þ

ø

2

ì

Ç

\*

~

P

è

4 () 4 ( 4 )

< ) () () () () () ()

towards additional safety provisions/conditions to be provided for/constructed as per the Engineer's instructions.

Further, any such decision of the Engineer shall not, in any way, absolve the Contractor of his responsibilities and in case, use of such a container or entry thereof into the Site area is forbidden by the Engineer, the Contractor shall use alternative methods with the approval of the Engineer without any cost implication to POWERGRID or extension of work schedule.

- GCC 22.4.3.4 Where it is necessary to provide and/or store petroleum products or petroleum mixtures and explosives, the Contractor shall be responsible for carrying-out such provision and/or storage in accordance with the rules and regulations laid down in Petroleum Act 1934, Explosives Act, 1948 and Petroleum and Carbide of Calcium Manual published by the Chief Inspector of Explosives of India. All such storage shall have prior approval of the Engineer. In case, any approvals are necessary from the Chief Inspector (Explosives) or any statutory authorities, the Contractor shall be responsible for obtaining the same.
- GCC 22.4.3.5 All equipment used in construction and erection by Contractor shall meet Indian/International Standards and where such standards do not exist, the Contractor shall ensure these to be absolutely safe. All equipment shall be strictly operated and maintained by the Contractor in accordance with manufacturer's Operation Manual and safety instructions and as per Guidelines/rules of POWERGRID in this regard.
  - GCC 22.4.3.6 Periodical examinations and all tests for all lifting/holsting equipment & tackles shall be carried-out in accordance with the relevant provisions of Factories Act 1948, Indian Electricity Act 1910 and associated Laws/Rules in force from time to time. A register of such examinations and tests shall be properly maintained by the Contractor and will be promptly produced as and when desired by the Engineer or by the person authorised by him.
  - GCC 22.4.3.7 The Contractor shall be fully responsible for the sate storage of his and his Sub-Contractor's radioactive sources in accordance with BARC/DAE Rules and other applicable provisions. All precautionary measures stipulated by BARC/DAE in connection with use, storage and handling of

such material will be taken by the Contractor.

GCC 22.4.3.8 The Contractor shall provide suitable safety equipment of prescribed standard to all employees and workmen according to the need, as may be directed by the Engineer who will also have right to examine these safety equipment to determine their suitability, reliability, acceptability and adaptability.

- GCC 22.4.3.9 Where explosives are to be used, the same shall be used under the direct control and supervision of an expert, experienced, qualified and competent person strictly in accordance with the Code of Practice/Rules framed under Indian Explosives Act pertaining to handling, storage and use of explosives.
- GCC 22.4.3.10 The Contractor shall provide safe working conditions to all workmen and employees at the Site including safe means of access, railings, stairs, ladders, scaffoldings etc. The scaffoldings shall be erected under the control and supervision of an experienced and competent person. For erection, good and standard quality of material only shall be used by the Contractor.
- GCC 22.4.3.11 The Contractor shall not interfere or disturb electric fuses, wiring and other electrical equipment belonging to the Owner or other Contractors under any circumstances, whatsoever, unless expressly permitted in writing by POWERGRID to handle such fuses, wiring or electrical equipment
- GCC 22.4.3.12 Before the Contractor connects any electrical appliances to any plug or socket belonging to the other Contractor or Owner, he shall:
  - Satisfy the Engineer that the appliance is in good working condition;
  - b. Inform the Engineer of the maximum current rating, voltage and phases of the appliances;
  - c. Obtain permission of the Engineer detailing the sockets to which the appliances may be connected.
- GCC 22.4.3.13 The Engineer will not grant permission to connect until he is satisfied that;

#### Section VIII. Particular Conditions

\*

- a. The appliance is in good condition and is fitted with suitable plug;
- b. The appliance is fitted with a suitable cable having two earth conductors, one of which shall be an earthed metal sheath surrounding the cores.
- GCC 22.4.3.14 No electric cable in use by the Contractor/Owner will be disturbed without prior permission. No weight of any description will be imposed on any cable and no ladder or similar equipment will rest against or attached to it.
- GCC 22.4.3.15 No repair work shall be carried out on any live equipment. The equipment must be declared safe by the Engineer and a permit to work shall be issued by the Engineer before any repair work is carried out by the Contractor. While working on electric lines/equipment, whether live or dead; suitable type and sufficient quantity of tools will have to he provided by the Contractor to electricians/workmen/officers.
- GCC 22.4.3.16 The Contractors shall employ necessary number of qualified, full time electricians/electrical supervisors to maintain his temporary electrical installation.
- GCC 22.4.3.17 The Contractor employing more than 250 workmen whether temporary, casual, probationer, regular or permanent or on contract, shall employ at least one full time officer exclusively as safety officer to supervise safety aspects of the equipment and workmen, who will coordinate with the Project Safety Officer. In case of work being carried out through Sub-Contractors, the Sub-Contractor's workmen/employees will also be considered as the Contractor's employees/workmen for the above purpose.

The name and address of such Safety Officers of the Contractor will be promptly informed in writing to Engineer with a copy to Safety Officer-In charge before he starts work or immediately after any change of the incumbent is made during currency of the Contract.

GCC 22.4.3.18 In case any accident occurs during the construction/ erection or other associated activities undertaken by the Contractor thereby causing any minor or major or fatal 8-22

injury to his employees due to any reason, whatsoever, it shall be the responsibility of the Contractor to promptly inform the same to the Engineer in prescribed form and also to all the authorities envisaged under the applicable laws.

- GCC 22.4.3.19 The Engineer shall have the right at his sole discretion to stop the work. If in his opinion the work is being carried out in such a way that it may cause accidents and endanger the safety of the persons and/or property, and/or equipment. In such cases, the Contractor shall be informed in writing about the nature of hazards and possible injury/accident and he shall comply to remove shortcomings promptly. The Contractor after stopping the specific work can, if felt necessary, appeal against the order of stoppage of work to the Engineer within 3 days of such stoppage of work and decision of the Engineer in this respect shall be conclusive and binding on the Contractor.
- GCC 22.4.3.20 The Contractor shall not be entitled for any damages/compensation for stoppage of work due to safety reasons as provided in para GCC 22.4.3.19 above and the period of such stoppage of work will not be taken as an extension of time for completion of work and will not be the ground for waiver of levy of liquidated damages.
- GCC 22.4.3.21 It is mandatory for the Contractor to observe during the execution of the works, requirements of Safety Rules which would generally include but not limited to following:

#### Safety Rules

- a) Each employee shall be provided with initial indoctrination regarding safety by the Contractor, so as to enable him to conduct his work in a safe manner.
- b) No employee shall be given a new assignment of work unfamiliar to him without proper introduction as to the hazards incident thereto, both to himself and his fellow employees.
- c) Under no circumstances shall an employee hurry or take unnecessary chance when working under hazardous conditions.

٠,

5

2

¥

•

-

~ \* ~ ~

y,

, F

2

-#

÷,

~

- d) Employees must not leave naked fires unattended. Smoking shall not be permitted around fire prone areas and adequate fire fighting equipment shall be provided at crucial location.
- Employees under the influence of any intoxicating beverage, even to the slightest degree shall not be permitted to remain at work.
- f) There shall be a suitable arrangement at every work site for rendering prompt and sufficient first aid to the injured.
- g) The staircases and passageways shall be adequately lighted.
- h) The employees when working around moving machinery, must not be permitted to wear loose garments. Safety shoes are recommended when working in shops or places where materials or tools are likely to fall. Only experienced workers shall be permitted to go behind guard rails or to clean around energized or moving equipment.
- The employees must use the standard protection equipment intended for each job. Each piece of equipment shall be inspected before and after it is used.
- Requirements of ventilation in underwater working to licensed and experienced divers, use of gum boots for working in slushy or in inundated conditions are essential requirements to be fulfilled.
- In case of rock excavation, blasting shall invariably be done through licensed blasters and other precautions during blasting and storage/transport of charge material shall be observed strictly.
- GCC 22.4.3.22 The Contractor shall follow and comply with all POWERGRID Safety Rules, relevant provisions of applicable laws pertaining to the safety of workmen. employees, plant and equipment as may be prescribed from time to time without any demur, protest or contest or reservations. In case of any discrepancy between statutory requirement and POWERGRID Safety Rules

8-37

referred above, the latter shall be binding on the Contractor unless the statutory provisions are more stringent.

If the Contractor fails in providing safe working GCC22.4.3.23 environment as per POWERGRID Safety Rules or continues the work even after being instructed to stop work by the Engineer as provided in para GCC 22.4.3 19 shall promptly pay to the Contractor above. POWERGRID, on demand by the Owner, compensation at the rate of Rs.5, 000/- per day of part thereof till the instructions are complied with and so certified by the Engineer. However, in case of accident taking place causing injury to any individual, the provisions contained in para GCC 22.4.3.24 shall also apply in addition to compensation mentioned in this para.

GCC 22.4.3.24 If the Contractor does not take adequate safety precautions and/or fails to comply with the Safety Rules as prescribed by POWERGRID or under the applicable law for the safety of the equipment and plant or for the safety of personnel or the Contractor does not prevent hazardous conditions which cause injury to his own employees or employees of other Contractors or POWERGRID employees or any other person who are at Site or adjacent thereto, then the Contractor shall be responsible for payment of a sum as indicated below to be deposited with POWERGRID, which will be passed on by POWERGRID to such person or next to kith and kin of the deceased:

| a. | Fatal Injury or accident causing          | Rs. 1,000,000/- per<br>person |
|----|---|-------------------------------|
| b. | Major injuries or<br>accident causing 25% | Rs. 100,000/- per<br>person   |
|    | or more permanent disablement             |                               |

Permanent disablement shall have same meaning as indicated in Workmen's Compensation Act. The amount to be deposited with POWERGRID and passed on to the person mentioned above shall be in addition to the compensation payable under the relevant provisions of the Workmen's Compensation Act and rules framed there under or any other applicable laws as applicable from

8·24

the 24 A. mobile like Cards

Section VIII. Particular Conditions

time to time. In case the Contractor does not deposit the above mentioned amount with POWERGRID, such amount shall be recovered by POWERGRID from any monles due or becoming due to the Contractor under the contract or any other on-going contract.

GCC22.4.3.25 If the Contractor observes all the Safety Rules and Codes. Statutory Laws and Rules during the currency of Contract awarded by the Owner and no accident occurs then POWERGRID may consider the performance of the Contractor and award suitable 'ACCIDENT FREE SAFETY MERITORIOUS AWARD' as per scheme as may be announced separately from time to time.

GC 22.6 Emergency Work (GC Clause 22.6)

Replace the words "Otherwise" with "In case such work is not in the scope of the Contractor", in the second last line of second paragraph of GC clause 22.6.

GC 23.3 Supplementing sub-clause GC 23.3

For notification of testing, four weeks shall be deemed as reasonable advance notice.

GC 23.7 Test and Inspection (GC Clause 23.7)

Replace the words "GC Sub-Clause 6.1" with "GC Sub-Clause 46.1". in the last line of GC clause 23.7.

GC 24.4 Replacing Sub-Clause GC 24.4

As soon as all works in respect of Precommissioning are completed and, in the opinion of the Contractor, the Facilities or any part thereof is ready for Commissioning, the Contractor shall commence Commissioning as per procedures stipulated in Technical Specification, and as soon as Commissioning is satisfactorily completed, the Contractor shall so notify the Project Manager in writing.

GC 24.5 Replacing Sub-Clause GC 24.5

The Project Manager shall, within fourteen (14) days after receipt of the Contractor's notice under GC Sub-Clause 24.4, notify the Contractor in writing of any defects and/or deficiencies.

3 19 \* ¥ 1 . \* Ŧ ÷ 2 ¥ ÷., Ŷ 1 N 1 N -¥ ,... W , , -----5-" If the Project Manager notifies the Contractor of any defects and/or deficiencies, the Contractor shall then correct such defects and/or deficiencies, and shall repeat the procedure described in GC Sub-Clause 24.4. If the Project Manager is satisfied that the Facilities or that part thereof have passed Precommissioning, the Project Manager shall, within fourteen (14) days after receipt of the Contractor's notice/ seven (7) days after receipt of the Contractor's repeated notice, advise the Contractor to proceed with the Commissioning of the Facilities or that part thereof. If the Project Manager is not so satisfied, then it shall notify the Contractor in writing of any defects and/or deficiencies within seven (7) days after receipt of the Contractor's repeated notice, and the above procedure shall be repeated.

# GC 24.6 Replacing Sub-Clause GC 24.6

If the Project Manager fails to advise the Contractor to proceed with the Commissioning of the Facilities or the relevant part thereof or inform the Contractor of any defects and/or deficiencies within fourteen (14) days after receipt of the Contractor's notice under GC Sub-Clause 24.4 or within seven (7) days after receipt of the Contractor's repeated notice under GC Sub-Clause 24.5, then the Facilities or that part thereof shall be deemed to have passed Precommissioning. as of the date of the Contractor's notice or repeated notice, as the case may be

Existing Sub-clause GC24.7 stands amended and renumbered as GC 24.9 and following Sub-Clauses stand added as new Sub-Clauses GC 24.7, 24.7.1, 24.7.2, 24.7.3, 24.7.4, 24.7.5, 24.7.5.1 & 24.7.6

- GC 24.7 GC 24.7 Commissioning
- GC 24.7.1 Commissioning of the Facilities (or specific part thereof where specific parts are specified in the <u>GC 1.1</u>) shall be commenced by the Contractor immediately after being advised by the Project manager, pursuant to GC sub-clause 24.5 or immediately after the deemed Completion except for Commissioning Precommissioning (including deemed Precommissioning) under GC sub-clause 24.6.
- GC 24.7.2 The Employer shall, to the extent specified in Appendix-6 (scope of works and supply by the Employer), deploy the operating and maintenance personnel and supply raw materials, utilities, lubricants, chemicals, catalysts, facilities, services and other materials required for Commissioning.
- GC 24.7.3 On passing of the Precommissioning and charging of the Facilities at rated voltage, Commissioning would be attained.

- 2.11.6 Wet locations shall be kept completely dewatered, both during and 24 hour after placing the concrete, without disturbance of the concrete.
- 2.11.7 If the concrete surface is found to be defective after the form work has beer removed, the damage shall be repaired with a rich cement sand mortar were satisfaction of the Employer before the foundation is back filled.
- 2.12 Backfilling and Removal of Stub Templates
- 2.12.1 After opening of formwork and removal of shoring, timbering, etc. backfilling shall be started after repairs, if any, to the foundation concrete Backfilling shall normally be done with the excavated soil, unless it is a day type or it consists of large boulders/stones, in which case the boulders doub be broken to a maximum size of 80-mm. At locations where borrowed suris required for backfilling. Contractor shall bear the cost irrespective of leads & lift.
- 2.12.2 The backfilling materials shall be clean and free from organic or other foreign materials. A clay type soil with a grain size distribution of 50% or more passing the nu. 200 sieve as well as a black cotton soil are unacceptable for backfilling. The earth shall be deposited in maximum 200mm layer-levelled, wetted if necessary and compacted properly before another layer or deposited. The moisture content for compaction shall be based on the Proctor compaction test results given in the Geo-technical Report. Clause is of section III. The density of the compacted backfill material may further biverified to the satisfaction of the Employer based on the sand-cone method described in the ASTM D1556-82 standard.

2.12.3 The backfilling and grading shall be carried to an elevation of about Zonica above the finished ground level to drain out water. After backfilling fourhigh, earthen embankment (band) will be made along the sides of excavatore pits and sufficient water will be poured in the backfilling earth for at least 14 hours. After the pits have been backfilled to full depth the stub templates to be removed.

#### 2.13 Curing

The concrete shall be cured by maintaining the concrete wet for a period to al least 10 days after placing. Once the concrete has set for 24 hours the potmay be backfilled with selected moistened soil and well consolidated layers not exceeding 200mm thickness and thereafter both the backfill each and exposed chirmey shall be kept wer for the remainder of the presences 10 days. The exposed concrete chirmey shall also be kept wet by exceeding empty gumm bags around it and welting the bags continuously during the critical 10 days period.

2.14 Benching

STREES FOR STREET

When the line passes through hilly/undulated terrain, leveling the ground may be required for casting of lower footings. All such activities shall be termed benching and shall include cutting of excess earth and removing the same to a suitable point of disposal as required by Employer. Benching shall be resorted to only after approval from Employer. Volume of the earth to be cut shall be measured before cutting and approved by Employer for payment purposes. Further, to minimize benching, unequal leg extensions shall be considered and provided if found economical. If the levels of the pit centres be in sharp contrast with the level of tower centre, suitable leg extensions may be deployed as required. The proposal shall be submitted by the Contractor with detailed justification to the Employer.

- 2.15 Protection of Tower and Tower Footing
- 2.15.1 Tower spotting shall endeavor to minimise the quantity of revetment required.
- 2.15.2 The work shall include all necessary stone revetments, concreting and earth filling above ground level, the clearing from site of all surplus excavated soil, special measures for protection of foundation close to or in nalas, river bank / bed, undulated terrain, protection of up hill / down hill slopes required for protection of tower etc., including suitable revetment or galvanised wire netting and meshing packed with boulders. The top cover of stone revetment shall be sealed with M-15 concrete (1:2:4 mix). Contractor shall recommend protection at such locations wherever required. Details of protection of tower/tower footing are given in drawing enclosed with these specifications for reference purpose only.
- 2.15.3 Tower footings shall generally be backfilled using soil excavated at site unless deemed unsuitable for backfilling. In the latter case, backfilling shall be done with borrowed earth of suitable quality irrespective of leads and lift. The unit rate for backfilling quoted in BPS shall include the required lead and consolidation and leveling of earth after backfilling.
- 2.15.4 The provisional quantities for protection work of foundations are furnished in price schedule of Bid Proposal Sheet(BPS). The unit rates shall also be applicable for adjusting with the actual quantities of protection works done. These unit rates shall hold good for protection work carried out on down hills or up hills slopes applicable for the tower locations.
- 2.15.3 The unit rates for random rubble masonry revelment quoted in price schedule shall also include excavation & (1:5) random masonry and unit rate for top sealing with M-15 concrete. For payment purposes the volume of random rubble masonry revetment shall be measured from bottom to top sealing coat and paid at the quoted rates indicated in price scheduly.

No extra rates shall be paid for allied work such as excavation, for reveneent packed stone at head of weep holes etc. However, no deduction

- 1.9.4 The cases containing easily damageable material shall be very carefully packed and marked with appropriate caution symbols, i.e. fragile, handle with care, use no book etc. wherever applicable.
- 1.9.5 Each package shall be legibly marked by the Contractor at his expenses showing the details such as description and quantity of contents, the name of the consignee and address, the gross and net weights of the package, the name of the Contractor etc.
- 2.0 Employer's Environment and Social Policy and its Implementation
- 2.1 Development and growth of mankind through Industrialization and univarranted use of natural resources has inflicted considerable impact on Environment and Society. As a result, Environmental and Social issues have emerged as the focal point of global debate.

Employer's activities by their inherent nature and flexibility have negligible impacts on environmental and social attributes. In order to address these issues and to match the rising expectations of a cleaner, safer and healthier environment, Employer has evolved its Environmental and Social Policy and Procedures (ESPP). The key principles of Employer Environmental and Social Policy are :

- Avoidance of environmentally and socially sensitive areas while planning project activities.
- ii) Minimisation of impacts when project activities occur in environmentally and socially sensitive areas.
- iii) Mitigation of any unavoidable adverse impacts arising out of its projects.
- 2.2 Basic issues to be kept in mind while carrying out construction activities are to.
  - Acoud socially sensitive areas with regard to human habitations and areas of cultural significance
  - Secure the interest of people affected by Employer's projects.
  - (ii) Involve local people affected by transmission line projects as per requirement and suitability
  - iv) Consult affected people in decisions having implication to them if considered necessary
  - Apply, efficient and safe technology/practices
  - vi) Keep abreast of all potential dangers to people's health occupational safety and safety of environment and the respective initiatory measures.

#

- vii) Establish preventive mechanisms to guarantee safety.
- viii) Miligation measures in case of accidents.
- ix) Avoid univarranted cutting of trees in forest area.
- 2.3 While constructing the lines through forest stretches the contractor will provide alternate fuel to its employee e.g. working labours/supervisors etc in order to avoid cutting of forest woods.
- 2.4 Contractor will ensure safety to the wild lite, during working/camping near to the National park.
- 2.5 Contractor during construction of lines in agricultural fields will ensure minimum damages to the crops, trees, bunds, irrigation etc. If the same is un-avoidable, the decision of Engineer-in-charge shall be final.
- 2.6 The waste/excess material/debris should be removed from the construction site including agricultural field, forest stretches, river etc. immediately after construction work.
- 2.7 The Contractor will ensure least disturbance to the hill slope and natural drainage so as to avoid soil erosion. Natural drainage in plain area is disturbed to be trained to the satisfaction of Engineer- in-charge.
- 2.8 As far as possible existing path/kutchha road/approach shall be used for the construction.
- 2.9 The Contractor will ensure supply of stone chips/sand from authorised/approved quarry areas.
- 2.10 Proper documentation of above, if any.

#### STEERING ELGORDANISHT

1200-22

# **ANNEXURE – 5**

**HEALTH & SAFETY CHECKLISTS** 

## HEALTH AND SAFETY CHECKLIST

## Safety Related Check List during Construction of Transmission Lines

| Region : Name of DHQ/GHQ: | . Date of Safety Audit: |
|---------------------------|-------------------------|
| Name of Tr. Line:         |                         |
| Loc. No:                  | Voltage Level:          |
| Name of Contractor:       |                         |
| Name of Sub Contractor:   |                         |

#### A. DURING TOWER FOUNDATION :

| SN          | Description of Activity   | Feed back | Remarks |
|-------------|---|-----------|---------|
| I) <b>F</b> | EXCAVATION :  |           |         |
| 1.          | Dumping of Excavated soil. (Minimum 1.5 Mts. or half the depth of the pit which ever is more)   | Yes / No. |         |
| 2.          | Whether angle of repose of soil as per design in the foundation is maintained or not.   | Yes / No. |         |
| 3.          | De watering arrangement is available ( If necessary)  | Yes / No. |         |
| 4.          | Working area has been protected properly to avoid against fall of passerby or animal in the excavated pit.  | Yes / No. |         |
| 5           | Shoring & Shuttering to protect the loose rock / soil against fall exists.  | Yes / No. |         |
| 6           | Arrangement of illumination at construction site is available. (if required )   | Yes / No. |         |
| 7           | Check proper/adequate arrangement is made for extension of electric supply. (Proper size of cable, Use of fuse, No loose connection for De-watering Pumps/ Illumination / Electric compressors etc. if applicable). | Yes / No. |         |
| 8           | Check for damage / Uneven settlement of foundation.   | Yes / No. |         |
| 9           | Ensure Life saver arrangements have been made during construction of well foundation in river bed. (Where necessary)  | Yes / No. |         |
| 10          | Check that the adequate arrangement is made for the storage of blasting material at safe place. (if required)   | Yes / No. |         |
| 11          | Check that the blasting materials is handled with due care at site. ( If required )   | Yes / No. |         |
| 12          | Check that during blasting operation, Labour / Workmen / Passerby<br>are at safe places and arrangement is made to inform public by<br>caution markings (Red Flag) / Public Notices.                                | Yes / No. |         |
| 13          | Check that the Blaster is holding the proper license issued by the appropriate authority. as per the Indian Explosive Act.  | Yes / No. |         |
| 14          | Check that the length of the fuse wire used during blasting operation is adequate.  | Yes / No. |         |
| 15          | Ensure Laying of temporary cable used for operation of Machines   |           |         |

| SN | Description of Activity   | Feed back | Remarks |
|----|---|-----------|---------|
|    | used during construction should not cause any danger for electrocution of workmen.  | Yes / No. |         |
| 16 | Check that PPEs i.e. Safety helmets, Safety Shoes, is used by blaster<br>and their gang members during blasting.  | Yes / No. |         |
| 17 | Ensure that Shuttering and timbering has been made as detailed in I:S: 3764.  | Yes / No. |         |
| 18 | Ensure that before undertaking excavation, the soil has been tested<br>and in case of availability of any explosive / dangerous gas,<br>necessary arrangement must be made to remove / dilute such gases.   | Yes / No. |         |
| 19 | The positions of underground installations such as sewers, water<br>pipes and electrical cables have been verified and in case of their<br>existence, they must be isolated.  | Yes / No. |         |
| 20 | Arrangement shall be made to prevent external vibrations due to rail / road traffic (If required).  | Yes / No. |         |
| 21 | Safety is ensured during the construction of Tr. Lines for buildings, structures etc. which are coming in the vicinity of the excavated area from collapse. (If required )  | Yes / No. |         |
| 22 | Check that sufficient strong ladder of suitable length is available for ingress / outgress of persons in the pit  | Yes / No. |         |
| 23 | Lone worker should not be allowed to work in the excavated area beyond shoulder level.  | Yes / No. |         |
| 24 | Check for any possibility of seepage of water from nearby pond / river should be estimated and taken care of.   | Yes / No. |         |
| 25 | After excavation the work has been completed speedily and back filling done at the earliest.  | Yes / No. |         |
| П) | Casting of Foundation / Concreting :  |           |         |
| 1  | Check construction materials are stacked at safe place and also does<br>not cause any danger. (Away from pit by 1.5 Mtrs. Or half the depth<br>of pit, which ever is more. )  | Yes / No. |         |
| 2  | Check arrangement of illumination at Construction Site. (If required).  | Yes / No. |         |
| 3  | Ensure life saver arrangements have been made during construction of Well foundation in River Bed.  | Yes / No. |         |
| 4  | Check that the Concreting Mixer machine is placed at a safe place.<br>(Not very near to pit.)   | Yes / No. |         |
| 5  | Check proper / adequate arrangement is made for extension of<br>electric supply. (Proper size of cable, Use of fuse, No loose<br>connection for De watering Pumps / Illumination / Electric<br>compressors etc. if applicable).   | Yes / No. |         |
| 6  | Check that laying of temporary cables used during construction activities should not cause any danger for electrocution to workmen.   | Yes / No. |         |
| 7  | Inspection of excavations shall be made by a Competent Person<br>every day. In case, possible cave in or slide is apparent, all working<br>in the excavation shall be seized until the necessary precautions<br>have been taken to safeguard the possible cave in or slide. | Yes / No. |         |
| 8  | Jacks and vertical supports shall be positioned in such a manner that   |           |         |

| SN | Description of Activity   | Feed back | Remarks |
|----|---|-----------|---------|
|    | the vertical loads are distributed equally and do not exceed the        | Yes / No. |         |
|    | capacity of the jacks and the jacks are placed away from pit edge       |           |         |
|    | etc.  |           |         |
| 9  | Proper Jacking arrangement is made to take the entire load of           |           |         |
|    | template.   | Yes / No. |         |
| 10 | In case of long template in stub setting, more jacks have been          |           |         |
|    | provided and check that the Jacks are placed on levelled and hard       | Yes / No. |         |
|    | surface to avoid the unbalancing and fallen.                            |           |         |
| 11 | Wire mesh rolls shall be secured in order to prevent dangerous          |           |         |
|    | recoiling action.   | Yes / No. |         |
| 12 | Lone worker should not be allowed to work in the excavated area.        | Yes / No. |         |
| 13 | Check that sufficient strong ladder of suitable length is available for |           |         |
|    | ingress / outgress of persons in the pit                                | Yes / No. |         |

# **B.** Tower Erection :

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
| 1   | Check proper communication facility is available at site during<br>Tower erection. (If required)  | Yes / No. |         |
| 2.  | Check damages or uneven settlement of foundation.   | Yes / No. |         |
| 3.  | Ensure the derrick used before tower erection has been checked for<br>adequate strength/ size. Ensure for copy of test certificate for all the<br>lifting machines and tackles.   | Yes / No. |         |
| 4.  | Ensure that the pulleys used before tower erection has been checked<br>for adequate strength / proper size (diameter). Also in case of open<br>type pulleys proper locking arrangements like providing of Safety<br>Pin is made. Ensure for copy of test certificate for all the lifting<br>machines and tackles. | Yes / No. |         |
| 5.  | Ensure that the ropes used before tower erection has been checked<br>for adequate strength / physical condition (Free from break of<br>strands and knots etc.   | Yes / No. |         |
| 6.  | Check that the lifting tools and tackles i.e. Winch Machine, Chain<br>Pulley Block, Trifor, D - Shackle etc. are in healthy condition and<br>has been tested periodically. (Attach copy of test certificate).   | Yes / No. |         |
| 7.  | Ensure that permission has been obtained from Aviation Authority for erection of special towers. (Where necessary).   | Yes / No. |         |
| 8.  | Ensure that permission has been obtained form Aviation Authority<br>for erection of towers which comes in the vicinity of flying zone.<br>(Where necessary)   | Yes / No. |         |
| 9.  | Check that the safety measures has been taken before undertaking for the Road / Rail / River Xing jobs involving like wise stretches.   | Yes / No. |         |
| 10. | For rail or road crossing check whether written working plan is<br>available at site with specific reference to safety e.g. local earthing,<br>skilled & experience manpower, proper T&P, strength and height of<br>scaffolding to maintain the required clearance etc.   | Yes / No. |         |
| 11. | Ensure that all the members and proper size of Nuts and Bolts of<br>lower section are fitted properly before erection of the upper section<br>of tower is taken up.   | Yes / No. |         |
| 12. | Check that the anti climbing devices are provided in the tower after  |           |         |

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
|     | erection job.   | Yes / No. |         |
| 13. | Check that the danger plates have been provided.  | Yes / No. |         |
| 14. | Check that only erection team members are allowed to stand near<br>the tower while erection is in process and should wear the safety<br>helmet / Safety Shoes.                                      | Yes / No. |         |
| 15. | Working area of the tower has been demarcated during erection.  | Yes / No. |         |
| 16  | Check that proper guying arrangement has been made. And also to<br>see that proper size of the crow bars has been used which has been<br>fixed at hard surface in case of sandy soil or loose soil. | Yes / No. |         |
| 17  | Check that proper arrangement is made while lifting the tower<br>members and fixing them at height i.e. Proper size and strength of<br>the hook used for lifting the tower members.                 | Yes / No. |         |
| 18  | Check sufficient numbers of guys are made while lifting the assembled cross arm and also avoiding use of single sheeve pulleys while lifting the assembled cross arm / heavy load.                  | Yes / No. |         |

## C. CONDUCTOR STRINGING:

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
| 1.  | All drivers and plant operators are holding the valid driving license.  | Yes / No. |         |
| 2.  | Check that the permit has been obtained from the Competent<br>Authority for stringing of conductor while crossing through Road /<br>Rail / River / Venerable areas etc. (Where necessary)   | Yes / No. |         |
| 3.  | Check that required painting has been made on tower falling in the vicinity of aviation zones. (Where necessary.)   | Yes / No. |         |
| 4.  | Check that all safety measures have been taken during stringing of conductor crossing the EHV / HV / LT lines (Earthing of existing lines etc.)   | Yes / No. |         |
| 5.  | Ensure that proper size of Nuts and Bolts is rigidly tightened and punching / tacking / tack welding is done in towers before undertaking stringing job.  | Yes / No. |         |
| 6.  | Ensure that proper scaffolding arrangements made during stringing of conductor ( While Road Xing / Power Line Xing etc.   | Yes / No. |         |
| 7.  | Ensure that all members are fitted in tower before undertaking conductor stringing work.  | Yes / No. |         |
| 8.  | Check that the back filling of the foundation has been done as per specification.   | Yes / No. |         |
| 9.  | Ensure that the discharge rod is electrically tested before use.  | Yes / No. |         |
| 10. | Stringing Machine / Tension pullor Machine are properly earthed.  | Yes / No. |         |
| 11. | Check the brake arrangement of the TSE Machines is working.   | Yes / No. |         |
| 12. | Ensure that the pulleys used before conductor stringing has been<br>checked for adequate strength / proper size (diameter), also in case<br>of open type pulleys proper locking arrangements like providing of<br>Safety Pin is made Ensure for copy of test certificate for all the<br>lifting machines and tackles. | Yes / No. |         |
| 13. | Ensure the ropes used before conductor stringing has been checked<br>for adequate strength / physical condition (Free from break of<br>strands and knots etc.   | Yes / No. |         |
| 14. | Check that the lifting tools and tackles i.e. Winch Machine, Chain  |           |         |

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
|     | Pulley Block, Trifor, D - Shackle etc. are in healthy condition and has been tested periodically. (Attach copy of test certificate).  | Yes / No. |         |
| 15. | Check for the brake arrangement of the Drum reel of conductor during laying / paying out of conductor.  | Yes / No. |         |
| 16. | Check that proper communication facility is available at site during of stringing of conductor ( If required )  | Yes / No. |         |
| 17. | Whether the tower has been permanently earthed.   | Yes / No. |         |
| 18. | Check that Sag Board is provided at two locations.  | Yes / No. |         |
| 19. | Check that the Sag Board arrangement is made by the experienced / trained persons.  | Yes / No. |         |
| 20. | Check approved Sag tension chart is available and followed at site.   | Yes / No. |         |
| 21. | While clamping of conductor / EW to be done, check for earthing.  | Yes / No. |         |
| 22. | Ensure sending signal to puller to stop when last layer of conductor / EW being pulled.   | Yes / No. |         |
| 23. | Check tension applied on the dynamo meter dial and check values with approved data.   | Yes / No. |         |
| 24. | Before stringing starts check that the villagers do not come<br>underneath the job of the concerned section.  | Yes / No. |         |
| 25. | Only nylon or polypropylene ropes should be used during conductor stringing in vicinity of live overhead lines.   | Yes / No. |         |
| 26. | Ensure that PTW has been taken from the concerned authority.  | Yes / No. |         |
| 27. | Ensure that Winch, Pulleys etc. are properly earthed.   | Yes / No. |         |
| 28. | For LT lines, whether special persons are posted at each point of isolation till return of permit (PTW).  | Yes / No. |         |
| 29. | Whether the network of LT lines has been thoroughly checked and precautions taken Against inadvertent charging.   | Yes / No. |         |
| 30. | Check that proper arrangement is made / available for development<br>and use of a Portable Earthing and Short – Circuiting Devices which<br>can be engaged and disengaged to and from the LT lines, keeping<br>away from the LT lines, until all operations on the same are<br>completed and all men and materials are removed from LT lines. | Yes / No. |         |
| 31. | Check the provision and proper positioning for the guying and back staying (Where necessary).   | Yes / No. |         |
| 32. | Check demarcation of feeder is done for D/c Line.   | Yes / No. |         |
| 33. | Ensure that all the insulator strings are thoroughly checked for<br>availability and proper fixing of cotter / split pins before hoisting the<br>same.  | Yes / No. |         |

## General Points common for all activities during Excavation, Casting of Foundation

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
| 1.  | Check whether the contractor had procured required quantity of<br>PPEs considering maximum numbers of erection gangs deployed at<br>one time.   | Yes / No. |         |
| 2.  | Supervisors/ Workmen have been provided with required healthy PPEs, like Safety helmet / Safety Belts / Safety Shoes / Gum Boot etc. as applicable.   | Yes / No. |         |
| 3.  | Availability of First Aid Box with required medicines at site.  | Yes / No. |         |
| 4.  | Instruction register is available at site.  | Yes / No. |         |
| 5.  | Ensure that Supervisor / Gang Leader always issues instruction to the Workmen before start of work.   | Yes / No. |         |
| 6.  | Ensure that supervisory staff from Power Grid is available at site during construction.   | Yes / No. |         |
| 7.  | All driver and plant operators are holding valid driving license.   | Yes / No. |         |
| 8.  | Check the vehicle for rescue is available at site.  | Yes / No. |         |
| 9.  | Ensure engaged labour are aware of the job.   | Yes / No. |         |
| 10. | Check that the unskilled labourers are not engaged in skilled job.  | Yes / No. |         |
| 11. | Ensure that supervisor / workmen engaged in the field are aware of<br>First Aid Techniques (Such as in case of Electric Shock, Fall from<br>the height, Snake bite and the person rescued from buried under the<br>debris etc.                  | Yes / No. |         |
| 12. | Check for nearby Hospital / Doctor in case of emergencies arises.   | Yes / No. |         |
| 13. | While transporting heavy consignment of conductor / EW drums<br>from central store to site by the use of Cranes, Truck, and Tractor.<br>The safety aspect for construction and failure of brake system of<br>moving machinery is to be checked. | Yes / No. |         |
| 14. | At least one dry powder type of portable fire extinguisher shall be<br>provided especially where explosive or blasting agents are used for<br>excavation.   | Yes / No. |         |
| 15. | Check the competence (Qualification / Experience) of supervisor / gang leader of contractor.  | Yes / No. |         |

## A. ERECTION OF TOWER AND STRINGING OF CONDUCTOR :

## REMARKS IF ANY:

| Signature         | Signature                  | Signature                 |
|-------------------|----------------------------|---------------------------|
|                   |                            |                           |
|                   |                            |                           |
| Name ·            |                            |                           |
| Designation ·     | Name ·                     | Name ·                    |
| Representative of | Designation:               | Designation:              |
| Contractor        | Power Grid Rep. from Site. | Power Grid Rep. from RHQ. |

# Safety Related Check List during Construction of Substation

| Region: Name of DHQ / GHQ:             | Date of Safety Audit: |
|--|-----------------------|
| Name of Sub Stn. / Switching Stn.:     |                       |
| Name of Contractor:                    |                       |
| Contractor License / Registration No.: | Validity              |
| Name of Sub Contractor :               |                       |

#### A. SUB STATION CIVIL WORKS :

| SN     | Description of Activity   | Feed back | Remarks |
|--------|---|-----------|---------|
| I): S. | AFETY DURING EXCAVATION :   |           |         |
| 1.     | Check Sub station area has been protected by constructing boundary<br>wall all around the sub station to avoid entry of passerby /<br>unauthorized person or animal in the sub station.   | Yes / No. |         |
| 2.     | De watering arrangement is available ( If necessary )   | Yes / No. |         |
| 3.     | Check proper / adequate arrangement is made for extension of<br>electric supply. (Proper size of cable, Use of fuse, No loose<br>connection and no naked wire connection to Pumps / Illumination /<br>Electric compressors etc. if applicable).   | Yes / No. |         |
| 4.     | Check arrangement of illumination at construction site is available.  | Yes / No. |         |
| 5.     | Check dumping of Excavated soil (Minimum 1.5 Mts. Or half the depth of the pit which ever is more from the edge of the pit.)  | Yes / No. |         |
| 6.     | Check Shoring & Shuttering to protect the loose rock / soil against fall. (if required).  | Yes / No. |         |
| 7.     | Check lone worker is not be allowed to work in the excavated area.  | Yes / No. |         |
| 8.     | Ensure Laying of temporary cables used for operation of Machines<br>used during construction should not cause any danger for<br>electrocution of persons / animals.   | Yes / No. |         |
| 9.     | Ensure that before undertaking excavation, the soil has been tested<br>and in case of availability of any explosive / dangerous gas,<br>necessary arrangement must be made to remove / dilute such gases.   | Yes / No. |         |
| 10.    | The positions of underground installations such as sewers, water<br>pipes and electrical cables has been verified and in case of their<br>existence, they must be isolated before further excavation works to<br>ensure Human Safety.   | Yes / No. |         |
| 11.    | Check that the scaffolds are not overloaded in any case. Scaffolds are to be erected and supported properly.  | Yes / No. |         |
| 12.    | Stability of the soil of the excavated pit for safe working is to be<br>checked and certified by a competent person daily before start of<br>work. A register at site is maintained where competent person can<br>certify accordingly. No manhole should remain uncovered during<br>night & off days. | Yes / No. |         |
| 13.    | Check the provision of sufficient strong ladder of suitable length is available near the working place during excavation.   | Yes / No. |         |

| SN     | Description of Activity  | Feed back   | Remarks |
|--------|--|-------------|---------|
| 14.    | Check if any permission is required from local statutory body before   |             |         |
|        | excavation.  | Yes / No.   |         |
| 15.    | Check for No undercutting / toe cutting in soil.   | Yes / No.   |         |
| 16.    | Check after excavation the work should be speedily completed without delay and back filling done at the earliest.  | Yes / No.   |         |
| 17.    | Check for any possibility of seepage of water from nearby pond / river has been estimated and taken care of.   | Yes / No    |         |
| 18.    | Check to avoid slide / collaps of side walls of excavated pit, the excavation is to be done in trapezoidal cross – section.  | Yes / No.   |         |
| II): S | AFETY PRECAUTION DURING STORAGE, HANDLING AND USE OF B   | LASTING MAT | 'ERIAL: |
| 1      | Check that the adequate arrangement is made for the storage of<br>blasting material at safe place. (Temporary Magazine is to be<br>installed observing all norms) as per Indian Explosive Act. | Yes / No.   |         |
| 2.     | Check that the blasting materials is handled by licensed blaster with due care at site. (If applicable)  | Yes / No.   |         |
| 3.     | Check smoking is prohibited in the vehicle carrying explosives.  | Yes / No.   |         |
| 4.     | Check that the Blaster is holding proper license issued by the appropriate authority. As per Indian Explosive Act.   | Yes / No.   |         |
| 5.     | Check that the length of the fuse wire used during blasting operation is adequate.   | Yes / No.   |         |
| 6.     | Check while transportation, no unauthorized person is allowed in vehicle carrying explosives.  | Yes / No.   |         |
| 7.     | Check that the loading and unloading of explosives is being done carefully.  | Yes / No.   |         |
| 8.     | Check explosives and detonators or blasting caps is not being transported in the same vehicle.   | Yes / No.   |         |
| 9.     | Check while transportation the detonators and explosives are not carried loose or mixed with other materials.  | Yes / No.   |         |
| 10     | Check surplus explosives shall not be stacked near working area during loading / unloading.  | Yes / No.   |         |
| 11.    | Check explosives shall not be held in hands when lightening the fuse.  | Yes / No.   |         |
| 12.    | Check that blasting in the open has been carried out during the fixed<br>hours every day or on fixed days in the week so that the public at<br>large should know about this.                   | Yes / No.   |         |
| 13.    | Check that arrangement has been made to display sufficient<br>warnings / sign board to enable the people to get out of the blasting<br>area to get off the danger zone                         | Yes / No.   |         |
| 14.    | Check that the danger zone has been suitably cordoned off.   | Yes / No.   |         |
| 15.    | Check during blasting operations begin / after the firing of explosives shall follow the loud siren.   | Yes / No.   |         |
| 16.    | Check that during blasting operation, Labour / Workmen / Passerby<br>are at safe places and arrangement is made to inform public by<br>caution markings ( Red Flag ) / Public Notices etc.     | Yes / No.   |         |
| 17.    | Check that PPEs i.e. Safety helmets, Safety Shoes, is used by blaster<br>and their gang members during blasting and also the persons<br>supervising the blasting operations.                   | Yes / No.   |         |

| SN   | Description of Activity   | Feed back | Remarks |
|------|---|-----------|---------|
| 18.  | For covered blasting ensure placement of cover plates of proper thickness and sufficient numbers of sand filled bags.   | Yes / No. |         |
| 19.  | Ensure that permission for blasting has been obtained from the appropriate authority.   | Yes / No. |         |
| III) | SAFETY DURING CASTING OF FOUNDATION / CONCRETING :  |           |         |
| 1.   | Check construction materials are stacked at safe place and also does<br>not cause any danger. (Away from pit) i.e. 1.5 Mtrs. or half the<br>depth of the pit which ever is more.)   | Yes / No. |         |
| 2.   | Check proper arrangement of illumination at Construction Site of Sub station is available.  | Yes / No. |         |
| 3.   | Check that the Concreting Mixer/ Vibrator machines etc are placed<br>at a safe place (Not very near to any pit at least 1.5 Mtr. from the<br>edge of the pit) to avoid transfer of vibrations and should be<br>operated by skilled persons. | Yes / No. |         |
| 4.   | Check proper / adequate arrangement is made for extension of<br>electric supply. (Proper size of cable, Use of fuse, No loose<br>connection for De watering Pumps / Illumination / Electric<br>compressors etc. if applicable).             | Yes / No. |         |
| 5.   | Check for laying of temporary cables used during construction activities should not cause any danger for electrocution to persons / animals.  | Yes / No. |         |
| 6.   | All bracing, struts and shuttering in excavations shall be adequately secured so as to prevent their accidental displacement.   | Yes / No. |         |
| 7.   | Ensure Shuttering and timbering has been made as detailed in I:S: 3764 for protecting the loose rock / soil against fall.   | Yes / No. |         |
| 8.   | Check for proper placing of Hydraulic jacks with stability and<br>constant watch of these instruments (which are continuously loaded)<br>to avoid any danger of displacement causing sever accident.  | Yes / No. |         |

## **B.** SAFETY DURING STRUCTURE, EQUIPMENT ERECTION & CABLE LAYING ETC. :

| SN | Description of Activity   | Feedback  | Remarks   |
|----|---|-----------|---|
| 1. | Check Back filling done prior to erection activity.   | Yes / No. |   |
| 2. | Check the derrick used before structure erection has been<br>checked for adequate strength / size and no joints are<br>permitted.   | Yes / No. | Test certificate is<br>required apart<br>from visual<br>inspection. |
| 3. | Check that the pulleys used before structure erection /<br>Equipment Erection has been checked for adequate strength /<br>proper size (diameter), also in case of open type pulleys<br>proper locking arrangements like providing of Safety Pin is<br>made Safe working load should be punched. | Yes / No. | Test certificate is<br>required apart<br>from visual<br>inspection. |
| 4. | Check the ropes used before structure erection / Equipment<br>Erection has been checked for adequate strength / physical<br>condition (free from break of strands and knots etc.  | Yes / No. | Test certificate is<br>required apart<br>from visual<br>inspection. |

| SN  | Description of Activity   | Feedback  | Remarks   |
|-----|---|-----------|---|
| 5.  | Check that the lifting tools and tackles are in healthy condition and has been tested periodically.   | Yes / No. | Test certificate is<br>required apart<br>from visual<br>inspection. |
| 6.  | Check permission has been obtained from Aviation Authority<br>for erection of Lightning Mast which comes in the vicinity of<br>flying zone. (Where necessary )  | Yes / No. |   |
| 7.  | Check that all Nuts and Bolts are fitted in the structure before<br>undertaking the job of other section of the structure and are<br>tightened.   | Yes / No. |   |
| 8.  | Check area has been cordoned off to prevent injuries to<br>unauthorized persons from hitting against structural<br>component or falling in the excavated pits.  | Yes / No. |   |
| 9.  | Check that danger plates are available on all the equipment & structures in the switchyard.   | Yes / No. |   |
| 10. | Check demarcation of feeder is done for Double Circuit Line.  | Yes / No. |   |
| 11. | Check only erection team members are allowed to stand near<br>the structure / Equipment while erection is in process and<br>should wear the safety helmet / Safety Shoes.   | Yes / No. |   |
| 12. | Check proper guying arrangement has been made while lifting structure / Equipment, if necessary.  | Yes / No. |   |
| 13. | Check that proper arrangement is made while lifting the structure members and fixing them at height i.e. Proper size and strength of the hook used for lifting the structure members.   | Yes / No. |   |
| 14. | Check sufficient numbers of guys are made while lifting the assembled structure / heavy loads and also avoiding use of single sheeve pulleys while lifting the assembled structure / heavy load.  | Yes / No. |   |
| 15. | Check arrangement has been made for equipment identification.   | Yes / No. |   |
| 16. | Check that required painting made on tower falling in the vicinity of aviation zones. (Where necessary.)  | Yes / No. |   |
| 17  | Check no live wires nearby. Take shut down if necessary.  | Yes / No. |   |
| 18. | Check the structure has been permanently earthed.   | Yes / No. |   |
| 19. | Check crane are preferably be used for erection of pipe<br>structure in the sub station building works ( if required.)  | Yes / No. |   |
| 20. | Check all safety procedures for erection work like use of<br>safety helmets, Safety belts, use of guy wires, lowering /<br>lifting of tools by rope etc. are strictly adhered to during<br>structure erection works is in progress in the switchyard. | Yes / No. |   |
| 21. | Check that correct size of spanner (Box or ring type) as well as DE spanners is being used.   | Yes / No. |   |
| 22. | Check working area of the structure has been demarcated during erection.  | Yes / No. |   |
| 23. | Check heavy structures are lifted with crane with proper safety.  | Yes / No. |   |

| SN  | Description of Activity  | Feedback  | Remarks |
|-----|--|-----------|---------|
| 24. | Only polypropylene ropes are to be used to tie the aluminium<br>tube / Bus bar since this is soft material and will not damage<br>aluminium tube / Bus bar during erection.  | Yes / No. |         |
| 25. | Ensure that R clips in insulator caps are fixed properly to avoid disconnection of insulator discs.  | Yes / No. |         |
| 26. | Ensure that all the necessary security pins (split pins) are fixed.  | Yes / No. |         |
| 27. | Check all nuts of jumper fittings are properly tightened and<br>live metal clearance have been maintained as per<br>POWERGRID specification.   | Yes / No. |         |
| 28. | In case of tension fitting dead end joint dimensions before & after the compression are checked and recorded.  | Yes / No. |         |
| 29. | No damaged component of any hardware fitting should be used on works.  | Yes / No. |         |
| 30. | Length of jumpers has been measured properly to give it a parabolic shape. No sharp bend should exist.   | Yes / No. |         |
| 31. | Check surge counter erection facilitates proper reading and that earthing is done with minimum bends.  | Yes / No. |         |
| 32. | Check Surge monitor has been earthed by connecting it to main earth mat with (G I Flat 75 x 12 mm) and earth pit separately as per drawing.  | Yes / No. |         |
| 33. | Check the alignment of earth switch with isolator, earth<br>switch of isolator is put into operation and the contacts are<br>cleaned. After completion of pre commissioning checks and<br>formats are dully filled and signed.   | Yes / No. |         |
| 34. | Ensure that the rubber beedings are kept in good condition.  | Yes / No. |         |
| 35. | Check CT has been placed on the support structure very carefully and all nuts have been tightened. Earthing is done as per drawing.  | Yes / No. |         |
| 36. | Ensure the lattice structure of CT has been earthed at two points.   | Yes / No. |         |
| 37. | Check the marshalling box in the switchyard has proper illumination arrangement.   | Yes / No. |         |
| 38. | Check the capacitor unit is short circuited & earthed, until<br>erection and commissioning works are being done on CVT.<br>(The capacitor get charged by the electrical fields in the<br>vicinity and they keep these charges for a long time, which<br>can be dangerous to human life. Hence the shorting of<br>capacitor unit is necessary). It should be removed before tests<br>/ use. | Yes / No. |         |
| 39. | Check Fuses in the marshaling box are OK.  | Yes / No. |         |
| 40. | Check proper earthing of CVT tank has been done.   | Yes / No. |         |
| 41. | Check all housing accessories, mounting stools including<br>bolts / Nuts for fixing Line Trap and insulators are of non<br>magnetic material.  | Yes / No. |         |
| 42. | Check H.F. point of CVTs on which the coupling device is not mounted has been earthed.   | Yes / No. |         |

| SN  | Description of Activity   | Feedback  | Remarks |
|-----|---|-----------|---------|
| 43. | Check the remaining CVTs have been earthed thro' coupling device.   | Yes / No. |         |
| 44. | Cable drums after visual inspection should be stored preferably in the covered area. Cable ends should be clamped.  | Yes / No. |         |
| 45. | Ensure each cable and conduit run should be tagged with<br>cable identity numbering as per the approved that appear in<br>the cable and conduit schedule.   | Yes / No. |         |
| 46. | The tag should be of aluminium plate with ID number<br>punched on it and securely attached to the cable conduit by<br>not less than two turns. Cable tags should of rectangular<br>shape for power cables and of circular shape for control<br>cables.  | Yes / No. |         |
| 47. | Check underground cable markers should project 150 mm<br>above ground and spaced at an interval of 30 Mts. They shall<br>be located on both sides of road and drain crossing and also at<br>every change in direction.  | Yes / No. |         |
| 48. | Check cable tags should be provided inside the switchgear,<br>motor control centres, control and relay panels etc. wherever<br>required for cable identification, where a number of cables<br>enter together through a gland plate.   | Yes / No. |         |
| 49. | The cable (power and control) between LT stations, Control<br>room, DG set building and fire fighting pump house should<br>be laid in the buried cable trenches. In addition to the above,<br>for lighting purpose also, buried cable trench can be used in<br>outdoor area.(as per Technical specification of specific<br>contract)  | Yes / No. |         |
| 50. | Cable route and joint markers and RCC warning covers<br>should be provided wherever required. The voltage grade of<br>cables should be engraved on the marker.  | Yes / No. |         |
| 51. | Tray Identification Number on each run of trays at an interval of 10 Mtrs should be painted.  | Yes / No. |         |
| 52. | In case the outer sheath of a cable is damaged during handling / installation, the same should be repaired to the satisfaction of the site. In case any other part of a cable is damaged, the same should be replaced by a healthy cable. Power cables should be at the top most layers. The armor of control cable is to be earthed. | Yes / No. |         |
| 53. | All cable termination should be appropriately tightened to<br>ensure secure and reliable connections. All the exposed parts<br>of cable lugs should be covered with tape, sleeve or paint.  | Yes / No. |         |
| 54. | Power and control cables are laid on separate cable trays   | Yes / No. |         |
| 55. | Co-axial cable is laid separately from power cable.   | Yes / No. |         |
| 56. | All cable trays, racks and metallic ducts have been grounded<br>by connecting each to earth / mat. ( As per Scheme )  | Yes / No. |         |
| 57. | Check sections of cable trays have been bridged by copper jumpers/ G I to retain continuity of earthing. (As per Scheme)  | Yes / No. |         |
| 58. | Check earthing of panel is done by the erection contractor for connecting it with switchyard earth mat. ( As per Scheme )   | Yes / No. |         |

| SN  | Description of Activity  | Feedback  | Remarks |
|-----|--|-----------|---------|
| 59. | Auxiliary bus wiring for AC and DC supplies, Voltage<br>Transformer circuits, annunciation circuits and other common<br>services is provided near the top of the panels running<br>through out the entire length of the panels.  | Yes / No. |         |
| 60. | All internal wiring to be connected to external equipment is<br>terminated on terminal blocks, preferably vertically mounted<br>on the side of each panel.   | Yes / No. |         |
| 61. | Check whether Mimic Diagram is available preferably made<br>of anodized aluminium or plastic of approved fast colour<br>material and screwed on to the panel that can be easily<br>cleaned.  | Yes / No. |         |
| 62. | Check the panels all equipment mounted on front and rear<br>side as well as equipment mounted inside are provided with<br>individual name plates with equipment designated engraved.   | Yes / No. |         |
| 63. | Check on top of each panel on front as well as rear side, large<br>and bold name plates are provided for circuit / feeder<br>designation.  | Yes / No. |         |
| 64. | Check all front mounted equipments are provided at the rear<br>with individual name plates engraved with tag numbers<br>corresponding to panel internal wiring to facilitate easy<br>tracing of the wiring.  | Yes / No. |         |
| 65. | Check the name plates mounted directly by the side of the respective equipments should not be hidden by equipment wiring.  | Yes / No. |         |
| 66. | Check availability of 240V single phase 50 HZ, AC socket with switch suitable to accept 5 Amps and !5 Amps pin round standard plug, is provided in the interior of each cubicle with ON-OFF switch for connection of hand lamps.   | Yes / No. |         |
| 67. | Check that panels are provided with a fluorescent lighting<br>fixture rated with 240 Volts single phase, 50 Hz supply for<br>the interior illumination of the panel during maintenance. The<br>fittings are complete with switch fuse unit and switching of<br>the lighting is controlled by the respective panel door switch.<br>Adequate lighting with fuse unit is also provided for the<br>corridor in control panels. | Yes / No. |         |
| 68. | Check control panels are provided with necessary<br>arrangements for receiving, distributing, isolating and fusing<br>of DC and AC supplies for various control, signalling,<br>lighting and space heater circuits. The incoming and sub<br>circuits are separately with switch fuse units.  | Yes / No. |         |
| 69. | Check panels are provided with a space heater rated for 240 V, single phase, 50 Hz, AC supply for the internal heating of the panel to prevent condensation of moisture.   | Yes / No. |         |
| 70. | Check all panels are equipped with an earth bus securely fixed   | Yes / No. |         |
| 71. | Check when several panels are mounted adjoining each other,<br>the earth bus is made continuous with necessary connectors<br>and clamps for this purpose.  | Yes / No. |         |
| 72. | Check provision is made for extending the earth bus bars to adjoining panels on either side.   | Yes / No. |         |

| SN  | Description of Activity   | Feedback  | Remarks |
|-----|---|-----------|---------|
| 73. | Check provision is made on each bus bar of the end panels for connecting earthing grid.   | Yes / No. |         |
| 74. | Check all metallic cases of relays, instruments and panel<br>mounted equipment including gland plates are connected to<br>the earth bus by copper wires of specified size.  | Yes / No. |         |
| 75. | Check the colour code of the earthing wire is green.  | Yes / No. |         |
| 76. | Check that earthing made with equipment is with Nuts and<br>Bolts i.e. For such connection lugs should be pressed and<br>tightened to the terminals through Nuts and Bolts. | Yes / No. |         |
| 77. | Check that no equipment is mounted on the panel doors.  | Yes / No. |         |
| 78. | Check each switch should bear clear inscription identifying its function.   | Yes / No. |         |
| 79. | Check those who have sufficient knowledge of steel structural job have been employed in steel structural works only.  | Yes / No. |         |
| 80. | Check necessary instruction has been communicated by<br>supervisor before start of the day's works to workmen under<br>his control.   | Yes / No. |         |
| 81. | Storing of equipments is to be made properly to avoid any accident during handling.   | Yes / No. |         |
| 82. | Check all Nuts and bolts are properly raised or lowered preferably using closed loop pulleys and gully bags / hand bags tied at the end for carrying nuts and bolts.        | Yes / No. |         |
| 83. | Check that Fire resistant sheets are used before entrance of control cable in control room.   | Yes / No. |         |
| 84. | Check air compressor tubing properly tightened.   | Yes / No. |         |
| 85. | Check all carrying connectors / clamps properly tightened.  | Yes / No. |         |

# C. CONDUCTOR LAYOUT DURING CONSTRUCTION STAGE :

| SN | Description of Activity  | Feed back | Remarks |
|----|--|-----------|---------|
| 1. | Check all members are fixed in structure and ensure proper size of<br>Nuts and Bolts are rigidly tightened and punching / tacking / tack<br>welding is done in towers / structures before undertaking conductor<br>laying job. | Yes / No. |         |
| 2. | Ensure proper scaffolding arrangements made during laying of conductor (While Power Line crossing etc).  | Yes / No. |         |
| 3. | Ensure that all members are fitted in structure before undertaking conductor laying work.  | Yes / No. |         |
| 4. | Ensure that the discharge rod is electrically tested before use.   | Yes / No. |         |
| 5. | Ensure whether the structure is properly earthed.  | Yes / No. |         |
| 6. | Only nylon or polypropylene ropes should be used during conductor laying in vicinity of live overhead lines.   | Yes / No. |         |
| 7. | Ensure that PTW has been taken from the concerned authority when<br>extension of existing sub station is under execution.  | Yes / No. |         |
| 8. | Ensure that Winch, Pulleys etc. are properly earthed.  | Yes / No. |         |

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
| 9.  | For LT lines, check whether special persons are posted at each point<br>of isolation till return of permit (PTW) if positioning of person is<br>not possible then it is to be seen that all the point of isolation has<br>been kept in the locked position till the work is in progress.  | Yes / No. |         |
| 10. | Whether the network of LT lines has been thoroughly checked and precautions taken against inadvertent charging.   | Yes / No. |         |
| 11. | Check that proper arrangement is made / available for grounding LT<br>lines coming across during conductor laying. (This can be done by<br>way of portable earthing and short circuiting devices which cab be<br>engaged to and disengaged from LT lines, keeping away from the<br>LT lines until all operations on the same are completed and all man<br>and materials are removed from the LT lines). | Yes / No. |         |
| 12. | Check the provision and proper positioning for the guying and back staying (Where necessary).   | Yes / No. |         |
| 13. | Check working of hydraulic crimping machine.  | Yes / No. |         |
| 14. | Check before and after crimping, dimensional changes in clamps<br>and are in accordance with the drawings and specifications.   | Yes / No. |         |

# **D** Switchyard Earthing during construction stage:

| SN  | Description of Activity  | Feed back | Remarks |
|-----|--|-----------|---------|
| 1.  | Check that while earthing conductor crossing the road is laid 300 mm below the road or at greater depth depending upon the site conditions.      | Yes / No. |         |
| 2.  | Check that while laying the Earthing conductor in outside area is<br>buried at least 600 mm below the furnished ground level.                    | Yes / No. |         |
| 3.  | Check that the earthing pads have been provided for the apparatus / equipments at accessible position.   | Yes / No. |         |
| 4.  | Check all steel columns, metallic stairs are connected to nearby<br>earthing grid conductor by two earthing leads.                               | Yes / No. |         |
| 5.  | Check of earthing of lightening fixtures, receptacles switches, junction boxes lighting conduits has been done by a separate earthing conductor. | Yes / No. |         |
| 6.  | Check that the railway tracks within switchyard area has been earthed at a spacing of 30 Mts. / specified distance and also at both ends.        | Yes / No. |         |
| 7.  | Check cable trays has been connected to earthing flat of 50X6 mm / specified sized earthing flat at intervals specified in approved drawing.     | Yes / No. |         |
| 8.  | Check that this earthed flat is earthed at about 30 Mts. distance.   | Yes / No. |         |
| 9.  | All accessories in transformer and reactor like radiators tank, cooling banks etc are connected to the earthing grid at minimum two points.      | Yes / No. |         |
| 10. | Check metallic conduits are not used as earth continuity conductor.  | Yes / No. |         |
| 11. | Check flexible earthing connectors should be provided for the moving parts.  | Yes / No. |         |

| SN  | Description of Activity   | Feed back | Remarks |
|-----|---|-----------|---------|
| 12. | Check sheath and armor of single core power cable is earthed at switchgear end and equipment side.  | Yes / No. |         |
| 13. | Check contact surface of earthing pads for jointing free from scale, paint, enamel, grease, rust or dust.   | Yes / No. |         |
| 14. | Check that light poles, junction boxes on the poles, cable and cable<br>boxes / glands, lockout switches etc. are connected to the earthing<br>conductor running along with the supply cable which intern is<br>connected to the earthing grid conductor at a minimum two points. | Yes / No. |         |
| 15. | Check earthing conductor which is generally buried 2000 mm outside the switchyard fence. All the gates and every alternate post of the fence are to be connected to earthing grid.  | Yes / No. |         |
| 16. | Check megger used for measuring soil resistivity is calibrated with desired accuracy.   | Yes / No. |         |
| 17. | The earth resistivity has been measured in dry weather condition.   | Yes / No. |         |
| 18. | Check the earthing of Transformers and Shunt reactor, earth pits are constructed as per relevant standard / approved drawing.   | Yes / No. |         |
| 19. | Check that the measured value of combined earth resistance should<br>be less than 1 Ohm.  | Yes / No. |         |
| 20. | Check that for earth electrode and individual earth pits, this value should not be more than one Ohm.   | Yes / No. |         |
| 21. | Check all non current carrying metal parts shall be effectively<br>earthed by two separate and distinct earth connections (Indian<br>Electricity Rule 61,67)  | Yes / No. |         |
| 22. | Check that all pylon supports in the Fire Fighting HVSW system has been earthed to the earthmat.  | Yes / No. |         |

## E: GENERAL POINTS COMMON FOR ALL ACTIVITIES DURING EXCAVATION, CASTING OF FOUNDATION

## Erection of structures, laying of Conductor, storage and transportation of material:

| SN | Description of Activity   | Feed back | Remarks |
|----|---|-----------|---------|
| 1. | Check Supervisors / Workmen have been provided with required<br>healthy PPEs. Like (Safety helmet / Safety Belts / Safety Shoes /<br>Gum Boot etc. as applicable) | Yes / No. |         |
| 2. | Check availability of First Aid Box with required medicines at site.  | Yes / No. |         |
| 3. | Check Site Instruction register is available at site.   | Yes / No. |         |
| 4. | Ensure Supervisor / Gang Leader always issues instruction to the Workmen including contractor labour before start of work.  | Yes / No. |         |
| 5. | Ensure supervisory staff from Power Grid is available at site during construction.  | Yes / No. |         |
| 6. | Check all driver and plant operators are holding valid driving license.   | Yes / No. |         |
| 7. | Check the vehicle for rescue is available at site.  | Yes / No. |         |
| 8. | Ensure engaged labour are aware of the job.   | Yes / No  |         |
| 9. | Ensure supervisor / workmen engaged in the field are aware of First<br>Aid Techniques ( Such as in case of Electric Shock, Fall from the                          | Yes / No. |         |

| SN  | Description of Activity  | Feed back | Remarks |
|-----|--|-----------|---------|
|     | height, Snake bite and the person rescued from buried under the debris, rescue of person from drowning etc.  |           |         |
| 10. | Check for availability and to keep a record of nearby Hospital / Doctor in case of emergencies arises.   | Yes / No. |         |
| 11. | While transporting heavy consignment of conductor / EW drums<br>from central store to site by the use of Cranes, Truck, Tractor. The<br>safety aspect for construction and failure of brake system of moving<br>machinery is to be checked.  | Yes / No. |         |
| 12. | At least one dry powder type of portable fire extinguisher shall be<br>provided especially where explosive or blasting agents are used for<br>excavation. (If applicable)  | Yes / No. |         |
| 13. | Check the competence (Qualification / experience) of supervisor / gang leader of contractor.   | Yes / No. |         |
| 14. | Wire mesh rolls shall be secured in order to prevent dangerous recoiling action.   | Yes / No. |         |
| 15. | Proper unloading arrangement has been made at site (Preferably with crane) to unload the material.   | Yes / No. |         |
| 16. | After unloading the material visual inspection of the materials has<br>been carried out along with the erection contractor to check that the<br>material has not been damaged or not (Galvanizing is proper or not)<br>As per approved Field Quality Plan etc.   | Yes / No. |         |
| 17. | While transporting the heavy laden equipment like transformer /<br>Reactor by road from Rly Stn to Sub station check whether for all<br>safety precaution taken. Like safe lifting capacity of crane, safe load<br>on culvert / Bridge / Nala / Drain etc.and working plan is available<br>at site with specific reference to safety e.g. local earthing, skilled &<br>experience manpower, proper T&P, strength and LT wires / HT<br>wires interrupting the height of equipment and the required<br>clearance maintained etc. Permission to be obtained from concerned<br>authority if required. "Impact recorder on the equipment like<br>Reactor / Transformer must be installed during transportation" | Yes / No. |         |
| 18. | Check that the adequate and safe means of access and aggress has<br>been provided for all work places as far as reasonably practicable<br>and is being used by the workers.  | Yes / No. |         |
| 19. | Check proper illumination is provided at the work places and their approaches including passage ways.  | Yes / No. |         |
| 20. | Check that the lamps have been protected by suitable guards where<br>necessary to prevent danger, in case the lamp breaks.   | Yes / No. |         |
| 21. | Check loose materials which are not required for use shall not be<br>placed or left so as dangerously to obstruct work places or passage<br>ways.  | Yes / No. |         |
| 22. | Check all projected nails has been removed or bent over to prevent injury.   | Yes / No. |         |
| 23. | Check scrap, waste and rubbish has not been allowed to<br>accommodate on the site or the scrap materials has been stored at<br>the isolated place.   | Yes / No. |         |
| 24. | Check that the worker while working at height scaffold materials, waste materials and tools are not being thrown by them to cause injury to any person.  | Yes / No. |         |

| SN  | Description of Activity  | Feed back | Remarks |
|-----|--|-----------|---------|
| 25. | Check whether contractor has procured required quantity of PPE considering maximum number of erection gangs deployed at one time. Check the quantity of PPEs.  | Yes / No. |         |
| 26. | Check that the PPEs required by the workmen are being utilized by them always.   | Yes / No. |         |
| 27. | Check the worker is under constant surveillance by the other person while working at height.   | Yes / No. |         |
| 28. | Check construction site has been barricaded for unauthorized persons / animals.  | Yes / No. |         |
| 29. | Check that lifting appliances and machines and vehicles used on the construction site is of sound material and good quality and is free from patent defects and is strong enough to with safely the load and stresses to which they will be subjected. | Yes / No. |         |
| 30. | Check structures and equipment is being used only for the purpose<br>for which they were intended.   | Yes / No. |         |
| 31. | Check equipment has been operated by the competent person.   | Yes / No. |         |
| 32. | Check portable ladders shall not exceed 9 Mts. in length, other wise<br>may cause danger while climbing of person and back legs shall be<br>equally braced.  | Yes / No. |         |
| 33. | Check unskilled labour are not utilized for skilled jobs and only<br>experience persons are deployed for erection.   | Yes / No. |         |
| 34. | Check a well planed and documented procedure for the entire<br>Construction works of Sub station shall be prepared by contractor<br>and get approved from Power Grid for distribution to Contractors'<br>field staff and Power Grid for follow up.     | Yes / No. |         |
| 35. | Check no metallic measuring tapes are being used during expansion of charged bays.   | Yes / No. |         |
| 36. | Check metal ladders are not being used in the vicinity of exposed live electrical equipment.   | Yes / No. |         |
| 37. | Check one bore well is available for water supply in case Municipal<br>Construction supply is not available  | Yes / No. |         |
| 38. | Check charged area of a yard should be properly fenced off.  | Yes / No. |         |
| 39. | Check ladders / lengthy articles / lengthy equipments etc. should always be carried in horizontal position.  | Yes / No. |         |
| 40. | Check insurance by contractor for the labour to provide adequate coverage for any accident etc.  | Yes / No. |         |

## **REMARKS IF ANY:**

| Signature       | Signature            | Signature     |
|-----------------|----------------------|---------------|
|                 |                      |               |
|                 |                      |               |
| Name :          | Name :               | Name :        |
| Designation:    | Designation:         | Designation : |
| Power Grid Rep. | Rep. from Contractor | Rep. from     |
|                 |                      |               |