Draft Initial Environmental Examination

August 2014

IND: Rajasthan Urban Sector Development Program – Water Supply and Sewerage in Sri Ganganagar

Prepared by Rajasthan Urban Infrastructure Development Project, Government of Rajasthan for the Asian Development Bank.

CURRENCY EQUIVALENTS

(as of 28 August 2014) ency unit – rupee (INR)

``	5	/
Currency unit	-	rupee (INR)
INR1.00	=	\$0.016
\$1.00	=	INR 60.3395
ψ1.00	_	INIX 00.553

ABBREVIATIONS

ADB	_	Asian Development Bank
AC	_	Asbestos Cement
AE	_	Assistant Engineer
ADB	_	Asian Development Bank
ASI	_	Archeological Survey of India
ASO	_	Assistant Safeguards Officer
CAPC	_	Community Awareness and Participation Consultant
CFE	_	Consent for Establishment
CFO	_	Consent for Operation
CPCB		Central Pollution Control Board
EA	-	Executing Agency
EAC	_	Expert Appraisal Committee
EC	_	Environmental Clearance
EHS	_	Environmental Health & Safety
EIA	-	Environmental Impact Assessment
SEIAA	_	State Environmental Impact Assessment Authority
EMP	_	Environmental Management Plan;
GOI	-	Government of India
GOR	-	Government of Rajasthan
IA	-	Implementing Agency
IEE	-	Initial Environmental Examination;
PIU	-	Project Implementation Unit;
PMU	-	Project Management Unit
LSGD	-	Local Self Government Department
MOEF	-	Ministry of Environment and Forest
MLD	-	Million Liters per Day
LPCD	-	Liters per Capita per Day
PE	-	Polyethylene
DWC	-	Double Corrugated Duct
NHAI	-	National Highways Authority of India
NOC	-	No Objection Certificate
PHED	-	Public Health Engineering Department
PO	-	Project Officer
PMDSC	-	Project Management, Design and Supervision Consultant
PPTA	-	Project Preparatory Technical Assistance
PWD	-	Public Works Department
REA	-	Rapid Environmental Assessment Checklist
RoW	-	Right of Way
RPCB	-	Rajasthan Pollution Control Board
RUIDP	-	Rajasthan Urban Infrastructure Development Project
RUSDP	-	Rajasthan Urban Sector Development Program
SPS	-	Safeguard Policy Statement, 2009
STP	-	Sewage Treatment Plant

SGNP	-	Sri Ganganagar Nagar Parishad

ULB	-	Urban Local Body	
WTP	_	Water Treatment Plant	

WEIGHTS AND MEASURES

°C	Degree Celsius
km	kilometre
lpcd	litres per capita per day
mm	milli meter
m	metre
MLD	million litres per day
mm	millimetre
Nos	Numbers
Sq.km	Square Kilometer

NOTE{S}

In this report, "\$" refers to US dollars. "INR" and "₹" refer to Indian rupees

This initial environmental examination is a document of the borrower. The views expressed herein do not necessarily represent those of ADB's Board of Directors, Management, or staff, and may be preliminary in nature.

In preparing any country program or strategy, financing any project, or by making any designation of or reference to a particular territory or geographic area in this document, the Asian Development Bank does not intend to make any judgments as to the legal or other status of any territory or area

TABLE OF CONTENTS

EXEC	CUTIVE SUMMARY	
I.	INTRODUCTION A. Background B. Background of IEE C. Environmental Regulatory Compliance D. Scope of IEE E. Report Structure	1 1 1 5 5
11.	 DESCRIPTION OF THE PROJECT A. Present Situation B. Infrastructure Improvements Proposed in Ganganagar under RUSDP C. Energy Efficiency Measures included in the subproject D. Investment Program Implementation Schedule 	5 5 7 8 8
III.	 DESCRIPTION OF THE ENVIRONMENT A. Physical Resources B. Ecological Resources C. Economic Development D. Socio Cultural Resources E. Environmental Settings of Investment Program Component Sites 	13 13 16 16 18 20
IV.	 ANTICIPATED ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES A. Introduction B. Pre-Construction Impacts C. Construction Impacts D. Operation and Maintenance Impacts 	20 20 21 23 30
V.	PUBLIC CONSULTATION AND INFORMATION DISCLOSURE A. Overview B. Public Consultation C. Information Disclosure	32 32 33 34
VI.	GRIEVANCE REDRESS MECHANISM A. Project Specific Grievance Redress Mechanism B. Grievance Redress Process	34 34 35
VII.	 ENVIRONMENTAL MANAGEMENT PLAN A. Environmental Management Plan B. Institutional Requirements C. Training Needs D. Monitoring and Reporting E. EMP Implementation Cost 	36 36 56 60 61 62
VIII.	CONCLUSION AND RECOMMENDATION	63

APPENDIXES:

1.	REA Check list	66
2.	National Ambient Air Quality Standards	71
3.	National Ambient Air Quality Standards in Respect of Noise	72
4.	General Standards for Discharge of Environmental Pollutants (Wastewater)	73
5.	Vehicle Exhaust Emission Norms	74
6.	Drinking Water Standards	75
7.	Compliance with Environmental Criteria for Subproject Selection	78
8.	Salient Features of Applicable Major Labor Laws	80
9.	Sample Outline Spoil Management Plan	82
10.	Sample Outline Traffic Management Plan	83
11.	Public Consultations Conducted During Project Preparation	93
12.	Sample Monthly Reporting Forma	98
13.	Sample Environmental Site Inspection Report	103
14.	Sample Grievance Registration Form	105

EXECUTIVE SUMMARY

1. The proposed Rajasthan Urban Sector Development Program (RUSDP) will complement the past and ongoing efforts of Government of Rajasthan (GoR) to improve water supply and wastewater services to the residents of the state of Rajasthan. The program component of the RUSDP will support policy reforms and consolidate institutional development and governance improvement in the urban sector in the state, while the investment component of the RUSDP will invest in water distribution network improvements and sewerage systems in the six project cities¹ each having a population of more than 100,000, and identified considering the lack of basic services at present and willingness to undertake reforms and institutional restructuring. RUSDP will be implemented over a 5-year period beginning in March 2015, and will be funded by ADB via a Sector Development Program (SDP) loan modality.

2. Sri Ganganagar Town water supply and sewerage subproject is one of the subprojects proposed under the RUSDP. Water supply at present in Ganganagar is intermittent, unreliable and suffers with huge losses and quality issues. There is no sewerage system in the town. Currently, sewerage project is under implementation by Ganganagar Urban Improvement Trust with technical support of the RUIDP Project Management Unit (PMU). Due to lack of sewerage system, most of the households depend on septic tanks for disposal of sewage. Effluent from septic tanks and sullage is let off into open drains which ultimately discharge into streams and ponds.

3. ADB requires consideration of environmental issues in all aspects of the Bank's operations, and the requirements for Environmental Assessment are described in ADB's SPS (2009). This Initial Environmental Examination (IEE) addresses the infrastructure components proposed under Ganganagar water supply and sewerage subproject.

4. **Categorization.** Ganganagar water supply and sewerage subproject is classified as Environmental Category B as per the SPS as no significant impacts are envisaged. Accordingly, this Initial Environmental Examination (IEE) assesses the environmental impacts and provides mitigation and monitoring measures to ensure that there are no significant impacts as a result of the project.

5. **Project Scope**. The subproject is formulated to address gaps in water and sewerage infrastructure in a holistic and integrated manner. The main objective of the RUSDP is to improve water efficiency, security, and provide safe sewage collection, and with the on-going investments in sewage treatment, this will have an important effect on public health and environment. Investments under this subproject include: (i) water distribution network improvement (37 km new and 668 km replacement); (ii) provision of bulk water meters (iii) provision of house service connections with consumer meters; (iv) laying new sewers (417 km); and (v) provision of sewer connections to houses.

6. **Implementation Arrangements.** The Local Self Government Department (LSGD) of Government of Rajasthan will be the Executing Agency (EA) and existing RUIDP will be the Implementing Agency (IA). The LSGD will be responsible for overall strategic planning, guidance and management of the RUSDP, and for ensuring compliance with tranche release conditions and loan covenants. A policy support unit will be established in the LSGD to support the government for implementation of the tranche release policy actions under the program

¹ Pali, Tonk, Ganganagar, Jhunjhunu, Bhilwara and Hanumangarh.

loan. The RUIDP will be responsible for planning, implementation, monitoring and supervision, and coordination of all activities under the RUSDP. The RUIDP will recruit two consulting firms – (i) project management, design and supervision consultant (PMDSC), and (ii) community awareness and participation consultant (CAPC) to provide support in implementation of RUSDP. Six Project Implementation Units (PIUs), one each of in six project towns, shall be set up directly to assist in implementation. PMU will support PIUs in implementation, management and monitoring of the project. PMU and PIUs will be assisted by PMDSC and CAPC. PIUs will appoint construction contractors to build infrastructure. Once the infrastructure is built and commissioned, the Urban Local Bodies will operate and maintain the infrastructure. Project Officer (Environment) at PMU and Assistant Safeguard Officer (ASO) at each of the PIUs will be responsible for environment management and monitoring activities, and will be supported by Environment, Health and Safety (EHS) supervisor.

7. **Description of the Environment.** Subproject components are located in Ganganagar Town and in its immediate surroundings which were converted into urban use for many years ago, and there is no natural habitat left at these sites. The project sites are located in existing road right of way (RoW) and government-owned lands. There are no protected areas, wetlands, mangroves, or estuaries in or near the project locations. Soils are deep, and do not require cutting of rocks for pipe laying.

8. **Environmental Management.** An environmental management plan (EMP) is included as part of this IEE, which includes (i) mitigation measures for environmental impacts during implementation; (ii) an environmental monitoring program, and the responsible entities for mitigating, monitoring, and reporting; (iii) public consultation and information disclosure; and (iv) a grievance redress mechanism. A number of impacts and their significance have already been reduced by amending the designs. The construction phase EMP will be included in civil work bidding and contract documents.

9. Locations and siting of the proposed infrastructures were considered to further reduce impacts. These include (i) locating facilities on government-owned land to avoid the need for land acquisition and relocation of people; and (ii) laying of pipes in RoW alongside main/access roads, to reduce acquisition of land and impacts on livelihoods specifically in densely populated areas of the town.

10. Potential impacts were identified in relation to location, design, construction and operation of the improved infrastructure. During the construction phase, impacts mainly arise from the need to dispose of moderate quantities of waste soil and disturbance of residents, businesses, and traffic. These are common temporary impacts of construction in urban areas, and there are well developed methods for their mitigation. Mitigation measures have been developed to reduce all negative impacts to acceptable levels. Resettlement Plan prepared for the Ganganagar Subproject addresses temporary resettlement/livelihood issues resulting mainly from laying of sewer/pipelines in busy commercial areas.

11. Measures such as appropriate scheduling of works (non-monsoon season, low traffic hours, etc.,) and minimizing inconvenience by best construction methods will be employed. Traffic management plan will be prepared for pipe/sewer-laying works on busy roads. In the operational phase, all facilities and infrastructure will operate with routine maintenance, which should not affect the environment. Facilities will need to be repaired from time to time, but environmental impacts will be much less than those of the construction period as the work will

be infrequent, affecting small areas only. Measures are included to prevent industrial discharges into sewers, which may affect the working of sewage treatment plants.

12. Mitigation measures have been developed to reduce all negative impacts to acceptable levels. Mitigation will be assured by a program of environmental monitoring to be conducted during construction. The environmental monitoring program will ensure that all measures are implemented, and will determine whether the environment is protected as intended. It will include observations on- and off-site, document checks, and interviews with workers and beneficiaries. Any requirements for corrective action will be reported to the ADB.

13. The stakeholders were involved in developing the IEE through discussions on-site and public consultation, after which views expressed were incorporated into the IEE and in the planning and development of the project. The IEE will be made available at public locations in the city and will be disclosed to a wider audience via the ADB, RUIDP and PMU websites. The consultation process will be continued and expanded during project implementation to ensure that stakeholders are fully engaged in the project and have the opportunity to participate in its development and implementation.

14. The citizens of the Ganganagar town will be the major beneficiaries of this subproject. With the improved water supply, they will be provided with a constant supply of better quality water, piped into their homes. The sewerage system will remove the human waste from their homes safely and quickly. Combined with the on-going investments in sewage treatment, this subproject, in addition to improved environmental conditions, will improve the over-all health condition of the town. People would spend less on healthcare and lose fewer working days due to illness, so their economic status should also improve, as well as their overall health.

15. **Consultation, Disclosure and Grievance Redress.** Public consultations were done in the preparation of the project and IEE. Consultations will continue throughout the project implementation period with the assistance of the NGOs. A grievance redress mechanism is described within the IEE to ensure any public grievances are addressed quickly.

16. **Monitoring and Reporting.** The PMU and PMDS consultants will be responsible for monitoring. The PMDSC will submit monthly/semi-annual monitoring reports to PMU, and the PMU will review and send the semi-annual monitoring reports to ADB. ADB will post the environmental monitoring reports on its website.

17. **Conclusions and Recommendations.** The proposed project is therefore unlikely to cause significant adverse impacts. The potential impacts that are associated with design, construction and operation can be mitigated to standard levels without difficulty through proper engineering design and the incorporation or application of recommended mitigation measures and procedures. Based on the findings of the IEE, there are no significant impacts and the classification of the project as Category "B" is confirmed. No further special study or detailed environmental impact assessment (EIA) needs to be undertaken to comply with ADB SPS (2009) or Gol EIA Notification (2006).

I. INTRODUCTION

A. Background

1. **Project background and context**. The proposed Rajasthan Urban Sector Development Program (RUSDP) will complement the past and ongoing efforts of Government of Rajasthan (GoR) to improve water supply and wastewater services to the residents of the state of Rajasthan. The program component of the RUSDP will support policy reforms and consolidate institutional development and governance improvement in the urban sector in the state, while the investment component of the RUSDP will invest in water distribution network improvements and sewerage systems in the six project cities² each having a population of more than 100,000, and identified considering the lack of basic services at present and willingness to undertake reforms and institutional restructuring. RUSDP will be implemented over a 5-year period beginning in March 2015, and will be funded by ADB via a Sector Development Program (SDP) loan modality. The expected impact of the RUSDP will be sustainable urban development in Rajasthan. The expected outcome will be improved urban service delivery in Rajasthan. RUSDP will have five outputs, out of which Outputs 1 and 2 will be supported by the program component, while Outputs 3, 4 and 5 will be supported by the investment component.

2. The focus of the RUSDP investment will be on water supply and sewerage infrastructure. A series of subprojects will be implemented under the Project, with each subproject providing improvements to water supply or sewerage or both in a project town

B. Background of IEE

3. Ganganagar Town water supply and sewerage subproject is one of the subprojects proposed in RUSDP. Water supply is currently intermittent, and suffers with huge losses and quality issues. There is no sewerage system exists in the town. ADB requires the consideration of environmental issues in all aspects of the Bank's operations, and the requirements for environmental assessment are described in ADB's Safeguards Policy Statement (2009). Accordingly, this Initial Environmental Examination (IEE) has been conducted to assess the environmental impacts and provide mitigation and monitoring measures to ensure that there are no significant impacts as a result of the subproject.

C. Environmental Regulatory Compliance

4. Table 1 presents a summary of environmental regulations and mandatory requirements applicable to Ganganagar Town water supply and sewerage subproject.

Law	Description	Requirement
EIA Notification	The EIA Notification of 2006 set out the requirement for environmental assessment in India. Environmental Clearance is required for certain defined activities/projects, and this must be obtained before any construction work or land preparation (except land acquisition) may commence. Projects are	Project is not a listed activity in Schedule I of this notification and hence environmental clearance is not required.
	scale of the project and the nature of its	

Table 1: Applicable Environmental Regulations

² Pali, Tonk, Ganganagar, Jhunjhunu, Bhilwara and Hanumangarh.

Law	Description	Requirement
	impacts. Category A projects require Environmental Clearance from the Ministry of Environment and Forest (MoEF). Category B projects require Environmental Clearance from the State Environmental Impact Assessment Authority (SEIAA).	
Water (Prevention and Control of Pollution) Act of 1974, Rules of 1975, and amendments	Act was enacted to provide for the prevention and control of water pollution and the maintaining or restoring of wholesomeness of water, by Central and State Pollution Control Boards and for conferring on and assigning to CPCB/SPCBs powers and functions relating to water pollution control. Control of water pollution is achieved through administering conditions imposed in consent issued under provision of the Water (Prevention and Control of Pollution) Act of 1974. These conditions regulate the quantity and quantity of effluent, the location of discharge and the frequency of monitoring of effluents. Any component of the subproject having the potential to generate sewage or trade effluent will come under its purview. Such projects have to obtain Consent For Establish (CFE) under Section 25 of the Act from Rajasthan Pollution Control Board (RPCB) before starting implementation and Consent For Operate (CFO) before commissioning.	Not applicable
Air (Prevention and Control of Pollution) Act of 1981, Rules of 1982 and amendments.	This Act was enacted to achieve prevention, control and abatement of air pollution activities by assigning regulatory powers to Central and State boards for all such functions. The Act also establishes ambient air quality standards The projects having potential to emit air pollutants into the atmosphere have to obtain CFE and CFO under Section 21 of the Act from RPCB The occupier of the project/facility has the responsibility to adopt necessary air pollution control measures for abating air pollution.	Not applicable
Environment (Protection) Act, 1986 and CPCB Environmental Standards.	Emissions and discharges from the facilities to be created or refurbished or augmented shall comply with the notified standards	Appendix 2 provides applicable standards for ambient air quality.
Noise Pollution (Regulation and Control) Rules, 2000 amended up to 2010.	Rule 3 of the Act specifies ambient air quality standards in respect of noise for different areas/zones.	Appendix 3 provides applicable noise standards.
Ancient ivionuments	The Act designates areas within 100 meters	There are no ASI protected

Law	Description	Requirement
and Archaeological Sites and Remains Act, 1958 and Ancient Monuments and Archaeological Sites and Remains (Amendment and Validation) Act, 2010	(m) of the "protected monument/area" as "prohibited area" and beyond that up to 200 m as "regulated area" respectively. No "construction" is permitted in the "prohibited area" and any construction activity in the "regulated area" requires prior permission of the Archaeological Survey of India (ASI).	monuments/sites in Ganganagar. Archeological potential is negligible. However, in case of chance finds, the contractors/PIU will be required to follow a protocol as defined in the Environmental Management Plan (EMP).
Rajasthan State Environment Policy, 2010 including And Rajasthan Environment Mission and Climate Change Agenda for Rajasthan (2010-14)	Follows the National Environment Policy, 2006 and core objectives and policies are: - Conserve and enhance environmental resources; assure environmental sustainability of key economic sectors; and, improve environmental governance and capacity building - it recommends specific strategies and actions to address the key environmental issues: water resources, desertification and land degradation, forest and biodiversity, air quality, climate change: adoption and mitigation, mining, industry, tourism, energy, urban development, etc. - Establishment of Environment Mission under the chairpersonship of the Chief Minister and a Steering Committee under the chairpersonship of Chief Secretary, Government of Rajasthan Tasks force set up for six key areas	 Project implementation should adhere to the policy aims of: conservation & enhancement of environmental resources, integration of environmental concerns into projects/plans, and capacity building in environmental management under water sector, major concerns, as the policy notes, are: huge water losses & wastage, declining water availability, pollution Relevant recommendations for the project include: control of losses, integrated water resources management, control of raw water pollution, reuse and recycling avoid/minimize use of forest lands With reference to Climate change adoption & mitigation following should be considered in the project: diminishing flows in surface water bodies, and groundwater depletion, and revival traditional water bodies as water sources (lakes/tanks) equal stress on demand side management in water minimize energy use - design energy efficiency systems-
The Rajasthan Monuments, Archaeological Sites and Antiquities Act, 1961; the Rajasthan Monuments, Archaeological Sites and Antiquities (amendment) Act 2007	Any construction/excavation work in the 'protected area' (as declared by GoR under the Act) requires priori permission of Department of Archeology & Museums -Application under the Rules shall be submitted to Director, State Archeological Department, at least 3 months prior to the work. Department provides conditional permission, including time for completion, procedures to be followed during the work and for chance finds etc.	There are no monuments in the town. However, in case of chance finds, the contractor/PIU will be required to follow a protocol as defined in the Environmental Management Plan (EMP).

Law	Description	Requirement
The Right to fair compensation and transparency in land acquisition, rehabilitation and resettlement Act,	Private land acquisition is guided by the provisions and procedures of this Act.	Not applicable to this subproject as there is no private land acquisition or resettlement
2013		
Labor Laws	The contractor shall not make employment decisions based upon personal characteristics unrelated to job requirements. The contractor shall base the employment relationship upon equal opportunity and fair treatment, and shall not discriminate with respect to aspects of the employment relationship, including recruitment and hiring, compensation (including wages and benefits), working conditions and terms of employment or retirement, and discipline. The contractor shall provide equal wages and benefits to men and women for work of equal value or type.	Appendix 7 provides applicable labor laws including amendments issued from time to time applicable to establishments engaged in construction of civil works.
Biodiversity Act of 2002	The Biodiversity Act 2002 primarily addresses access to genetic resources and associated knowledge by foreign individuals, institutions or companies, to ensure equitable sharing of benefits arising out of the use of these resources and knowledge to the country and the people.	Not applicable
Ramsar Convention, 1971	The Ramsar Convention is an intergovernmental treaty that provides the framework for national action and international co-operation for the conservation and wise use of wetlands and their resources. India is one of the signatories to the treaty. The Ramsar convention made it mandatory for the signatory countries to include wetland conservation in their national land use plans.	There are no Ramsar sites in Ganganagar. Not applicable to Ganganagar water supply and sewerage subproject
Wildlife Protection Act, 1972	This overarching Act provides protection to wild animals, birds, plants and matters connected with habitat protection, processes to declare protected areas, regulation of wildlife trade, constitution of state and national board for wildlife, zoo authority, tiger conservation authority, penalty clauses and other important regulations.	Not applicable
(Conservation) Act, 1980	use of forest land for non-forest purposes without the approval of Ministry of Environment and Forests (MoEF), Government of India	
Rajasthan Forest	This Act makes the basis for declaration of	Not applicable
Act, 1953 and	Reserved Forests, constitution of village	
Rajasthan Forest	torest committees, management of reserved	

Law	Description	Requirement
Rules, 1962	forests and penalties and procedures.	

5. The ADB guidelines stipulate addressing environmental concerns, if any, of a proposed activity in the initial stages of project preparation. For this, the ADB SPS categorizes the proposed projects into various categories (A, B or C) to determine the level of environmental assessment required to address the potential impacts. Level of environmental assessment required for each category is presented below.

- (i) **Category A:** Projects with potential for significant adverse environmental impacts. An Environmental Impact Assessment (EIA) is required to address significant impacts.
- (ii) Category B: Projects likely to have some adverse environmental impacts, but of lesser degree and/or significance than those for Category A. An initial environmental examination (IEE) is required to determine whether significant environmental impacts warranting an EIA are likely. If an EIA is not needed, the IEE is regarded as the final environmental assessment report.
- (iii) **Category C:** Projects unlikely to have adverse environmental impacts. No EIA or IEE is required, although environmental implications are still reviewed.

6. The environmental impacts of Ganganagar water supply and sewerage subproject have been identified and assessed as part of the planning and design process. An environmental assessment using ADB's Rapid Environmental Assessment Checklist for Water Supply and Sewerage (**Appendix 1**) was conducted, and results of the assessment show that the subproject is unlikely to cause significant adverse impacts. Thus, this IEE has been prepared in accordance with ADB SPS's requirements for environment category B projects.

D. Scope of IEE

7. The IEE was based mainly on secondary sources of information and field reconnaissance surveys; no field monitoring (environmental) survey was conducted. Stakeholder consultation was an integral part of the IEE.

E. Report Structure

This Report contains nine (9) sections: (i) Executive summary; (ii) Introduction and regulatory framework (iii) Description of the project (iv) description of the environment; (v) Anticipated environmental impacts and mitigation measures; (vi) public consultation and information disclosure; (vii) Grievance redress mechanism; (viii) Environmental management plan, and, (ix) Conclusion and recommendation.

II. DESCRIPTION OF THE PROJECT

8. Sri Ganganagar is headquarter of Sri Ganganagar District, and is situated in the northern most part of Rajasthan State, close to international border with Pakistan. It is located at about 470 km north of State Capital, Jaipur and 425 km northwest of the National Capital, Delhi. Sri Ganganagar is one of the six project towns selected for implementation of the ADB funded Rajasthan Urban Sector Development Program (RUSDP).

A. Present Situation

9. **Water Supply**. Gang canal, of Sutlej River Canal system, is the main source of water supply to Ganganagar Town. Two intake points, one on distributary at Sadhuwala head and

second one at 68-69 RD. Raw water is pumped to the existing water treatment plants (WTPs) at Old & New Head works in PHED campus. Treated water is collected in clear water reservoirs (CWRs) at WTPs and pumped to zonal elevated service reservoirs (ELSRs) for distribution by gravity.

10. Water supply system in Ganganagar consists of (i) 2 WTPs with a total capacity of 42 MLD; (ii) 24 elevated service reservoirs of total capacity 19.97 ML (consisting of 18 elevated and 6 ground level reservoirs); (iii) 43 km of raw and clear water transmission mains; and (iv) 673 km of distribution network. At present, 80% of the total town area is covered with the piped water supply system. About 61% of the households are serviced through individual water service connections. Water supply is intermittent – 1.5 hours to 3 hours of supply daily. Water is also supplied through public stand-posts (mainly in urban poor areas). House service connections are metered; however, presently meters 65 percent are non-functional. The newly developing outer areas of the town do not have water supply system.

11. While gross water supply rate is over 162 litres per capita per day (LPCD), the water provided at consumer end is 116 LPCD, which less than standard of 135 LPCD. This is due to heavy losses in the existing distribution network – bulk flow measurement study during the project preparation indicates water losses (physical leakage) in the range of 28%, while total non-revenue water is 50%. The water transmission and distribution network is old, profusely leaking and is badly in need of rehabilitation and replacement.

12. **Sewerage.** There is no sewerage system in Sri ganganagar, Most of the households in the town have individual toilets. Open defecation is also prevalent. Due to lack of sewerage system, people depend on septic tanks for disposal of sewage. Since there is no soak pit arrangement, effluent from septic tanks is directly let into open drains. Due to poor maintenance, septic tanks do not function properly and often overflow into drains, which will ultimately joins depression areas, creating unsanitary conditions and water/land pollution.

13. At present a sewerage project is under implementation in Sri Ganganagar. This project is financially supported by the centrally sponsored scheme of Urban Infrastructure Development in Small and Medium Towns (UIDSMT). Sri Ganganagar Urban Improvement Trust (UIT) is implementing this project with technical support of RUIDP PMU. This project includes 38 km of trunk sewers to collect and transfer sewage from open drains to treatment plants, and three Sewage Treatment Plants (STP) of total capacity (10 MLD + 10 MLD + 15 MLD). Currently, work is in progress and scheduled to be completed by March 2016.

B. Infrastructure Improvements Proposed in Ganganagar under RUSDP

14. **Water Supply**. It is projected that the water demand of the town will increase from 41 MLD in 2016 to 54 MLD in 2031, and ultimately to 71 MLD by 2046. The water availability from Gang canal is sufficient to cater the demand. Current storage capacity in the town is adequate for next 15 years. Water transmission and distribution network is old, profusely leaking and is badly in need of rehabilitation and replacement.

15. In RUSDP, under water supply component of the Ganganagar Subproject, it is proposed to provide a strategic water supply network connecting CWRs with ELSRs, in the form of a ring main that will supply water to all ELSRs. It is proposed to replace entire existing distribution network with new PE pipes with electro-fusion welded joints and electro-fusion saddles. The new distribution system will be conveniently divided into District Metering Areas consisting about 500 to 700 connections with flow from one direction to facilitate monitoring the NRW. Project will also provide bulk water meters, house service connections with consumer meters.

16. **Sewerage**. Sewage collection and conveyance network is proposed for Ganganagar Town under this RUSDP. This network will be synchronized with the ongoing sewerage project. The network developed under RUSDP will collect sewage from houses and convey to the trunk sewers for further conveyance to the STPs. As stated earlier, trunk sewers and STPs are under construction in Ganganagar. The sewer network will cater to the entire town, barring the outer areas with low population density (100 persons/hectare). Of the total base year population (2016) of 261,231, this subproject will cover 70% of the population. The rest 30% population, residing in the outer areas with low population density, will continue to depend on individual septic tank and soak pit arrangements. The sewer system will be designed as a separate sewer system that carries only the domestic wastewater, the open drain system that exists in the town will cater to storm runoff.

17. This subproject complies with the environmental subproject selection criteria agreed between the government and the ADB (Compliance checklist is at Appendix 7).Following Table 2 shows the nature and size of the various components of the subproject. Conceptual layout plans are shown in Figure 1 to Figure 3.

Infrastructure	Function	Description	Location
1. Water Supply		•	
Distribution network Improvement	To distribute water from service reservoirs to consumers	<i>Replacement</i> - 668 km 63-600 mm dia DI/PE pipes <i>New</i> 37 km 63-600 mm dia DI/PE pipes	Pipes will be laid underground' along the roads; this work will cover entire town as all the existing pipes is proposed to be replaced, and in currently uncovered areas new pipes will be laid About 80% of exiting pipes are of AC; and therefore existing pipes will be left as it is in the ground untouched.
Bulk Water	Monitor water flow	New	Fixed at strategic

Table 2: Proposed Water Supply & Sewerage Subproject & Components

Meters	in the improved network	36 no,s Bulk Meters	locations at source, CWR and network
Domestic Meters	Monitor & regulate water usage by consumers and improve cost recovery	<i>New</i> 44341 Domestic Meters,	Meters will be attached to the water delivery pipe at each house with meter chamber
2. Sewerage			
Sewer network and house connections	Collect wastewater from dwelling units and convey by gravity to the STP	<i>New</i> 417 km; 200 to 900 mm diameter DWC pipes for sewers and MDPE for house connections	Sewers will be laid underground along the roads in the town. The work will extend to most of the town area, except the core town area where sewers are being laid

18. Excavation for the pipe/sewer laying works will be undertaken through open trenching, which will be maximum width of 1 m only on one side of the road ROW with maximum length, an average 140 m per day for water supply lines and 70 m for sewers. Excavation, laying of pipes and backfilling will be completed within the day. Subsequent to completion of works, road reinstatement will be undertaken by the contractor as part of the civil works. The same shall be mentioned in the bid document to make it binding on the contractor.

19. The subproject is primarily designed to improve environmental quality and living conditions of Ganganagar through provision of water supply and sewerage. The benefits arising from this subproject include: (i) increased availability of potable water at appropriate pressure to all households including urban poor; (ii) reduced time and costs in accessing alternative sources of water. (iii) better public health particularly reduction in waterborne and infectious diseases; (iv) reduced risk of groundwater contamination; (v) reduced risk of contamination of treated water supplies; and, (vi) improvement in quality of water bodies due to disposal of treated effluent meeting disposal standards.

C. Energy Efficiency Measures included in the subproject

20. Both the water supply and sewer network in Ganganagar are designed with utmost consideration to energy efficiency. Gravity flow systems adopted. In existing water supply system, water losses (UFW) are very high, reducing the losses and improving the efficiency of the system is identified as the most important component under RUSDP. This is considered as an alternative for source development/augmentation.

21. To make the project energy efficient, as part of this PPTA, "Guidelines for Adopting Eco-Friendly and Energy Efficient Equipment and Facilities in the Design of the Sub-Projects" have been prepared and is being followed in the design of the projects. Accordingly, energy efficiency measures are being considered and incorporated into the subproject designs where appropriate.

D. Investment Program Implementation Schedule

22. The detailed design of this subproject will be completed by May 2014. After the approval, bid will be prepared and tenders invited by September 2014, and the contract will be awarded by January 2015. Construction is likely to start in February 2015, and will take about 36 months, i.e. the construction work is likely to be completed by February 2018. This schedule is

compatible with the on sewerage scheme which is scheduled to be completed by March 2016. All the STPs should be operational before the completion of this project in February, 2018.



Figure 1: Proposed Distribution Network Improvement



Figure 2: Proposed Sewer Network Coverage



III. DESCRIPTION OF THE ENVIRONMENT

A. Physical Resources

1. Location, Area & Connectivity

23. Sri Ganganagar is the administrative headquarters of Ganganagar District, and is situated in the northern most part of Rajasthan state in western India. Geographically, the town is located at 29°55'N latitude and 73°19'E longitude at a height of 177 m above Mean Sea Level (MSL). Ganganagar District's western boundary forms international border with Pakistan, and is about 30 km from the town. District also shares borders with neighboring states of Punjab and Haryana.

24. Located at about 470 km north of State Capital, Jaipur and 425 km northwest of the National Capital, Delhi, it is well connected by Road and Rail. National Highway 15 (NH 15) connecting Samakhiali in Gujarat with Pathankot in Punjab passes through the town. This highway connects all important towns along the western boarder of the country. This highway in turn connects several other highways, and provides good connectivity to Ganganagar. Besides, there is a state highway and other district roads connecting surrounding towns and its hinterland. Ganganagar is an important railway head in this, and is well connected with Delhi, Jaipur and other towns. The Nearest airport is at Amritsar (271 km).

25. Town was named after Maharaja Shri Ganga Singh Bahadur, Maharaja of Bikaner. Sri Ganganagar is one of the well planned cities of India, and believed to be influenced by the town planning of Paris. Owing to good irrigation facilities, and agricultural lands, district produces large quantities of wheat, grains etc., and is referred as "the food basket of Rajasthan" and "green district of Rajasthan". Extending to an area of 19.217 sq.km in the jurisdiction of Sri Ganganagar Nagar Parishad (Municipal Council), the population of the town is 237,780 (2011 Census). The town is divided into 55 municipal wards.

2. Topography, Soils and Geology

26. Topography of the town is plain and the elevation ranges from 174 m - 178 m above the MSL, and gently slopes towards southwest. Due to low rainfall and desert environment, natural drainage system is very poorly developed. There are no water bodies, rivers or streams in or near the town. There are two natural depressions in the town - one near Balmiki Mandir and other at Idgah area, in which water (mostly wastewater) is accumulated.

27. The geology of the area is overlain by the thick blanket of dunal sand and alluvial deposits of quaternary age. No rock exposure at the ground surface occurs in the area. Sand dunes consist of silt & fine grained sand which are brownish, yellowish or buff in color. Geology is marked by a thick cover of blown sand and alluvium except for a few isolated patches of recent calcareous and sandy sediments associated with gypsite/ gypsum. The oldest rocks in the area belong to the Aravalli Super group which includes phyllite, shale and quartz veins.

3. Seismology

28. As per the seismic zoning map of India, Ganganagar Town falls under the Zone II, which is the lowest earthquake risk zone in India. This zone is termed as "low damage risk zone".

4. Climatic Conditions

29. Ganga Nagar district falls in the Hot Arid Eco Region (Western plain, Kachch and part of Kathiawar Peninsula), and experiences extreme weather conditions. The climate of Sri Ganganagar is hot and arid throughout most part of the year. The summers (March/April to June/July) are hot with average daily maximum temperature of over 41°C and average daily minimum temperature of about 27°C; maximum temperatures can reach up to 50°C. Monsoon season is from July to September, during which it experiences rains, and temperature comes down and humidity increases. Ganganagar is one of the lowest rainfall receiving places in India, and experiences very low and unreliable rainfall under the influence of southwest monsoon from June/July to September. Long term Average Annual Rainfall (AAR) is just about 248 mm per year. On an average, there are 15 rainy days in a year. The predominant direction of wind is from south-west in April to September and during October to March, it flows from North-East and North-West direction.

30. Following Table shows the average climate data of Ganganagar, both the long-term and short-term. The average rainfall over the period of 2008-13 (212 mm) was significantly below the long term AAR (248 mm).

Month	Long Term average (1970-2000)				Short term average (2008-13)			
	Min.	Max.	Avg.	Wind Speed	Rain	Min.	Max.	Rain
	Temp (°c)	Temp (°c)	RH (%)	(kmph)	(mm)	Temp (°c)	Temp (°c)	(mm)
Jan	5.7	20.8	67.7	1.6	6.4	7.3	19.2	4.1
Feb	8.1	23.7	60.1	2.7	6.9	10.6	23.5	9.9
Mar	13.2	29.3	52.9	3.3	7.8	16.8	31.5	2.9
Apr	19.1	36.8	37.3	3.8	5.2	22.1	36.9	4.0
May	24.3	41.1	31.7	4.4	11.6	27.0	42.1	3.5
Jun	27.8	41.6	70.1	5.5	23.1	28.9	41.0	14.7
Jul	27.5	38.2	60.2	5.2	78.7	28.8	38.4	54.7
Aug	26.7	37.4	63.7	4.3	66.9	27.6	35.9	67.0
Sep	23.8	37.0	58.0	3.5	32.5	25.5	35.4	45.8
Oct	17.7	35.0	52.3	1.6	2.5	21.3	34.2	1.5
Nov	11.2	29.6	59.1	1.0	2.1	14.3	28.7	2.2
Dec	6.7	23.4	67.8	1.0	4.1	9.3	22.7	2.2
	17.7	32.8	56.7	3.2	247.8	20.0	32.5	212.4

Table 3: Climate Data of Ganganagar

5. Surface Water

31. Owing to its location in western desert region, with dry extremely low rainfall climate, there are no notable natural water bodies in the region. There are two natural depressions in the town - one near Balmiki Mandir and other at Idgah area. Rainwater accumulated in these depressions, forming water ponds. Due to lack of sewerage system, wastewater from town areas flows into these depressions via open drains. Due to low rainfall, most of the time these ponds hold wastewater, effecting the public health and environment. Very low rainfall has resulted into poorly developed drainage network, and as a result, even low rainfall results in inundation of the low lying areas, though for a short duration.

32. On the other hand, the region is bestowed with good irrigation facilities of Sutlej River. The canals of Gang Canal System crisscross the region, and has transformed the otherwise

desert region into lush green fields. The proposed project will not interfere with the irrigation system as the canals are mostly located outside the town.

33. Following Table shows the water quality of Gang Canal which is the raw water supply source for Ganganagar. As per the CPCB's surface water quality criteria, raw water quality meets the 'C' class criteria which denote the best use as "drinking water source after conventional treatment and disinfection".

Parameter		Gang Canal	Water Quality Criteria	
DO	Min	4.3		
mg/l	Max	7.4	4 or more	
	Mean	5.7		
рН	Min	6		
	Max	8.2	6.5 – 8.5	
	Mean	7.5]	
Conductivity	Min	230		
µmho/cm	Max	560	Not specified	
	Mean	325		
BOD	Min	0		
mg/l	Max	1.9] 3	
-	Mean	1]	
Nitrate	Min	0.08		
mg/l	Max	0.92	Not specified	
-	Mean	0.39		
Feacal coliform	Min	3		
MPN/100 ml	Max	7	Not specified	
	Mean	4		
Total coliform	Min	4		
MPN/100 ml	Max	20	500	
	Mean	11]	

 Table 4: Gang Canal Water Quality (2011)

34. There are several agro-based industries in the town, including a sugar factory. The treated and untreated effluents flow in the open drains, and due to poor natural drainage system, accumulates in low lying areas, creating both public health and environmental issues.

6. Groundwater

35. The alluvium at Sri Ganganagar includes unconsolidated and semi consolidated sediments comprising sand, silt, gravel, clay and kanker etc. The alluvium is mostly of fluvial origin. It is yellowish to yellowish brown in colour, medium to fine grained and inter mixed with kanker (stone aggregate). In local terminology this aquifer is called Reli. Part of the Ganganagar block has shallow water level of less than 20 m. Due to saline nature, groundwater use is limited. Excess irrigation and poor drainage have resulted into water logging and salinity build-up in canal command areas of Ganganagar District.

7. Air Quality

36. Ambient air quality in Rajasthan is monitored by Rajasthan Pollution Control Board. However, there is no at present there is no monitoring station in Ganganagar, and therefore no data on ambient air quality available. Due to the location in dry arid zone coupled with dust storms, especially during summer the months, the particulate matter in ambient air is likely to be high. The roads are not in good condition, traffic on these roads and winds are the main source of dust generation. Besides, there are few industries in the town, including a major sugar mill, and brick kilns, the generate air emissions from burning of fuels and use of boilers. This is adding to the air pollution, however, there is no data to establish the level of pollution.

B. Ecological Resources

37. According to Agro climatic classification by ICAR³, Ganga Nagar district falls in the Hot Arid Eco Region of Western plain, Katchch and part of Kathiawar Penisula. Planning Commission grouped the Ganga Nagar district into Trans Gangetic Plain Agro Climatic Zone. Although Ganganagar District lies in the great Thar Desert, irrigation provided via the Gang canal has put the district on the agricultural map of India prominently. It is one of the important wheat and cotton producing areas. Besides, the canals have transformed this desert region into a lush green area, where one can find variety of trees. Desert ecosystem is still exists in the areas where there are no canals.

38. There are no notable ecological resources in the study area. There are no forests or ecologically sensitive areas. Owing to good irrigation facilities, the areas around the urban areas are extensively cultivated. Therefore almost all the lands are either converted into urban or agricultural use, and there is no natural habitat left in the project area. There are trees along some roads. Tree cutting will be avoided for the project.

C. Economic Development

1. Land use

39. Sri Ganganagar is one of the well planned cities of India. As per the available information, Ganganagar plan was drawn during late 1920s, when the canal system was

implemented in the region. The town is divided into residential blocks and commercial areas including grain market. Residential Blocks have large parks for each Blocks and Community centers and places of worship are at junctions of three or four blocks.

40. The Town Planning department prepared Sri Ganganagar's first master plan in 1982 followed by 2001. The Master Plan 2001-2023 comprises areas of Sri Ganganagar Municipal Council and 30 villages. As per the Master Plan 2001-2023, the 2001 land use indicates that the total developed area is 1,501.39 Ha. Table 2 presents the distribution of land use in 2001. Of the total developed area, nearly 60% is under residential use.



Indian Council for Agricultural Research

3

No	Land use	Area	Developed	Urbanizable
			Area	Area
		Ha	%	%
1	Residential	898.40	59.84	37.63
2	Commercial	109.27	7.28	4.58
3	Industrial	81.75	5.44	3.42
4	Government & Semi-Government	15.38	1.02	0.64
5	Recreational	14.57	0.97	0.61
6	Public & Semi Public	132.33	8.81	5.54
7	Circulation	249.69	16.63	10.46
	Sub Total	1,501.39	39.38	
8	Government Reserved	562.51		23.56
9	Nursery, Orchards, etc.	238.76		10.00
10	Vacant Land	58.68		2.46
11	Ponds & Lakes	26.30		1.10
	Total	2,387.65		100.00

Table 5: Land Use of Gangnagar Town (2001)

2. Industry & Agriculture

41. This desert land was converted to a green area by the efforts of Maharaja Ganga Singh, who brought the Gang canal which carries the excess waters of Punjab and Himachal Pradesh to the region, making Ganganagar district as "the food basket of Rajasthan". The economy of the city is based on agriculture; its main crops are wheat, mustard and cotton. Other crops are guar, bajra, sugar cane and grams. In recent years, farmers are also diverted towards horticulture. Kinnow (a citrus family fruit and a hybrid citrus fruit from "orange") is a popular horticultural product of Sri Ganganagar and is exported to various places.

42. Industries in Sri Ganganagar District are based on agriculture. Major industries are: cotton ginning and pressing factories, mustard oil mills, wheat flour mills and a major sugar mill (Rajasthan State Ganganagar Sugar Mills). Sri Ganganagar is the largest producer of cotton and has cotton spinning and textile factories. Most of the factories are located outside the city. Rajasthan State Industrial Development and Investment Corporation (RIICO) have developed a new township – Udyog Vihar near Chak Shyam Singh Wala on Hanumangarh road at a distance of 12 km from Sri Ganganagar.

3. Infrastructure

43. **Water Supply:** Both Surface water as well as ground water source is available for serving drinking water needs to Sri Ganganagar town. The main source of water supply to Ganganagar town is Gang canal. Two intake points one at Distributary at Sadhuwala Head and second one at 68-69 RD. Hence, the municipality is depending on surface water. Currently, the PHED is extracting water from two surface water sources and 7 tube wells. 32 MLD of water from surface sources and, around 6 MLD water from 7 tube wells is extracted. At present, the PHED is supplying water for duration of 2 hours daily. Raw water from Gang canal is drawn by gravity whereas pumping from tube wells.

44. **Sewerage**: There is no sewerage system in the town at present. The wastewater coming from the households are disposed in the roadside drains. The sewage is either draining in roadside open drains/nallas or into soak pit outside their houses or ponds. At some locations,

due to lack of maintenance and insufficient drain size; the drains are chocked and overflowing. Most of slum dwellers and low income families depend on public toilets and practice open defecation. Sri Ganganagar Municipal Council has constructed public convenience facilities with a total capacity of 105 seats. However, due to lack of maintenance most of these public conveniences are in unhygienic condition.

45. **Solid Waste management:** In Sri Ganganagar, there is no proper organized Solid Waste Management (SWM) system. Town generates 60 tons of solid waste daily. Sri Ganganagar Nagar Parishad (SGNP), has initiated door-to-door waste collection in the part of the town, and in other parts waste is collected through community dust bins located in various places. Regular sweeping is carried out by SGNP. Waste from houses, dust bins and other areas is collected, and transported by SGNP to dumping site at Shul Chhai, and disposed via crude open dumping method.

46. **Storm Water Drainage:** There are no natural drains flowing through the municipal area of Sri Ganganagar. There are two main depressions in the town. One is near Balmikimandir and second one is at Idgah area. Balmikimandir depression receives wastewater through a drain starting from Adarsh Theatre running east to west. Idgah area depression receives water from a drain running north to south. During non-rainy season, these depressions receive domestic wastewater, which will be pumped to nearby agricultural field. During rainy season, the drains also receive surface runoff from rainwater. This is causing temporary flooding. With respect to road side drains total drain length in Sri Ganganagar town is 183 km. Drain coverage with respect to road length is around 30 percent. However, most of the roads are having one side drain.

47. **Power Supply**. Thermal power is the main source of energy in Rajasthan, contributing nearly 90% of the electricity, compared to hydropower, which produces the remainder. State-level companies (Rajya Vidyut Utpadan Nigam Ltd, RVUN; and Rajya Vidyut Prasaran Nigam Ltd, RVPN) are responsible for power generation and transmission respectively, and distribution is provided by a regional company, the Jodhpur Vidyut Vitaran Nigyam Limited (JVVNL). Power is supplied from the central grid by overhead cables carried on metal and concrete poles, mainly located in public areas alongside roads. The power supply in the state is continuous and reliable, except in warmer months with periodic outages in warmer months, and large fluctuations in voltage.

48. **Transport:** Sri Ganganagar is broadly radial and grid iron pattern in its urban form with Suratgarh Road (Old NH-15) and Padampur Road being the two major roads passing through the town. Being a border district as well as regional town of the canal irrigation region, it has well developed road network and all the important mandi towns are connected with Sri Ganganagar. The intra-city traffic is more significant than the inter-city traffic in Sri Ganganagar. Two-wheelers, cycles and shared autorickshaw form the major motorized modes of transport in the city. There is no dedicated off-street parking facility in the city. The total length of the road network in Sri Ganganagar is about 610 km, of which, 41% are black topped roads, 8% cement concrete roads, 37% WBM roads and 14% Kutcha roads.

D. Socio Cultural Resources

1. Demography

49. Sri Ganganagar population, as per 2011 census, is 237,780, grown from 210,713 in 2001, registering a compounded annual growth rate of 1.22% (decadal growth of 12.85%),

which is much lower than the state urban population growth rate of 2.58% during the same decade. As presented in the Chart below, while the population is on growing trend, the rate of growth has always been on the decline, from very high to lower than state average. The average town density works out to 12,373 persons/sq. km. The old part of the town comprising of wards 19-22, and 28-30 witness high density in comparison with other parts of the town. Average household size of Ganganagar is 4.83.

50. Sex ratio of the town is 860 females per 1000 males. This is lower than Ganganagar district's sex ratio (878), and the state-level figure of 928. Literacy rate is 73.01% (Census 2011), which is slighter higher than the state literacy rate of 66.11%. Scheduled Caste (SC) and Scheduled Tribe (ST) population comprises 16.3 percent and 2.1 percent of the total population respectively. Workforce participation rate in Ganganagar is 34.8 percent, which is higher the State level WPR of 29.6%.



51. Largest proportion of population comprises Hindus followed by Skihs, Muslims, Jains and Christians. Main languages spoken are Bagri (local dialect), Punjabi and Hindi.

2. History, Culture and Tourism

52. Sri Ganganagar was established by Maharaja Ganga Singh, near Ramnagar, which was named after Ram Singh Ji Saharan, and now known as 'Purana Gaam'. This place was originally part of Bikaner State, a princely state in the pre-independence era. In 1899-1900, when Bikaner State was affected by the worst famine, Maharaja Ganga Singh, initiated the plan to bring Sutlej River waters to Bikaner State. Although the Sutlej Valley Project was developed, it was delayed from the erstwhile princely State of Bahawalpur. With the intervention of the then Viceroy of India, an agreement was reached, and the project, which included the Canal Head Works at Ferozpur, and 143 km of lined canals, was completed in 1927. This has completely transformed this desert region into agriculturally rich area.

53. During this time, Maharaja Ganga Singh, built Ganganagar City near the entry point of this Gang (Bikaner) canal into Bikaner State, and the plan of the city was drawn on the lines of Paris. After the independence it became part of Rajasthan state and the district of Ganganagar was formed in 1949. In 1994, Ganganagar district was district was reorganized by separating some areas as Hanumangarh District.

54. It is believed that that the Indus Valley civilization extended into the present day Ganganagar District as well. Archeological Survey of India (ASI) conducted explorations in Baror (about 100 km Ganganagar), a pre-historic site on a dry river bed, and found evidence of houses and streets and pottery of Pre Harappan and Harappan period. Kalibangan, another archaeological site for the Indus Valley Civilization is located at about 70 km from Ganganagar. Besides, there are several ancient mound sites in Ganganagar district, notified by ASI as protected sites. However, these sites are located far from the town (more than 50 km from

Ganganagar) and none are located in or near the town/project sites.

55. There are religious places of local importance in the town. There are no notable tourist places, and therefore tourist visiting Ganganagar is almost negligible.

E. Environmental Settings of Investment Program Component Sites

56. The subproject includes laying of water supply pipes and sewer network in the municipal area of Ganganagar. Pipes and sewers will be laid along the roads/streets in the town within the road right of way (ROW). In wider roads pipes/sewers will be laid in the road shoulder beside the tarmac, and in narrow roads, where there is no space, pipes/sewers will be laid in the road carriage way by break opening the tarmac. Roads in some part of the town are narrow. Roads are lined both sides with open drains. In narrow roads pipes/sewers will be laid in the middle of the road, which may affect the traffic. Bigger diameter strategic water mains and trunk sewers will be laid along the main roads, which are wide and have adequate space. No tree cutting is anticipated as there is adequate space to lay the sewer/pipelines in those roads.

IV. ANTICIPATED ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES

A. Introduction

57. Potential environmental impacts of the proposed infrastructure components are presented in this section. Mitigation measures to minimize/mitigate negative impacts, if any, are recommended along with the agency responsible for implementation. Monitoring actions to be conducted during the implementation phase is also recommended to reduce the impact.

58. Screening of potential environmental impacts are categorized into four categories considering subproject phases: location impacts and design impacts (pre-construction phase), construction phase impacts and operations and maintenance phase impacts.

- (i) **Location impacts** include impacts associated with site selection and include loss of on-site biophysical array and encroachment either directly or indirectly on adjacent environments. It also includes impacts on people who will lose their livelihood or any other structures by the development of that site.
- (ii) **Design impacts** include impacts arising from Investment Program design, including technology used, scale of operation/throughput, waste production, discharge specifications, pollution sources and ancillary services.
- (iii) **Construction impacts** include impacts caused by site clearing, earthworks, machinery, vehicles and workers. Construction site impacts include erosion, dust, noise, traffic congestion and waste production.
- (iv) **O&M impacts** include impacts arising from the operation and maintenance activities of the infrastructure facility. These include routine management of operational waste streams, and occupational health and safety issues.

59. Screening of environmental impacts has been based on the impact magnitude (negligible/moderate/severe – in the order of increasing degree) and impact duration (temporary/permanent).

60. This section of the IEE reviews possible project-related impacts, in order to identify issues requiring further attention and screen out issues of no relevance. ADB SPS (2009) require that impacts and risks will be analyzed during pre-construction, construction, and

operational stages in the context of the project's area of influence.

61. The ADB Rapid Environmental Assessment Checklist in <u>http://www.adb.org/documents/guidelines/environmental_assessment/eaguidelines002.asp</u> has been used to screen the project for environmental impacts and to determine the scope of the IEE.

62. In the case of this project (i) most of the individual elements are relatively small and involve straight forward construction and operation, so impacts will be mainly localized and not greatly significant; (ii) most of the predicted impacts are associated with the construction process, and are produced because that process is invasive, involving excavation and earth movements; and (iii) being located in an urban area, will not cause direct impact on biodiversity values. The project will be in properties held by the local government and access to the project location is through public rights-of-way and existing roads hence, land acquisition and encroachment on private property will not occur.

B. Pre-Construction Impacts

63. **Design of the Proposed Components**. The Central Public Health and Environmental Engineering Organization (CPHEEO) manual suggests a design period of 15/30 years⁴ in general while designing the systems for water supply and sewerage components. It is proposed to consider 2046 as the design year for all the components in order to maintain unanimity in the design period and design population. Accordingly, 2016 shall be the base year and 2031 the intermediate year to cross check the designs pertaining to intermediate demand. The rate of water supply has been taken as 135 lpcd for 100% population. Sewage generation is 85% of water supply (including 5% to account for infiltration) and coverage is 100% population. For sewerage design, though sewerage system will be made available for 100% population, it is assumed based on the experience from other towns that only 70% of design year population will be connected to sewer system.

64. One of the critical aspects in sewerage system operation is, change in raw sewage characteristics at inlet of sewage treatment plant may affect the process and output quality. STPs are designed for municipal wastewater, which does not include industrial effluent. Characteristics of industrial effluent widely vary depending on the type of industry, and therefore disposal of effluent into sewers may greatly vary the inlet quality at STP, and will upset process and affect the efficiency. Although legally the disposal of effluent meeting certain standards is allowed into municipal sewers (refer **Appendix 4**), the monitoring of the same is not-practical. Industrial development in Ganganagar is very limited, there are however few industries (chemical and textile) in town with problematic water discharges. Therefore disposal of such wastewater into sewers will impede the treatment efficiency. Following measures should be incorporated:

- (i) No industrial wastewater shall be allowed to dispose into municipal sewers
- (ii) No domestic wastewater from industrial units shall be allowed into municipal sewers
- (iii) Ensure that there is no illegal discharge through manholes or inspection chambers

⁴ As per CPHEEO, pumps, motors, STP, storage reservoirs are to be designed for a life of 15 years.

- (iv) Conduct public awareness programs; in coordination with RPCB, issue notice to all industries for compliance
- (v) Conduct regular wastewater quality monitoring (at inlet and at outlet of STP) to ensure that the treated effluent quality complies with the standards

65. **Sewer system – collection & conveyance.** The sewerage system is designed as a separate system of sewage collection (i.e. caters only to wastewater). There is considerable length of existing surface drains in the project area that can be used for disposal of storm runoff. The underground gravity sewers will carry sewage from households to trunk sewers and further to STPs. To maximize the benefits as intended, Sri Ganganagar Nagar Parishad should ensure that all existing septic tanks are phased out by bypassing the inlet and connecting the toilet discharge from each house directly to sewerage system.

66. Accumulation of silt in sewers in areas of low over time, overflows, blockages, power outages, harmful working conditions for the workers cleaning sewers etc. are some of the issues that needs to be critically looked into during the sewer system design. A properly designed system is a must for system sustainability.

67. Measures such as the following shall be included in sewer system design to ensure that the system provides the benefits as intended:

- (i) Limit the sewer depth where possible
- (ii) Sewers shall be laid away from water supply lines and drains (at least 1 m, wherever possible);
- (iii) In all cases, the sewer line should be laid deeper than the water pipeline (the difference between top of the sewer and bottom of water pipeline should be at least 300 mm)
- (iv) In unavoidable, where sewers are to be laid close to storm water drains, appropriate pipe material shall be selected (stoneware pipes shall be avoided)
- (v) For shallower sewers and especially in narrow roads , use small inspection chambers in lieu of manholes;
- (vi) Design manhole covers to withstand anticipated loads & ensure that the covers can be readily replace if broken to minimize silt/garbage entry
- (vii) Ensure sufficient hydraulic capacity to accommodate peak flows & adequate slope in gravity mains to prevent buildup of solids and hydrogen sulfide generation
- (viii) Equip pumping stations with a backup power supply, such as a diesel generator, to ensure uninterrupted operation during power outages, and conduct regular maintenance to minimize service interruptions. Consider redundant pump capacity in critical areas

68. **Utilities**. Telephone lines, electric poles and wires, water lines within the proposed project locations may require to be shifted in few cases. To mitigate the adverse impacts due to relocation of the utilities, the contractor, in collaboration with ULB will (i) identify the locations and operators of these utilities to prevent unnecessary disruption of services during construction phase; and (ii) instruct construction contractors to prepare a contingency plan to include actions to be done in case of unintentional interruption of services.

69. Social and Cultural Resources. Any work involving ground disturbance can uncover

and damage archaeological and historical remains. For this project, excavation will occur in project sites, so it could make medium risk of such impacts if the site contains any archeological and historical remains. Nevertheless, PIU will:

- (i) consult Department of Archaeology and Museums to obtain an expert assessment of the archaeological potential of the site;
- (ii) consider alternatives if the site is found to be of high risk;
- (iii) include state and local archaeological, cultural and historical authorities, and interest groups in consultation forums as project stakeholders so that their expertise can be made available; and
- (iv) develop a protocol for use by the construction contractors in conducting any excavation work, to ensure that any chance finds are recognised and measures are taken to ensure they are protected and conserved.

70. Site selection of construction work camps, stockpile areas, storage areas, and disposal areas. Priority is to locate these near the project location. However, if it is deemed necessary to locate elsewhere, sites to be considered will not promote instability and result in destruction of property, vegetation, irrigation, and drinking water supply systems. Residential areas will not be considered for setting up construction camps to protect the human environment (i.e., to curb accident risks, health risks due to air and water pollution and dust, and noise, and to prevent social conflicts, shortages of amenities, and crime). Extreme care will be taken to avoid disposals near forest areas, water bodies, swamps, or in areas which will inconvenience the community.

71. **Site selection of sources of materials**. Extraction of materials can disrupt natural land contours and vegetation resulting in accelerated erosion, disturbance in natural drainage patterns, ponding and water logging, and water pollution. To mitigate the potential environmental impacts, locations of quarry site/s and borrow pit/s (for loose material other than stones) would be assessed by PIU. Priority would be sites already permitted by Mines and Geology Department. If new sites are necessary, these would be located away from population centers, drinking water intakes and streams, cultivable lands, and natural drainage systems; and in structurally stable areas. It will be the construction contractor's responsibility to verify the suitability of all material sources and to obtain the approval of Department of Mines & Geology and local revenue administration. If additional quarries will be required after construction is started, then the construction contractor shall use the mentioned criteria to select new quarry sites, with written approval of PIU.

C. Construction Impacts

72. The civil works for the subproject include earth work excavation for pipeline/sewer trenches, pipe/sewer laying, installing valves, flow meters and data loggers, shifting of public utilities and providing house service connections. Earth work excavation will be undertaken by machine (backhoe excavator) and include danger lighting and using sight rails and barricades at every 100 m., while pipe/sewer laying works will include laying pipes/sewer at required gradient, fixing collars, elbows, tees, bends and other fittings including conveying the material to work spot and testing for water tightness.

73. The excavation is done in such a way that there will be a minimum depth of 1.2 m above the water pipe line, and in narrow streets the cover above the will be 0.7 m only. The maximum depth for sewers depends on the design, and in Ganganagar most of the sewers will be laid 1.2 to 2 m below the ground, and some sewers will be laid deeper (> 2m) and maximum

depth will be 4m. Sufficient care will be taken while laying so that existing utilities and cables are not damaged and pipes are not thrown into the trenches or dragged, but carefully laid in the trenches. Trenches deeper than 2 m will be protected by bracings to avoid collapse of trenches, and also to avoid any risk to surrounding buildings. Once they are laid, pipes will be joined as per specification and then tested for any cracks of leakages. The minimum working hours will be 8 hours daily, the total duration of each stage depends on the soil condition and other local features. The excavation of trenches for water pipes is estimated to generate 587,910 cubic meters of soil, about 97% of this soil will be used for refilling the trench after placing the pipe and therefore residual soil after pipe laying and refilling is expected to be only 17,410 cubic meters. In case of sewers, estimated soil generation is 617,927 cubic meters, of which about 83% will be used for refilling, and the remaining 103,725 cubic meters needs to be disposed. This soil shall be used for filling low lying area or stored/ dumped in approved debris disposal sites. The beneath and sides of sewers in trench will be filled with sand to form cushion/bed for sewer, and the sand requirement is estimated as 83,105 cubic meter.

74. Although construction of these project components involves quite simple techniques of civil work, the invasive nature of excavation and the project locations in the built-up areas of the town where there are a variety of human activities, will result in impacts to the environment and sensitive receptors such as residents, businesses, and the community in general. These anticipated impacts are temporary and for short duration. Water and sewer lines will be laid on either side of the roads/streets.

75. Physical impacts will be reduced by the method of working and scheduling of work, whereby the project components will be (i) constructed by small teams working at a time; (ii) any excavation done near sensitive area like school, religious places and house will be protected as per standard norms etc.

76. **Sources of Materials**. Significant amount of gravel, sand, coarse aggregate, and cement will be required for this project. The construction contractor will be required to:

- (i) Use material sources permitted by government;
- (ii) Verify suitability of all material sources and obtain approval of PIU; and
- (iii) Submit to PIU on a monthly basis documentation of sources of materials.

77. **Air Quality**. Emissions from construction vehicles, equipment, and machinery used for excavation and construction will induce impacts on the air quality in the construction sites. Anticipated impacts include dusts and increase in concentration of vehicle-related pollutants such as carbon monoxide, sulfur oxides, particulate matter, nitrous oxides, and hydrocarbons. These however will be temporary limiting to construction activities only. To mitigate the impacts, construction contractors will be required to:

- (i) Consult with PIU/ on the designated areas for stockpiling of, soils, gravel, and other construction materials;
- (ii) Damp down exposed soil and any stockpiled material on site by water sprinkling;
- (iii) Use tarpaulins to cover sand and other loose material when transported by trucks;
- (iv) Clean wheels and undercarriage of haul trucks prior to leaving construction site
- (v) Don't allow access in the work area except workers to limit soil disturbance and prevent access by barricading and security personnel

(vi) Fit all heavy equipment and machinery with air pollution control devices which are operating correctly

78. **Surface Water Quality**. Run-off from stockpiled materials, and chemical contamination from fuels and lubricants during construction works can contaminate downstream surface water quality of the streams. These potential impacts are temporary and short-term duration only. However, to ensure that these are mitigated, construction contractor will be required to:

- (i) Prepare and implement a spoils management plan (**Appendix 8**);
- (ii) Avoid stockpiling of earth fill especially during the monsoon season unless covered by tarpaulins or plastic sheets;
- (iii) Prioritize re-use of excess spoils and materials in the construction works. If spoils will be disposed, consult with PIU on designated disposal areas;
- (iv) Install temporary silt traps or sedimentation basins along the drainage leading to the water bodies;
- Place storage areas for fuels and lubricants away from any drainage leading to water bodies;
- (vi) Dispose any wastes generated by construction activities in designated sites; and
- (vii) Conduct surface quality inspection according to the Environmental Management Plan (EMP).

79. **Noise and Vibration Levels**. Construction works will be conducted along the roads in Ganganagar urban area, where there are houses, schools and hospitals, religious places and small-scale businesses. The sensitive receptors are the general population in these areas. Increase in noise level may be caused by excavation, particularly breaking of cement concrete or bitumen roads, operation of construction equipment like concrete mixers, and the transportation of equipment, materials, and people. Vibration generated from construction activity, for instance from the use of pneumatic drills, will have impact on nearly buildings. This impact is negative but short-term, and reversible by mitigation measures. The construction contractor will be required to:

- (i) Plan activities in consultation with PIU so that activities with the greatest potential to generate noise are conducted during periods of the day which will result in least disturbance;
- (ii) Horns should not be used unless it is necessary to warn other road users or animals of the vehicle's approach;
- (iii) Minimize noise from construction equipment by using vehicle silencers, fitting jackhammers with noise-reducing mufflers, and use portable street barriers to minimise sound impact to surrounding sensitive receptor; and
- (iv) Maintain maximum sound levels not exceeding 80 decibels (dBA) when measured at a distance of 10 m or more from the vehicle/s.
- (v) Identify any buildings at risk from vibration damage and avoiding any use of pneumatic drills or heavy vehicles in the vicinity;
- (vi) Consult the custodians of important buildings, cultural and tourism authorities and local communities in advance of the work to identify and address key issues, and avoid working at sensitive times, such as religious and cultural festivals.

80. **Landscape and Aesthetics**. The construction works does not envisage any cutting of trees, but it will produce excess excavated earth, excess construction materials, and solid waste such as removed concrete, wood, packaging materials, empty containers, spoils, oils, lubricants, and other similar items. Haphazard disposal of these will have negative impacts on

landscape and overall aesthetics. These impacts are negative but are of short-term and reversible by mitigation measures. The construction contractor will be required to:

- (i) Prepare and implement spoils management plan;
- (ii) Avoid stockpiling of excess excavated soils;
- (iii) Coordinate with ULB for beneficial uses of excess excavated soils or immediately dispose to designated areas;
- (iv) Recover used oil and lubricants and reuse or remove from the sites;
- (v) Manage solid waste according to the following preference hierarchy: reuse, recycling and disposal to designated areas;
- (vi) Remove all wreckage, rubbish, or temporary structures which are no longer required; and
- (vii) Request PIU to report in writing that the necessary environmental restoration work has been adequately performed before acceptance of work.

81. **Surface and Groundwater Quality**. Another physical impact that is often associated with excavation is the effect on drainage and the local water table if groundwater and surface water collect in the voids. In Ganganagar groundwater is much deeper than the proposed trenching depth, and rains are scarce and limited to very short duration during monsoon. However, to ensure that water will not pond in pits and voids near project location, the construction contractor will be required to conduct excavation works in non-monsoon season to the maximum extent possible.

82. **Accessibility**. Excavation along the roads, hauling of construction materials and operation of equipment on-site can cause traffic problems. Potential impact is negative but short term and reversible by mitigation measures. The construction contractor will be required to:

- (i) Prepare and implement a Traffic Management Plan (**Appendix 9**)
- (ii) Plan transportation routes so that heavy vehicles do not use narrow local roads, except in the immediate vicinity of delivery sites;
- (iii) Schedule transport and hauling activities during non-peak hours;
- (iv) Locate entry and exit points in areas where there is low potential for traffic congestion;
- (v) Keep the site free from all unnecessary obstructions;
- (vi) Drive vehicles in a considerate manner;
- (vii) Coordinate with Traffic Police for temporary road diversions and for provision of traffic aids if transportation activities cannot be avoided during peak hours; and
- (viii) Notify affected sensitive receptors by providing sign boards informing nature and duration of construction works and contact numbers for concerns/complaints.

83. Wherever road width is minimal, there will be temporary loss of access to restrains and vehicular traffic (including 2-wheelers) during the laying of pipes. Under those circumstances, contractor shall adopt following measures:

- (i) Inform the affected local population 1-week in advance about the work schedule
- (ii) Plan and execute the work in such a way that the period of disturbance/ loss of access is minimum.
- (iii) Provide pedestrian access in all the locations until normalcy is restored. Provide wooden/metal planks over the open trenches at each house to maintain the access.
84. **Socio-Economic – Income**. The project components will be located in government land and there is no requirement for land acquisition or any resettlement. Construction works will impede the access of residents to specific site in limited cases. The potential impacts are negative and moderate but short-term and temporary. The construction contractor will be required to:

- (i) Prepare and implement spoils management plan (**Appendix 8**);
- (ii) Leave spaces for access between mounds of soil;
- (iii) Provide walkways and metal sheets where required to maintain access across for people and vehicles;
- (iv) Increase workforce in the areas with predominantly institutions, place of worship, business establishment, hospitals, and schools;
- (v) Consult businesses and institutions regarding operating hours and factoring this in work schedules; and
- (vi) Provide sign boards for pedestrians to inform nature and duration of construction works and contact numbers for concerns/complaints.
- (vii) Notify community/ water users in advance about likely interruptions in water supply.
- (viii) Provide alternate sources of clean water until water supply is restored.

85. **Socio-Economic – Employment**. Manpower will be required during the 36-months construction stage. This can result in generation of temporary employment and increase in local revenue. Thus potential impact is positive and long-term. The construction contractor will be required to:

- (i) Employ at least 50% of the labour force, or to the maximum extent, local persons within the 2-km immediate area if manpower is available; and
- (ii) Secure construction materials from local market.

86. **Occupational Health and Safety**. Workers need to be mindful of the occupational hazards which can arise from working in height and excavation works. Potential impacts are negative and long-term but reversible by mitigation measures. The construction contractor will be required to:

- (i) Comply with all national, state and local labor laws (see **Appendix 7**);
- Develop and implement site-specific occupational health and safety (OH&S) Plan which will include measures such as: (a) excluding public from the site; (b) ensuring all workers are provided with and use personal protective equipment;
 (c) OH&S Training⁵ for all site personnel; (d) documented procedures to be followed for all site activities; and (e) documentation of work-related accidents;

⁵ Some of the key areas that may be covered during training as they relate to the primary causes of accidents include (i) slips, trips and falls; (ii) personal protective equipment; (iii) ergonomics, repetitive motion, and manual handling; (iv) workplace transport; and (v) legislation and responsibilities. Training can provide the foundations of competence but it does not necessarily result in a competent worker. Therefore, it is essential to assess staff competence to ensure that the training provided is relevant and effective. Supervision and monitoring arrangements shall be in place to ensure that training has been effective and the worker is competent at their job. The level of supervision and monitoring required is a management decision that shall be based on the risks associated with the job, the level of competence required, the experience of the individual and whether the worker works as part of a team or is a lone worker.

- (iii) Ensure that qualified first-aid is provided at all times. Equipped first-aid stations shall be easily accessible throughout the site;
- (iv) Provide medical insurance coverage for workers;
- (v) Secure all installations from unauthorized intrusion and accident risks;
- (vi) The project area experiences extreme temperature during summer months of April and May, which may affect the health of workers engaged in construction work. Contractor should take necessary measures during summers including the following:
- a. Work schedule should be adjusted to avoid peak temperature hours (12 3 PM)
- (vii) Provide appropriate shade near the work place; allow periodic resting and provide adequate water Provide supplies of potable drinking water;
- (viii) Provide necessary medicine and facilities to take care of dehydration related health issues
- (ix) Provide clean eating areas where workers are not exposed to hazardous or noxious substances;
- (x) Provide H&S orientation training to all new workers to ensure that they are apprised of the basic site rules of work at the site, personal protective protection, and preventing injuring to fellow workers;
- Provide visitor orientation if visitors to the site can gain access to areas where hazardous conditions or substances may be present. Ensure also that visitor/s do not enter hazard areas unescorted;
- (xii) Ensure the visibility of workers through their use of high visibility vests when working in or walking through heavy equipment operating areas;
- (xiii) Ensure moving equipment is outfitted with audible back-up alarms;
- (xiv) Mark and provide sign boards for hazardous areas such as energized electrical devices and lines, service rooms housing high voltage equipment, and areas for storage and disposal. Signage shall be in accordance with international standards and be well known to, and easily understood by workers, visitors, and the general public as appropriate; and
- (xv) Disallow worker exposure to noise level greater than 85 dBA for a duration of more than 8 hours per day without hearing protection. The use of hearing protection shall be enforced actively.

87. **Asbestos Materials.** Existing water distribution network is mostly asbestos cement (AC) pipes, and because of the health risks these will be left in situ and replaced by new pipes. Details will be obtained from the PHED of the nature and location of all water supply infrastructure, and planning pipeline alignments carefully to avoid any conflict or damage. Given the dangerous nature of this material for both workers and citizens, additional measure should be taken to protect the health of all parties in the event (however unlikely) that AC pipes are encountered. This is that, prior to start of construction works of water supply system, PIU will develop a protocol to be applied in any instance that AC pipes are encountered, to ensure that appropriate action is taken. This should be based on the approach recommended by the United States Environmental Protection Agency (USEPA),⁶ and amongst other things, should involve:

⁶ In the USA, standards and approaches for handling asbestos are prescribed by the Occupational Health and Safety Administration (OHSA) and the Environmental Protection Agency (EPA) and can be found at http://www.osha.gov/SLTC/asbestos

- (i) Training of all personnel (including manual labourers) to enable them to understand the dangers of AC pipes and to be able to recognise them in situ;
- (ii) Reporting procedures to inform PIU immediately if AC pipes are encountered;
- (iii) Development and application of a detailed H&S procedure to protect both workers and citizens. This should comply with national and international standards for dealing with asbestos, and should include: (a) removal of all persons to a safe distance; (b) usage of appropriate breathing apparatus and protective equipment by persons delegated to deal with the AC material; and (c) Procedures for the safe removal and long-term disposal of all asbestoscontaining material encountered.

88. **Community Health and Safety**. Hazards posed to the public, specifically in highpedestrian areas may include traffic accidents and vehicle collision with pedestrians. Potential impact is negative but short-term and reversible by mitigation measures. The construction contractor will be required to:

- (i) Plan routes to avoid times of peak-pedestrian activities.
- (ii) Liaise with PIU in identifying risk areas on route cards/maps.
- (iii) Maintain regularly the vehicles and use of manufacturer-approved parts to minimize potentially serious accidents caused by equipment malfunction or premature failure.
- (iv) Provide road signs and flag persons to warn of on-going trenching activities.

89. Central part of the town is characterized by narrow roads. Particularly, the areas located on hill slopes have very narrow roads with sharp turns and are accessible only to pedestrians. Besides impeding the access, the trench excavation and pipe laying will pose safety risks to pedestrians, and the people living in these areas. Though the width (<500 mm) and depth (<750 mm) of trench is minimal, it will pose safety risk, especially for children and elders The construction contractor will be required to:

- (i) Provide prior information to the local people about the nature and duration of work
- (ii) Conduct awareness program on safety during the construction work
- (iii) Undertake the construction work stretch-wise; excavation, pipe laying and trench refilling should be completed on the same day
- (iv) Provide barricades, and deploy security personnel to ensure safe movement of people and also to prevent unnecessary entry and to avoid accidental fall into open trenches

90. **Work Camps**. Operation of work camps can cause temporary air and noise pollution from machine operation, water pollution from storage and use of fuels, oils, solvents, and lubricants. Potential impacts are negative but short-term and reversible by mitigation measures. The construction contractor will be required to:

- (i) Consult PIU before locating project offices, sheds, and construction plants;
- (ii) Minimize removal of vegetation and disallow cutting of trees;
- (iii) Provide drinking water, water for other uses, and sanitation facilities for employees;
- (iv) Ensure conditions of liveability at work camps are maintained at the highest standards possible at all times;
- (v) Prohibit employees from poaching wildlife and cutting of trees for firewood;

- (vi) Train employees in the storage and handling of materials which can potentially cause soil contamination;
- (vii) Recover used oil and lubricants and reuse or remove from the site;
- (viii) Manage solid waste according to the following preference hierarchy: reuse, recycling and disposal to designated areas;
- (ix) Remove all wreckage, rubbish, or temporary structures which are no longer required; and
- (x) Request PMU to report in writing that the camp has been vacated and restored to pre-project conditions before acceptance of work.

91. **Social and Cultural Resources**. For this project, excavation will occur at locations known not to have archaeological values, so it could be that there is a low risk of such impacts. Nevertheless, the construction contractor will be required to:

- (i) Strictly follow the protocol for chance finds in any excavation work;
- (ii) Request PIU or any authorized person with archaeological/historical field training to observe excavation;
- (iii) Stop work immediately to allow further investigation if any finds are suspected;
- (iv) Inform PIU/ACM if a find is suspected, and take any action they require ensuring its removal or protection in situ.
- (v) Adjacent to religious/historic sites, undertake excavation and construction work in such a way that no structural damage is caused to the building.

92. **Debris disposal.** Prior to the commencement of works, contractor shall identify a debris disposal site in consultation with the PIU and adhering to following criteria:

- (i) The site shall be selected preferably from barren, infertile lands. In case agricultural land needs to be selected, top-soil stripping, stacking and preservation should be undertaken prior to initiation of any activities.
- (ii) Debris disposal site shall be at least 200 m away from surface water bodies⁷.
- (iii) No residential areas shall be located within 100 m downwind side of the site.
- (iv) The site is minimum 250 m. away from sensitive locations like hospitals, religious places, ponds/lakes or other water bodies.
- (vi) The local governing body and community shall be consulted while selecting the site.

D. Operation and Maintenance Impacts

93. Operation and Maintenance of the water supply system will be carried out by Sri Ganganagar Nagar Parishad directly or through an external operator. The system have a design life of 15/30 years, during which shall not require major repairs or refurbishments and should operate with little maintenance beyond routine actions required to keep the equipment in working order. The stability and integrity of the system will be monitored periodically to detect any problems and allow remedial action if required. Any repairs will be small-scale involving manual, temporary, and short-term works involving regular checking and recording of performance for signs of deterioration, servicing and replacement of parts.

⁷ In the absence of site meeting the stipulated criteria, an alternate site can be selected specifying the reasons. In such a case, the construction camp management plan should incorporate additional measures specific to the site as suggested by the Construction Manager.

94. Recurrence of pipe bursting and leakage problems can be managed by the leak detection and water auditing surveys. The ULB will be required to ensure that the leak detection and rectification time is minimized.

95. Improper disposal of silt and debris removed from trenches could cause inconvenience to public. Silt and debris shall be collected in trucks and transported to the approved disposal site and or can be used as covering material for wastes being landfilled.

96. Repair works could cause some temporary disruption of activities at locations of social and cultural importance such as schools, hospitals, churches, tourist sites etc., so the same precautions as employed during the construction period should be adopted. ULB needs to:

- (i) Identify any buildings at risk from vibration damage and avoiding any use of pneumatic drills or heavy vehicles in the vicinity;
- (ii) Complete work in these areas quickly;
- (iii) Consult the custodians of important buildings, cultural and tourism authorities and local communities in advance of the work to identify and address key issues, and avoid working at sensitive times, such as religious and cultural festivals.

97. There are also certain environmental risks from the operation of the sewer system, most notably from leaking sewer pipes as untreated faecal material can damage human health and contaminate both soil and groundwater. It will be imperative therefore that the operating agency establishes a procedure to routinely check the operation and integrity of the sewers, and to implement rapid and effective repairs where necessary. There is an occupation health risk to workers engaged in sewer maintenance activities. Following measures should be followed:

- (i) Establish regular maintenance program, including:
 - Regular cleaning of grit chambers and sewer lines to remove grease, grit, and other debris that may lead to sewer backups. Cleaning should be conducted more frequently for problem areas.
 - Inspection of the condition of sanitary sewer structures and identifying areas that need repair or maintenance. Items to note may include cracked/deteriorating pipes; leaking joints or seals at manhole; frequent line blockages; lines that generally flow at or near capacity; and suspected infiltration or exfiltration; and
 - Monitoring of sewer flow to identify potential inflows and outflows
 - Conduct repairs on priority based on the nature and severity of the problem. Immediate clearing of blockage or repair is warranted where an overflow is currently occurring or for urgent problems that may cause an imminent overflow (e.g. pump station failures, sewer line ruptures, or sewer line blockages);
- Review previous sewer maintenance records to help identify "hot spots" or areas with frequent maintenance problems and locations of potential system failure, and conduct preventative maintenance, rehabilitation, or replacement of lines as needed;
- (iii) When a spill, leak, and/or overflow occurs, keep sewage from entering the storm drain system by covering or blocking storm drain inlets or by containing and diverting the sewage away from open channels and other storm drain facilities (using sandbags, inflatable dams, etc.). Remove the sewage using vacuum equipment or use other measures to divert it back to the sanitary sewer system.

- (iv) Prohibit/prevent disposal of wastewater/effluent from industrial units in the sewers; ensure regular checking to ensure no illegal entry of industrial wastewater into sewers
- (v) Develop an Emergency Response System for the sewerage system leaks, burst and overflows, etc.
- (vi) Provide necessary health & safety training to the staff in sewer cleaning & maintenance
- (vii) Provide all necessary personnel protection equipment
- (viii) For personnel cleaning underground sewers there is a risk due to oxygen deficiency and harmful gaseous emissions (hydrogen sulphide, carbon monoxide, methane, etc.); provide for adequate equipment (including oxygen masks) for emergency use

98. The citizens of the Ganganagar Municipal Council will be the major beneficiaries of the improved water supply and sewerage, as they will be provided with a constant supply of better quality water, piped into their homes and the human waste from the homes will be removed rapidly, which otherwise would flow in open drains. In addition to improved environmental conditions, the project will improve the over-all health condition of the town as diseases of poor sanitation will be reduced. This should improve the environment, should deliver major improvements in individual and community health and well-being. Diseases of poor sanitation, such as diarrhea and dysentery, should be reduced, so people should spend less on healthcare and lose fewer working days due to illness, so their economic status should also improve, as well as their overall health.

V. PUBLIC CONSULTATION AND INFORMATION DISCLOSURE

A. Overview

99. The active participation of stakeholders including local community, NGOs/CBOs, and the media in all stages of project preparation and implementation is essential for successful implementation and as well as operation of the project. It will ensure that the subprojects are designed, constructed, and operated with utmost consideration to local needs, ensures community acceptance, and will bring maximum benefits to the people. Public consultation and information disclosure is a must as per the ADB policy.

100. A three tier consultation process has been adopted for RUSDP: focus group discussions, primary household sample surveys and a town-level public consultation workshop. Most of the main stakeholders have already been identified and consulted during preparation of this IEE, and any others that are identified during project implementation will be brought into the process in the future. Primary stakeholders of the subproject are: residents, shopkeepers and businesspeople who live and work alongside the roads in which network improvements will be provided and near sites where facilities will be built (STP), and government and utility agencies responsible for provision of services Ganganagar Nagar Parishad, Public Health Engineering Department, Department of Archeology and Museums and Rajasthan Pollution Control Board. Secondary stakeholder are: NGOs and CBOs working in the area, community representatives, beneficiary community in general, government agencies, the executing and implementing agencies (LSGD and RUIDP), Government of India and the ADB.

B. Public Consultation

101. The public consultation and disclosure program is a continuous process throughout the project implementation, including project planning, design and construction. Socio economic surveys were conducted in June-August, 2013. Women groups were consulted in April and May, 2014 (Appendix 11).

1. Consultation during Project Preparation

102. Institutional consultations were conducted with the Governmental Departments such as Local Self Government Department, Public Works Department, Pollution Control Board, Public Health Engineering Department, Ganganagar Nagar Parishad, etc. The project proposals are formulated in consultation with PHED and Ganganagar Nagar Parishad and the proposals will be finalized only after certification of Commissioner Ganganagar NP that the proposals suit the requirements of the ULB.

103. Focus-group discussions with affected persons and other stakeholders were conducted to learn their views and concerns. A socio economic household survey has been conducted in the town, covering sample households, to understand the household characteristics, health status, and the infrastructure service levels, and also the demand for infrastructure services. General public and the people residing along the project activity areas were also consulted during visits to the project sites.

104. It was observed that people are willing to extend their cooperation as the proposed activities are proposed to enhance the infrastructure service levels and the living standard of the public. The public expressed their concern regarding the nuisance and disturbance (dust, road closure and traffic management activities) during the construction stage which can have impact on their day to day activities. Public demanded for advance notice before construction and proper warning signs along the construction area to avoid accidents and inconvenience. Public opined that an appropriate operation and maintenance system should be in place, especially for sewerage system, for its best functioning and to have the maximum health and aesthetic benefits.

105. A stakeholder consultation meeting was conducted in Ganganagar Town on April 25, 2014 to which representatives of primary and secondary stakeholders were invited. Participants were invited to understand the project and likely environment and social issues, benefits, and to express their views and concerns. Proceedings of the stakeholder consultation meeting is at Appendix 14. Stakeholders are supportive of the project, and opined that this project will improve the quality of life in the town, and will benefit them immensely.

2. Consultation during construction

106. Prior to start of construction, ULB and PIU with the assistance of PMDSC will conduct information dissemination sessions at major intersections and solicit the help of the local community leaders/prominent citizens to encourage the participation of the people to discuss various environmental issues. At each ward/neighborhood level, focus group meetings will be conducted to discuss and plan construction work with local communities to reduce disturbance and other impacts, and provide a mechanism through which stakeholders can participate in project monitoring and evaluation.

107. A constant communication will be established with the affected communities to redress

the environmental issues likely to surface during construction and operational phases and also regarding the grievance redress mechanism. ULB/PIU and PMDSC will organize public meetings and will appraise the communities about the progress on the implementation of EMP. Meeting will also be organized at the potential hotspots/sensitive locations before and during the construction.

C. Information Disclosure

108. Executive summary of the IEE will be translated in the local language and made available at the offices of RUIDP, PMU and PIU. Copies of summary will be provided to participants of city level workshop to be organized in Ganganagar. Hard copies of the IEE will be accessible to citizens as a means to disclose the document and at the same time creating wider public awareness. Electronic version of the IEE in English and Executive Summary in Hindi will be placed in the official website of the ULB/RUIDP/PMU after approval of the IEE by Government and ADB. Stakeholders will also be made aware of grievance register and redress mechanism.

109. Public information campaigns via newspaper/radio/TV, to explain the project details to a wider population will be conducted. Public disclosure meetings will be conducted at key project stages to inform the public of progress and future plans. Prior to start of construction, the PIU will issue Notification on the start date of implementation in local newspapers A board showing the details of the project will be displayed at the construction site for the information of general public.

110. Local communities will be continuously consulted regarding location of construction camps, access and hauling routes and other likely disturbances during construction. The road closure together with the proposed detours will be communicated via advertising, pamphlets, radio broadcasts, road signage, etc.

VI. GRIEVANCE REDRESS MECHANISM

A. Project Specific Grievance Redress Mechanism

111. A project-specific grievance redress mechanism (GRM) will be established to receive, evaluate, and facilitate the resolution of AP's concerns, complaints, and grievances about the social and environmental performance at the level of the project. The GRM will aim to provide a time-bound and transparent mechanism to record and resolve social and environmental concerns linked to the project.

112. **Common GRM**. A common GRM will be in place for social, environmental, or any other grievances related to the project; the resettlement plans (RPs) and IEEs will follow the GRM described below. The GRM will provide an accessible and trusted platform for receiving and facilitating resolution of affected persons' grievances related to the project. The multi-tier GRM for the project is outlined below, each tier having time-bound schedules and with responsible persons identified to address grievances and seek appropriate persons' advice at each stage, as required.

113. ULB-wide public awareness campaigns will ensure that awareness on grievance redress procedures is generated through the campaign. PIU Assistant Safeguards Officer (ASO) through Community Awareness and Participation Consultant (CAPC) will conduct ULB-wide awareness campaigns to ensure that poor and vulnerable households are made aware of

grievance redress procedures and entitlements.

114. APs will have the flexibility of conveying grievances/suggestions by dropping grievance redress/suggestion forms in complaints/suggestion boxes will be installed by project ULBs or by e-mail, by post, or by writing in a complaints register in ULB/PIU offices. **Appendix 11** has the sample grievance registration form. Careful documentation of the name of the complainant, date of receipt of the complaint, address/contact details of the person, location of the problem area, and how the problem was resolved will be undertaken. The PMU Project Officers (Environment & Social) will have the overall responsibility for timely grievance redressal respectively on environmental and social safeguards issues and for registration of grievances, related disclosure, and communication with the aggrieved party through the PIU ASO.

B. Grievance Redress Process

115. In case of grievances that are immediate and urgent in the perception of the complainant, the contractor, and supervision personnel from PIU and PMDSC on-site will provide the most easily accessible or first level of contact for quick resolution of grievances. Contact phone numbers and names of the concerned PIU Assistant Safeguards Officer, contractors, will be posted at all construction sites at visible locations.

- (i) 1st level grievance. The contractors, PIU supervision personnel, PIU Assistant Safeguards Officer and implementing NGO/CAPC⁸ can immediately resolve issues on-site in consultation with each other, and will be required to do so within 3 days of receipt of a complaint/grievance.
- (ii) 2nd level grievance. All grievances that cannot be redressed within 3 days at field/ward level will be brought to the notice of respective Project Officers (Environment/Social) of PMU. PMU POs will resolve the grievance within 7 days of receipt of compliance/grievance in discussion with the PIU, CAPC and the Contractor. PMDSC will assist POs in resolving the issue.
- (iii) 3rd level grievance. All the grievances that are not addressed by PMU within in 7 days of receipt will be brought to the notice of notice of the Grievance Redressal Committee (GRC). The City Level Committee (CLC) that will be established in every project town will act as GRC⁹. GRC will meet twice a month and determine the merit of each grievance brought to the committee. The PIU ASO will be responsible to see through the process of redressal of each grievance. The GRC will resolve the grievance within 15 days of receiving the complaint.
- (iv) **4th level grievance**. Very major issues that are beyond the jurisdictional authority of the CLC or those that have the potential to cause social conflicts or

⁸ Community Awareness and Public Participation (CAPC) will oversee the matters if there is no Resettlement Plan (RP) Implementing NGO

⁹ City Level Committees (CLC) will be formed at town-level with members composed of: District Collector (DC) as Chairperson, and following as members: ULB Commissioner; Assistant Safeguards Officer PIU; representative from RPCB regional office; and one representative each from relevant government departments as appropriate (PWD / PHED / DAM etc). All town-level GRCs will have at least one woman member/chairperson. In addition, for project-related grievances, representatives of APs, community-based organizations (CBOs), and eminent citizens will be invited as observers in GRC meetings

environmental damage or those that remain unresolved at PMU/CLC level, will be referred to the Empowered Committee (EC)¹⁰. All decisions taken by the GRC and PSC will be communicated to the APs by the PIU ASO.

116. The project GRM notwithstanding, an aggrieved person shall have access to the country's legal system at any stage, and accessing the country's legal system can run parallel to accessing the GRM and is not dependent on the negative outcome of the GRM. Alternatively, if the grievance is related to land acquisition, resettlement & rehabilitation, the APs can approach the Land Acquisition, Rehabilitation and Resettlement Authority (LARRA). As per the latest Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation, and Resettlement Act, 2013, the state government will have to establish the LARRA to address grievances in implementation of LARRA.

117. In the event that the established GRM is not in a position to resolve the issue, the affected person also can use the ADB Accountability Mechanism through directly contacting (in writing) the Complaint Receiving Officer (CRO) at ADB headquarters or the ADB India Resident Mission (INRM). The complaint can be submitted in any of the official languages of ADB's DMCs. The ADB Accountability Mechanism information will be included in the PID to be distributed to the affected communities, as part of the project GRM.



Figure 4: Grievance Redressal Process

VII. ENVIRONMENTAL MANAGEMENT PLAN

A. Environmental Management Plan

118. The following tables show the potential environmental impacts, proposed mitigation

¹⁰ The Empowered Committee (EC) will be chaired by the Minister of Urban Development and Housing, and members will include Ministers, Directors and/or representatives of other relevant Government Ministries and Departments

measures and responsible agencies for implementation and monitoring.

119. The purpose of the environmental management plan (EMP) is to ensure that the activities are undertaken in a responsible, non-detrimental manner with the objectives of: (i) providing a proactive, feasible, and practical working tool to enable the measurement and monitoring of environmental performance on-site; (ii) guiding and controlling the implementation of findings and recommendations of the environmental assessment conducted for the project; (iii) detailing specific actions deemed necessary to assist in mitigating the environmental impact of the project; and (iv) ensuring that safety recommendations are complied with.

120. A copy of the EMP must be kept at work sites at all times. This EMP will be included in the bid documents and will be further reviewed and updated during implementation. The EMP will be made binding on all contractors operating on the site and will be included in the contractual clauses. Non-compliance with, or any deviation from, the conditions set out in this document constitutes a failure in compliance.

121. For civil works, the contractor will be required to (i) establish an operational system for managing environmental impacts (ii) carry out all of the monitoring and mitigation measures set forth in the EMP; and (iii) implement any corrective or preventative actions set out in safeguards monitoring reports that the employer will prepare from time to time to monitor implementation of this IEE and EMP. The contractor shall allocate budget for compliance with these EMP measures, requirements and actions.

Field	Anticipated Impact	Mitigation Measures	Responsible for Implementation/ Monitoring	Cost and Source of Funds
Changing of raw sewage quality	Mixing of industrial effluent with sewage	 (i) No industrial wastewater shall be allowed to dispose into municipal sewers (ii) No domestic wastewater from industrial units shall be allowed into municipal sewers (iii) Ensure that there is no illegal discharge through manholes or inspection chambers (iv) Conduct public awareness programs; in coordination with RPCB, issue notice to all industries for compliance (v) 	PIU / PMU	Project Costs

Table 6: Design Stage Environmental Management Plan

Table 7: Environmental Management Plan of Anticipated Impacts during Pre-Construction

Field	Anticipated Impact	Mitigation Measures	Responsible for	Monitoring of Mitigation	Cost and Source of
Compliance with environmental subproject selection criteria	Environmental impacts due to subproject	Compliance with environmental subproject selection criteria A compliance checklist is appended to this report (Appendix 8)	PIU and Ganganagar Nagar Parishad	PMU	No costs required
Utilities	Telephone lines, electric poles and wires, water lines within proposed project area	 (i) Identify and include locations and operators of these utilities in the detailed design documents to prevent unnecessary disruption of services during construction phase; and (ii) Require construction contractors to prepare a contingency plan to include actions to be 	Contractor in collaboration with PIU and with approval of PMU	 (i) List of affected utilities and operators; (ii) Bid document to include requirement for a contingency plan for service interruptions (example provision of water if disruption is more than 24 hours), spoil management plan (Appendix 8), 	No cost required. Mitigation measures are part of TOR of PMU, PIU and PMDSC

Field	Anticipated Impact	Mitigation Measures	Responsible for	Monitoring of	Cost and Source of
		taken in case of unintentional interruption of services. (iii) Require contractors to prepare spoils management plan (Appendix 8) and traffic management plan (Appendix 9)		and traffic management plan (Appendix 9)	
Social and Cultural Resources	Ground disturbance can uncover and damage archaeological and historical remains	 (i) Consult Dept. of Archeology and museums, Government of Rajasthan to obtain an expert assessment of the archaeological potential of the site; (ii) Consider alternatives if the site is found to be of medium or high risk; (iii) Develop a protocol for use by the construction contractors in conducting any excavation work, to ensure that any chance finds are recognized and measures are taken to ensure they are protected and conserved. 	PIU	Chance Finds Protocol	No cost required. Mitigation measures are part of TOR of PIU and PMDSC
Construction work	Disruption to traffic	(i) Prioritize areas	Contractor to finalize	(i) List of selected	No cost required.
camps, hot mix	flow and sensitive	within or nearest	locations in	sites for construction	

Field	Anticipated Impact	Mitigation Measures	Responsible for	Monitoring of	Cost and Source of
			Implementation	Mitigation	Funds
plants, stockpile	receptors	possible vacant space	consultation and	work camps, hot mix	Mitigation measures
areas, storage areas,		in the project location;	approval of PIU	plants, stockpile	are part of TOR of
and disposal areas.		(II) If it is deemed		areas, storage areas,	PIU and PMDSC and
		necessary to locate		and disposal areas.	also part of
		elsewhere, consider		(ii) Written consent of	contractual terms
		sites that will not		landowner/s (not	
		promote instability and		lessee/s) for reuse of	
		result in destruction of		excess spoils to	
		property, vegetation,		agricultural land	
		irrigation, and drinking			
		water supply systems;			
		(iii) Do not consider			
		residential areas;			
		(iv) Take extreme care			
		in selecting sites to			
		avoid direct disposal			
		to water body which			
		will inconvenience the			
		community.			
		(v) For excess spoil			
		disposal, ensure (a)			
		site shall be selected			
		preferably from			
		barren, infertile lands.			
		In case agricultural			
		land needs to be			
		selected, written			
		consent from			
		landowners (not			
		lessees) will be			
		obtained; (b) debris			
		disposal site shall be			
		at least 200 m away			
		from surface water			
		bodies; (c) no			
		residential areas shall			
		be located within 50 m			
		downwind side of the			

Field	Anticipated Impact	Mitigation Measures	Responsible for Implementation	Monitoring of Mitigation	Cost and Source of Funds
		site; and (d) site is minimum 250 m away from sensitive locations like settlements, ponds/lakes or other water bodies.			
Sources of Materials	Extraction of materials can disrupt natural land contours and vegetation resulting in accelerated erosion, disturbance in natural drainage patterns, ponding and water logging, and water pollution.	(i) Prioritize sites already permitted by the Department of Mines and Geology (ii) If other sites are necessary, inform construction contractor that it is their responsibility to verify the suitability of all material sources and to obtain the approval of PMU and (iii) If additional quarries will be required after construction is started, inform construction contractor to obtain a written approval from PIU.	Contractor to prepare list of approved quarry sites and sources of materials with the approval of PIU	 (i) List of approved quarry sites and sources of materials; (ii) Bid document to include requirement for verification of suitability of sources and permit for additional quarry sites if necessary. 	No cost required. Mitigation measures are part of TOR of PIU and PMDSC and also part of contractual terms
Consents, permits, clearances, NOCs, etc.	Failure to obtain necessary consents, permits, NOCs, etc. can result to design revisions and/or stoppage of works	 (i) Obtain all necessary consents, permits, clearance, NOCs, etc. prior to award of civil works. (ii) Ensure that all necessary approvals for construction to be obtained by contractor are in place before 	PIU and PMDSC	Incorporated in final design and communicated to contractors.	No cost required. Cost of obtaining all consents, permits, clearance, NOCs, etc. prior to start of civil works responsibility of PIU. Mitigation measures are part of TOR of

Field	Anticipated Impact	Mitigation Measures	Responsible for Implementation	Monitoring of Mitigation	Cost and Source of Funds
		start of construction (iii) Acknowledge in writing and provide report on compliance all obtained consents, permits, clearance, NOCs, etc. (iv) Include in detailed design drawings and documents all conditions and provisions if necessary			PIU and PMDSC
Asbestos Cement Pipes	Health risk due to exposure to asbestos materials	 (i) Obtain details from PHED on location of underground AC pipes (ii) Locate the new pipe/sewer carefully to avoid encountering AC pipes (ii) Leave the AC pipes undisturbed in the ground. 	PIU and PMDSC	(i) Detailed construction drawings showing alignment of AC pipes	No cost required. Mitigation measures are part of TOR of PIU and PMDSC

Table 8: Environmental Management Plan of Anticipated Impacts during Construction

Field	Anticipated Impact	Mitigation Measures	Responsible	Monitoring of	Cost and Source of
			for	Mitigation	Funds
EMP Implementation Training	Irreversible impact to the environment, workers, and community	(i) Project manager and all key workers will be required to undergo EMP implementation including spoils management, Standard operating procedures (SOP) for construction works; occupational health and safety (OH&S), core labor laws,	Construction Contractor	(i) Certificate of Completion (Safeguards Compliance Orientation) (ii) Posting of Certification of Completion at	Cost of EMP Implementation Orientation Training to contractor is responsibility of PMU. Other costs responsibility of
		applicable environmental laws,		worksites	contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
		etc.		(iii) Posting of EMP at worksites	
Air Quality	Emissions from construction vehicles, equipment, and machinery used for installation of pipelines resulting to dusts and increase in concentration of vehicle-related pollutants such as carbon monoxide, sulfur oxides, particulate matter, nitrous oxides, and hydrocarbons.	 (i) Consult with PIU on the designated areas for stockpiling of clay, soils, gravel, and other construction materials; (iii) Damp down exposed soil and any stockpiled material on site by water sprinkling necessary during dry weather; (iv) Use tarpaulins to cover sand and other loose material when transported by trucks; and (v) Fit all heavy equipment and machinery with air pollution control devices which are operating correctly. 	Construction Contractor	 (i) Location of stockpiles; (ii) Complaints from sensitive receptors; (iii) Heavy equipment and machinery with air pollution control devices; (iv) Certification that vehicles are compliant with Air Act 	Cost for implementation of mitigation measures responsibility of contractor.
Surface water quality	Mobilization of settled silt materials, and chemical contamination from fuels and lubricants during installation of pipelines can contaminate nearby surface water quality.	 (i) Prepare and implement a spoils management plan (Appendix 4) (ii) Avoid stockpiling of earth fill especially during the monsoon season unless covered by tarpaulins or plastic sheets; (ii) Install temporary silt traps or sedimentation basins along the drainage leading to the water bodies; (iii) Place storage areas for fuels and lubricants away from any drainage leading to water bodies; (iv) Dispose any wastes generated by work in designated sites; and (v) Conduct surface quality inspection according to the Environmental Management Plan 	Construction Contractor	 (i) Areas for stockpiles, storage of fuels and lubricants and waste materials; (ii) Number of silt traps installed along trenches leading to water bodies; (iii) Records of surface water quality inspection; (iv) Effectiveness of water management measures; (v) No visible degradation to nearby drainages, nallahs or water bodies due to civil works 	Cost for implementation of mitigation measures responsibility of contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible	Monitoring of	Cost and Source of
			tor Mitigation	Mitigation	Funds
		(EMP).	milgation		
Noise Levels	Increase in noise level due to earth- moving and excavation equipment, and the transportation of equipment, materials, and people	 (i) Plan activities in consultation with PIU/PMDSC so that activities with the greatest potential to generate noise are conducted during periods of the day which will result in least disturbance; (ii) Horns should not be used unless it is necessary to warn other road users or animals of the vehicle's approach; (iii) Minimize noise from construction equipment by using vehicle silencers, fitting jackhammers with noise-reducing mufflers, and portable street barriers the sound impact to surrounding sensitive receptor; and (iv) Maintain maximum sound levels not exceeding 80 decibels (dbA) when measured at a distance of 10 m or more from the vehicle/s. 	Construction Contractor	(i) Complaints from sensitive receptors; (ii) Use of silencers in noise-producing equipment and sound barriers; (iii) Equivalent day and night time noise levels (see Appendix 3 of this IEE)	Cost for implementation of mitigation measures responsibility of contractor.
Landscape and aesthetics	Impacts due to excess excavated earth, excess construction materials, and solid waste such as removed concrete, wood, packaging materials, empty containers, spoils, oils, lubricants, and other similar items.	 (i) Prepare and implement spoils management plan (Appendix 8); (ii) Avoid stockpiling of excess excavated soils; (iii) Coordinate with ULB/PIU for beneficial uses of excess excavated soils or immediately dispose to designated areas; (iv) Recover used oil and lubricants and reuse or remove from the sites; (v) Manage solid waste according to the following preference 	Construction Contractor	 (i) Complaints from sensitive receptors; (ii) Worksite clear of hazardous wastes such as oil/fuel (iiv) Worksite clear of any excess excavated earth, excess construction materials, and solid waste such as removed concrete, wood, packaging materials, empty 	Cost for implementation of mitigation measures responsibility of contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
		hierarchy: reuse, recycling and disposal to designated areas; (vi) Remove all wreckage, rubbish, or temporary structures which are no longer required; and (vii) Request PIU to report in writing that the necessary environmental restoration work has been adequately performed before acceptance of work.		containers	
Existing Infrastructure and Facilities	Disruption of service and damage to existing infrastructure at specified project location	 (i) Obtain from PIU the list of affected utilities and operators if any; (ii) Prepare a contingency plan to include actions to be done in case of unintentional interruption of service 	Construction Contractor	Existing Utilities Contingency Plan	Cost for implementation of mitigation measures responsibility of contractor.
Ecological Resources – Terrestrial	Loss of vegetation and tree cover	 (i) Minimize removal of vegetation and disallow cutting of trees; (ii) If tree-removal will be required, obtain tree-cutting permit from the Revenue Department; and (iii) Plant two native trees for every one that is removed. 	Construction Contractor	PIU to report in writing the no of trees cut and planted.	Cost for implementation of mitigation measures responsibility of contractor.
Land use	Environmental Issues due to land use change	The impact due to change in land use will be negligible due to this project.	Not applicable	Not applicable	Not applicable
Accessibility	Traffic problems and conflicts near project locations and haul road	 (i) Plan transportation routes so that heavy vehicles do not use narrow local roads, except in the immediate vicinity of delivery sites; (ii) Schedule transport and hauling activities during non-peak hours; (iii) Locate entry and exit points in 	Construction Contractor	 (i) Traffic route during construction works including number of permanent signages, barricades and flagmen on worksite (Appendix 9); (ii) Complaints from sensitive receptors; 	Cost for implementation of mitigation measures responsibility of contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible	Monitoring of	Cost and Source of
			for	Mitigation	Funds
			witigation		
		areas where there is low potential			
		for traffic congestion;		signages placed at	
		(IV) Keep the site free from all		project location.	
		unnecessary obstructions;			
		(V) Drive venicies in a considerate			
		manner;			
		(VI) Coordinate with Traffic Police			
		for temporary road diversions and			
		with for provision of traffic aids if			
		transportation activities cannot be			
		avoided during peak hours;			
		(vii) Notify affected sensitive			
		receptors 1-week in advance by			
		providing sign boards informing			
		nature and duration of			
		construction works and contact			
		numbers for concerns/complaints.			
		(viii) Plan and execute the work in			
		such a way that the period of			
		disturbance/ loss of access is			
		minimum.			
		(ix) Provide pedestrian			
		access in all the locations until			
		normalcy is restored.			
Socio-Economic –	Impede the access	(i) Prepare and implement spoils	Construction	(i) Complaints from	Cost for
Income.	of residents and	management plan (Appendix 8)	Contractor	sensitive receptors;	implementation of
	customers to nearby	(ii) Leave spaces for access		(ii) Spoils management	mitigation measures
	shops	between mounds of soil;		plan	responsibility of
		(ii) Provide walkways and metal		(iii) Number of	contractor.
		sheets where required for people;		walkways, signages,	
		(iii) Increase workforce in front of		and metal sheets	
		critical areas such as institutions,		placed at project	
		place of worship, business		location.	
		establishment, hospitals, and			
		schools;			
		(iv) Consult businesses and			
		institutions regarding operating			

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
		hours and factoring this in work schedules; and (v) Provide sign boards for pedestrians to inform nature and duration of construction works and contact numbers for concerns/complaints.			
Socio-Economic - Employment	Generation of temporary employment and increase in local revenue	 (i) Employ at least 50% of the labour force, or to the maximum extent, local persons within the 2- km immediate area if manpower is available; (ii) Secure construction materials from local market. (iii) Comply with labor laws 	Construction Contractor	 (i) Employment records; (ii) Records of sources of materials (iii) Compliance to labor laws (see Appendix 7 of this IEE) 	Cost for implementation of mitigation measures responsibility of contractor.
Occupational Health and Safety	Occupational hazards which can arise during work	 (i) Comply with all national, state and local core labor laws (see Appendix 7 of this IEE) (ii) Develop and implement site- specific occupational health and safety (OH&S) Plan which will include measures such as: (a) excluding public from the site; (b) ensuring all workers are provided with and use personal protective equipment like helmet, gumboot, safety belt, gloves, nose musk and ear plugs; (c) OH&S Training for all site personnel; (d) documented procedures to be followed for all site activities; and (e) documentation of work-related accidents; (ii) Ensure that qualified first-aid can be provided at all times. Equipped first-aid stations shall be easily accessible throughout 	Construction Contractor	 (i) Site-specific OH&S Plan; (ii) Equipped first-aid stations; (iii) Medical insurance coverage for workers; (iv) Number of accidents; (v) Supplies of potable drinking water; (vi) Clean eating areas where workers are not exposed to hazardous or noxious substances; (vii) record of H&S orientation trainings (viii) personal protective equipment; (ix) % of moving equipment outfitted with audible back-up alarms; 	Cost for implementation of mitigation measures responsibility of contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible	Monitoring of	Cost and Source of
			for	Mitigation	Funds
			Mitigation		
		the site;		(xi) permanent sign	
		(iii) Provide medical insurance		boards for hazardous	
		coverage for workers;		areas such as	
		(iv) Secure all installations from		energized electrical	
		unauthorized intrusion and		devices and lines,	
		accident risks;		service rooms housing	
		(v) Provide supplies of potable		high voltage	
		drinking water:		equipment, and areas	
		(vi) The project area experiences		for storage and	
		extreme temperature during		disposal.	
		summer months of April and May,		(xii) Compliance to	
		which may affect the health of		core labor laws (see	
		workers engaged in construction		Appendix 7 of this	
		work. Contractor should take		IEE)	
		necessary measures during		,	
		summers including the following:			
		(a) work schedule should be			
		adjusted to avoid peak			
		temperature hours (12 – 3 PM);			
		(b) provide appropriate shade			
		near the work place; allow			
		periodic resting and provide			
		adequate water, and (c) provide			
		necessary medicine and facilities			
		to take care of dehydration			
		related health issues			
		(vii) Provide clean eating areas			
		where workers are not exposed			
		to hazardous or noxious			
		substances;			
		(viii) Provide H&S orientation			
		training to all new workers to			
		ensure that they are apprised of			
		the basic site rules of work at the			
		site, personal protective			
		protection, and preventing			
		injuring to fellow workers;			

Field	Anticipated Impact	Mitigation Measures	Responsible	Monitoring of	Cost and Source of
			for	Mitigation	Funds
			Mitigation		
		(ix) Provide visitor orientation if			
		visitors to the site can gain			
		access to areas where hazardous			
		conditions or substances may be			
		present. Ensure also that visitor/s			
		do not enter hazard areas			
		unescorted;			
		(x) Ensure the visibility of workers			
		through their use of high visibility			
		vests when working in or walking			
		through heavy equipment			
		operating areas;			
		(xi) Ensure moving equipment is			
		outfitted with audible back-up			
		alarms;			
		(xii) Mark and provide sign			
		boards for hazardous areas such			
		as energized electrical devices			
		and lines, service rooms housing			
		high voltage equipment, and			
		areas for storage and disposal.			
		Signage shall be in accordance			
		with international standards and			
		be well known to, and easily			
		understood by workers, visitors,			
		and the general public as			
		appropriate;			
		(xiii) Disallow worker exposure to			
		noise level greater than 85 dBA			
		for a duration of more than 8			
		hours per day without hearing			
		protection. The use of hearing			
		protection shall be enforced			
		actively; and			
		(xiv) Provide proper solid and			
		liquid waste management			
		program in workers' campsites,			

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
		separate from spoils and debris disposal, as their presence can add to existing waste volume at the project sites.			
Asbestos Cement (AC) Materials	Health risks associated with AC pipes	 (i) Left AC pipes in-situ. (ii) Training of all personnel (including manual labourers) to enable them to understand the dangers of AC pipes and to be able to recognize them in situ; (iii) Reporting procedures to inform management immediately if AC pipes are encountered; (iv) Development and application of a detailed OH&S procedure to protect both workers and citizens. This should comply with national and international standards for dealing with asbestos, and should include: (a) removal of all persons to a safe distance; (b) usage of appropriate breathing apparatus and protective equipment by persons delegated to deal with the AC material; and (c) Procedures for the safe removal and long-term disposal of all asbestos- containing material encountered. 	Construction Contractor	 (i) Site-specific OH&S Plan including AC pipe protocol (iii) record of OH&S orientation on AC Cement Materials Protocol (iv) personal protective equipment for AC materials (v) sign boards for pipe alignment identified as AC pipes. 	Cost for implementation of mitigation measures responsibility of contractor.
Community Health and Safety.	Traffic accidents and vehicle collision with pedestrians during material and waste transportation	 (i) Plan routes to avoid times of peak-pedestrian activities. (ii) Liaise with PIU/ULB in identifying high-risk areas on route cards/maps. (iii) Maintain regularly the vehicles and use of manufacturer-approved parts to 	Construction Contractor	 (i) Traffic Management Plan; (ii) Complaints from sensitive receptors 	Cost for implementation of mitigation measures responsibility of contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
		minimize potentially serious accidents caused by equipment malfunction or premature failure. (iv) Provide road signs and flag persons to warn of on-going trenching activities.			
Safety of sensitive groups (children, elders etc.) and others pedestrians in narrow streets	Trench excavation in in narrow streets will pose high risk to children and elders in the locality	 (i) Provide prior information to the local people about the nature and duration of work (ii) Conduct awareness program on safety during the construction work (iii) Undertake the construction work stretch-wise; excavation, pipe laying and trench refilling should be completed on the same day (iv) Provide barricades, and deploy security personnel to ensure safe movement of people and also to prevent unnecessary entry and to avoid accidental fall into open trenches 	Construction Contractor	Complaints from neighborhood and monitoring of accidents	Cost for implementation of mitigation measures responsibility of contractor.
Work Camps and worksites	Temporary air and noise pollution from machine operation, water pollution from storage and use of fuels, oils, solvents, and lubricants Unsanitary and poor living conditions for workers	 (i) Consult with PIU before locating project offices, sheds, and construction plants; (ii) Minimize removal of vegetation and disallow cutting of trees; (iii) Provide drinking water, water for other uses, and sanitation facilities for employees; (iv) Ensure conditions of livability at work camps are maintained at the highest standards possible at all times; Prohibit employees from 	Construction Contractor	 (i) Complaints from sensitive receptors; (ii) Drinking water and sanitation facilities for employees 	Cost for implementation of mitigation measures responsibility of contractor.

Field	Anticipated Impact	Mitigation Measures	Responsible	Monitoring of Mitigation	Cost and Source of
			Mitigation	witigation	T UIIUS
		poaching wildlife and cutting of trees for firewood; (v) Train employees in the storage and handling of materials which can potentially cause soil contamination; (vi) Recover used oil and lubricants and reuse or remove from the site; (vii) Manage solid waste according to the preference hierarchy: reuse, recycling and disposal to designated areas; (viii) Ensure unauthorized persons specially children are not allowed in any worksite at any			
Social and Cultural Resources	Risk of archaeological chance finds	 given time. (i) Strictly follow the protocol for chance finds in any excavation work; (ii) Request PIU or any authorized person with archaeological field training to observe excavation; (iii) Stop work immediately to allow further investigation if any finds are suspected; (iv) Inform PIU if a find is suspected, and take any action they require ensuring its removal or protection in situ. 	Construction Contractor	Records of chance finds	Cost for implementation of mitigation measures responsibility of contractor.
Submission of EMP implementation report	Unsatisfactory compliance to EMP	 (i) Appointment of supervisor to ensure EMP implementation (ii) Timely submission of monitoring reports including pictures 	Construction contractor	Availability and competency of appointed supervisor Monthly report	Cost for implementation of mitigation measures responsibility of contractor.
Post-construction	Damage due to	(i) Remove all spoils wreckage,	Construction	PIU/PMDSC report in	Cost for

Field	Anticipated Impact	Mitigation Measures	Responsible for	Monitoring of Mitigation	Cost and Source of Funds
			Mitigation		
clean-up	debris, spoils,	rubbish, or temporary structures	Contractor	writing that (i) worksite	implementation of
	excess construction	(such as buildings, shelters, and		is restored to original	mitigation measures
	materials	latrines) which are no longer		conditions; (ii) camp	responsibility of
		required; and		has been vacated and	contractor.
		(ii) All excavated roads shall be		restored to pre-project	
		reinstated to original condition.		conditions; (iii) all	
		(iii) All disrupted utilities restored		construction related	
		(iv) All affected structures		structures not relevant	
		rehabilitated/compensated		to O&M are removed;	
		(v) The area that previously		and (iv) worksite	
		housed the construction camp is		clean-up is	
		to be checked for spills of		satisfactory.	
		substances such as oil, paint, etc.			
		and these shall be cleaned up.			
		(vi) All hardened surfaces within			
		the construction camp area shall			
		be ripped, all imported materials			
		removed, and the area shall be			
		top soiled and regrassed using			
		the guidelines set out in the			
		revegetation specification that			
		forms part of this document.			
		(vii) The contractor must arrange			
		the cancellation of all temporary			
		services.			
		(viii) Request PIU to report in			
		writing that worksites and camps			
		have been vacated and restored			
		to pre-project conditions before			
		acceptance of work.			

Table 9: Environmental Management Plan of Anticipated Impacts during Operation

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
Construction	All work sites	Implementation of dust control, noise	Weekly during	Supervising	No costs

Field	Anticipated Impact	Mitigation Measures	Responsible for Mitigation	Monitoring of Mitigation	Cost and Source of Funds
disturbances, nuisances, public & worker safety,		control, traffic management, & safety measures. Site inspection checklist to review implementation is appended at Appendix 12	construction	staff and safeguards specialists	required
Check for blockage and leakage problems reducing the water losses	It may affect the water supply system	Effectiveness of leak detection and water auditing to reduce the water losses Implementation of regular O&M schedules	Ganganagar Nagar Parishad/Oper ator	Ganganagar Nagar Parishad	SGNP Cost
Check the leakages blockages, overflow problem in sewers	It may affect the sewer system, contaminate land, water and create public health issues	Effective operation to avoid and/or immediate clearance of such leaks, blockages Implementation of regular O&M schedules	Ganganagar Nagar Parishad/Oper ator	Ganganagar Nagar Parishad	SGNP Cost
Check the leakages blockages, overflow problem in sewers	Occupational health & safety: for personnel cleaning underground sewers there is a risk due to oxygen deficiency and harmful gaseous emissions (hydrogen sulphide, carbon monoxide, methane, etc.);	 (i) Provide necessary health & safety training to the staff engaged sewer cleaning & maintenance (ii) provide appropriate personal protection equipment (including oxygen masks) 	Ganganagar Nagar Parishad/Oper ator	Ganganagar Nagar Parishad	SGNP Cost
Asset management	Reduction in NRW Increased efficiency of the system	Preparation of O & M Manual	Ganganagar Nagar Parishad	Ganganagar Nagar Parishad	SGNP cost

Table 10: Environmental Monitoring Plan of Anticipated Impacts during Construction

Monitoring field	Monitoring location	Monitoring parameters	Frequency	Responsibility	Cost & Source of Funds
Construction disturbances, nuisances, public & worker safety,	All work sites	Implementation of dust control, noise control, traffic management, & safety measures. Site inspection checklist to review implementation is appended at Appendix 12	Weekly during construction	Supervising staff and safeguards specialists	No costs required

Ambient air quality	3 locations (STP site, and centre of the town, and at construction)	 PM10, PM2.5, NO2, SO2, CO 	Once before start of construction Quarterly (yearly 4-times) during construction	Contractor	Cost for implementation of monitoring measures responsibility of contractor (51 samples x 4000 per sample = 204,000)
Ambient noise	3 locations (STP site, and centre of the town, and at construction)	Day time and night time noise levels	Once before start of construction Quarterly (yearly 4-times) during construction	Contractor	Cost for implementation of monitoring measures responsibility of contractor (51 samples x 1500 per sample = 76,500)

Table 11: Environmental Monitoring Plan of Anticipated Impacts during Operation

Monitoring field	Monitoring location	Monitoring parameters	Frequency	Responsibility	Cost & Source of Funds
Monitoring of quality of water supplied to consumers	Consumer end- random sampling in all zones	pH, Nitrite, Nitrate, Turbidity BOD, Total Alkalnity, Total coliform and Feacal coliform	Monthly once	SGNP	SGNP Cost
Pipeline network to sustain operational efficiency and avoid clogging and early occurrence of leakages	Pipeline network	to be included in O&M plan prepared under the project	as per O&M plan	SGNP	SGNP Cost

B. Institutional Requirements

Government. The Local Self Government Department (LSGD) of Government of 122. Rajasthan will be the Executing Agency (EA) and existing RUIDP will be the Implementing Agency (IA). The LSGD will be responsible for overall strategic planning, guidance and management of the RUSDP, and for ensuring compliance with loan release conditions and loan covenants. A policy support unit will be established in the LSGD to support the government for implementation of the policy actions under the program loan. The RUIDP will be responsible for planning, implementation, monitoring and supervision, and coordination of all activities under the RUSDP. The RUIDP will recruit two consulting firms - (i) project management, design and supervision consultant (PMDSC), and (ii) community awareness and participation consultant (CAPC) to provide support in implementation of RUSDP. Six Project Implementation Units (PIUs), one each of in six project towns, shall be set up directly to assist in implementation. PMU will support PIUs in implementation, management and monitoring of the project. PMU and PIUs will be assisted by PMDSC and CAPC. PIUs will appoint construction contractors to build infrastructure. Once the infrastructure is built and commissioned, the Urban Local Bodies will operate and maintain the infrastructure.

123. Project Officer (Environment) at PMU and Assistant Safeguard Officer (ASO) at each of the PIUs will be responsible for environment management and monitoring activities, and will be supported by Environment Safeguard Specialist of PMDSC Team and Community Mobilization of Community Awareness and Participation Consultant (CAPC).

124. At state-level an inter-ministerial Empowered Committee (EC) will be established to provide overall policy direction EC will provide approval for the projects and recommend to Government for providing administrative sanction for the sub-projects. City Level Committees (CLCs) will be established in each town to oversee the implementation at town level.

125. **Consultants**. PMU and PIUs will be assisted by Project Management, Design and Supervision Consultants (PMDSC) in project planning, preparation of project and cost estimates, coordination, technical guidance and supervision, financial control, training and overall project management. Consultant Team includes an environmental safeguards specialist (ESS), who will support PO (Environment) at PMU and ASOs at PIUs in implementation, management and monitoring of all safeguard related activities. The consultant team also includes an Assistant Construction Manager at each PIU responsible for the construction supervision including environmental safeguards at subproject town level. CAPC will support PIU in construction facilitation, community consultation and grievance registration and redressal during the construction.

126. **Contractor.** The contractor shall appoint an Environment, Health and Safety (EHS) supervisor who will be responsible on a day-to-day basis for (i) ensuring implementation of EMP, (ii) coordinating with the ACM and environment safeguards specialists (all levels PO, ASO & ESS); (iii) community liaison, consultations with interested/affected parties, and grievance redressal; and (iv) reporting. Requirement of EHS Supervisor will be included in the bid documents.

127. The following figure and **Table 12** summarizes the institutional responsibility of environmental safeguards at all stages of the project.



Figure 4: Environmental Safeguards Implementation Arrangement

ADB – Asian Development Bank; EARF – Environmental Assessment and Review Procedures; EHS – Environment, Health & Safety, EIA – Environmental Impact Assessment; EMP – Environmental Management Plan; GoR – Government of Rajasthar; IA – Implementing Agency; IEE – Initial Environmental Examination; PIU – Project Implementation Unit; PMU - Project Management Unit; PMDSC – Project Management, Design & Supervision Consultant; RUDP – Rajasthan Urban Infrastructure Development Project; REA – Rapid Environmental Assessment; SPS – Safeguard Policy Statement; 2009,

Responsible		Responsibility	
Agency	Pre-Construction Stage	Construction Stage	Post-Construction
Project Officer (Environment), RUIDP, PMU	 (i) Review REA checklists and assign categorization based on ADB SPS 2009 (ii) Review and approve EIA/IEE (iii) Submit EIA/IEE to ADB for approval and disclosure in ADB website (iv) Ensure approved IEEs are disclosed in RUIDP/PMU websites and summary posted in public areas accessible and understandable by local people. (v) Ensure environmental management plans (EMPs) are included in the bid documents and contracts (vi) Organize an orientation workshop for PMU, PIU, ULB and all staff involved in the project implementation on (a) ADB SPS, (b) Government of India national, state, and local environmental laws and regulations, (c) core 	 (i) Over-all environmental safeguards compliance of the project (iii) Monitor and ensure compliance of EMPs as well as any other environmental provisions and conditions. (i) Review monthly monitoring report (ii) Prepare and submit to ADB semi-annual monitoring reports (iv) If necessary prepare Corrective Action Plan and ensure implementation of corrective actions to ensure no environmental impacts; (iii) Review and submit Corrective Action Plans to ADB (iv) Organize capacity building programs on environmental safeguards 	Compliance monitoring to review the environmental performance of project component, if required and as specified in EMP

Table 12: Institutional Roles and Responsibilities

Responsible	Responsibility				
Agency	Pre-Construction Stage	Construction Stage	Post-Construction		
	labor standards, (d) OH&S, (e)	(iv) Coordinate with national			
	EMP implementation especially	and state level government			
	spoil management, working in	agencies			
	congested areas, public relations	(vi) Assist in addressing any			
	and ongoing consultations,	grievances brought about			
	grievance redress, etc.	through the Grievance			
	(VII) Assist in addressing any	timely meaner as par the IEEe			
	the Crievenee Bodroop	(iv) Coordinate Blue NCOo			
	Mechanism in a timely manner as	(IX) COORDINATE PIDS, INGOS,			
	ner the IFFs	mitigation measures involving			
	(viii) Organize an induction course	the community and affected			
	for the training of contractors	persons and ensure that			
	preparing them on EMP	environmental concerns and			
	implementation, environmental	suggestions are incorporated			
	monitoring requirements related to	and implemented			
	mitigation measures; and taking				
	immediate actions to remedy				
	unexpected adverse impacts or				
	ineffective mitigation measures				
	found during the course of				
	(ix) Ensure compliance with all				
	(ix) Ensure compliance with all dovernment rules and regulations				
	regarding site and environmental				
	clearances as well as any other				
	environmental requirements				
	(x) Assist PMU, PIUs, and project				
	NGOs to document and develop				
	good practice construction				
	guidelines to assist the				
	contractors in implementing the				
	provisions of IEE.				
	(XI) Assist in the review of the				
	to oncure compliance with the				
Assistant	(i) Conduct initial environmental	(i) Ensure EMP	(i) Conducting		
Safequard Officer.	assessment for proposed project	implementation is included in	environmental		
PIU & ULB	using REA checklists and submit	measuring works carried out	monitoring, as		
	to PMU	by the contractors and	specified in the EMP.		
	(ii) Prepare EIA/IEE based on	certifying payments.	(ii) Issuance of		
	categorization and submit to PMU	(ii) Ensure Corrective Action	clearance for		
	for approval	Plan is implemented.	contractor's post-		
	(iii) Ensure IEE is included in bid	(ii) Conduct public awareness	construction activities		
	documents and contract	campaigns and participation	as specified in the		
	agreements. Ensure cost of EMP	programs	EMP.		
	(iv) Disclose approved EIAs/IEEs	(iii) Frepare montiny reports.			
	(iv) Obtain all necessary	brought about through the			
	clearances, permits, consents	Grievance Redress			
	NOCs, etc. Ensure compliance to	Mechanism in a timely manner			
	the provisions and conditions.	as per the IEEs			
	(vi) EMP implementation				
	regarding sites for disposal of				
	wastes, camps, storage areas,				
	quarry sites, etc.				
	(vii) Ensure contractors undergo				
	EMP implementation orientation				
	prior to start of civil works				

Responsible	Responsibility				
Agency	Pre-Construction Stage	Construction Stage	Post-Construction		
Consultant - PMDSC 1. Environmental Safeguard Specialist 2. Assistant Construction Manager at PIU	 (i) Assist PIU in preparation of REA checklists and EIAs/IEEs (ii) Assist PIU in obtaining all necessary clearances, permits, consents, NOCs, etc. Ensure provisions and conditions are incorporated in the IEE and detailed design documents. (iii) Assist in ensuring IEE is included in bid documents and contract agreements. Assist in determining adequacy of cost for EMP implementation. (iv) Assist in addressing any concern related to IEE and EMP. (v) Assist in summarizing IEE and translating to language understood by local people. 	 (i) Monitor EMP implementation (ii) Recommend corrective action measures for non- compliance by contractors (iii) Assist in the review of monitoring reports submitted by contractors (iv) Assist in the preparation of monthly monitoring reports (vi) Assist in addressing any grievances brought about through the Grievance Redress Mechanism in a timely manner as per the IEEs 	(i) Assist in the inspection and verification of contractor's post- construction activities.		
Contractors	 (i) Ensure EMP implementation cost is included in the methodology. (ii) Undergo EMP implementation orientation prior to award of contract (iii) Provide EMP implementation orientation to all workers prior to deployment to worksites (iv) Seek approval for camp sites and sources of materials. (v) Ensure copy of IEE is available at worksites. Summary of IEE is translated to language understood by workers and posted at visible places at all times. 	 (i) Implement EMP. (ii) Implement corrective actions if necessary. (iii) Prepare and submit monitoring reports including pictures to PIU (iv) Comply with all applicable legislation, is conversant with the requirements of the EMP; (v) Brief his staff, employees, and laborer about the requirements of the EMP and provide environmental awareness training to staff, employees, and laborers; (vi) Ensure any sub-contractors/ suppliers who are utilized within the context of the contract comply with all requirements of the EMP. The Contractor will be held responsible for non-compliance on their behalf; (vii) Bear the costs of any damages/compensation resulting from non-adherence to the EMP or written site instructions; (viii) Ensure that PIU and ACM/ASO are timely informed of any foreseeable activities related to EMP implementation. (vi) Address any grievances brought about through the Grievance Redress Mechanism in a timely manner as per the IEEs 	(i) Ensure EMP post- construction requirements are satisfactorily complied (ii) Request certification from PIU		

C. Training Needs

128. The following **Table 13** presents the outline of capacity building program to ensure EMP implementation. The estimated cost is Rs.275,000 (excluding trainings of contractors which will be part of EMP implementation cost during construction) to be covered by the project's capacity building program. The detailed cost and specific modules will be customized for the available skill set after assessing the capabilities of the target participants and the requirements of the project by the ESS of PMDSC.

Description	Target Participants &	Estimate (INR)	Cost and Source of	
	Venue		Funds	
 Introduction and Sensitization to Environmental Issues (1 day) ADB Safeguards Policy Statement Government of India and Rajasthan applicable safeguard laws, regulations and policies including but not limited to core labor standards, OH&S, etc. Incorporation of EMP into the project design and contracts 	All staff and consultants involved in the project At PMU, Jaipur	INR 100,000 (Lump sum)	PMU cost	
- Monitoring, reporting and				
corrective action planning 2. EMP implementation (2 days) - Roles and responsibilities - OH&S planning and implementation - Wastes management (water, hazardous, solid, excess construction materials, spoils, etc.) - Working in congested areas, - Public relations - Consultations - Grievance redress - Monitoring and corrective action planning - Reporting and disclosure - Post-construction planning	All staff and consultants involved in the Ton subproject All contractors prior to award of contract At PIU, Ganganagar	INR 50,000 (Lump sum)	PMU cost	
3. Plans and Protocols (1	All staff and consultants	Lump sum	PMU cost	
day) - Construction site	involved in the project	INR 25,000 (Lump sum)		
standard operating procedures (SOP)	All contractors prior to	Lump sum	Contractors cost as compliance to contract	

Table 13: Outline Capacity Building Program on EMP Implementation

Description	Target Participants & Venue	Estimate (INR)	Cost and Source of Funds	
 AC pipe protocol Site-specific EMP Traffic management plan Spoils management plan Waste management plan 	award of contract or during mobilization stage. At PIU Ganganagar	INR 25,000 (Lump sum)	provisions on EMP implementation (refer to EMP tables)	
 Chance find protocol O&M plans Post-construction plan 				
 4. Experiences and best practices sharing Experiences on EMP implementation Issues and challenges Best practices followed 	All staff and consultants involved in the project All contractors All NGOs At PIU Jaipur	INR 100,000 (Lump sum)	PMU Cost	
5. Contractors Orientation to Workers on EMP implementation (OH&S, core labor laws, spoils management, etc.)	All workers (including manual laborers) of the contractor prior to dispatch to worksite	Lump sum INR 25,000 (Lump sum)	Contractors cost as compliance to contract provisions on EMP implementation (refer to EMP tables)	

Summary of Capacity Building cost for EMP Implementation

Total	- INR 325,000
PMU Cost	- INR 275,000
Contractor Cost	- INR 50,000

D. Monitoring and Reporting

129. Prior to commencement of the work, the contractor will submit a compliance report to PIU ensuring that all identified pre-construction environmental impact mitigation measures as detailed in the EMP will be undertaken. PIU with the assistance of the ASO and ESS of PMDSC will review the report and thereafter PMU will allow commencement of works.

130. During construction, results from internal monitoring by the contractor will be reflected in their fortnightly (twice a month) EMP implementation reports to the PIU and Assistant Construction Manager of PMDSC. ASO and ACM will review and advise contractors for corrective actions if necessary. Monthly report summarizing compliance and corrective measures taken will be prepared by ASO with the assistance of ACM and submitted to PMU.

131. Based on monthly reports and measurements, PMU will draft, review, and submit to ADB, 6-monthly (twice a year) EMP implementation progress report (**Appendix 10**). Once concurrence from the ADB is received the report will be disclosed in the Project website.

132. ADB will review project performance against the RUSDP commitments as agreed in the legal documents. The extent of ADB's monitoring and supervision activities will be commensurate with the project's risks and impacts. Monitoring and supervising of social and environmental safeguards will be integrated into the project performance management system

E. EMP Implementation Cost

133. Most of the mitigation measures require the contractors to adopt good site practice, which should be part of their normal procedures already, so there are unlikely to be major costs associated with compliance. Regardless of this, any costs of mitigation by the construction contractors or consultants are included in the budgets for the civil works and do not need to be estimated separately here. Mitigation that is the responsibility of PIU/ULB will be provided as part of their management of the project, so this also does not need to be duplicated here. Cost for the capacity building program is included as part of the project.

	Particulars	Stages	Unit	Total Number	Rate (INR)	Cost (INR)	Costs Covered By
Α.	Mitigation Measures						
1	Compensatory plantation measures	Construction	Per tree	20	1,000	20,000	Civil works contract
	Subtotal (A)					20,000	
В.	Monitoring Measures						
	Air quality monitoring	Construction	per sample	3 x 17 = 51	4,000	204,000	Civil works contract
	Noise levels monitoring	Construction	Per sample	3 x 17 = 51	1,500	76,500	Civil works contract
	Subtotal (B)					280,500	
С.	Capacity Building						
1.	Introduction and sensitization to environment issues	Pre- construction	lump sum			100,000	PMU
2.	EMP implementation	Construction	lump sum			50,000	PMU
3.	Plans and Protocols	Construction	lump sum			25,000	PMU
			lump sum			25,000	Civil works contract
4.	Experiences and best practices sharing	Construction/P ost- Construction	lump sum			100,000	PMU
5.	Contractors Orientation to Workers on EMP implementation	Prior to dispatch to worksite	Lump sum			25,000	Civil works contract
	Subtotal (C)					325,000	
D	Civil Works						<u></u>
1	Construction of shelters for workers.	Construction	Lump sum			1,300,000	Civil works contract
2	Providing Water Supply Facility for the workers	Construction	Lump sum			250,000	Civil works contract
3	Providing Sanitation	Construction	Per unit	13	20,00	260,000	Civil

Table 14: Cost Estimates to Implement the EMP
	Particulars	Stages	Unit	Total Number	Rate (INR)	Cost (INR)	Costs Covered By
	Facility for the workers				0		works contract
5	Barricading to a height of 1.8 m (frame with MS pipes and cover with corrugated sheets)	Construction	m2	14,789	126	1,863,446	Civil works contract
6	Traffic management (Pavement Markings, Channelizing Devices, Arrow Panels and Warning Lights)	Construction	Per unit (at each location)	12	3000 0	360,000	Civil works contract
	Sub Total (D)					4,033,446	
	Total (A+B+C)				INR	4,658,946	

Contractor Cost	- 4,383,946
PMU Cost	- 275,000
Total	- 4,658,946

VIII. CONCLUSION AND RECOMMENDATION

134. The process described in this document has assessed the environmental impacts of all elements of the Ganganagar water supply and sewerage subproject. All potential impacts were identified in relation to pre-construction, construction, and operation phases. Planning principles and design considerations have been reviewed and incorporated into the site planning and design process wherever possible; thus, environmental impacts as being due to the project design or location were not significant. During the construction phase, impacts mainly arise from the construction dust and noise, the need to dispose of large quantities of waste soil and import a similar amount of sand to support the sewer in the trenches; and from the disturbance of residents, businesses, traffic and important buildings by the construction work. The social impacts (access disruptions) due to construction activities are unavoidable, as the residential and commercial establishments exist along the roads where pipes/sewers will be laid. A resettlement plan has been developed in accordance with ADB SPS 2009 and Government of India laws and regulations.

135. Anticipated impacts of water supply during operation and maintenance will be related to detection and repair of leaks, pipe bursts. These are, however, likely to be minimal, as proper design and selection of good quality pipe material shall mean that leaks are minimal. Leak repair work will be similar to the pipe-laying work. Similarly sewers are not 100% watertight and leaks can occur at joints. Faulty section will be exposed and repaired following the same basic procedure as when the sewer was built. Also, sewer pipes require regular maintenance as silt inevitably collects in areas of low flow over time. Necessary equipment for cleaning and removal of blockages in the sewers are included in the project.

136. The public participation processes undertaken during project design ensured stakeholders are engaged during the preparation of the IEE. The planned information disclosure measures and process for carrying out consultation with affected people will facilitate their participation during implementation. The project's grievance redressal mechanism will provide the citizens with a platform for redressal of their grievances, and describes the channels, time

frame, and mechanisms for resolving complaints about environmental performance.

137. The EMP will assist the PMU, PIU, PMDSC and contractors in mitigating the environmental impacts, and guide them in the environmentally sound execution of the proposed project. The EMP will also ensure efficient lines of communication between PIU/ULB, PMU, consultants and contractor. A copy of the EMP shall be kept on-site during the construction period at all times. The EMP shall be made binding on all contractors operating on the site, and will be included in the contractual clauses. Non-compliance with, or any deviation from, the conditions set out in this document shall constitute a failure in compliance.

138. The project will benefit the general public by contributing to the long-term improvement of water supply and sewerage systems and community livability in Sri Ganganagar. The potential adverse environmental impacts are mainly related to the construction period, which can be minimized by the mitigating measures and environmentally sound engineering and construction practices.

139. Therefore, as per ADB SPS, the project is classified as environmental category B and does not require further environmental impact assessment.



Appendix 1: REA Check list

WATER SUPPLY

Instructions: This checklist is to be prepared to support the environmental classification of a project. It is to be attached to the environmental categorization form that is to be prepared and submitted to the Chief Compliance Officer of the Regional and Sustainable Development Department. This checklist is to be completed with the assistance of an Environment Specialist in a Regional Department. This checklist focuses on environmental issues and concerns. To ensure that social dimensions are adequately considered, refer also to ADB checklists and handbooks on (i) involuntary resettlement, (ii) indigenous peoples planning, (iii) poverty reduction, (iv) participation, and (v) gender and development. Answer the questions assuming the "without mitigation" case. The purpose is to identify potential impacts. Use the "remarks" section to discuss any anticipated mitigation measures.

Country/Project Title: Rajasthan Urban Sector Development Program/ Ganganagar Subproject

Sector Division: Urban Development

SCREENING QUESTIONS		No	REMARKS
Water Supply			
A. Project Siting			
Is the project area			
 Densely populated? 	N		Subproject activities extend to the entire town including the densely populated areas. There are no major negative impacts envisaged, because pipeline will be located in unused government lands alongside the existing roads and can be constructed without causing disturbance to, houses, and commercial establishments. In narrow streets, disruption to road users is likely, and measure like best activity scheduling, alternative routes, prior information to road users, houses and shops will minimize the impact to acceptable levels.
 Heavy with development activities? 			Ganganagar is a developing town; urban expansion is considerable
 Adjacent to or within any environmentally sensitive areas? 			
Cultural heritage site		\checkmark	
Protected Area			
Wetland			
Mangrove			
Estuarine			
Buffer zone of protected area		\checkmark	
 Special area for protecting biodiversity 		\checkmark	
• Bay			
B. Potential Environmental Impacts Will the Project cause			

SCREENING QUESTIONS	Yes	No	REMARKS		
 Pollution of raw water supply from upstream wastewater discharge from communities, industries, agriculture, and soil erosion runoff? 		V	Not applicable. The present project does not involve any proposal for intake works.		
 Impairment of historical/cultural monuments/areas and loss/damage to these sites? 					
 Hazard of land subsidence caused by excessive ground water pumping? 			Not applicable; subproject does not involve groundwater abstraction		
 Social conflicts arising from displacement of communities? 			Project does not involve land acquisition /displacement. No social conflicts envisaged		
 Conflicts in abstraction of raw water for water supply with other beneficial water uses for surface and ground waters? 			Not applicable. The present project does not involve any proposal for intake works		
 Unsatisfactory raw water supply (e.g. excessive pathogens or mineral constituents)? 		\checkmark	The existing raw water supply will continue; no source intervention (new/ augmentation/ modification) is part of this subproject		
 Delivery of unsafe water to distribution system? 		\checkmark	The present project does not involve any proposal for upgrade / refurbishment of water treatment plant. The existing treatment plants will be maintained properly by the ULB to have the outlet quality meeting drinking water standards		
 Inadequate protection of intake works or wells, leading to pollution of water supply? 		\checkmark	Not applicable. The civil works are limited to distribution network improvement (DNI)		
 Over pumping of ground water, leading to salinization and ground subsidence? 		\checkmark	Not applicable; subproject does not involve groundwater abstraction		
Excessive algal growth in storage reservoir?		\checkmark	Not applicable; subproject does not involve storage reservoirs		
 Increase in production of sewage beyond capabilities of community facilities? 			Sewerage system will also be improved under RUSDP along with water supply		
 Inadequate disposal of sludge from water treatment plants? 		\checkmark	The present project does not involve any proposal for altering design / facilities in Water Treatment Plant. The ULB has to ensure appropriate disposal of sludge		
 Inadequate buffer zone around pumping and treatment plants to alleviate noise and other possible nuisances and protect facilities? 		V	. The present project does not involve any pumping and treatment plants.		
 Impairments associated with transmission lines and access roads? 			Temporary impairments are anticipated along the new transmission line routes during construction stage. No new access roads are proposed.		
 Health hazards arising from inadequate design of facilities for receiving, storing, and handling of chlorine and other hazardous chemicals. 			The present project does not involve any proposal for altering design / facilities for chlorination		
Health and safety hazards to workers from the management of chlorine used for disinfection and other contaminants?		V	The present project does not involve any proposal for changes in operation of Water Treatment Plant. The ULB to follow proper safety procedures		
Dislocation or involuntary resettlement of people			There is no resettlement of people for project implementation.		
 Social conflicts between construction workers from other areas and community workers? 		1	The contractor will be utilizing the local labour force as far as possible; in case if it is unavoidable, labour camps and facilities will be provided appropriately. No conflicts envisaged		

SCREENING QUESTIONS		No	REMARKS
 Noise and dust from construction activities? 	\checkmark		All the construction machineries employed will comply with noise emission standards of Central Pollution Control Board. Dust suppression measures such as water sprinkling will be employed
 Increased road traffic due to interference of construction activities? 	\checkmark		Excavation and laying pipelines along public roads will interfere with the traffic. Construction material transport will increase traffic within city. Proper traffic management and construction planning will be ensured to minimize the interference
 Continuing soil erosion/silt runoff from construction operations? 	\checkmark		Construction work during monsoon shall be carried out with due care so that silt run off due to construction operation is prevented. No construction will be allowed during rains.
 Delivery of unsafe water due to poor O&M treatment processes (especially mud accumulations in filters) and inadequate chlorination due to lack of adequate monitoring of chlorine residuals in distribution systems? 		\checkmark	The present project does not involve any proposal for altering design / facilities for chlorination facilities
 Delivery of water to distribution system, which is corrosive due to inadequate attention to feeding of corrective chemicals? 		\checkmark	Not envisaged
 Accidental leakage of chlorine gas? 			The present project does not involve any proposal for altering design / facilities for chlorination facilities
Excessive abstraction of water affecting downstream water users?			The existing raw water supply will continue; no source intervention (new/ augmentation/ modification) is part of this subproject
 Competing uses of water? 		\checkmark	The existing raw water supply will continue; no source intervention (new/ augmentation/ modification) is part of this subproject
 Increased sewage flow due to increased water supply 	\checkmark		Sewerage system will also be improved under RUSDP along with water supply
 Increased volume of sullage (wastewater from cooking and washing) and sludge from wastewater treatment plant 	\checkmark		Sewerage system will also be improved under RUSDP along with water supply; this will take care of additional wastewater. Treatment & disposal facilities are under construction in Ganganagar.
Sewerage	Yes	No	Remarks
A. Potential Environmental Impacts Will the Project cause			
 impairment of historical/cultural monuments/areas and loss/damage to these sites? 		V	No
 interference with other utilities and blocking of access to buildings; nuisance to neighboring areas due to noise, smell, and influx of insects, rodents, etc.? 	V		Sewers will be laid underground, and will be located away from water lines maintaining the minimum distance according to standards. Construction work may interfere with the power and communication lines, but resultant impact will be minimized with co-ordination of concerned agencies in finalization of best alignment and shifting of utilities, if required.

SCREENING QUESTIONS	Yes	No	REMARKS
 dislocation or involuntary resettlement of people 			Project does not involve land acquisition / involuntary resettlement /displacement.
			During the sewer construction, particularly in narrow streets and streets with on street commercial activities, there may be temporary disruption or relocation of hawkers and vendors. These are addressed through preparation of resettlement plan.
 Impairment of downstream water quality due to inadequate sewage treatment or release of untreated sewage? 		\checkmark	Sewage treatment facilities are already in place, no new facilities are constructed in the project
 Overflows and flooding of neighboring properties with raw sewage? 		V	Sewerage system is designed following standards. Flooding and overflowing will be avoided through regular operation and maintenance.
 Environmental pollution due to inadequate sludge disposal or industrial waste discharges illegally disposed in sewers? 		\checkmark	Sewage treatment facilities are already in place, no new facilities are constructed in the project
			domestic wastewater, no industrial wastewater discharge is allowed into the sewerage system.
 Noise and vibration due to blasting and other civil works? 		V	Blasting for underground works is unlikely, mainly because of geological setting. Road cutting works for sewers is likely to generate noise. Scheduling of works appropriately and prior information to the affected people will minimize the impact.
 Discharge of hazardous materials into sewers, resulting in damage to sewer system and danger to workers? 		V	This sewerage system will cater only to domestic wastewater, no industrial wastewater discharge is allowed into the sewerage system. As a precaution, domestic wastewater from industrial units will also not be allowed into sewers.
 Inadequate buffer zone around pumping and treatment plants to alleviate noise and other possible nuisances, and protect facilities? 		\checkmark	There are no pumping stations in the project
 Social conflicts between construction workers from other areas and community workers? 		\checkmark	The contractor will be utilizing the local labour force as far as possible; in case if it is unavoidable, labour camps and facilities will be provided appropriately. No conflicts envisaged
 Road blocking and temporary flooding due to land excavation during the rainy season? 		√	Underground construction works (sewer laying, foundations) will be carried out in non-monsoon period. In Ganganagar, rainfall is scanty and confined only to a limited period. No impacts envisaged
 Noise and dust from construction activities? 	V		Road cutting (cement and bituminous roads) for sewer laying works is likely to generate noise. Scheduling of works appropriately and prior information to the affected people will minimize the impact. Dust generation will be controlled through water sprinkling, immediate transportation of excess soil, covered transport etc.

SCREENING QUESTIONS	Yes	No	REMARKS
 traffic disturbances due to construction material transport and wastes? 	\checkmark		Linear activities like sewer laying along the roads is likely to disrupt traffic. Vehicle movement for construction purpose will increase the traffic. Identification of alternate routes, allowing limited - at least one-way traffic, prior information about the works and alternative arrangements, providing information/sign boards etc. will reduce the impact.
temporary silt runoff due to construction?		\checkmark	Ganganagar is predominantly dry and rainfall is very limited
 hazards to public health due to overflow flooding, and groundwater pollution due to failure of sewerage system? 	V		Sewerage system will be designed with applicable standards. Adequate trained staff and necessary equipment will be in place for regular operation and maintenance of the system. Proposed treatment system will be efficient and appropriate repair and maintenance procedure will be developed. Sufficient funds for operation will be ensured. Backup power supply system is part of project.
 deterioration of water quality due to inadequate sludge disposal or direct discharge of untreated sewage water? 		\checkmark	No treatment plant proposed in this project; existing facilities will be utilized for the purpose.
 contamination of surface and ground waters due to sludge disposal on land? 			No treatment plant proposed in this project; existing facilities will be utilized for the purpose.
 Health and safety hazards to workers from toxic gases and hazardous materials which may be contained in sewage flow and exposure to pathogens in sewage and sludge? 		\checkmark	Necessary apparatus and personal protection equipment will be provided. Staff will be trained in safe handling of sewage and in cleaning of sewers

Climate Change and Disaster Risk Questions The following questions are not for environmental categorization. They are included in this checklist to help identify potential climate and disaster risks.	Yes	No	Remarks
Is the Project area subject to hazards such as earthquakes, floods, landslides, tropical cyclone winds, storm surges, tsunami or volcanic eruptions and climate changes?	\checkmark		Arid zone, low and unreliable rainfall, less vegetation cover
Could changes in temperature, precipitation, or extreme events patterns over the Project lifespan affect technical or financial sustainability (e.g., changes in rainfall patterns disrupt reliability of water supply; sea level rise creates salinity intrusion into proposed water supply source)?		V	No
Are there any demographic or socio-economic aspects of the Project area that are already vulnerable (e.g.,high incidence of marginalized populations, rural-urban migrants, illegal settlements, ethnic minorities, women or children)?		V	No
Could the Project potentially increase the climate or disaster vulnerability of the surrounding area (e.g., by using water from a vulnerable source that is relied upon by many user groups, or encouraging settlement in earthquake zones)?		V	No

SL	Pollutants	Time	Concentration in ar	nbient air	Method of measurement
NO:		average	Industrial, Residential, Rural & Other Areas	Ecologically Sensitive Areas	
1	Sulphur Dioxide (SO ₂) µg/m ³	Annual 24 hours	50 80	20 80	Improved West and Geake- Ultraviolet fluorescence
2	Nitrogen Dioxide (NO ₂) µg/m ³	Annual 24 hours	40 80	30 80	Modified Jacob & Hochheiser (Na-Arsenite) Chemiluminescence
3	Particulate Matter (Size less than 10 µm) or PM10 µg/m ³	Annual 24 hours	60 100	60 100	Gravimetric -TOEM -Beta attenuation
4	Particulate Matter (Size less than 2.5 µm) or PM2.5 µg/m ³	Annual 24 hours	40 60	40 60	Gravimetric -TOEM -Beta attenuation
5	Carbon Monoxide (CO) mg/m ³	8 hours 1 hours	02 04	02 04	Non Dispersive Infra Red (NDIR) Spectroscopy

Appendix 2: National Ambient Air Quality Standards

Area code	Category of area/zone	Limit in dB (A)		
		Day time	Night time	
А	Industrial area	75	70	
В	Commercial area	65	55	
С	Residential area	55	45	
D	Silence zone	50	40	

Appendix 3: National Ambient Air Quality Standards in Respect of Noise

S. No.	Parameter	Inland surface water	Public sewers	Land for irrigation
	2		3	
		(a)	(b)	(c)
1	Suspended solids mg/l, max.	100	600	200
2	Particle size of suspended solids	shall pass 850 micron IS Sieve	-	-
3	pH value	5.5 to 9.0	5.5 to 9.0	5.5 to 9.0
4	Temperature	shall not exceed 5oC above the receiving water temperature		
5	Oil and grease, mg/l max,	10	20	10
6	Total residual chlorine, mg/l max	1.0	-	-
7	Ammonical nitrogen (as N),mg/l, max.	50	50	-
8	Total kjeldahl nitrogen (as N);mg/l, max. mg/l, max.	100	-	-
9	Free ammonia (as NH3), mg/l,max.	5.0	-	-
10	Biochemical oxygen demand (3 days at 27oC), mg/l, max.	30	350	100
11	Chemical oxygen demand, mg/l, max.	250	-	-
12	Arsenic(as As).	0.2	0.2	0.2
13	Mercury (As Hg), mg/l, max.	0.01	0.01	-
14	Lead (as Pb) mg/l, max	0.1	1.0	-
15	Cadmium (as Cd) mg/l, max	2.0	1.0	-
16	Hexavalent chromium (as Cr + 6).mg/l, max.	0.1	2.0	-
17	Total chromium (as Cr) mg/l, max.	2.0	2.0	-
18	Copper (as Cu)mg/l, max.	3.0	3.0	-
19	Zinc (as Zn) mg/l, max.	5.0	15	-
20	Selenium (as Se)	0.05	0.05	-
21	Nickel (as Ni) mg/l, max.	3.0	3.0	-
22	Cyanide (as CN) mg/l, max.	0.2	2.0	0.2
23	Fluoride (as F) mg/l, max.	2.0	15	-
24	Dissolved phos- phates (as P),mg/l, max.	5.0	-	-
25	Sulphide (as S) mg/l, max.	2.0	-	-
26	Phenolic compounds (as C6H50H)mg/l, max.	1.0	5.0	-
27	Radioactive materials: (a) Alpha emitters micro curie mg/l, max.	10-7	10-7	10-8
	(b)Beta emittersmicro curie mg/l	10-6	10-6	10-7
28	Bio-assay test	90% suivival of fish after 96 hours in 100% effluent	90% survival of fish after 96 hours in 100% effluent	90% suivival of fish after 96 hours in 100% effluent
29	Manganese	2 mg/l	2 mg/l	-
30	Iron (as Fe)	3mg/l	3mg/l	-
31	Vanadium (as V)	0.2mg/l	0.2mg/l	-
32	Nitrate Nitrogen	10 mg/l	-	-

Appendix 4: General Standards for Discharge of Environmental Pollutants (Wastewater)

Appendix 5: Vehicle Exhaust Emission Norms

1. Passenger Cars					
Norms	CO(g/km)	HC+ NOx(g/km)			
1991Norms	14.3-27.1	2.0(Only HC)			
1996 Norms	8.68-12.40	3.00-4.36			
1998Norms	4.34-6.20	1.50-2.18			
India stage 2000 norms	2.72	0.97			
Bharat stage-II	2.2	0.5			
Bharat Stage-III	2.3	0.35 (combined)			
Bharat Stage-IV	1.0	0.18 (combined)			

2. Heavy Diesel Vehicles

Norms	CO(g/kmhr)	HC (g/kmhr)	NOx (g/kmhr)	PM(g/kmhr)
1991Norms	14	3.5	18	-
1996 Norms	11.2	2.4	14.4	-
India stage 2000 norms	4.5	1.1	8.0	0.36
Bharat stage-II	4.0	1.1	7.0	0.15
Bharat Stage-III	2.1	1.6	5.0	0.10
Bharat Stage-IV	1.5	0.96	3.5	0.02

Source: Central Pollution Control Board

CO = Carbon Monixide; g/kmhr = grams per kilometer-hour; HC = Hydrocarbons; NOx = oxides of nitrogen; PM = Particulates Matter

No.	Substance or characteristic	Requirement Desirable limit	Undesirable effect outside the desirable	Permissible limit in the absence of alternate Source	Remarks
Esse	ntial Characteristic		·	·	
1.	Colour Hazen Units, Max	5	Above 5, consumer acceptance decreases	25	Extended to 25 only if toxic Substance are not suspect in absence of alternate sources
2.	Odour	Unobjectiona ble	-	-	a) test cold and when heated b) test are several dilutions
3.	Taste	Agreeable	-	-	Test to be conducted only after safely has been established
4.	Turbidity (NTU) Max	5	Above 5, consumer acceptance decreases	10	-
5.	pH value	6.5 to 8.5	Beyond this range the water will after the mucous membrane and/or water supply system	No relaxation	-
6.	Total Hardness (mg/L) CaCO3	300	Encrustation in water supply structure and adverse effects on domestic use	600	-
7.	Iron (mg/L, Fe) Max	0.3	Beyond this limit taste/appearance are affected; has adverse effects on domestic uses and water supply structure and promotes iron bacteria	1.0	-
8.	Chlorides 250 (mg/L, Cl) Max	250	Beyond effects outside the desirable limit	1000	-
9.	Residual free Chlorine (mg/L), Max	0.2	-	-	To be applicable only when water is chlorinated. Tested at customer end. When protection against viral infection is required, it should be min. 0.5 mg/L.
Desi	rable Characteristics	1		1	
10.	Dissolved solids mg/L. Max	500	Beyond this, palatability decreases and may cause gastrointestinal irritation.	2000	-
11.	Calcium (mg/L, Ca) Max.	75	Encrustation in water supply structure and adverse effects on domestic use.	200	-
12.	Magnesium (mg/L, Mg) Max	30	Encrustation in water supply structure and adverse effects on domestic use.	100	-
13.	Copper (mg/L, Cu) Max	0.05	Astringent taste dis coloration and corrosion of pipes fittings and utensils	1.5	-

Appendix 6: Drinking Water Standards

No.	Substance or characteristic	Requirement Desirable limit	Undesirable effect outside the desirable	Permissible limit in the absence of alternate Source	Remarks
			will be caused beyond this.		
14.	Manganese (mg/L, Mn) Max	0.1	Beyond this limit taste/appearance are affected, has advers effect on domestic use and water supply structure	0.3	-
15.	Sulphate (mg/L, SO4) Max.	200	Beyond this causes gastro intestinal irritation when magnesium or sodium are present	400	May be extended upto 400 provided magnesium (as Mg) does not exceed 30
16.	Nitrate (mg/L, NO3) Max.	45	Beyond this methaemo globinemia takes place.	100	-
17.	Fluoride (mg/L, F) Max.	1.0	Fluoride may be kept as low as possible. High fluoride may cause fluorosis.	1.5	-
18.	Phenolic Compounds (mg/L C6H5OH) Max.	0.001	Beyond this, it may cause objectionable taste and odour	0.002	-
19.	Mercury (mg/L Hg) Max	0.001	Beyond this the water becomes toxic	No Relaxation.	To be tested when pollution is suspected
20	Cadmium (mg/L, Cd) Max	0.01	Beyond this the water becomes toxic	No Relaxation.	To be tested when pollution is suspected
21.	Selenium (mg/L, Se) Max	0.01	Beyond this the water becomes toxic.	No Relaxation.	To be tested when pollution is suspected
22.	Arsenic (mg/L, As) Max.	0.05	Beyond this the water becomes toxic	No Relaxation	To be tested when pollution is suspected
23.	Cyanide	0.05	Beyond this the water becomes toxic	No Relaxation	To be tested when pollution is suspected
24.	Lead (mg/L Pb) Max.	0.05	Beyond this the water becomes toxic	No Relaxation	To be tested when pollution is suspected
25.	Zinc (mg/L, Zn) Max.	5	Beyond this limit it can cause astringent taste and an opalescence in water	15	To be tested when pollution is suspected
26.	Anionic detergents (mg/L, MBAS) Max	0.2	Beyond this limit it can cause a light froth in water	1.0	To be tested when pollution is suspected
27.	Chromium (mg/L, Cr6+	0.05	May be carcinogenic above this limit	-	-
28.	Polynuclear Aromatic Hydrocarbons (mg/l, PAH) Max	-	May be carcinogenic	-	-
29.	Mineral oil (mg/L)	0.01	Beyond this limit, undesirable taste and odour after chlorination takes place	0.03	To be tested when pollution is suspected
30.	Pesticides (mg/L) max	Absent	Toxic	0.001	-
Radio	pactive materials				
31.	Alpha emitters Bq/L Max	-	-	0.1	-
32.	Beta emitters Pci/L Max	-	-	1.0	-
33.	Alkalinity (mg/L,) Max	200	Beyond this limit, taste becomes unpleasant	600	-

No.	Substance or characteristic	Requirement Desirable limit	Undesirable effect outside the desirable	Permissible limit in the absence of alternate Source	Remarks
34.	Aluminum (mg/L, Al) Max	0.03	Cumulative effect is reported to cause dementia	0.2	
35.	Boron (mg/L) Max	1.0	-	5.0	-

Appendix 7: Compliance with Environmental Criteria for Subproject Selection

All Subprojects i. Comply with all requirements of relevant national and state laws. Being complied iii. Avoid significant environmental impacts. Being complied iii. Avoid significant environmental impacts. Complied iii. Avoid significant environmental impacts. Complied iii. Avoid significant environmental impacts. Complied iii. Avoid and/or minimize involuntary resettlement by prioritzing Complied iv. Avoid locating subprojects in forest areas Complied v. If there are underground asbetos cement (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground Being complied vi. Froi to site clearance & trench exaction for pipes/sewers, exact location of underground AC pipes should be ascertain with the Public Health Engineering Department (PHED) Complied vii. Avoid where possible. Retain mature roadside trees which are important/valuable on historically significant. If any trees Being complied ix. Avoid tree-cuting where possible. Retain mature roadside trees which are important/valuable on historically significant. If any trees Being complied water Supply i. Comply with all requirements of relevant national and local laws, trues, and guidelines. Being complied water Supply i. Avoid water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source ove	Applicability	Environmental Selection Criteria	Compliance
iii. Avoid significant environmental impacts. Being complied iiii. Avoid and/or minimize involuntary resettlement by prioritizing Complied ivi. Avoid locating subprojects in forest areas Complied ivi. Avoid locating subprojects in forest areas Complied vi. Avoid locating subprojects in forest areas Complied vi. Prior to site clearance & trench exaction for pipes/sewers, exact locations of underground AC pipes should be ascentani with the Public Being complied vii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Complied viii. Avoid there coupsible calconinmize to extent feasible, facilities in locations with social conflicts. Being complied viii. Avoid three-cuting where possible. Retain mature roadside trees Being complied viii. Avoid three-cuting where possible. Retain mature roadside trees Being complied viii. Avoid tree-cuting where possible. Retain mature roadside trees Being complied whore to be removed, plant two new trees for every one that is lost. Being complied viii. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied whore to be removed, plant two new tests for groups Being complied with void using vue test corees stabilishing water availability	All Subprojects	i. Comply with all requirements of relevant national and state laws.	Being complied
iii. Avoid and/or minimze involuntary resettlement by prioritizing Complied iii. Avoid and/or minimze involuntary resettlement by prioritizing Complied iv. Avoid locating subprojects in forest areas Complied v. If there are underground asbestos cement (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground Design and the project design should include that the AC pipes are left undisturbed in the ground Design and the project design should include that the AC pipes are left undisturbed in the ground Design and the project design should include that the AC pipes are left undisturbed in the ground Design and the project design should include that the AC pipes are left undisturbed in the ground Design and the project design should include that the AC pipes are left undisturbed in the ground Design and the project design should include the accellant the project design should include the accellant mature tradicide trees Being complied viii. Avoid there possible consultation and turber places/values. Being complied Design complied ix. Avoid tree-cutting where possible. Retain mature tradicide torees which are important/valuable on thiorclarily significant. If any trees and neclude women, Reflect inputs from public consultation and factoral value design and decisions are made in consultation with local consultation and local laws, trues, and guidelines. Being complied Water Supply I. Comply with all requirements of relevant national and local laws, trues, and guidelines. <		ii. Avoid significant environmental impacts.	Being complied
rehabilitation over new construction, using vacant government land where possible, and taking all possible measures in design and selection of site or alignment to avoid resettlement impacts Complied iv. Avoid locating subprojects in forest areas Complied v. If there are underground absetsos coment (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground Being complied viii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Complied viii. Avoid where possible catations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid there-culting where possible. Retain mature roadside trees which are important/valuable or historical significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied ii. Complied Eeing complied water Supply i. Complied communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied with vising/mictant reductions in the quantity or quality of the source overall); augmentation of weater supply from an existing groundwater source or development of new groundwater subles groundwater source or development of new groundwater subles groundwater source or development of new groundwater subles of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of weater supply more an exist		iii. Avoid and/or minimize involuntary resettlement by prioritizing	Complied
where possible, and taking all possible measures in design and selection of site or void resettlement impacts Complied iv. Avoid locating subprojects in forest areas Complied Complied v. If there are underground absestos cement (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground vi. Prior to site clearance & trench exaction for pipes/severs, exact. Iocation of underground AC pipes should be ascentain with the Public Health Engineering Department (PHED) Complied vii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Complied viii. Avoid where possible locations that will result in destruction/disturbance to historically significant. If any trees which are importanze to historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied Water Supply i. Complivith all requirements of relevant national and local laws, selection. Being complied witter Supply i. Comply with all requirements of relevant national and local laws, selection. Being complied witter Supply i. Utilize water sources at sustainable levels of abstraction only (i.e. withou significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable with Audit		rehabilitation over new construction, using vacant government land	
selection of site or alignment to avoid resettlement impacts Complied iv. Avoid locating subprojects in forest areas Complied v. If there are underground asbestos cement (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground Being complied vi. Prior to site dearance & trench exaction for pipes/severs, exact locations of underground AC pipes should be ascertain with the Public Health Engineering Department (PHED) Complied viii. Avoid where possible focations that will result in destruction/disturbance to historical and cultural places/values. ix. Avoid tree-cuting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every on ethat is lost. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied without significant reductions in the quantity or quality of the source overally: augmentation of water supply from a vesting groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable vii. Locate all new facilities/buildings at istes where there is no risk of rooker purposes (e.g., irrigation); Not applicable vii. Locate all new facilities/buildings at istes where there is no risk of roother purposes (e.g., irrigation); Not applicable vii. Locate all new fa		where possible, and taking all possible measures in design and	
iv. Avoid locating subprojects in torest areas Complied v. If there are underground absetsos cement (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground Being complied ear left undisturbed in the ground V. Prior to site clearance & trench exaction for pipes/sewers, exact location of underground AC pipes should be ascertain with the Public Complied vii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Complied viii. Avoid where possible locations that will result in destruction/disturbance to historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied ix. Avoid tree-cutting where possible for ensultation and disclosure for site selection. Being complied water Supply I. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied water Supply I. Utilize water sources that may be polluted by upstream users: Not applicable waters: v. Locate all new tacilities builting at distrestream or nor sits of flooding or other tazards that might imgair functioning of, or present a nay obstruct, sources hould be supported by groundwater studies establishing water availability and sustainability or water treatment plants, tankstreservisor, or their environs. Complied v. Locate all new tacilities b		selection of site or alignment to avoid resettlement impacts	
v. If there are underground asbestos cement (AC) pipes in the existing systems, the project design should include that the AC pipes are left undisturbed in the ground vi. Prior to site clearance & tench exaction for pipe/sewers, exact location of underground AC pipes should be ascertain with the Public Health Engineering Department (PHED) Complied vii. Avoid where possible. and minimize to extent feasible, facilities in locations with social contincts. Department (PHED) Department (PHED) vii. Avoid there cutting where possible. Retain mature roadside trees which are important/valuable or historicall and cultural places/values. Deing complied ix. Avoid there-cutting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied water Supply I. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied Water Supply Ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source over anil; augmentation of water source should be supported by groundwater sources that may be polluted by upstream users; Not applicable vii. Avoid water-use conflicts by not abstracting water that is used for the purposes (e.g., irrigation); Not applicable vii. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present of flooding or other hazards that might impair functioning or, or pre		iv. Avoid locating subprojects in forest areas	Complied
existing systems, the project design should include that the AC pipes are left undisturbed in the ground vi. Prior to site clearance & trench exaction for pipes/sewers, exact location of underground AC pipes should be ascertain with the Public Health Engineering Department (PHED) Complied vii. Avoid where possible and minimize to extent feasible, facilities in locations with social conflicts. Being complied viii. Avoid where possible cations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid tree-cutting where possible. Retain mature roadside trees which are important/valuable on historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied with using water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater subalishing water availability and sustainability Not applicable vi. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs,		v. If there are underground asbestos cement (AC) pipes in the	Being complied
are left unbisturbed in the ground vi. Prior to site clearance & trench exaction for pipes/sewers, exact location of underground AC pipes should be ascertain with the Public Health Engineering Department (PHED) vii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Complied viii. Avoid where possible locations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid tree-cutting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability. Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi.		existing systems, the project design should include that the AC pipes	
Vi. Prior basile clearance & therein exaction for pipes/sewers, exact location of underground AC pipes should be accertain with the Public Health Engineering Department (PHED) Complied Vii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Being complied Vii. Avoid tree-outling where possible. Ration mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied X. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply I. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied Iii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater sudies establishing water availability and sustainability Not applicable Vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of read rate. Suppliced where supply as part of the scheme. Complied Vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of new land. Ensure that pipeline roother facilities are provided with an improved water su		are left undisturbed in the ground	
Health Engineering Department (PHED) Complied viii. Avoid where possible, and minimize to extent feasible, facilities in locations with social conflicts. Complied viii. Avoid where possible locations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid tree-cutting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied iii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable Complied v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. <td></td> <td>VI. Prior to site clearance & trench exaction for pipes/sewers, exact</td> <td></td>		VI. Prior to site clearance & trench exaction for pipes/sewers, exact	
vielant Engineering Department (PED) vielant engineering beginning to extent feasible, facilities in locations with social conflicts. Complied vielant engineering of the extent exposible locations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid wree-cutting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable vi. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); V. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impart functioning of, or present arisk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as f		Health Engineering Department (PHED)	
With Avoid where possible locations that will result in deside, facilities in design complied Complete viii. Avoid where possible locations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid tree-cutting where possible. Retain mature roadside trees have to be removed, plant two new trees for every one that is lost. Being complied ix. Avoid tree-cutting where possible. Retain mature roadside trees have to be removed, plant two new trees for every one that is lost. Being complied ix. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied iii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Complied v. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of and from private owners in amounts that		vii Avoid where possible, and minimize to extent feasible, facilities in	Complied
Viii. Avoid where possible locations that will result in destruction/disturbance to historical and cultural places/values. Being complied ix. Avoid tree-cutting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied X. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be susported by groundwater studies establishing water availability and sustainability Not applicable W. Avoid water-use conflicts by not abstracting water that is used for other purpose (e.g., irrigation); Not applicable Complied vi. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vii. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total lan		locations with social conflicts	Complied
Initial construction of disturbance to historical and cultural places/values. Description ix. Avoid tree-cutting where possible. Retain mature roadsidint Being complied which are important/valuable or historical and cultural places/values. Being complied water to be removed, plant two new trees for every one that is lost. Second plant two new trees for every one that is lost. x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply I. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied iii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of		viji Avoid where possible locations that will result in	Being complied
Ix. Avoid tree-cutting where possible. Retain mature roadside trees which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Being complied x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater sources should be supported by groundwater sources that may be polluted by upstream users; Not applicable v. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other faci		destruction/disturbance to historical and cultural places/values	Denny complied
which are important/valuable or historically significant. If any trees have to be removed, plant two new trees for every one that is lost. Design of the optimization optimization optimization optimization optimization of the optimization optimization optimization optimization optimization optimization optimization optimis optimizatio optimizatio optimization optimization optimization		ix Avoid tree-cutting where possible. Retain mature roadside trees	Being complied
have to be removed, plant two new trees for every one that is lost. Here x Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source overall); augmentation of water supply from an existing groundwater source overally augmentation of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable Not applicable viv. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied viv. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable viv. Ensure tha		which are important/valuable or historically significant. If any trees	Donig complica
x. Ensure all planning and design interventions and decisions are made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable Users; iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (ROW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (<10%).		have to be removed, plant two new trees for every one that is lost.	
made in consultation with local communities and include women. Reflect inputs from public consultation and disclosure for site selection. Image: Consultation and disclosure for site selection. Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable Not applicable v. Acvid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable Complied v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of and from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied viii. Avoid all usage of pipes that are manufactured from asbestos concorrete.		x. Ensure all planning and design interventions and decisions are	Being complied
Reflect inputs from public consultation and disclosure for site selection. Being complied Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable Not applicable vis. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable Complied v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied		made in consultation with local communities and include women.	U
selection. selection. Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overally, augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable vi. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (ROW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme.		Reflect inputs from public consultation and disclosure for site	
Water Supply i. Comply with all requirements of relevant national and local laws, rules, and guidelines. Being complied ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable v. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of hand from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied x. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied <td< td=""><td></td><td>selection.</td><td></td></td<>		selection.	
rules, and guidelines. ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of new land. Ensure that pipeline routes do not require the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied x. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in wastewater and drainage to deal with the inc	Water Supply	i. Comply with all requirements of relevant national and local laws,	Being complied
ii. Utilize water sources at sustainable levels of abstraction only (i.e. without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Fusure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied x. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in wastewater and drainage to deal with the increa		rules, and guidelines.	
without significant reductions in the quantity or quality of the source overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied i. K. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied <td></td> <td>ii. Utilize water sources at sustainable levels of abstraction only (i.e.</td> <td>Not applicable</td>		ii. Utilize water sources at sustainable levels of abstraction only (i.e.	Not applicable
overall); augmentation of water supply from an existing groundwater source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable viii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		without significant reductions in the quantity or quality of the source	
source or development of new groundwater source should be supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tank/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in the source and drainage to deal with the increased discharge of domestic wastewater. Being complied		overall); augmentation of water supply from an existing groundwater	
Supported by groundwater studies establishing water availability and sustainability Not applicable iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater. Being complied		source or development of new groundwater source should be	
iii. Avoid using water sources that may be polluted by upstream users; Not applicable iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of their total land holding (>10%). Complied vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		supported by groundwater studies establishing water availability and	
iii. Avoid using water sources that may be political by upsiteant Not applicable iii. Avoid using water use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in the water supply system are combined with improvements in wastewater. Being complied x. Ensure appropriate training will be provided to UI B staff on the Being complied		Sustainability	Not oppliaghla
iv. Avoid water-use conflicts by not abstracting water that is used for other purposes (e.g., irrigation); Not applicable v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Complied vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		III. Avoid using water sources that may be politited by upstream	Not applicable
with Avoid water base commiss by not abstracting water that is used for other purposes (e.g., irrigation); Inter substracting water that is used for other purposes (e.g., irrigation); Inter substracting water that is used for flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Complied vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater. Being complied x. Ensure appropriate training will be provided to UI B staff on the Being complied		iv Avoid water-use conflicts by not abstracting water that is used for	Not applicable
v. Locate all new facilities/buildings at sites where there is no risk of flooding or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Complied vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		other purposes (e.g., irrigation):	
If locing or other hazards that might impair functioning of, or present a risk of damage to water treatment plants, tanks/reservoirs, or their environs. Complied vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Complied vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater. Being complied		v Locate all new facilities/buildings at sites where there is no risk of	Complied
risk of damage to water treatment plants, tanks/reservoirs, or their environs.Compliedvi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%).Compliedvii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme.Not applicableviii. Avoid all usage of pipes that are manufactured from asbestos concrete.Compliedix. Ensure water to be supplied to consumers will meet national drinking water standards at all times.Being compliedx. Ensure that improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater.Being compliedxi. Ensure appropriate training will be provided to UI B staff on theBeing complied		flooding or other hazards that might impair functioning of, or present a	Complica
environs. vi. Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Complied vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		risk of damage to water treatment plants, tanks/reservoirs, or their	
vi.Locate pipelines within road right of way (RoW) as far as possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%).Compliedvii.Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme.Not applicableviii.Avoid all usage of pipes that are manufactured from asbestos concrete.Compliedix.Ensure water to be supplied to consumers will meet national drinking water standards at all times.Being compliedx.Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater.Being complied		environs.	
possible, to reduce the acquisition of new land. Ensure that pipeline routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		vi. Locate pipelines within road right of way (RoW) as far as	Complied
routes do not require the acquisition of land from private owners in amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied		possible, to reduce the acquisition of new land. Ensure that pipeline	
amounts that are a significant proportion of their total land holding (>10%). Not applicable vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		routes do not require the acquisition of land from private owners in	
(>10%). vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		amounts that are a significant proportion of their total land holding	
vii. Ensure that communities who relinquish land needed for pipelines or other facilities are provided with an improved water supply as part of the scheme. Not applicable viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		(>10%).	
or other facilities are provided with an improved water supply as part of the scheme. Improved water supply as part of the scheme. viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		vii. Ensure that communities who relinquish land needed for pipelines	Not applicable
or the scheme. viii. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		or other facilities are provided with an improved water supply as part	
VIII. Avoid all usage of pipes that are manufactured from asbestos concrete. Complied ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		OT THE SCHEME.	Complied
ix. Ensure water to be supplied to consumers will meet national drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		vill. Avoid all usage of pipes that are manufactured from asbestos	Compliea
initial drinking water standards at all times. Being complied x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		UITUTETE.	Roing complied
x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the Being complied		IX. Ensure water to be supplied to consumers will meet hattonal	being complied
x. Ensure that improvements in the water supply system are combined with improvements in wastewater and drainage to deal with the increased discharge of domestic wastewater. Being complied xi. Ensure appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service appropriate training will be provided to UI B staff on the service approprise to the service approprise to the service appropria		uninking water standards at an innes.	Roing complied
the increased discharge of domestic wastewater.		combined with improvements in westewater and drainage to deal with	Being complied
xi. Ensure appropriate training will be provided to UI B staff on the Being complied		the increased discharge of domestic wastewater	
		xi Ensure appropriate training will be provided to LILR staff on the	Being complied
operations and maintenance of the facilities.		operations and maintenance of the facilities.	_ sing complica

Applicability	Environmental Selection Criteria	Compliance
	xii. Ensure sludge management facilities are included in the water treatment plant.	Not applicable
Sewerage	i. Comply with all requirements of relevant national and local laws, rules, and guidelines.	Being complied
	ii. Ensure no immediate downstream drinking water intakes at treated wastewater disposal point.	Being complied
	iii. Locate sewage treatment plant (STP) preferably 500 m from any inhabited areas, in locations where no urban expansion is expected in the next 20 years, so that people are not affected by odor or other nuisance from the STP.	Not applicable
	iv. Locate facilities where there is a suitable means of disposal for the treated wastewater effluent and bio-solids.	Not applicable
	v. Locate facilities where there is no risk of flooding or other hazards that might impair operations and present a risk of damage to the facilities or its environs.	Not applicable
	vi. Ensure appropriate training will be provided to ULB staffs on the operations and maintenance of the facilities.	Being complied
	vii. Locate sewage pipelines on roads RoW wherever feasible, to reduce the acquisition of new land	Complied

Appendix 8: Salient Features of Major Labor Laws Applicable to Establishments Engaged in Construction of Civil Works

(i) Workmen Compensation Act, 1923 - The Act provides for compensation in case of injury by accident arising out of and during the course of employment.

(ii) Payment of Gratuity Act, 1972 - Gratuity is payable to an employee under the Act on satisfaction of certain conditions on separation if an employee has completed 5 years' service or more or on death at the rate of 15 days wages for every completed year of service. The Act is applicable to all establishments employing 10 or more employees.

(iii) Employees' PF and Miscellaneous Provisions Act, 1952 - The Act provides for monthly contributions by the employer plus workers @10 % or 8.33 %. The benefits payable under the Act are: (a) Pension or family pension on retirement or death as the case may be; (b) deposit linked insurance on the death in harness of the worker; (c) payment of PF accumulation on retirement/death etc.

(iv) Maternity Benefit Act, 1951 - The Act provides for leave and some other benefits to women employees in case of confinement or miscarriage etc.

(v) Contract Labour (Regulation and Abolition) Act, 1970 - The Act provides for certain welfare measures to be provided by the Contractor to contract labor and in case the Contractor fails to provide, the same are required to be provided by the Principal Employer by Law. The principal employer is required to take Certificate of Registration and the Contractor is required to take a License from the designated Officer. The Act is applicable to the establishments or Contractor of principal employer if they employ 20 or more contract labor.

(vi) Minimum Wages Act, 1948 - The employer is supposed to pay not less than the Minimum Wages fixed by appropriate Government as per provisions of the Act if the employment is a scheduled employment. Construction of Buildings, Roads, Runways are scheduled employment.

(vii) Payment of Wages Act, 1936 - It lays down as to by what date the wages are to be paid, when it will be paid and what deductions can be made from the wages of the workers.

(viii) Equal Remuneration Act, 1979 - The Act provides for payment of equal wages for work of equal nature to Male and Female workers and not for making discrimination against Female employees in the matters of transfers, training and promotions etc.

(ix) Payment of Bonus Act, 1965 - The Act is applicable to all establishments employing 20 or more workmen. The Act provides for payments of annual bonus subject to a minimum of 8.33 % of wages and maximum of 20 % of wages to employees drawing Rs. 3,500/- per month or less. The bonus to be paid to employees getting Rs. 2,500/- per month or above up to Rs.3,500/- per month shall be worked out by taking wages as Rs.2,500/- per month only. The Act does not apply to certain establishments. The newly set up establishments are exempted for five years in certain circumstances. Some of the State Governments have reduced the employment size from 20 to 10 for the purpose of applicability of the Act.

(x) Industrial Disputes Act, 1947 - The Act lays down the machinery and procedure for resolution of industrial disputes, in what situations a strike or lock-out becomes illegal and what are the requirements for laying off or retrenching the employees or closing down the establishment.

(xi) Industrial Employment (Standing Orders) Act, 1946 - It is applicable to all establishments employing 100 or more workmen (employment size reduced by some of the States and Central Government to 50). The Act provides for laying down rules governing the conditions of employment by the employer on matters provided in the Act and get the same certified by the designated Authority.

(xii) Trade Unions Act, 1926 - The Act lays down the procedure for registration of trade unions of workmen and employees. The trade unions registered under the Act have been given certain immunities from civil and criminal liabilities.

(xiii) Child Labor (Prohibition and Regulation) Act, 1986 - The Act prohibits employment of children below 14 years of age in certain occupations and processes and provides for regulation of employment of children in all other occupations and processes. Employment of child labor is prohibited in Building and Construction Industry.

(xiv) Inter-State Migrant Workmen's (Regulation of Employment and Conditions of Service) Act, 1979 -The Act is applicable to an establishment which employs 5 or more inter-state migrant workmen through an intermediary (who has recruited workmen in one state for employment in the establishment situated in another state). The inter-state migrant workmen, in an establishment to which this Act becomes applicable, are required to be provided certain facilities such as housing, medical aid, traveling expenses from home up to the establishment and back, etc.

(xv) The Building and Other Construction Workers (Regulation of Employment and Conditions of Service) Act, 1996 and the Cess Act of 1996 - All the establishments who carry on any building or other construction work and employ 10 or more workers are covered under this Act. All such establishments are required to pay Cess at rate not exceeding 2% of the cost of construction as may be notified by the Government. The employer of the establishment is required to provide safety measures at the building or construction work and other welfare measures, such as canteens, first-aid facilities, ambulance, housing accommodation for workers near the workplace etc. The employer to whom the Act applies has to obtain a registration certificate from the Registering Officer appointed by the Government.

Appendix 9: Sample Outline Spoil Management Plan

- The Spoil Management Plan should be site specific and be part of the monthly Construction Management Plan.
- The contractor, in consultation with the ULB, has to find out appropriate location/s for the disposal of the excess soil generated. The spoils should be deposited only at these sites.
- Further precautions need to be taken in case of the contaminated spoils.
- The vehicle carrying the spoil should be covered properly.
- The spoils generating from each site should be removed on the same day or immediately after the work is complete. The site / road should be restored to the original condition.

I. Spoils information

The spoil information contains the details like a) The type / material, b) Potential contamination by that type, c) Expected volume (site / component specific), d) Spoil Classification etc.

II. Spoils management

The Spoil Management section gives the details of a) Transportation of spoil b) disposal site details c) Precautions taken d) Volume of contaminated spoil, if present, d) Suggested reuse of disposal of the spoil

III. Documentation

The volume of spoil generated (site specific, date wise), site disposed, reuse / disposal details should be documented properly.

Appendix 10: Sample Outline Traffic Management Plan

A. Principles for TMP around the Water Pipes/Sewer Construction Sites

1. One of the prime objectives of this TMP is to ensure the safety of all the road users along the work zone, and to address the following issues:

- (i) the safety of pedestrians, bicyclists, and motorists travelling through the construction zone;
- (ii) protection of work crews from hazards associated with moving traffic;
- (iii) mitigation of the adverse impact on road capacity and delays to the road users;
- (iv) maintenance of access to adjoining properties; and
- (v) addressing issues that may delay the project.

B. Operating Policies for TMP

2. The following principles will help promote safe and efficient movement for all road users (motorists, bicyclists, and pedestrians, including persons with disabilities) through and around work zones while reasonably protecting workers and equipment.

- (i) Make traffic safety and temporary traffic control an integral and high-priority element of project from planning through design, construction, and maintenance.
- (ii) Inhibit traffic movement as little as possible.
- (iii) Provide clear and positive guidance to drivers, bicyclists, and pedestrians as they approach and travel through the temporary traffic control zone.
- (iv) Inspect traffic control elements routinely, both day and night, and make modifications when necessary.
- (v) Pay increased attention to roadside safety in the vicinity of temporary traffic control zones.
- (vi) Train all persons that select, place, and maintain temporary traffic control devices.
- (vii) Keep the public well informed.
- (viii) Make appropriate accommodation for abutting property owners, residents, businesses, emergency services, railroads, commercial vehicles, and transit operations.

3. **Figure A2 to Figure A12** illustrates the operating policy for TMP for the construction of water pipes and the sewers along various types of roads.

C. Analyze the impact due to street closure

4. Apart from the capacity analysis, a final decision to close a particular street and divert the traffic should involve the following steps:

- (i) approval from the ULB/ Public Works Department (PWD) to use the local streets as detours;
- (ii) consultation with businesses, community members, traffic police, PWD, etc., regarding the mitigation measures necessary at the detours where the road is diverted during the construction;
- (iii) determining of the maximum number of days allowed for road closure, and incorporation of such provisions into the contract documents;

- (iv) determining if additional traffic control or temporary improvements are needed along the detour route;
- (v) considering how access will be provided to the worksite;
- (vi) contacting emergency service, school officials, and transit authorities to determine if there are impacts to their operations; and
- (vii) developing a notification program to the public so that the closure is not a surprise. As part of this program, the public should be advised of alternate routes that commuters can take or will have to take as result of the traffic diversion.

5. If full road-closure of certain streets within the area is not feasible due to inadequate capacity of the detour street or public opposition, the full closure can be restricted to weekends with the construction commencing on Saturday night and ending on Monday morning prior to the morning peak period.



Figure A1: Policy Steps for the TMP

D. Public awareness and notifications

6. As per discussions in the previous sections, there will be travel delays during the constructions, as is the case with most construction projects, albeit on a reduced scale if utilities and traffic management are properly coordinated. There are additional grounds for travel delays in the area, as most of the streets lack sufficient capacity to accommodate additional traffic from diverted traffic as a result of street closures to accommodate the works.

6. The awareness campaign and the prior notification for the public will be a continuous activity which the project will carry out to compensate for the above delays and minimize public claims as result of these problems. These activities will take place sufficiently in advance of the time when the roadblocks or traffic diversions take place at the particular streets. The reason for this is to allow sufficient time for the public and residents to understand the changes to their travel plans. The project will notify the public about the roadblocks and traffic diversion through public notices, ward level meetings and city level meeting with the elected representatives.

7. The PIU will also conduct an awareness campaign to educate the public about the following issues:

- (i) traffic control devices in place at the work zones (signs, traffic cones, barriers, etc.);
- (ii) defensive driving behaviour along the work zones; and
- (iii) reduced speeds enforced at the work zones and traffic diversions.

8. It may be necessary to conduct the awareness programs/campaigns on road safety during construction.

9. The campaign will cater to all types of target groups i.e. children, adults, and drivers. Therefore, these campaigns will be conducted in schools and community centres. In addition, the project will publish a brochure for public information. These brochures will be widely circulated around the area and will also be available at the PIU, and the contractor's site office. The text of the brochure should be concise to be effective, with a lot of graphics. It will serve the following purpose:

- (i) explain why the brochure was prepared, along with a brief description of the project;
- (ii) advise the public to expect the unexpected;
- (iii) educate the public about the various traffic control devices and safety measures adopted at the work zones;
- (iv) educate the public about the safe road user behaviour to emulate at the work zones;
- (v) tell the public how to stay informed or where to inquire about road safety issues at the work zones (name, telephone, mobile number of the contact person; and
- (vi) indicate the office hours of relevant offices.

E. Install traffic control devices at the work zones and traffic diversion routes

10. The purpose of installing traffic control devices at the work zones is to delineate these areas to warn, inform, and direct the road users about a hazard ahead, and to protect them as well as the workers. As proper delineation is a key to achieve the above objective, it is important to install good traffic signs at the work zones. The following traffic control devices are used in work zones:

- Signs
- Pavement Markings
- Channelizing Devices
- Arrow Panels
- Warning Lights

11. Procedures for installing traffic control devices at any work zone vary, depending on road configuration, location of the work, construction activity, duration, traffic speed and volume, and pedestrian traffic. Work will take place along major roads, and the minor internal roads. As such, the traffic volume and road geometry vary. The main roads carry considerable traffic; internal roads in the new city areas are wide but in old city roads very narrow and carry considerable traffic. However, regardless of where the construction takes place, all the work zones should be cordoned off, and traffic shifted away at least with traffic cones, barricades, and temporary signs (temporary "STOP" and "GO").

12. **Figure A2 to Figure A12** illustrates a typical set-up for installing traffic control devices at the work zone of the area, depending on the location of work on the road way, and road geometrics:

- Work on shoulder or parking lane
- Shoulder or parking lane closed on divided road
- Work in Travel lane
- Lane closure on road with low volume
- Lane closure on a two-line road with low volume (with yield sign)
- Lane closure on a two-line road with low volume (one flagger operation)
- Lane closure on a two lane road (two flagger operation)
- Lane closure on a four lane undivided Road
- Lane closure on divided roadway
- Half road closure on multi-lane roadway
- Street closure with detour

13. The work zone should take into consideration the space required for a buffer zone between the workers and the traffic (lateral and longitudinal) and the transition space required for delineation, as applicable. For the works, a 30 cm clearance between the traffic and the temporary STOP and GO signs should be provided. In addition, at least 60 cm is necessary to install the temporary traffic signs and cones.

14. Traffic police should regulate traffic away from the work zone and enforce the traffic diversion result from full street closure in certain areas during construction. Flagggers/ personnel should be equipped with reflective jackets at all times and have traffic control batons (preferably the LED type) for regulating the traffic during night time.

16. In addition to the delineation devices, all the construction workers should wear fluorescent safety vests and helmets in order to be visible to the motorists at all times. There should be provision for lighting beacons and illumination for night constructions.



Figure A2 & A3: Work on shoulder or parking lane & Shoulder or parking lane closed on divided road



Figure A4 & A5: Work in Travel lane & Lane closure on road with low volume



Figure A6 & A7: Lane closure on a two-line road with low volume (with yield sign) & Lane closure on a two-line road with low volume (one flagger operation)



Figure A8 & A9: Lane Closure on a Two-Lane Road (Two Flagger Operation) & Lane Closure on a Four-Lane Undivided Road



Figure A10 & A11: Lane Closure On Divided Roadway & Half Road Closure On Multi-Lane Roadway



Figure A12: Street closure with detour

Appendix 11: Public Consultations Conducted During Project Preparation

A. Results of Socio-Economic Surveys Conducted in June to August 2013

1. Transect walks identified a total of 49 APs whose business will be temporarily affected during pipe laying, as they carry their activities with in RoW. These businesses can be broadly classified into four main categories as: (i) vegetable/fruit selling; (ii) cloth selling; (iii) small business other than food items such as cobbler, barbers etc.; and (iv) small businesses related to food items such as juice, tea and fast food selling. Close to 50 percent of these however are engaged in vegetable/fruit selling. Some of the



surveyed APs (especially those engaged in vegetable/fruit selling) indicated that they sometimes take rounds in confined areas to sell their products home-to-home though their place of standing is stationary/fixed otherwise. Almost all of them (95 percent) have movable structures while some APs sit on roads for selling their goods. An average cost of their business unit/structure was estimated at Rs. 13,592 with minimum at Rs. 3,000 and maximum at Rs. 45,000.

2. Street vending is quite a common practice in Sri Ganganagar and around 73 percent of the APs indicated that they are doing their business at present location for more than 10 years. An additional 14 percent indicated that they have this fixed location for more than five years while the remaining 12 percent said they have moved in respective places in last 1-5 years.

3. In terms of the socio-economic background around two percent of the APs earn income below poverty line (Rs. less than 2,500 per month). A little more than 50 percent earn monthly income between Rs. 5,000-10,000 and belong to lower middle class group. Average monthly income works out at Rs. 6,888 with minimum at Rs. 2,000 and maximum at Rs. 30,000. Considering work week of six days (26 days per month), average daily income is estimated at Rs. 265 for APs. This is certainly higher than daily minimum wages prescribed for the region for skilled labour at Rs.166.



4. A majority of the APs (86%) belong to general (upper) caste category while the remaining are scheduled caste (SCs-2%), and other backward classes (OBC-12%). There were

no scheduled tribe (ST) APs and women headed households (WHH)¹ found during the survey. Total vulnerable² APs comprise four percent of the total surveyed APs. Average family size for surveyed APs was 5.1. All the surveyed APs were residents of Sri Ganganagar living in the city for more than 5 years.

5. Transect walk data/analysis will be updated road wise where pipelines will be laid before mobilization of contractor and



revised RP will be submitted to the ADB for approval.³ A 100 percent census and socioeconomic surveys will be undertaken to register and document the status of affected people (APs) within subproject impact area.⁴

B. Proceedings of City Level Stakeholder Consultation Meeting At Sri Ganganagar on April, 25, 2014

1. This stakeholder consultation meeting was organised on April 25, 2014 at Sri Ganganagar District collector's meeting hall. The meeting was organised by the Sri Ganganagar Nagar Parishad (SGNP) with the support of RUIDP PMU and ADB PPTA Team. District Collector Ganganagar chaired the meeting. The SGNP Chairman (elected head of PNP), and Commission (administration head of SGNP) participated in the meeting. In all 26 persons, representing various agencies, attended the meeting (List of persons attended the meeting is enclosed herewith).

2. The objective of the meeting was to appraise the stakeholders about the proposed Rajasthan urban Infrastructure Development Project III (RUIDP III). The subprojects proposed for Ganganagar in water supply and sewerage sector, and the likely environmental and social issues, and the proposed mitigation measures were discussed during the meeting.

3. A detailed presentation on overall RUIDP III, and subprojects and components proposed in Ganganagar was made to the stakeholders. Executive summary of Initial Environmental Examination (IEE) conducted for the Ganganagar subproject, Environmental

¹ Household is considered women headed when she is the single bread earner of the family or earn most of the income for the family.

² Vulnerable households may include female-headed household, physically handicapped-headed household, scheduled tribe-headed households, Below Poverty Line households, and households with marginal land holdings, that is the only source of livelihood, and majority of that land is being acquired under the project.

³ It is suggested under this RUSDP that separate RPs needs to be prepared for each subproject (separate for water supply and sewerage, and not city wise) and list of temporary APs should be separated from any APs which envisage permanent impacts. RPs should also include separate and clear sections on their socio-economic profile, impacts and entitlements.

⁴ During RP revision, census/socio-economic surveys for temporary impacts should include specific questions on place of business, its seasonal variation and AP's migrant nature. A separate list of such APs should be made to suggest that they may not be present at the same location during construction time/compensation. These APs however will be still entitled for compensation (if affected due to project). However, such list will tentatively indicate PMU/PIU/ADB the extent of missing APs during implementation. It is also suggested under this RUSDP that missing APs under temporary impacts not traceable for more than 18 months after the start of compensation disbursement, or do not claim their entitlement within project construction period, will bear no impacts of the project and hence will not be considered for compensation.

Management Plan, proposed Grievance Redress Mechanism (GRM), draft Entitlement Matrix of the Resettlement Framework was displayed at the meeting, and were made available to the interested persons.

- 4. The comments, suggestions of the stakeholders are presented below:
 - All the stakeholders were supportive of the project and indicated their willingness to participate in the project to make it successful.
 - Stakeholders were of the view that these subprojects provide benefits to all the people by improving water supply and sewerage.
 - Stakeholder suggested that the treated sewage from all the STPs be transported to a single location, and an artificial water body with parks and play grounds should be developed.
 - Stakeholders concerned about poor natural drainage and inadequate drain capacities.



Photographs:















List of Participants:

RAJASTHAN URBAN INFRASTRUCTURE DEVELOPMENT PROJECT (RUIDP), JAIPUR

Public Consultation Workshop by PPTA for RUIDP Phase-III

Town: Sri Ganganagar Venue: Meeting Hall at District Collector Office Time & Date: 11 Am on 25.04.2014

S.No	Name of the Officer/Participant	Designation	Mobile No.	Signature
1	Sh. R.S. Jakhar	District Collector		2
2	Sh. Jaudich Jandu	Chairman, Municipal Council		dan
	Shi sugarsi sunda	COMMISSIONAL M.C	99.507278.99	9
	Partice Preside	Cometan 10 T 6	111124427	200
- 7	Dir Sumi-	Acal	A1110 81371	- Sm
-5	Sanderp Nappel	AC Municipal	9414 71.100	dra
	Mangal Selia	ACN M.C. SGNR	0 CA10 75686	al date
	Ved marax " gana son	J. CAL M.C. SYNC	85610 12407	2-62
8.	Major suga Bhau	JEN M.C. SGAL	99007144/1	magin
- 14	GOUGE SHAPKED	JENI M.C. SONA	115031446	de >
10.	RAKESMSIDANN	HEIV-DIT-SGAIL	9919251700	MA
11.	Nitesh Kuman Jonigir	J.En. UIT-SGNK	9615203040	ann
12 -	Mukeon - Jarohit	The UIT SUMO	747320 20 71	mil
13.	news wing an ingal	DEM ORI ROMIE	9132053344	6 ts -
14	Syrender Pronies	II DUN D COLD	9460646529	Ludd.
15	Sikandar singh Gell	AENPHEDLYNK	34142.51169	and
16	Ashok KR Grupta	JERUTBUED DON	94132-29054	am
17.	BOLDON SUARMA	ExEx (mm).	94140-93831	ann
18	Vined Kugar Jam	XEN (R) SCATE	94144-82206	1000 T
19	V.K. singhaf	X BH MED FTH	9/493 0111	TUOP .
20.	Dalip Kumar Gaun	EE, MED, SOU	29133 1116	61
21.	K.S. Sharng	SEI PHED, SOUR	7665005333	The Car
22.	Barrendera	Usering Limine, com	995024811	ALA
23.	Alarmeet K, stain	EE, KUIDY, Jaime	74144 3 901	-Hor Sud
24.	Nagarafu. A.	T.L. PUIDE IN	9448909130	Sitte
27	Sureh Chandra Khandun	CRE-PITA	9711 8515>	an //
26	Krushna chathanya T	Sr. Super Egen, ATP	9828917712	em_

Appendix 12: Sample Monthly Reporting Format for Assistant Safeguards Officer/Assistant Construction Manager

1. Introduction

- Overall project description and objectives
- Description of sub-projects
- Environmental category of the sub-projects
- Details of site personnel and/or consultants responsible for environmental monitoring
- Overall project and sub-project progress and status

	Sub Project	Status of Sub-Project				List of	Brograss
No.	Name	Design	Pre- Construction	Construction	Operational Phase	Works	of Works

2. Compliance status with National/ State/ Local statutory environmental requirements

No.	Sub-Project Name	Statutory Environmental Requirements	Status of Compliance	Action Required

3. Compliance status with environmental loan covenants

No. (List schedule and paragraph number of Loan Agreement)	Covenant	Status of Compliance	Action Required

4. Compliance status with the environmental management and monitoring plan

- Provide the monitoring results as per the parameters outlined in the EMP. Append supporting documents where applicable, including Environmental Site Inspection Reports.
- There should be reporting on the following items which can be incorporated in the checklist of routine Environmental Site Inspection Report followed with a summary in the semi-annual report send to ADB. Visual assessment and review of relevant site documentation during routine site inspection needs to note and record the following:
 - What are the dust suppression techniques followed for site and if any dust was noted to escape the site boundaries;
 - If muddy water was escaping site boundaries or muddy tracks were seen on adjacent roads;
 - adequacy of type of erosion and sediment control measures installed on site, condition of erosion and sediment control measures including if these were intact following heavy rain;
- Are their designated areas for concrete works, and refuelling;
- Are their spill kits on site and if there are site procedure for handling emergencies;
- o Is there any chemical stored on site and what is the storage condition?
- Is there any dewatering activities if yes, where is the water being discharged;
- How are the stockpiles being managed;
- How is solid and liquid waste being handled on site;
- o Review of the complaint management system;
- Checking if there are any activities being under taken out of working hours and how that is being managed.

Summary Monitoring Table

Impacts (List	Mitigation	Parameters Monitored (As a	Method of	Location of	Date of	Name of Person
from IEE)	Measures (List	minimum those identified in	Monitoring	Monitoring	Monitoring	Who Conducted
	from IEE)	the IEE should be monitored)			Conducted	the Monitoring
Design Phase						
Pre-Construction F	Phase		•	•		•
Construction Phas	e		•	•		•
Operational Phase						

Overall Compliance with CEMP/ EMP

No.	Sub-Project Name	EMP/ CEMP Part of Contract Documents (Y/N)	CEMP/ EMP Being Implemented (Y/N)	Status of Implementation (Excellent/ Satisfactory/ Partially Satisfactory/ Below Satisfactory)	Action Proposed and Additional Measures Required

5. Approach and methodology for environmental monitoring of the project

• Brief description on the approach and methodology used for environmental monitoring of each sub-project

6. Monitoring of environmental impacts on project surroundings (ambient air, water quality and noise levels)

- Brief discussion on the basis for monitoring
- Indicate type and location of environmental parameters to be monitored
- Indicate the method of monitoring and equipment to be used
- Provide monitoring results and an analysis of results in relation to baseline data and statutory requirements

As a minimum the results should be presented as per the tables below.

Air Quality Results

Site No.	Date of Testing	Site Location	Parameters (Government Standards)		
			PM10 μg/m ³	SO ₂ µg/m ³	NO ₂ µg/m³

Site No.	Date of Testing	Site Location	Parameters (Monitoring Results)		
			ΡΜ10 μg/m ³	SO ₂ µg/m ³	NO₂ µg/m³

Water Quality Results

Sito	Data of		Parameters (Government Standards)					5)
No	Sampling	Site Location	pН	Conductivity	BOD	TSS	TN	TP
NO.	Sampling			μS/cm	mg/L	mg/L	mg/L	mg/L

Sito	Data of		Parameters (Monitoring Results)					
No	Dale Of Sampling	Site Location	рН	Conductivity	BOD	TSS	TN	TP
NO.	Sampling			μS/cm	mg/L	mg/L	mg/L	mg/L

Noise Quality Results

Site No. Data of Testing		Site Logation	LA _{eq} (dBA) (Government Standard)		
Sile NO.	Date of Testing	Sile Location	Day Time	Night Time	

Sita No	Data of Tasting	Site Location	LA _{eq} (dBA) (Monitoring Results)		
Sile No.	Date of Testing		Day Time	Night Time	

7. Summary of key issues and remedial actions

• Summary of follow up time-bound actions to be taken within a set timeframe.

8. Appendixes

- Photos
- Summary of consultations
- Copies of environmental clearances and permits
- Sample of environmental site inspection report
- Other

APPENDIX 13: SAMPLE ENVIRONMENTAL SITE INSPECTION REPORT

Project Name Contract Number

NAME:	DATE:	
TITLE:	DMA:	
LOCATION:	GROUP:	

WEATHER:

Project	Survey	
Activity	Design	
Stage	Implementation	
	Pre-Commissioning	
	Guarantee Period	

Monitoring Items	Compliance
Compliance marked as Yes / No / Not applicable (NA) / Partially Implemented (PI)	
EHS supervisor appointed by contractor and available on site	
Construction site management plan (spoils, safety, schedule, equipment etc.,) prepared	
Traffic management plan prepared	
Dust is under control	
Excavated soil properly placed within minimum space	
Construction area is confined; no traffic/pedestrian entry observed	
Surplus soil/debris/waste is disposed without delay	
Construction material (sand/gravel/aggregate) brought to site as & when required only	
Tarpaulins used to cover sand & other loose material when transported by vehicles	
After unloading, wheels & undercarriage of vehicles cleaned prior to leaving the site	
No AC pipes disturbed/removed during excavation	
No chance finds encountered during excavation	
Work is planned in consultation with traffic police	
Work is not being conducted during heavy traffic	
Work at a stretch is completed within a day (excavation, pipe laying & backfilling)	
Pipe trenches are not kept open unduly	
Road is not completely closed; work is conducted on edge; at least one line is kept open	
Road is closed; alternative route provided & public informed, information board provided	
Pedestrian access to houses is not blocked due to pipe laying	
Spaces left in between trenches for access	
Wooden planks/metal sheets provided across trench for pedestrian	
No public/unauthorized entry observed in work site	
Children safety measures (barricades, security) in place at works in residential areas	
Prior public information provided about the work, schedule and disturbances	
Caution/warning board provided on site	
Guards with red flag provided during work at busy roads	
Workers using appropriate PPE (boots, gloves, helmets, ear muffs etc)	
Workers conducting or near heavy noise work is provided with ear muffs	
Contractor is following standard & safe construction practices	
Deep excavation is conducted with land slip/protection measures	
First aid facilities are available on site and workers informed	

Monitoring Items	Compliance
Drinking water provided at the site	
Toilet facility provided at the site	
Separate toilet facility is provided for women workers	
Workers camps are maintained cleanly	
Adequate toilet & bath facilities provided	
Contractor employed local workers as far as possible	
Workers camp set up with the permission of PIU	
Adequate housing provided	
Sufficient water provided for drinking/washing/bath	
No noisy work is conducted in the nights	
Local people informed of noisy work	
No blasting activity conducted	
Pneumatic drills or other equipment creating vibration is not used near old/risky buildings	

Signature

Sign off

Name Position Name Position

Appendix 14: Sample Grievance Registration Form

(To be available in Hindi and English)

The ______Project welcomes complaints, suggestions, queries, and comments regarding project implementation. We encourage persons with grievance to provide their name and contact information to enable us to get in touch with you for clarification and feedback. Should you choose to include your personal details but want that information to remain confidential, please inform us by writing/typing *(CONFIDENTIAL)* above your name. Thank you.

Date		Place of registration	Project Town				
			Project:				
Contact information/personal details							
Name			Gender	* Male * Female	Age		
Home address							
Place							
Phone no.							
E-mail							
Complaint/suggestion/comment/question Please provide the details (who, what, where, and how) of your grievance below:							
If included as attachment/note/letter, please tick here:							
How do you want us to reach you for feedback or update on your comment/grievance?							

FOR OFFICIAL USE ONLY

Registered by: (Name of official registering grie	rance)					
Mode of communication:						
Note/letter						
E-mail						
Verbal/telephonic						
Reviewed by: (Names/positions of officials reviewing grievance)						
Action taken:						
Whether action taken disclosed:	Yes					
	No					
Means of disclosure:						