SFG1139 v5

JANUARY 2012

ENVIRONMENTAL IMPACT ASSESSMENT PROJECT REPORT FOR THE PROPOSED LABORATORY AT MALINDI DISTRICT HOSPITAL IN MALINDI



MISCELLANEOUS

NAME OF PROPONENT:	Ministry of Public Health
ADDRESS:	P. O. Box 19982-00202, Nairobi
NAME OF CONTACT PERSON:	Dr. Willis Akwale, MBS
POSITION OF CONTACT PERSON:	Project Manager
TELEPHONE NO:	+254 20 2716934/5
LOCATION:	Malindi District Hospital, Malindi town

SIGNED: _

D: _____ DATE: _____ (PROJECT PROPONENT)

Green Globe Foundation, a registered Environmental Impact Assessment Firm comprising of Lead and Associate Lead Experts compiled this Project Report for the proposed laboratory for Malindi District Hospital. The following are the names of the staff members involved in the actual Environmental Impact Assessment.

✤ Kyalo Patrick Judith Kanini

Reg no. 1275 Community Mobilizer

Shandrack Ngewa

Contact: 0721997876

The Environmental Impact Assessment was done in January 2012

SIGNED: _____ DATE: _____ For Green Globe Foundation

ABSTRACT

This report addresses both environmental and socioeconomic issues related to the development, operation or decommissioning of the proposed laboratory. The proposed Malindi hospital laboratory is under the Ministry of Public Health and Sanitation which is financed by World Bank. It is located at Malindi district hospital. The proposed facility has been designed on the basis of the client brief and the additional information collected during the site visits. The site has an efficient road network that connects to main roads. There is an on-going project to provide a sewer line to the town of Malindi, and hence expected to benefit the hospital in sewer and waster water management. However, there will be a septic tank for the new laboratory unless the sewer system is commissioned before project completion. Electricity and water is also available, but the facility will also benefit from water desalination equipment. The new laboratory therefore will have 2 levels, ground and first floor plan.

The facility is to be constructed to a standard laboratory as provided in the designs, hence some construction work will be undertaken. Throughout the world, construction activities impact the environment in one way or another, be it the social, economical, biological or physical environments. Such impacts should be checked to avoid or reduce any negative effects to the environment and public health.

As well, with improved infrastructure (health facilities/offices) provision, there is bound to be a rise in business/economic opportunities leading to increased population within the development site and its surrounding. Increase of population; be it temporary (during construction as a result of labor import) or permanent is likely to stretch services and other facilities in and around the project area. Measures should be put in place to ameliorate against any negative impacts and maximize on any positive ones.

Referring to the environmental law of the country and in accordance with Section 58 of the Environmental Management and Coordination Act (1999) and Legal Notice No. 101 of 2003, a project of this magnitude is supposed to be subjected to an Environmental Impact Assessment (EIA). Procedural guidelines on the EIA are spelt out in Legal Notice No. 101. The procedural steps involved in this assessment included Identification of key stakeholders; Scoping and development of the Terms of References using a variety of methods and tools; Baseline Studies; Consultation and public participation; Impacts identification and analysis; Development of mitigation measures; Analysis of project alternatives and Development of Social and Environmental Management Plan.

The objectives of the EIA were to Consider all possible positive and adverse impacts to the environment, critical habitats, wildlife, aquatic ecosystems and the overall fauna and flora; Determine socio-economic impacts of the project; Assess environmental hazards and risks associated with the project; Design and prepare mitigation measures and action plans to address all possible significant negative environmental impacts.

In Kenya, the Environmental Impact Assessment (EIA) has to be conducted according to the requirements of the Environmental Management and Co-ordination Act (1999). An EIA document submitted to the enforcement authority, National Environmental Management Authority (NEMA), enables the issuing of an Environmental Impact Assessment License.

When properly designed and implemented, EIA is a powerful tool for ensuring that environmental issues are given due consideration during project design, allowing the benefits of the project to be maximized, while reducing the environmental and social costs of development. Thus, all due care should be taken into account to ensure that the environment of the project area is not disturbed in a way that could affect the living standards and styles of the surrounding people in a negative manner. The terms of reference for the EIA were to establish baseline conditions, impact assessment, development of mitigation measures and an Environmental Management Plan (EMP) with respect to habitat and vegetation, socio-economic and community participation, demography and settlement, historical, archeological monuments and cultural heritage, physical environment, wildlife and fisheries, forest and forest products, energy, community environmental/public health and safety, analysis of legislative and institutional framework for environmental management in Kenya, and analysis of project and technology alternatives. It was also required to establish institutional needs to implement the recommended action plans. A number of institutions, professional individuals/groups, local people and their leaders and academicians were consulted for their inputs to the assessment. Many individuals were consulted through one-to-one meetings, to collect views from as many stakeholders as possible.

The preliminary findings during public consultations with stakeholders indicated that the public support the project. Following is an outline of issues that were raised during the consultation and public participation process:

- Safety of the public during the construction period
- Occupational health and safety during the operation phase
- Concern of increased dust around the project site especially during the construction period
- Increased traffic jam around the area, especially during the construction period
- What plans are in place to address, Biomedical/clinical, solid and liquid waste management in and around the project area

A number of project alternatives were considered in the assessment. These included the "no project" alternative. Although this would lead to preservation of the environmental conditions, this alternative was the least favorable because it would mean people will not benefit from the much needed casual jobs as well as the improvement of health care services in and around Malindi.

Decommissioning phase impacts included loss of direct and indirect employment, large amounts of demolition waste, noise pollution, dust and exhaust emissions, likely occupational health and safety hazards.

The EMP that was developed for this EIA report outlines the actions that are required to address the identified negative impacts, responsibility, implementation stage, costs and relevant regulations/ standards to guide monitoring and auditing of the effectiveness of the proposed mitigation measures.

The proposed project offers many significant positive impacts at the local, regional, national and even international levels. The anticipated positive impacts include: direct and indirect employment generation and the provision of the much needed high quality health care services.

Being a project of a storey building, it offers some potential avenues for a better environment such as the following:

Environment - The potential reduction in environmental impacts through a reduced 'ecological footprint' and reduction in transportation energy make the storeyed health centre issues critically important in today's context with regard to urban environment. In the urban context, storey buildings provide great potential for renewable energy generation. For example, wind energy, as wind density increases with altitude, and even tapping of solar energy as few obstructions from either trees or other buildings exist etc.

Through the study of ecologically sustainable storey-building designs, construction and operation issues, and presenting representative solutions, the project aims to ensure that energy and water savings and harvesting strategies are incorporated in the proposed design. This will

ensure that we continue to work towards commitments to CO_2 emission reduction, whilst continuing to maintain the highest standards for the project's in and out patients.

Social - The development and history of storied buildings in Kenya has not been a success story due to accidental collapsing. But high-density city housing/ buildings is a priority for urban centres not only in Kenya, but all over the world. Given the increasing demand for city buildings for different purposes, storey-buildings have an important role to play in the regeneration and sustainability of our cities.

This project will highlight the key requirements for 'socially sustainable' health care facility, such as privacy, accessibility, etc by understanding the potential social impact of high-rise working. The project through its dissemination strategy will try and remove the stigma being attached to storied-buildings due to their poor safety in case of emergencies and embrace ways to design socially acceptable storey building.

Economic -The project will present approximate costs of sustainable strategies, such that the client and developer can appreciate the economic benefits and understand that sustainable storey buildings are a profitable and affordable proposition. Radical technological interventions could be employed to ensure the development of truly sustainable buildings. Particular building technologies and features that are currently used in storey house construction to enhance their sustainability include Natural ventilation; Natural day-lighting; Balconies, terraces and sky-courts; Sustainable and renewable energy systems including photovoltaic panels and wind turbines; Maximised floor plan space; Sky gardens and vertical landscaping; Intelligent building management systems; Variety of facilities; Low embodied energy and construction processes

On the other hand, potential significant negative project impacts may affect environmentally sensitive areas such as wetlands (rivers), groundwater, air quality and humans and their cultural properties. The main issues are geographically limited, well defined, and well understood in Kenya. Thus, the proponent's major task in respect of the EMP is to properly manage the negative impacts while enhancing the positive ones to ensure a project that is economically, socially and environmentally sustainable. In so doing, the proposed project could be approved for implementation provided that the proponent shows capacity to implement the EMP.

Table of Contents

MISC	ELLANEOUS	. ii
ABST		111
1. II	NTRODUCTION	. 1
1.1	The Satellite Laboratories	. 1
1.2	Laboratory Design	. 1
1.2.1	Ground floor	. 1
1.2.2	First floor	. 1
1.2.3	Other Laboratory Design Provisions	. 2
1.3	Objectives of the EIA	. 3
1.4	Environment Impact Assessment Methodologies	. 3
1.5	Need for the Project	.4
2. E	NVIRONMENTAL AND BASELINE INFOERMATION	. 5
2.1	Identification of the site	. 5
2.2	Malindi Town	. 5
2.2.1	Population	. 5
2.2.2	Landscape and Climate	. 6
2.2.3	Climate	. 6
2.2.4	Natural Ecosystem around the Town	. 6
2.3	Malindi District	. 7
2.3.1	Vegetation in Malindi	. 7
3. E	NVIRONMENTAL LEGISLATION IN KENYA	. 8
3.1	Constitutional Provisions	. 8
3.2	Land Tenure and Land Use Legislation	. 8
3.3	Legislation Relevant to Water Resources	. 8
3.4	Environmental Health	.9
3.4.1	Public Health	.9
3.4.2	The Working Environment	10
343	Radiation Control	10
344	Management of Hazardous Waste	10
3.5	Legislation on specifically protected areas	11
3.6	The Environmental Management and Co-ordination Act (EMCA)	11
361	Protection and Conservation of the Environment	11
362	Fnvironmental Impact Assessment	12
363	Environmental Audit and Monitoring	12
364	Waste Management Regulations 2006	12
9 St	tandarde for Liquid Waste	13
a. 5 37	The Occupational Safety and Health Act. 2007	13
28	The National Health Care Waste Management Plan 2008, 2012	11
39	Kenva National Cuidelines on Safe Disposal of Pharmaceutical Waste 2001	14
391	National Policy on Injection Safety and Medical Waste Management	14
3 10	Padiation Protection Act. Cap 243	14
3.10 4 C	CONSULTATIONS AND DUDUC DADICUDATION (CEDD)	10
4. C	$D \cap \mathbb{R}^{T}$	10
5, F.	Introduction	17
5.1	Introduction	17
0.Z	No-action alternative	17
5.5 5.4	Reflection option	11 17
0.4 5 5	Wasta Watan Traatmant Systems	11 10
0.0 5 5 1	Pia digastara	1ð 10
0.0.1 E E 0	DIU-UIZESIEIS	1ð 10
5.5.Z	otput talik	1ð 10
5.5.3	BIO-POX TECHNOLOgy	1ð 10
5.5.4	CONNECTION TO A SEWER LINE.	19
6. A	INTICIPATED ENVIKONMENTAL IMPACTS AND MITIGATION MEASURES	20
6.1	Introduction	20

6.2 Construction phase- Potential Environmental and Social Impacts	20
6.3 Operational Phase- Potential Environmental and Social Impacts	21
6.3.1 The Scope of the EIA during the Operating Phase	21
6.3.2 Environmental Conservation Activities	21
6.3.3 Water Utilization and Conservation	21
6.3.4 Waste Disposal and Management	21
a. Liquid Waste Management (Human Excrement)	21
b. Liquid Bio-Medical Waste	21
i. Challenge of Liquid Bio-Medical Waste	22
ii. Liquid bio-medical waste standards	22
6.3.5 Solid Waste Generation and Management	23
A. Potential Health impacts of health-care waste	23
a) Types of hazards	23
b) Persons at risk	23
c) Hazards from infectious waste and sharps	24
d) Hazards from chemical and pharmaceutical waste	24
e) Hazards from genotoxic waste	25
f) Public sensitivity	25
B. Potential Public health impact of health-care waste	25
6.3.6 Emergency response	26
6.3.7 Dealing with spillages	26
6.3.8 Reporting accidents and incidents	
6.3.9 Other Health and Safety issues to be considered in the Health Care Facility	
6.4 De-Commissioning Stage	27
6.4.1 Positive Decommissioning Impacts	28
6.5 Negative Decommissioning Impacts	28
7. ENVIRONMENTAL MANAGEMENT/MONITORING PLAN	29
7.1 Introduction	29
7.2 Environmental Monitoring and Auditing Program	29
7.3 Environmental Management Plans (EMP)	31
7.4 Operational Phase EMP	38
7.5 Decontinuitsioning rhase	41
8. AUAILLIARY INFORMATION	42
8.1 DUUZEL	42
8.2 Monitoring Guidelines	42
8.4 Conclusion and Recommendations	42 19
0.4 CONCLUSION AND RECOMMENDATIONS	44 12
	43
IV. KLI EKLINCEO	44

1. INTRODUCTION

The proposed East Africa Public Health Laboratory Networking (EAPHLN) Project is being under taken in selected hospital facilities in Kenya, Uganda, Rwanda and Tanzania. The project is intended on establishing a network of efficient, high quality, accessible public health Laboratories for the diagnosis and surveillance of TB and other communicable disease. The beneficiary countries will also be able to share information about those diseases and mount on effective regional response. The objectives of the project are:

- Enhance access to diagnostic services for vulnerable groups.
- Improve capacity to provide specialized diagnostic services
- Conduct drug resistance monitoring.
- Strengthen laboratory based disease surveillance to provide early warning of public health events.
- Support training and capacity building for laboratory personnel.
- Increase pool of experts in the region.
- Improve the effectiveness of public health laboratories.
- Create a platform to share information regionally on operational research, impact of TB diagnostic technologies and enhance TB surveillance.

1.1 The Satellite Laboratories

The client has selected six health care facilities to benefit from this scheme. These include:

- National Public Health Laboratory services (NPHLS) Building, Nairobi.
- Machakos District Hospital
- Kitale District Hospital
- Busia District Hospital
- Malindi District Hospital
- Wajir District Hospital

1.2 Laboratory Design

The proposed laboratory is designed to address the movement related to patients, personnel and specimens. It clearly indicates how specimens move from the specimen receiving area to the laboratory for test and dispatch of the results to the patients.

The proposed laboratory for the Malindi District Hospital has been designed on the basis of the client brief and the additional information collected during the site visits. The new laboratory will entail a two level building, ground and first floor plan. It will include the following provisions:

1.2.1 Ground floor

The ground floor will accommodate a Waiting area, Specimen reception area, Reception area, Reports release desk, Cashier office, Records room, Patients WCS, Phlebotomy room, Donor room, washing area, Counseling room, Blood donor room, Rest room, Blood bank, Pathologists office, Server room, Staff Lounge, Office for in-charge, Office for County laboratory Technician, Utility Room, Cold Room, Training Room; video conferencing, Suppliers store and Staff WCs

1.2.2 First floor

The first floor will accommodate Blood transfusion laboratory, Serology laboratory, Chemistry laboratory, Hematology laboratory, Parasitology laboratory, Histology laboratory, Microscopy,

Freezer room, Media prep room, Specimen Museum, Quality control laboratory, Molecular laboratory, Virology laboratory, Microbiology laboratory, TB laboratory, Decontamination room, Glassware washing, Store and Staff WCS.

1.2.3 Other Laboratory Design Provisions

i. Laboratory Worktops.

The worktops/workbenches will be constructed in 25mm thick solid panels which are acid, solvent, stain and scratch resistant made as TRESPA Toplab Plus or equal and approved with a marine edge top and applied backsplash to contain spillage.

ii. Lab Shelves

The laboratory will have shelving for reagent storage which will have lipped edges which makes sure the reagents do not fall off.

iii. Emergency shower and Eye wash.

The design will provide an emergency body shower, wall mounted with self-draining head. An emergency wash will also be provided and a stainless steel bowl to mechanical engineers specifications. The eyewash will be a fixed unit that is centrally located to ensure it is accessible by the staff within the first ten seconds.

iv. Floor finishes.

The laboratory floors will be finished in epoxy floor finish which can be laid in continuous form and is compatible with the base materials such as concrete. The office floor finishes will be nonslip granite tiles while the wet areas will have ceramic tiles to floor and wall up to 2100mm high.

v. Heating, Ventilation and Air-conditioning

In the laboratory, certain rooms will be air-conditioned to ensure safety of staff and comfort; such spaces include TB laboratory, Media prep, Microbiology laboratory, Virology suite and Training room.

vi. Coat Hooks

The design has provided for coat hooks next to the laboratory doors to ensure the laboratory staff can access laboratory coats easily when entering the laboratory.

vii. Hand washing Sinks

The hand washing sinks have been located near doors and the taps will be elbow operated. A shelve will be provided for the soap dispensers as well as a mirror near the wash hand basin.

viii. Water Supply

The domestic water branch piping serving the laboratory will be fitted with backflow preventers and an isolation valve if considered necessary for safety reasons.

ix. Laboratory waste water Handling

In order to ensure the laboratory waste water is sterilized before being released into the sewer system, the following measures may be desirable, especially in the TB Lab;

- □ Drainage traps to be provided up to the required deep seal depth.
- □ Autoclave condensate drains to have closed connections.

x. Gas Supply

The gas supply to the laboratory will be piped and the LPG cylinders located outside the labs for safety purposes.

xi. Emergency Lighting

The laboratory will be fitted with emergency lighting and signage. All the doors shall be fitted with LED type exit signs.

xii. Communication system

The laboratory will have communication system between the various sections and also LIMS for electronic transfer of information and data from the laboratory area to other sections or other satellite labs.

1.3 Objectives of the EIA

This is the report of an Environmental Impact Assessment for the proposed project in accordance with Section 58 of the Environmental Management and Coordination Act (1999) and Legal Notice No. 101 of 2003. The objectives of the study were:

- □ To assess the potential environmental and social impacts of the proposed project, whether positive or negative, and propose mitigation measures which will effectively address these impacts;
- □ To inform the proponent and contractor of the potential impact of different alternatives, and relevant mitigation measures and strategies;
- □ To inform stakeholders of the proposed project and to seek their views regarding its potential environmental and social impacts as well as measures to mitigate the negative impacts.

1.4 Environment Impact Assessment Methodologies

The scope of this assessment was guided by the requirements in the Environmental Management & Coordination Act No. 8 of 1999) and in particular by the Environmental (Impact Assessment and Audit) Regulations, 2003. Environmental Impact Assessment (EIA) is the systematic examination conducted to determine whether or not a program, activity or project will have any adverse effects on the environment. According to the Canadian Environmental Assessment Agency (2004), EIA provides benefits such as "an opportunity for public participation; increased protection of human health; the sustainable use of natural resources; reduced project costs and delays; minimized risks of environmental disasters; and increased government accountability".

The objective of EIA is not to force decision makers to adopt the least environmentally damaging alternative because if this were the case, few developments would take place. However, EIA is just but one of the issues addressed by decision makers as they seek to balance the competing demands of development and environmental protection. The EIA will also assist the government through National Environmental Management Authority (NEMA) to advice the project proponent via licensing on whether the project should be implemented or not, and if it should proceed, then under what conditions. It also provides a monitoring guideline for the project management to act upon.

A wide range of methods were used in the various stages of the EIA. They included methods used by the various specialists for:

- Stakeholder analysis and consultation and public participation
- Scoping of key issues and carrying out the various baseline studies
- Impact analysis and
- The development of an Environmental Management Plan (EMP).

The range of interested and affected parties was identified through consultations with the project proponent, leaders as well as relevant Government Departments with knowledge of the area. The purpose of the scoping exercise was to capture issues that required investigation in the EIA process. The scoping was conducted in a number of consultative one-to-one meetings with individuals surrounding the project area.

Previous reports of the project area were key sources of secondary data to review habitat; demographic and settlement; the physical environment; historical, archeological monuments and cultural heritage. The review of literature included work done by government Lead Agencies and local and international Non-governmental Organizations (NGOs). These assessments have formed the background information for the present EIA.

Aspects of the physical and biological environment studied included physical features of the project area, agro-ecological zones, soils and their properties, potential ecological problems, siltation and accumulation of pollutants in the soil, air and water. Data was obtained from both secondary and primary sources.

1.5 Need for the Project

The project is intended on establishing a network of efficient, high quality, accessible public health Laboratory for the diagnosis and surveillance of TB and other communicable diseases. Other objectives of the project are to:

- □ Enhance access to diagnostic services for vulnerable groups.
- □ Improve capacity to provide specialized diagnostic services
- □ Conduct drug resistance monitoring.
- Strengthen laboratory based disease surveillance to provide early warning of public health events.
- □ Support training and capacity building for laboratory personnel.
- □ Increase pool of experts in the region.
- □ Improve the effectiveness of public health laboratories.
- □ Create a platform to share information regionally on operational research, impact of TB diagnostic technologies and enhance TB surveillance.

2. ENVIRONMENTAL AND BASELINE INFOERMATION

This chapter provides the main features of the baseline biophysical and socio-economic information of the project area. Environmental description, also known as baseline studies, is intended to establish the present state of the environment, taking into account changes resulting from natural events and from other human activities (Glasson, 1994; Canning et al., 2003). If an environmental description is flawed, this will reduce the accuracy of subsequent predictions and mitigation measures (Canning et al., 2003).

2.1 Identification of the site

The proposed laboratory is within the compound of Malindi district hospital which is located within Malindi town in Malindi District. The baseline study below covers within the scope of the project area.



Figure 1: Part of Malindi hospital compound

2.2 Malindi Town

Malindi, located on the East Coast of Kenya, is a popular tourist town with scenic beauty, clean white beaches and a lot of history.

2.2.1 Population

Malindi is the second largest coastal town of Kenya. Malindi Municipality has a population of about 145,000 inhabitants (in the year 1999) with the two most important townships namely Malindi (app. 81,000 inhabitants) and Watamu (app. 17,000 inhabitants). The Municipality's population forms 51.3% of the District's population. It also houses 58.1% of the total district's households.

 Table 1: Malindi Municipality population and household's distribution by locations 1999

Centre	Population	Number	of Households	Area in KM ²	Density
Malindi	80 721		19 402	91.5	882
Ganda	12 738		2 013	36.4	350
Gede	21 128		3 269	67.9	311
Watamu	16 579		3 642	58.8	282
Goshi	13 260		2 000	92.3	144
Total	144 426		30 326	350.5	393.8
DISTRICT	281 552		52 164	7750.60	36.0

Source: District Statistics Office - Malindi 2001

However, it must be noted that the above shown census figures cannot accurately reflect Malindi population alone. This is because of the invasion of the town by foreign residents and tourists who stay up to three or four months a year and then return home. During this time the population of Malindi increases. Apart from the tourists there are many other Kenyans who come for trade and other purposes for the duration of the tourist season i.e. between June to September and January to March.

2.2.2 Landscape and Climate

The landscape in Malindi is predominantly plain. Malindi town could be divided in three broad landscape units. Namely:

- i. the "beach",
- ii. the "coral landscape" and
- iii. the "plateau".

The "beach" is characterized by coral cliff, sandy soil and is an unstable new dune formation.

The "coral landscape" consists of higher situated old reefs and lagoons. It is characterized by depressions with clayish soils and areas susceptible to water logging. The "plateau" is a prominent area of shallow sandy clay soils underlain by coral limestone rock.

Through the old town from the old market until the Lawfords Hotel stretches a depression, which was an old lagoon. It is a geological sea arm whose level is below sea level. Most of the surface run off and storm water of Malindi West and North catchments with an area of approximately 10.56km² drains towards this central lagoon.

2.2.3 Climate

The climate is generally hot and humid throughout the year. The daily temperature is around 22° Celsius minimum and 30.5° Celsius maximum. There are short rains from October to November and long rains from April to July. The vegetation extent from mangroves and swamps to tropical monsoon forest, lowland dry forests in Arabuko-Sokoke Forest to Savannah and bush land in the backwoods.

2.2.4 Natural Ecosystem around the Town

The renowned Malindi Marine National Park is a protected coastal area south of Malindi. Malindi Marine National Park has fine white-sandy beaches, emerald water and colorful fish (All fishing within the Park is forbidden). On the northwest of Malindi, near Marafa Depression exists an eroded wasteland of sandstone cliffs and precipices, locally known as Nyari or Hell's Kitchen, exists also a small Arabian town called Mambrui, and beyond that a small village and harbor called Ngomeni. The entire coastline from Mambrui to Lamu has minimal development, in terms of tourism, although wonderful beaches, coves and seascapes exist inplenty.

The nearby Watamu and the lost town of Gede (abandoned for no known reason in the 16th century), are located south of Malindi. The Arabuko Sokoke National Park hides a world of wonders such as rare endemic birds and mammals, and impressive herds of Elephant.

The Malindi Museum is housed in the former home of an Indian trader, built in 1891. Exhibits include early photographs of Mombasa, wooden grave posts of the Gohu people, information about Vasco Da Gama among other interesting information.

2.3 Malindi District

Malindi District rises from the "coastal plains" through a "foot plateau" to a low "coastal range" up to the "Nyika plateau" to an elevation of 300m above sea level. The "coastal plains" comprise a coastal coral limestone reef, inland of which is sandy back-reef farcies (Margarini sands). It is a narrow belt, varying in width between 3km and 20km. It lies below 30m above sea level. A creek in Mida breaks the belt and gives rise to excellent marine and swamps with mangroves.

The "foot plateau" lies west of the coastal plain with slightly undulating terrain between 60m and 135m altitudes. The plateau characterizes a seaward sloping plain whose surface has been dissected by numerous dry water courses, with underlying Jurassic sediments consisting of shells, sandstones and impervious clays. It supports grassland and stunted vegetation.

The "coastal range" consists of low range sandstone hills 150m to 420m high. The rest of the hinterland forms the "Nyika plateau", which is 130m to 300m above sea level. The highest point within the municipal boundary of Malindi is a point in the Arabuko Sokoke Forest rising to almost 120m. Considering that this is almost 10km away from Malindi old town the gradient is very low. At the northern border of Malindi Municipality flows the Sabaki River, one of the biggest rivers in Kenya. West of Watamu there is Mida Creek, an extended mangrove area. Mida Creek limits the development of Watamu in South and South-West direction.

2.3.1 Vegetation in Malindi

The area of the Malindi can be divided into three major vegetation zones as follows:

a) Lowland dry forest on coral rag:

This vegetation zone covers the coastal strip stretching some 1 to 1,5km from the coastline inward and from the Mida Creek in Watamu all the way to Sabaki River Delta. The natural forest remnant is found near Gede with indicator species like *Combretum Schumanii, Ficus Bussei and Gyrocarpus Americanus.* Most of this area is covered with dense thicket with scattered cultivated plots planted mainly with cassava, maize and cowpeas.

b) Lowland dry forest (Arabuko-Sokoke Forest):

This vegetation zone covers the most land of the municipality and is mainly cultivated with cashew nuts, mangoes, coconuts and food crops and is mainly grassland. It is found in Ganda, Kanuyuni, Mijamboni, Gede and Malindi Town. The major remnant of this type of vegetation is the protected *Arabuko Sokoke* Forest. The main indigenous trees are e.g. *Mtandarusi, Mrihi and Mbambakofi.*

c) Mangroves and swamps:

This vegetation zone covers only a small portion of Malindi Municipal area mainly on the sides of the Mida Creek in Watamu. There are only a few species, which form dense forest. Mainly three different vegetation zones cover the hinterland of Malindi, namely *Manilkara-Acacia Savannah, Tropical monsoon forest and the Acacia Euphorbia bush land.*

3. ENVIRONMENTAL LEGISLATION IN KENYA

Kenyan Acts of Parliament which mention the environment and/or natural resources are numerous. But some are more direct than others, and thus indicate certain critical areas of legal intervention in the management of natural resources and the environment. A prominent feature of Kenya's environmental legislation is its diffuse nature with provisions being contained in about 77 statutes. Most of the statutes are sectoral either by the natural resources such as fisheries, water, forestry and wildlife, or by the functional sectors such as public health, agriculture, factories, mining, shipping or chiefs' authority

For analytical purpose, this report will briefly review relevant Kenyan statutes as discussed in the following categories: (1) Statutes relating to land use; (2) Water resources legislation; (3) Statutes on Environmental health including public health, the working environment, radiation control and disposal of hazardous wastes (4) Fisheries legislation; (5) Statutes on specially protected areas, including forests, wildlife and marine parks; (6) Statutes applicable to the Marine Environment; (7) Legislation relating to tourism.

3.1 Constitutional Provisions

Before we review the statutes relevant to environmental protection in Kenya, it is important to ascertain any provision relating to environmental protection in the national constitution. Although the current Constitution of Kenya does not have direct environmental protection provisions, it has been argued that Section 71 of the Constitution which deals with the right to life encompasses the right to a clean and healthy environment, as this right can only be meaningful if enjoyed within a conducive environment.

3.2 Land Tenure and Land Use Legislation

The following statutes cover land use activities with direct impact on the environment: the Agriculture Act (Cap. 318 of the Laws of Kenya); the Land Control Act (Cap. 302); the Chief's Authority Act (Cap 128); the Mining Act (Cap 306); the Local Government Act (Cap 268) the Trust Lands Act (Cap 288) the Land Planning Act (Cap. 303); Governments Land Act (Cap 280); the Physical Planning Act of 1996, the Registered Land Act (Cap 300) the Irrigation Act (Cap 347); the Crop Production and Livestock Act (Cap 321.

The Agriculture Act is the principle land use statute covering, *inter alia*, soil conservation and agriculture land use in general. Two major parts of the Act deals with the central conservation issues: preservation of soil fertility and prevention or control of soil erosion.

Watercourse and land abutting on these are also protected under the Rules. Cultivation, destruction of soil, cutting down of vegetation, or de-pasturing land within two meters of a watercourse is permissible only if done with a written consent of an authorized officer.

The Mining Act of 1972 (revised in 1987) is primarily for the purpose of stipulating the terms of mining as a commercial operation. However, the Act prohibits any nuisances or disturbance of the rights of the owner or occupier of any adjoining land. It similarly prohibits damage to such land, trees, crops, buildings, stocks or works thereon. The holder of a mining license is required to mine only for the minerals specified in the lease for the specific location. The license holder may cut, take and use trees from the leased land that may be necessary for the mining operation, provided that he obtains consent of the landowner or occupier. However, he remains civilly liable for any fees or royalties which may be payable under the national law.

3.3 Legislation Relevant to Water Resources

Water resources are dealt with under several Sectoral Statutes and it is not practical to bring all those statutes under one heading. The Agricultural Act (Cap 318), for instance has several

provisions on water resources especially in relation to catchment conservation, because agriculture depends on water supply and security. But the Agriculture Act provides that where any provision there is inconsistent with a provision of the Water Act, the provisions of the latter shall prevail.

This part is therefore restricted to an overview of the Water Act No. 8 of 2002. The additional instruments in Kenya's law are the National Water Conservation and Pipeline Corporation Order of 1988 issues as Legal Notice No. 270 in 1988. Other legislation that have a bearing on the management of water resources include; the Forests Act (Cap 385), the Irrigation Act (Cap 347), the Malaria Prevention Act (Cap 246), the Fisheries Act (Cap 378), the Lakes and Rivers Act (Cap 409), the River Basin Development Authorities Act (Cap 443), the Maritime Zone Act (Cap 371) and all the land tenure and land use legislations.

The purpose of the Water Act according to its title is to provide for the management, conservation, use and control of water resources and for the acquisition and regulation of rights to use water, to provide for the regulation and management of water supply and sewerage services. Except for waters that are wholly situated in a private landowner's domain, the Act vests the rights over all surface and ground water in the state. This is only subject to the rights which users may acquire under license from time to time.

3.4 Environmental Health

The health of the environment is a broad issue that should apply to any activity occasioning environmental degradation. However, what we have in Kenya is construed rather narrowly to apply only to environmental problems which affect the human body, but not including diseases. For brief analytical purposes, it is handled in four subsections, namely:

- Public Health,
- The Working Environment,
- Radiation Control,
- The Management of Hazardous Wastes.

3.4.1 Public Health

Under this section the review is confined to the provision of the Public Health Act (Cap 242), the Traffic Act (Cap 403), the Local Government Act (Cap 265), the Penal Code (Cap 63) and the Factories Act (Cap. 514). Within the Public Health Act, the sections on housing and prevention of mosquitoes are directly pertinent.

On sanitation, the Act borrows from the common law doctrine of nuisance which makes it an offence for any landowner or occupier to allow nuisance or any other condition liable to be injurious or dangerous to health to prevail on his land. A medical health officer, once satisfied of the danger, may issue an order requiring the owner or occupier of the land to remove the nuisance.

Fighting malaria is also a critical environmental task dealt under the Act. Part XII makes it an offence to leave on one's land or premises, any collection of water, sewage, rubbish, well, pool, gutter, channel cesspit, latrine, urinal or dump pit where mosquitoes may breed. Such a situation constitutes a nuisance. Any person who fails to clear such a nuisance is guilty of an offence under the Act.

Environmental health requirements are also provided for under the general powers and duties of the local authorities in the Local Government Act (Cap 265). Municipal Councils are required to provide and maintain sanitary services, sewage and drainage facilities, take measures for the control, destruction of rats, vermin, insects and pests, control or prohibit industries, factories and

businesses which emit smoke, fumes, chemicals, gases, dust, smell, noise vibrations, discomfort or annoyance to the neighborhood, and to prohibit or control work or trade of disinfect ion or fumigation by cyanide or other means.

The Penal Code (Cap 65) carries the offence of common nuisance identical to that in the Public Health Act. The offence under the Penal Code is a misdemeanor punishable by imprisonment for one year. This however is distinct from that in the Public Health Act which may require the offender to abate the offence.

Air pollution is dealt with by the Traffic Act (Cap 403) and the Factories (Amendment) Act of 1990. The Factories Act specifically prohibits factories from emitting any dust, fumes or impurities into the atmosphere without undergoing appropriate treatment to prevent air pollution or other ill effects to life and property. The amendment further prohibits the use of any stationary internal combustion engine, discharging exhaust gas into the atmosphere without treatment.

The Traffic Act prohibits air pollution through Section 51 which requires that motor vehicle use proper fuels. The Rules promulgated under the Act provide that every vehicle be so constructed, painted and used as not to emit any smoke, or visible vapor.

Air pollution as a manifestation of nuisance is also prohibited under the Mining Act (Cap 306). Section 26 requires that a holder of prospecting or mining license who causes a nuisance or damage to a landowner or lawful occupier to pay reasonable compensation for such nuisance or damage.

3.4.2 The Working Environment

The two statues relevant to this subject are the Factories Act (Cap 514) and the Mining Act (Cap 306). The primary environmental requirements under the Factories Act are that each factory must observe as high standards of cleanliness as are possible for the respective operations; avoid overcrowding, construct and maintain adequate ventilation, provide and maintain suitable natural or artificial lighting, as appropriate, provide drainage of floors and construct and maintain clean sanitary conveniences. The Minister for Labor may make rules specifying the requirements for these standards. All the standards prescribed and the rules promulgated by the Minister are however to be enforced by the local authority with the jurisdiction over the area in question.

3.4.3 Radiation Control

Since 1982, Kenya decided to join in the global movement for the use of nuclear energy for peaceful purposes, a movement lead by the International Atomic Energy Agency (IAEA). Most of such uses are in the fields of medicine, agriculture, energy and environmental monitoring. The dangers of injury to the public prompted the adoption of the Radiation Protection Act (Cap 243) in November 1984 to provide according to its citation, protection of the public and radiation workers from the dangers arising from the use of devices or materials capable of producing ionizing radiation and for connected purpose.

The Act prohibits the unauthorized manufacture, production, possession or use, sale, disposal, lease, loan or dealership, import, export of any irradiating device or radioactive material. All authorized buyers, sellers, users, of such device must be properly licensed.

3.4.4 Management of Hazardous Waste

In the foregoing section, we saw that radiation protection focuses largely on protection of human beings against injury by such wastes or radiations. The Public Health Act is also concerned with the protection of human health. Section 75 of the Constitution whose purpose is protection from

the deprivation of property, empowers the government to acquire property "in circumstances where it is necessary to do so because that property is in a dangerous state or injurious to the health of human beings or animals or plants." This is the closest reference to the protection of the environment and its resources.

3.5 Legislation on specifically protected areas

These are areas which through Gazettement by the government are designated as protected by law. Applicable statutes are the Forest Act, Cap 385, the Wildlife (Conservation and Management) Act, Cap 376 and the Water Act 2002. The principal legislation dealing with the management of wildlife resources is the Wildlife (Conservation and Management) Act of 1989. Wildlife in Kenya is classified as a national heritage held in trust for the benefit of the public. The administrative agency charged with the control and management of national parks and management of wildlife in general is the Kenya Wildlife Service (KWS). This regulatory regime requires that the Minister can declare that a given area is a national park, nature reserves or a sanctuary by gazette notice. The Act also provides for various offences and penalties thereof for those who enter and reside, hunt, collect products of bees or animals or their trophy, introduction of alien species, disturbing or quarrying, animals, damaging geological, prehistoric, archeological or marine and other scientific objects or structures lawfully placed in the parks, sanctuaries or reserves. In addition Cap 376 also provides for the regulation of the movement of tourists through the parks, as well as licenses for access thereto.

3.6 The Environmental Management and Co-ordination Act (EMCA)

The Environmental Management and Co-ordination Act No. 8 of 1999 is an Act of Parliament that provides for the establishment of an appropriate legal and institutional framework for the management of the environment. As earlier provided, prior to its enactment in 1999, there was no framework environmental legislation. Kenya's approach to environmental legislation and administration was highly Sectoral and legislation with environmental management components had been formulated largely in line with natural resource sectors as aforementioned.

EMCA was developed as a framework law, and this is due to the fact that the Act is thus far, the only single piece of legislation that contains to date the most comprehensive system of environmental management in Kenya. The Act provides for the establishment of an appropriate legal and institutional framework for the management of the environment in Kenya and for matters connected therewith and incidental hereto. The Act is based on the recognition that improved legal and administrative co-ordination of the diverse Sectoral initiatives is necessary in order to improve national capacity for the management of the environment, and accepts the fundamental principle that the environment constitutes the foundation of our national, economic, social, cultural and spiritual advancement. Section 3 of the Act enunciates the General Principles that will guide the implementation of the Act. Every person in Kenya is entitled to a clean and healthy environment and has the duty to safeguard and enhance the environment. It is worth noting that the entitlement to a clean and healthy environment, but also the duty to ensure that the environment is not degraded in order to facilitate one's own as well as other persons' enjoyment of the environment.

3.6.1 Protection and Conservation of the Environment

Part V of E.M.C.A. provides legal tools for sustainable management of the environment. It covers the protection and management of wetlands, hilly and mountainous areas, forest, environmentally significant areas, the ozone layer and the coastal zone. It further provides for the conservation of energy and biological diversity, access to genetic resources and environmental incentives. This Part of EMCA delegates onto the Director General various responsibilities to ensure protection and sustainable management of the environment. In addition, the part also gives the Minister in charge of environmental affairs the mandate to give orders, directions or regulations and standards vide gazette notice.

3.6.2 Environmental Impact Assessment

The importance of public participation in decision-making in environmental matters is further highlighted by the requirement for Environmental Impact Assessment (EIA) study report under Part VI of the Act. Any person, being a proponent of a project is required to apply for and obtain an E.I.A licence from NEMA before he can finance, commence, proceed with, carry out, execute, or conduct any undertaking specified in the 2nd Schedule of the Act. The EIA study report is published and the public is given a maximum period of sixty days for inspection of the report and submission of oral or written comments on the same. Any person may extend this period on application. The EIA process, thus, gives individuals and communities a voice in issues that may bear directly on their health and welfare and entitlement to a clean and healthy environment.

3.6.3 Environmental Audit and Monitoring

Part 7 of the Act (Sections 68-69) gives NEMA the responsibility of carrying out environmental audits of all activities that are likely to have significant effect on the environment. In consultation with lead agencies, the Act also authorises NEMA to carry out environmental monitoring of all environmental phenomena and operations of industry, projects or activities to determine their impacts.

3.6.4 Waste Management Regulations, 2006

These Regulations apply to all categories of waste as is provided for. According to the regulations, no person should dispose of any waste on a public highway, street, road, recreational area or in any public place except in a designated waste receptacle. Any person whose activities generate waste shall collect, segregate and dispose or cause to be disposed off of such waste in the manner provided for under these Regulations. Any person whose activities generates waste has an obligation to ensure that such waste is transferred to a person who is licensed to transport and dispose off such waste in a designated waste disposal facility. Any person, whose activities generate waste, should segregate such waste by separating hazardous waste from non-hazardous waste and shall dispose of such wastes in such facility as is provided for by the relevant Local Authority. Any person who owns or controls a facility or premises which generates waste should minimize the waste generated by adopting the following cleaner production principles, namely:

✤ improvement of production process through:

- i. conserving raw materials and energy
- ii. eliminating the use of toxic raw materials within such time as may be prescribed by the Authority
- iii. reducing toxic emissions and wastes
- iv. monitoring the product cycle from beginning to end by:
 - a. Identifying and eliminating potential negative impacts of the product.
 - b. Enabling the recovery and re-use of the product where possible.
 - c. Reclamation and recycling.
- v. Incorporating environmental concerns in the design, process and disposal of a product.

Every trade or industrial undertaking should install at its premises anti-pollution technology for the treatment of waste emanating from such trade or industrial undertaking. No owner or operator of a trade or industrial undertaking should discharge or dispose of any waste in any state into the environment, unless the waste has been treated in a treatment facility and in a manner prescribed by the Authority in consultation with the relevant lead agency.

PARAMETERSPERMISSIBLE LIMITSpH6.5-9.8.5Suspended solids100 mg/1Oil and greaseNilBOD30 mg/1COD50 mg/1Bio-assay test90% survival of fish after 96 hours in 100% effluent

a. Standards for Liquid Waste

Table 2: The effluent generated from any facility should conform to the following limits:

3.7 The Occupational Safety and Health Act, 2007

Is an Act of Parliament to provide for the safety, health and welfare of workers and all persons lawfully present at workplaces, to provide for the establishment of the National Council for Occupational Safety and Health and for connected purposes. This Act shall apply to all workplaces where any person is at work, whether temporarily or permanently. The purpose of this Act is to secure the safety, health and welfare of persons at work and protect persons other than persons at work against risks to safety and health arising out of, or in connection with, the activities of persons at work.

According to the Act, every occupier shall ensure the safety, health and welfare at work of all persons working in his workplace. Without prejudice to the generality of an occupier's duty under subsection (1), the duty of the occupier includes the provision and maintenance of plant and systems and procedures of work that are safe and without risks to health; arrangements for ensuring safety and absence of risks to health in connection with the use, handling, storage and transport of articles and substances; the provision of such information, instruction, training and supervision as is necessary to ensure the safety and health at work of every person employed, the maintenance of any workplace under the occupier's control, in a condition that is safe and without risks to health and the provision and maintenance of means of access to and egress from it that are safe and without such risks to health; the provision and maintenance of a working environment for every person employed that is, safe, without risks to health, and adequate as regards facilities and arrangements for the employees welfare at work; informing all persons employed of any risks from new technologies; and imminent danger; and ensuring that every person employed participates in the application and review of safety and health measures. Every occupier shall carry out appropriate risk assessments in relation to the safety and health of persons employed and, on the basis of these results, adopt preventive and protective measures to ensure that under all conditions of their intended use, all chemicals, machinery, equipment, tools and process under the control of the occupier are safe and without risk to health and comply with the requirements of safety and health provisions in this Act.

Every occupier shall send a copy of a report of risk assessment carried out under this section to the area occupational safety and health officer; every occupier shall take immediate steps to stop any operation or activity where there is an imminent and serious danger to safety and health and to evacuate all persons employed as appropriate. It is the duty of every occupier to register his workplace unless such workplace is expected from registration under this Act. An occupier who fails to comply with a duty imposed on him under this section commits an offence and shall on conviction be liable to a fine not exceeding five hundred thousand shillings or to imprisonment for a term not exceeding six months or to both. It is also the duty of every occupier to prepare and, as often as may be appropriate, revise a written statement of his general policy with respect to the safety and health at work of his employees and the organisation and arrangements for the time being in force for carrying out that policy; and to bring the statement and any revision of it to the notice of all of his employees.

3.8 The National Health Care Waste Management Plan 2008-2012

The National Health Care Waste Management Plan of Action is a document intended for use by health managers and programme officers across the health sector (including those in the private health sector). The purpose of developing this plan was to provide a tool that gives health managers guidance in planning, implementing and monitoring the activities of health care waste management in health facilities.

This plan describes the situation of health care waste management on the basis of a survey which was conducted in order to document the situation of waste management in Kenya. A holistic approach has been recommended to include, clear delineation of responsibilities, occupational health and safety programmes, waste minimization and segregation. This document is designed to provide viable options to address the challenges encountered in planning for health care waste management in Kenya.

3.9 Kenya National Guidelines on Safe Disposal of Pharmaceutical Waste, 2001

The provisions of these guidelines describe a series of steps that need to be followed in order to dispose unwanted pharmaceuticals. The steps required include; identification of pharmaceutical waste, sorting of pharmaceutical waste by category, filling the relevant forms to seek authority from the DHMT and the Chief Pharmacist among other persons to dispose such waste. Upon obtaining all the relevant approvals, the disposal of the pharmaceutical waste shall be effected under the supervision of the local pharmaceutical waste disposal team or the Waste Management Team (WMT).

The recommended methods for disposing of unwanted pharmaceuticals include:

- ✓ The use of either medium temperatures incineration at a minimum of 850°C or high temperature incineration exceeding 1200°C with two chamber incinerator for solids, semi- solids and powders for controlled substances e.g. anti-neoplastics.
- ✓ Engineered sanitary landfill to be used for disposal of expired or unwanted pharmaceuticals.
- ✓ Sewer disposal for diluted liquids, syrups, intravenous fluids, small quantities of diluted disinfectants and antiseptics.

3.9.1 National Policy on Injection Safety and Medical Waste Management

The mission statement of this policy is to ensure safety of health workers, patients, and the community and to maintain a safe environment through the promotion of safe injection practices and proper management of related medical waste. This is the first document of the Ministry of Public Health and Sanitation that is explicit on the need to address health waste management problems. The policy objectives spell out the need to advocate for support and implementation of proper management of medical waste among others.

Some of the guiding principles for the implementation of this policy include:

- Establishment of organizational structures at all levels for all the implementation of injection safety and related medical waste.
- ✓ The policy also addresses the need for environmental protection through appropriate waste disposal methods.
- ✓ Minimization of risks to patients, health workers, communities and the environment through application of safer injection devices and sharps waste disposal methods.

✓ Advocating for the strengthening of the necessary human resource capacity through training and sensitization for safe waste disposal

The provision of sustained supplies and equipment for waste management through strengthened logistics system addresses the need for commensurate investment in waste handling requirements. A unique strategy recommended also is the advocacy of best waste management practices through behaviour change communication as a key element in the strategy.

3.10 Radiation Protection Act, Cap 243

The Radiation Protection Act, Chapter 243, aims to control the; import, export, possession and use of radioactive substances and irradiating apparatus. Under this Act in section 9, a license is required to handle any radioactive substances or irradiating apparatus from the National Radiation Protection Board.

Handling here includes the method of disposing of radioactive waste products, transportation of radioactive materials, storage, use and maximum working hours that employees are expected to work with radioactive materials. Under this Act also, institutions generating this category of waste shall be expected to apply for a license from the same board.

4. CONSULTATIONS AND PUBLIC PARTICIPATION (C&PP)

The integration of public participation/involvement of stakeholders in EIA process is very important in terms of its implication for sound decision making and the sustainability of development activities. In this regard, the Kenya EIA Procedures provide for the involvement of stakeholders and the public in the assessment and review of proposed undertakings. This is achieved through a number of mechanisms, including the administration of questionnaires.

Public participation is a key component of an EIA and is used to integrate citizens into the environmental decision-making process. Traditional decision-making approaches such as closed-door discussions between politicians and experts are no longer appropriate. Public participation, if it is to be democratic, must foster trusting relationships through open and honest negotiations between proponents and the public (Barrington et al., 2003).

But it should be evident, when necessary, that a plan for public involvement was developed early in the process. The public should be provided with sufficient information about the proposed project and properly understand the project and issues to be able to give informed comments and participate fully in the process (Huang et al., 2003). It is important that there is evidence that all public comments are considered in the formulation of the list of concerns. All public comments should be recorded without judgment or prioritizing in the initial stages of the process (UNEP, 2002; Huang et al., 2003).

The public must be involved early in the process (Barrington et al., 2003). The public must not be placed in a reactive position. Decisions must not be evaluated after they have been made but rather participants must be involved at all stages of the EIA process. The public must be given sufficient time to digest information and prepare its comments, while keeping the whole procedure within a reasonable time frame.

Public and Stakeholders' involvement in the EIA process is essential and may lead to enormous benefits for the proponent, stakeholders and the nation. Where this is ignored, conflicts and problems may be created for project implementation and sustainability. Not only does the involvement of the public in the EIA process often strengthen the project, but public participation is required by the Environmental Management and Coordination Act (Environmental Impact Assessment) (EMCA-1999). The participation of beneficiaries and partners and the public in general has been identified as an essential component in ensuring sustainable and conflict free development.

To accomplish the mission of getting the public's opinion on the proposed project, one on one discussion with neighbors to gather the public opinions on the proposed laboratory project. The respondents included business people, patients and the residents of the region. All the respondents were in support for the project.

Issues raised included job creation, infrastructure improvement, gains in local and national economy, potential noise pollution, potential dust emissions, and potential increase in water demand, potential increased solid and liquid waste generation, risks of Accidents and Injuries to Workers and the public among others.

5. PROJECT ALTERNATIVE

5.1 Introduction

This chapter analyses the project alternatives in terms of site, technologies and non-implementation.

The purpose of including alternatives in the EIA is to identify and evaluate alternate actions that accomplish similar goals and promote sustainable development. Alternatives should be economically feasible with minimal adverse environmental impacts and time delays. Diverse alternatives to the proposed action must be included in the EIA. Alternatives may include both design and location options.

In most cases, the EIA process often occurs too late in decision-making to consider a full range of alternatives. This can undermine EIA goals to encourage more environmentally sound and publicly acceptable solutions. Allowing new alternatives and objectives to evolve in relation to environmental conditions and public preferences may be a solution to most of the environmental and socio-economic problems associated with the implementation of new projects (Anderson et al., 2003).

5.2 No-action alternative

The 'no-action' alternative, which serves as a baseline for comparative analysis, must be included where the environmental impacts of taking the proposed action is too high compared to the impact of not taking the proposed action. The No project alternative option in respect to the proposed project implies that the status quo is maintained. This option is the most suitable alternative from an extreme environmental perspective as it ensures non-interference with the existing conditions.

Under No project option, the proponent's proposal would not receive necessary approval from Authorities. The proposed construction would not be implemented. This option would however, involve several losses both to the proponent and the community as a whole. The No Project Alternative option is the least preferred from the socio-economic and partly environmental perspective due to factors such as the economic status of the Kenyans would remain unchanged; The local skills would remain under utilized (in terms of labor provision); Increased poverty and crime in Kenya due to lack of job opportunities; and The health sector would continue to suffer due to lack of enough and high quality health services in the area.

5.3 Renovation option

Renovation of the existing project is also one of the alternatives in ensuring the environmental status of the area is not affected. But, it is quite clear that as per the current situation, the existing laboratory cannot just be renovated. This is because it is too small to accommodate all proposed uses of the proposed facility. In this regard, the best option is to provide a new laboratory for the facility and which is in line with the schedule of accommodation.

5.4 Relocation option

Relocation of the proposed project is also one of the alternatives in ensuring the environmental status of the area is not affected. But, it is quite clear that as per the current situation, the proposed project cannot be relocated because the proponent currently owns the proposed site of development, hence getting an alternative site could be a very expensive venture. Hence this is

not an economically viable alternative. The laboratory will also serve the Malindi District Hospital, in which compound the facility will be constructed.

5.5 Waste Water Treatment Systems

The proponent has a variety of waste water treatment systems to choose from, which include the construction and utilization of bio-digesters, septic tanks, bio-box technologies or connecting to a sewer line.

5.5.1 Bio-digesters

The main physical features, the principles and process of bio-digestion are basically the same, regardless of the type of digester used. All bio-digesters degrade organic wastes to give methane which can be burnt to give energy. According to studies by Brown (1987), Silayo (1992) and Lekule (1996) the following advantages of the biogas technology were cited:

- ✓ It provides an alternative source of energy thus reducing the rate of deforestation
- ✓ It is a relatively cheap source of energy
- ✓ It improves crop-livestock-tree system through nutrient cycling
- ✓ It reduces time and workload of collecting fuel wood
- ✓ It reduces kitchen smoke-pollution thereby promoting human health
- ✓ It promotes good health through safe treatment of organic waste
- \checkmark As a renewable source of energy, it provides a reliable power supply that is environmentally friendly
- ✓ It is a rich source of nitrogen, phosphorus (P), potassium (K) and other macro- and micronutrients

But it needs a lot of care. It is highly involving and needs a highly committed community that is cooperative. No detergents/chemicals should find their way into the bio-digester. This is difficulty to monitor in a population characterized by people of different culture and values to such systems. This means the chances of a bio-digester failing are high. Once it fails, it can easily lead to environmental pollution.

5.5.2 Septic tank

This also one of the commonly utilized methods of treating sewage in urban set ups. But for a large urban population, it could be expensive to maintain and thus become an unsustainable way of handling wastewater. For this project, a septic tank and a soak could be appropriate option and sustainable way of managing wastewater provided it is built to the specified standards and well maintained.

5.5.3 Bio-box technology

Bio-box is a complete waste water treatment system (typically known as a packaged plant), suitable for establishments producing from $2m^3$ up to $320m^3$ (320,000 litres) of sewage per day. Typically, the establishment is not connected to a municipal sewerage system, and is thus responsible for disposing of its own effluent by means of a conservancy tank, septic tank or French drain.

A Bio-box sewage treatment plant treats the effluent on-site and produces clear, odourless and environmentally safe water for the irrigation of lawns, sports fields, golf courses and agricultural plots – or for filling dams where wildlife comes to drink, such as below a game lodge viewing platform, or simply to return it to the environment in streams, rivers or dams.

The system is modular in design and can thus be replicated to meet increasing demands for treatment from 2m³ to 320m³ (320,000litres) per day if required. Bio-box can treat both grey water (from laundries, baths, basins, kitchen sinks) and black water (toilet water). However, the technology needs electricity energy to run efficiently, hence if one can access a technology that needs no power to run, it becomes cheaper in the long run.

5.5.4 Connection to a Sewer Line

Following an assessment of the area surrounding the development site, it was established that a Malindi Municipal Council is currently doing a sewer line, which could serve the facility if completed before the operationalization of the laboratory.

This leaves the proponent with the option of a septic tank system or the bio-box system to manage sewage and waste water.

6. ANTICIPATED ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES

6.1 Introduction

A summary of the potential impacts on the socio-economic and biophysical environment is given below. Impacts are assessed in terms of their magnitude (size) and significance (importance). Actions necessary to mitigate potential impacts are given. Impacts' monitoring requirements are summarized in a section of this report.

6.2 Construction phase- Potential Environmental and Social Impacts

Construction phase potential negative impacts would include: stress on infrastructure as a result of increased population and vehicle traffic, soil erosion, possible surface and ground water hydrology changes and water quality degradation, solid waste generation, noise pollution, dust emissions, generation of exhaust emissions, increased water demand, increased energy consumption, increased use of building materials, likely accidents; physical and economic displacement and diseases. To ameliorate against the potential negative effects:

- Awareness creation and education of the project communities regarding HIV/AIDS and other diseases.
- The contractor will ensure that all machines are well tuned and maintained to reduce amount of exhaust emission.
- We recommend that delivery of construction materials to the site be well coordinated to reduce vehicle traffic jams in the area as well as possible accidents. By reducing traffic jam, the amount of engine idling of transportation trucks and other vehicles will be reduced considerably thus reducing on the exhaust emission released to the atmosphere.
- All materials will be ordered as per need to avoid over piling on site which leads to destruction of materials and unnecessary obstruction.
- The construction will be done in design that will allow for natural ventilation and lighting as well as both vertical and horizontal ventilation. The incorporation of natural ventilation and lighting will contribute to the reduction of the amount of energy consumed in artificial ventilation and lighting. Landscaping and greening of the buildings will be a contribution to the ongoing beautification and greening of the city, a factor that will subsequently be beneficial to carbon sequestration within the city.
- To save on water, the construction would also incorporate water saving designs such as waterless urinals in common areas, self timing taps and low volume water closets. Water harvesting from the roof will be implemented to provide water for cleaning, landscaping and use in the toilets. Roof water harvesting will also lead to the reduction of the amount of runoff within the area hence controlling the flooding that afflicts parts of the city during the rain seasons.
- Emergency escape routes will also be incorporated during this stage.
- To safeguard against accidental falls, all balconies and staircases will be fitted with metal rails and grills.
- Waste handling cubicles will also be constructed during this stage.
- To protect the health of workers on the site, they should be provided with protective gears and the contractor ensures that they make full use of them. Workers should not be forced or allowed to lift heavy loads. All materials on site should not be piled to heights that are prone to accidental falls. First Aid kits and emergency numbers should be conspicuously displayed. This means that someone trained in administering first aid should be present at the construction site all the time of the work. An insurance cover by

the contractor should be acquired to compensate for any unforeseen medical emergencies and injuries or destructions

• Provisions should be included during the construction period to allow for greening of public places. The proponent is committed to this.

On the other hand the anticipated positive impacts include:

- Creation of alternative employment opportunities,
- Improving growth of the economy,
- Improved health services, and
- > Provision of market for supply of construction materials and other services.

6.3 Operational Phase- Potential Environmental and Social Impacts

6.3.1 The Scope of the EIA during the Operating Phase

After the initial general assessment of all the proposed facilities, installations, activities, the general environment in and around the proposed Facility site and discussion with the proponent, we focused our assessment on the following issues: ~

- Environmental conservation activities and Environmental awareness
- Energy utilization and conservation
- Water Utilization and Conservation
- The Laboratory Operations
- Waste disposal and management
- Health and safety

6.3.2 Environmental Conservation Activities

It was observed that the Malindi Hospital has an incinerator. It is also connected to a septic tank system to ensure management of liquid waste from the health care facility. The hospital has relatively adequate vegetation cover, but more needs to be planted.

6.3.3 Water Utilization and Conservation

Water will be utilized in the bathrooms, sanitation services, in the laboratory operations and for general cleaning purposes. This water will be sourced from Malindi Water and Sanitation Company supply. But it should also be noted that no roof water harvesting within the hospital. The proponent should initiate roof water harvesting and install water storage tanks within the facility.

6.3.4 Waste Disposal and Management

a. Liquid Waste Management (Human Excrement)

The Laboratory under assessment will be served by a septic tank system. This means that flushing toilets will be fitted in each floor, both for men and women. The proponent has designed the sanitation facilities such that they will be fitted with easy to clean tiles on their walls. They should be construted in such a way that they are friendly to the disabled.

b. Liquid Bio-Medical Waste

Handling of bio-medical waste is proving to be an overwhelming challenge for the health sector in general. However, within the broader theme of bio-medical waste, liquid bio-medical waste is

emerging as particularly difficult to handle. Liquid biomedical waste is far more mobile and moves to a wider area after entering the subsurface water bodies or underground aquifers.

i. Challenge of Liquid Bio-Medical Waste

Most existing systems and technologies being used in handling liquid bio-medical waste are failing to address this problem. For instance, the routine exercise of pouring biomedical liquid waste is being questioned for posing higher infection threat to medical staff due to its susceptibility to spilling, splashing and aerosolising. Liquid bio-medical waste, if untreated, contains a wide variety of material that poses health hazards.

ii. Liquid bio-medical waste standards

According to the Waste Management Regulations *(EMCA provision, Sep. 2006)*, liquid pathological and chemical waste should be appropriately treated before discharge into the sewer. Pathological waste must be treated with chemical disinfectants, neutralised and then flushed into the sewage system. Chemical waste should first be neutralised with appropriate reagents and then flushed into the sewer system.

The treated effluent should conform to the limits as provided for under Waste Management Regulations of 2006. These limits are applicable to hospitals that are either connected with sewers without terminal sewage treatment plant or not connected to public sewers for discharge into public sewers with terminal facilities. Minimal safety requirements where medical establishments cannot afford treatment of biomedical liquid waste, following measures should be undertaken to reduce risks:

- ✓ Patients with enteric diseases should be isolated to wards where their excreta can be collected in buckets for chemical disinfection. This is of utmost importance in cases of cholera outbreaks.
- ✓ No chemicals or pharmaceuticals should be discharged into the septic before undergoing neutralization
- ✓ Sludges from hospital cesspools should be dehydrated on natural drying beds and disinfected chemically (for example, with sodium hypochlorite, chlorine gas, or preferably chlorine dioxide).
- ✓ Sewage from health care facilities should never be used for agricultural, aqua-cultural, drinking water, or recreational purposes.





6.3.5 Solid Waste Generation and Management

In Kenya and the world over, health-care services inevitably generate wastes that may be hazardous to health or have harmful environmental effects. Potentially infectious waste such as; sharps, cultures from medical laboratories or infected blood, carry a higher risk for infection and injury than any other type of waste. Other wastes of significant importance include; body fluids, all body parts, human tissues, placenta and radioactive waste among others. The absence of proper management measures to prevent exposure to hazardous health-care waste (HCW) results in important health risks to the general public, in- and out-patients as well as the medical and the supportive staff.

Improper disposal of health care soild waste may result in syringes and needles being scavenged and reused thus leading to significant numbers of hepatitis B, hepatitis C, and HIV infections among others. Even after the formulation of policies and laws on health care waste management, many health care establishments in Kenya still lack enforcement of legislation for handling, and disposal of health care waste. Furthermore, improper treatment or disposal of HCW such as open-air burning can constitute a significant source of pollution to the environment through the release of substances such as dioxins, furans or mercury. It is worthy to note that the proposed Facility is not peculiar and hence the above scenarion appllies to it. They generate what could be termed as Hospital Waste or Health Care Waste or Bio-Medical Waste.

Waste to be generated from the Health Care Facility includes sharps, bandages, cotton, syringes, paper, bottles, plastics and polythene (packanging materials) not to forget cultures and liquid waste.

A. Potential Health impacts of health-care waste

a) Types of hazards

Exposure to hazardous health-care waste can result in disease or injury. The hazardous nature of health-care waste may be due to one or more of the following characteristics:

- ✓ it contains infectious agents;
- \checkmark it is genotoxic;
- ✓ it contains toxic or hazardous chemicals or pharmaceuticals;
- \checkmark it is radioactive;
- \checkmark It contains sharps.

b) Persons at risk

All individuals exposed to hazardous health-care waste are potentially at risk, including those within health-care facility that generate hazardous waste, and those outside these sources who either handle such waste or are exposed to it as a consequence of careless management. The main groups at risk are the following:

- ✓ medical doctors, nurses, health-care auxiliaries, and hospital maintenance personnel;
- ✓ patients in health-care establishments or receiving home care;
- ✓ visitors to health-care establishments;
- ✓ workers in support services allied to health-care establishments, such as laundries, waste handling, and transportation;
- ✓ Workers in waste disposal facilities (such as landfills or incinerators), including scavengers.

The hazards associated with scattered, small sources of health-care waste should not be overlooked; waste from these sources includes that generated by home-based health care, such as dialysis, and that generated by illicit drug use (usually intravenous).

c) Hazards from infectious waste and sharps

Infectious waste may contain any of a great variety of pathogenic microorganisms. Pathogens in infectious waste may enter the human body by a number of routes:

- \checkmark through a puncture, abrasion, or cut in the skin;
- \checkmark through the mucous membranes;
- \checkmark by inhalation;
- ✓ By ingestion

Concentrated cultures of pathogens and contaminated sharps (particularly hypodermic needles) are probably the waste items that represent the most acute potential hazards to health. Sharps may not only cause cuts and punctures but also infect these wounds if they are contaminated with pathogens. Because of this double risk of injury and disease transmission sharps are considered as a very hazardous waste class. The principal concerns are infections that may be transmitted by subcutaneous introduction of the causative agent, e.g. viral blood infections. Hypodermic needles constitute an important part of the sharps waste category and are particularly hazardous because they are often contaminated with patient's blood.

d) Hazards from chemical and pharmaceutical waste

Many of the chemicals and pharmaceuticals used in the health-care establishments are hazardous (e.g. toxic, genotoxic, and corrosive, flammable, reactive, explosive, and shock-sensitive). These substances are commonly present in small quantities in the health-care waste; larger quantities may be found when unwanted or outdated chemicals and pharmaceuticals are disposed of. They may cause intoxication, either by acute or by chronic exposure, and injuries, including burns. Intoxication can result from absorption of a chemical or pharmaceutical through the skin or the mucous membranes, or from inhalation or ingestion. Injuries to the skin, the eyes, or the mucous membranes of the airways can be caused by contact with flammable, corrosive, or reactive chemicals (e.g. formaldehyde and other volatile substances). The most common injuries are burns.

Disinfectants are particularly important members of this group: they are used in large quantities and are often corrosive. It should also be noted that reactive chemicals may form highly toxic secondary compounds. Obsolete pesticides, stored in leaking drums or torn bags, can directly or indirectly affect the health of anyone who comes into contact with them.

During heavy rains, leaked pesticides can seep into the ground and contaminate the groundwater. Poisoning can occur through direct contact with the product, inhalation of vapours, drinking of contaminated water, or eating of contaminated food. Other hazards may include the possibility of fire and contamination as a result of inadequate disposal such as burning or burying.

The proposed Health Care Facility will be well equipped with firefighting equipment. All laboratory water sinks should be connected to a dilution chamber before reaching the main septic tank.

This is because chemical residues discharged into the sewerage system may have adverse effects on the operation of biological sewage treatment plants or toxic effects on the natural ecosystems of receiving waters. Similar problems may be caused by pharmaceutical residues, which may include antibiotics and other drugs, heavy metals such as mercury, phenols, and derivatives, and disinfectants and antiseptics. Although the Health Care Facility under study will not be connected to a sewer system, it will utilize a septic tank system, which has some biological fucntions as well.

e) Hazards from genotoxic waste

The severity of the hazards for health-care workers responsible for the handling or disposal of genotoxic waste is governed by a combination of the substance toxicity itself and the extent and duration of exposure. Exposure to genotoxic substances in health care may also occur during the preparation of or treatment with particular drugs or chemicals. The main pathways of exposure are inhalation of dust or aerosols, absorption through the skin, ingestion of food accidentally contaminated with cytotoxic drugs, chemicals, or waste, and ingestion as a result of bad practice, such as mouth pipetting. Exposure may also occur through contact with the bodily fluids and secretions of patients undergoing chemotherapy. The cytotoxicity of many antineoplastic drugs is cell-cycle-specific, targeted on specific intracellular processes such as DNA synthesis and mitosis. Other anti-neoplastics, such as alkylating agents, are not phase specific, but cytotoxic at any point in the cell cycle. Experimental studies have shown that many antineoplastic drugs are carcinogenic and mutagenic; secondary neoplasia (occurring after the original cancer has been eradicated) is known to be associated with some forms of chemotherapy.

Many cytotoxic drugs are extremely irritant and have harmful local effects after direct contact with skin or eyes. They may also cause dizziness, nausea, headache, or dermatitis. Special care in handling genotoxic waste is absolutely essential; any discharge of such waste into the environment could have disastrous ecological consequences.

f) Public sensitivity

Quite apart from fear of health hazards, the general public is very sensitive about the visual impact of anatomical waste that is recognizable human body parts including fetuses. In no circumstances is it acceptable to dispose of anatomical waste inappropriately, such as on a landfill or together with other solid wastes.

In some cultures, especially in Asia, religious beliefs require that human body parts be returned to a patient's family, in tiny "coffins" to be buried in cemeteries. The Muslim culture, too, generally requires that body parts are buried in cemeteries.

B. Potential Public health impact of health-care waste

a. Impacts of infectious waste and sharps

For serious virus infections such as HIV/AIDS and hepatitis B and C, health-care workers particularly nurses and laboratory technicians are at greatest risk of infection through injuries from contaminated sharps (largely hypodermic needles). Other hospital workers and waste-management operators outside health-care establishments are also at significant risk, as are individuals who scavenge on waste disposal sites. The risk of this type of infection among patients and the public is much lower. Certain infections, however, spread through other media or caused by more resilient agents, may pose a significant risk to the general public and to hospital patients. For instance, uncontrolled discharges of sewage from field hospitals treating cholera patients have been strongly implicated in cholera epidemics. It is for this reason that we recommend the proper connection of laboratory discharge systems and not, under any circumstances be left to empty into the open.

b. Potential Impacts of chemical and pharmaceutical waste

While there is no scientifically documented incidence of widespread illnesses among the general public due to chemical or pharmaceutical waste from hospitals, many examples may be found of extensive intoxication caused by industrial chemical waste. Moreover, many cases of injury or

intoxication result from the improper handling of chemicals or pharmaceuticals in health-care establishments. Pharmacists, anaesthetists, and nursing, auxiliary, and maintenance personnel may be at risk of respiratory or dermal diseases caused by exposure to such substances as vapours, aerosols, and liquids. To minimize this type of occupational risk, protective equipment should be provided to all personnel likely to be exposed. Premises where hazardous chemicals are used should be properly ventilated, and personnel at risk should be trained in preventive measures and in emergency care in case of accident. It should be made mandatory for all workers to be in protective gears when within the facilities.

6.3.6 Emergency response

One person should be designated as responsible for the handling of emergencies, including coordination of actions, reporting to managers and regulators, and liaising with emergency services, and a deputy should be appointed to act in case of absence.

In health-care establishments, spillage is probably the most common type of emergency involving infectious or other hazardous material or waste. Response procedures are essentially the same regardless of whether the spillage involves waste or material in use, and should ensure that:

- ✓ The waste management plan is respected;
- ✓ Contaminated areas are cleaned and, if necessary, disinfected;
- ✓ Exposure of workers is limited as much as possible during the clearing up operation;
- ✓ The impact on patients, medical and other personnel, and the environment is as limited as possible.

Health-care personnel should be trained for emergency response, and the necessary equipment should be to hand and readily available at all times to ensure that all required measures can be implemented safely and rapidly. Written procedures for the different types of emergencies should be drawn up and well displayed. For dangerous spills, the clean-up operation should be carried out by designated personnel specially trained for the purpose.

6.3.7 Dealing with spillages

Spillages usually require clean-up only of the contaminated area. For spillages of infectious material, however, it is important to determine the type of infectious agent; in some cases, immediate evacuation of the area may be necessary. In general, the more hazardous spillages occur in laboratories rather than in health-care departments. Procedures for dealing with spillages should specify safe handling operations and appropriate protective clothing. An example of such a procedure is provided below. Appropriate equipment for collecting the waste and new containers should be available as should means for disinfection;

In case of skin and eye contact with hazardous substances, there should be immediate decontamination. The exposed person should be removed from the area of the incident for decontamination, generally with copious amounts of water. Special attention should be paid to the eyes and any open wounds. In case of eye contact with corrosive chemicals, the eyes should be irrigated continuously with clean water for 10-30 minutes; the entire face should be washed in a basin, with the eyes being continuously opened and closed. Example of general procedure for dealing with spillages:

- i. Evacuate the contaminated area.
- ii. Decontaminate the eyes and skin of exposed personnel immediately.
- iii. Inform the designated person (usually the Waste Management Officer), who should coordinate the necessary actions.
- iv. Determine the nature of the spill.

- v. Evacuate all the people not involved in cleaning up if the spillage involves a particularly hazardous substance.
- vi. Provide first aid and medical care to injured individuals.
- vii. Secure the area to prevent exposure of additional individuals.
- viii. Provide adequate protective clothing to personnel involved in cleaning-up.
- ix. Limit the spread of the spill.
- x. Neutralize or disinfect the spilled or contaminated material if indicated.
- xi. Collect all spilled and contaminated material. [Sharps should never be picked up by hand; brushes and pans or other suitable tools should be used. Spilled material and disposable contaminated items used for cleaning should be placed in the appropriate waste bags or containers.
- xii. Decontaminate or disinfect the area, wiping up with absorbent cloth. The cloth (or other absorbent material) should never be turned during this process, because this will spread the contamination. The decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used.
- xiii. Rinse the area, and wipe dry with absorbent cloth.
- xiv. Decontaminate or disinfect any tools that were used.
- xv. Remove protective clothing and decontaminate or disinfect it if necessary.
- xvi. Seek medical attention if exposure to hazardous material has occurred during the operation.

(Adapted from: Reinhardt & Gordon (1991). Infectious and medical waste. Chelsea, MI, Lewis.)

6.3.8 Reporting accidents and incidents

All waste management staff should be trained in emergency response and made aware of the correct procedure for prompt reporting. Accidents or incidents, including near-misses, spillages, damaged containers, inappropriate segregation, and any incidents involving sharps should be reported to the Waste Management Officer (if waste is involved) or to another designated person. The report should include details of:

- ✓ The nature of the accident or incident;
- ✓ The place and time of the accident or incident;
- \checkmark The staff who were directly involved;
- ✓ Any other relevant circumstances

The cause of the accident or incident should be investigated by the Waste Management Officer (in case of waste) or other responsible officer, who should also take all possible action to prevent recurrence. The records of the investigation and subsequent remedial measures should be well documented.

6.3.9 Other Health and Safety issues to be considered in the Health Care Facility

It is hihgly recommded that all openings be well covered. All stare-cases should be well guarded with rails, a consideration that has already been undertaked by the proponent. To be installed in strategic positions within the Health Care Facility/Laboratory are fire extinguishers. However, it is recommendable that regular fire grills are carried out to sensitize all the Health Care staff on how to use them incase of fire outbreaks. Also to be provided and palce strategically are sand filled buckets within the facility.

6.4 De-Commissioning Stage

The economical life of the proposed project is expected to be between 50-80 years. At that point, the proponent shall have to vacate the site. The decommissioning exercise will have both positive and negative impacts:

6.4.1 Positive Decommissioning Impacts

a) Rehabilitation and Employment Creation

During the decommissioning stage, demolition or renovations will be done, creating job opportunities for the youth. As well, rehabilitation works will be undertaken for the proposed project site to restore it to its original state. This will include replacement of the topsoil and re-vegetation, which will enhance the aesthetic value of the area.

There will be need to employ people who will be involved in the reclamation of the site to near its original state.

6.5 Negative Decommissioning Impacts

a) Noise, Vibration and Dust

The earth moving works during top soil replacement will lead to significant deterioration of the acoustic environment within the area and the surrounding areas. This will be as a result of the noise and vibration that will be experienced from machines and workforce being utilized. Dust will also be emitted affecting the surrounding environment.

The proponent will put in place mitigation measures for noise and dust pollution during the decommissioning phase. The following noise containment techniques could be employed to minimize the impact of temporary destruction noise at the site:

- Use of equipments designed with noise control elements
- Limit pick up trucks and other small equipment to a minimum idling time and observe a common-sense approach to vehicle use, and encourage workers to switch off engines whenever possible.
- Wetting the development incase of demolition to reduce dust

7. ENVIRONMENTAL MANAGEMENT/MONITORING PLAN

7.1 Introduction

The development of new laboratory activities will have some impacts on the biophysical environment, health and safety of its employees and members of the public, and socio economic well being of the local residents. Thus, the main aim of the project should focus on reducing the negative impacts and maximizing the positive ones associated with its activities through a programme of continuous improvement.

An Environmental Management/monitoring Plan (EMP) has been developed to assist the proponent in mitigating and managing environmental impacts associated with the life cycle of the project. The EMP has been developed to provide a basis for an Environmental Management System for the project. It is noteworthy that key factors and processes may change in the course of the life of the project and considerable provisions have been made for dynamism and flexibility of the EMP. As such, the EMP will be subject to a regular regime of periodic review.

7.2 Environmental Monitoring and Auditing Program

There will be environmental management of any implications of the project that may not have been foreseen, which will include the administrative and production staff, the management, the public, the government and environmental experts.

Once a year, the project management will submit to the National Environment Management Authority (NEMA):

- ➤ A compilation of all monitoring data;
- ➤ A highlight of the activities related to environmental protection, environmental health, public health and safety and
- If the project has been cited for violation of environment and safety standards or regulations, certification from relevant authorities showing that the defect has been corrected or an acceptable plan of action is in place to correct the defect.

This can be termed as **the Annual Environmental Audit**. The following tables provide a summary of the monitoring that could be utilized.

The following tables form the core of this EMP for the construction, operational and decommissioning phases of this project. In general, the Tables outline the potential safety, health and environmental risks associated with the project and detail all the necessary mitigation

measures, as well as the persons responsible for their implementation and monitoring. The EMP will be used as checklist in future environmental audits of the project.

Issues	Decommendations	Type of Action	╘
188068	Recommendations	Type of Action	
Undercutting and tunneling (digging foundations) and presence of loose hanging rocks	 a. No undercutting and tunneling should be allowed in or around the project site so as to cause collapse or result to damage to property, injury or loss of life. b. No loose hanging rocks/material shall be allowed near or on the face of construction so as to endanger the safety of public. 	Administrative	
Poor site management; no fencing, no warning notices/signage	a. Warnings notices/signs of appropriate font size and in the national and local languages should be erected in appropriate places to warn the public of any danger e.g. 'Danger, no smoking'.	Administrative	
Lack of Personal Protective Equipment	 a. The following protective gear shall be used by persons working in the project site: protective helmets against falling objects gloves to protect against cuts and bruises protective shoes safety goggles overall/dust coat 	Administrative	
Lack of safety training and absence of any individual in charge of safety within the project site	a. Project workers should be trained on safety, health and environmental issues; The construction site to have a person in charge of safety; Establishment of 'Safety, Health and Environment Committees' (SHEC) at the project site.	Administrative	
Inadequate welfare facilities such as sanitation, first aid facilities and drinking water.	a. The project contractor should ensure provision of clean water and sanitation as well as well equipped first aid kit with trained first aiders within the project site	Administrative	
Working from heights, use of ladders and conveyance of materials from heights	a. where use of ladders is required, they should be strong, firmly secured and have a hand rail; where materials are conveyed down slope by gravity, there should be adequate barriers to check material rolling down slope.	Management , Administrative	
Disaster preparedness and response	Enhance training of the project workers on Disaster preparedness and response	Management Administrative	

Table 3: Occupational, Public Safety and Health Issues

Table 4: Environmental Issues

Issues	Recommendations	Type of Action	
Negative landscape	a. Project proponent should establish site rehabilitation and/or after	Administrative	
effects due to Presence	use plan. The after use plan should identify suitable beautification and		
of abandoned	landscaping plans to be implemented within and around the site.		
construction materials,			
pits and heaps of			
debris/wastes			
Dust emissions	a. The use of PPEs is recommended for both manual and mechanized	Administrative	
	operations while watering of the aggregates within the project site		
	should be mandatory for mechanized operations		
Excessive noise and	a. Adherence to the Noise and Excessive Vibrations Regulations, 2009	Administrative	
vibrations			

Table 5: Socio-Economic issues

Issues	Recommendations	Type of Action
Underage persons working in the construction site	a. Ensure that no minors work in the site	Administrative
Alcoholism and Drug abuse	a. Ensure no alcohol or drugs are available in the site	Administrative
Inadequate advisory services by relevant Government departments	a. Scheduled regular inspections and site meetings/Barazas	Administrative

HIV/Aids prevalence	a. Awareness creation on HIV/Aids in and around the	Administrative
	construction site	

7.3 Environmental Management Plans (EMP)

For the effective implementation of the mitigation measures, monitoring and remedial requirements presented in the EIA, a systematic Environmental Management Plan (EMP) should be set up. Environmental Auditing of the project will be done against the EMP and advise the necessary remedial actions required. The proponent and the Environmental Consultant through contractual means could enforce these remedial actions.

An Environmental Assessment has been completed for the proposed laboratory project, according to the requirements given in the EMCA 1999 and it's Subsequent Legal Notice No. 101 of 2003. The environmental aspects that have been thoroughly studied include Air quality impact; Noise/vibration impact; Water supply and quality impact; Effect on vegetation; Disposal of storm waters; Energy supply and use; Waste management implications; Landscape and visual impact; Environmental Monitoring and Audit (EM&A) requirements. A brief summary of the mitigation measures is given below for ease of reference.

	connential mermering, management p		PILLOU	
Expected Negative Impacts	Recommended Mitigation Measures	Responsible Party	Time Frame	Estimate Cost (Ks 1s.
High Demand of Raw materials	1. Source building materials from local suppliers who use environmentally	Resident Project Manager & Contractor	Throughout construction	
	2. Ensure accurate budgeting and estimation of actual construction material requirements to ensure that the least amount of material necessary is ordered.	Resident Project Manager & Contractor	Throughout construction period	Part of th
	3. Ensure that damage or loss of materials at the construction site is kept minimal through proper storage.	Resident Project Manager & Contractor	Throughout construction period	main bucge
	4. Use of some recycled/refurbished or salvaged materials to reduce the use of raw materials and divert material from landfills.	Resident Project Manager & Contractor	Throughout construction period	
	5. Specify locations for trailers and equipment, and areas of the site that should be kept free of traffic, equipment, and storage.	Civil Engineer, Architect and Resident Project Manager	1 month	
	6. Designate access routes and parking within the site.	Civil Engineer, Architect and Project Manager	1 month	
	7. Introduction of vegetation (trees, shrubs and grass) on open spaces and their maintenance., especially at the front side of the development	Architect, Resident Project Manager & Landscape specialist	Monthly to Annually	100,0000
	8. Design and implement an appropriate landscaping programme to help in revegetation of part of the project area after construction.	Architect & Landscape specialist	During the beginning phase of the project	
Increased storm water, runoff and soil erosion	1. Roof water to be harvested and stored in underground/ground reservoirs for use in cleaning and in the toilets. To ensure the use of such water for the stated purposes, the building should be	The Civil Engineer, Mechanical Engineer and Resident Project Manager	During the beginning phase of the project	100,000.00
	fitted with a dual water distribution system	L		

Table 6: Environmental monitoring/Management plans for the construction phase

	2. A storm water management plan that The Civil Engineer, minimizes impervious area infiltration by Mechanical Engineer and use of recharge areas and use of Resident Project Manager detention and/or retention with graduated outlet control structure will be designed.	1 month	50,000	.0
	3. Apply soil erosion control measures The Civil Engineer, such as leveling of the project site to Mechanical Engineer and reduce run-off velocity and increase Resident Project Manager infiltration of storm water into the soil.	1 months		
	4. Ensure that construction vehicles are The Civil Engineer, restricted to existing roads to avoid soil Mechanical Engineer and compaction within and around the Resident Project Manager project site.	Throughout construction period		
	5. Ensure that any compacted areas are Civil /Mechanical Eng. ripped to reduce run-off. and Project Manager	2 months	50,000	.0
	6. Open drains all interconnected will be Civil Engineer provided on site.	Throughout construction		
	7. Roof catchments will be used to collectCivil Engineer the storm water for some uses such as washing of floors and landscaping	Throughout construction period		
Increased solid waste generation	1. Use of an integrated solid waste Resident Project Manager management system i.e. through a& Contractor hierarchy of options: reduction, sorting, re-use, recycling and proper disposal	Throughout construction period		
	2. Through accurate estimation of the Resident Project Manager sizes and quantities of materials required, & Contractor order materials in the sizes and quantities they will be needed, rather than cutting them to size, or having large quantities of residual materials.	One-off		
	3. Ensure that construction materials leftResident Project Manager over at the end of construction will be Contractor used in other projects rather than being disposed of.	One-off		
	4. Ensure that damaged or wastedResident Project Manager construction materials including& Contractor cabinets, doors, plumbing and lighting fixtures, marbles and glass will be recovered for refurbishing and use in other projects	One-off		
	5. Donate recyclable/reusable or residualResident Project Manager materials to local community groups,& Contractor institutions and individual local residents	One-off		
	6. Use of durable, long-lasting materials Resident Project Manager that will not need to be replaced as often, & Contractor thereby reducing the amount of construction waste generated over time	Throughout construction period		
	7. Provide facilities for proper handlingResident Project Manager and storage of construction materials to & Contractor reduce the amount of waste caused by damage or exposure.	One-off		
	8. Purchase of perishable constructionResident Project Manager materials such as paints should be done Contractor incrementally to ensure reduced spoilage of unused materials	Throughout construction period		
	9. Use building materials that have Resident Project Manager minimal or no packaging to avoid the Contractor generation of excessive packaging waste	Throughout construction period	5 <u>0,</u> 000	.0

	10. Use construction materials Resident Pr containing recycled content when & Contract possible and in accordance with accepted standards.	roject Manager Throughout or construction period		
	11. Reuse packaging materials such as Resident Pr cartons, cement bags, empty metal and Mechanica plastic containers to reduce waste at the Contractor site	roject Manager, Throughout Il Engineer & construction period		
	12. Dispose waste more responsibly by Resident Pr dumping at designated dumping sites or Mechanica landfills only.	roject Manager, Throughout Il Engineer & construction period		
	13. Waste collection bins to be providedProject Maat designated points on siteMechanicaContractor	nager, Throughout Il Eng.& construction period		
	14. Private waste disposal company to be Resident Pr contracted to transport and dispose the Mechanica solid waste from site Contractor	roject Manager, Throughout Il Engineer & the project life cycle		
Dust emission	1. Ensure strict enforcement of on-site Resident Properties of the speed limit regulations & Contract 2. Avoid excavation works in extremely Resident Properties of the stremely Resident Properties of th	roject Manager Throughout or construction		
	2. Avoid excavation works in extremely resident ifdry weathers if and when possible3. Sprinkle water on graded access routes Resident Prwhen necessary to reduce dust Contractgeneration by construction vehicles	roject Manager Throughout roject Manager Throughout for construction period	100,000	20
T 1	4. Personal Protective equipment to beResident Pr worn	roject Manager Throughout construction		-
Exhaust emission	 Venicle failing time shall be minimized Resident Fi & Contract Alternatively fuelled construction Resident Pi equipment shall be used where feasible; Contract equipment shall be properly tuned and maintained 	roject Manager Throughout construction roject Manager Throughout construction period	50,000	0.0
	3. Sensitize truck drivers to avoid Resident Pr unnecessary racing of vehicle engines at & Contract loading/offloading points and parking areas, and to switch off engines at these points	roject Manager Throughout cor construction period		
Noise and vibration	1. Sensitize construction vehicle drivers Resident Pr and machinery operators to switch off & Contract engines of vehicles or machinery not being used.	roject Manager Throughout or construction period		
	2. Sensitize construction drivers to avoid Resident Por gunning of vehicle engines or hooting & Contract especially when passing through sensitive areas such as churches, residential areas and hospitals	roject Manager Throughout or construction period		
	3 . Ensure that construction machineryResident Pa are kept in good condition to reduce&Contract noise generation	roject Manager Throughout or construction period	50,000	0.0
	4 . Ensure that all generators and heavy duty equipment are insulated or placed & Contract in enclosures to minimize ambient noise levels.	roject Manager Throughout or construction period		
	5. The noisy construction works will Resident Prentirely be planned to be during day time & all site for when most of the neighbors will be away at work.	roject Manager Throughout preman construction period		
	1 Ensure electrical equipment Resident P	oject Manager Throughout	Part of	Fh.

consumption	appliances and lights are switched off Contractor	construction period	main budge
	2. Install energy saving fluorescent tubes Resident Project Manager at all lighting points instead of bulbs & Contractor which consume higher electric energy	Throughout construction period	
	3. Ensure planning of transportation of Resident Project Manager materials to ensure that fossil fuels Contractor (diesel, petrol) are not consumed in excessive amounts	Throughout construction period	
	4 .Monitor energy use during Resident Project Manager construction and set targets for reduction & Contractor of energy use.	Throughout construction period	
High Water Demand	1. Harness rainwater for some uses suchMechanical Engineer, as general cleaning, in the toilets &proponent and Resident gardening, hence the need for a dualProject Manager water distribution system within the building	Throughout construction period	
	2. Install water conserving taps that Resident Project Manager, turn-off automatically when water is notproponent & Contractor being used as wells low flush toilets and waterless urinals	One-off	
	3. Promote recycling and reuse of waterResident Project Manager as much as possible (need for a dual& Contractor water distribution system within the building)	Throughout construction period	100,000.00
	4. Install a discharge meter at water Resident Project Manager outlets to determine and monitor total Contractor water usage	One-off	
	5. Promptly detect and repair water pipe Resident Project Manager and tank leaks & Contractor	Throughout construction	
	6. Sensitize staff to conserve water by Resident Project Manager avoiding unnecessary toilet flushing etc. & Contractor	Throughout construction	
	7. Ensuring taps are not running when Resident Project Manager not in use & Contractor	Throughout construction	
Generation of wastewater	1. Provision of means for handling Mechanical Engineer & sewage generated by construction Resident Project Manager workers	One-off	
	2. Conduct regular checks for sewageMechanical Engineer & pipe blockages or damages since suchResident Project Manager vices can lead to release of the effluent into the land and water bodies	Throughout construction period	Part of the main bucge
	3. Monitor effluent quality regularly to Mechanical Engineer & ensure that the stipulated discharge rules Resident Project Manager and standards are not violated	Throughout construction period	
Machinery/ equipment safety	1. Arrangements must be in place for the Resident Project Manager, medical examination of all construction Developer & Contractor employees before, during and after termination of employment	Continuous	
	2. Ensure that machinery, equipment, Resident Project Manager, personal protective equipment, Developer & Contractor appliances and hand tools used in construction do comply with the prescribed safety and health standards and be appropriately installed maintained and safeguarded	One-off	50,000.00
	3. Ensure that equipment and work tasks Resident Project Manager, are adapted to fit workers and their Developer & Contractor ability including protection against mental strain	Continuous	

		4. All machines and other moving parts Resident Project Manager of equipment must be enclosed or guarded to protect all workers from injury	One-off		
		5. Arrangements must be in place to Resident Project Manager train and supervise inexperienced workers regarding construction machinery use and other procedures/operations	Continuous		
		6. Equipment such as fire extinguishers Resident Project Manager must be examined by a government authorized person. The equipment may only be used if a certificate of examination has been issued	Continuous		
		7. Reports of such examinations must be Resident Project Manager presented in prescribed forms, signed by the examiner and attached to the general register	Continuous		
Incidents, accidents dangerous occurrences	and	1. Ensure that materials are stored or Resident Project Manager stacked in such manner as to ensure their stability and prevent any fall or collapse	Continuous		
		2. Ensure that items are not Resident Project Manager stored/stacked against weak walls and partitions	Continuous		
		3. All floors, steps, stairs and passages of Resident Project Manager the premises must be of sound & Contractor construction and properly maintained	Continuous		
		4. Securely fence or cover all openings in Resident Project Manager	One-off		
		5. Ensure that construction workers are Resident Project Manager not locked up such that they would not & Contractor escape in case of an emergency	Continuous		
		6. All ladders used in construction works Resident Project Manager must be of good construction and sound & Contractor material of adequate strength and be properly maintained	One-off	50,000	.oc
		7. Design suitable documented Resident Project Manager emergency preparedness and evacuation & Contractor procedures to be used during any emergency	One-off	,	
		8. Such procedures must be tested at Resident Project Manager	Every 3 months		
		9. Ensure that adequate provisions are in Resident Project Manager place to immediately stop any operations & Contractor where there is an imminent and serious danger to health and safety and to evacuate workers	One-off		
		10. Ensure that the most current Resident Project Manager emergency telephone numbers posters & Contractor are prominently and strategically displayed within the construction site	One-off		
		11. Provide measures to deal with Resident Project Manager emergencies and accidents including & Contractor adequate first aid arrangements	Continuous		
		12. Ensure that provisions for reporting Resident Project Manager incidents, accidents and dangerous Developer & Contractor occurrences during construction using prescribed forms obtainable from the	, Continuous	50,000	.00
		presented torms obtainable from the			

	local Occupational Health and Safety Office (OHSO) are in place. 13. Enforcing adherence to safety procedures and preparing contingency plan for accident response in addition to safety education and training shall be	The Contractor, Resident Project Manager& Site Safety Officer	Continuous	
	14. Ensure that the premises are insured as per statutory requirements (third party and workman's compensation)	Developer	Annually	
	15. Develop, document and display prominently an appropriate SHE policy for construction works	Resident Project Manager, Developer & Contractor	One-off	
	16. Provisions must be put in place for the formation of a Health and Safety Committee, in which the employer and the workers are represented	Resident Project Manager	One-off	
occupational health and safety risks during	1. Well stocked first aid box which is easily available and accessible should be provided within the premises	Resident Project Manager & Contractor	One-off	
construction period and occupational	2. Provision must be made for persons to be trained in first aid, with a certificate issued by a recognized body.	Resident Project Manager & Contractor	One-off	
phase	3. Fire fighting equipment such as fire extinguishers and hydrant systems should be provided at strategic locations such as stores and construction areas.	Resident Project Manager & Contractor	One-off	
	4. Regular inspection and servicing of the equipment must be undertaken by a reputable service provider and records of such inspections maintained	Resident Project Manager & Contractor	Every 3 months	
	5. Signs such as "NO SMOKING" must be prominently displayed within the estate, especially in parts where inflammable materials are stored	Resident Project Manager & Contractor	One-off	
	6. Enough space must be provided within the premises to allow for adequate natural ventilation through circulation of fresh air	Resident Project Manager & proponent/residents/ contractor	One-off	50,000.0
	7. There must be adequate provision for artificial or natural lighting in all parts of the premises in which persons are working or passing	Resident Project Manager & Contractor	One-off	
	8. Circuits must not be overloaded	Project Manager & Contractor/ proponent	Continuous	
	9. Distribution board switches must be clearly marked to indicate respective circuits and pumps	Resident Project Manager & Contractor	One-off	
	10. There should be no live exposed connections	Project Manager & Contractor/ proponent	Continuous	
	11. Electrical fittings near all potential sources of ignition should be flame proof	Project Manager & Contractor/ proponent	One-off	
	12. All electrical equipment must be earthed	Project Manager & Contractor/ proponent	One-off	
	13. Develop a suitable system for the safe collection, recycling and disposal of chemical wastes, obsolete chemicals and empty chemical containers to avoid their	Resident Project Manager & Contractor/ proponent/residents	One-off	

	reuse for other purposes and to eliminate or minimize the risks to safety, health and environment			
	14. Ensure that all chemicals used in Resident Project Manager construction are appropriately labeled or & Contractor/ marked and that material safety data proponent/residents sheets containing essential information regarding their identity, suppliers classification of hazards, safety precautions and emergency procedures are provided and are made available to	One-off		
	15. Keep a record of all hazardous Resident Project Manager chemicals used at the premises, cross- & Contractor/ referenced to the appropriate chemical proponent/residents	Continuous	-	
	16. There should be no eating or Resident Project Manager drinking in areas where chemicals are & Contractor/	Continuous	-	
	17. Provide workers in areas with Resident Project Manager elevated noise and vibration levels, with & Contractor/ suitable ear protection equipment such proponent/residents as ear muffs	One-off		
	18. Ensure that construction workers are Resident Project Manager provided with an adequate supply of & Contractor wholesome drinking water that should be maintained at suitable and accessible points.	One-off		
	19. Ensure that conveniently accessible, Resident Project Manager clean, orderly, adequate and suitable & Contractor washing facilities are provided and maintained in within the site	One-off		
	20. Provision for repairing and Resident Project Manager maintaining of hand tools must be in & Contractor place	One-off		
	 21. Hand tools must be of appropriate Resident Project Manager size and shape for easy and safe use & Contractor 22. Height of equipment controls or Resident Project Manager 	One-off		
	work surfaces should be positioned to & Contractor reduce bending posture for standing workers			
Oil Spills	1. A designated garage section of the site Resident Project Manager fitted with oil trapping equipments to be planned for changes. Such an area will be well protected from contaminating the soil	Continuous	5, 000.0 per mo	01 1tl
Increased Food Supply/demand	1. Construction workers will be given Resident Project Manager breaks to go for lunch& Contractor	Continuous	- 50,000	00
	2. Onsite canteen to supply food if Resident Project Manager & Contractor	Continuous		
Hydrology and Water Quality Degradation	<i>1.</i> Hazardous substance control and The Mechanical Engineer, emergency response plan that will Resident Project Manager, include preparations for quick and safe Contractor & the clean up of accidental spills. Developer	Continuous	Part eros	t o ioi
	2. Hazardous-materials handling The Mechanical Engineer procedures to reduce the potential for a spill during construction	Continuous	con	rc
Vector /Water Borne Disease	1. Complete refuse collection and Mechanical Engineer handling service to be provided	Continuous	50,000	00

Incidence					
Possible Exposure to Diseases	1. Shall be mitigated by occupational health and safety standards enforcement	Contractor & all foremen	Continuous		
Increased Pressure on	1. Coordinate with other planning goals and objectives for region	Contractor and the Developer	Continuous		
Infrastructure	2. Upgrade existing infrastructure and services, if and where feasible.	Contactor and the Developer	Continuous		
Insecurity	1. Appoint security personnel operating 24 hours	Security Officer, Resident Project Manager & Police	Continuous		
	2. Body-search the workers on entry, to avoid getting weapons on site, and leaving site to ensure nothing is stolen.	Security Officer	Continuous	Par gene sai	: of ral ety
	3. Ensure only authorized personnel get to the site	Security Officer	Continuous		
Air Pollution	1. Suitable wet suppression techniques need to be utilized in all exposed areas	The Contractor & Site Safety Officer	Continuous	D (()	
	2. All unnecessary traffic must be strictly limited on site; speed controls are to be enforced	The Contractor & Site Safety Officer	Continuous	- Part of c con	rol
Emergence of new	1. Due to the nature of the project, the	Firm of Experts.	Continuous		
environmental concerns during the construction phase	Firm of experts shall carry out monitoring and evaluation. More so an initial environmental audit will also be carried within a period of 12 months			100,000	00
	after commencement of the operations				

7.4 Operational Phase EMP

The necessary objectives, activities, mitigation measures, and allocation of responsibilities pertaining to prevention, minimization and monitoring of significant negative impacts and maximization of positive impacts associated with the operational phase of proposed Health Care Project are outlined in the table below

Environmental	Mitigation	Responsibility	Monitoring	Monitoring	Monitoring	Duratic	n
Concerns	_		Means	Frequency	by:	and	
					-	Budget	
Safety	Such holes should be	Management	Observation	One off	An EIA	Ksh.	
	filled with soil or		to ensure that	activity	Expert and	20,000	
Likely open	covered with a		any open pits	-	the		
areas	concrete cover that is		are covered		management.		
	heavy enough not to be				-		
	lifted by children to						
	prevent accidental						
	falls.						
Safety	-Place sand filled	Management	Observation	Continuous	An EIA	Ksh.20	00
	buckets in strategic		to ensure	activity	Expert and	0	
Fire outbreak	places; Install a fire		that all fire		the		
preparedness	hydrant preferably		fighting		management.		
	near the main		mechanisms		-		
	entrances; Train all		are put into				
	workers in fire fighting		place				
	and subject them to		_				
	frequent fire grills; All						
	windows should be						
	fitted with openable						
	grills						

Table 7: Environmental Management Plan for the operation phase

Health and Safety For Patients and general	Waste bins should never be placed within the patients' waiting shades especially those	Management	Observation to ensure that this is implemented	Continuous activity	An EL Expert and the management	Ksh.5, 000 month	per
public	holding medical waste		mplemented		managemen	•	
Health and Safety Lack of protective gears	All staff within the facility should be in protective gears at all times	Management	Observation to ensure that this is implemented	Continuous activity	An ELA Expert and the management	Ksh5, C	00
Health and Safety within the facility	Reporting all incidents and accidents to include details of: -The nature of the accident	Management	Observation to ensure that this is implemented	Continuous activity	An ELA Expert and the management	<u>\</u> 1	
Accidents	or incident; The place and time of the accident or incident; The staff who were directly involved; Any other relevant circumstances		Implomented		lituriugenien		
Health and	-Evacuate the	Management	Observation	Continuous	An EL	1	
Safety	contaminated area; Decontaminate the		to ensure that this is	activity	Expert and the	1	
spillages	eyes and skin of exposed personnel immediately; Inform the designated person (usually the Waste Management Officer), who should coordinate the necessary actions.; Determine the nature of the spill; Evacuate all the people not involved in cleaning up if the spillage involves a particularly hazardous substance; Provide first aid and medical care to injured individuals; Secure the area to prevent exposure of additional individuals; Provide adequate protective clothing to personnel involved in cleaning- up; Limit the spread of the spill; Neutralize or disinfect the spilled or contaminated material if indicated; Collect all spilled and contaminated material. [Sharps should never be picked up by hand; brushes and pans or other suitable tools should be used. Spilled		implemente d		management		

material and disposable contaminated items used (or cleaning should be placed in the appropriate waste bags or containers. -Docontaminate absorbent cloth. The cloth containers. -Docontaminate absorbent cloth. The cloth containers. -Docontaminate absorbent cloth. The cloth containers. -Docontaminate absorbent cloth. The cloth containers. -Docontamination. the contamination. should never be turned during this process, bocause the working from the least to the most contamination. least to the most contamination. contaminate decontamination. -Rines the acca, and wipe dry with absorbent cloth. -Rines the acca, and wipe dry with absorbent cloth. -Remove protective clothing and decontaminate or disinfect in the cases or liquid should be used. -Rines the acca, and wipe dry with absorbent cloth. -Remove protective clothing and decontaminate or disinfect in the accass occurred during the operation. Water harvesting Initiate roof water harvesting waterial has occurred during the storbent cloth. -Remove protective clothing Management are fixed One off activity of the larines. Water harvesting Initiate roof water harvesting and install water storage tanks Management are fixed One off activity of typert and the management. Water harvesting -Construct a well functioning incinerator Management activity of typert and the Ksh.500, the							
disposable contaminated items used for clearing should be placed in the appropriate wase bags or containers. -Decontaminate or disinfect the arca, wiping up with absorbert absorbert absorbert absorbert cloth (or other absorbert absorbert matcrial) should never be turned during this process, because this most contamination should be carried out by working, from the contamination should be carried out by working, cloth by working, cloth measorbert a cach stage. Dry cloth cloth should be used -Rines the arca, and wipe dry with absorbert (cloth. -Becontaminate or disinfect thi necessary. -Seek medical attention -Seeveme to id contaminate or disinfect thi necessary. -Becontaminate or disinfect thi necessary. -Seek medical attention -Renove protective clothing and borge orduning the cords attention activity </th <th></th> <th>material and</th> <th></th> <th></th> <th></th> <th></th> <th></th>		material and					
contaminated items used for cleaning should be placed in the appropriate waste bags or containers.		disposable					
used for cleaning should be placed in the appropriate waste bags or containers. -Decontaminate or disinfect the area, wiping up with absorbent cloth. The cloth (or other absorbent material) should never be turned during this process, because this will spread the contamination. The decontamination should be carried out by working from the least to the most commination should be area; and will a change of cloth at each stage. Dry cloths should be used in the case of liquid in the case of liquid in the case of liquid should be used. -Rinse the area, and wige dry with absorbent cloth. -Decontaminate disinfect area; and wige dry with absorbent cloth. -Decontaminate of should be used. -Rinse the area; and wige dry with absorbent cloth. -Decontaminate of disinfect attention if exposure to hazardous material has courred during the operation. Observation activity One off An EIA Ash.300, Expert and the management. Latrines and other public cleaning velaming and storage facilities Management areas Observation activity One off An EIA Ash.20, An EI		contaminated items					
sheuld be placed in the appropriate waste bags or containers. Decontaminate or disinfact the area, wiping up with absorbent cloth. The cloth (or other absorbent material) should hever be turned during this process, because this will spread the contamination. The decontamination should be used in the carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregrated with water (acidic, basic, or neutral as appropriate) should be used. - Rinse the area, and wipe dry with absorbent cloth. - Decontaminate or disinfect any tools that were used. - Remove protective clothing and decontaminate or disinfect any tools that were used. - Remove protective clothing and decontaminate or disinfect any tools that were used. - Remove protective clothing and decontaminate or disinfect any tools that were used. - Remove protective clothing and decontaminate or disinfect any tools that were used. - Remove protective clothing and decontaminate or disinfect any tools that were used. - Remove protective clothing and decontaminate or approver tools - Remove protective clothing and decontaminate or approver tools - Remove protective clothing and decontaminate or approver tools - Remove protective cleaning - Construct awell functions water storage tanks - Construct a well functioning incinerator - sort water at source		used for cleaning					
appropriate waste bags or containinate bisinfect the area, wiping up with absorbent cloth. The cloth for other absorbent material should never be turned during this process, because this will spread the econtamination. The decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, to contaminate part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, the each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, the each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, the each stage. Dry cloth should be used inter (acidi, basic, or neutral as appropriate) should be itsed. -Remove protective clothing and decontaminate or disinfect animate or public areas should be fitted with white smooth files for easy cleaning. One off An EIA Ksh.300, Expert and the larines and walls of public areas should be fitted with white smooth files for easy cleaning. Management Observation are fixed and fitted in the case and the furthes and walls of public areas should be fitted with white smooth files for easy cleaning. One off An EIA Ksh.200, Expert and 000 Water harvesting and storage and storage tadilities Management Observation are fixed in the tarken and Ksh.200, activity An EIA Ksh.200, Expert and 000		should be placed in the					
or containinate or disinfect the area, wiping up with absorbent cloth. The cloth (or other absorbent bin material) should never be turned during this process, because this will spread the contamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. Image of the solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. Image of the solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. Image of the solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. Image of the solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. Image of the solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. Image of the solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be trace. Image of the solids, cloth if the arcs, and with the arcs, and with the arcs, and with the arcs, and with the arcs and the management. Itatrines and disinfect if if necessary. -scck medical attention if a exposure to the lattrines and walls or public arcas should be filted with white smooth tiles for casy cleaning water storage tanks water storage tanks water storage tanks One off area fixed area fixed activity An EIA base the management. Foor wase fullties -Construct a well fullties Management and spilles Observation are fixed activity An EIA base the and QOO		appropriate waste bags					
-Decontaminate or disinfect the area, wiping up with absorbent cloth. The cloth (or other absorbent material) should never be turned during this process, because this will spread the contamination. The decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. Image of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. Image of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. Image of cloth at each stage. Dry cloths should be used. -Rimes the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect if necessary. -seek medical attention if expessure to hazardous material has occurred during the operation. Observation activity One off An EIA Ksh.200, Expert and 000 the management. Vater harvesting and storage tacilities Imitiate recof water functioning incinerater -ort waste at source Management observation are fixed One off An EIA Ksh.200, activity		or containers.					
distinctthe area, wipingwiping upwith absorbent cloth. The clothcorrdistinct absorbent extrain should never be turned during this process, because this will spread the contamination. The decontamination should be carried out by working from the least to the most contaminated purt, with a change of cloth at each stage. Dry cloths should be used in the case of liquid splitage; for splitages of solud splitage; for splitages of solud be used. -Kinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect in the case, and were used. -Remove protective clothing and decontaminate or disinfect if in encessary, -Sock medical attention if exposure to the latrines and walls or public areas should be fitted with white smooth files for easy cleaningManagementObservation are fixed area fixed are fixedAn EIA calivityKsh.200 calivityWater Infraresting and storage tacilitiesManagementObservation are fixedOne off activityAn EIA ksh.200 calivityKsh.200 calivityWater Infraresting and storage tacilitiesManagementObservation are fixedOne off activityAn EIA ksh.200 calivityPoor waste disposal-Construct a well functioning incinerator -ser waste at sourceManagementObservation activityAn EIA ksh.200 calivity		-Decontaminate or					
Wing absorbent cloth. The cloth (or other absorbent material) should never be turned during this process, because this will spread the contamination. The decontamination should be carried out by working from the least to the most contaminated part, with a charge of cloth at each stage. Dry cloth should be used in the cass of liquid splitage; for splilages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe decontaminate operation.One contaminate of acidicid splitage; for splilages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if necessary. -seek medical attention if exposure to hazardous material has occurred during the operation.Observation activity of activity of An EIA Ksh.30 h Expert and 000 the harvesting and storage tealingWater harvesting and storage tacilitiesManagement observation are fixedOne activity of An EIA Ksh.20 h Expert and 000 the harvesting and instal water storage tanksObservation activity of An EIA Ksh.20 h Expert and 000 the harvesting and instalWater harvesting and storage cloatingManagement observation are fixedOne activity of Xpert and 000 the harvesting and instalPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement observation activity to typert and 000 the <br< th=""><th></th><th>disinfect the area,</th><th></th><th></th><th></th><th></th><th></th></br<>		disinfect the area,					
Latrines and other public areas Index or office absorberni materialb should never be turned during this process, because this will spread the contamination. The decontaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. In the case of liquid spillage; for spillages of solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. In the case of liquid spillage; for spillages of solids, cloth impregnated with water (acide, basic, or neutral as appropriate) should be used. In the case of liquid spillage; for spillages of solids, cloth impregnated with water acide, basic, or neutral as appropriate) should be used. In the case of liquid spillage; for spillages of solids, cloth impregnated with water acide, basic, or neutral as appropriate) should be used. In the case of liquid spillage; for spillages of solids, cloth impregnated of the case of the acide in the case of disinfect if fnecessary. -Seek medical attention if exposure to hazerding the operation. Observation activity One activity An ElA Expert and he management. Ksh.30 OO he management. Water harvesting and storage facilities Management water storage tanks Observation are fixed One activity An ElA Expert and he management. Ksh.30 OO he management.		absorbent cloth The					
Latrines and of the stronger targed areasMain agement the stronger the stronger<		cloth (or other					
should never be turned during this process, because this will spreadthe the contamination. The decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used impregnated with water dackic, basic, or neutral as appropriate) should be used. -Rimse the area, and wipe dry with absorbent Cloth. -Decontaminate or disinfect if if necessary, -Seek medical attention if exposure to hazardous material has cocurted during the operation.Observation are fixed operationAn ElA kSh.30°, the anagement.Ksh.30°, the activityLatrines and of the latrines and walls or disinfect if if necessary, -Seek medical attention if exposure to hazardous material has cocured during the operation.ObservationOne activityAn ElA kSh.30°, the management.Water harvesting and storage tasing and storage tasing and instage.Management costructionOne are fixedAn ElA kSh.20°, the management.Water harvesting and storage tasing and storage tasing and instage.Management costruction are fixedOne activity of Expert and the management.Water harvesting and instage managementManagement costruct a well functioning incinerator sort waste at sourceObservation and costruct and activity of activity of aco		absorbent material)					
during this process, because this will spread the contamination. The decontamination about be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid splitage; for splitages of solids, cloth, about bused. -Rinse the area, and wige dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing the latrines and walls or during the areasManagementObservation are fixed are fixedAn EIA Ksh.200, Expert and the latrines and walls of ubits areas should be fitted with white smooth ties for easy cleaning.ManagementObservation are fixed are fixedAn EIA Ksh.200, Expert and the latrines and walls of ubits areas should be fitted with white smooth ties for easy cleaning.ManagementObservation are fixed are fixedAn EIA Ksh.200, Expert and the latrines and walls of ubits areas should be fitted with white smooth ties for easy cleaning.ManagementObservation are fixedAn EIA Ksh.200, Ksh.200, An EIA Ksh.200, An EIA Ksh.200		should never be turned					
because this will spread the contamination. The decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid splilage; for spillages of solids, cloth impregnated with water facilic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothus material has occurred during the operation.Observation one off activityAn EIA EXP Ksh.30-, the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect any tools that were used.Observation activityOne off An EIA Ksh.30-, the area, and wire disinfect if necessary. -Seek medical attention if exposure to hazardious material has occurred during the operation.One off activityAn EIA Ksh.30-, Expert and the latrines and walls areasWater harvesting and storage fabilic areas should be fitted with white managementManagementObservation are fixedOne off An EIA Ksh.30-, Expert and the management.Water harvesting and storage fabilitiate roor waster disposalManagementObservation are fixedAn EIA Ksh.20-, Expert and the management.Por waste disposal-Construct a well inctioning incinerator -soft waste at sourceManagementObservation activity the Expert and the management.		during this process,					
spread the contamination contamination the decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at cach stage. Dry cloths should be used in the case of liquid is a spread nimpegnated with water (acidic, basic, or neutral as appropriate) should be used. is a spread is a spread -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. is a spread -Remove protective clothing One off -Remove protective clothing and decontaminate operation. Management Observation One An ELA Expert and other public areas Initiate roof water harvesting The walls and floors of harvesting Management Observation are fixed One An ELA Ksh.200, the management. Water Initiate roof water harvesting and storage Management Observation are fixed One An ELA Ksh.200, the management. Poor waste disposal -Construct a well functioning incinerator -sort waste at source Management Observation are fixed A continuous An ELA Ksh.200, the management.		because this will					
contamination decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbert cloth. -Decontaminate or disinfect any tools that were used. -Remove protective cloths appropriate) should be used. -Rinse the area, and wipe dry with absorbert cloth. -Decontaminate or disinfect if if necessary. -seek medical attention if exposure to the latrines and other public areasManagement observationOne off and foces of the latrines and using the latrines and of ublic areas should be fitted with white smooth tiles for casy cleaningManagement ObservationOne off activityAn EIA Expert and the latrines and the latrines and walls of public areas should be fitted with white smooth tiles for casy cleaningManagement ObservationOne off activityAn EIA Expert and the management.Ksh.200, oO0Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage lanksManagement observationOne off activityAn EIA Expert and the Expert and the the management.Por wasie disposal-Construct a well functioning incinerator -soft waste at sourceManagement observationObservation activityAn EIA Expert and the tarted vith white ensure that the		spread the					
decontamination should be carried out by working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (aclide, basic, or neutral as appropriate) should be used.		contamination. The					
Image: should be carred out by working from the least to the most contaminated part, with a charge of cloth at each stage. Dry cloth should be used in the case of liquid spilage; for spilages of solids, cloth and the used in the case of liquid spilage; for spilages of solids, cloth and the used -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if if necessary. -seek medical attention if exposure to hazardous material has occurred during the operation.Observation one off activityOne off An EIA Expert and the Remove protective clothing and decontaminate or disinfect if if necessary. -seek medical attention if exposure to hazardous material has occurred during the operation.Observation activityOne off An EIA Expert and the the lattices and walls of public areas should be fitted with white smooth files for easy cleaningManagement ObservationOne off are fixedAn EIA Expert and the management.Ksh.20, oO0Water harvesting and storage facilitiesImitiate roof water harvesting and install water storage tanksManagement ObservationOne off activityAn EIA Expert and the management.Ksh.50, OO0Por waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement observationObservation activityAn EIA Expert and the management.		decontamination					
Py working from the least to the most contaminated part, with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water facidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wire dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect any tools that were used. The walls and floors of the taitrines and operation.Management ObservationOne oneAn ELA Expert and the Expert and the management.Ksh.300, activityWater harvesting and dorage facilitiesInitiate noof water harvesting and install water storage tanksManagement Observation are fixedOne of correr of activityAn ELA Expert and the management.Ksh.200, activityWater harvesting and storage functioning incinerator -sort waste at sourceManagement Observation are fixedOne activityAn ELA Ksh.200, activityKsh.200, activityWater harvesting and storage functioning incinerator -sort waste at sourceManagement Observation activity to Expert and courted activity to Expert and courted activity to Expert and courted activity to Expert and courted activity to expert and courted		snould be carried out					
Latrines and of public areasThe case of liquid spillages of solids, cloth impregnated with water calcide, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure too hazardous material has occurred during the operation.Observation of public areasOne of AnAnEIA Ksh.30 h, oloLatrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagement Observation are fixedOne of AnAnEIA Ksh.30 h, oloWater harvesting and dorage facilitiesInitiate roof water harvesting and install water storage tanksManagement Observation are fixedOne of AnEIA Ksh.50 h, Expert and oloo the management.Water harvesting facilitiesInitiate roof water functioning incinerator -sort waste at sourceManagement Observation are fixedOne of AnAnEIA Ksh.50 h, olooWater harvesting facilitiesInitiate roof water functioning incinerator -sort waste at sourceManagement Observation are fixedA continuous AnEIA EXpert and olooPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement Observation are fixedA continuous AnEIA EXpert and oloo		by working from the					
with a change of cloth at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if in necessary. -Seek medical attention if exposure to hazardous material has occurred during the opperation.Observation one off activityAn EIA Expert and 000 the management.Ksh.30 the activityLatrines and of public areasThe walls and floors of of public areas should be firthed with white smooth tiles for easy cleaningManagement ObservationOne off activityAn EIA Expert and 000 the management.Water harvesting and storage facilitiesInitiate noof water harvesting and install water storage tanksManagement Observation are fixedOne off activityAn EIA Expert and 000 the the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement Observation activity to Expert and ool operation		contaminated nart					
at each stage. Dry cloths should be used in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfact any tools that were used. -Remove protective clothing and decontaminate or disinfact if freecessary. -Seek medical attention if exposure tool hazardous material has occurred during the operation.ObservationOne activityAn EIAKsh.300, Expert and the Ksh.300, the Ksh.300, activityLatrines and other public areasThe walls and floors of fuel values and sourceManagementObservation are fixedOne activityAn EIAKsh.300, Expert and the Ksh.300, the Ksh.300, the smooth tiles for easy cleaningWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ObservationOne activityOne continuous An ELAKsh.500, activity to Expert and O00Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagementObservation activity to activity to Expert and O00Non Expert and O00		with a change of cloth					
Cloths should be used in the case of liquid spillages for spillages of solids, cloth impregnated with water claidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Renove protective clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.One off conservationAn EIA EXP Ksh.300, Expert and 000 the management.Ksh.300, conservationLatrines and other public areasThe walls and floors of hazardous material has occurred during the should be fitted with white smooth tiles for easy cleaning.Management ObservationOne off activityAn EIA EXpert and 000 the management.Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ObservationOne off activityAn EIA EXpert and 000 the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ObservationOne off activity to Expert and 000 the activity to Expert and 000		at each stage. Dry					
in the case of liquid spillage; for spillages of solids, cloth impregnated with water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ObservationOne off activityAnEIA Ksh.30Ksh.30 OOLatrines and other public areasThe walls and floors of the latrines and walls areasManagementObservationOne activityAnEIA Ksh.30Ksh.30 OOWater harvesting and usdersInitiate roof water harvesting and install water storage tanksManagementObservation are fixedOne activityAnEIA Ksh.20 Ksh.20 Ksh.20 AnKsh.20 Ksh.20 AnKsh.20 Ksh.20 Ksh.20 AnAnEIA Ksh.20 Ksh.20 Ksh.20 Ksh.20 Ksh.20 An wate storage tanksManagementObservation are fixedAnEIA Ksh.20 Ksh.20 Ksh.20 Ksh.20 Ksh.20 Ksh.20 An wate storage tanksManagementObservation are fixedAnEIA Ksh.20 Ksh		cloths should be used					
spillage; for spillages of solids, cloth impregnated water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ManagementObservationOne activityAn EIA EXpert and the management.Ksh.30 (No ObservationLatrines and other public areasThe walls and floors of public areas should be fitted with white smooth tiles for easy cleaningManagementObservationOne activityAn EIA Expert and the kare storage tanksWater harvesting and vier storage tanksManagementObservation are fixedOne activityAn EIA Expert and the management.Water harvesting facilitiesInitiate roof water harvesting and install water storage tanksManagement ObservationOne are fixedOne activity of Expert and the activity of ensure that the the activity of ensure that the the activity of ensure that the the activity of ensure that the the activity of ensure that the ensure that the ensure that<		in the case of liquid					
solids,cloth impregnatedimpregnatedwith water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipedry-Rinse the area, and wipedrywith absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ObservationOne oneAnEIA EXpert and doo0 the management.Latrines and of other public areasThe walls and floors of public areas should be fitted with white smooth files for easy cleaningManagementObservation are fixedOne offAnEIA EXpert and doo0 the management.Water harvesting and storage facilitiesManagementObservation are fixedOne offAnEIA EXpert and ooo the management.Poor waste facilities-Construct a well functioning incinerator -sort waste at sourceManagementObservation activity to Expert and ooAnEIA EXpert and oo activity to ensureAnEIA EXpert and oo the management.		spillage; for spillages of					
impregnatedwith water harvesting and forzage facilitiesimpregnated with water storage tankswith with water harvesting and starts and occurred a well functioning incinerator ManagementManagement Observation are fixedOne off AnAnEIA EIA Ksh.30 \ Ksh.30 \ Ksh.30 \ OoWater harvesting and disposalInitiate roof waste functioning incinerator sort waste at sourceManagementObservation are fixedOne off AnAnEIA EXpert and dood AnKsh.30 \ OO AnPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagementObservation are fixedOne off AnAnEIA EXpert and dood AnKsh.30 \ OO AnMater harvesting and functioning incinerator sort waste at sourceManagement ManagementObservation are fixedOne off AnAnEIA EXpert and dood he management.		solids, cloth					
water (acidic, basic, or neutral as appropriate) should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ObservationOne activityAnEIA Ksh.30 h, 000Latrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaning.ManagementObservation activityOne activityAnEIA Ksh.20 h, O00 of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaning.ManagementObservation are fixedOne activityAnEIA Ksh.20 h, AnKsh.20 h, AnWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagementObservation are fixedOne activityAnEIA Ksh.20 h, AnKsh.20 h, AnPoor waste facilities-Construct a well functioning incinerator -sort waste at sourceManagementObservation activity to Expert and activity to Expert and cleaningEIA Ksh.50 h, OOO		impregnated with					
neutral as appropriate) should be used. -Remove protective clothing and decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if incressary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ManagementObservation observationOne activityAnEIA EXpert and the management.Latrines and of public areasThe walls and floors of the latrines and wills of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation are fixedOne activityAnEIA EXpert and the Expert and the areasKsh.20 OOOWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ObservationObservation activityOne off AnEIA EXpert and be fitted with white are fixedAnEIA EXpert and be fitted with white are fixedShould AnOne activityAnEIA EXpert and be fitted with white are fixedPoor waste facilities-Construct a well functioning incinerator -sort waste at sourceManagement ObservationObservation A continuous AnAnEIA EXpert and be fitted with theKsh.50 oOO		water (acidic, basic, or					
should be used. -Rinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ObservationOne activityAn ELAELA Ksh.30Ksh.30Latrines and other public areasThe walls and floors of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation activityOne activityAn ELA ExpertELA Ksh.30Ksh.30,Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne activityAn ELA ExpertELA Ksh.30Ksh.20,Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation activityA continuous A continuous An ensure that theKsh.50,		neutral as appropriate)					
-kinse the area, and wipe dry with absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.One observationAn EIAEIA Ksh.30 \ OOOLatrines and other public areasThe walls and floors of public areas should be fitted with white smooth tiles for easy cleaningManagement ManagementObservation are fixedOne offAn EIAEIA Ksh.30 \ OOOWater harvesting and storage facilitiesManagement harvesting and install water storage tanksManagement ManagementObservation are fixedOne activityAn EIA Ksh.20 \ Management.Ksh.20 \ OOOPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation activityA continuous A nEIA Ksh.50 OOO		should be used.					
Wipe absorbent cloth. -Decontaminate or disinfect any tools that were used. -Remove clothing and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.Observation activityOne off activityAn ELA Expert and the management.ELA Ksh.300, OO0Latrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagement and storage facilitiesObservation are fixedOne activityAn ELA Expert and the management.Ksh.300, OO0Water harvesting and storage facilitiesThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagement and storage are fixedOne activityAn ELA Expert and itstall water storage tanksKsh.20 An activityConstruct a well functioning incinerator -sort waste at sourceManagementObservation activityAn activityELA EXpert and the activityKsh.500, OO		-Rinse the area, and					
Absolute contaminate disinfect any tools that were used. -Remove clothing decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.AnnagementObservation activityOne activityAnn ELA Expert and door the management.Latrines and other public areasThe walls and floors of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation activityOne activityAnn ELA Expert and activityAnn ELA Expert and be fitted with white smooth tiles for easy cleaningManagementObservation are fixedOne activityAnn ELA Expert and be fitted with white smooth tiles for easy cleaningManagementObservation are fixedOne activityAnn ELA ExpertKsh.20 % Ann ELA Ksh.20 %Water harvesting and storage facilities-Construct a well functioning incinerator -sort waste at sourceManagementObservation activityA continuous activity to expert and activity to expert and ADOOAnn ELA Ksh.50 %		wipe ary with					
DescriptionDescriptiondisinfect any tools that were used. -Remove protective clothing and decontaminate or disinfect if if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.and addisinfect if if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ObservationOne off activityAn EIA Expert and the management.Latrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation observationOne off activityAn EIA Expert and the management.Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne off activityAn EIA Expert and the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ObservationObservation activityA continuous activity to expert and activity to expert and oO0		Decontaminate or					
Water harvesting and decontaminate or disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.ManagementObservation observationOne activityoff AnAnEIA EXpert and 000Ksh.30 000Latrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagement ManagementObservation activityOne off AnAnEIA EXpert and 000Ksh.30 000Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne off AnAnEIA EXpert and 000Ksh.20 the the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation activityA continuous activity to Expert and the construct a woll functioning incinerator -sort waste at sourceObservation A continuous A continuousAnEIA EXPert and OOOKsh.50 the management.		disinfect any tools that					
Remove clothing clothing disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.An EIA ManagementKsh.30 ObservationLatrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation observationOne activityAn EIA Expert and other management.Ksh.30 OO0Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne activityAn EIA Expert and OO0Ksh.20 OO0Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation activityA continuous and storage the management.EIA Ksh.50 OO0		were used					
Clothingand decontaminateor disinfect it if necessary. -Seek medical attention ifexposure to hazardous material has occurred during the operation.of ManagementAnEIA EXKsh.30 OOOLatrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation observationOne activityoff Expert and the management.An EIA Ksh.30 OOOKsh.30 OOOWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne off activityAn EIA Ksh.20 OOOKsh.20 OOOPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ObservationObservation activityA continuous activity to Expert activity to ExpertAn EIA Ksh.50 OOO		-Remove protective					
decontaminate disinfect it if necessary. -Seek medical attention if exposure occurred during the operation.decontaminate or disinfect it if necessary. -Seek medical attention if exposure operation.decontaminate or disinfect it if necessary. -Seek medical attention if exposure operation.decontaminate or hazardous material has occurred during the operation.decontaminate operation.decontaminate operation		clothing and					
disinfect it if necessary. -Seek medical attention if exposure to hazardous material has occurred during the operation.disinfect it if necessary. occurred during the operation.Seek medical attention if exposure to hazardous material has occurred during the operation.ManagementObservationAn export activityEIA Expert and the the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation activityOne activityoff Expert and the management.An EIA Expert and to 000Ksh.30 000Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne activityAn EIA Expert and the management.Ksh.200 OOPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation A continuous activity to ensure thatAnEIA EXpert and 000Ksh.50 OO		decontaminate or					
-Seek medical attention if-Seek medical attention if-S		disinfect it if necessary.					
ifexposuretohazardous material has occurred during the operation.hazardous material has occurred during the operation.hazardous material has occurred during the operation.hazardous material has occurred during the operation.ObservationOne activityAn EXPERT Expert and the haragement.Ksh.300, OO0Latrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation activityOne activityAn EXPERT Expert and the management.Ksh.200, OO0Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne off AnAn EIA Expert and the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement An An ensureObservation A continuous activityAn EIA EXpert and the management.		-Seek medical attention					
hazardous material has occurred during the operation.hazardous material has operation.hazardous material has operation.hazardous material has operation.hazardous material has operation.hazardous material has operation.hazardous material has operation.haves of management.AnEIA EXpertKsh.300, 000Inter areasof public areas should be fitted with white smooth tiles for easy cleaningManagementObservation activityOne offAnEIA EXpertKsh.200, 000Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne offAnEIA EXpertKsh.200, 000Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ObservationObservation A continuous activity to ensure that theKsh.500, 000		if exposure to					
Iatrines and other public areasThe walls and floors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagement managementObservation observationOne activityoff Expert and the management.An EIA Expert and 000Ksh.30 % 000Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation observation are fixedOne off An EIA Expert AnAn EIA EXpert and O00Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation A continuous A continuous An ensure ensure that theAn EIA Ksh.500 OO		hazardous material has					
Latrines and other public areasThe walls and floors of public areas should be fitted with white smooth tiles for easy cleaningManagement observationObservation activityOne activityoff Expert and observationAn ELA Expert and the management.EA Solution observationKsh.300, observation activityWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne activityOff Expert and off activityAn ELA Expert and off Management.One off are fixedAn ELA Expert and off activityKsh.200, ool ool cleaningWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation observation are fixedOne activityOff Expert and ool the management.An ELA Ksh.200, ool Expert and ool ool the management.An ool ELA Ksh.500, activity to Expert and the the management.Management the the management.Ool ool the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement theObservation activity to ensureA continuous the the ensureAn theELA the		occurred during the					
Latrices and other public areasThe wans and noors of the latrines and walls of public areas should be fitted with white smooth tiles for easy cleaningManagementObservation activityOne activityAn EXPert and the management.EA EXPert and the management.Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne off AnAn EIA Expert and OOOOO OOPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation activityAn EIA Expert activityEIA EXpert and OOO	I atrinos and	operation.	Managana	Obcorrection	010 24		Kah 200
of public areas areasof public areas should be fitted with white smooth tiles for easy cleaningManagementAnd the management.ManagementWater harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement managementObservation are fixedOne off activityAnEIA EXpert and the management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation are fixedActivity to Expert activity to ExpertAnEIA EIA the management.	other public	the latrines and walls	management	Observation	activity OII	Finert and	NSII.500,
Water harvesting and storage facilitiesInitiate roof water harvesting and install water storage tanksManagement ManagementObservation are fixedOne activityoff Expert and the management.An EIA 000Ksh.20 000Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation are fixedOne activityoff Expert and the management.An EIA Management	areas	of public areas should			activity	the	
Simooth tiles for easy cleaningSimooth tiles for easy cleaningManagementObservation are fixedOne activityoff Expert and the management.Water harvesting and storage facilitiesInitiate roof water storage tanksManagement ManagementObservation are fixedOne activityoff Expert and the management.An EIA MonagementKsh.200 OOOPoor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagementObservation A continuous activity to ensure that theAn EIA MonagementEIA Management	arow	be fitted with white				management	
cleaningcleaninganagementObservation are fixedOne activityoff Expert and the management.An OOOEIA Construct and the management.Water harvesting and storage facilitiesInitiate roof water storage tanksManagement managementObservation are fixedOne activityoff Expert and the management.An EIA Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation ObservationA continuous activity to Expert activity to ensure that theAn Construct EIA Construct		smooth tiles for easy				management.	
Water harvesting and storage facilitiesInitiate roof harvesting and install water storage tanksManagement managementObservation are fixedOne activityOff Expert and the management.An ELA CO00EIA CO00Ksh.200 OO0Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagementObservation are fixedAn continuous An ensureEIA Expert and Construct a well functioning incinerator -sort waste at sourceManagement ManagementObservation ObservationA continuous activity to Expert ensureAn EIA Construct Management		cleaning					
harvesting and storage facilitiesharvesting and install water storage tanksare fixedactivityExpert the management.000Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagementObservation observationA continuous activity to ensure thatAnEIA EXPERt OOOKsh.500, OOO	Water	Initiate roof water	Management	Observation	One off	An EIA	Ksh.200,
and storage facilitieswater storage tanksthe management.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ObservationObservation A continuous activity to ensure that theKsh.500, 000	harvesting	harvesting and install		are fixed	activity	Expert and	000
facilitiesmanagement.Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagement ObservationObservation activity to ensure thatManagement.	and storage	water storage tanks				the	
Poor waste disposal-Construct a well functioning incinerator -sort waste at sourceManagementObservation activity ensureA continuous Expert ensureAnEIA EXPERt OOOKsh.500 OOO	facilities					management.	
disposalfunctioning incinerator -sort waste at sourceactivity to ensure thatExpert and the000	Poor waste	-Construct a well	Management	Observation	A continuous	An EIA	Ksh.500,
-sort waste at source ensure that the	disposal	functioning incinerator			activity to	Expert and	000
		~sort waste at source			ensure that	the	

	-connect all laboratory sink to a functioning biomedical liquid waste treatment system.			appropriate solid and liquid waste management is established	management.		
Lack of enough vegetation cover around the Health Care Facility	-The management should plan for the establishment of trees and other aesthetic plants within and around the facility	Management	Observation to ensure that appropriate tree species are established around the facility	Continuous activity to ensure that appropriate and adequate vegetation species are established around the facility	An EIA Expert and the management.	Ksh. 10,000 per mo	nth

7.5 Decommissioning Phase

In addition to the mitigation measures provided in the tables above, it is necessary to outline some basic mitigation measures that will be required to be undertaken once all operational activities of the health care project have ceased. The necessary objectives, mitigation measures, allocation of responsibilities, time frames and costs pertaining to prevention, minimization and monitoring of all potential impacts associated with the decommissioning and closure phase of the project are outlined in the table below.

Table 8: Environmental Management/Monitoring Plan for the decommissioning phase

Reco	mmended Mitigation Measures	Responsible Party	Time Frame
1. Den	nolition waste management		
1.	All buildings, machinery, equipment, structures and partitions that will not be used for other purposes must be removed and recycled/reused as far as possible	Contractor, Proponent	One-off
2.	All foundations must be removed and recycled, reused or disposed of at a licensed disposal site	Contractor, Proponent	One-off
3.	Where recycling/reuse of the machinery, equipment, implements, structures, partitions and other demolition waste is not possible, the materials should be taken to a licensed waste disposal site	Contractor, Proponent	One-off
4.	Donate reusable demolition waste to charitable organizations, individuals and institutions	Contractor, Proponent	One-off
2. Reh	abilitation of project site		
1.	Implement an appropriate re-vegetation programme to restore the site to its original status	Contractor, Proponent	One-off
2.	Consider use of indigenous plant species in re-vegetation	Contractor, Proponent	One-off
3.	Trees should be planted at suitable locations so as to interrupt slight lines (screen planting), between the adjacent residential area and the development.	Contractor, Proponent	Once-off

8. AUXILLIARY INFORMATION

8.1 Budget

TOTAL PROJECT COST

Kshs.50, 000, 000 (Fifty Million Shillings Only)

8.2 Monitoring Guidelines

Continuous observations and assessment is essential so that if unforeseen dangers are noticed, alternatives are sort for. Risk assessment of fire outbreaks, and others should not be ignored in the construction plan. Waste management within the project site should be strictly followed. Mitigation measures of storm water management are essential. Safety standards should constantly be maintained. In brief, monitoring guidelines could be based on the following parameters:

- •Health and safety measures using such standards as the laid down regulatory framework
- Water demand, availability and use
- Waste management
- Quality management systems
- Laboratory Bio-safety
- •Accidents and risk assessment arising from the use of water, roads, electricity and or any other amenity
- Conservation and establishment of vegetation cover

8.3 Reporting

Constant reporting by the site contractor to the architect is necessary to ensure the project is executed as per the architectural drawings. The safety officer should always remain on site to report any safety concerns for urgent mitigation. He should also at all times enforce safety requirements as per the relevant legislations. The contractor must consult the architect to maintain a clear understanding of all the aspects of the project.

8.4 Conclusion and Recommendations

During the preparation of this report for the proposed laboratory development it was observed and established that most of the negative impacts on the environment are rated low and short term with no significant effect. They are all localized with no residual effects.

The positive impacts are highly rated and will benefit all stakeholders at large. The project proponent has proposed to adhere to prudent implementation of the Environmental Management Plan. They are obtaining all necessary permits and licenses from the relevant authorities and have qualified and adequate personnel to do the project as proposed. They have proposed adequate safety and health mitigation measures as part of the relevant statutory requirements

They could therefore be licensed to implement this project subject to adherence to the Environmental Management Plan proposed in this report and the statutory requirements.

9. APPENDICES

Architectural Designs and Drawings and NEMA Licenses

10. REFERENCES

- i. Ayliffe GAJ et al. (1992). *Control of hospital infection. A practical handbook*, 3rd ed. London, Chapman & Hall.
- ii. Beck EG, Schmidt P (1986). *Hygiene im Krankenhaus und Praxis. [Hygiene in the hospital and in medical practice.]* Berlin, Springer.
- iii. Block SS (1991). *Disinfection, sterilization, and preservation*, 4th ed. Philadelphia, Lea & Febiger.
- iv. Christen J (1996). Dar es Salaam Urban Health Project. Health care waste management in district facilities: situational analysis and system development.
- v. Daschner F (1997). *Praktische Krankenhaushygiene und Umweltschutz*, 2 Auff. [*Practical hospital hygiene and protection of the environment*, 2nd ed.] Berlin, Springer.
- vi. Garner JS (1996). Guideline for isolation precautions in hospitals. The Hospital Infection Control Practices Advisory Committee. *Infection control and hospital epidemiology*, 17:53Đ80.
- vii. Garner JS, Favero MS (1986). CDC Guideline for hand washing and hospital environmental control. *Infection control*, 7:231-243.
- viii. Garner JS, Simmons BP (1983). CDC Guideline for isolation precautions in hospitals. *Infection control*, 4:245-325.
- ix. 1. A. Pruss, E. Giroult and P. Rushbrook (1999)"Safe management of waste from health-care activities". Geneva, World Health Organisation.
- x. Mayhall CG (1996). *Hospital epidemiology and infection control.* Baltimore, MD, Williams & Wilkins.
- xi. Mehtar S (1992). *Hospital infection control. Setting up with minimal resources.* Oxford, Oxford Medical.
- xii. Ministry Of Health Kenya, The National Health Care Waste Management Plan 2008-2012
- xiii. Ministry of Health Kenya, 2007, National Policy on Injection Safety and Health Care Waste Management.
- xiv. Parker MT (1978). *Hospital-acquired infections: guidelines to laboratory methods.* Copenhagen, World Health Organization Regional OfFice for Europe (European Series, No. 4).
- xv. Philpott-Howard JN, Casewell MM (1994). *Hospital infection control. Policies and practical procedures.* London, Saunders.
- xvi. Republic of Kenya, Reversing the Trends: The Second National Health Sector Strategic Plan-Annual Performance Report July 2007–June 2008 (Annual Operational Plan 3 Report)
- xvii. Russell AD, Hugo WB, Ayliffe GAJ (1992). *Principles and practice of disinfection*, *preservation and sterilization*, 2nd ed. Oxford, Blackwell.
- xviii. Rutala A (1995). Chemical germicides in health care. Morin Heights, Canada, Polyscience.
- xix. Steuer W (1992). Hygiene in der .rtzlichen Praxis. [Hygiene in medical practice.]Stuttgart, Fischer.
- xx. Thofern E, Botzenhart K (1983). *Hygiene und Infektion im Krankenhaus. [Hygiene and infection in the hospital.]* Stuttgart, Fischer.
- xxi. St Gallen, Switzerland, Swiss Centre for Development Cooperation in Technology and Management (SKAT).
- xxii. StedmanÕs medical dictionary, 26th ed. (1995). Baltimore, MD, Williams & Wilkins.
- xxiii. WHO. *Guidelines for drug disposal after emergencies*. Geneva, World Health Organization (unpublished document, in preparation; will be available from Department of Essential Drugs and other Medicines, World Health Organization 1211 Geneva 27, Switzerland).

- Wenzel RP (1997). *Prevention and control of nosocomial infections*, 3rd ed. Baltimore, MD, Williams & Wilkins. WHO, 2005, Decision making Guide, Management of Solid Health Waste at Primary Health Care Centres. xxiv.
- xxv.